This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

LANE MEDICAL LIBRARY STANFORD
TEED 2470 54 2

448

LANE

MEDICAL LIBRARY

LEVI COOPER LANE FUND

TEXT-BOOK OF

OPHTHALMOLOGY

NOV 25 1893 NEW YORK HOSPITAL

BY

DR. ERNEST FUCHS

PROFESSOR OF OPHTHALMOLOGY IN THE UNIVERSITY OF VIENNA

AUTHORIZED TRANSLATION FROM THE SECOND ENLARGED AND IMPROVED GERMAN EDITION

BY A. DUANE, M. D.

ASSISTANT SURGEON OPHTHALMIC AND AURAL INSTITUTE, NEW YORK

LANE MEDICAL LIBRARY 17870 SAN FRANCISCO

WITH NUMEROUS ILLUSTRATIONS

NEW YORK
D. APPLETON AND COMPANY
1893

LANE LIBRARY

COPYRIGHT, 1892,
BY D. APPLETON AND COMPANY.

ED AND PRINTED
ON PRESS, U. S. A.

246
F951
1893

PREFACE.

No apology seems needed for presenting to American readers the translation of a book so well and so favorably known as Prof. Fuchs's Lehrbuch der Augenheilkunde. The care and judicious spirit governing the selection and presentation of facts, the thoroughness and freshness of the information, and the scientific accuracy which characterize the original, have won for it the first place among ophthalmological text-books. To these essential properties there is superadded one scarcely less important in a book of this character, namely, a clear, concise, and pleasing style. In the endeavor to make his version worthy of the original in this important regard, the translator has taken considerable liberties with the German text, and has not hesitated to alter grammatical relations, substitute and interpolate words, and in other ways depart from the strict letter of his model whenever it has seemed to him that clearness and the necessities of the English idiom required the change. Upon this point he is glad to say that he has the entire approval of Dr. Fuchs, who has not only given his authorization to the work of translation, but has been good enough to look over and indulgent enough to commend that portion of the book submitted to his inspection.

In consonance with his views of a translator's duties, the author of the present version has made only such additions as seemed necessary to adapt the book to American readers. These additions are everywhere distinguished by being inclosed in brackets, and, in the case of foot-notes, by having the letter D appended to them. The translator alone is responsible for such insertions; at the same time, it is but fair to state that a number of them have been submitted to Dr. Fuchs and have received his approval.

The appendix containing the cuts of instruments is also matter inserted by the translator. These cuts (and also the two on pages 656

and 657) have been kindly furnished by Tiemann & Co., and by E. B. Meyrowitz, the well-known instrument-makers of this city, to whom the translator desires here to make suitable acknowledgments for the courtesy extended.

It is the hope of the translator that he has succeeded in faithfully reproducing a work the many excellences of which should command for it a wide circulation in this country, as they have already done in Europe.

A. DUANE, M. D.

25 EAST THIRTY-FIRST STREET, NEW YORK, *July 6, 1892.*

CONTENTS.

PART I.

EXAMINATION OF THE EYE.

CHAPTER I.

OBJECTIVE EXAMINATION OF THE EYE.

PAGE

Examination of the eyes 1
Ophthalmoscopy 4
Principle of the ophthalmoscope 4
Method of examination 5
Application of the ophthalmoscope 7
Luminosity of the pupil 9
Examination of the refracting media 11
Normal fundus oculi 12
Determination of the refraction 16

CHAPTER II.

FUNCTIONAL TESTING.

Central and peripheral vision 20
Examination of the field of vision 21
Extent of the field of vision 23
Light-sense 27
Simulation of blindness 28

PART II.

DISEASES OF THE EYE.

CHAPTER I.

DISEASES OF THE CONJUNCTIVA.

Anatomy of the conjunctiva 31
Conjunctivitis catarrhalis 37
Acuta 37
Chronica 43
Follicularis 46
Conjunctivitis crouposa 47
Conjunctivitis blennorrhœa acuta 49
Blennorrhœa adultorum 49
Blennorrhœa neonatorum 56

PAGE
Conjunctivitis trachomatosa 58
Conjunctivitis diphtheritica 80
Conjunctivitis lymphatica 88
Vernal catarrh 94
Conjunctivitis exanthematica 97
Pemphigus conjunctivæ 98
Amyloid degeneration of the conjunctiva 99
Injuries of the conjunctiva 100
Tuberculosis and ulcers of the conjunctiva 102
Pterygium 104
Symblepharon 109
Xerosis 111
Extravasation of serum and blood beneath the conjunctiva 113
Tumors of the conjunctiva 115
Affections of the plica semilunaris and caruncle 120

CHAPTER II.

Diseases of the Cornea.

Anatomy of the cornea 122
Clinical examination of the cornea 126
Inflammation of the cornea. 128
General statement. 128
Subdivision of keratitis. 137
Suppurative keratitis 138
Ulcer of the cornea 138
Abscess of the cornea 154
Keratitis e lagophthalmo 161
Keratomalacia 162
Keratitis neuroparalytica 164
Non-suppurative keratitis 168
Pannus 168
Keratitis with the formation of vesicles (herpes febrilis, herpes zoster, and keratitis vesiculosa) 168
Parenchymatous keratitis 172
Keratitis profunda. 182
Sclerosing keratitis 182
Keratitis springing from the posterior surface of the cornea . . 183
Traumatic striped keratitis 184
Deep keratitis in irido-cyclitis 184
Deep scrofulous infiltrates 185
Keratitis marginalis 185
Injuries of the cornea 185
Foreign bodies in the cornea 185
Solutions of continuity of the cornea 186
Injuries of the cornea by caustic agents and burns 188
Opacities of the cornea 189
Ectasiæ of the cornea 197
Staphyloma of the cornea 197
Keratectasia 207
Keratoconus 208
Keratoglobus 209
Tumors of the cornea 210

CHAPTER III.

Diseases of the Sclera.

PAGE
Anatomy of the sclera 211
Inflammation of the sclera 212
Superficial forms of scleritis 212
Deep forms of scleritis 213
Injuries of the sclera 216
Foreign bodies in the eye 219
Ectasiæ of the sclera 227
Ulcers and tumors of the sclera 233

CHAPTER IV.

Anatomy and Physiology of the Uvea—Embryology of the Eye.

Anatomy of the uvea 234
Iris 234
Ciliary body 241
Chorioid 245
Circulation and metabolism of the uvea 248
Blood-vessels 248
Lymph-passages 250
Nourishment of the eye 252
Intra-ocular pressure 253
Participation of the uvea in the visual act 256
Function of iris; reaction of pupil 256
Function of ciliary body 264
Function of chorioid 264
Development of the eye 264

CHAPTER V.

Diseases of the Iris and of the Ciliary Body.

Inflammation (iritis, cyclitis, irido-cyclitis) 268
Symptoms of iritis 268
Symptoms of cyclitis 272
Differential diagnosis between iritis and cyclitis 274
Course and termination of iritis and cyclitis 279
Etiology and varieties of iritis and cyclitis 285
Treatment of iritis and cyclitis 294
Injuries of the iris 299
Tumors of the iris and ciliary body (including cysts and tuberculosis) . . 302
Disorders of motility of the iris 306
Mydriasis 307
Miosis 308
Paralysis of the sympathetic 308
Hippus 308
Congenital anomalies of the iris 309
Persistent pupillary membrane 309
Coloboma iridis 309
Irideremia 310
Ectopia pupillæ 310

CHAPTER VI.

Diseases of the Chorioid.

PAGE
Inflammation of the chorioid 312
Chorioiditis exudativa 313
Chorioiditis and irido-chorioiditis suppurativa 319
Atrophia et phthisis bulbi 323
Detachment of the chorioid 323
Rupture of the chorioid 323
Tumors of the chorioid 324
Tuberculosis of the chorioid 327
Congenital anomalies of the chorioid 328
Albinism 330

CHAPTER VII.

Glaucoma.

General considerations 332
Primary glaucoma 337
Glaucoma inflammatorium 337
Glaucoma simplex 343
Hydrophthalmus 344
Theories of glaucoma 346
Anatomy of glaucoma 351
Treatment of primary glaucoma 353
Secondary glaucoma 358
Diminution of the intra-ocular pressure 360

CHAPTER VIII.

Diseases of the Lens.

Anatomy of the lens 361
Opacities of the lens, cataract 364
General considerations 364
Clinical forms of cataract 368
Anterior polar cataract 368, 372
Posterior polar cataract 369
Circumscribed opacities 369
Perinuclear cataract 370, 373
Cortical cataract 372, 374
Progressive cataracts (senile cataract) 374
Etiology of cataract 381
Treatment of cataract 386
Changes of position of the lens 386
Lenticonus 394

CHAPTER IX.

Diseases of the Vitreous.

Anatomy of the vitreous 395
Opacities of the vitreous 395
Liquefaction of the vitreous 396
Foreign bodies in the vitreous 397

CHAPTER X.

Diseases of the Retina.

PAGE

Anatomy and physiology of the retina 400
Inflammation of the retina 403
Retinitis 403
Hyperæmia of the retina 405
Hæmorrhages into the retina 406
Embolism of the central artery 406
Thrombosis of the central vein 408
Anæmia of the retina 408
Uræmic retinitis and amaurosis 409
Retinitis from dazzling 410
Atrophy of the retina; retinitis pigmentosa 410
Detachment of the retina 413
Injuries of the retina 419
Glioma of the retina 416

CHAPTER XI.

Diseases of the Optic Nerve.

Anatomy of the optic nerve. 420
Intra-ocular division 420
Orbital division 423
Intra-cranial division 425
Continuation of the fibers to the cerebral cortex; decussation of the optic nerves; hemiopia 425
Inflammation of the optic nerve 433
Neuritis intra-ocularis 433
Hyperæmia of optic nerve 437
Neuro-retinitis 437
Retrobulbar neuritis 439
Tobacco-amblyopia 441
Atrophy of the optic nerve 442
Tumors of the optic nerve 444
Anatomy of affections of the optic nerve 444
Disturbances of vision without apparent lesion 445
Congenital amblyopia 446
Amblyopia ex anopsia 446
Hemeralopia and nyctalopia 447
Amblyopia and amaurosis of central origin 449
Scintillating scotoma 449
Hysterical amblyopia and asthenopia 450
Color-blindness 452

CHAPTER XII.

Diseases of the Lids.

Anatomy and physiology of the lids 459
Inflammation of the skin of the lids 468
Exanthemata (erysipelas, herpes zoster, eczema) 468
Phlegmonous inflammation 470
Ulcers of the skin of the lids 471

PAGE
Elephantiasis of the lids 472
Chromidrosis 472
Œdema of the lids 472
Inflammation of the border of the lids 475
Hyperæmia 475
Blepharitis squamosa and ulcerosa 476
Phthiriasis palpebrarum 481
Diseases of the palpebral glands 481
Hordeolum 482
Chalazion 483
Infarcts of the Meibomian glands 484
Anomalies of position and connection of the lids 486
Trichiasis and distichiasis 486
Entropion 488
Ectropion 490
Ankyloblepharon 493
Symblepharon 493
Blepharophimosis 493
Lagophthalmus 494
Diseases of the palpebral muscles 497
Spasm of the orbicularis (blepharospasm) 497, 500
Paralysis of the orbicularis 498
Paralysis of the levator palpebræ superioris (ptosis) 499, 501
Spasm and paralyses of Müller's muscle 502
Injuries of the lids 502
Tumors of the lids 504
Congenital anomalies of the lids (coloboma, epicanthus, etc.) 506

CHAPTER XIII.

Diseases of the Lachrymal Organs.

Anatomy and physiology 508
Blennorrhœa of the lachrymal sac 511, 519
Dacryocystitis 517, 521
Diseases of the lachrymal gland 518
Affections of puncta and canaliculi 519
Tuberculosis of lachrymal sac 520
Treatment of lachrymal disease 520
Epiphora and increase of lachrymal secretion 522
Abolition of lachrymal secretion 523

CHAPTER XIV.

Disturbances of Motility of the Eye.

Anatomy and physiology of the ocular muscles 524
Anatomy of muscles 524, 533
Action of muscles 525, 534
Orientation and diplopia 528, 539
Nerves of ocular muscles 536
Binocular and stereoscopic vision 539
Insufficiency of the ocular muscles 542
Paralysis of the ocular muscles 547
Squint 562

PAGE
Nystagmus 574
Tonic spasms of ocular muscles 576

CHAPTER XV.

Diseases of the Orbit.

Anatomy of the orbit 577
Position of the eyeball in the orbit; exophthalmus 579
Enophthalmus 581
Inflammation 581
Inflammation of the bony wall and the periosteum 581, 584
Inflammation of the cellular tissue; cellulitis 583
Thrombosis of the cavernous sinus 584
Tenonitis 585
Injuries of the orbit 586
Contusion of the eye; summary of appearances 588
Basedow's disease 589
Tumors of the orbit 591
Dilatation of the cavities adjoining the orbit 595

PART III.

ANOMALIES OF REFRACTION AND ACCOMMODATION.

Introduction 597

CHAPTER I.

The Theory of Glasses.

Varieties and properties of lenses 598
Numbering of glasses 602

CHAPTER II.

Optical Properties of the Normal Eye.

Refraction 605
Visual acuity 606
Accommodation 610
Measurement of accommodation 615
Changes of the accommodation in age; presbyopia 622

CHAPTER III.

Myopia.

Nature and determination 626
Typical myopia 629

CHAPTER IV.

Hypermetropia.

Nature and determination 640
Typical hypermetropia 644

CHAPTER V.

Astigmatism.

PAGE
Regular astigmatism 650, 655
Irregular astigmatism 654
Determination of astigmatism 655
Method of indicating axes of cylindrical glasses 656
Anisometropia 658

CHAPTER VI.

Anomalies of Accommodation.

Paralysis of accommodation. 660
Spasm of accommodation 663

PART IV.

OPERATIONS.

CHAPTER I.

General Remarks.

The antiseptic method in eye-operations 665
Anæsthesia in operations 666
Instruments for supporting the lids 666
Character and shape of incisions in the eyeball 667, 672
Maintenance of proper position of the iris 668, 674
Hæmorrhage in operations 669, 676
After-treatment of operations 670, 676
Regular healing of operation-wounds. 670
Irregular healing of operation-wounds 670
Suppuration of wound after operations 671
Inflammation of the uvea after operations. 672
Collapse of the cornea 676

CHAPTER II.

Operations upon the Eyeball.

Paracentesis of the cornea 678
Paracentesis of the sclera; sclerotomy 679
Iridectomy 680
Iridotomy 687
Discission of soft cataract 688
Discission of membranous cataract 690
Extraction of cataract 692
Simple linear extraction 692
Flap-extraction 693, 701
Scleral flap-extraction 693, 702
Corneal flap-extraction 694
Extraction of lens in closed capsule 696
Extraction by Wenzel's method 696
Accidents in cataract-extraction 696
Results of the cataract-extraction. 697

PAGE
Early operations for cataract 699
Depression 700
Reclination 700
Daviel's operation 701
Beer's operation 701
The operations of Von Graefe and others 701

CHAPTER III.

Operations upon the Adnexa Bulbi.

Squint-operations; tenotomy and advancement. 705
Enucleation of the eyeball 713
Artificial eye. 715, 717
Exenteratio bulbi 718
Optico-ciliary neurotomy 718
Exenteration of the orbit 718
Operations for trichiasis 719
Ablation of the zone of hair-follicles 719, 723
Transplantation of the zone of hair-follicles 720, 723
Hotz's operation 722
Straightening of the tarsus 723
Flap-operations 724
Canthoplasty 725
Tarsorrhaphy 726
Operations for entropion 728
Gaillard's suture 728
Excision of a horizontal strip of skin, and other methods 729
Operations for ectropion 730
Snellen's suture 730
Kuhnt's operation. 731
Blepharoplasty 731
Operations for ptosis 734
Von Graefe's operation. 734
Pagenstecher's operation 735
Panas's operation 735
Eversbusch's operation. 736

APPENDIX.

Instruments used in Ophthalmology:
Instruments for opening the eye and keeping it in place 737
Instruments for operations upon the lids 738
Instruments for strabismus and enucleation 739
Instruments for lachrymal stricture 740
Instruments for removing foreign bodies 741
Tattooing-needles. 741
Instruments for iridectomy and iridotomy 742
Instruments for paracentesis and discission 743
Instruments for cataract-extraction 744
Ophthalmoscopes 746
The ophthalmometer 748
The perimeter 749

PART I.

EXAMINATION OF THE EYE.

CHAPTER I.

OBJECTIVE EXAMINATION OF THE EYES.

1. The examination of a patient's eyes is begun after establishing the history of the case. In making this examination too much stress can not be laid upon the necessity of proceeding systematically, since otherwise important matters can very readily be overlooked. We first examine the patient with regard to his general physical condition as well as with regard to the expression of his countenance, and then, in observing the eyes themselves, proceed gradually from the superficial parts—lids, conjunctiva, and cornea—to the deeper portions.

In respect to the *lids*, there are to be considered their position and mobility, the breadth of the fissure between them, and their power of closing. The character of the skin lining the lids is examined, and especially at their margins, where pathological changes are most often found. Apart from the symptoms of inflammation, which are localized with especial frequency at the borders of the lids, the things that we must look for are whether the palpebral edges have not possibly lost their sharply defined form and outline, whether the cilia are correctly placed, and also whether the puncta dip properly into the lacus lacrymalis. At the same time, we must not neglect to investigate the region of the tear-sac. Should simple inspection disclose no alteration, it is yet often possible, by pressure with the fingers in this region, to make the contents of the diseased sac exude through the puncta.

The examination of the *eyeball* itself is often rendered very difficult by strong spasm of the lids—blepharospasm. This is especially the case in children who, the more the physician attempts to draw the lids apart, squeeze them the more tightly together. In these cases the forcible separation of the lids calls for the greatest caution, since, if this is not observed, and a deeply penetrating ulcer is present, it is easy to cause a sudden perforation of the cornea, nay, even the extrusion of the lens from the eye. By dropping a solution of cocaine between the

slightly parted lids we try to diminish their sensitiveness; and for the separation of the lids we can, with advantage, use Desmarre's elevator, with which we shall less readily inflict an injury than we should do if, in using the fingers, we exerted too great a pressure upon the eyeball. Finally, in many cases it is only by means of narcosis that we can obtain a sufficiently satisfactory view of the eyes. In spite of all these difficulties we should not be deterred from insisting upon an exact examination of the eyes at the patient's first visit, in order to establish the diagnosis and prognosis and to determine the treatment.

In regard to the eyeball itself, we must first satisfy ourselves whether its situation in the orbit, its position in respect to the other eye, its size, and its mobility are normal or not.

The *conjunctiva* of the lids can be brought into view by everting the latter. With the lower lid, it is sufficient for this purpose to simply draw it down, while the patient is told at the same time to look up. With the upper lid, eversion requires a certain degree of skill, which must be obtained by practice. It is the more important to acquire this facility, since it is just the conjunctiva of the upper lid that generally affords the best evidence for the diagnosis of conjunctival diseases: the thickening of the conjunctiva, the uneven surface, the formation of cicatrices, which are characteristic of trachoma, are here most easily to be perceived. Further, the eversion of the upper lid is very frequently necessary for the removal of foreign bodies.

In the examination of the *cornea*, besides a careful inspection (without and eventually with the aid of a loupe), there are two artifices which are particularly in use—examination of the corneal reflex and lateral illumination. To examine the corneal reflex signifies nothing more than to direct the eye in such a manner that the reflection of a window placed opposite it is visible upon the cornea (in Fig. 24 the image of four window-panes is seen upon the upper and outer quadrant of the cornea). By causing the eye to follow the movements of a finger held before it, the reflection is gradually brought upon different portions of the corneal surface, of whose curvature and smoothness we in this way obtain an impression.

Lateral illumination consists in the concentration of light upon a certain portion of the cornea by means of a convex lens. This important method, although already employed by Himly, Mackenzie, and Sanson, was yet very little known formerly, and first obtained general currency through the efforts of Helmholtz. A light (candle or lamp) is placed beside and somewhat in front of the patient. Then, by the aid of a strong convex lens (of 15–20 D.), the rays are concentrated to a cone of light, whose apex is made to fall upon the portion of the cornea to be examined. This method is designated as focal illumination, because the point to be illuminated is brought into the focus of the lens. This point stands out with special distinctness because, on

the one hand, a great quantity of light is concentrated upon it, and because, on the other hand, the parts immediately surrounding it remain almost completely in darkness. On this latter ground, lateral illumination gives the most advantageous result if in its application the room is darkened. By lateral illumination we can recognize opacities in the cornea which are perceptible in no other way. The iris, too, and the lens as well, can be examined in this way by varying the depth to which the light is projected. By so doing we have not merely the advantage of getting very sharp images, but also, from the fact that we can at will vary the depth to which the apex of the conical sheaf of rays is projected, we get information as to the depth at which the changes that we observe are situated. A handier method of lateral illumination is furnished by the lamp of Priestley Smith. This carries in its center a small candle as a source of light; a strong convex lens let into the side of the lamp serves for the production of the cone of light.

In addition to the appearance of the cornea we have further to examine its sensitiveness, which is best done by touching it with the point of a thread.

The *anterior chamber* must be examined more especially in respect to its depth—that is, whether it is shallower or deeper, as a whole, or whether possibly it is of unequal depth. Further, we look for any abnormal matters which may be present in the chamber, such as an exudate, blood, foreign bodies, etc.

In the *iris* its color as well as the clearness of its markings must be observed. For the recognition of adhesions the instillation of atropine is often requisite. We inspect the active movements (reaction) of the iris as well as any passive movement that may be present (tremulousness of the iris in movements of the eyeball). In order to determine the reaction of the iris to light, we first cover the eye by holding the hand before it, and then see whether, upon suddenly removing the hand, the pupil contracts. Besides this, we must test the reaction of the pupil to convergence and accommodation. Lastly, we determine whether the pupil is circular, of normal width, centrally placed, and of pure black hue.

Of the *lens* we see under ordinary circumstances only the small section of the anterior surface, which lies free in the pupil. If we wish to examine the lens more extensively, we dilate the pupil with homatropine and use lateral illumination. As long as the lens is still transparent, the ophthalmoscope gives us the best conclusions in regard to its constitution. Whether the lens is present in the eye at all or not can be determined by investigating the Purkinje-Sanson reflex images. If a candle is placed before the eye and somewhat to one side of it, two brilliant reflections are observed. One of these at once attracts our attention by its size and brilliancy; it is the corneal reflex

—that is, the erect image of the flame reflected from the anterior surface of the cornea. It is this reflex which even from a distance is visible in every eye, and gives to the latter its fire and luster. The second reflex is quite as bright, but so small that we have to look for it at first in order to find it. It presents the very small inverted image of the flame which is reflected from the posterior surface of the lens (posterior lenticular reflex). It is distinguished by moving in the contrary sense to the source of light when the position of the latter is shifted; if the candle is depressed, the shining point rises, and vice versa, in opposition to the corneal reflex, which moves in the same sense as the candle-flame. Now, this second reflex, or, as it is called, the posterior lenticular image, is a certain proof of the presence of the lens in the eye. It is not, however, permissible to reverse this proposition—that is, if the posterior lenticular image is not present, the lens, of course, may be wanting; but it may also happen that, because of turbidity of the substance of the lens, a reflection can no longer be developed on its posterior surface.

Finally, before proceeding to an examination with the ophthalmoscope, the *tension* of the eye is to be tested. The eye is closed and palpation is made by means of the two index-fingers, which are placed upon the upper lid. Here, as in all the previously mentioned methods of examination, the best measure for any variation from the normal is obtained by a comparison with the other eye, it being presupposed that the latter is healthy.

Examination with the Ophthalmoscope (Ophthalmoscopy).

2. The invention of the ophthalmoscope by Helmholtz in the year 1851 was one of the most beneficent achievements in modern medicine. It has made the interior of the eye accessible to investigation; blood-vessels and nerves, which in the rest of the body are exposed only by surgical manipulation, here lie unveiled before us and permit us to study their minutest variations. In ophthalmology, the ophthalmoscope has produced a complete revolution, since it has thrown light into the dark region of what was formerly called black cataract, and has acquainted us with the manifold morbid processes which lie at the root of this dreaded malady. Many of these processes, if diagnosticated correctly and in time, would, at the present day, receive successful treatment. Furthermore, in general medicine the ophthalmoscope has become an indispensable aid to diagnosis, since many internal disorders produce characteristic changes in the fundus of the eye.

Principle of the Ophthalmoscope.—In order to see the fundus of an eye, we must throw light by the aid of suitable apparatus through the pupil and upon the fundus, and receive the light reflected from the latter into our own eye and unite the rays to form a sharp image. In the original ophthalmoscope of Helmholtz this end was obtained in the

following way: Before the eye under investigation (*A*, Fig. 1) a glass plate, *PP*, is placed in an oblique position. A source of light, *L*, placed to one side of the eye, throws upon the glass plate rays, part of which are reflected at the surface of the plate and pass through the pupil into the eye, *A*. The rays reflected from the fundus, *a*, arrive once more at the glass plate and are there in part reflected to the source of light, *L*, while another part goes through the glass plate and enters the observer's eye, *B*, which unites the rays upon its retina into a well-defined image, *b*. In order to increase reflection at the surface of the plate and thereby illuminate the background of the eye more intensely, Helmholtz placed three such plates one behind the other. A later modification consisted in increasing the reflecting power of the glass plate by lining its posterior surface with a mirror



FIG. 1.—PRINCIPLE OF HELMHOLTZ'S OPHTHALMOSCOPE.

coating, a round hole through the plate or at least through the mirror-coating enabling the observer to see through it. Of this sort are the coated plane mirrors, or mirrors of feeble illumination which are now employed. As mirrors of strong illumination we designate concave mirrors, which are also coated and are perforated through the center (first employed by Ruete). These, from the fact that they render convergent the rays springing from the source of light, throw a still greater quantity of light through the pupil into the observed eye. An apparatus is placed in front of the perforation in the mirror, which renders it possible to bring different sorts of lenses before the aperture. In this way it is possible to give the rays of light which fall into the observer's eye any path that may be necessary in order to unite them into a sharp image upon the retina.

Method of Examination.—The examination is conducted in a darkened room. The patient sits opposite the physician, and has on the

side of the eye to be investigated a lamp as a source of light. Then there are two different methods to be employed for seeing clearly the fundus of the eye. In order to make the explanation of them simpler, we first presuppose that both the patient and the physician have a normal refraction (emmetropia, see § 138). In the examination with the *erect image* (*direct method*), the physician places himself and his mirror directly in front of the eye that he is observing. If now he holds the mirror obliquely in such a manner that he throws the light of the lamp into the pupil of the observed eye, he will immediately get a clear view of the patient's fundus. For (Fig. 2) a certain portion of the fundus of the eye, *A*, is illuminated by the mirror, *S S*. The rays reflected from any point, as *a* of this illuminated region of the retina, leave the eye in a parallel direction, pass through the central aperture of the mirror, and fall into the observer's eye *B*. Here they are again united at a single point, *b*, upon the retina of this eye, so that here



FIG. 2.—OPHTHALMOSCOPIC EXAMINATION WITH THE ERECT IMAGE.
The eyes are drawn of the natural size of an emmetropic eye having an axial length of 24 mm.

there is produced a sharp image of the point *a*. Since the same process is repeated for all the other points of the illuminated region of the retina of the eye, *A*, a sharp image of this portion of the retina is formed in the eye of the observer.

The examination with the *inverted image*, or by means of the *indirect method* (Ruete), is conducted with the aid of a strong convex lens of about six cm. focus. This lens, *L* (Fig. 3), is held at a distance of about six cm. from the eye (*A*) under examination. The fundus of this eye is now illuminated by means of the mirror *S S*. The rays reflected from the illuminated region, *a*, of the retina pass out in a parallel direction, fall upon the lens and are united at the focus, *f*, of the latter. Thus there is formed at this spot an image of the point *a*. In like manner images from the other points of the illuminated region of the retina are produced in the focal plane of the lens, so that there is

formed here an *inverted* image of this portion of the fundus. The observer's eye *B*, now through the aperture, *o*, of the mirror examines this image at the ordinary reading distance (about thirty cm.), for which purpose a certain accommodative effort is required.*

Each of these two methods has its advantages. The erect image is highly magnified—about fourteen times—as opposed to the inverted image, which is magnified but little (about four times). The direct method is therefore particularly adapted for the recognition of the

FIG. 3.—OPHTHALMOSCOPIC EXAMINATION WITH THE INVERTED IMAGE.

The illumination of the fundus is accomplished by means of the source of light, *L*, from which the cone of rays, *k*, falls upon the mirror, *S S*, and from this is thrown into the eye, *A*. In order not to confuse the representation, these rays are not shown, but only those which pass out of the eye, *A*, again.

finer details. The indirect method, on the other hand, affords a larger field of view, and therefore gives a better general prospect. The indirect method gives a more luminous image, and hence, when the refracting media are turbid, will still render the fundus visible when it is no longer to be seen in the direct image. In most cases, both methods are applicable, and then it is advisable to conduct the examination with the aid of both.

3. Application of the Ophthalmoscope.—Before examining the fundus we test the *transparency of the refracting media* by means of the ophthalmoscope. For this purpose light is thrown by the ophthalmoscope, held at the ordinary reading distance, into the eye under examination. If the refracting media are perfectly clear, the pupil shines with a uniform red luster. If there are places in the refracting media that are opaque, such stand out upon the red background of the illuminated pupil as dark points or spots. For example, the rays

[* It is better to obviate this strain upon the accommodation, and this can be readily done by interposing before the aperture of the mirror a convex lens of 3 or 4 D.—D.]

which correspond to the opaque spot *t* (Fig. 4) are cut off on their return from the fundus, *a*, so that this spot is not illuminated and hence looks black. This is the case even when the opacities are actually, as



FIG. 4.—VISIBILITY OF OPACITIES IN THE MEDIA BY MEANS OF THE OPHTHALMOSCOPE.

seen by light thrown directly upon them, light colored—that is, white or gray. So also even a piece of chalk looks black if it is held in front of a flame.

The *fundus* itself in a normal eye appears as a red surface, the most striking feature of which is the shining entrance of the optic nerve (Fig. 5). The entrance of the optic nerve (papilla nervi optici) forms a disk, the color of which is a light, grayish or yellowish red. The center of the disk often shows a depression of lighter hue—the vascular funnel (Fig. 9)—out of which rise the central vessels of the optic nerve. If this depression is more extensive (and it may be large enough to reach in places to the edge of the papilla), it is called the physiological excavation (Fig. 5). The vessels springing from the papilla divide upon it and pass over its edge into the retina, in which they keep on branching after the fashion of a tree-trunk. They can readily be distinguished into arteries and veins. The former are of a brighter red, narrower, and run a straight course (Figs. 5 and 9, *a a*); the latter are darker, of greater caliber, and very crooked (Figs. 5 and 9, *v v*). The red background on which the retinal vessels run is the chorioid, which, in consequence of the great abundance of its vessels, appears as a red surface, The retina itself, as it lies upon the chorioid, is, with the exception of its blood-vessels, invisible, because in its normal condition it is perfectly transparent. It is only just at the site of the fovea centralis that a reflex derived from the surface of the retina is recognizable as a small bright spot (*f*, Fig. 5).

Finally, the ophthalmoscope is also useful for making an objective determination of the *refraction*. This is effected by employing the erect image. In the example represented in Fig. 2 it was assumed that the patient was emmetropic. In this case, the rays pass out of the

eye parallel to each other, and can be united to form a sharp image by an observer without any strain upon the accommodation provided he is also emmetropic. Should, however, the eye under observation have an error of refraction, the rays would no longer be parallel as they pass out: in that case they would have to be made parallel by a lens placed before the eye. Thus the rays proceeding from a myopic eye would be convergent, and it would require a concave lens to make them parallel (Fig. 10); on the other hand, a hypermetropic eye renders divergent the rays proceeding from it and needs a convex lens to give them a parallel direction (Fig. 11). Accordingly, from the kind and strength of glass necessary for this purpose the examiner elicits the kind and degree of the refractive error.

Luminosity of the Pupil.—Under ordinary circumstances the pupil appears black. This was formerly ascribed to the absorption by the dark background of the eye of all the light entering the pupil from the outside. In reality, however, the cause of this phenomenon is as follows: If (Fig. 6) light

Fig. 5.—Normal Fundus of the Left Eye, seen in the Erect Image.

The optic disk, which is somewhat oval longitudinally, has the point of entrance of the central vessels somewhat to the inner side of its center. That portion of the papilla lying to the inner side of the point of entrance of the vessels is of darker hue than the outer portion; the latter shows, directly to the outside of the vascular entrance, a spot of lighter color, the physiological excavation with fine grayish stippling, representing the lacunæ of the lamina cribosa. The papilla is surrounded, first by a light-colored ring, the scleral ring, and externally to this by an irregular black stripe, the chorioidal ring, which is especially well marked on the temporal side. The central artery and vein divide immediately after their entrance into the eye into an ascending and descending branch, which appear somewhat lighter than their continuations upon the retina, because they lie in the depth of the physiological excavation. The branches, while still on the papilla, split into a number of smaller divisions and fine offshoots from them run from all directions toward the macula lutea, which itself is devoid of vessels, and is distinguished by its darker color. In its center a bright punctate reflex, *f*, is visible.

from a source of light, *L*, enters the eye, *A*, and the latter is accurately focused for the source of light, the rays coming from *L* are united to form a sharp image upon the retina at *l*. *L* and *l* are called conjugate foci. For these the law holds good that they can be substituted for each other—that is, if the rays should start from the posterior focus, *l*, they would come together again at the

anterior focus, *L*. Accordingly, the rays reflected from the illuminated portion of the retina, *l*, are returned to the source of light, *L*, and could be seen by an observer only in case the latter was in identically the same spot as the

FIG. 6.—PATH OF THE RAYS WHEN THE EYE IS FOCUSED FOR THE SOURCE OF LIGHT.

source of light. The solution of this problem is another of the ingenious discoveries of Helmholtz.

The conditions are different when the eye is not focused for the source of light before it. Suppose, for example, that the eye is hypermetropic (Fig. 7). Then the rays springing from the illuminated portion of the retina, *l*, leave the eye as a divergent beam, so that only a part of the rays are returned to the source of light, *L*, while another part passes to the side of the latter and can be seen by an observer stationed near it. Hence comes the striking luminosity of the pupil in so-called amaurotic cat's-eye (see § 100), in which a markedly hypermetropic condition of the refraction is produced by the pushing forward of the retina. In like manner, luminosity is frequently apparent in eyes which are deprived of their lens by the operation for cataract and are therefore strongly hypermetropic. Moreover, the enlargement of the pupil, which is at the same time present, and which is due to the iridectomy, renders it still easier to observe the luminosity. The luminosity of the eyes of many beasts,



FIG. 7.—EXPLANATION OF LUMINOSITY OF THE EYE.

The source of light, *L*, throws the conical beam of rays, *k*, into the eye. The further course of these rays is not shown in the figure, but only that of the rays reflected from the retina at *l*.

especially the carnivora, is also in part to be ascribed to the hypermetropic character of their refraction, although here the presence of a strongly reflecting layer (the so-called tapetum) in the chorioid of these eyes contributes to this result.

The luminosity of the pupils of albinos' eyes is to be explained in a different way. In such eyes the light passes not only through the pupil, but also

through the unpigmented iris, and even through the sclera. Accordingly, in these eyes, not simply a limited district of the retina, but the whole fundus, is flooded with diffused light; and therefore rays from the different portions of the fundus pass out of the pupil in every direction and can very readily be caught up by the observer's eye. That this explanation is the correct one is proved by the fact that the pupil of an albino's eye looks black as soon as we hold before the eye a screen having an aperture that corresponds in size to the pupil. This shuts off from the eye any light which might enter it through other media than the pupil, and in this respect makes the eye of an albino like that of a normal person.

In making an examination with the ophthalmoscope, the tyro will do well to dilate the pupil with cocaine or homatropine. Before doing so he must make sure that there is no reason to suspect glaucoma, in which case artificial dilatation of the pupil might have dangerous results, and therefore must not be employed. Directions as to the technique of ophthalmoscopy must be reserved for a course of practical study. Whoever wishes to get more precise information than can be had from the following pages can use as a brief guide Dimmer's The Ophthalmoscope and Ophthalmoscopic Diagnosis (1887); of ophthalmoscopic atlases that by Jäger is the best.

In the ophthalmoscopic examination of the eye we invariably proceed by carefully investigating the eye by means of lateral illumination first, next testing the transparency of the refracting media with the ophthalmoscope, and not going on to the examination of the fundus itself until last of all. This last examination is best made first with the inverted, afterward with the erect image; and in examining the latter the refraction can be determined at the same time.

Examination of the Refracting Media.—For this purpose, when pronounced opacities are present, we make use of the concave mirror; slight opacities, on the other hand, are discovered only by means of the mirror of feeble illumination (plane mirror). In examining, we must not neglect to make the eye move in different directions, in order, on the one hand, to obtain a view of laterally placed opacities, and, on the other hand, to stir up in this way opacities which have sunk to the bottom of the vitreous humor. Smaller opacities look black; larger opacities appear gray or even white, since the light reflected from their surface is strong enough to shine out upon the vivid red background of the illuminated pupil. In order to recognize the site of the opacity, we decide, in the first place, whether the latter is movable or fixed. In the former case it can be situated only in the vitreous; in the latter case—that is, if the opacity moves only with the eye, and not spontaneously—it is probably situated in the cornea or in the lens; but it may still be in the vitreous, since here too fixed opacities are sometimes observed. In many cases this can be decided by employing lateral illumination. If we can obtain no result in this way, we then, in order to determine the site of the opacity, make use of the *parallactic displacement* of the latter with reference to the margin of the pupil. This is accomplished in the following way: In the eye, *A* (Fig. 8), suppose four opaque points to be present, which lie at different depths, namely, in the cornea (1), upon the anterior capsule of the lens (2), at the posterior pole of the lens (3), and in the anterior part of the vitreous (4). For simplicity's sake we assume that they are all disposed in the optical axis of the eye. Then, if the observer, *B*, looks into the eye from directly in front, he will

see each one of these points precisely in the center of the pupil, *P*. Suppose, now, that the observer's eye passes from *B* to B_1. The position of the points with relation to the pupil will be changed at once. Point 1 approximates to the upper border of the pupil P_1 ; point 2, which is situated in the pupil itself, keeps its place unchanged ; points 3 and 4 have approached the lower border of the pupil ; and 4, on account of its greater depth in the eye, more so than 3. From this example the following rule for the determination of the site of an opacity can be deduced : We look into the eye from directly in front and note the position of the opacity in the pupil. Then, while the patient holds his eye fixed, we move slowly to one side and observe whether the opacity remains in the same spot or not. In the former case, the opacity lies in the pupillary plane (upon or directly beneath the anterior capsule of the lens) ; in the latter case, in front of or behind this plane—in front of it, if the opacity shifts its place with a movement opposed to that of the investigating eye ; behind it, if the opacity moves in the same sense as the eye. The more quickly this change of place occurs, the farther removed is the opacity from the pupillary plane.



FIG. 8.—DIAGNOSIS OF THE SITE OF AN OPACITY FROM PARALLACTIC DISPLACEMENT.

(Evidently we can also proceed by keeping our own eye still and telling the patient to move his. This way of examining has the disadvantage that, if the movement of the observed eye is rather extensive, a minute opacity, whose position has been marked, may disappear out of sight and then frequently is found again only with difficulty.)

Dark, ill-defined shadows on the red background of the pupil, which change their position suddenly on moving the mirror, are to be referred to irregularities of the refracting surfaces (most frequently to facetting of the cornea); the irregular astigmatism so caused further betrays itself by the fact that the image of the fundus appears irregularly distorted.

NORMAL FUNDUS OCULI.—In making a systematic examination of the fundus we begin at the papilla. In order to bring the latter into view at once, we make the patient look, not straight in front of him, but a little inward (toward his nose). For the entrance of the optic nerve does not lie at the posterior pole of the eye, but on the nasal side of it, and hence is brought directly opposite

the observer only after a corresponding rotation of the eye inward. The shape of the papilla is circular or oval ; in the latter case generally an erect oval. Its size apparently varies quite a good deal, which, however, is due to the varying degree of enlargement under which the papilla is seen. For instance, the enlargement varies not only according as we examine with the inverted or the erect image, but also, although within smaller limits, it varies with the refraction of the eye. The true size of the papilla, measured in enucleated eyes, is, as a matter of fact, almost always the same—that is, about 1·5 mm. in diameter. On account of this constancy we use the papilla for taking measurements in the fundus ; we say, for example, that a diseased area is 2 papilla-breadths in diameter.

Circumscribing the papilla, we very often (especially in making the examination with the erect image) recognize two rings distinct in color. The inner ring, lying next the border of the papilla, is white (Fig. 9 *A* between *c* and *d* ; see also Fig. 5), and is called the *scleral ring*, because it owes its white color to the fact that the sclera is here exposed to view. It is present when the aperture in the chorioid, designed for the passage of the optic nerve, is larger than the corresponding aperture in the sclera, so that the latter membrane in the immediate neighborhood of the optic nerve (Fig. 9 *B* between *c* and *d*) is no longer covered by the chorioid. At the edge of the aperture the chorioid is often marked by a larger accumulation of pigment, by which the second, exterior ring is formed. This is apparent as a black, narrow, sometimes complete, sometimes incomplete, ring, which is designated as the *chorioidal ring* or pigment ring (Fig. 9, *d*, and Fig. 5, where it is particularly visible at the outer border of the papilla).

The demarkation of the outline of the papilla, produced in this way, is generally much less sharp on the nasal than on the temporal side; for at the nasal side a greater number of nerve-fibers pass over the margin of the papilla and thus obscure it. For the same reason the inner half of the papilla looks redder, the outer half paler, because the layer of nerve-fibers in the latter situation being thinner allows the lamina cribrosa to show through more.

The optic disk under normal conditions lies in the plane of the retina, and does not therefore form a projection upon it as the name papilla would lead one to suppose. On the contrary, it very frequently contains in its center a depression, which is produced by the fibers of the optic nerve separating from each other comparatively early and thus leaving a funnel-shaped space between them (Fig. 9 *B*, *b*). The central vessels ascend on the inner wall of the funnel. The color of the vascular funnel seems white to us because we see the white lamina cribrosa at its bottom. Often, instead of a small funnel-shaped depression, a large excavation (*physiological excavation*) is present. This is situated in the outer half of the papilla, to whose external border it often reaches. The blood-vessels come out upon the inner border of the excavation (Fig. 5), and at the bottom of the latter are seen grayish dots, the lacunæ of the lamina cribrosa. With the brilliant white of the excavated exterior half of the papilla the grayish-red hue of the unexcavated interior half is in vivid contrast. Sometimes the physiological excavation is so large that it takes in the larger part of the papilla, but it never takes in the whole; there is always a part (though it may be a small part) of the papilla that escapes it. By this circumstance the physiological is distinguished from the pathological excavation, which affects the entire papilla (total excavation).

The central vessels of the optic nerve divide at the head of the nerve into a number of larger and smaller branches. The arrangement of these latter is not



FIG. 9.—HEAD OF THE OPTIC NERVE.

A, OPHTHALMOSCOPIC VIEW.—Somewhat to the inner side of the center of the papilla the central artery rises from below, and to the temporal side of it rises the central vein. To the temporal side of the latter lies the small physiological excavation with the gray stippling of the lamina cribrosa. The papilla is encircled by the light scleral ring (between *c* and *d*), and the dark chorioidal ring at *d*.

B, LONGITUDINAL SECTION THROUGH THE HEAD OF THE OPTIC NERVE.—Magnified 14×1. The trunk of the nerve up to the lamina cribrosa has a dark color because it consists of medullated nerve-fibers, *n*, which have been stained black by Weigert's method. The clear interspaces, *se*, separating them, correspond to the septa composed of connective tissue. The nerve-trunk is enveloped by the sheath of pia mater, *p*, the arachnoid sheath, *ar*, and the sheath of dura mater, *du*. There is a free interspace remaining between the sheaths, consisting of the subdural space, *sd*, and the subarachnoid space, *sa*. Both spaces have a blind ending in the sclera at *e*. The sheath of dura mater passes into the external layers, *sa*, of the sclera, the sheath of pia mater into the internal layers, *si*, which latter extend as the lamina cribrosa transversely across the course of the optic nerve. The nerve is represented in front of the lamina as of light color, because here it consists of non-medullated and hence transparent nerve-fibers. The optic nerve spreads out upon the retina, *r*, in such a way that in its center there is produced a funnel-shaped depression, the vascular funnel, *b*, on whose inner wall the central artery, *a*, and the central vein, *v*, ascend. The chorioid, *ch*, shows a transverse section of its numerous blood-vessels, and toward the retina a dark line, the pigment epithelium; next the margin of the foramen for the optic nerve and corresponding to the situation of the chorioidal ring the chorioid is more darkly pigmented. *ci* is a posterior short ciliary artery which reaches the chorioid through the sclera. Between the edge of the chorioid, *d*, and the margin of the head of the optic nerve, *c*, there is a narrow interspace in which the sclera lies exposed, and which corresponds to the scleral ring visible by the ophthalmoscope.

always the same; most frequently it happens that two main branches run upward and two downward, while only small and short twigs pass to the outer and inner sides of the disk (Fig. 5). The region of the macula lutea is devoid

of larger vessels; the larger trunks, running to the outside above and below, encircle it and send finer branches in toward it.

In the larger vessels we notice a shining white streak running along the center of the vessels. This streak, which is more distinctly visible in the arteries (Fig. 9 *A*, *a a*) than in the veins (*v v*), is called the *reflex streak* because it is due to the reflection of the light from the anterior surface of the column of blood (Jäger). A *pulsation* is frequently observed in the vessels at the spot where they first come to view upon the papilla. A venous pulse is a physiological occurrence: in the same eye it is sometimes present, sometimes absent. In the latter case, slight pressure upon the eye with the finger suffices to produce it. An arterial pulse is present under pathological conditions only. In order to produce it artificially in a healthy eye, no inconsiderable pressure must be exerted upon the eyeball. When this is done, the person under examination notices a simultaneous obscuration of the field of vision, amounting finally to complete abrogation of sight, as a result of the obstruction to the retinal circulation produced by the pressure. In like manner a rise in pressure produced by pathological conditions (glaucoma) causes an arterial pulsation. The explanation of this is as follows: As a result of the increased pressure in the interior of the eye, the blood is able to enter the vessels of the retina only during the systole of the heart; during the diastole, when the pressure in the arteries becomes somewhat lower, the latter are occluded by the intraocular pressure. Such a disproportion between the intraocular pressure and the pressure of the blood in the central artery may also, of course, be produced by the fact that while the former remains normal, the latter is diminished. Accordingly, an arterial pulsation is observed in general anæmia, chlorosis, Basedow's disease, aortic insufficiency, and also in local compression of the central artery within the optic nerve (e. g. in optic neuritis).

Since in healthy living eyes the retina is transparent, we see no part of it with the ophthalmoscope except the blood-vessels. At most we find the red fundus in the immediate neighborhood of the papilla covered by a delicate gray veil which shows a radiating fine striation and which is the representative of the layer of nerve-fibers of the retina, which in this situation is still quite pronounced. In children vivid reflexes often exist which are especially pronounced along the vessels, change their place with every movement of the mirror, and give the retina a luster like that of watered silk. We must avoid regarding these as pathological opacities of the retina. The region of the retina that is most important for vision, the *macula lutea*, with the fovea centralis, is just the part that has very few distinctive ophthalmoscopic features. We find it with the ophthalmoscope, if we go a distance of $1\frac{1}{2}$ to 2 diameters of the papilla outward from the outer border of the papilla. Here we come upon a region devoid of vessels which is somewhat darker than the rest of the fundus. Directly in its center, corresponding to the situation of the fovea centralis, we see a bright point or a small, crescentic spot, caused by reflection of the light from the shelving wall of the retinal depression (Fig. 5, *f*). In the inverted image the macula lutea is represented by a fine white line which forms a horizontal oval of about the size of the papilla. The region inclosed by the line is colored a dark brownish red and sometimes has in its center a little bright dot. These appearances, too, are nothing more than reflexes produced by the light, and like the white spot in the erect image are not constantly present.

The red background on which the appearances above described are visible

is made by the *chorioid*. This owes its red color to the blood circulating in the chorioidal vessels, and especially in the capillaries. That the individual vessels are not themselves recognized, that on the contrary the fundus appears uniformly red, is due to the fact that the pigment epithelium covers the chorioid like a murky veil. A finely granular condition of the chorioid, such as is often perceived in the erect image, is caused by the cells of this pigment epithelium. Under certain circumstances, however, the vessels also of the chorioid are visible. We observe this chiefly under two conditions, viz. :

(1.) In many eyes the interspaces between the chorioidal vessels (the so-called intervascular spaces) have an especially profuse pigmentation, so that they stand out as dark oblong islands; the bright-red striæ running between them and anastomosing everywhere with each other, correspond to the chorioidal vessels which are chiefly veins. Such a fundus is said to be *tesselated* (Fig. 68); it is often confounded with chorioiditis by beginners.

(2.) In other eyes, on the contrary, it is the abnormally scanty pigmentation of the fundus that permits the vascular system of the chorioid to be seen; the epithelial layer, on account of the unduly small amount of pigment which it contains, allowing the chorioidal vessels to appear through it. This is in the greatest degree the case in albinos, who are entirely devoid of pigment. In these the whole network of chorioidal vessels down to the most delicate ramification stands out upon the pale-red background.

The chorioidal vessels are always easy to distinguish from retinal vessels. The chorioidal vessels are broader, less sharply defined, and look flat and ribbon like ; they lack the reflex streak. In opposition to the retinal vessels,



FIG. 10.—CORRECTION OF MYOPIA BY A CONCAVE LENS.
The eye is drawn of the natural size of a myopic eye having an axial length of 27 mm.

which branch after the manner of a tree and do not anastomose, they form by their numerous anastomoses a dense network with oblong meshes.

DETERMINATION OF THE REFRACTION.—The following example serves to explain how the refraction can be determined with the aid of the erect image : Suppose the eye to be examined (*A*, Fig. 10) to be myopic, with its far point at *F* so that the rays coming from *F* are united on the retina at *f* (see § 143). *F* and *f* are conjugate foci, and the course of the rays is therefore the same if they should proceed in the opposite direction—i. e., from *f* toward *F* ; in that case, they would be united at *F*, as they emerge from the eye. A point *f* of the retina, illuminated by the ophthalmoscope, will then emit a bundle of rays con-

verging at F; and at this distance there is produced a clear image of the illuminated fundus. The observer's eye, which is placed at a short distance (a few centimetres) from the eye A, would catch the rays emitted from the latter, before they were united at F—that is, while they still had a certain amount of



FIG. 11.—CORRECTION OF HYPERMETROPIA BY A CONVEX LENS.
The eye is drawn of the natural size of a hypermetropic eye having an axial length of 21 mm.

convergence. But the observer's eye, unless it were hypermetropic, is not in a position to unite convergent rays into a sharp image. If the eye is emmetropic, as we will assume it to be, the rays which fall upon it must first be made parallel, which evidently is accomplished by a concave lens, L. Now, how is this lens related to the degree of myopia of the eye under investigation? If we imagine the course of the rays reversed, then parallel rays coming from in front and falling upon the lens L would be rendered by the latter so divergent that they would come to a focus upon the retina of the myopic eye; the myopic eye accordingly would get sharp vision with this lens for parallel rays—that is, rays coming from an infinite distance. L would therefore be the correcting glass for the myopia of the eye, A. We can hence say this: In order that an emmetropic observer should see clearly the fundus of the myopic eye, A, he must use the same glass that will correct the myopia of this eye. If, therefore, an emmetropic observer has to determine the refraction of a myopic eye with the ophthalmoscope, he keeps placing concave glasses before it until he finds one with which he gets a sharp view of the fundus in the erect image; the glass employed gives directly the degree of the myopia. The same principle holds good for hypermetropic eyes, only that convex instead of concave glasses are required. The rays emitted from the hypermetropic eye, A (Fig. 11), are divergent, and the more so the higher the hypermetropia is. The convex glass, L, which is required in a given case of hypermetropia in order to render parallel the divergent rays emerging from the eye and thus make it possible for the emmetropic observer to perceive the fundus, is the same as that which renders rays falling upon the eye in a parallel direction so convergent that they are united upon the retina, and is therefore the glass which corrects the hypermetropia. Hence the degree of hypermetropia of the eye under examination is given immediately by the convex lens with which the emmetropic observer sees the fundus distinctly.

How is it in those cases in which the physician himself is not emmetropic? In that case he must simply correct in addition his own ametropia. If, for

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

instance, an emmetrope is examining an eye having a myopia of 2 D, he needs for this purpose — 2 D. If the observer himself should have a myopia of 3 D, he would have to take in addition — 3 D for himself ; hence he would employ a glass of — 5 D. If the observer were a hypermetrope of 1 D, he would need + 1 D for the correction of his own ametropia ; this, in combination with the — 2 D which are required for the eye under examination, gives a lens of —1 D. A similar procedure must be adopted in those frequently occurring cases in which the observer is indeed emmetropic, but can not completely relax his accommodation during the ophthalmoscopic examination. He is then to be regarded as a myope, inasmuch as he has to neutralize his residual accommodation by a corresponding concave glass.

The determination of the refraction can evidently be conducted for every point by itself of the visible fundus. So we establish the degree of astigmatism by making accurate adjustment first for the vertical, then for the horizontal vessels running over the papilla, and determining the refraction for both separately. If a point in the fundus projects above its surroundings, as, for instance, the swollen papilla in neuritis, the axis of the eye corresponding to



FIG. 12.—PARALLACTIC DISPLACEMENT OF THE INVERTED IMAGE OF POINTS OF THE FUNDUS, LYING AT DIFFERENT LEVELS.

this point is shorter—that is, there is a hypermetropia. By determining the degree of the hypermetropia we can compute the height of the prominence. Conversely, a point of the fundus which lies farther back (for example, the bottom of an excavation) possesses myopic refraction, from which the linear measure of the amount of depression can be found. As the basis of this computation the rule holds that a difference of level of about one millimetre corresponds to a difference of refraction of 3 D.

Differences of level of the fundus are also made apparent in the inverted image by *parallactic displacement*. We proceed for this purpose by moving the convex lens which serves for the production of the inverted image a little up and down during the examination. If the points of the fundus which we have fixed upon lie all in the same plane, they do not change their relative position to each other with the shifting of the convex lens. If, on the contrary, a difference of level exists between them, we notice a displacement with relation to each other, so that they now come nearer together, now go farther apart. Fig. 12 may elucidate what takes place. Let *a* be a point on the edge, *b* a point

behind it, on the bottom of an excavation of the optic nerve. If the convex lens stands at I, the images of the two points a_1 and b_1 fall behind each other and cover each other. If the convex lens is now brought to II, the image of the point a is reproduced at a_2, that of b at b_2; the points appear to have separated from each other. Had the convex lens been carried in the opposite direction, the apparent displacement of the two points would have taken place in the opposite sense; it would have looked as if the edge of the excavation had been drawn over the bottom of it. From the magnitude of the displacement the difference of level of the two points can be estimated, but can not be exactly computed, as is possible with the aid of the erect image.

It is also possible to determine the refraction with the *inverted image* by the method of Schmidt-Rimpler. Finally, there is a method of determining the refraction, in which we do not require to see the fundus distinctly. This is the method of keratoscopy (also called pupilloscopy, retinoscopy, and skiascopy), discovered by Cuignet. This is in brief as follows: We place ourselves at a distance of rather more than one metre from the patient, and by means of a concave mirror throw light into the pupil, so that the latter is illuminated and appears red. If now the mirror is rotated slightly about its vertical axis, a black shadow appears at the edge of the pupil, and, if the mirror is rotated more strongly, spreads over the whole pupil until the latter is completely darkened. From the direction in which the shadow moves, we can determine the state of refraction of the eye under examination. In myopia of at least 1 D, the shadow moves in the same sense as the mirror; in hypermetropia and also in emmetropia, and in myopia of less than 1 D, it moves in the contrary sense. Suppose, for example, that we have before us a myope. As we turn the mirror from right to left, a shadow appears on the right margin of the pupil, and from there travels across to the left margin (left, that is, as seen by the observer), and therefore moves, like the mirror, from right to left. In order now to estimate the degree of the error of refraction, we place the appropriate glasses in a trial-frame set before the observed eye. With a myope we keep adding continually stronger concave glasses until we come to a glass with which the course of the shadow is reversed—that is, the shadow moves in a direction contrary to that in which the mirror is rotated. This glass, plus 1 D, gives the degree of the myopia. With hypermetropes we keep adding convex glasses until the shadow is reversed and travels in the same direction as that in which the mirror rotates; this glass, less 1 D, corresponds to the degree of the hypermetropia.

This method is of great simplicity; of all methods it is the easiest to learn and has the advantage that in it the refraction and accommodation of the observer do not need to be considered. Withal it gives as exact results as any one of the other methods.

CHAPTER II.

FUNCTIONAL TESTING.

4. BESIDES instituting the objective examination, we have further to test the function of the eye In doing this we are limited almost entirely to the statements of the patient, so that in this respect we are quite dependent upon the latter's intelligence and good-will.

Our visual sensations are of three different kinds, inasmuch as in looking at objects we take cognizance of their form, their color, and their brightness. The faculty by which we recognize the form of objects is called the space-sense, and finds its numerical expression in the visual acuity; the faculty by which we distinguish colors constitutes the color-sense; the faculty by which we distinguish different degrees of brightness constitutes the light-sense. These three faculties are resident in the retina throughout its entire extent, although in very different degrees. In this regard we must distinguish between central and peripheral vision.

Central or direct vision is vision with the fovea centralis. When we wish to see an object distinctly, we "fix" it—that is, we turn the eye in such a way as to make the image of the object fall upon the fovea centralis, as the latter, on account of its peculiar anatomical structure, gives us the sharpest vision that we are capable of. It is with reference to central vision that we test the refraction, the accommodation, and the visual acuity. For more precise particulars in regard to these tests, see the third part of this book, which treats of the optical defects of the eye.

Peripheral or indirect vision is vision with those parts of the retina which do not belong to the fovea centralis. Since the fovea centralis never measures more than one half millimetre in diameter, the parts concerned in peripheral vision comprise by far the greatest part of the retina Vision with the peripheral portion of the retina affords a less distinct, a duller sensation, of which we can best get an idea by holding the outspread fingers of our hand to one side of the eye, while the latter is looking straight ahead. The farther from the fovea centralis is the image produced upon the retina, the more indistinct is the sensation which it excites.

Of what use, then, is peripheral vision, if we can get no well-defined perceptions with it? We can best understand this by observing persons who have lost peripheral vision to such an extent that only the fovea centralis and its immediate vicinity retain their functional activity, as happens in many diseases, especially in retinitis pigmentosa. Such persons can sometimes still read the finest print, and yet are in no condition to go about alone. We can put ourselves in this condition if we fasten in front of the eyes a long tube which allows us to see only the point lying directly in front of our line of vision. We can not go about with such an apparatus, because we strike against objects everywhere. Peripheral vision, therefore, is of service in orientation. How? If, as we are walking, we look straight before us and there is a stone lying in our path, the latter forms an image in the periphery of the retina of our eye, in this case in the upper part of it. The stone, to be sure, is not distinctly perceived, but still it excites our attention. Our gaze is then directed at it; it is seen directly; we recognize it as an obstacle, and avoid it. The same thing happens if we go out upon the street and men come toward us from one side, etc. The images falling upon the periphery of the retina give us warning signals which make us cast our eye directly upon the objects which excite the images. In this regard, it is of great advantage that it is just the peripheral portions of the retina that have a high degree of sensibility for the perception of movement (Exner), so that our attention is attracted most surely by moving objects.

5. Examination of the Field of Vision.—The examination of the field of vision—that is, of the limits of indirect vision—must be made for each eye separately. The eye examined is directed at a fixed point, in order that it may thus remain steadily in the same position, while the other eye is kept closed.

The simplest way of investigating the extent of the field of vision is by using the *hand* as a test-object. The physician places himself directly in front of the patient and at a short distance from him; the patient fixes his gaze upon the eye of the physician, which is opposite to him. The physician now gradually moves his hand from the periphery inward over the limits of the field of view; the patient must tell as soon as he sees the hand. In this way the physician has in his own eye a means of judging the field of view of the patient; if this is normal, the patient must see the hand at the same time that the physician does with his eye.* This method is sufficiently exact for the recognition of the larger encroachments upon the visual field; but small defects can not be thus recognized. It is the only method of testing, applicable in

---

[* This presupposes that the physician shuts the eye corresponding to that which he is examining (i. e., his own left eye, if he is examining the patient's left eye), and holds his hand in a plane midway between the patient and himself.—D.]

those cases in which smaller test-objects are no longer made out, because the vision is too poor. If the patient is no longer in condition to see even the hand, we must make use of a candle-flame which we carry about through the field of vision. In this way, for instance, we test the visual field of a person who is blind from cataract.

We can get at the field of vision more exactly by means of a *blackboard*. We place the patient before this and take care that during the examination the distance between the eye and the board remains always the same (e. g., 30 cm.). Directly opposite the patient's eye we make a mark on the blackboard with chalk, and direct him to fix his gaze on this mark during the examination. The chalk is now gradually brought from the edge of the blackboard to its center, and the patient is to tell at what moment he first sees it. By marking on the blackboard the limits of the visual field in every direction and connecting the points thus determined, we fix the extent of the field of vision. The size of he latter is, of course, in direct proportion to the distance from the eye, at which it is received.

Even this method is not entirely free from drawbacks, which spring from the difficulty of projecting a hollow sphere upon a plane. The most important drawbacks are the following: Unequal distances in the field of vision correspond to equal distances on the retina. Thus, in Fig. 13, the distances *ma* and *bc* upon the retina are equal, each corresponding to an angle of ten degrees. In the field of vision projected on the board, *TT*, however, the section (from 70° to 80°) that corresponds to the second region of the retina is many times greater than that (from 0° to 10°) which corresponds to the first. Hence, a spot upon the retina of definite size that has become insensitive to light would in such a visual field appear as a gap, the size of which would be quite different according as it is nearer to or farther from the center, and thus mistakes might be caused. A second evil is that the whole of a normal visual field does not find a place on a plane, be the latter ever so large. The normal field of vision, that is, extends outward to 90° and more. Therefore, as is evident from Fig. 13, the temporal limit of the visual field can never be projected on the board.

After what has been said, therefore, there is only one exact method of representing the visual field, and that is the projection of it upon a hollow sphere (Aubert). Upon this principle different *perimeters* are constructed. To Förster belongs the credit of having introduced this instrument into ophthalmic practice. Förster's perimeter consists, not of a complete hemisphere, but of a metallic semicircle (Fig. 13, *P*) which represents, as it were, one meridian of the hemisphere. The semicircle is capable of being revolved so as to take the direction of each meridian in succession. The patient supports his head on a chin-rest which is so placed in front of the semicircle that the eye to be examined is situated in the center of curvature of the latter. In the ex-

amination, the eye must be fixed upon the middle point of the semicircular arc, while the mark that serves for the test is carried to and fro along the latter. A scale of degrees marked upon the semicircular arc enables us to read off directly the situation of the boundary of the visual field, and the result obtained is transferred to a diagram (Fig. 14).

FIG. 13.—PROJECTION OF THE VISUAL FIELD.

The field of vision of the eye, *A*, projected in the semicircle of the perimeter, *P*, extends from 65° on the nasal side to 90° on the temporal side, corresponding to the points, *e* and *d*, of the retina. These mark the anterior border of the sensitive portion of the retina, which extends farther forward on the nasal side than on the temporal. On a flat surface, *T T*, the field of vision can not be represented as far as its temporal limit, since its projection, *O*, falls outside of the surface.

6. Extent of the Field of Vision.—The normal field of vision, as a glance at the appended diagram (Fig. 14) shows, does not by any means extend equally far in all directions. It stretches farthest toward the external (temporal) side, where it has an extent of over 90°. Accordingly, we can still see objects on the temporal side, although they lie in, or even somewhat behind, a plane passing through the pupil (for example, the point *O* in Fig. 13). This is rendered possible by the fact that the rays from such a point undergo such strong refraction at the surface of the cornea that they can still enter the pupil. The field of vision is much less extensive in other directions, especially to the inside, and to the inside and below. The cause of this is to be sought for in the fact that the nose and the eyebrows project into the field of view and limit it. This obstacle can indeed be partially overcome by making suitable rotation of the head while the field of vision is being examined, but even then we never find the field of vision as extensive on the nasal side as it is on the temporal. The cause of this is that the margin of the percipient layers of the retina does

not extend as far forward on the temporal side as on the nasal (Fig. 13, *d* and *e*).

The *pathological alterations* of the visual field consist in its curtailment. This is either produced by a pushing in of the boundary of the visual field at some point, or it occurs under the form of gaps lying like islands inside of the field of vision.

Narrowing of the visual field *at the periphery* presents varying characters. If the limits of the visual field are brought nearer to the



FIG. 14.—FIELD OF VISION OF THE RIGHT EYE FOR WHITE, BLUE, AND GREEN. (AFTER LANDOLT.)

F, point of fixation ; *M*, Mariotte's blind spot.

center from all points alike we speak of a concentric contraction. When this is considerable, it results in that incapacity for orientation which has been already described, although it may be that direct vision (visual acuity in the narrower sense) is still quite good. In other cases, the contraction extends from one side only of the periphery into the visual field. If it has the shape of a triangle whose base corresponds to the periphery of the visual field, it is called a sector-shaped contraction. A peculiar variety of contraction of the visual field is the hemi-

opic, in which exactly one half of the field is wanting (see § 101 and Figs. 87 and 88).

Island-like gaps in the visual field are called *scotomata.** One of these exists in the healthy eye at that point of the visual field which corresponds to the entrance of the optic nerve, and is known as Mariotte's blind spot (Fig. 14, *M*). In the field of vision it lies about 15° to the outside of the point of fixation, *F*. The scotomata which occur as the result of disease have a very different significance for vision according to their situation; and, according to the latter, we distinguish them into central and peripheral. A central scotoma is one which involves the point of fixation. In this case direct vision is either greatly diminished or is abrogated altogether. The patient can no longer do any fine work, although his power of orientation remains intact. Peripheral scotomata cause little disturbance of sight, especially if they lie far from the point of fixation, in which case they may not come to the patient's knowledge until his visual field is being examined. A special variety of scotoma is the annular, which encircles the point of fixation like a ring (which is not always completely closed), but leaves intact the point of fixation itself.

Von Graefe was the first to call attention to the importance of testing the visual field in ophthalmic practice. He showed that for many intra-ocular diseases there are special varieties of contraction of the visual field, which are more or less characteristic of these diseases, and can be utilized for their diagnosis. Since then the study of the visual field has been much cultivated, so that at present its examination has great significance, both for diagnosis and prognosis.

Concentric contraction of the visual field, associated with retention of good central vision, we meet with especially in retinitis pigmentosa, and sometimes also in glaucoma. In other diseases which are frequently accompanied by concentric contraction of the visual field, as, for instance, in atrophy of the optic nerve or of the retina, central vision is also simultaneously and markedly affected.

We find the sector-shaped deficiencies especially in atrophy of the optic nerve; also in occlusion of one of the larger retinal arteries, when the sector-shaped district of the retina supplied by such an artery has its function abrogated. We observe more extensive, although not triangular, contractions of the visual field in detachment of the retina, and these most often extending in an upward direction, since the detachment, if of long standing, generally involves the lowermost part of the eye. In glaucoma a contraction of the visual field toward the nasal side is of relatively frequent occurrence.

Scotomata are most frequently met with in diseases of the fundus with circumscribed lesions; especially, therefore, in chorioiditis disseminata, in which, as a rule, the gaps in the visual field correspond to the separate maculæ visible with the ophthalmoscope. So long as these gaps affect the periphery only of the visual field, they cause little disturbance of sight. If they are very numerous, the visual field acquires a sieve-like character. If, finally, one of the cho-

* From *σκότος*, darkness.

rioiditic masses is localized at the region of the chorioid corresponding to the yellow spot the visual power is very considerably depressed by the formation of a central scotoma in addition to those in the periphery.

Isolated central scotomata occur in diseases of the chorioid at the posterior pole of the eye, especially as a result of syphilis and of myopia of a high degree. In the latter, moreover, hæmorrhage into the macula lutea very often occurs with a central scotoma as a sequel. In this way many myopes lose their visual power, which hitherto has been sufficient for their needs, and become incapable of working. In all these cases there corresponds to the scotoma a change in the macula lutea, visible with the ophthalmoscope. In another series of cases, on the contrary, a central scotoma exists, while the result of the ophthalmoscopic examination is negative; the cause of the scotoma is then to be looked for in the optic nerve. In the latter it is just those fibers which supply the region of the macula lutea that are the most favorite seat of disease (in retro-bulbar neuritis; see § 103).

As the expression scotoma is used in different senses, it will require in this place a more precise explanation. We distinguish between positive and negative scotomata (Förster).

By a *positive scotoma* we understand a dark spot which the patient perceives in his visual field—projects, that is, upon some portion of his visual field. The cause of a positive scotoma lies either in the refracting media or in the retina. Opacities in the refracting media throw their shadow upon the retina, and are therefore visible as dark spots. If the opacities lie in the vitreous they are motile (muscæ volitantes), and the scotomata caused by them are characterized as motile scotomata. Fixed scotomata originate either from stationary opacities (e. g., those in the lens), or, still more frequently, from changes in the fundus (e. g., from an exudation in the retina or in the chorioid adjacent to it). Scotomata of the latter kind are best brought to light by making the patient fix his gaze upon a uniformly bright surface (e. g., a sheet of white paper). They are often more readily perceived if the illumination is at the same time diminished (as by letting down the window curtains). We can direct the patient to make a copy of the dark spots that become visible upon the paper, and from this we can determine the position and extent of the diseased portions of the retina.

We characterize as a *negative scotoma* a hiatus in the visual field, an isolated spot within the confines of which the patient does not perceive any external objects. Such a scotoma, accordingly, is not discovered as a rule until the visual field is examined. But there is nothing to prevent a negative scotoma from being at the same time a positive one too; the same diseased regions of the retina that are insensitive to external luminous impressions can at the same time be themselves perceived as dark spots and be projected exteriorily.

Negative scotomata are divided into absolute and relative. An absolute scotoma is present if within its limits all perception of light is wanting, while with relative scotomata the perception of light is merely diminished. We discover a relative scotoma by making the examination of the visual field with small objects, and especially by choosing colored objects for this purpose. For with a certain diminution of the visual power the ability to distinguish colors accurately disappears, while the outlines of objects can still be recognized. For example, in a recent case of chronic poisoning by nicotine, the visual field, measured with the aid of a white test-object, may seem quite normal; but if a small

red paper disk is chosen for the examination there is a small region in the center in which the disk is no longer recognized as red. A relative scotoma is present, and that, moreover, a color-scotoma (scotoma for red).

Even in the normal visual field the perception of colors is not everywhere the same. Just as in regard to the visual acuity, so also in regard to the color-sense, a distinction must be made between central and peripheral color-perception. While the former is tested by the mere exhibition of colored samples, the latter must be investigated, just like the visual field, by using as test-objects colored marks, which are moved to and fro on the board or on the perimeter. By such examinations it has been proved that the most peripheral portions of the retina are color-blind. If a colored substance is pushed from the periphery of the visual field toward the center, the person examined at first recognizes only the presence of a moving object. It is not till the substance approaches nearer the center of the visual field that its color is correctly given. The moment when this occurs is not the same for all colors, some being recognized further out from the center than others. The visual field for green is the smallest, that for red somewhat larger, that for blue the largest (see Fig. 14), while, as has been said, the extreme periphery of the visual field is quite color-blind.

The examination of the visual field with colored objects is of great practical importance. For instance, we find in one case the visual field normal when tested with white, while the examination with colors shows already a considerable introcession of its borders at one spot. After some time, if the disease has progressed, we now, on testing with white, establish the same deficiency in the visual field that had before existed for colored objects only. The examination with colors is accordingly a more delicate test than that with white; it makes us discover a diminution of the visual power before it has advanced so far that a white object can no longer be recognized. If, therefore, we take two cases in which the visual field for white is equally large, but the visual field for colors is unequal, that case in which the visual field for colors is smaller affords the worse prognosis, since here a still further diminution of the general visual field is to be expected. Rapid diminution of color perception is pre-eminently associated with the progressive lesions of the optic nerve that lead to blindness. The examination of the visual field with colors is also requisite for the recognition of central scotomata, so long as they are not absolute.

Light-Sense.—Let us assume that we have before us two persons who in ordinary daylight have the same visual acuity; both under equally good illumination read print of the same size at the same distance. We now gradually lessen the illumination. As a result of this, the difference in brightness between the black letters and the white paper diminishes and the letters are distinguished with greater and greater difficulty. At a certain stage in the process of obscuration, one of the two persons ceases to recognize the print while the other is still able to read, and the darkening has to be carried further in order to make reading impossible for him. In this case we say: The two persons have the same space-sense, i. e., the same susceptibility of the retina for impressions of forms, but they have a different light-sense (L)—i. e., a different susceptibility for impressions of brightness and of differences of brightness.

The light-sense can be tested in various ways. We determine either the lowest limit of illumination with which an object is still visible (minimum stimulus) or the smallest difference in brightness which can still be appreciated

(minimum of differentiation). The most usual method of measuring the light-sense is with Förster's *photometer*, which gives the minimum stimulus. A box, *A* (Fig. 15), blackened on the inside, bears on its anterior wall two apertures for the two eyes, *a* and a_1, which look through these apertures at a plate, *T*, which is placed upon the posterior wall, and upon which large black stripes upon a white ground are placed as test-objects. The illumination is produced by a normal candle,* *L*, the light from which falls through a window, *F*, into the interior of the box. In order to make the illumination perfectly uniform, the window is covered with paper which is made translucent (by impregnating it with fat). By a screw, *S*, the size of the window can be altered from complete closure up to an aperture of five square centimetres. In this way the illumination of the plate is varied. The patient is then made to look into the apparatus with the window closed and the plate therefore unillumined. Then the window is slowly opened until the stripes upon the plate can be recognized. The size of the opening requisite for this purpose gives a measure of the light-



FIG. 15.—PHOTOMETER OF FÖRSTER.

sense of the person examined. In conducting this examination the precaution must be adopted of making the person that is examined stay beforehand in darkness. If we come from daylight into a moderately darkened room we see so little for the first moment that we can not move about without stumbling over the objects in the room. The longer we remain in the latter the better we see, and at last, perhaps, see well enough to be able to read. This we call *adaptation* of the retina. In the examination of the light-sense, a period of adaptation of ten minutes, which the patient must pass with bandaged eyes in a perfectly dark room, is sufficient for practical purposes.

The examination of the light-sense in different diseases has shown that it is not always by any means diminished in proportion to the visual acuity, but is sometimes but little diminished, sometimes excessively so, a circumstance from which diagnostic points may be gathered. The diminution of the light-sense is greatest in those cases which are characterized as hemeralopia (see § 105).

SIMULATION OF BLINDNESS.—In testing the function we shall at times have to reckon with the fact that the patient is purposely trying to lead the physician astray by simulating blindness or weakness of sight when these do not exist. This most frequently occurs with those persons who wish to be relieved of mil-

---

[* I. e., one of one-candle power. D].

itary service or who wish to get testimony as to their inability to work ; sometimes also with children, hysterical persons, etc. We are first led to suspect simulation by the lack of agreement between the results of the functional testing and of the objective examination ; an eye, for example, which is alleged to be perfectly blind presenting no pathological changes of any sort. Or the tests of the individual functions give contradictory results, inasmuch as the visual acuity, the field of vision, the color-sense, etc., do not stand in the right relation with each other and with the result of the objective examination. Various methods of examination have been proposed for furnishing a certain proof of simulation; we shall accomplish this more or less readily by their aid according to the degree of skill of the simulant. Only some of these methods need be here adduced.

Complete blindness of both eyes is rarely simulated; much oftener it is simply unilateral blindness that is alleged ; and still more frequently a feebleness of sight actually present in one eye is exaggerated (aggravation). In the case of an alleged complete blindness of one or both eyes we regard in the first place the reaction of the pupil to the light. If this is well-preserved, it will always afford a strong ground for suspecting simulation, although there are rare cases in which in the presence of actual blindness the pupillary reflex for light is still retained. Schmidt-Rimpler recommends the following procedure: The patient is made to look with the blind eye at his own hand, which he holds in front of him. A blind man will do this without hesitation since he is informed of the position of his hand by the sense of feeling ; a malingerer will perhaps look purposely in the wrong direction. Simulated unilateral blindness can also be discovered in the following way: A lighted candle is brought in front of the good eye and is slowly carried toward the side of the blind eye. The patient is detected if he declares that he still sees the candle at the moment when it is just concealed from the sound eye by the dorsum of the nose (Cuignet).

The following methods are furthermore of service in detecting the simulation of unilateral blindness or amblyopia.

1. We make the patient read, and then hold a pencil in a vertical direction between the eye and the book. If there is vision with only one eye the pencil conceals certain words from it, and thus interferes with reading. If, however, there is good vision with both eyes, those letters which are concealed from one eye by the pencil are visible to the other, and vice versa, and reading is carried on without difficulty (Cuignet).

2. A convex glass of 6 D is placed before the sound eye. In this way the eye is made artificially myopic, so that its far point lies at a distance of about 17 cm. (it being presupposed that the eye is emmetropic). The eye can therefore read fine print only at a distance of 17 cm. or less, but no further. After placing the glass before the eye we first make the patient read at quite a short distance, and then slowly and imperceptibly move the book farther and farther away. If it is possible in this way to withdraw the book considerably farther than 17 cm. without the patient's ceasing to read, it proves that he has been reading with the eye alleged to be bad. That is, he began reading with the good eye and, when the book was carried too far off for that, continued with the other eye, without noticing the alternation in the employment of the two eyes.

3. We make a show of occupying ourselves with the sound eye only. We

hold before the latter a prism in such a way that the refracting edge is horizontal and extends transversely across the middle of the pupil. In this case two images of every external object will be thrown upon the retina, one transmitted through the free half of the pupil, the other through the half covered by the prism, and the eye sees double the object upon which it is fixed (monocular diplopia)—a fact which the patient will admit without hesitation, since, of course, it is the sound eye only that is concerned in the matter. Now the prism is imperceptibly pushed along until it covers the entire pupil. Now the eye that is provided with the prism again has only one single retinal image, which, however, is thrown upon a higher or lower point of the retina than is the case in the other eye. If now there is still double vision (binocular diplopia), it is a proof that both eyes see. If we use the reading-test for this examination and compel the person under examination to read sometimes the upper, sometimes the lower of the two double images, we can determine directly the visual acuity of each eye separately without the patient being aware of it (Alfred Graefe).

4. Snellen has constructed a board with test-types which are alternately red and green. To read it, a pair of spectacles is put upon the patient, in which are introduced a red glass for one eye and a green glass for the other. Through the red glass the red letters alone, and not the green, can be seen, because green is the complementary color of red, and, therefore, green rays are not transmitted through red glass. For the same reason the red letters can not be perceived through the green glass.* If, therefore, any one who is blind in one eye looks through these spectacles at the test-types, he will read off only the red, or only the green letters, according as the red or the green glass of the spectacles is placed in front of the eye which alone can see. He will not once suspect that still other letters of a different color lie between the letters that he has read. Should the patient, on the other hand, read all the letters it proves that he sees with both eyes and in such a way as to recognize the red letters with one eye and the green with the other.

For the tests for the motility of the eye and for binocular vision, see § 123.

[* This test presupposes that the letters are placed upon a black ground. Red letters on a *white* ground become invisible when looked at through a red glass, since the latter, allowing only red rays to pass through it, excludes from the white ground surrounding the red letters all rays except those which the latter themselves emit, and hence both ground and letters appear of the same color. Red letters on a black ground appear much lighter—indeed, almost white—when viewed through a red glass. D.]

PART II.

DISEASES OF THE EYE.

CHAPTER I.

DISEASES OF THE CONJUNCTIVA.

ANATOMY.

7. THE *conjunctiva* coats the posterior surface of the lids and the anterior surface of the eyeball. It forms a sac, the conjunctival sac, which is slit open anteriorly in a line corresponding with the palpebral fissure. In the conjunctiva we distinguish three divisions. That part of the conjunctiva which covers the posterior surface of the lids and which is closely adherent to the tarsus is called the conjunctiva tarsi; that division which coats the anterior surface of the eyeball is the conjunctiva bulbi. The connection between the two is formed by the third division, which we name the transitional part of the conjunctiva (conjunctiva fornicis). That region where the conjunctiva is reflected from the lids to the eyeball and which forms the bottom of the conjunctival sac is called the fornix conjunctivæ.

We get a view of the *conjunctiva tarsi* in the living eye by everting the lids. It has a smooth surface and is intimately and immovably adherent to the subjacent tarsus (Fig. 16, *t*). (It is therefore impossible to cover up losses of substance of the palpebral conjunctiva by performing an operation to draw the adjacent conjunctiva over them, as is often done with the conjunctiva bulbi.) On account of its thinness, the conjunctiva tarsi allows the Meibomian glands, which lie in the tarsus itself, to be seen through it clearly.

The microscope shows that the palpebral conjunctiva is covered with a laminated cylindrical epithelium. The mucous membrane proper is of adenoid character—that is, even in the healthy state it contains an abundant quantity of round cells (lymph-corpuscles), which notably increase in number with every inflammation of the conjunctiva. Of glands it possesses acinous mucous glands, which are found along the convex border of the tarsus (Fig. 16, *w*; Waldeyer); analogous glands (Krause's glands) are also present in the fornix conjunctivæ.

The conjunctiva of the upper lid obtains its blood-supply from two arterial arches, the arcus tarseus superior (*as*, Fig. 16) and the arcus tarseus inferior (*ai*, Fig. 16). These lie upon the anterior surface of the



FIG. 16.—PERPENDICULAR SECTION THROUGH THE UPPER LID. MAGNIFIED 5 × 1.

The skin of the lid presents in the upper part, above a sulcus, the protecting fold, *d*; below, it covers the anterior edge of the lid, *v*. In the skin are found fine hairs, *e*, *e*, sweat-glands, *a*, cilia, *c*, *c*, *c*, and in the neighborhood of the latter Zeiss's glands, *z*, and the modified sweat-glands, *s*. Beneath the skin lie the transversely-divided bundles of fibers of the orbicularis, *o*, *o*, of which those placed most internally, *r*, *r*, form the musculus ciliaris Riolani. The posterior surface of the lid is covered by conjunctiva which at the fold of transition, *b*, shows an adenoid character, but over the tarsus, *t*, shows papillæ, especially where it corresponds to the convex border, *co*, of the tarsus. The Meibomian glands, *g*, have their orifices, *m*, in front of the posterior edge, *h*, of the lid; above them lie Waldeyer's mucous glands, *w*, and still higher Müller's musculus palpebralis superior, *p*, and the levator palpebræ superioris, *l*. From the latter the leash of fibers, *l*, passes to the skin of the lid. *as* is the arcus tarseus superior; *ai*, the arcus tarseus inferior; from the latter the rami perforantes, *rp*, run, at first straight downward, then backward, through the tarsus.

tarsus, near its upper and its lower edges. To reach the conjunctiva, the branches of the arcus tarseus inferior (*rp*, Fig. 16) perforate the tarsus through its entire thickness from before backward, two to three

mm. above the free edge of the lid. The line along which the vessels come out from the tarsus is marked by a shallow furrow (sulcus subtarsalis) on the conjunctival surface of the lid. On the lower lid there is only one arterial arch.

The conjunctiva of the region of transition is very readily brought to view in the lower lid by drawing the lid down while the eye looks up. In the upper lid, on the contrary, the fold of transition is hard to see, unless we make a double eversion of the lid. The region of transition is the loosest part of the conjunctiva, this being here so abundant that it lies in horizontal folds. This arrangement insures the eye its free power of movement. If the conjunctiva were to pass directly from the lid to the eye, as is sometimes observed in consequence of disease of the conjunctiva, every movement of the eyeball would be transmitted to the lids; and if one of the lids was held still with the finger, the eyeball would be hampered by it in its movements. But the conjunctiva is present in such quantity at the fornix that the eye is able to move in complete independence of the lids, the folds in the region of transition being smoothed out or crumpled together, as the case may be. Appearing through the lower fold of transition are the extensive subjacent plexus of veins and also the white glistening fascia. Its lax character and also its abundant blood-supply render the fold of transition particularly liable to great swelling in inflammations of the conjunctiva.

The *conjunctiva bulbi* covers the anterior surface of the eyeball. It has no aperture corresponding to the cornea, but continues, even if with altered character, over the latter. This continuity of the conjunctiva makes it plain to us why morbid processes of the latter do not stop at the margin of the cornea but are continued upon the surface of the latter, as we see very clearly in trachoma and in conjunctivitis lymphatica. The two divisions of the conjunctiva bulbi are distinguished as the conjunctiva scleræ and conjunctiva corneæ. The conjunctiva corneæ is perfectly transparent, and is so intimately adherent to the cornea proper that it must be regarded as the uppermost layer of the latter, and is better treated of at the same time with the cornea itself (see § 29).

The conjunctiva scleræ covers the anterior segment of the sclera in the form of a thin pellicle. It is connected with the sclera by lax connective tissue (the episcleral tissue) so loosely that it can readily be moved about from side to side upon the sclera. It is only at the periphery of the cornea where it ends in a sharp edge, the limbus * conjunctivæ, that the conjunctiva scleræ is intimately adherent to its substratum. It is very thin and elastic and lets the white sclera be seen through it plainly, thus forming the "white of the eye." In old peo-

* *Limbus*, edge.

ple there is a spot at the inner and the outer margins of the cornea, which contrasts by its yellow color with this whiteness. This has the shape of a triangle with its base at the corneal margin, and projects a little above the rest of the conjunctiva. It is called the interpalpebral spot or the pinguecula,* and is produced by the fact that that part of the conjunctiva which, being included in the interpalpebral fissure, is constantly exposed to atmospheric influences, has undergone an alteration in its tissues.

The conjunctiva scleræ is covered with laminated pavement epithelium and contains no glands. At the inner angle of the eye it forms a crescentic duplication, the semilunar fold (plica semilunaris), which represents an abortive remnant of the palpebra tertia of animals. To the inside of the semilunar fold is a small, reddish, nipple-like prominence, the caruncle,† which occupies the bottom of the horseshoe-shaped excavation at the angle of the eye (Fig. 24, *C*). This is shown to be histologically a small island made of skin, containing sebaceous and sweat glands and having its surface covered with delicate light-colored hairs.

The conjunctiva of the eyeball receives its blood-vessels chiefly from the vessels of the fold of transition—the posterior conjunctival vessels (Fig. 17, *o* and o_1). Furthermore, the anterior ciliary vessels (Fig. 17, *e* and e_1) take part in supplying the conjunctiva with blood. These vessels come from the four recti muscles (*R*, Fig. 17) and run under the conjunctiva (through which they are visible, shining with a bluish luster) until near the edge of the cornea, where they suddenly disappear, since they pass through the sclera into the interior of the eye. But, before this happens, they give off branches which end in vascular loops, in the limbus conjunctivæ directly at the margin of the cornea (marginal network of the cornea—*q*, Fig. 17). This latter is of great importance for the cornea which is chiefly dependent upon it for its nutrition. Other branches of the ciliary vessels (anterior conjunctival vessels, *p*, Fig. 17) run backward in the conjunctiva toward the posterior conjunctival vessels and anastomose with them.

We have, therefore, in the conjunctiva two vascular systems—that of the posterior conjunctival vessels and that of the anterior ciliary vessels. According as the one or the other system is overdistended with blood, the conjunctiva has a different aspect, which we designate respectively as conjunctival and as ciliary injection.

Conjunctival injection presents to us a superficially disposed network of larger and smaller vessels, whose situation in the conjunctiva can be demonstrated by the fact of their being capable of displacement along with the conjunctiva. The color of the injection is a vivid scarlet or brick-red; the individual vascular meshes are plainly to be

---

* *Pinguis*, fat. † *Caruncula*, dim. of *caro*, flesh.

recognized. This injection is characteristic of diseases of the conjunctiva itself.



FIG. 17.—BLOOD-VESSELS OF THE EYE (SCHEMATIC, AFTER LEBER).

The *retinal system of vessels* is derived from the central artery, a, and the central vein, a_1, of the optic nerve, which give off the retinal arteries, b, and the retinal veins, b_1. These end at the ora serrata, *Or*.

The *system of ciliary vessels* is fed by the posterior short ciliary arteries, c, c, the posterior long ciliary arteries, d, and the anterior ciliary arteries, e. From these arise the vascular network of the choroidal capillaries, f, and of the ciliary body, g, and the circulus arteriosus iridis major, h. From this last spring the arteries of the iris, i, which at the lesser [inner] circumference of the latter form the circulus arteriosus iridis minor, k. The veins of the iris, i_1, of the ciliary body, and of the choroid are collected into the vasa vorticosa, l; those veins, however, that come from the ciliary muscle (m) leave the eye as anterior ciliary veins, e_1. With the latter Schlemm's canal, n, forms anastomoses.

The *system of conjunctival vessels* consists of the posterior conjunctival vessels, o and o_1. These communicate with those branches of the anterior ciliary vessels which run to meet them; that is, with the anterior conjunctival vessels, p, and form with these the marginal loops of the cornea, q. *O*, optic nerve; *S*, its sheath; *Sc*, sclera; *A*, chorioid; *N*, retina; *L*, lens; *H*, cornea; *R*, internal rectus; *B*, conjunctiva.

Ciliary injection occurs as a rose-red or pale-violet zone round the cornea (hence the designation peri- [circum-] corneal injection), in which we are unable to recognize clearly any individual vessels. With injection of greater intensity we see, still farther removed from the cornea, a coarser network of vessels, which are to be recognized as deeply placed by their violet color and their hazy appearance; by the fact, moreover, that when the conjunctiva is displaced they do not move with it. Ciliary injection is most markedly distinguished from that of the conjunctiva by its violet hue as well as by the diffuse appearance of the redness, due to the fact that the individual engorged vessels are recognized either indistinctly or not at all. Ciliary injection most frequently accompanies diseases of the cornea, and also of the iris and the ciliary body, parts which belong to the vascular district of the anterior ciliary vessels. On account of the numerous anastomoses between the two vascular districts of the conjunctiva, we find both injected in every inflammation of any great violence in the anterior section of the eyeball; it is, however, still generally possible to recognize, along with the superficial conjunctival injection, the ciliary injection, more deeply situated and directly surrounding the cornea.

The conjunctiva of the tarsus is really perfectly smooth only in the young. In older persons we find it having a velvety surface on the upper lid toward the angles of the tarsus, and often also along the entire convex edge of the tarsus (Fig. 16, *co*). This condition of the conjunctiva we call papillary. In reality, however, it is not, properly speaking, papillæ which are here found in the conjunctiva, but fine folds into which the surface of the somewhat hypertrophied conjunctiva has been thrown. In microscopic sections through regions of the conjunctiva, which have undergone this change, the transversely divided folds look like papillæ, between which the epithelial lining dips down deeply. Should the sloping sides of two such folds lie very close to one another, the epithelial-lined depression between the folds can in cross-section give the impression of its being a glandular tube (*i*, Fig. 20). In this way is to be explained the alleged new formation of tubular glands, which have been found in some cases of so-called papillary hypertrophy of the conjunctiva. Nevertheless, it is not to be denied that true tubular glands do exceptionally occur in the conjunctiva, both normal and diseased. These are called, after their discoverer, Henle's glands (Fig. 21, *d*).

With regard to the papillary character of the conjunctiva at the upper border and at the angles of the tarsus, it is a question whether this is ever to be considered as perfectly normal and not rather as a product of repeated hyperæmia of the conjunctiva. The same question must be put in regard to the adenoid character of the conjunctiva, which is looked upon by many as also the residuum left by a previous inflammatory irritation. Since this mucous membrane is exposed more than any other to external influences, attacks of hyperæmia of it occur often to every man in the course of his life, and these may result in permanent alteration of the membrane. The action of external injuries shows itself most plainly in forming the pinguecula. This corresponds precisely to that region of the conjunctiva which is most exposed to wind, dust,

etc. This interpalpebral spot owes its name pinguecula to its yellow color, which was formerly referred to deposition of fat in the conjunctiva. What actually exists, however, is a thickening of the conjunctiva, chiefly as the result of an increase in the number and size of its elastic fibers. Associated with this is the formation of numerous concretions of a yellowish colloid substance, to which in fact the pinguecula owes its yellow color. As a result of these changes, the conjunctiva in this place becomes less transparent, for which reason the pinguecula appears most prominent when the conjunctiva bulbi is markedly reddened, whether from injection or from extravasation of blood. In this case the pinguecula does not allow the red color of the blood to shine through as plainly as does the adjacent conjunctiva that is not thickened, and the former, therefore, stands out from the red substratum in the form of a light-colored triangle, so that by beginners it is easily confounded with a diphtheritic infiltration of the conjunctiva, or, when the yellow color is pronounced, with a small pustule.

I. Conjunctivitis Catarrhalis.

(*a*) *Conjunctivitis Catarrhalis Acuta.*

8. **Symptoms.**—Acute conjunctival catarrh, in the *lighter* cases, chiefly affects the conjunctiva of the lids and of the region of transition. The conjunctiva of the lids presents a vivid redness and is relaxed. The injection is usually reticulate—i. e., the separate vessels can still be distinguished as such; it is only when the injection is especially dense that the conjunctiva acquires a uniformly red appearance. The surface of the conjunctiva is smooth; catarrh is thus distinguished from some other forms of inflammation of the conjunctiva in which the latter is infiltrated and subsequently hypertrophied, as shown by the unevenness of its surface. The fold of transition (as well as the semilunar fold) is likewise greatly reddened and is somewhat swollen, while the conjunctiva bulbi shows little or no change.

The *severer* are distinguished from the lighter cases by the fact that the process invades the conjunctiva bulbi. The redness and swelling of the palpebral conjunctiva are greater, and moderate œdema of the lids is often present at the same time. Very frequently we find in the midst of the reticulate injection red-colored spots—i. e., small hæmorrhages, ecchymoses of the conjunctiva—produced by rupture of small vessels. The severer cases, in which the conjunctiva is affected throughout its entire extent, are designated under the name of *ophthalmia catarrhalis*, to distinguish them from the lighter forms, which are named conjunctivitis catarrhalis without qualification.

Inflammation of the conjunctiva is accompanied by increased *secretion* from the latter. The secretion of the conjunctiva appears under the form of flakes of mucus, swimming in the abundant lachrymal fluid. The more intense the inflammation the greater the secretion, and the more the character of the latter changes from mucous to purulent. Violent cases of ophthalmia catarrhalis, therefore, are in their

inception often hard to distinguish from an acute blennorrhœa of light intensity, although, of course, the subsequent development of the case makes the diagnosis clear. The secretion which exudes from the palpebral fissure dries at night upon the edges of the lids and glues them together.

The *subjective* symptoms consist of copious lachrymation, photophobia, and itching and burning of the eyes. The intensity of the annoyance given depends naturally upon the degree of inflammation. Violent pains, however, are but rarely present, and then, as a rule, are excited, not by the catarrh itself, but by its complications (especially ulcers of the cornea). A very troublesome sensation that is frequently present is that of a foreign body being in the eye, caused by flakes and filaments of tough mucus in the conjunctival sac. If such filaments lie upon the cornea, they produce the disturbances of sight of which the patients sometimes complain. These are distinguished from visual disturbances of more serious character by the fact that clear vision is immediately restored by brushing the mucus off with the lids. It is a characteristic feature of catarrh that all its disagreeable characters are least pronounced in the morning, and afterward gradually increase until they reach their highest point in the evening.

Course.—This is favorable in uncomplicated cases, the inflammation disappearing spontaneously after from eight to fourteen days. Not infrequently, however, there remains a condition of chronic inflammation (chronic conjunctival catarrh), which, to be sure, causes less annoyance than the acute stage, but which is yet protracted over a comparatively long time. In the majority of cases acute conjunctival catarrh attacks both eyes, either both simultaneously or one eye a few days after the other.

The *complications* which are observed in catarrh are corneal ulcers and iritis. The development of corneal disease is manifested by an increase in the pain and photophobia. At first we recognize, in the neighborhood of the corneal margin, small gray points, which are arranged in a row concentric with the corneal margin. On the days following, these punctate infiltrations of the cornea become more numerous and at length confluent, so as to form a small gray crescent. By a process of superficial disintegration an excavation is produced, so that finally a crescentic ulcer is formed, situated very near the corneal margin and concentric with it. Such ulcers are characteristic of conjunctival catarrh and are hence called *catarrhal ulcers*. Ordinarily the ulcer becomes clean quickly and heals, leaving behind it a slight arcuate opacity; in cases, however, that are of especial intensity, perforation of the cornea may occur. The existence of a corneal ulcer is frequently a cause of iritis—a contingency, indeed, which is observed in ulceration of the cornea of every sort; but a violent catarrh can also be complicated with iritis directly, without a corneal ulcer being present.

The complications above mentioned are observed only in severe cases—that is, only in ophthalmia catarrhalis. They very often owe their existence to faulty treatment of the catarrh. Among the laity, all sorts of household remedies are in use for inflammation of the eyes, such as the application of raw meat, or of bread soaked in milk, or of cooked onions, or a bathing with urine, etc. Such remedies are well adapted to increase the inflammation and produce complications. But even simple warm or cold compresses can have the same results.

Etiology.—Atmospheric influences are the most frequent cause of catarrh. Mere refrigeration is not to be reckoned among these; on the contrary, we have to do with influences which are still unknown to us. Possibly there is a special contagium which is transmitted through the atmosphere. This noxious influence makes itself felt more at certain seasons than at others, so that catarrh of the conjunctiva occurs with especial frequency at these times. For instance, this is the case in the spring, when so many people are attacked by catarrhs of the air-passages, by coryza, coughs, etc., and at the same time conjunctival catarrhs too are generally present in especially great number. At this time real epidemics of conjunctival catarrh occur, and under these circumstances it is the violent form (ophthalmia catarrhalis) which is prevalent. During such an epidemic, contagion, effected by a transmission of the secretion from one individual to another, probably plays a part in spreading the disease. This can occur, especially among children belonging to one family, by the indiscriminate use of towels, handkerchiefs, etc. Hence, even though conjunctival catarrh is in general but slightly contagious, we must still, in violent cases with much secretion, pay attention to this factor of contagion and strive to prevent it.

Therapy.—By suitable treatment the duration of a conjunctival catarrh can be considerably shortened and the development of a chronic catarrh prevented. The sovereign remedy in all the more intense cases of catarrh is the cauterization of the conjunctiva with nitrate of silver. This should come into contact with the conjunctiva only, and not with the cornea. In applying it, we evert the lids so that their conjunctival surface looks forward. The latter is then brushed over with a two-per-cent solution of silver nitrate and the excess of the solution is quickly washed off with lukewarm water or with a weak solution of salt. We now find the surface of the conjunctiva covered with a delicate bluish-white pellicle. This is the superficial slough which the solution has produced. The immediate result of this procedure, which is called touching the conjunctiva, is violent burning and marked irritation of the eye, an increase, in short, of all the inflammatory phenomena (stage of exacerbation). After this has lasted from a quarter to half an hour, according to the energy of our application, improvement gradually sets in. An examination of the eye at this time shows that the thin slough is separating and is being thrown off in the form of shreds. When this

is completed, we find the eye paler and the patient feels relieved and much less annoyed by his catarrh than was the case before the application of the brush (stage of remission). This improvement lasts from half a day to a day, according to the intensity of the catarrh. Then the troubles gradually increase again (recrudescence). This is a signal for repeating the application. As a rule, it is sufficient to make the application once a day, and best in the morning.

Beginners must particularly avoid making the application too energetically. If this has been done, the pain that follows the application lasts uncommonly long (an hour), and we find that even after a pretty long time, indeed even on the following day, the slough is still adherent in places. This is a proof that the sloughing process has penetrated too deeply. If, in spite of this, we should repeat the application, we would produce a progressively deeper and deeper sloughing of the tissue, and increase the inflammation instead of curing it. We must omit the application, therefore, as long as the slough is still adherent to any part of the conjunctiva.

Persons who are not able to visit the physician every day, can be allowed to instill the silver solution at home. Since by this method the remedy comes into contact with the cornea, we must choose a weaker solution ($\frac{1}{4}$ to $\frac{1}{2}$ per cent), which, of course, acts less energetically upon the conjunctiva. This way of employing the silver solution is, therefore, resorted to only as a makeshift in those cases in which treatment by means of the brush is inapplicable from extrinsic reasons. When the inflammatory phenomena have in the main disappeared, the silver solution is exchanged for collyria that act less energetically, those namely that are employed in chronic catarrh, to which subject reference must therefore be made for details (see § 9).

In addition to our medicinal treatment of conjunctival catarrh, we must not forget to enjoin upon the patient general rules for taking care of himself; telling him to keep the eye clean by washing it with lukewarm water, and to avoid smoke, dust, and bad air in general, and recommending him instead to pass his time in the open air. He must also refrain from straining the eyes much, especially in the evening by artificial light. In consideration, too, of the possibility of the spread of the disease by contagion, of which there is always a chance, the patient must take care not to use the same wash-basin, towels, etc., with other people.

Catarrhal conjunctivitis, also called conjunctivitis simplex, or by Stellwag Goldsmith's* catarrhalis, is, like catarrh of the air-passages, reckoned among the so-called refrigeration diseases (diseases produced by cold). This etiological factor can, of course, really form the basis of the catarrh in individual instances; but in the great majority of cases it is highly probable that there is

* From σύνδεσμος, a joining together.

an infection of the conjunctiva from without, the morbific matter being brought to the conjunctiva through the atmosphere. We would naturally be disposed to think of this virus as a micro-organism, and, as a matter of fact, a peculiar *Bacillus* has already been found in certain forms of acute catarrh (Weeks). Further investigations are required to clear up this matter. The dependence of conjunctival catarrh upon atmospheric influences is especially striking in that form which accompanies *hay-fever*. This affection, which is pretty frequent in certain countries, attacks individuals, who are predisposed to it, in the beginning of the summer, and makes itself apparent by fever and also by violent catarrhal inflammation of the conjunctiva and of the air-passages. While the infection which, in all probability, excites the catarrh of the conjunctiva comes to the latter from without in most cases, there are also instances in which a poisonous principle circulating in the blood causes the conjunctival inflammation. This is the case in the conjunctival catarrh which accompanies measles, and indeed often forms the first prominent symptom of it. This form will receive more extended consideration under the head of conjunctivitis exanthematica (see § 21).

Is catarrh contagious? Those cases that are associated with considerable secretion are probably contagious; and yet it must be admitted that attempts at artificial infection by transferring the secretion to a healthy conjunctiva are as a rule unsuccessful (Piringer), a fact of whose truth I have repeatedly assured myself.

From the clinical picture of acute conjunctival catarrh, as sketched above, we sometimes find variations forming what are described as special varieties of catarrh. Among these variations belongs the development of so-called *follicles*, which will be described more precisely in § 10. Another variety of catarrh is *vesicular catarrh*, in which the conjunctiva of the tarsus is covered with numerous minute elevations, looking as if fine sand had been scattered over a moist glass plate (Arlt). This appearance is caused by minute vesicular bodies formed by the separation and elevation of the upper layer of epithelium by means of fluid. A third variety of catarrh is that which is given the name of the *pustular* form. In this, flat elevations develop upon the conjunctiva bulbi, mostly near the margin of the cornea. These break down into pus on their surface, and in this way are formed grayish or yellowish ulcers with somewhat elevated base and of the size of a millet-seed or more. These have a great resemblance to the efflorescences occurring in conjunctivitis lymphatica (§ 18). The distinction between the pustular form of catarrh and conjunctivitis lymphatica consists in the fact that in the former the phenomena of catarrhal inflammation are present in the conjunctiva of the lids and of the region of transition, while in conjunctivitis lymphatica these divisions of the conjunctiva take little or no part in the inflammation. Many regard this form as a mixture of conjunctivitis catarrhalis and conjunctivitis lymphatica. And, as a matter of fact, we must take this view into consideration in our treatment to this extent that in the beginning of the disease the application of the silver solution ordinarily proves to be the best thing, but later, after the more violent inflammatory phenomena have run their course, calomel is of the most service.

The three varieties of catarrh just named are seen chiefly in children or in adolescents. They occur only as an exception in adults; in the latter, on the contrary, we encounter much more frequently the crescentic ulcers of the cornea that result from catarrh, which are but rarely observed in children. Several

crescentic ulcers may be present in the same eye at different parts of the circumference of the cornea; nay, more, by their confluence, an annular ulcer may be formed, completely encircling the cornea. In the latter case the annular opacity which is left has a great resemblance to the arcus senilis corneæ (see § 29). In cases where such an annular ulcer has penetrated deeply, the very detrimental result of a permanent ectasia of the cornea has been observed.. For the cornea, being very much thinned at its periphery as a result of the deep gutter running round it, gives way before the intra-ocular pressure and moves forward en masse. In this case the region of the cornea, inclosed by the annular ulcer, lies like a watch-glass on top of the marginal portions of the cornea.

Nitrate of silver, our most important remedy in catarrh, was first employed for inflammations of the conjunctiva by St. Yves in the last century, although it was in this century that it first found general acceptation. People had a natural dread of instilling so irritating a liquid as a nitrate-of-silver solution into a violently inflamed eye. In fact, in a perfectly sound eye this solution excites violent irritation of the conjunctiva, and it is quite possible to produce an artificial catarrh by too frequent application of it. How then does it happen that the nitrate-of-silver solution has such a beneficent action in conjunctival catarrh? The delicate bluish-white pellicle which covers the conjunctiva directly after the application is due to coagulation of the albumin of the cells in the upper layers of the epithelium by the nitrate of silver, so that these layers become opaque and die. The escharotic process acts like an irritant which increases the existing hyperæmia. This not only gives rise to an increase of the annoyance suffered (exacerbation), but also induces an exudation under the eschar, so that the latter is loosened and finally cast off. We have now only to imagine that by this exudation the vessels are unloaded and the hyperæmia consequently diminished. If micro-organisms should prove to be the cause of the catarrh, we might well bring forward a better explanation of the action of cauterization by saying that the micro-organisms contained in the upper layers of the epithelium have, together with the epithelial cells, been killed by the silver solution and have afterward been thrown off.

The silver solution finds an extensive application not only in catarrh, but also in other affections of the conjunctiva. In regard to it the following hints may be laid to heart: (*a*) Many physicians apply weaker or stronger solutions according to the effect which is to be obtained, but we can always succeed with a 2-per-cent solution, since we have it in our power to regulate the effect by making a light or a penetrating application with the brush. (*b*) The application should not be made at night, because the secretion, which is poured out more abundantly after the application, would be retained in the conjunctival sac by the closure of the lids in sleep. For the same reason the eye ought not to be bandaged immediately after the application. (*c*) Corneal ulcers do not constitute a contra-indication for making the application; on the contrary, they furnish a direct indication for it, in case they prove to be catarrhal ulcers. Only still greater care than would otherwise be necessary must be taken to prevent the caustic from coming into contact with the cornea. (*d*) If the treatment of the conjunctiva with the silver solution is kept up too long (for some months or a year), there is produced little by little a dirty-gray coloration of the conjunctiva, which never afterward disappears. This phenomenon, called argyrosis or argyria,* is caused by the fact that silver is deposited in the form of an

* From ἄργυρος, silver.

oxide or an albuminate in the tissues of the conjunctiva (in its elastic fibers), and can never afterward be removed. Argyrosis is produced even more readily by the constant instillation of the silver solution than by the application of the brush, since in the former case the excess of the solution is not removed by being washed off, but remains in the conjunctival sac. This coloration of the conjunctiva is also observed when the conjunctiva is constantly exposed to the action of silver dust, as occurs, for example, in many of those who work in silver.

In conjunctival catarrh, as well as in other affections of the conjunctiva, acetate of lead is also employed, partly as an astringent, partly as a mild caustic, and either under the form of a solution to be applied on compresses, by instillations, and by means of the brush, or under the form of an ointment. As long as the cornea is perfectly normal this remedy is without ill effect; but as soon as a loss of substance (ulcer) exists in the cornea, there is formed, if the use of the remedy is continued, an intensely white, very disfiguring opacity at the site of the ulcer. This lead incrustation, as it is called, is caused by the impregnation of the tissues of the cornea with the lead salt, and can be removed from the cornea with difficulty or not at all. For this reason it is best to employ the lead acetate as little as possible in the treatment of conjunctival diseases; the more so, because a sufficiency of other remedies is at our command, with which we can accomplish the same results without danger.

Bandaging the eye in catarrh, as in all diseases of the eye accompanied with profuse secretion, is to be avoided as much as possible, since by it the free exit of the secretion is obstructed.

(*b*) *Conjunctivitis Catarrhalis Chronica.*

9. Symptoms.—In chronic conjunctival catarrh the changes *objectively* perceptible are on the whole but slightly pronounced. A moderate degree of redness of the conjunctiva exists either over the tarsus alone or in the region of transition also. The conjunctiva is smooth and not swollen; it is only in old cases that hypertrophy with thickening and a velvety appearance of the conjunctiva is developed. The secretion is scanty and makes itself chiefly apparent by a gluing together of the lids in the morning. The whitish foam, often found at the angles of the lids, is produced by the lachrymal fluid being beaten up with the secretion of the Meibomian gland into a sort of foamy emulsion, as a result of the frequent blinking of the lids. The constant moistening of the skin at this spot often leads to the formation of excoriations. In many cases the secretion, instead of being increased, seems even to be diminished. In view of the fact that there is little or no increase in the secretion, several authors call many of these cases not by the name of chronic catarrh, but by that of hyperæmia of the conjunctiva.

In proportion to the insignificance of the objective symptoms, the greater is the attention that has to be paid to the complaints made by the patient—in fact, the *subjective* symptoms are generally so characteristic that the diagnosis of chronic conjunctival catarrh can easily be

made from them alone. The discomfort of the patient is usually greatest at night. The heaviness of the lids, scarcely noticeable in the daytime, becomes at night so marked that the patients have difficulty in keeping the eyes open; they have the feeling of being sleepy. A very annoying sensation of there being a foreign body—like a speck of dust—in the eye, is produced by the scanty secretion which remains in the conjunctival sac in the form of mucous filaments, and if these filaments lie upon the cornea the sight is interfered with, or rainbow-colors make their appearance about a candle-flame when looked at. Further unpleasant sensations of various kinds are described, as, for example, that the eyes burn and itch; that they are dazzled by the light; that, moreover, they are tired out quickly by working; that they blink often, etc. In the morning the eyes are somewhat stuck together, or a little yellowish dried secretion is found to have collected in the inner angle of the eye. In other cases there exists an annoying sensation of dryness, and the eyes can be opened only with difficulty, the patient, at the same time, having the feeling as if the lids were stuck to the eyeball because of the lack of moisture (*catarrhus siccus*). These troubles, so various in their nature, do not always by any means bear any definite relation to the objective condition. We see the conjunctiva quite intensely reddened in many people without their complaining in the least; while in others, who do nothing but annoy the physician with their expressions of discomfort, there are often scarcely any changes perceptible in the conjunctiva.

Course.—Chronic conjunctival catarrh is one of the most frequent of ocular diseases, chiefly affecting adults, and especially persons somewhat advanced in age. In old people it is almost the rule to find a light grade of chronic conjunctival catarrh, which is denominated senile catarrh. The duration of conjunctival catarrh is ordinarily a long one; many people suffer from it for a great part of their lives. The disease can lead to complications which in part produce irreparable changes. Among the most frequent complications is inflammation of the edges of the lids (*blepharitis*), resulting from the frequent moistening of the palpebral margins by the copiously secreted tears. As a further consequence of this wetting with the tears, the skin of the lower lid is attacked with eczema, or it becomes rigid and contracted, so that its free edge is no longer in perfect apposition with the eyeball. As a result of this the punctum lacrimale no longer dips into the lacus lacrimalis, so that the transportation of the tears into the lachrymal sac is impeded, the epiphora increased, and thus again a still further injurious reaction upon the character of the skin is produced. In this way there is formed a vicious circle, which leads to a constantly increasing depression of the lower lid (ectropion). This outcome is still further promoted by the circumstance that the patient keeps wiping away the overflowing tears, and thus makes stroking movements from above

downward, by which the lower lid is drawn down. If the contraction of the skin of the lids which have been moistened by the tears is more pronounced in the horizontal direction, blepharophimosis is developed. Lastly, small ulcerations of the cornea are among the frequent products of catarrh.

Etiology.—The causes which lie at the foundation of chronic catarrh are—1. A preceding acute catarrh, which, instead of healing completely, passes into the chronic stage. 2. General injurious influences of various kinds. Chief among these is bad air, vitiated by smoke, dust, heat, the presence of many people, etc. Workers in factories where dust prevails largely, waiters in inns that are filled with smoke, etc., very frequently suffer from chronic conjunctival catarrh. Going late to bed, being up at night, and the immoderate use of alcoholic beverages, are additional predisposing factors. Persons who already suffer from chronic conjunctival catarrh find that the latter is made considerably worse after the action of any injurious influence of this sort—for example, after an evening spent at the theatre or in a smoky place. So also the constant action of wind and bad weather frequently causes catarrh in farmers, coachmen, etc. For the same reason, too, eyes which are very prominent (goggle-eyes), or whose lids are contracted (lagophthalmus), are attacked by catarrh, because they are too little protected against the air. The effect which constant contact with the air exerts upon the conjunctiva is best shown in ectropion, where the conjunctiva tarsi, as it lies bare, becomes very much reddened and thickened, and velvety or even covered with large prominences. The conjunctiva bears continued exclusion from the air as little as it does constant contact with it, on which account chronic catarrh sets in when bandaging of the eye is kept up for a long time. 3. Excessive straining of the eyes, especially in hypermetropic or astigmatic persons can result in chronic catarrh. 4. Local injurious influences. Here belongs irritation of the conjunctiva by foreign bodies lodging in the conjunctival sac, among which, using the term foreign bodies in the wider sense of the word, are to be reckoned cilia which are turned in toward the eye. In most cases the local injurious influence consists of some other disease of the eye, which induces catarrh as a sequela, as, for example, blepharitis or infarction of the Meibomian glands. Accumulation of the tears, as a result of blennorrhœa of the tear-sac, or because the punctum lacrimale does not dip properly into the lacus lacrimalis, is a frequent cause of catarrh, so that we should never forget to look for an affection of the tear-passages in unilateral catarrh. We say unilateral, for catarrh produced by local causes is distinguished from that due to general injurious influences in this respect, that the former is very frequently unilateral, while in the latter, from the nature of the case, both eyes are generally affected.

Therapy.—It is clear that treatment must first of all pay regard to the causal factor by regulating in a suitable way, as far as is compatible with the patient's calling, the general conditions under which he lives, and by removing all local causes of catarrh that may be present, etc. For the treatment of the conjunctiva itself we first employ, as we do in acute catarrh, the nitrate of silver, which is used either for application by the brush (in 2-per-cent solution) or for instillation (in ¼ to ½ per cent solution). We make use of it in those cases only in which the catarrh is accompanied with rather abundant secretion and with relaxation of the conjunctiva—that is, in periods of acute exacerbation, such as frequently occur in the course of every chronic catarrh and, furthermore, use it when hypertrophy of the conjunctiva has already set in. Otherwise we succeed better with astringent collyria, which the patient can himself instill. The most usually employed of these are: The collyrium astringens luteum * or tinctura opii crocata, which are not ordinarily prescribed undiluted, but mixed with an equal quantity of water; lapis divinus † and sulphate of zinc, both in ¼ to 1 per cent solution; also alum, tannin, boric acid, and other astringents.

The order in which these collyria are here arranged about corresponds to their gradation in activity from the strongest to the mildest. They should be instilled once or twice a day, but not at night. So many of them are enumerated, because it is good to have a pretty large number to select from, since, if the catarrh is of long duration, a change will have to be made pretty often in the remedies. Every remedy, if too long applied, loses its activity, since the conjunctiva grows accustomed to it. For the sticking together of the lids, as well as for any excoriations that may be present, an ointment of white precipitate (½ to 1 per cent) may be rubbed upon the closed lids at night before going to bed.

(*c*) *Conjunctivitis Follicularis.*

10. Follicular catarrh is characterized by the presence of follicles. These are small round granules of about the size of a pin's head, which

---

* This collyrium, called also Horst's eye-water, is at present no longer official in most countries; yet it is of the greatest service, and in many cases can be replaced by no other. According to the new (seventh) edition of the Austrian Pharmacopœia, which went into effect on the 1st of January, 1890, it is to be prepared in the following way:

Take of ammonium chloride 50 centigrammes and zinc sulphate 125 centigrammes, dissolve in 200 grammes of distilled water, and add a solution of 40 centigrammes of camphor in 20 grammes of dilute alcohol, and 10 centigrammes of saffron. Digest for twenty-four hours with frequent agitation, and filter.

Romershausen's eye-water, which is also frequently employed in chronic ophthalmic catarrh, consists of a mixture of aqua fœniculi and tinctura fœniculi.

[† Or aluminated copper: a preparation made by fusing together 32 parts each of copper sulphate, potassium nitrate, and alum, and adding a mixture of 2 parts each of camphor and alum.—D.]

lie in the region of transition of the conjunctiva. They are of a pale, translucent aspect and puff up the conjunctiva in the form of small eminences. Either a few follicles only or many are present; in the latter case they are ordinarily arranged in rows like the pearls of a rosary. Microscopic examination shows that the follicles, as well as the so-called trachoma granules, consist of a circumscribed accumulation of adenoid tissue (Fig. 21, *T*).

Follicles are most frequently observed in youth, and can accompany both acute and chronic catarrh. Their significance consists in the fact that, when follicles are present, the malady is a protracted one. In chronic cases, the follicles remain stationary in the conjunctiva for a series of years. The follicles ultimately disappear without leaving a trace behind; the disease, therefore, in spite of its long duration, has a good prognosis, in that it is cured without leaving any sequelæ. In this particular, follicular catarrh is essentially distinguished from trachoma which, in its external appearance, bears a great resemblance to it, but which, however, always leads to permanent changes in the conjunctiva.

The etiology of follicular catarrh has not up to this time been established. By some contagion, by others miasm (vitiated air), has been assigned as a cause of the disease, without any certain proofs being brought for either one view or the other. The malady is found with especial frequency in schools, boarding establishments, etc., in which often many scholars are attacked by it at the same time. In many of these people the disease exists in an entirely latent way, as, in spite of there being a considerable number of follicles, the conjunctiva is not reddened and causes no sort of discomfort, so that the affection is first discovered by the physician's examination.

The treatment is the same as we are accustomed to employ against conjunctival catarrh in any case. By means of it the inflammatory symptoms on the part of the conjunctiva and along with them the annoyance suffered are relieved; but the follicles themselves generally remain obstinately stationary. In order to make them disappear, the best thing is to rub a lead ointment (acetate of lead 0·1–0·2 grammes, fatty matter 5 grammes) into the conjunctival sac. In doing this it must not be forgotten that the presence of corneal ulcers very strongly contra-indicates the use of a lead ointment. Cases in which the follicles exist without causing any annoyance are best left without any treatment. As in catarrh of all kinds, so especially in follicular catarrh, living in fresh, pure air is to be recommended.

II. Conjunctivitis Crouposa (*sive* Membranacea).

11. Symptoms and Course.—In this disease the inflammation begins with the symptoms of a violent catarrhal ophthalmia, which, however, within a few days rise to a height which they are not accustomed to at-

tain in catarrh. There are œdema of the lids, great redness and swelling of the conjunctiva, especially of the folds of transition, and lastly abundant muco-purulent secretion. As soon as the inflammation has reached this point, there appears, either upon the conjunctiva tarsi alone or upon it and the fold of transition, a whitish-gray membrane, the croupous membrane, which is the characteristic feature of the disease. This adheres pretty closely to the surface of the conjunctiva, but still can usually be removed from it with a forceps. When this is done we find the conjunctiva beneath to be greatly reddened and swollen and in some places bleeding, but we notice no great losses of substance in it. This proves that the membrane has lain upon the surface of the conjunctiva only, but, in contra-distinction to diphtheria of the conjunctiva, has not penetrated into the depth of the tissue. After from one to two weeks the membrane gradually disappears; the eye now once more presents the condition of a simple intense catarrh, which, after from one to two weeks more, generally disappears of itself. The disease, therefore, as a rule, terminates in complete recovery. The inflammation is but seldom so intense that the conjunctiva bulbi likewise appears covered with the croupous membrane; in such cases corneal ulcers are observed as a complication.

Croupous conjunctivitis appears in its essential character to be nothing but a particularly violent form of catarrh. In intense acute catarrhs we often see the profuse secretion clot on contact with the air, so that we can draw it out of the conjunctival sac in large cohering shreds. If the secretion is still richer in fibrin, and hence is still more disposed to coagulate, it clots at the very moment it reaches the surface of the mucous membrane; in this way the croupous membrane is produced. If this is removed, new secretion appears upon the surface, so that we find that the membrane is soon replaced. Microscopical examination of the croupous membrane, in fact, proves that it consists of a fibrous meshwork of clotted fibrin, in which pus-corpuscles and a few epithelial cells from the conjunctiva are imbedded.

Croupous conjunctivitis is a disease of childhood. Its causes are probably the same as those of acute catarrh of the conjunctiva. It has no etiological connection with croup of the larynx, with which it has nothing in common but its external phenomena, that is, the formation of superficial exudative membranes.

Treatment.—As long as the conjunctiva is covered by a membrane we must refrain from any very energetic kind of treatment. Brushing the conjunctiva with a silver solution would only promote still more the formation of the membranes, and the removal of the latter also subserves no purpose, since they form again. In this stage, therefore, we confine ourselves to keeping the eye clean by washing it with an antiseptic liquid (for instance, a sublimate solution of 1 to 5,000). When, after complete separation of the membranes, the picture of a

simple intense catarrh is presented to us, we treat this latter according to the rules already given.

There are some cases of croupous conjunctivitis in which the membranes persist for several months and are constantly reformed (Hulme, Arlt). Moreover, membranes similar to those of croupous conjunctivitis occur occasionally in other affections of the conjunctiva. For instance, superficial exudative membranes are produced as a result of too strong or too frequent application of nitrate-of-silver solution to the conjunctiva. Membranes of this sort, also, are sometimes found in acute blennorrhœa (especially in blennorrhœa neonatorum) and in pemphigus of the conjunctiva; and in the rarely occurring herpes iris conjunctivæ these membranes are a characteristic symptom.

III. Conjunctivitis Blennorrhoica Acuta.

12. *Acute blennorrhœa* * is an acute inflammation of the conjunctiva, which originates in contagion from gonorrhœal virus, and whose copious purulent secretion is likewise contagious in its action. The carriers of the contagium are micro-organisms, namely, the gonococci discovered by Neisser. They bear this name because they also occur in the secretion of gonorrhœa. The gonococci are found both in the pus secreted by the conjunctiva and also in the most superficial layers of the conjunctiva itself. They are mostly arranged in pairs, as diplococci, and as a rule lie together in heaps. Fig. 18 shows a specimen taken from the secretion of an acute blennorrhœa. In it are seen the heaps of gonococci partly free (*a*), partly upon and within the cells, which are either pus-cells (*b*) or cast-off epithelial cells (*c*).

Fig. 18.—Secretion of Acute Blennorrhœa with Gonococci.

Acute blennorrhœa occurs both in adults and in new-born infants —blennorrhœa adultorum and blennorrhœa neonatorum.

(*a*) *Blennorrhœa Acuta Adultorum* (*Conjunctivitis Gonorrhoica*).

Symptoms and Course.—When infection has taken place, the disease breaks out after a certain period of incubation, the duration of which varies according to the intensity of the contagious action from a few hours up to three days. The lids grow red, become hot, and are swollen with œdema, generally to such an extent that the patient can no longer open them, and even the physician often has trouble in separating them far enough from each other to bring the cornea

* From βλέννα, mucus, and ῥέω, I flow.

into view. The conjunctiva of the lids and of the region of transition is intensely reddened and greatly swollen. The swelling, in distinction from that of catarrh, is produced by an abundant infiltration of the conjunctiva with exudation, so that the conjunctiva is tense, and, instead of being smooth, is of a granular, uneven surface. The conjunctiva of the eyeball shows a like swelling which stops short at the corneal margin, so that a raised wall is thus formed about the more deeply placed cornea (chemosis). The secretion produced by the conjunctiva is like meat-juice—that is, it is a serum which is colored red by admixture with blood, and in which float some flakes of pus. The eye is uncommonly sensitive to contact, the lymphatic gland in front of the ear is swollen, the patient has slight fever.

Ordinarily it takes from two to three days for the disease to mount from its initial point to the pitch just described, and at this pitch it is maintained for two or three days more. This period is designated as the first stage, or *stage of infiltration*. Succeeding this as a second stage is that of *pyorrhœa*. The swelling of the lids gradually diminishes, a fact which we recognize principally by means of the return of the small wrinkles of the skin of the lids, and the tense infiltration of the conjunctiva slowly retrogrades. Simultaneously with this there begins a very profuse secretion of pus, which trickles out continually from the palpebral fissure; hence the name pyorrhœa, or flow of pus. In the further course of the disease the swelling of the conjunctiva keeps on constantly diminishing, the eye, in many cases, returning to the normal state within the next four or six weeks. In most cases, however, a condition of chronic inflammation of the conjunctiva remains, which is designated as the third stage of the disease, the stage of *chronic blennorrhœa*. In this period the lids are no longer swollen. The conjunctiva is reddened and thickened, especially upon the tarsus, where its surface looks uneven, granular, or velvety. The fold of transition forms an ungainly swelling; the conjunctiva of the eyeball, which shows hyperæmia only, is the least changed.

The description here given corresponds to cases of most frequent occurrence, which are those of medium intensity. In addition, both light and also very severe cases of the disease come under observation which exhibit rather different features. In the light cases, which we are accustomed to call *subacute blennorrhœa*, all the inflammatory changes are less, and the changes are limited chiefly to the conjunctiva of the lids. Such cases are frequently not to be distinguished with certainty by their external aspect from violent catarrh. The diagnosis can be rendered certain by the microscopic examination of the secretion, since by it the presence or absence of gonococci is demonstrated.

In the severest cases, the infiltration of the conjunctiva is so great that the latter in places appears no longer red, but grayish-yellow, because, as in diphtheritic disease of the conjunctiva, the vessels are com-

pressed by the bulky exudation, and the conjunctiva is thus rendered anæmic. The conjunctiva forms about the cornea a tense grayish-red wall. Quite often the surface of the conjunctiva is found to be covered with a clotted exudate like a croupous membrane.

The most dreaded complication of acute blennorrhœa is the *involvement of the cornea*, by which, in many cases, incurable blindness is produced. At first the cornea becomes dull upon its surface and covered with a slight diffused opacity. Then circumscribed infiltrations of grayish color make their appearance, which soon become yellow and break down into ulcers. These infiltrations may be situated at the margin of the cornea, and give rise to speedy perforation of the latter. This is a comparatively favorable result, as, after the perforation has taken place, the purulent infiltration of the cornea is not rarely brought to a standstill, and so a portion of the cornea is preserved. But it can also happen that the marginal infiltrations become rapidly confluent, and unite into a yellow ring surrounding the entire cornea (a so-called annular abscess). In that event the cornea is lost, for this ring soon spreads over the entire cornea and destroys it. In other cases the purulent disintegration occurs first in the middle layers of the cornea, after the manner of the typical abscess of the cornea (see § 37). A rare and peculiar form of involvement of the cornea occurs, in which the latter melts away, as it were, like a piece of ice in the sun, until it has disappeared altogether, with the exception of a narrow portion of its rim. When, in one way or another, the cornea has gone either entirely or in part to destruction, cicatrices are formed with incarceration of the iris, or panophthalmitis itself may be produced. Since these sequelæ are observed after every destruction of the cornea, even when due to other causes, they will find detailed description under the diseases of the cornea.

Involvement of the cornea is so much the more to be expected, the severer the blennorrhœa, and, in particular, the more pronounced the participation of the conjunctiva bulbi in the inflammation. In the severest cases with tense chemosis the cornea is always affected, and is, as a general thing, irretrievably destroyed. In the cases of moderate severity, when the chemotic swelling of the conjunctiva is less pronounced and especially is less hard, it is usually possible to preserve the cornea, either entirely or in great part, inasmuch as the ulcers that develop, even if they are attended with perforation, are of but small size. In the lightest cases, where the process is limited to the palpebral conjunctiva, there is, on the whole, little danger to the cornea.

The severer the course of the inflammation, the earlier the involvement of the cornea sets in; in violent cases, the cornea is already clouded by the second or third day. Sometimes corneal ulcers are not developed until late in the disease, when the blennorrhœa is already well on the retrograde path. These late affections of the

cornea are not very dangerous, and it is generally possible to check them readily.

The *prognosis* of the disease results from what has been said, it being essentially founded upon the condition of the cornea. This is dependent upon the intensity of the inflammation of the conjunctiva bulbi, in accordance with which, therefore, the prognosis must be made.

Etiology.—Acute blennorrhœa is produced simply and solely by infection. The poison can be introduced into the eye from the genitals directly, generally by an individual (whether man or woman) affected with gonorrhœa, touching the eyes with unclean fingers after these have been in contact with the genitals. The infection, however, can also come from an eye affected with blennorrhœa. If, for instance, one eye is already diseased and is affected with profuse suppuration, the other eye also can be infected by a transfer of the secretion to it. An individual with an eye diseased with blennorrhœa can infect the persons who are nursing him or any others who may share his room, so that we sometimes see an entire family stricken with this baneful malady.

Therapy.—By proper *prophylaxis* infection by acute blennorrhœa can be prevented, a matter to be so much the more considered because, when the disease has once broken out, an unfortunate result can not always be averted. It is the physician's duty to call the attention of every man with gonorrhœa, and also of every woman with a vaginal discharge, to the danger of infecting the eyes, and to urge upon them strenuously the requisite cleanliness. If the eye is already attacked with acute blennorrhœa, care must be taken to keep the other eye from being infected by it and also to keep the disease from being transferred to persons in the vicinity. The protection of the second eye which has not as yet been involved in the disease is best effected by a bandage which is applied in the following manner: The palpebral fissure is first closed by means of some narrow strips of sticking-plaster applied in a vertical direction. Then the hollow about the eye is filled up with cotton and the whole is covered by a flap of linen provided with adhesive plaster strips, which is carefully attached all round the margins of the orbit. In order to secure it better, the edges of the flap and the adjacent skin may further be coated with collodion. To prevent the spread of the disease to those in the neighborhood of the patient, the greatest cleanliness must be inculcated both upon him and upon the persons attending to him; they must always cleanse the hands after touching the affected eye, and must remove, or, best of all, burn, all materials that have been used for cleansing the eye (pieces of linen, cotton, etc.).

The *treatment* of the disease itself consists principally in a careful and frequently repeated cleansing of the eye from its profuse secretion. We may employ for this purpose weak antiseptic solutions (solution of

corrosive sublimate, 1–4,000, or of potassium permanganate). If the great swelling of the lids does not permit the palpebral fissure to be properly opened, and thus makes cleansing impossible, the palpebral fissure must be fully widened by a section made with the scissors at the external angle of the lids (canthoplasty; see § 169). This section has the further advantage of diminishing the pressure which the much-swollen lids exert upon the eyeball.

In the first stage of the disease we combat the inflammation by iced compresses, and also by the application of leeches (six to ten in number) to the temple. In the second stage brushing the conjunctiva with nitrate of silver is the best means for making the swelling of the conjunctiva and the profuse secretion rapidly disappear. The application of the brush must not, however, be begun until the tense swelling of the conjunctiva has given place to a soft, succulent condition; there should no longer be any membranous deposit, any grayish infiltrated spots upon the conjunctiva. The application should be made with a two-per-cent solution, but quite freely, and must be repeated twice a day as long as the profuse secretion is still present. The presence of ulcers of the cornea furnishes no contra-indication to the use of nitrate of silver.

As soon as, in the third stage, the inflammatory symptoms and the secretion also have nearly disappeared and the thickening of the conjunctiva is the only thing that still remains to be removed, we exchange the silver solution for copper sulphate. This is applied by whittling a crystal of the substance down to a smooth, rounded extremity (copper pencil or blue-stone) and stroking with it once or more the conjunctiva of the everted lids. In this way we cauterize more energetically than with the silver solution, and thus more quickly accomplish our end; but this treatment is permissible only if the cornea is either quite sound or has ulcers already in process of cicatrization, and not if there are fresh ulcerations of the cornea, which are still coated with pus.

The treatment of complications involving the cornea is conducted according to the rules (§§ 36, 38) for purulent keratitis (ulcer and abscess of the cornea). If very severe, all treatment proves powerless to preserve the cornea, so that we must confine ourselves to attempting to avoid the more remote evil consequences of destruction of the cornea, like panophthalmitis or the formation of staphyloma, and to obtain a flat cicatrix.

It is now established beyond doubt that acute blennorrhœa is developed by the direct transfer of virulent pus to the conjunctiva. The earlier view, which explained the connection between gonorrhœa and ophthalmia by looking upon the latter as a sort of *metastasis* of gonorrhœa, has now no longer any adherents. Nevertheless, cases have been described recently (by Riccord, Roosbrock, Haltenhoff, Rückert, Armaignac, and others), in which a conjunctival inflammation of a lighter kind is connected with a gonorrhœa in the way of

metastasis, just as arthritis and iritis sometimes complicate a gonorrhœa. This metastatic mode of origin is to be understood by supposing that the gonorrhœal poison has got into the circulation, and is exciting inflammation in remote organs which have a predisposition for this poison. A conjunctivitis originating in this way ought to show the characters, not of a blennorrhœa, but of a violent catarrhal conjunctivitis. In any case, we shall have to be uncommonly careful in making the diagnosis of such a metastatic gonorrhœal conjunctivitis, since light cases of conjunctivitis can also develop from direct infection with gonorrhœal secretion, in case the gonorrhœal poison has been weakened by various circumstances. (See infra, the investigations of Piringer.) As a gonorrhœa of the urethra can by metastasis excite a conjunctivitis, so also conversely cases have been observed in which a gonorrhœal arthritis has arisen by way of metastasis from a blennorrhœa of the conjunctiva (Deutschmann).

The secretion containing gonococci is usually brought into the eye by means of dirty fingers. Sometimes, however, a *direct transfer* from the diseased mucous membrane to the sound one is observed; for example, when a drop of secretion spurts into the eye of the physician or the attendent while cleansing genitals that are affected with gonorrhœa, or even when cleansing the eye of a patient affected with blennorrhœa. For this reason the old method of cleansing blennorrhœal eyes by means of a glass syringe has been given up in most ophthalmic clinics, as it endangers both the eye of the patient and the eyes of the corps of attendants. Furthermore, in the treatment of such patients, physicians and attendants ought always to use protective glasses (large, colorless coquille-glasses). If, in spite of this, any secretion does spurt into the eye, the latter must immediately be very thoroughly washed out; then a couple of drops of two-per-cent nitrate-of-silver solution instilled, and subsequently for some hours cold compresses placed upon the eye.

I have seen a case in which a patient, because of a mild conjunctival catarrh, washed his eyes in his own urine (a popular remedy among the laity in many places); as he had gonorrhœa, he acquired an acute blennorrhœa. Acute blennorrhœa, moreover, has been seen to originate from the use of another household remedy—that is, from the practice of laying upon the eye a piece of placenta, which in this case came from a woman affected with gonorrhœa.

If one eye is already infected, the transfer to the other is often brought about by the secretion of the diseased eye flowing over the bridge of the nose into the sound eye during sleep. Furthermore, the secretion can be transferred from the eye affected with blennorrhœa to the sound one by the finger, the water used for washing, the sponge, the handkerchief, etc. For these reasons the sound eye should be bandaged. If there is ground for suspecting that infection has already taken place, we can endeavor to prevent the outbreak of the disease by instilling a two-per-cent solution of nitrate of silver before applying the bandage. In order that the patient may see with the bandaged eye, we can insert a watch-glass in an aperture which we make in the middle of the bandage.

The transfer of blennorrhœa from an eye affected with the latter to the eyes of other people is likewise not rare. It occurs most frequently in children who are affected with blennorrhœa neonatorum, and thus infect their mothers, nurses, etc. In the Vienna Foundling Asylum, during the years 1812 and 1813, there were, for every hundred infants affected with blennorrhœa, more than fifteen nurses so affected, who had acquired their eye-disease from the infants. I have seen a whole family infected with blennorrhœa by a child hav-

ing blennorrhœa neonatorum, and thus plunged in the greatest misery. Great caution, therefore, and especially precise directions to the people, are here imperatively required.

We sometimes also observe *acute blennorrhœa in small girls* of the age of two to ten years, who at the same time are troubled with a vaginal discharge (Arlt). Here are we still dealing with contagion from a virulent vaginal catarrh; or is the vaginal discharge of these girls a benign catarrh caused by scrofula, anæmia, and the like? In some of these cases it has been possible to prove the origin of the vaginal blennorrhœa. The children have acquired the latter from their mothers or from other women about them, who were suffering from virulent vaginal catarrh, and had transmitted the latter by soiled clothes, sponges, baths, etc., to the children (Hirschberg). In other cases, the children had been raped by individuals affected with gonorrhœa. Here, therefore, we are dealing with a pure vaginal gonorrhœa in the children, and, accordingly, it is possible in such cases, too, to demonstrate the presence of the gonococcus both in the secretion of the vagina and in the conjunctiva as well (Widmark). But it would be going much too far to regard the vaginal discharge in little girls as pure gonorrhœa in all cases in which infection of the conjunctiva results from the discharge. It seems to me probable that even a non-virulent, simple catarrhal secretion of the vagina is in position to excite an inflammation of the conjunctiva, which in this instance runs a less severe course, and exhibits the character of a mild (subacute) blennorrhœa. The distinction from a pure blennorrhœa could be made in this case only by the microscopical examination of the secretion for gonococci.

The interesting researches of Piringer have instructed us in regard to the *relation between the infective material and the ophthalmia produced by it*, as he has made a great number of intentional transfers of virus (generally in the eyes of people already blind, who were paid for the experiment). He found that the period of incubation is of shorter duration in proportion, as the blennorrhœa which the inoculated material produces is more violent. The infective power of the secretion is weakened by various influences, as by dilution with water—by dilution to the one-hundredth part any secretion can be rendered inert—or by drying. Secretion that has been dried upon a piece of linen loses its activity after thirty-six hours. Preserved like vaccine, it remains infective for sixty hours. In proportion as the virulence of the infecting secretion is weakened, the period of incubation increases in length and the inflammation excited grows milder. The differences that we observe in the grades of blennorrhœa can therefore be referred to the fact that the source of infection supplies secretion of different degrees of virulence, and this virulence is, moreover, still further modified by the immediate circumstances attending the process of infection. That the lymphatic gland in front of the ear should swell up in acute blennorrhœa is a fact that accords with the virulent character of the latter; sometimes even suppuration of this gland has been observed (bubo præauricularis).

The *purulent inflammation of the cornea*, which so often complicates the blennorrhœa, is to be referred to infection of the cornea by the secretion which constantly bathes the latter. Since the secretion collects most of all in the gutter lying at the rim of the cornea, between the latter and the steep slope of the chemotic conjunctiva, the purulent infiltration most frequently begins here, too. The dense infiltration existing in this chemotic wall of conjunctiva is to be regarded as a second factor in the production of corneal trouble. This leads

to obstruction of the circulation in the marginal loops of the cornea, and thus interferes with the nutrition of the latter. Hence, the more pronounced and the more tense the chemosis, the more confidently is an affection of the cornea to be anticipated. It is in harmony with this fact that, in cases where the chemosis is unequally great, we often see the involvement of the cornea take place first at that portion of the corneal rim where the chemosis is the greatest. Since infection of the cornea is certainly very greatly favored by the existence of gaps in the epithelium of the latter, we must avoid injuring the epithelium of the eye by carelessness in cleansing.

If acute blennorrhœa happens to affect an eye which is covered with pannus the latter will afford the cornea a secure protection against suppuration. Nay, more, it is often apparent, after the violence of the inflammation has passed, that the pannus has cleared up considerably, so that in cases of old pannus inoculation with acute blennorrhœa has been designedly performed.

The fact that acute blennorrhœa is produced by micro-organisms would lead us to expect that disinfectant substances would be the best remedies in the *treatment* of it. Nevertheless, it has been shown that nitrate of silver far surpasses the disinfectants proper for this purpose. Only, we must avoid beginning too early with the application. In the first stage of the disease, some make use of scarifications of the chemotic conjunctiva in severe cases, and also of liberal doses of mercury both internally and in the form of inunctions of blue ointment ; from neither of these two remedies have I seen any special result. In using iced applications we must take care not to depress too greatly by the excessive employment of cold the already embarrassed circulation of the conjunctiva.

(*b*) *Blennorrhœa Neonatorum.*

13. This disease is identical with the blennorrhœa of adults. Moreover, it owes its origin to infection by secretion from genitals which are affected with virulent catarrh. The infection occurs as a rule during parturition. In the passage of the child's head through the vagina, the eyelids are covered with the secretion of the latter, and this either penetrates immediately into the conjunctival sac through the palpebral fissure, or does so as soon as the child opens his eyes for the first time. Under these circumstances the disease breaks out as a rule on the second or third (rarely on the fourth or fifth) day after birth. In those cases in which the disease makes its appearance still later than this, the infection can not any longer be referred to the act of birth. It has then been brought about through subsequent infection by the vaginal secretion of the mother (as is readily possible, particularly if the child sleeps in bed with the mother), or the child has been infected by another child, as, for instance, not rarely happens in lying-in establishments and foundling asylums.

The *symptoms* of the disease are the same as in the blennorrhœa of adults, except that they are in general less severe. For even when there are great swelling of the lids and very profuse purulent discharge, the part which the bulbar conjunctiva takes in the process is relatively small, and we rarely find great chemosis. Hence also the danger of sup-

puration of the cornea is not so great. It does indeed occur, and that often enough too, but only in those cases which are treated badly or not at all. If a case comes under treatment in season—that is, while the cornea is still intact—the latter can almost to a certainty be maintained in a healthy state. Supposing this condition to be fulfilled, therefore, the prognosis can be stated as favorable.

The treatment in the first stage consists in diligent cleansing of the eye; when suppuration commences we begin with the application of a two-per-cent nitrate-of-silver solution to the conjunctiva. In cases with profuse secretion this must be done twice a day. The application should be continued until the cure is complete, as otherwise it is easy for the process to recur to a moderate degree. A condition of chronic inflammation (chronic blennorrhœa), remaining as a sequela, is much more rare in infants than in adults..

In blennorrhœa of the new-born, *prophylaxis* plays an even greater rôle than in the blennorrhœa of adults. There is perhaps no other disease in which the rigorous carrying out of prophylactic treatment would afford more gratifying results than in blennorrhœa of the new-born, which might in this way be made to disappear almost entirely. The principle which lies at the foundation of prophylaxis is the avoidance of infection during parturition. To this end the vagina should be cleansed as well as possible by antiseptic injections directly before parturition, a procedure which is also advisable on other grounds. As soon as the child is born, the lids while still closed are to be wiped off carefully with a clean piece of cloth. While the first bath is being given the child's eyes should not be wet with the water of the bath. As soon as the child has been wrapped up after the bath, the eyes should again be cleansed with clean water and with a piece of cloth or cotton designed for this purpose expressly, and then a drop of two-per-cent silver solution dropped into each eye. By this procedure, which was devised by Credé, blennorrhœa of the new-born can be avoided almost to a certainty. For protection against infection occurring after birth, whether from the mother or from other children, the ordinary precautionary rules hold good.

Blennorrhœa of the new-born belongs among the diseases of frequent occurrence. The majority of pregnant women have catarrh of the vagina with a mucous or purulent discharge. In the greater portion of these cases we have to do with a benign vaginal catarrh, in a smaller portion with a virulent catarrh (gonorrhœa). In individual cases the distinction between benign and virulent is difficult or impossible, for which reason prephylactic treatment ought to be carried out in all cases. The frequency of ophthalmia among the children, before the introduction of prophylactic treatment, varied from one to twenty per cent in different lying-in establishments. Among these are comprised light and severe cases. In the former, ordinarily no gonococci are found in the secretion ; these cases are hence probably to be regarded as not blennorrhœa

but as simple catarrh. Conjecturally these are the cases in which the mother had a benign catarrh of the vagina. Of the severe cases, those of blennorrhœa proper, a certain number go blind on account of the failure to treat them in season, so that a very considerable number of cases of blindness are to be laid to the account of this disease. In the asylums for the blind of Germany and Austria, those who are rendered blind by blennorrhœa neonatorum form more than a third part of the whole number; on the whole, those who are rendered blind in this way certainly constitute more than the tenth part of all living blind persons. The number of the blind in Europe is reckoned at more than three hundred thousand. If blennorrhœa neonatorum were made to disappear from the causes of blindness by universally carrying out a prophylactic treatment, there would be in Europe alone at least thirty thousand fewer blind people.

That prophylaxis, as introduced into practice by Credé, is actually efficient, is proved by the following data: Credé formerly had in the Leipsic Lying-in Asylum on an average in the whole number of new-born 10·8 per cent of cases of blennorrhœa neonatorum; after the introduction of his prophylactic method the number sank to 0·1 to 0·2 per cent. Others have similar favorable results to record. Unfortunately, up to the present time, the prophylaxis of blennorrhœa has not been generally introduced by law; it has merely been brought into use in lying-in establishments and also in the private practice of many physicians, while the enormous majority of children come into the world without it.

Disinfectant remedies like boric acid, salicylic acid, carbolic acid, corrosive sublimate, etc., have been employed for purposes of prophylaxis; but a two-per-cent solution of nitrate of silver has proved to be the most efficient of all. Its action is to be explained by the fact that it cauterizes the uppermost layers of the epithelium. By reason of this, those gonococci, which have already penetrated into these layers, and not merely those which occur on the surface of the conjunctiva, are destroyed.

Credé's prophylactic treatment acts as a protection against infection during parturition only. Infection can, however, take place even earlier; children have been known to come into the world with a blennorrhœa already fully developed—in fact, with the cornea already destroyed. Furthermore, against subsequent infection by the vaginal secretion of the mother, or by other children, other measures will have to be adopted, among which great cleanliness is to be assigned the first place. In foundling asylums, infants infected with blennorrhœa should be isolated from the rest, as otherwise infection will frequently take place. In the Vienna Foundling Asylum, during the years 1854–'66, no less than fourteen hundred and thirteen children were first attacked by blennorrhœa while in the asylum, and hence caught the infection in the latter.

IV. Conjunctivitis Trachomatosa.

14. Trachoma, like acute blennorrhœa, is an inflammation of the conjunctiva, which originates by infection, and produces an infectious, purulent secretion. It is distinguished from acute blennorrhœa principally by its chronic course, in which is developed a hypertrophy of the conjunctiva, that forms the most characteristic symptom of trachoma. From the roughness of the conjunctiva, caused by this hypertrophy, the disease has in fact received its name.*

* Trachoma, from τραχύς, rough.

Symptoms.—The patients complain of sensitiveness to light, of lachrymation, and of sticking together of the lids; pain and visual disturbances are also often present. The examination of the eye shows that the latter is less widely opened, partly because of photophobia, partly because the heavy upper lid hangs lower down. After everting the lids, we see the conjunctiva of the tarsus and also that of the fold of transition reddened and thickened; its surface at the same time has become uneven to a varying degree. These changes are to be referred to a hypertrophy of the mucous membrane, which occurs under two different forms.

The *first form* consists in the development of the so-called papillæ. These are elevations newly formed on the surface of the conjunctiva which consequently appears velvety, or, if the papillæ are large, ap-



FIG. 19.—SCHEMATIC SECTION THROUGH THE LIDS AND EYEBALL (*A*, IN RECENT, *B*, IN OLD TRACHOMA).

A shows the way in which the two forms of hypertrophy of the conjunctiva are distributed among the separate divisions of the latter; *B*, the stage of sequelæ of trachoma; s, s_1, eyebrows; o, o_1, furrow between the brow and the lid (sulcus orbito-palpebraris); d, d_1, covering fold; c, cilia in their proper position; c_1, cilia turned toward the cornea; r, free border of the lid, with the borders of the upper and lower lids running parallel and the posterior margins of the lids acute; r_1, free border of the lid, looking backward, and with its posterior margin rounded; t, tarsus thickened by infiltration and covered with the velvety conjunctiva tarsi; t_1, tarsus thinned (atrophic), bent at an angle near its free extremity, and covered with smooth epithelium; f, fornix with numerous trachoma granulations, T, in the folds of the conjunctiva; f_1, fornix smooth, without folds (symblepharon posterius); p, thick pannus covering the upper half of the cornea; p_1, a pannus that has undergone contraction, extending over the whole cornea.

pears studded with coarse granules, with small nodules, or even with raspberry-like projections. There is now no thickening of the conjunctiva, the subjacent Meibomian glands being visible through the latter. This kind of hypertrophy, which is called the *papillary form*, is found exclusively in the tarsal conjunctiva (Fig. 19 *A*). It is always

most clearly pronounced on the upper lid, which, therefore, must be everted in making the diagnosis of the trachoma.

The *second form* of hypertrophy is characterized by the presence of the trachoma granules. These are gray or yellow, translucent, roundish bodies, which push up the most superficial layers of the conjunctiva in the form of a hemisphere, and are visible through the conjunctiva. On account of their translucent, seemingly gelatinous character, they have been likened to the eggs of frog-spawn or to grains of boiled sago. They are found principally in the folds of transition (*f*, Fig. 19 *A*), in which they are imbedded in such numbers that, when the lower lid is drawn down, the fold projects as a thick, rigid swelling, at the summit of which we sometimes see the granules arranged in rows like a string of pearls. In the conjunctiva tarsi the trachoma granules are less readily visible. They are smaller in this situation, and can not push the conjunctiva up because the latter is very closely adherent to the tarsus. Here, therefore, they generally appear as small, bright-yellowish points, which are situated deeply in the mucous membrane; quite often, though, they are hidden from sight altogether by the development of the papillæ. More rarely trachoma granules are found in the semilunar fold as well as in other parts of the conjunctiva of the eyeball. This variety of proliferation of the conjunctiva is called the *granular* form.

The two forms of proliferation of the conjunctiva sometimes occur separately. In the great majority of cases, however, both are found at the same time in the same eye, and so distributed that in the conjunctiva of the lids the most prominent feature is the proliferation of papillæ, in the fold of transition it is the formation of trachoma granules (Fig. 19 *A*). The conjunctiva of the eyeball is, in light cases, unaltered, but when the irritation is more intense shows a coarsely reticulate injection. The conjunctiva discharges a purulent secretion, the quantity of which is more abundant in the fresh cases and those attended with marked symptoms of irritation. In older cases, on the contrary, and in those which run a more sluggish course, it is very scanty.

The disturbance of sight, of which many patients complain, is founded upon a complication affecting the cornea, and appearing under two different forms, pannus and ulceration, which very frequently occur together.

Pannus trachomatosus* consists in the deposition upon the surface of the cornea of a newly formed, brawny, vascular tissue, which pushes its way from the edge toward the center of the cornea. At the spot where the pannus is located, the surface of the cornea is uneven and studded with fine projections, and there is a gray, translucent, superficially situated cloudy mass, which is traversed by numerous vessels.

* *Pannus*, a cloth.

The latter spring from the vessels of the conjunctiva, which pass over the limbus and out upon the cornea, and, after arriving within the pannus, branch in an arborescent fashion. The pannus ordinarily begins its development at the upper margin of the cornea, and cover first the upper half of the latter (*p*, Fig. 19 *A*). Quite often it terminates below in a sharp, straight, horizontal border. Afterward pannus develops at other portions of the corneal margin, until at length the entire cornea is covered by it. When pannus is pretty fully developed, the iris likewise participates in the inflammation (iritis). Disturbance of vision sets in as soon as the pannus has advanced into the pupillary area of the cornea—that is, in that region of the latter which lies directly opposite the pupil. If this region is entirely covered by pannus, vision is reduced until it is limited to the recognition of large objects, or even to the mere ability to distinguish between light and darkness (quantitative vision).

The *ulcers of the cornea* either develop at a spot that is otherwise normal, or they occur in connection with pannus. In the latter case they are found principally at the free border of the pannus, more rarely within the latter. Since their character agrees with that of ulcers of the cornea generally, a more detailed account of them will be given under the latter head (§§ 34 et seq).

Course.—This is of the following character: The hypertrophy of the conjunctiva gradually increases, growing steadily greater, until it has reached a certain height which is not the same in all cases. Then it disappears again, step by step, while a cicatricial state of the conjunctiva with contraction takes its place. In this way the trachoma is cured in the sense that the specific morbid process has come to an end. Nevertheless, the conjunctiva has not become normal again by any means; on the contrary, it bears upon it lasting marks of the disease that has past, namely, the signs of a cicatricial contraction which, in many instances entails other, additional consequences, such as we will group together under the phrase "the state of sequelæ of trachoma." The more considerable the degree which the hypertrophy of the conjunctiva attains, the greater and more striking is the contraction of the latter, and the longer, too, is the duration of the disease, which in most cases is counted by years. Accordingly, there is a direct proportion between the severity of the disease and its duration, as well as the severity of its later sequelæ. The object of the treatment, therefore, must consist in checking the hypertrophy of the conjunctiva while it is developing, as thus both the duration of the disease is shortened and its evil consequences also are reduced to a smaller amount.

In the *conjunctiva tarsi*, the beginning of the *formation of cicatrices* is betokened by a few narrow, whitish striæ (fine cicatricial bands), which we see emerging in the midst of the reddened and thickened conjunctiva. These striæ gradually become more numerous and unite

to form a delicate network, the meshes of which are occupied by red islands—that is, by those portions of the conjunctiva which are still hyperæmic and hypertrophied. Little by little the cicatricial lines grow steadily broader and the islands that they inclose steadily narrower, until at length that condition is produced in which the conjunctiva of the tarsus has become perfectly pale, thin, and smooth. The cicatricial condition of the conjunctiva corresponds in extent and intensity to the amount of hypertrophy that has preceded it. In those cases in which the hypertrophy of the conjunctiva has attained a considerable height in certain spots only, it is also only at these spots that deep cicatrices remain after the trachoma has run its course, while those parts of the conjunctiva which were simply infiltrated, or were hypertrophic to only a very slight degree, return to the normal state.

In the *conjunctiva of the fornix*, the same conversion of hypertrophy into cicatricial contraction takes place. Only, the external phenomena are somewhat different, in conformity with the different character of the conjunctiva in this situation. Here we do not see any whitish bands, but we find that the thick swellings which are formed by the hypertrophic fold of transition are becoming gradually thinner and flatter. Associated with this process, and proceeding with it step by step, is a condition of contraction taking place in the conjunctiva, a condition which steadily increases until even the folds that in the normal eye are present in the fornix are smoothed out and disappear (Fig. 19 *B* at f_1). The conjunctiva has grown pale, and a delicate bluish-white coating is witness to the cicatricial character of its superficial layers.

Pannus, provided that further changes, such as will be described later, have not occurred in it, is capable of complete retrogression, so that the cornea can reacquire its normal transparency. Ulcers heal, leaving behind them cloudy spots, the influence of which upon vision is dependent upon the degree of their opaqueness and also upon their situation within the pupillary area of the cornea.

The morbid changes in the conjunctiva and cornea, which are characteristic of trachoma, vary so greatly in their *intensity* that it will be necessary to distinguish the cases into those that are light and those that are severe. In the lightest cases the hypertrophy of the conjunctiva is small and the cicatricial formation that succeeds it is correspondingly insignificant; so much so, perhaps, that it may scarcely be possible any longer to make the diagnosis of trachoma, if some time has elapsed since it occurred. When once the cornea has become implicated, the case must always be characterized as severe. It must be remarked however: (1) That the symptoms of irritation do not always by any means bear a fixed proportion to the objective changes; cases with very great hypertrophy of the conjunctiva and thick pannus often running their course without inflammatory accidents, and vice versa. (2) That

similarly no fixed relation exists between the changes in the conjunctiva of the lids and those of the cornea. We see cases with very pronounced proliferation of the palpebral conjunctiva without pannus, and, on the other hand, cases with pannus and ulcers associated with a trifling affection of the conjunctiva. (3) In one and the same case the course is often very variable, in that sometimes intermissions or even spontaneous partial recoveries, sometimes relapses and exacerbations, occur. The latter are surely to be expected if, in a case that has been improved by treatment, treatment is too soon discontinued; but it is noticed that they also occur without any known cause under appropriate treatment properly carried out. Thus a suddenly occurring supplemental attack of pannus can in a short time annihilate the results of months of treatment.

It is not only, however, with regard to the intensity of the morbid changes, but also with regard to the *swiftness* with which they take place that such great variety prevails, and the same is true of the associated symptoms of irritation, which are usually the more considerable the more rapid the progress of the disease. In the majority of cases the disease sets in with moderate symptoms of irritation—photophobia, lachrymation, pain—which augment with the increase in the objective changes. Not infrequently, however, trachoma develops so *insidiously* that for a long time those whom it has attacked are not aware of it. Such persons sometimes do not have their attention called to their disease until the pannus as it covers the cornea begins to disturb their sight. These cases belong as a rule to the granular form of trachoma. When the people living in barracks, schools, etc., that are infected with trachoma undergo medical examination, there is always found a number of inmates who do not complain of any troubles whatever and who regard themselves as perfectly healthy, while examination shows in the folds of transition a very considerable development of trachoma granules. In contrast with cases running this insidious course are the cases of what is called *acute trachoma*. In these the disease begins with very violent inflammatory accessories; the œdema of the lids, the great swelling of the conjunctiva, the profuse purulent secretion would almost lead us to imagine the case to be an acute blennorrhœa. The correct diagnosis can be made as a rule by our finding the conjunctiva studded with numerous trachoma granules. But if these are absent during the first days of illness, or if, because of the great swelling of the conjunctiva, they are not apparent, the subsequent course of the disease may be the only thing that can clear up the nature of the latter; which it does, since the hypertrophy of the conjunctiva, that is characteristic of trachoma, soon develops. Such acute cases occur chiefly during the prevalence of an epidemic of trachoma; they are dangerous to sight not so much on account of pannus as of corneal ulcers, that make their appearance during the acute stage.

15. Stage of Sequelæ of Trachoma.—It is only the lightest cases, or those that come under treatment early, that are completely cured. In other cases there are left sequelæ, which are accompanied by a permanent impairment of the eye. These affect either the lids and conjunctiva or the cornea. They are as follows:

1. *Distortion of the lids* with faulty disposition of the cilia. The distortion is produced by the cicatricial contraction of the conjunctiva and the tarsus, as a result of which the tarsus bends in such a way as to be convex anteriorly. This distortion is recognizable even from an inspection of the lids while in situ, from the fact that they bulge more than usual. It appears still more clearly on everting the lids, especially in the upper lid, in which the distortion is always more pronounced. We find the conjunctival surface of this lid traversed by cicatrices, among which one that is particularly striking is a cicatricial band which runs in the form of a narrow white line two or three millimetres above the free edge of the lid and parallel with it. Along this line there is a furrow-like depression produced by the drawing in of the conjunctiva and the tarsus. On everting the lids we feel that this spot corresponds to an angular bend of the tarsus (t_1, Fig. 19 *B*), which lies, therefore, in the neighborhood of the free border of the lid. From this bending of the tarsus the whole lid acquires a boat-like or bowl-like shape.

The cause of the distortion of the tarsus lies partly in the cicatricial contraction of the conjunctiva; for, as the conjunctiva grows shorter upon the posterior surface of the tarsus, it tends to bulge the latter forward. But the distortion is mainly produced by changes in the tarsus itself. The latter is as much the seat of inflammatory infiltration in severe cases of trachoma as the conjunctiva itself. It is hence increased in size and, when we evert the lid, we feel that it is thicker, wider, and at the same time less pliable, so that sometimes the eversion of the lids is rendered considerably more difficult. From such a state of things the experienced observer would infer that he has to fear a subsequent distortion of the tarsus with its consequences. The infiltration and thickening of the tarsus are greatest near its lower margin, along the line at which the blood-vessels passing to the conjunctiva from in front perforate the tarsus (see page 36 and Fig. 16, *rp*). There is no doubt but that it is chiefly along these vessels that the inflammatory infiltration makes its way from the conjunctiva to the tarsus. Hence, cicatricial contraction which succeeds the infiltration and which makes the whole tarsus thinner and narrower, is greatest at this spot and produces there an angular bending of the tarsus, corresponding to which is the cicatricial line that is seen running horizontally upon the conjunctiva tarsi, and the position of which accordingly agrees in general with that of the sulcus subtarsalis present in the normal lid.

The immediate consequence of the distortion of the lid is an altera-

tion in the position of its free border and of the cilia springing from it. In the upper lid the free border no longer looks straight downward, but downward and backward (inward). The internal margin of the lid, which in the healthy state is sharp, becomes rounded off ("shaved off") and is no longer to be recognized with distinctness (Fig. 19 *B*, r_1), this being due partly to the way in which it is drawn by the contracting conjunctiva, partly to the pressure of the eyeball upon it. By the turning inward of the free border of the lid the direction of the cilia (c_1) is changed, so that they now no longer look forward, but look downward and backward, and touch the surface of the cornea (*trichiasis*). Another factor besides the distortion of the tarsus that contributes to this false position of the cilia, is the tension which the contracting conjunctiva exerts. This tends to draw the skin, and with it the cilia, over the free border of the lid and up upon the posterior surface.

If the distortion of the lid progresses, the entire border of the lid turns backward and *entropion* is produced. In trichiasis and entropion alike there is a permanent condition of irritation, which is excited and maintained in the eye by the constant contact of the cilia with the cornea; if this condition lasts any length of time, diseases of the cornea make their appearance as a consequence of the mechanical injury produced by the cilia (see §§ 36 and 46).

The opposite kind of anomaly of position of the lid—that is, its turning outward, or *ectropion*—also occurs as a result of trachoma. The cause of this is that the conjunctiva, when it is thickened and has undergone great proliferation, crowds the lid away from the eyeball; the contraction of the muscular fibers of the orbicularis then suffices to complete the eversion of the lid. This kind of ectropion is usually found only in the lower lid (see § 112).

2. *Symblepharon Posterius.*—When the cicatricial contraction of the conjunctiva reaches a high degree, the folds of the region of transition flatten out completely; the conjunctiva passes directly from the lid to the eyeball (f_1, Fig. 19 *B*). If the lower lid is drawn down with the finger, the conjunctiva stretches tightly in the form of a vertical fold between the lid and the eyeball, and, if the lid is drawn down still farther, the eyeball, being fastened tightly to it by the conjunctiva, must follow. This condition is characterized as symblepharon posterius (see § 25). In particularly severe cases the lower half of the conjunctival sac is reduced to a shallow groove between the lid and the eyeball.

3. *Xerosis Conjunctivæ.*—When very greatly contracted, the conjunctiva loses its power of contributing through its own special secretion to the moistening of the eyeball. A feeling of dryness develops in the eye; the scanty, muco-purulent secretion shows a tough, sticky, viscid character. Subsequently there appear on the conjunctiva tarsi

several dry-looking places, to which the lachrymal fluid can not adhere any more than if they were smeared with grease. This condition tends to spread, until finally the conjunctiva may be affected by it throughout its whole extent. The conjunctiva in that case looks dry and brittle; the lachrymal fluid, which is secreted in less amount than usual, does not adhere to it. The cornea, which as a rule has become partly cicatricial from previous pannus and ulcers, likewise suffers from the deficient moistening; its epithelium becomes thicker, epidermoid, dry upon the surface, and hence opaque. Thus is produced that melancholy condition which is called *xerophthalmus* and which forms the worst termination of trachoma: the eye is rendered incurably blind, is disfiguring to its possessor, and in addition keeps torturing him with a constant, very tormenting sense of dryness (see § 26, xerosis conjunctivæ).

4. *Corneal Opacities.*—These are after-effects, both of ulcers of the cornea and of pannus. A recent pannus, it is true, can disappear completely by a process of resorption, so that the cornea reacquires its normal transparency But often further changes take place in the pannus, which render its complete disappearance impossible. Among them is to be reckoned in the first place (*a*) the *transformation into connective tissue*, which the pannus undergoes if it lasts for a long time. In this the same change takes place in the pannus as in the trachomatous conjunctiva, a portion of the round cells of which the pannus is composed growing into spindle-cells and finally into connective-tissue fibers. As a consequence of this the pannus becomes thinner, its surface grows smooth, the vessels with a few exceptions disappear, and at length the pannus is transformed into a thin membrane of connective tissue which covers the surface of the cornea. This connective tissue no longer admits of resorption. In cases in which the pannus is quite thick and succulent and covers the whole cornea, (*b*) *ectasia of the cornea* sometimes results. That is, as the tissue of the pannus, which is soft and abounding in cells, penetrates more deeply into the cornea, the tissue of the latter softens and gives way before the intra-ocular pressure (keratectasia e panno). Such a cornea never becomes perfectly clear again. The same thing is true, finally, of those cases in which (*c*) pannus is complicated with *ulcers;* the regions which are occupied by the latter likewise have permanent opacities left upon them.

Trachoma, then, is a disease which is distinguished by its duration, extending over years, and which in many cases renders those who are attacked by it half or wholly blind. If we add to this the fact that because of its infectious nature it is exceedingly apt to spread, we shall understand how, for those regions in which it is endemic, it is a veritable scourge.

16. Etiology.—Trachoma originates exclusively in infection proceeding from another eye affected with trachoma. Infection takes

place by transfer of the secretion; contagion by means of the atmosphere, the existence of which was formerly accepted, seems not to occur. In all probability the secretion owes its infectious character to a *micrococcus*, in regard to whose nature, however, investigations so far have led to no concordant results. Since it is the secretion alone that transmits the infection, the danger of infection, which any given case carries with it, is in direct proportion to the amount of the secretion; the more profuse the latter, the greater being the danger of those in the immediate neighborhood of the patient. The transfer of the secretion from one eye to another generally takes place indirectly through the medium of the finger or chiefly through the medium of certain articles of the toilet, like sponges, towels, handkerchiefs, etc., which are brought into contact with the eyes. A special opportunity for this to occur is afforded when a pretty large number of people have their sleeping-apartments in common, and so make common use, too, of the articles above mentioned. Hence, trachoma spreads most extensively in barracks, penal establishments, poor-houses, orphan-asylums, boarding-schools, and indeed schools of all kinds, etc. Moreover, outside of such institutions the same factor asserts itself, since trachoma preferably attacks poor people who live crowded close together and bestow little care upon cleanliness. Moreover, the fact that in many countries the Jews are special sufferers from trachoma is to be attributed to the same cause. Trachoma, finally, varies in its geographical distribution. It is most frequent in Arabia and in Egypt, which is regarded as its proper home (ophthalmia Ægyptiaca, Egyptian ophthalmia). In Europe it is much more extensively distributed in the east than in the west. Elevated lands (Switzerland, Tyrol) are almost entirely free from it, while it is very frequently found in the low lands (Belgium, Holland, Hungary, and the whole region of the lower Danube).

Therapy.—The treatment of the trachomatous *conjunctiva* has a twofold object in view: on the one hand it seeks to do away with the inflammatory complications and the increase of secretion, which is associated with them; on the other hand, to further the disappearance of the conjunctival hypertrophy. In this way it is most likely that the process of shrinking in the conjunctiva will be restricted as much as possible, so as to avert the evil consequences resulting from its cicatricial contraction. We attain both objects by the proper employment of caustics, of which two are almost exclusively in use: nitrate of silver in two-per-cent solution and sulphate of copper in the form of a stick. The silver has the feebler action, and is therefore borne better; copper, being applied in substance, has a correspondingly stronger cauterant action, but also causes more irritation. These remedies are, as a rule, applied once a day, it being only in severe cases that they are used twice a day. The indications for the two remedies are as follows: Nitrate of silver is em-

ployed in all recent cases with violent inflammatory symptoms and great secretion. It can also be used when there are ulcers upon the cornea that are still in the progressive stage, if we take care that none of the solution comes into contact with the cornea itself. Copper sulphate is suitable for those cases in which the inflammatory symptoms are small, and its chief use is in removing the hypertrophy of the conjunctiva. For this purpose it acts much more energetically than the silver solution, and should, therefore, be used in preference to it in all those cases in which its application is allowable at all. Great inflammatory irritation, but most of all the presence of ulcers of the cornea in a state of active progress, contra-indicate the use of the bluestick.

From these indications it follows that, as a rule, we treat a recent case with the silver solution until the inflammatory symptoms have disappeared and the secretion has diminished. As soon as this has occurred —and several weeks are generally sufficient for the purpose—we replace the silver solution by bluestone. At any rate, we must avoid using the silver solution for too long a time on account of the argyrosis which may develop as a result of it. The copper is now to be used, the application of it being made stronger or weaker according to the degree of hypertrophy; and is to be kept up for months and even years, until every trace of hypertrophy has vanished and the conjunctiva has become free from congestion and smooth throughout. At first the application is made every day; but when only slight remains of the hypertrophy exist, it is sufficient to make the application every other day, and subsequently every third day. Moreover, the application should be made less and less energetically all the time, until, finally, when the cure of the trachoma is complete, the application is entirely suspended. In these later stages of the disease we can instruct the patient how to evert the lid himself and touch it with the bluestone, so that he need not come so often to the physician. Or, we can prescribe for him an ointment of copper sulphate (one half to one per cent), which he himself can rub into the conjunctival sac. When there is great cicatricial contraction of the conjunctiva it is not applicable at all, and must be replaced by the use of ointments. A one or two per cent ointment of white or yellow mercurial precipitate (the latter acts more energetically) may be rubbed into the conjunctival sac. In relapses with great inflammatory irritation, such as often occur in the course of the treatment, the copper is always to be replaced for a short time by the silver solution. If, however, the symptoms of irritation are very violent, the silver solution itself can not always be borne, and must then be replaced for some time by milder remedies such as instillations or compresses made with weak solutions of corrosive sublimate or boric acid.

The treatment of trachoma must be kept up until the hypertrophy of the conjunctiva is completely done away with, as otherwise relapses

are to be looked for sooner or later. The chief difficulty in the treatment lies in its great length, it often requiring many months for a complete cure. Those patients who have not the endurance or the means necessary for such a course, give up treatment as soon as their subjective troubles have disappeared, without, however, being completely cured. Then we commonly see them returning after some time with a relapse, which is often more severe than the disease for which we originally treated them. This lack of completeness in the treatment is the reason why the disease with many men drags on through their whole life.

The treatment of *complications affecting the cornea* is conducted on the principle that the affections of the cornea, caused by a conjunctival trouble, are best cured by the treatment of the conjunctival trouble itself. Hence, *corneal ulcers* and pannus occurring in connection with trachoma are not combated directly, but have their cure brought about by means of applications made to the conjunctiva. The only limitation to this is that, where there are corneal ulcers in active progress, the silver solution is demanded and the bluestone, on the other hand, is contra-indicated, and further, that contact of the caustic with the cornea should be avoided as far as possible. For the iritis, which is not rarely associated with ulcers of the cornea, atropine in one-per-cent solution is instilled. In other respects, ulcers of the cornea are to be treated according to the rules which are in general applicable to them (see § 36). It must only be noted that bandaging, which is generally indicated in the case of ulcers of the cornea, should be avoided as far as possible when trachoma is present, because by the closure of the eye the secretion is retained in the conjunctival sac, and thus both the conjunctival and the corneal troubles are aggravated.

Pannus, in recent cases, disappears of itself, simply from applications being made to the conjunctiva. If the pannus is unusually dense, it is allowable to make careful applications of the caustic to the pannus itself. Since pannus is often associated with slight iritis, atropine should be instilled from time to time, in order to keep the pupil dilated and prevent the formation of posterior synechiæ. Very old pannus, which already is partly made up of connective tissue and has lost all but a few of its vessels, requires special treatment. Experience has shown that further resorption can be obtained in such a pannus by exciting a violent inflammation in it, and so producing an increased succulence and a greater vascularity. For this purpose we make use of the jequirity treatment (De Wecker). We here employ a three to five per cent infusion of jequirity, which is prepared by steeping the ground jequirity-beans for twenty-four hours in cold water. With this infusion, which is to be prepared fresh every day, the conjunctiva of the everted lids is painted very thoroughly two or three times a day. The inflammation that is thus produced reaches the desired height on the second or third day, when the lids are reddened and are swollen with œdema,

the conjunctiva is strongly injected and covered with a croupous membrane, and slight chemosis is often present. This inflammation we designate as jequirity-ophthalmia. As soon as it has attained the height just described, the further application of the remedy is discontinued, as otherwise we should make the inflammation increase to the point where it would cause a necrotic disintegration of the conjunctiva and cornea. We now allow the inflammation to run its course, simply keeping the eye clean; when the inflammation has completely subsided, the cornea is found to have gained in transparency as compared with its former state, and sometimes to a very considerable extent. This very energetic treatment is adapted only to those old cases of trachoma in which the more pronounced symptoms of inflammation are wanting, the conjunctiva is in great part cicatricial, and the cornea is entirely covered by old pannus.

Of the *sequelæ* of trachoma, trichiasis and entropion demand operative treatment (see the section on operations, §§ 168 and 171). The symblepharon posterius, which is produced by the shrinking of the conjunctiva, is amenable to no treatment. Xerosis of the conjunctiva is also incurable, so that treatment must be limited to the amelioration of the patient's sufferings. To diminish the sense of dryness, frequent instillations of milk, glycerin, or mucilaginous substances (e. g., the mucilago seminum cydoniorum), may be made.

In addition to the foregoing measures for the treatment of trachoma, it is self-evident that care must be taken to keep the eye clean, for which purpose we may prescribe weak antiseptic solutions. The patient should have a nourishing diet; he ought not to be kept in his room, but, on the contrary, should be made to go out in the open air and take exercise, and perhaps may be directed to engage in some light out-of-door work.

With a disease of this infectious character, its dissemination should be checked by suitable *prophylaxis*. The physician must set a good example, and must cleanse his hands very carefully after touching a trachomatous eye. He must call the attention of the patient affected with trachoma to the infectious nature of his disease. He must teach him how to protect from infection the other eye which may be still healthy, and how to avoid spreading the disease among those in his immediate neighborhood, his family, his fellow-workmen, etc. For securing the latter object, the prime requisite is that the patient should have his own washing materials, linen, bed, etc., and should keep them for his own individual use.

The prevention of epidemics of trachoma in public establishments, such as barracks and institutions and schools of every sort, constitutes an important duty of the officials in charge of such places. These officials should take care that the members of their community have separate washing-materials, linen, etc., for their use. They should be kept ap-

prised of the presence of any trachomatous patients by means of frequent medical inspection, and, as soon as such a patient is found, he should be immediately removed from the community; for, where no trachomatous patient is found, no extension of the disease is possible.

There is no disease of the eyes in regard to which such a mass of literature has been reared in the course of the ages as in regard to trachoma. Nevertheless, we are to-day still far from a clear understanding of the matter, or from any unity of views in regard to it. The many people who have worked upon the subject have given us a great number of divisions of the disease and various names; and the confusion has been carried so far that for almost every designation that we employ we must give a description, too, in order to make clear to our audience what we mean.

It was at the commencement of our own century that trachoma began to attract the attention of physicians to any great degree. It was then that the disease first showed itself as an *epidemic* among the European armies (ophthalmia militaris). People were of the opinion that it had been introduced into Europe from Egypt (hence ophthalmia ægyptiaca) by Napoleon I. For when the latter, in July, 1798, landed in Egypt with an army of thirty-two thousand men, most of the soldiers were very soon attacked by a violent ophthalmia, and these were supposed to have brought with them upon their return to Europe the disease which was formerly confined to Egypt. Subsequent historical researches, however, have shown that the disease had already been endemic in Europe since antiquity. Celsus mentions the disease, and gives a good description of the roughness of the lids and the purulent discharge that it occasions. For treatment the ancients employed scarification of the conjunctiva, which is still to-day made use of by some, and which was accomplished both by means of various instruments and also by friction with fig-leaves.

From time immemorial, then, trachoma has existed in Europe as an endemic disease. But when, by reason of the Napoleonic wars the armies came so repeatedly in contact with each other and with the civil population, the disease became more widely disseminated and occurred in epidemics. In some countries it became frightfully prevalent. In the English army, during the year 1818, there were more than 5,000 on the invalid list, who had been rendered blind as a consequence of trachoma. In the Prussian army, from 1813 to 1817, 20,000 to 30,000 men were attacked with it; in the Russian army, from 1816 to 1839, 76,811 men were subjects of the disease. In Belgium, in 1840, one out of every five soldiers was affected with trachoma. The French army, which was supposed to form the starting-point of the disease, was just the one that, relatively speaking, was least attacked. The armies disseminated trachoma among the civil population through the discharge of soldiers affected with eye diseases, through the quartering of troops, etc. When they had so many trachomatous soldiers in the Belgian army that they did not know what to do, the Government applied to Jüngken, who was at that time a celebrated ophthalmologist in Berlin. He recommended them to dismiss the trachomatous soldiers to their homes. By means of this fatal measure trachoma soon became diffused in Belgium to an extent which has been observed in no other European state.

Among the *civil population* trachoma finds a favorable soil for its dissemination in places where many men dwell together, hence among the poorer classes,

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

but particularly in large public asylums. If trachoma has made its way into such an establishment, and no measures are taken against its spreading, soon a great number or even all the inmates will be attacked by it. In a pauper school at Holborn, the whole five hundred children suffered from trachoma (Bader). Hairion, in 1840, found in an orphan asylum at Mecheln sixty-four out of sixty-six orphan girls affected with trachoma; in Mons, seventy-one out of seventy-four orphan girls were suffering from the disease. In the workhouse at Dublin, no less than 134,838 persons were attacked by trachoma from 1849 to 1854. On board ships, where the crew live so closely crowded together, trachoma can spread very quickly. Mackenzie tells the story of the epidemic which raged upon the French slave-ship Rodeur in the year 1819. The disease broke out during the voyage, and first among the negroes who, to the number of 160, were crowded together in the hold. When they took the unfortunate people up on deck, because the fresh air seemed to have a favorable influence on the ophthalmia, many threw themselves overboard, so that they had to desist from doing this. Soon one of the sailors also was attacked, and three days later the captain and almost the whole crew were taken down with the disease, so that it was only with the greatest difficulty that the ship could be brought to its destination.

According to the descriptions of that time, trachoma then ran a very acute course, and was attended with profuse secretion, circumstances which explain the rapidity with which the disease spread. It seems that they then had to

FIG. 20.—CROSS-SECTION THROUGH THE TRACHOMATOUS CONJUNCTIVA OF THE UPPER LID. MAGNIFIED 24×1.

Both small papillæ. *P*, *P*, *P*, and large ones, P_1, P_1, are found. The former stand side by side like the pickets of a palisade; the depressions, *t*, *t*, *t*, lying between them and coated with epithelium, look like the tubules of glands. The large papillæ contain trachoma granules, *T*, T_1, which are not sharply limited and do not possess a capsule. The epithelium of the conjunctiva is in many places, *e*, *e*, thickened. The mucous coat is in a condition of cellular infiltration, *a*, which is especially marked in the vicinity of the blood-vessels, *g*, *g*.

deal with the acute form of trachoma, which, now that epidemics have ceased, has become rare. At present trachoma exists in many countries as an endemic disease, but mostly occurs under that chronic form under which, with scarcely any exceptions, we now see it.

The different forms under which trachoma shows itself nowadays are regarded by some as distinct diseases. In order to discover the relation existing between these forms, we must study first of all the *anatomical alterations* which belong to the different forms.

The *papillary* growths which impart to the conjunctiva its velvety or rasp-

berry-like appearance are caused by an increase in size of the surface of the hypertrophic conjunctiva. The latter is thrown into folds, between which correspondingly deep clefts are formed; then on cross-section the folds appear under the form of papillæ (Fig. 20, P and P_1). The connective tissue forming the papillæ is stuffed full of round cells; the surface of the papillæ is covered with a very much thickened epithelium (e, e), which, of course, is continued on into the depressions (t, t) that exist between the papillæ. These depressions hence have in microscopical cross-section the appearance of a narrow canal coated with epithelium, and were accordingly regarded at one time as tubular glands; and hence the formation of new glands was alleged to occur in trachoma. That this in fact does sometimes occur can not be absolutely denied, for, even though the depressions between the papillæ are not glands, yet tubes coated with epithelium grow out from them and extend into the tissue of the conjunctiva, and these tubes are then in no respect distinguishable from true glands.

Papillary hypertrophy of the conjunctiva, however, is by no means a characteristic feature of trachoma, in the sense of being limited to it alone. In a less marked degree it is found in connection with every long-continued irritation of the conjunctiva, as in chronic catarrh; in conjunctivitis lymphatica that has lasted a long time; in ectropion, upon the portion of the conjunctiva that is exposed to the air, etc. Papillæ, that are large but compressed and flat, are the distinguishing mark of vernal catarrh (§ 20). Still more intense degrees of

FIG. 21.—TRACHOMATOUS GRANULATION FROM THE FOLD OF TRANSITION. MAGNIFIED 24×1.

The trachomatous granulation T pushes up the conjunctiva in the form of an elevation, and is inclosed by a layer of thickened connective tissue, the capsule, k. The conjunctiva is infiltrated with cells, both in its upper layers, a, and along the vessels, g: the epithelium, e, shows, above the place marked a, bright spots which correspond to the goblet-cells; at d it lines one of Henle's glands.

papillary growth are observed after acute blennorrhœa, whenever the so-called chronic blennorrhœa develops from it. For this reason many authors call all cases of papillary trachoma chronic blennorrhœa, even though they have not been preceded by acute blennorrhœa. Others call the papillary form ophthalmia purulenta chronica, others conjunctivitis granulosa or granulations, because the papillæ of the conjunctiva have a resemblance to the granulations of a wound. This resemblance, however, is a purely external one, since the hypertrophied conjunctiva does not have a raw surface, but is covered with epithelium; besides, by such a designation, a confusion would necessarily be produced with the granular form of trachoma.

The *granular form* is characterized by the presence of trachomatous granu-

lation. These, in microscopic cross-section, appear as a rounded aggregation of lymph-corpuscles, forming, as it were, a little lymphatic gland or a lymphatic follicle, analogous to those which compose Peyer's patches. The trachomatous granulation either passes without any sharp line of demarkation into the surrounding tissue, which is also very rich in cells (Fig. 20, T and T_1), or it has a sort of incomplete capsule of connective tissue (Fig 21, T). This capsule (Fig. 21, k), according to Raehlmann, is developed only in trachomatous granulations which have existed for a pretty long time.

The granular form is called trachoma verum, trachoma Arlti, and trachoma folliculare (Horner). Many, in view of the trachomatous granulations (granules) present, give this form the name of granulations, while, as has been said above, others, on the contrary, use just this expression for the papillary form; hence the confusion that exists.

The mixed form (trachoma mixtum, according to Stellwag), which clinical observation has already shown to be the most frequent, is proved by microscopical examination to be almost the only one that occurs. That is, even in those cases in which papillæ alone appear to the naked eye to be present, trachomatous granulations are found in cross-sections examined under the microscope, either lying within the papillæ themselves, or imbedded in the deeper portions of the mucous membrane. In the former case the papillæ have a particularly broad or even knob-shaped appearance (Fig. 20, P_1). In the second case the trachomatous granulations are concealed by the papillary bodies, beneath which they lie; then we often see them coming into view afterward, when the papillary growths have disappeared, as the result of a prolonged course of treatment.

By *trachoma diffusum*, Stellwag understands a pretty high degree of development of mixed trachoma, in which large growths, which sometimes project like a cock's comb, cover the tarsal conjunctiva. The *brawny trachoma* of Stellwag represents a later stage of mixed trachoma, in which the papillary excrescences have disappeared, and thus the surface of the conjunctiva has become pretty smooth; but the lymphoid infiltration in the deeper parts has persisted, or as a result of relapses has even increased. We have in that case a conjunctiva which is thickened, smooth on the surface, yellowish, and of brawn-like translucency.

The transformation of the conjunctiva into *cicatricial tissue* proceeds as follows: A part of the numerous cells which are contained in the conjunctiva, and which are either uniformly scattered through it or occur in circumscribed accumulations (trachomatous granulations), disappears by resorption; another part gradually grows into spindle-shaped cells, and finally into connective-tissue fibers. This new-formed connective tissue shrinks, and to such a great extent that the conjunctiva contracts and becomes thinner and of tendinous character. We have here a process similar to that which occurs in cirrhosis of the liver—i. e., the shrinking of a new connective tissue which has developed out of an inflammatory infiltration. It would be a mistake to suppose that in the trachomatous conjunctiva there are raw spots which become covered with a cicatrix—a mistake into which we might be more apt to fall because of the term granulations. What we call granulations in trachoma have nothing at all in common with the granulations of wounds, except their external appearance.

Pannus proves, upon histological examination, to be a layer of new-formed tissue, which, starting from the limbus, spreads over the cornea. It consists of

a soft tissue, extremely rich in cells, which greatly resembles the infiltrated trachomatous conjunctiva. This tissue abounds in vessels, and occurs in alternately thicker and thinner layers, for which reason the pannus looks uneven and nodulated. Pannus, when it begins, insinuates itself between Bowman's membrane (Fig. 22, *B*) and the epithelium (Fig. 22, *E*), the latter being thus lifted off from Bowman's membrane and made to cover the pannus. The parenchyma proper of the cornea is protected by the still intact Bowman's membrane and suffers no essential change. Hence it is possible for the cornea to regain completely its normal structure and transparency after the resorption of the pannus, since then the epithelium is once more directly applied to Bowman's

FIG. 22.—CROSS-SECTION THROUGH THE MARGIN OF A CORNEA AFFECTED WITH PANNUS. MAGNIFIED 125 × 1.

Beneath the epithelium, *E*, *E*, is the limbus, *L*, greatly thickened by cellular infiltration; from it the pannus, *P*, in which are perceived the cross-sections of several vessels, extends between the epithelium and Bowman's membrane, *B*, over the cornea, *C*. *S*, sclera.

membrane. But this is possible in recent cases only of pannus; later Bowman's membrane gets to be destroyed in places, and the pannus then penetrates into the corneal tissue proper, the superficial layers of which consequently are also destroyed in spots. Then the complete restoration of the transparency of the cornea has become impossible.

For some forms and stages of pannus special names are in use. A recent pannus, which has not yet become thick, is called pannus tenuis, and, if it is very vascular, pannus vasculosus. If the pannus has acquired a considerable thickness, it is then known as pannus crassus or pannus carnosus. Sometimes the pannus is so big that one might imagine that he was looking at exuberant granulations ("proud flesh") upon the affected region of the cornea. This is pannus sarcomatosus. This adjective is also applied to the proliferating conjunctiva, as, for example, in the expression ectropion sarcomatosum. It would be best to discard these antiquated expressions altogether, and especially the designation sarcomatosus, which can give rise to confusion with neoplasms —sarcomata. An old pannus, composed of connective tissue and poor in vessels, is a pannus siccus.

What are the *causes* of pannus in trachoma? Some see in pannus a direct transfer of the inflammatory process from the conjunctiva of the region of transition to the cornea. Against the occurrence of any such transfer per continuitatem, it has been urged, and with justice, that that portion of the conjunctiva which is interposed between the fold of transition and the rim of the cornea, namely, the conjunctiva bulbi, takes little or no part in the trachomatous process. Another explanation starts from the fact that pannus in trachoma as a rule begins in the

upper half of the cornea, and under ordinary circumstances has covered this portion entirely, before the lower half has been attacked at all. This would indicate that the upper lid, by reason of the roughness of its conjunctival surface, causes mechanically an irritation of the upper half of the cornea, and thus gives rise to inflammation in it. It is not to be doubted that this factor does come into play in the production of pannus, but it can not be the only nor even the most important cause of pannus; for we often find the greatest roughness of the palpebral conjunctiva without pannus, and conversely find pannus in cases in which the palpebral conjunctiva is almost perfectly smooth. At the present time we can merely say that anatomically pannus is analogous to trachoma of the palpebral conjunctiva; that it is a trachomatous affection of that part of the conjunctiva which covers the cornea—i. e., of the conjunctival layer of the cornea. That this part of the conjunctiva becomes diseased in trachoma as readily as the conjunctiva of the lids or of the fold of transition, should not excite our wonder; on the contrary, it is more difficult to understand why the remainder of the conjunctiva, the conjunctiva scleræ, does not take a more active part in the trachomatous process. Perhaps the following explanation is the correct one. Fig. 22 shows that the infiltration of small cells is particularly marked in the limbus of the cornea (*L*), and gradually diminishes as it extends from the latter over the cornea itself. So also, where we make a microscopical inspection, we find the limbus, at the spot where a pannus is on the point of developing, intensely reddened and so greatly swollen that sometimes it forms quite a thick outgrowth. Hence the impetus to the formation of a pannus seems to be given by the trachomatous affection of the limbus. Now, then, we must propound the following questions: 1. Why is it that the limbus in particular is affected so intensely in trachoma? and, 2. Why does the inflammation pass from the limbus to the cornea and not in the opposite direction—i. e., to the scleral conjunctiva? The first question must find its explanation in the fact that the limbus is by far the most vascular portion of the bulbar conjunctiva, and hence the part that is the most apt to be inflamed. That the inflammation spreads from the limbus in a centripetal direction—that is, upon the cornea, and not in a centrifugal direction upon the conjunctiva scleræ, agrees with what we have been able to observe in other affections of the limbus and of the adjacent portions of the cornea. We are acquainted with many diseases in which inflammatory infiltrations or vessels push their way inward from the limbus into the cornea. Probably this depends upon the centripetal direction of the circulation of the blood in the scleral conjunctiva. The arterial vessels run from the periphery toward the limbus, where they form a dense network of capillary loops. At this point, where the centripetal stream of blood finds its limits, a circulation of lymph begins, which is directed in the same sense and which enters the cornea; and it is in the same direction that the inflammatory products advance, and that the blood-vessels which jut out from the marginal loops of the cornea tend to make their way. Finally, it still remains to be explained why pannus generally begins at the upper margin of the cornea, or why, in other words, the limbus is first affected at this point. If an eye is infected with trachoma, the conjunctiva is not attacked by the infection in its whole extent alike, but the infective matter adheres first to some circumscribed portion of the conjunctiva—generally to the conjunctiva of the tarsus or of the fornix, which is particularly apt to be affected with trachoma. Now, there are two ways in which the affection can spread from the portion of conjunctiva

that is first attacked to other parts, namely, by continuity, in which case it extends gradually over the neighboring parts; and, by contiguity, in which case through contact with the diseased conjunctiva tarsi there is an infection of those portions of the conjunctiva bulbi that lie opposite the former, and especially of the limbus, which is especially predisposed to infection. Now, it is precisely at the upper margin of the cornea that the limbus is in contact with the conjunctiva of the upper lid, and that, too, not only at night, but also all day, while the eye is open, since normally, even when the eye is open, the uppermost part of the cornea is covered by the upper lid. Here, therefore, the constant contact that exists is most favorable to an infection of the limbus by the diseased conjunctiva of the lids. That the rough condition of the latter assists in the production of this infection is likely. Such a condition acts partly as a mechanical irritant, partly by giving an impetus to infection through the production of small multiple lesions of the conjunctival and corneal epithelium. (That infection, by the contact of opposed surfaces, which is so frequently observed in the skin and other organs, may also occur in the conjunctiva, is proved by the case of vernal catarrh, adduced in the note to § 20.)

What *relation* do the separate forms of trachoma bear to each other? Is trachoma papillare (blennorrhœa chronica, etc.) a disease perfectly distinct from trachoma granulosum (trachoma verum, etc.), or are both merely different forms of the same process? Anatomy shows that in the enormous majority of cases the changes that are characteristic of the two forms (papillary growths and trachomatous granulations) are found simultaneously, so that scarcely any unmixed cases of either form are left. This speaks decidedly for the unitary theory of the disease. We arrive at the same result if we follow out the etiology of the disease. Cases are observed in which one individual, affected with one of the two forms, infects other persons, in some of whom, thereupon, the same form, in others the other form, develops. Piringer, moreover, by his inoculations experimentally established the fact that the secretion from one and the same case produced the first form in one individual, the second form in another; indeed, in one and the same person there was once produced by inoculation with the same secretion one form in one eye, the other form in the other. We may, therefore, be quite justified in regarding the two forms of granular and papillary trachoma as one and the same disease.

Does any connection exist between trachoma and acute blennorrhœa? These two diseases, which both originate in infection, are, of course, in their typical form very different from each other. Nevertheless, the chronic blennorrhœa which develops from an acute blennorrhœa is so similar to the papillary form of trachoma that the two can not be distinguished from each other with certainty either by the clinical examination of the eye or by anatomical dissection. We may advance the following hypothesis: Recent acute blennorrhœa when transferred to another eye produces acute blennorrhœa in the latter also. But, if the acute blennorrhœa has already passed into the chronic form, its transfer to another eye no longer excites an acute but a chronic inflammation, which latter is trachoma. Different observations speak for the possibility of such a method of origin of trachoma. Goldzieher reports an epidemic of trachoma in the school for the blind at Buda-Pesth, an epidemic which had been introduced by a new-comer, a boy who had lost his sight from acute blennorrhœa. Through him all the male and most of the female scholars became affected with trachoma, all possible forms of which, including the pure papillary, the pure

granular, and the mixed, could be recognized. Sattler has observed the following case: A mother, who was affected with leucorrhœa, gave birth to a child having acute blennorrhœa of moderate degree. The mother acquired a genuine trachoma by infection from her child. As she lived in a region perfectly free from trachoma, infection from any other source was excluded. Against such a connection between chronic blennorrhœa, following the acute form, and trachoma, the objection has been raised that in the former disease granulations (lymphatic follicles) have never been observed. But this is not always the case. In the autumn of 1887 two girls, sisters, were admitted to my clinic, the elder of whom had acquired an acute blennorrhœa of the conjunctiva of both eyes as a result of her own leucorrhœa. The younger sister had caught the infection from the eyes of the elder, and likewise acquired acute blennorrhœa of both eyes. In her case this was not quite so severe in its onset, and, after the greatest violence of the inflammation had abated, papillary outgrowths developed on the conjunctiva tarsi and numerous granulations in the folds of transition, so that there was presented a perfect picture of mixed trachoma. In many other cases besides this I have been able to observe the development of granulations in the folds of transition after acute blennorrhœa, and still more frequently have been able to prove their existence by the microscopical examination of excised portions of the conjunctiva.

From what has preceded we draw the following conclusions: There is but *one kind of trachoma, which, however, appears under various forms.* The ultimate origin of the disease is probably referable to the secretion of genitals affected with gonorrhœa. This secretion produces in the human conjunctiva acute blennorrhœa, which passes into chronic blennorrhœa. The secretion of the latter produces in a healthy eye directly a chronic inflammation, trachoma, which then, by a repeated process of transfer, spreads of itself.

It still remains to speak of the position of *follicular conjunctivitis* with regard to trachoma. The former is found chiefly in young people, while trachoma, on the contrary, is very seldom met with in children. The two diseases are very similar, in that lymph-follicles occur as characteristic formations in both. In follicular catarrh they are smaller, are more sharply limited, and project farther above the surface of the conjunctiva; in trachoma they are larger, destitute of sharp outlines, and less prominent. Follicles proper are often oblong-oval (cylindrical) and placed side by side, in a row like a string of pearls, while trachomatous granulations are round and more rarely present any such arrangement in rows. But these characteristics are sometimes so obscured that even experts can not, in many cases, make the diagnosis with certainty, and the subsequent course of the disease alone affords the desired information. Even in the histological structure no thorough-going distinction can be found between follicles and trachomatous granulations. A further resemblance between follicular catarrh and trachoma consists in the fact that they both chiefly occur among bodies of men who are confined in a small space. It is, therefore, easy to understand that these two diseases have repeatedly been confounded with each other; and a number of authors, in fact, explain follicular catarrh as being a kind of trachoma distinguished by its mildness and freedom from danger. But to such a view the following objection must be raised: It is not yet certain whether follicular catarrh occurring among confined bodies of men is propagated by infection like trachoma, or is merely a result of the contamination of the air by dust, exhalations, etc. On the other hand, it is quite satisfactorily

established that, under certain circumstances, follicular catarrh can arise without any infection whatever. This is the case after the prolonged instillation of atropine, which is followed in many persons by the development of a typical follicular catarrh with very numerous follicles. But trachoma can never arise without infection. A further and more important distinction between the two diseases is the course. Follicular catarrh is not associated, or is associated to only an inconsiderable degree, with papillary hypertrophy of the conjunctiva; it never leads to shrinking of the conjunctiva, to pannus, or to any of the other sequelæ; it is a disease perfectly devoid of danger, one which, even without any treatment, finally gets well and leaves no trace behind; so that on this account alone the differentiation of the two diseases is not only theoretically, but also practically, of great importance.

The question with regard to the relations of the different forms of blennorrhœa, trachoma, and follicular conjunctivitis to each other, will first receive a definitive solution through the medium of bacteriology. At present only the micrococcus of acute blennorrhœa, the gonococcus, has been satisfactorily determined. In conjunctival diseases, which, like trachoma and follicular catarrh, are associated with the formation of granulations, several observers (Leber, Sattler, Koch, Michel, Poncet, Schmidt, Kucharsky, Staderini, Goldschmidt, and others) have also proved the existence of micro-organisms, some of which pretty closely resemble the gonococcus without being identical with it. So far, however, the observations of individual investigators are not sufficiently accordant for us to be able to formulate any definite conclusions. Probably we must regard the formation of granulations composed of adenoid tissue not as anything at all specific, but only as a particular form of reaction, which the conjunctiva of the eye, like other mucous membranes, exhibits toward many different sorts of irritants. These irritants can be of a bacterial nature, as in trachoma and in follicular catarrh. Then there are cases of tuberculosis of the conjunctiva (see § 23), which begin with an abundant development of granulations, quite as in trachoma; of these Rhein has described some examples, and I myself have seen one. Again, Goldzieher and Sattler have seen cases in which there was an abundant formation of granulations in a conjunctival affection which they regarded as syphilitic. In regard to the follicular catarrh produced by atropine, it is not yet determined whether the irritation is a chemical one or is dependent upon Schizomycetes, which may chance to have developed in the atropine solution.

The *treatment* of trachoma encounters its greatest difficulty in the length of time that it requires. With the view of abbreviating this, attempts of the most varying nature have been made to attack directly the outgrowths upon the conjunctiva (papillæ, granulations) and destroy them. These measures, which in part were already employed in ancient times, consist in scarification of the conjunctiva, excision and expression or rupture of the trachomatous granulations, their cauterization with a pointed cautery-iron or with a galvano-cautery point, excision of the fold of transition which lodges the granulations, nay, even the excision of the conjunctiva tarsi, together with the tarsus. I have myself tried most of these methods, which are constantly coming into vogue again and being extolled anew. In order to subject them to a positive test, I chose for the trial cases in which trachoma existed in the same degree in both eyes. Then, as one eye was treated in the ordinary way and the other by excision of the conjunctiva or by destruction of the isolated granulations,

it was possible for me to draw a decisive comparison between the various procedures. In this way I have found that every process for directly destroying the conjunctiva renders the shrinking of the latter only so much the greater and does not cure the trachoma any more quickly, inasmuch as we can not remove all the diseased portions of the conjunctiva. I can not, therefore, recommend these procedures except, perhaps, for those rare cases in which the portions of the conjunctiva that are affected with trachoma are quite circumscribed, and can, therefore, be completely removed.

For getting rid of a thick pannus many employ *peritomy*. This is the operation of dividing the conjunctival vessels running to the pannus, either by simply making an incision round the cornea through the conjunctiva, or by excising a narrow annular strip of the latter.

In order to make an old pannus transparent, it was formerly the practice to deliberately make an inoculation of acute blennorrhœa, because it had been found by experience that an eye with pannus, which is accidentally attacked by acute blennorrhœa, instead of losing its cornea by suppuration, has its pannus made actually more transparent. This procedure is, at the present time, replaced by the treatment with jequirity, which accomplishes the same thing without exposing the eye of the other side, or the eyes of other persons, to the danger of blennorrhœal infection.

Jequirity (the seeds of the Abrus precatorius) has for a long time been in use in Brazil, where trachoma is epidemic, as a popular remedy for this disease. To De Wecker is mainly due the credit of having subjected this remedy to scientific examination and of having introduced it into Europe. The action of jequirity does not depend upon the presence of micro-organisms in the infusion, as was originally believed, but upon an unorganized ferment which is excessively poisonous (Hippel, Neisser, Salomonsen, Venneman).

V. Conjunctivitis Diphtheritica.

17. Conjunctivitis diphtheritica,* like acute blennorrhœa and trachoma, is a purulent inflammation of the conjunctiva, which spreads by infection, and the secretion of which is contagious. But the contagium is a specific one, different from that of the other two diseases. It has the property of exciting in the tissue of the conjunctiva a profuse exudation, which has a great tendency to coagulate, and thus leads to the necrosis of the infiltrated tissue.

Symptoms and Course.—The lids of the affected eye are swollen, reddened, hot, and painful to the touch. The swelling is generally very considerable; sometimes the lids are of board-like hardness, so that it is impossible to evert them, and scarcely possible even to open the palpebral fissure. The conjunctiva as a whole is greatly swollen and reddened; in contrast with this general character are one or two places which are somewhat depressed, smooth, and of a grayish-yellow color, and often contain a few dirty-red speckled markings (ecchymoses). Such places are characteristic of diphtheria; they are the spots where the exudate deposited in the tissues is so excessive that it com-

* From διφθέρα, a membrane.

presses the vessels, and so makes the tissue bloodless and pale. According to the extent to which these spots are distributed we distinguish two degrees of the disease. The lighter cases are those which we call *partial* diphtheria (*diphtheria en plaques*). In this we find the diphtheritic spots in the conjunctiva (especially the palpebral conjunctiva), under the form of more or less big islands, between which lie the less affected portions of the membrane, which latter are merely much reddened and swollen and bleed readily, and are not gray and bloodless. In the severer cases, on the other hand, the diphtheritic foci increase rapidly in size and coalesce, so that the *confluent* form of diphtheria is produced. In this, then, either a very large portion of the conjunctiva, or even its entire surface, is uniformly gray and hard, just as it is after being intensely cauterized, *e. g.*, by the action of quicklime.

A thin liquid like whey flows off from the palpebral fissure. Small-sized diphtheritic patches are frequently found at the edges and angles of the lids, the nostrils, and the angles of the mouth; sometimes there is also a fully developed pharyngeal or nasal diphtheria. The little patients (for the disease attacks children almost exclusively) have a high fever and are greatly prostrated.

The condition just described, which develops rapidly after a short period of incubation, is called the first stage of the disease, or stage of *infiltration*. It keeps up for from five to ten days, according to the extent of the diphtheritic process upon the conjunctiva. Then the spots of diphtheritic infiltration begin gradually to disappear. Where the infiltration is not so very dense, resorption of the exudate occurs, but, in those spots from which the circulation has been altogether cut off by the infiltration, and the tissue has consequently mortified, the necrotic portions slough away. Thus are produced losses of substance in the conjunctiva, which soon become covered with granulations such as cover a raw surface. Meanwhile the secretion has become more abundant and more purulent, for which reason this second stage is characterized as the stage of *blennorrhœa*. The third stage is that of *cicatrization*, in which the granulating surfaces, that are produced by the sloughing off of the gangrenous portions of the conjunctiva, gradually grow smaller and are covered over with a new epithelial lining. Since the latter change is effected by the drawing in of the neighboring conjunctiva, the conjunctival sac as a whole is contracted; frequently, too, in single spots adhesions are produced between the conjunctiva of the lid and that of the eyeball (symblepharon). The more extended the diptheritic process, the more striking is the subsequent cicatricial contraction of the conjunctiva.

Diphtheria is pre-eminently dangerous to the eye from the fact that, in all severe cases, there is a simultaneous affection of the cornea. This affection appears in the guise of a purulent inflammation of the cornea, occurring under forms like those which have been already described

under the head of acute blennorrhœa (page 51). The greater the extension of the diphtheritic process upon the conjunctiva, the more certain is corneal suppuration to occur. Indeed, in the confluent form of diphtheria, the cornea is always irretrievably lost. In less severe cases, the cornea may escape with a few opacities or even be quite uninjured. The prognosis, therefore, in respect to the preservation of sight in diphtheria of the conjunctiva is always serious; even as regards life itself it is sometimes unfavorable. Weakly children not infrequently succumb to the severity of the general disease and to the high fever. Special danger springs from the fact that the diphtheritic process may develop, either at the same time or subsequently, in the mucous membrane of the nose, the throat, or the larynx, and can thus cause the child's death.

Etiology.—Diphtheria of the conjunctiva as a rule attacks children, and most frequently those between the second and eighth year of life. Adults are only exceptionally attacked, and then generally to a less marked degree. In its nature diphtheria of the conjunctiva is identical with diphtheria of other mucous membranes; all kinds owe their origin to contagion. Accordingly, conjunctival diphtheria is chiefly observed at times when an epidemic of pharyngeal diphtheria is prevailing. Hence, too, it is found pre-eminently in those countries where diphtheria of all sorts is a frequent occurrence, it being thus especially prevalent in North Germany. Thus it is that we are indebted for the first exact description of the disease to Von Graefe, who, in Berlin, had an opportunity of observing many cases of diphtheria of the conjunctiva. In lands where diphtheria prevails, this disease appears either sporadically or as an epidemic. Moreover, at the time of an epidemic of diphtheria, other violent inflammations of the conjunctiva show a tendency to assume all at once a diphtheritic character. In Austria* severe cases of conjunctival diphtheria are a rare occurrence.

Treatment.—In the first stage of the disease we must chiefly limit ourselves to careful cleansing of the eye, for which purpose the best thing for us to employ is a weak antiseptic liquid (solution of corrosive sublimate, salicylic acid, or potassium permanganate). Cold compresses, which would seem to be indicated by the great swelling and redness of the lids, must be applied with much caution, so as not to depress still further the conjunctival circulation, already seriously embarrassed by the diphtheritic infiltration. Hence, we very soon change these for warm compresses, which accelerate the resorption of the infiltration as well as the separation of the slough. As soon as the second stage declares itself by its abundant purulent secretion, we begin the application of a nitrate-of-silver solution to the conjunctiva, in order to limit the secretion and bring the swollen conjunctiva back to its

[* And in America.—D.]

normal state. In so doing we must at first proceed with great caution and use pretty weak solutions (one half to one per cent). In no case should such an application be made, as long as any gray spots of diphtheritic infiltration are anywhere to be seen, since the necrosis of the tissue would be promoted by the silver-nitrate solution. It would, therefore, be a gross mistake to apply the silver solution in the first stage of the disease.

We keep on making the applications to the conjunctiva as long as the latter is red and swollen and discharges a copious secretion. During the subsequent period of cicatrization we try to oppose, as far as possible, the formation of adhesions between the lids and the eyeball (doing this by frequently drawing the lid away from the eyeball, or by laying a pledget soaked in oil between the two); for adhesions once formed can be removed only by an operation. Complications affecting the cornea are to be treated according to the rules that will be given further on for purulent inflammation of the cornea in general.

All operative procedures, whether upon the cornea or upon the lids, should be avoided in the first stage, as the wounds thus produced generally become diphtheritic too. Besides treating the eye, every attention should evidently be paid to the severe disturbance of the general condition; especially is it incumbent upon us to keep up the little patient's strength in every possible way.

In consideration of the very infectious character of diphtheria, our special aim must be prophylaxis. While acute blennorrhœa and trachoma exert an infectious action only through a transfer of the secretion, infection in diphtheria can, in all probability, occur simply by means of the air, without any direct transfer. Accordingly, we remove from the vicinity of the patient all persons who are not indispensably necessary for purposes of nursing; but most of all we insist upon the removal of children, who are particularly susceptible to infection. If diphtheria has attacked only one of the patient's eyes, the other must be protected against infection by a carefully applied occluding bandage, just as in acute blennorrhœa.

The persons who have the care of the patient must be particularly charged to cleanse the hands carefully after touching the diseased eye, to destroy at once the materials employed in cleansing, etc.

Croup and diphtheria are anatomical terms denoting definite forms of inflammation. Croupous inflammation is characterized by the deposition of an exudate upon the surface of a tissue, where, by coagulation, it hardens into a membrane. The essence of the diphtheritic inflammation, on the contrary, consists in the exudation of a great mass of material within the tissue itself, together with consecutive necrosis of the latter. These two varieties of inflammation can be produced in different ways—that is, either by external irritants (mechanical, chemical, or thermic) or by the action of a special contagium. The former act by setting up an inflammation of a high degree of severity. Thus, by frequently

repeated cauterization with the nitrate-of-silver solution, we can produce a croupous layer upon the conjunctiva, and, by still stronger applications, we can excite a diphtheritic inflammation with necrosis of the tissue in spots. The repeated application of the jequirity infusion produces first a croupous, afterward a diphtheritic, inflammation of the conjunctiva. These processes throughout their course are altogether local, and do not implicate the rest of the organism. Etiologically they are perfectly distinct from the true diphtheria of mucous membranes, which is produced only by a definite contagium. This form of diphtheria has associated with it, besides the local inflammation, severe poisoning of the whole body, to which the patients may succumb, even when the local symptoms are very trifling. Hence, to the same anatomical form of mucous-membrane inflammation correspond two groups of diseases, which are etiologically quite distinct, and which can not be too sharply differentiated, the more so as mistakes can easily be made on account of their external similarity of appearance. I once saw a young man whose palpebral conjunctiva, besides marked inflammation, showed very extensive diphtheritic infiltration; a clever ophthalmologist had declared it to be true diphtheria, and had given an extremely serious prognosis. But a precise inquiry into the history of the case soon elicited the fact that excessive applications to the conjunctiva, made by a country doctor, had set up this inflammation, which, when the applications were discontinued, very soon subsided.

As regards croupous conjunctivitis, it is due to a contagium which, in opposition to that of diphtheria, causes a purely local inflammation, and is probably identical with the infectious agent that produces simple conjunctival catarrh. Croup of the conjunctiva has nothing in common with croup of the larynx, which is regarded by many authors as a form of diphtheria peculiar to the air-passages. Diphtheria of the conjunctiva, on the other hand, is undoubtedly an inflammation caused by the diphtheritic contagium, and is analogous to diphtheria of the pharynx. A child with pharyngeal diphtheria, brought into a ward of a children's hospital, has been known to produce a pharyngeal diphtheria in his right-hand neighbor, and a conjunctival diphtheria in his neighbor on the left. Arlt reports the case of a physician into whose eye some secretion spurted while he was examining a child sick with pharyngeal diphtheria; the eye, in spite of being immediately washed out, was destroyed by diphtheria of the conjunctiva. Conversely, a diphtheritic affection of the nose and throat can be induced in the case of a child with conjunctival diphtheria, as a result of the latter. The tears secreted by the diseased eye carry the contagium through the lachrymal duct into the nose, and from there may, by being swallowed, arrive in the throat and the stomach, and set up diphtheria in these localities also. A common contagium lies at root of all these affections—a contagium which, perhaps, is to be looked for in Löffler's *Bacillus Diphtheriæ*.

The granulations developing after the separation of the diphtheritic slough are true granulations growing out of the losses of substance in the conjunctiva. They should, therefore, not be confounded with the so-called granulations of trachoma, which are simply overgrown conjunctiva still coated with epithelium. Hence, too, the subsequent cicatrization in diphtheria must be conceived of as something different from that of trachoma. In the former case we have to do with cicatrization in the ordinary sense—that is, with the formation of a pellicle over a wound; in the latter case, with the gradual contraction of a mucous membrane, which has never had a wound upon its surface. This fact does not

prevent the subsequent results of cicatrization in the two cases from being possibly the same in both cases; trichiasis, cicatricial entropion, even xerophthalmos itself, are observed after diphtheria.

In place of the simple expectant treatment of diphtheria in the first stage, Ficuzal has recommended an active form of treatment, consisting in the application of lemon-juice to the conjunctiva; and Leber has recommended the application of a one-per-cent solution of corrosive sublimate.

VI. Conjunctivitis Lymphatica (Scrofulosa, Phlyctænulosa).

18. Symptoms.—In its simplest, typical form, conjunctivitis lymphatica presents the following picture: A little red eminence, of about the size of a millet-seed, develops at some point upon the limbus of the conjunctiva. This is the *efflorescence*. In the beginning it is conical, its apex being covered by the epithelium of the conjunctiva. In a short time the epithelium at the summit of the efflorescence separates, and the tissue that lay beneath it breaks down, so that the apex of the cone, so to speak, melts away; and the cone itself bears on its top a minute gray ulcer, which thus lies above the level of the neighboring, healthy conjunctiva. By a continuation of the breaking-down process the cone at length disappears entirely, the ulcer sinks to the level of the conjunctiva, and speedily becomes clean and then covered with epithelium. Thus the ulcer heals, without a visible mark being left upon the conjunctiva. The whole process is completed in eight to fourteen days.

As the efflorescence springs up, the adjacent part of the conjunctiva becomes hyperæmic, the injected vessels being directed from all sides toward the little nodule. Hence, the reddened portion of the conjunctiva shows the form of a triangular sector, the apex of which lies in the limbus and corresponds to the nodule. The remainder of the conjunctiva is perfectly free from congestion.

The simplest type of conjunctivitis lymphatica, therefore, consists in the formation of a sharply circumscribed, nodular exudate, to which there corresponds an injected district of the conjunctiva. Conjunctivitis lymphatica is hence a focal affection of the conjunctiva of the eyeball, and is thus distinguished from all the varieties of conjunctival inflammation hitherto described, which are diffused inflammations, in that they extend in a uniform fashion over large sections of the conjunctiva.

The clinical pictures which conjunctivitis lymphatica actually exhibits present modifications of the type above described, which differ most widely from each other. These modifications concern—

(*a*) The *number* of the efflorescences. It is rare that we find but one of these; generally there are several, and not infrequently a good many, present at the same time. The fewer they are the larger they gen-

erally grow; in rare cases they almost attain the size of a lentil. When there are many nodules present they are small; often we find the entire limbus, or even the cornea itself, covered with very minute eminences, so that the surface of the eyeball looks as if fine sand had been strewn over it. Such very small nodules commonly disappear in a few days by resorption, without any preliminary disintegration. When multiple efflorescences are present, the injected portions of the bulbar conjunctiva belonging to the separate nodules become confluent, and the conjunctiva then appears reddened all over, so that the focal character of the disease is obscured, and declares itself only by the presence of separate nodular exudates. So, too, when the inflammation is great, the palpebral conjunctiva also participates in the injection, so that, in that case, conjunctivitis lymphatica is no longer an affection limited to the bulbar conjunctiva.

(*b*) The *site* of the efflorescences may be not only in the limbus itself, but also exterior to the latter, in the anterior segment of the bulbar conjunctiva, and likewise interior to the limbus, in the cornea itself. In the latter are situated small gray nodules, which consist of an accumulation of round cells superficially disposed between Bowman's membrane (Fig. 23, *B*) and the epithelium (Fig. 23, *E*), which is bulged forward by them. By the breaking down of the nodule there is produced in the cornea a loss of substance, which is quite shallow, affects merely the epithelium, and heals without leaving a permanent opacity. Often, however, the affection assumes a more serious form, from the fact that the exudations have a tendency to spread farther in the cornea, extending either into the depth of the latter or along its surface. If the infiltration extends through Bowman's membrane into the parenchyma proper of the cornea, an ulcer is produced, when it breaks down, which penetrates more deeply and can even perforate the cornea. In that case, after the ulcer heals, a permanent opacity remains.

FIG. 23.—EFFLORESCENCE ON THE CORNEA IN CONJUNCTIVITIS LYMPHATICA (AFTER IWANOFF).

The nodule which consists of cells lies between Bowman's membrane, *B*, and the epithelium, *E*, which latter is thus raised so as to form a prominence. In the epithelium we distinguish the lowermost layer of cylindrical cells, *u*, the middle layer of polygonal cells, *m*, and the uppermost layer of flat cells, *o*; scattered between the epithelial cells lie a few round cells, *r*. A nerve, *n*, is seen extending through the parenchyma of the cornea, *C*, and the corneal corpuscles, *K*, up to the nodule.

(*c*) The corneal ulcers which result from the efflorescences may assume a serpiginous character—that is, they may spread by a sort of creeping process along the surface of the cornea. In this way is produced the *vascular fasciculus* (Fischer), which is also called keratitis

fascicularis, or, according to Stellwag, the herpetic bridge. This affection begins by the development of a small ulcer out of an efflorescence at the rim of the cornea. After some days this ulcer becomes clean in its peripheral half—that is, in the part turned toward the corneal rim. At the same time, in accordance with the ordinary behavior of regressive corneal ulcers, blood-vessels develop, which run from the limbus to that edge of the ulcer that is healing, and which serve to keep up the process of cicatrization. But, in the mean time, that margin of the ulcer that is toward the center has remained infiltrated and gray. Inasmuch as at this place the infiltration and the subsequent purulent disintegration keep on extending, the ulcer constantly advances toward the center of the cornea, while on its peripheral side it heals equally fast, and draws the blood-vessels after it. The vascular fasciculus accordingly appears as a narrow red band formed of blood-vessels (hence the name), and extending from the corneal margin some distance into the cornea. At its apex it bears a small gray crescent, the infiltrated, advancing margin of the ulcer. The arrest and recession of the process first occur when the ulcer is completely healed. Until this has taken place the vascular fasciculus can advance far into the cornea, to its center or even beyond it. The small ulcer, however, always remains superficial, and a perforation of the cornea due to it has never been observed. When the vascular fasciculus has at length come to a standstill, the vessels gradually disappear from it, and there only remains a superficial opacity of the cornea, which corresponds in shape to the long-drawn-out form of the vascular fasciculus. This opacity never clears up again completely, and hence, when found at any time during the whole subsequent life of the patient, enables us to diagnosticate the previous existence of a vascular fasciculus.

(*d*) The severest cases of conjunctivitis lymphatica are those in which the exudation, starting from in front, makes its appearance in the deep layers of the cornea as a diffused *deep-lying* infiltration. We then find the cornea occupied to a considerable extent by an opacity of a uniform gray or yellowish color, becoming fainter toward the edges. This opacity is situated in the deep layers of the cornea; and the surface of the cornea over it is dotted with minute spots. In the bad cases the infiltrate, originally gray, becomes more and more yellow, and finally breaks down into pus, so that an extensive loss of substance is produced in the cornea. In the benign cases, on the contrary, the infiltrate gradually disappears again by resorption, and the cornea regains its transparency either wholly or in part. It is astonishing to what an extent even extensive infiltrates can undergo resolution.

(*e*) Instead of appearing as separate circumscribed foci, the exudate may occur under the form of a continuous new formation of tissue upon the surface of the cornea—that is, under the form of *pannus*. This is called pannus scrofulosus, to distinguish it from trachomatous

pannus. It does not, like the latter, show a predilection for the upper part of the cornea, but develops from any spot whatever upon the corneal margin. It is ordinarily thin and not very vascular, and is quite disposed to undergo complete resolution.

Conjunctivitis lymphatica is generally accompanied by abundant lachrymation. Mucous or muco-purulent secretion, on the contrary, such as occurs in catarrh, is not present as a rule; hence the lids do not ordinarily stick together in the mornings. The only exception to this is formed by those old cases in which the inflammatory process has passed over to the palpebral conjunctiva, and has thrown it into a state of concomitant catarrhal inflammation.

The *subjective symptoms* consist of photophobia and spasm of the lids (blepharospasm). Slight in some cases, in others they reach an extraordinary pitch; children creep into a dark corner of the room, bury their face in their hands, and struggle so violently against any attempt at opening their eyes, that the examination on the part of the physician is conducted under great difficulties. The intensity of these symptoms bears no definite relation to the severity of the disease; in fact, it is precisely in that form of corneal affection which spreads more extensively and penetrates more deeply, that the evidences of irritation are often pretty slight. The annoyance suffered, contrary to what takes place in conjunctival catarrh, is, generally speaking, greater in the morning than in the afternoon and evening.

Course and Prognosis.—A single typical efflorescence upon the limbus passes through all its phases up to complete subsidence in eight to fourteen days. If several efflorescences are present, the process of cure requires a proportionately longer time. Nevertheless, the disease would not last so very long if it limited itself to a single attack. This, however, is but rarely the case. Usually, after a period of quiescence, or even before the first attack of inflammation has quite run its course, the eye becomes red again, and new nodules shoot up in or near the limbus. Thus the disease may, with longer or shorter intermissions, last on for months or years. Its beginning occurs in childhood; the separate attacks, however, are often protracted until the time of puberty or sometimes even later; the affection being situated now in one eye, now in the other, then in both at the same time. Finally, the attacks become less and less frequent, and at length cease altogether.

The constant wetting of the lids by the tears frequently leads to blepharitis, to eczema of the skin covering the lids, and, as a consequence, to ectropion of the lower lid. Excoriations are frequently present at the external angles of the lids, and blepharophimosis often develops later on.

The *prognosis* of conjunctivitis lymphatica is favorable, in so far as the eye is but rarely rendered entirely blind by it. Superficial efflores-

cences disappear without leaving a trace behind; ulcers which penetrate into the parenchyma proper of the cornea leave permanent opacities, which, however, are in most cases thin and superficial (maculæ of the cornea). In persons who have gone through with many recurrences of conjunctivitis lymphatica the corneæ often bear quite a number of such maculæ as signs of past attacks. Thus the sight is impaired, the patients being often incapable of doing fine work. In addition to this, children, in consequence of the frequently repeated inflammations of the eyes, fall behind in their physical and mental development. So, even if conjunctivitis lymphatica only in exceptional cases leads to blindness, it nevertheless does so much harm to those who are attacked by it, that we ought to strive to combat it with every means in our power.

19. Etiology.—Conjunctivitis lymphatica is one of the most frequent of eye diseases, and it has its origin in the scrofulous diathesis. Like the latter it is a disease of childhood and youth. In very young children—those under the age of one year—it occurs but seldom, and it generally ceases at the time of puberty. Adults are attacked by it only in case they have carried the disease along with them from their childhood. The enormous majority of children affected with conjunctivitis lymphatica belong to the poorer classes. Such children receive insufficient and unsuitable nourishment, live in damp, poorly ventilated dwellings, and are kept constantly dirty. Other children affected are those who, though once healthy, have become run down as a result of other diseases (scarlet fever, measles, typhoid fever, whooping-cough, etc.). Such children as these look either pale and thin, or bloated and flabby like a sponge. The glands at the lower jaw, in the neck, and in front of the ear, are swollen. Partly as a result of the suppuration of these glands, and partly as a result of the breaking down of the scrofulous infiltrations in the skin, ulcers and fistulous passages are produced, which require months and years for their cure, and leave characteristic and disfiguring scars behind. Patches of moist eczema occur at various spots upon the body, most frequently upon the face; and the constant coryza, from which many of these children suffer, is to be attributed to an eczematous affection of the nasal mucous membrane. In the lids we find blepharitis. The nose and the upper lip are rendered thick by frequently recurring attacks of inflammation. More profound affections that occur are caries of bones (caries of the petrous bones appearing under the form of an otorrhœa being frequent), tuberculosis, and, in girls, delayed and irregular menstruation.

Some one of the above-mentioned symptoms of scrofula, and often several of them at once, accompany most cases of conjunctivitis lymphatica. Sometimes, though rarely in comparison with the other cases, the disease is observed in an individual who otherwise is quite healthy, just in the same way that other indications of scrofula also occur at times as altogether isolated phenomena.

Therapy.—In the lighter cases the local treatment consists in the application of irritants, of which calomel and the yellow-precipitate ointment (Pagenstecher's ointment) are most in use. The calomel in a finely powdered state is sprinkled in a thin layer upon the conjunctiva of the lower lid by means of a camel's-hair brush; the precipitate ointment (0·05 to 0·15 of yellow precipitate to 5·00 of fat), on the other hand, is introduced into the conjunctival sac by means of a glass rod or a brush, and is then rubbed about with the lids, so as to be distributed over the whole conjunctiva.

Both remedies are irritant in their action; the precipitate ointment more so than the calomel. Hence, in the beginning of the disease, where the eyes are in a marked state of irritation, it is best to employ calomel; and subsequently, when the inflammatory symptoms are diminishing, to replace this by the yellow ointment. The remedies mentioned are to be applied only once a day. Both find a contra-indication in the presence of recent infiltrates or progressive ulcers in the cornea. In such cases, before having recourse to irritant remedies, we must wait, meanwhile employing atropine, until the process of infiltration has subsided or the ulcer has become clean. Pannus and vascular fasciculi do not contra-indicate calomel or the yellow ointment. If under their use the vascular fasciculi can not be brought to a standstill, we cauterize the advancing edge of the ulcer with the point of a delicate cautery-iron (or with a galvano-cautery or thermo-cautery point). In the case of ulcers of larger size covered with exudation, as well as in the case of deep infiltration of the cornea, moist and warm compresses, applied several times a day for one or two hours at a time over the closed eyes, prove most efficient. With regard to the treatment of deep ulcers and of the cicatrices that follow ulcers, the general rules set forth under the head of affections of the cornea are applicable. A bandage should be applied only in case of imperative necessity (e. g., when there are ulcers penetrating deeply into the cornea); otherwise its use had better be avoided. It hinders the ready escape of the tears which are so copiously secreted, and, as it very soon becomes wet through with the secretion, it is liable to set up eczema of the skin of the lids.

In conjunctivitis lymphatica, *general treatment*, conducted with due regard to the etiology, is of especial importance. The child's nourishment should be strengthening and administered at regular hours. Care must be taken that the dwelling-place be dry and well ventilated, and the child should be sedulously kept out in the open air, irrespective of any photophobia that may exist. Indeed, in any case, we must not yield too much to this symptom of photophobia, and it would be quite a mistake to keep children in a dark room just because they shun the light. As invigorating measures, spongings with cold water are of service; also a sojourn in the country, especially at the mountains or

the sea-shore. After the acute inflammation has run its course, the use of brine-baths or of sea-baths is of great service in preventing relapses. Unfortunately, the carrying out of all these regulations is only too often frustrated by the force of circumstances and by the poverty of the patients.

The medicinal treatment of scrofula consists in the administration of cod-liver oil and of the preparations of iodine, iron, arsenic, and quinine. The sort of remedy employed and its dose must be adapted to each individual case. Furthermore, the cure of the eye disease is favorably influenced by treating any coexisting scrofulous affections, especially blepharitis, and also eczema of the face and of the nasal mucous membrane. In these affections the application of white-precipitate ointment (one to two per cent) does good service. In blepharitis this ointment is smeared at night over the closed palpebral fissure. Eczematous spots upon the face are covered with a pledget of linen smeared with the ointment, and, to relieve eczematous coryza, the ointment is introduced from the anterior nares as far into the nose as possible and rubbed in. For relieving moist eczema of the face, we can also employ with great advantage a five to ten per cent nitrate-of-silver solution, applied with the brush, after removal of the crusts, to the raw cutaneous surface, which thus becomes covered with a thin eschar, under which the raw spots heal rapidly. This application must be repeated at first daily, afterward at intervals of several days, and be kept up as long as crusts continue to form.

Conjunctivitis lymphatica, like trachoma, rejoices in quite a number of *synonymous titles*, such as conjunctivitis phlyctænulosa, conjunctivitis pustulosa, herpes conjunctivæ (Stellwag), conjunctivitis exanthematica (seu eczematosa), (Desmarres, Horner, Michel). Most of these designations originate from the view that the efflorescence on the conjunctiva or cornea is a hollow vesicle filled with fluid (*φλύκταινα* [bladder], pustula, herpes-vesicle). But the efflorescence is in reality never a vesicle, but a solid, though soft, projection, which is formed chiefly by an accumulation of lymphoid cells (Fig. 23). The softening and liquefaction of this cellular mass do not begin in the interior of the projection, but at its apex, so that there is no formation of a cavity (vesicle or pustule), but a loss of substance (ulcer) occurs, lying upon the free surface at the apex. The name herpes corneæ, moreover, can give rise to a confusion with true herpes corneæ (herpes febrilis and herpes zoster, see § 42). The term conjunctivitis exanthematica or conjunctivitis eczematosa is based upon the notion that conjunctivitis lymphatica is an affection of the cornea, analogous to eczema of the skin. Even if it is not to be denied that this is possibly the case, nevertheless so far no certain proofs have been forthcoming for this assumption, so that up to the present time at least there is no warrant for designating the two diseases by a common name. Perhaps it will not be possible to assign conjunctivitis lymphatica its proper place with certainty until a micro-organism, which is characteristic of it, shall have been found; and already several different researches have been made in this direction (Gifford, Burchardt).

The authors separate the lymphatic affections of the conjunctiva from those

of the cornea; they speak of conjunctivitis and of keratitis phlyctænulosa, of herpes of the conjunctiva and of the cornea, according as the efflorescence is located upon the conjunctiva or the cornea. In this way, for mere love of system, a picture of disease that, clinically speaking, is a perfect whole is torn in two. In fact, we have here really but one single disease, which is localized sometimes in one place, sometimes in another. Frequently enough we find in the same eye, at the same time, an efflorescence in the conjunctiva; a second in the limbus, half in the conjunctiva and half in the cornea; and a third upon the cornea itself. Hence, in the foregoing description of the disease, the expression conjunctivitis lymphatica is employed for the disease in general, no matter upon what part of the surface of the eyeball it is localized. This can be done without doing violence to anatomy, inasmuch as the uppermost layer of the cornea must be looked upon as the continuation of the conjunctiva over the cornea. Accordingly, we can regard the involvement of the cornea in conjunctivitis lymphatica as an involvement of the "conjunctival layer" of the cornea. For the same reason pannus trachomatosus we regard as one of the symptoms of conjunctivitis trachomatosa, and not as an independent affection of the cornea.

The *differential diagnosis* between conjunctivitis lymphatica and the other affections of the conjunctiva and cornea is, as a rule, easily made. The characteristic mark of the former lies in the focal character of the affection as well as in its localization upon and immediately about the cornea. Only one other variety of conjunctivitis, the conjunctivitis ex acne, shares this peculiarity with conjunctivitis lymphatica; but that disease is readily distinguished from the latter by the accompanying acne rosacea upon the face (see § 21). In vernal catarrh (§ 20), in which also little nodules occur upon the limbus, the palpebral conjunctiva, too, is diseased, and in a characteristic fashion. Of the diffuse inflammations of the conjunctiva, catarrh might be confounded with conjunctivitis lymphatica. For, in intense and obstinate cases of conjunctivitis lymphatica the affection spreads to the palpebral conjunctiva, which may become very much reddened, swollen, or even velvety; in that case a mucous or mucopurulent secretion forms upon the conjunctiva. It is often difficult to disguish between such cases and catarrh, especially if just at the moment of examination there are no characteristic efflorescences present upon the conjunctiva of the eyeball. Fortunately, a mistake in diagnosis does no harm, since, with such a condition of the conjunctiva existing, gentle cauterization with the nitrate-of-silver solution is always indicated, no matter what the origin of the disease. The pustular form of acute conjunctival catarrh forms a sort of intermediate stage between catarrhal conjunctivitis and conjunctivitis lymphatica (see page 41).

Scrofulous pannus is to be chiefly distinguished from pannus trachomatosus by the fact that an exact examination of the conjunctiva of the lids and of the fold of transition either discloses the changes of trachoma or establishes the fact of their absence. In regard to corneal ulcers, which have been preceded by the efflorescences of a conjunctivitis lymphatica, it is sometimes impossible to recognize the fact of this origin with certainty, except when the ulcer is located at the very margin of the cornea, and extends into the limbus conjunctivæ; corneal ulcers, as peripherally situated as this, occurring only in connection with conjunctivitis lymphatica. The vascular fasciculus can readily be confounded with an ordinary corneal ulcer, to which, in the course of healing, vessels have made their way from the limbus so as now to form a reddish-colored bridge

between the limbus and the ulcer. In such a case there is no fear of the ulcer's extending into the pupillary area of the cornea, and, after the ulcer heals, only a small, rounded macula is left, and not a long, opaque stria as in the case of the vascular fasciculus. The distinction between these two affections can be made as follows: In the vascular fasciculus, the advancing margin of the ulcer, infiltrated with gray, is readily visible; the blood-vessels, as they run over the cornea, lie in the furrow which the ulcer has channeled in the course of its progress—lie, therefore, at or below the level of the corneal surface. In the case of a simple ulcer connected with which there has been a development of vessels, this furrow and the opacity corresponding to it are wanting.

In the treatment of conjunctivitis lymphatica, *calomel* plays the greatest part. Since this remedy under its own form is insoluble in water, it was at first believed that a purely mechanical action should be ascribed to it (a scratching open of the efflorescences, which were considered to be vesicles). But opposed to this view is the fact that indifferent powders, for instance, finely pulverized glass, which were also employed for inspersions, did not develop the same action. More recent investigations have proved that the action of calomel is a chemical one. The calomel powder, when sprinkled into the eye, remains a long time in the conjunctival sac; minute quantities of it are transformed by the sodium chloride contained in the tears into corrosive sublimate,* which is thus continually being formed in small quantities, and exerts a steadily continued action upon the conjunctiva. According to others, calomel itself is, to a small extent, soluble in a salt solution such as the tears represent, and is hence efficient under its own form. If we undertake the inspersion of calomel in patients to whom at the same time iodine is being administered internally, we not infrequently observe a strong corrosive action from the calomel; for the latter forms with the iodine excreted in the tears the very corrosive mercuric iodide (Schläfke). These two remedies, therefore, are incompatible with each other.

A symptom that is especially tormenting for the patients is the *photophobia*, so often connected with conjunctivitis lymphatica. In many cases this persists obstinately for months. The parents then bring the children to the physician, with the statement that they have been "blind" for such or such a number of weeks. The children offer the greatest resistance to the forcible opening of the eyes, especially when there are excoriations at the external commissure, which give pain, and are prone to bleed when the lids are separated. Hence, in such cases the palpebral fissure is to be opened cautiously and not too wide, so as to avoid making the struggles of the children still greater. The lids, and especially the upper lid, are rendered œdematous by the constant blepharospasm, because the veins of the lids, which pass between the fibers of the orbicularis, are compressed by persistent contraction of this muscle. Furthermore, a state of inversion of the lids (entropion spasticum) may be induced by the violent way in which the eyes are screwed together. Finally, cases have been described in which children who have suffered for a long time from blepharospasm were perfectly blind after the disappearance of this symptom (Von Graefe, Schirmer, Leber, Samelsohn, Silex, Fürstenheim). Such blindness is transient. As in most cases no objective changes were demonstrable as the cause of the blindness, no positive explanation for this can yet be assigned.

[* According to some, however, calomel can remain in contact with tear-fluid for an indefinite time without change.—D.]

In most cases the blepharospasm soon yields if the conjunctival trouble, which forms the basis of it, has been ameliorated by appropriate treatment. In case the spasm of the lid is particularly obstinate, Arlt's ointment (0·5 gramme of extract of belladonna to 5·0 grammes of blue ointment) may be rubbed into the patient's forehead and temples two or three times a day. Instillations of cocaine, pretty frequently repeated, or douching the entire surface of the body with cold water every day, are also frequently of efficacy. Finally, we can even perform the operation of splitting the external commissure (canthoplasty, see § 169), especially when the palpebral fissure has been abnormally contracted by reason of blepharophimosis.

Herz has called attention to the fact that many children who suffer from conjunctivitis lymphatica are infested with head-lice, and that after doing away with these vermin the conjunctival disease, which hitherto may have been obstinate, often heals with surprising rapidity. He concludes from this that the irritation of the skin, set up by the lice, is capable of exciting and of keeping up the affection of the conjunctiva.

VII. Vernal Catarrh.

20. Symptoms and Course.—Vernal catarrh (Saemisch) is a chronic disease, persisting for years and setting up very characteristic changes in the conjunctiva, both of the tarsus and of the eyeball. The conjunctiva of the tarsus is covered with papillæ, which are broad and flattened, so as to make the conjunctiva appear like a rough, irregular street-pavement. Over the whole lies a delicate, bluish-white film, as if a thin layer of milk had been poured over the conjunctiva. The changes in the conjunctiva of the eyeball are still more striking, although not so constantly present. Growths arise from the limbus at the outer and inner side of the cornea, under the form of brownish, uneven, hard nodules of gelatinous appearance. These extend partly into the transparent cornea for a short distance, and still farther in the opposite direction into the conjunctiva. In contradistinction to the nodules of conjunctivitis lymphatica, which break down so speedily, these nodules never ulcerate; on the contrary, they are very stable bodies, often lasting for years with but slight variations in size.

Quite as characteristic as the changes objectively preceptible are the statements given by the patients. They say that during the winter they experience little cr no annoyance from their eyes, but, as soon as the first warm days come in spring, the eyes begin to grow red and to water; the patients are greatly tormented by photophobia, and especially by a constant itching in the eyes. The warmer the weather, the greater the intensity of the subjective troubles; conversely, the patients feel easier if, for instance, there occur in summer a series of cool, rainy days. In autumn the troubles once more abate, and during the cold season they disappear completely, only to begin anew in the following spring. The difference in the objective condition at different seasons of the year is considerably less than one would suppose from the great

change in the patient's subjective state, and consists principally in the eyes being free from discoloration in winter and injected in summer, while the growths upon the conjunctiva appear but slightly smaller in winter than in summer.

Vernal catarrh is a pretty rare disease, chiefly affecting the male sex and the ages of boyhood and youth. Almost always both eyes are attacked by it. The disease generally keeps on making its return annually for three or four years, and often longer still, for ten or even twenty years, until finally it becomes extinct, without leaving any marked trace of its presence behind. The prognosis is therefore good as regards the ultimate outcome, but bad as regards the duration, as up to the present time we know of no remedy for curing the disease or for preventing its annual return. The cause of the disease is unknown.

Inasmuch as we are unable to cure the disease, the *treatment* must be limited to the amelioration of the subjective symptoms. We combat the inflammation with the remedies used for acute and chronic conjunctival catarrh. For the itching and photophobia, cocaine in two-per-cent solution may be instilled. If the growths are of a considerable size they may be removed.

Vernal catarrh is not a catarrh, as the not altogether suitable name chosen for it would indicate, but is a disease sui generis. It was first described by Arlt (1846), who regarded it as a peculiar variety of conjunctivitis lymphatica. Subquently Desmarres mentioned it under the title "hypertrophie périkératique," Von Graefe as gelatinous thickening of the limbus, Hirschberg as phlyctæna pallida. Saemisch first brought into prominence the characteristic exacerbation of the disease during the warm season, and therefore called it vernal catarrh, by which name it is at present commonly designated. Horner discovered the peculiar character of the tarsal conjunctiva, and thus completed the picture of the disease.

The cause of the disease is unknown. Perhaps it depends upon a peculiar sort of micro-organism, for which, however, I like others have looked in vain. Some years ago I saw a ten-year-old boy who exhibited a particularly light form of the disease; only the right eye was affected, and in it there was only one small, though characteristic, nodule in the limbus, at the outer margin of the cornea. The tarsal conjunctiva of the upper lid was also diseased, but only in one single spot, and that at the place which, when the lids were closed, came into contact with the nodule upon the limbus. Here there was a very small area covered with broad, flattened papillæ, with dull, bluish-white surface. While looking at this, one could not get rid of the notion that here the spot that was first diseased (conjecturally the one upon the limbus) had infected the area of the conjunctiva tarsi, which lay opposite to it, and with which it came constantly in contact—a fact which might well indicate micro-organisms as the exciting cause of the disease.

The papillæ on the tarsal conjunctiva are hard—sometimes as hard as cartilage. I found them to consist of a sort of areolar connective tissue, with a peculiar, hyaloid degeneration of the cells of the connective tissue and of the

vessels. The epithelium covering the papillæ is thickened, and to this is probably due the macroscopically visible, bluish-white film upon the surface, which is characteristic of the disease. The growths upon the limbus consist of connective tissue, which is provided with very many cells and blood-vessels. Here, also, the epithelium is greatly thickened, and in places penetrates into the parts below, under the form of solid epithelial plugs (Horner, Vetsch). The growths are separated from the healthy cornea by sharply defined borders. In the cornea a slender gray stria, resembling the arcus senilis, may be seen, which runs parallel to the margin of the nodule, and is separated from it by a slender strip of transparent cornea.

In the lightest cases, the growths upon the limbus are wanting, the changes upon the tarsal conjunctiva alone being found. The latter are, hence, more important for the diagnosis of the disease. But in severe cases the growths upon the limbus reach a considerable extent. They sometimes even go entirely round the cornea, so that the latter is encircled by a high, hard wall. In two cases I have seen the cornea itself quite extensively attacked by the morbid process. The first case was that of a sixteen-year-old boy, in whom a layer resembling a pannus, but pale, gelatinous-looking, and devoid of vessels, shot out over the cornea from the thickened limbus. In spite of all attempts to check by therapeutic measures the progress of the growth, the whole cornea was ultimately covered by it, and remained permanently clouded. In the second case, a Greek of thirty years of age, an analogous growth took place on the cornea of both eyes, although it did not cover the cornea completely, but left free on both sides a small central area, about corresponding to the size of the pupil. According to Van Millingen, such cases not infrequently come under observation in Constantinople, where the disease appears to occur much more often than it does here.

The second case is also of interest because it concerned a grown man, while the disease ordinarily occurs only in youth. Quite small children are also exempt from it; there is only one instance of a one-year-old child being observed to suffer from the disease.

The growths in the limbus might lead to a confusion of vernal catarrh with conjunctivitis lymphatica, the papillæ upon the conjunctiva tarsi to a confusion with trachoma. The growths in the limbus are distinguished from the efflorescences in conjunctivitis lymphatica, apart from their external appearance, chiefly by their unchangeable character during even a prolonged course of observation. The papillary outgrowths are most of all distinguished by their bluish-white coating, which is wanting in papillary trachoma. The history of the case is also of special importance in making the differential diagnosis. The extremely characteristic statements in regard to the fact of a return of the disease every year in the spring, often establish the correct diagnosis before we have even looked at the eye. In hay-fever, to be sure, there is also generally a return of the conjunctivitis every year in the spring (see page 41). But this recurrence is an acute one, and runs its course within a few weeks, while, on the contrary, the symptoms of vernal catarrh last during the whole of the warm season. At this time, too, the objective changes are at their acme. During the winter the eye becomes free from discoloration, and the growths at the limbus diminish somewhat in size—quite small growths, indeed, disappearing completely. On the other hand, the papillæ of the tarsal conjunctiva remain pretty nearly unaltered.

In the treatment of vernal catarrh I have found the instillation of a three-per-cent solution of boric acid and the inunction of a one to two per cent ointment of white precipitate, as recommended by Arlt, to be the most efficient means for alleviating the patient's sufferings. More recently I have employed with success upon Van Millingen's recommendation dilute acetic acid (one drop of acidum aceticum dilutum to ten to twenty grammes of water).

Following the analogy offered by trachoma, some have tried to make the growths of the conjunctiva disappear by daily cauterization with the copper-stick. This attempt, however, has been as a rule unsuccessful. Some recommend, combined with the local treatment, internal treatment, especially with arsenic (De Wecker, Horner).

VIII. Conjunctivitis Exanthematica.

21. Conjunctivitis exanthematica * is a collective name for all those inflammations of the conjunctiva which accompany exanthems of the skin.

Among the *acute exanthemata*, measles is regularly associated with a conjunctivitis. This appears under the form of an acute conjunctival catarrh at an early stage (even before the eruption of the exanthem upon the skin), and generally disappears of itself after two or three weeks. In variola, small-pox pustules not infrequently develop upon the conjunctiva, generally upon the tarsal conjunctiva near the intermarginal line. Small-pox pustules which develop upon the conjunctiva of the eyeball, near the limbus, are dangerous from their setting up a purulent keratitis in the adjacent part of the cornea—a condition which should not be confounded with the corneal abscesses that develop metastatically in small-pox (see § 38).

Among the *chronic exanthemata*, acne rosacea deserves the principal mention. In this cutaneous affection the conjunctiva is implicated as follows: A minute nodule forms, with moderate symptoms of irritation, upon the limbus. This efflorescence breaks down after some days, and the ulcer thus produced heals without leaving any visible cicatrix behind (Arlt). This affection bears the greatest resemblance to the simple typical picture of conjunctivitis lymphatica, and shares with the latter its peculiar tendency to frequent recurrence. On this account it is very tormenting to the patient. It is possible to make the differential diagnosis chiefly from the fact that conjunctivitis ex acne attacks only adults and those who are at the same time affected with acne rosacea. It is important to make the correct diagnosis, since otherwise we might labor in vain to prevent the recurrences—a thing which can be done only by a suitable and long-continued treatment of the acne rosacea. The conjunctivitis itself is most speedily cured by inspersions of calomel.

The conjunctivitis of measles sometimes takes on a blennorrhœal or even a diphtheritic aspect (without actually turning into true blennorrhœa or diph-

* *Exanthema*, from ἄνθος, flower.

theria). In such cases the cornea is endangered. During convalescence in some cases of measles, when the conjunctival inflammation has already become pretty slight, I have observed numerous Meibomian glands, both on the upper and the lower lids, becoming inflamed and suppurating (hordeola meibomiana, see § 109). The purulent contents were evacuated partly through the orifices of the glands, partly upon the inner surface of the lid after breaking through the tarsus and the conjunctiva.

Pemphigus Conjunctivæ.—In this disease the conjunctiva, although reddened as a whole, displays one or two spots that are deprived of their epithelium and covered with a gray coating. While these spots are slowly undergoing cicatrization—a process attended with shrinking of the subjacent conjunctiva—other spots of the same nature appear in other places. Thus there is produced a constantly increasing cicatricial contraction of the conjunctiva, whose progress, it is true, is very slow (extending over months and years), but is irresistible. The conjunctiva becomes whitish, cloudy, dry, smooth, and tense. First, the folds of transition vanish, then folds make their appearance, stretching in a vertical direction from the lids across to the eyeball. The cornea, too, becomes cloudy and dry upon its surface. In the bad cases the lids at length become completely adherent to the eyeball, so that the cornea is permanently covered by the lids and the eye is incurably blind (symblepharon totale). Hence, the prognosis of pemphigus is very unfavorable—the more so as both eyes are always attacked.

Pemphigus of the conjunctiva is generally found in conjunction with eruptions of pemphigus vulgaris upon the skin. That, with rare exceptions, no bullæ are found upon the conjunctiva as they are upon the skin, is explainable from the anatomical character of the latter. Its epithelium is so soft and delicate that it can not, like the epidermis, be lifted up in broad layers by serous exudation, but ruptures and is thrown off in the form of shreds; hence, the raw spots upon the conjunctiva, which soon become covered with a gray coating, as is so frequently the case in wounds of mucous membranes. But there is also a variety of pemphigus conjunctivæ, in which the skin is healthy, while the mucous membrane of the mouth and nose is affected with pemphigus, and pemphigus of a type resembling that of the conjunctiva. Finally, there are cases in which a conjunctival lesion of the kind just described exists without pemphigus being present elsewhere in the body. That such cases as these, which were first described by Von Graefe as essential phthisis of the conjunctiva, are also to be ascribed to pemphigus, is not certain, though probable.

Treatment has no power to restrain the process. Arsenic is administered internally for the pemphigus; and to make the patient easier, mucilaginous remedies are instilled into the eyes as in xerophthalmus (see § 16). Transplantation of pieces from another mucous membrane into the conjunctival sac may be tried in order to replace the conjunctiva that has been destroyed.

Lupus Conjunctivæ.—Lupus of the skin sometimes is continued over the edges of the lids upon the conjunctiva. In this situation it appears as an ulcer, the bottom of which is covered with granulations in which tubercle bacilli can be made out. Lupus of the conjunctiva must therefore be regarded as a tuberculous disease, for which reason reference for further details must be made to the article on tuberculosis of the conjunctiva (§ 23).

In the case of other exanthemata, too, for instance in macular and papular syphilides, in pityriasis, psoriasis, herpes iris, lepra, etc., the conjunctiva is

sometimes characteristically implicated. In lepra, nodules generally develop near the margin of the cornea, and subsequently grow down into the subjacent sclera and also upon the cornea; when upon the latter they not infrequently have the appearance of a new growth. There is an associated iritis sometimes combined with the formation of lepra nodules in the iris. The nodules in the different parts of the eye finally break down, and the eye is lost.

Amyloid Degeneration of the Conjunctiva.—This rare disease has hitherto been observed only in Russia and the countries adjacent, and was first described by Oettingen in Dorpat. It consists in a peculiar degeneration of the conjunctiva, by reason of which the latter becomes yellowish, translucent like wax, non-vascular, and very friable. With this there is associated a considerable thickening of the membrane, so that it forms large swellings which look like new growths. The affection begins in the fold of transition, and from this passes over to the conjunctiva of the eyeball and of the lids; in the lids the tarsus also is subsequently implicated in the degeneration. In a case that has lasted a long time the following clinical picture is found: The patient can not open the eye because the two lids, transformed into large, misshapen swellings, cover it up. If the lids are drawn as far apart as possible, the wax-like conjunctiva is seen rising up under the form of a rigid prominence all about the cornea, which latter is either clear or is covered by pannus. Thick swellings, belonging to the fold of transition, protrude between the lids and the eyeball; the plica semilunaris also is enlarged until it forms a misshapen mass. These various swellings are so friable that they often tear when an attempt is made simply to separate the lids for examination, although in so doing they bleed very little. The disease runs a very chronic course, dragging on for years without any real inflammatory symptoms, until at length the patient is deprived of the use of his eyes by his inability to open the misshapen lids.

Microscopic examination has shown that the degeneration of the conjunctiva originates from the subconjunctival cellular tissue. This at first is found to be very abundantly infiltrated with cells (adenoid proliferation); then hyaline, followed by amyloid, degeneration of the tissue elements sets in in the altered mucous membrane (Raehlmann). In doubtful cases the chemical reaction of amyloid renders the diagnosis certain. Finally, calcification or ossification may take place in the degenerated mucous membrane.

The disease attacks people in middle life, and ordinarily both eyes are affected. Very frequently amyloid degeneration is preceded by trachoma of the conjunctiva, which, however, should not be regarded as the cause of the affection, inasmuch as the latter can develop in eyes that previously were healthy. The actual cause of the disease is not known. In every instance it is a purely local process, for the individuals attacked by it are sound as far as the rest of the body is concerned, and do not suffer from amyloid degeneration of the internal organs, with which, therefore, amyloid degeneration of the conjunctiva has nothing at all to do.

Medical treatment is powerless against this disease. We must confine ourselves to removing the growths upon the conjunctiva to such an extent that the lids can be opened and vision thus rendered possible. It is by no means necessary, indeed it is not at all advisable, to remove by a radical operation all the diseased parts, since the portion of the growth that is left behind generally atrophies of itself afterward.

IX. Injuries of the Conjunctiva.

22. The following varieties of injuries of the conjunctiva, which are of such frequent occurrence, are observed:

(*a*) *Foreign bodies* in the conjunctival sac. Small-sized foreign bodies, like grains of dust, particles of coal or of ashes, which so often get into the eye during a railroad journey, the wing-cases of small beetles, etc., fall first upon the surface of the eyeball, are brushed away from this spot by the movements of the upper lid, and then generally stick to the inner surface of the latter at a spot not far from its free border, where a shallow furrow, the sulcus subtarsalis, runs parallel to the edge of the lid and catches the foreign body. The pain which such a foreign body causes, and which is often quite considerable, does not originate in the conjunctiva itself, which has very little sensitiveness, but in the cornea, inasmuch as with every movement of the lid the foreign body is carried over the cornea and scrapes it. Hence the pain is absent as long as the eye is kept quietly closed. It is easy to remove the foreign body after the lid is everted.

In other cases, small, sharp-pointed foreign bodies penetrate into the conjunctiva, and may remain there a long time. Grains of powder remain fixed in the conjunctiva of the eyeball without giving rise to any further irritation, and may, therefore, be left in the conjunctiva. Larger-sized foreign bodies are retained in the conjunctival sac only when they get into the upper fold of transition. In this spot they stay, remaining still even during the act of winking, cause no irritation of the cornea, and therefore produce but little trouble. After some time has elapsed they begin to excite the symptoms of chronic conjunctival catarrh.

(*b*) *Solutions of continuity* of the conjunctiva are not rare, and often associated with extensive infiltration of blood (ecchymosis). If the edges of the wound are not too greatly lacerated, the conjunctival wound can be closed with a stitch.

(*c*) *Burns* of the conjunctiva and *injuries by caustics* are pretty frequent. Burns are the result of hot water or steam, hot ashes (especially cigar-ashes), exploding powder, flames striking against the eye, molten metal, etc. Of the injuries by caustics, which may be produced both by acids and by alkalies, those that arise from the action of lime are the most frequent, the lime getting into the eye usually under the form of mortar.

The action of burns is the same as that of caustics; the conjunctiva at the affected spots is destroyed and converted into an eschar. These spots stand out as gray or white patches in the midst of the reddened and swollen portions of the conjunctiva that are not escharotic. The eschars separate in consequence of a delimiting suppuration, and the resultant granulating losses of substance in the conjunc-

tiva heal by a drawing in over them of the neighboring healthy conjunctiva. The final result is, therefore, always the formation of a cicatrix. This can lead to a diminution in size of the conjunctival sac, or, if of great extent, to adhesion of the lids to the eyeball (symblepharon).

The *prognosis* of an injury by burns or caustics with regard to the preservation of sight, depends primarily upon the condition of the cornea, which, indeed, is always simultaneously affected when there is an extensive lesion of the conjunctiva.

Next, although of secondary consequence, the losses of substance in the conjunctiva itself must be considered, inasmuch as the adhesions that develop from them may cause subsequently more or less disturbance of the function of the eye.

The prime *therapeutic* requisite, when we get an eye under treatment a short time after it has been injured by caustics, is the complete removal of any corrosive substance that may still be present. We remove solid particles with a pledget of linen or with a forceps, and then wash the conjunctival sac out thoroughly. For this latter purpose we use, as far as possible, such solutions as shall neutralize the corrosive substance or render it insoluble, and so put a stop to its injurious action. In the case of caustic alkalies we do not use water, but milk. In burns produced by lime our best plan is to wash the eye out with oil and afterward to drop in a concentrated solution of sugar, since cane-sugar forms with lime an insoluble compound.

In the further course of an injury produced by burns or caustics, it is incumbent upon us to restrain the subsequent inflammation by means of cold compresses, atropine, the application of a bandage, etc. After the separation of the eschars, our aim must be to confine the resulting adhesions within the smallest possible limits. For this purpose we repeatedly draw the lids away from the eyeball in order to prevent the adhesion of the two opposite raw surfaces. If the loss of substance extends so far as to implicate the fold of transition, an adhesion between the lid and eyeball, starting from the fornix (symblepharon posterius), can not in any way be avoided. Such an adhesion must be removed, as far as can be done, afterward, by operative measures.

Sometimes foreign bodies are introduced into the eye purposely. Chief among those thus used are what are called crab's-eyes—the *lapides cancrorum*. These are flat, calcareous concretions derived from the stomach of the crab, which are in great favor among the laity as a means of removing foreign bodies from the eye. The crab's-eye is introduced between the lid and the eyeball, and then is pushed across the cornea, carrying with it, it may be, mechanically any foreign body that may be there.* Sometimes it happens in the perform-

[* In this country eye-stones (the flat opercula of certain Mollusca) are used for the same purpose.—D.]

ance of this manipulation that the crab's eye slips into the superior fornix and remains there unnoticed. We may then find it there months or even years afterward, entirely imbedded in the outgrowths of the conjunctiva, which has undergone chronic inflammation. Foreign bodies, such as sand, ashes, and the like, are also intentionally introduced, for the purpose of simulating an eye disease, into the eye, where they set up a conjunctival catarrh.

After the action upon the eye of irritant substances, consisting either of acrid vapors or of liquids which are injected into it, an acute traumatic conjunctivitis is produced, evidenced by intense reddening of the conjunctiva with great photophobia, lachrymation, and pain, with which is associated in violent cases an œdematous swelling of the lids. A similar picture is presented by that variety of conjunctivitis which occurs after the action of intense light upon the eye, as, for example, after dazzling by the reflection from snow (snow-blindness), or by the electric arc-light. In violent cases of this sort there are found, besides the inflammation of the conjunctiva, contraction of the pupil and also slight opacities and erosions of the cornea. These symptoms, like the erythema of the skin occurring as a result of insolation, are produced by the action of the ultra-violet, chemically active light-rays (Widmark). These cases of traumatic conjunctivitis, in spite of the violent symptoms which they present in their beginning, generally get well within a few days without further bad results.

X. Ulcers of the Conjunctiva.

23. Among the morbid processes which lead to the formation of ulcers upon the conjunctiva, *tuberculosis* of the conjunctiva requires special mention. Tuberculous ulcers are located as a rule in the tarsal conjunctiva. The diseased lid even on external inspection looks thickened. In everting the lid there appears upon its conjunctival surface an ulcer which is either covered by grayish-red granulations, or has a yellowish-red, lardaceous-looking base. In its vicinity small gray nodules (tubercle nodules) are often found in the conjunctiva. The ulcer shows no disposition to heal; on the contrary, it spreads, although it does so very slowly. It may pass over to the conjunctiva of the eyeball; and even the cornea is sometimes covered over by a sort of pannus. In especially severe cases the ulcer does not remain confined to the conjunctiva, but eats through the entire thickness of the lid, so that even on external examination a deficiency of tissue is observable in the lid. Quite early in the disease the lymphatic gland in front of the ear becomes swollen; afterward, the lymphatic glands about the lower jaw and in the neck also become enlarged. The clinical picture afforded by the disease is thus pretty characteristic, although the diagnosis is to be considered as established only when fragments of tissue have been removed from the ulcer, and tubercle bacilli have been proved by the ordinary methods to exist in them.

Tuberculosis of the conjunctiva generally attacks only one eye. The patient does not suffer pain; it is only by the swelling of the lid, the purulent secretion, and subsequently by the diminution of visual

power, that he is annoyed and made aware of the existence of his trouble. The disease occurs, almost without exception, in young people, and runs an uncommonly chronic course, being often protracted over many years. Even after an apparently radical cure it shows a great tendency to recur, and it can, by infecting the rest of the organism, finally lead to the patient's death from tuberculosis. The treatment in the cases where a complete removal of all the diseased parts seems still possible, consists in the radical excision or curetting of the ulcer with a subsequent thorough cauterization of the raw surface. The wounds made by the operation are strewn every day until they are completely healed with finely powdered iodoform, a remedy which just in tuberculous processes proves to be of particular efficacy.

Tuberculosis and *lupus* of the conjunctiva are to be looked upon as affections which are identical in their essential character, in so far as both represent ulcerative processes which are produced and maintained by the presence of tubercle bacilli. In fact, the first cases of tuberculous ulcers of the conjunctiva were described as primary lupus of the conjunctiva (that is, lupus of the conjunctiva without any coincident lupus of the skin) (Arlt). The two processes are distinguished only by external points of difference relating to their outward aspect and their course. Thus, as a rule, lupous are distinguished from tuberculous ulcers of the conjunctiva by the fact that they have migrated from the skin to the conjunctiva, and that, like lupus of the skin, they show a spontaneous cicatrization on one side, while on the other the ulcer keeps advancing.

Tuberculosis of the conjunctiva may be primary or secondary. It is *primary* if no sign of tuberculosis is present in the rest of the body at the time when the affection of the conjunctiva begins. In that case tuberculosis of the conjunctiva represents a purely local affection which has, without doubt, been excited by direct infection of the conjunctiva. A particle of dust containing bacilli gets into the conjunctival sac, and with its sharp angles produces a small superficial lesion of the conjunctiva which is thus infected (tubercle bacilli not penetrating into the conjunctiva when the epithelium is intact, according to the researches of Valude). In favor of an infection of this sort is the fact that we see tuberculous ulcers so frequently beginning in the region of the sulcus subtarsalis, where small foreign bodies are most readily retained. Primary tuberculosis of the conjunctiva may remain for a long time confined to the latter; indeed, in exceptional cases it may even heal spontaneously; the rule, however, is for tuberculosis to spread from here to the other parts of the organism. This extension may take place by way of the lymphatic circulation, the neighboring lymph-glands becoming first affected with tuberculosis. Or, the disease may extend by continuity, the lachrymal passages first and subsequently the nasal mucous membrane being infected by means of the tears which contain bacilli.

Those cases of conjunctival tuberculosis are to be regarded as *secondary* in which either there is at the same time an evident tuberculosis of the internal organs (especially of the lungs), or in which tuberculosis is transmitted to the conjunctiva from places in its vicinity. A tuberculous affection of the nasal mucous membrane may be transferred to the conjunctiva by way of the lachrymal passages. Not infrequently, therefore, we find conjunctiva, lachrymal sac, and

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

nasal mucous membrane attacked at the same time by tuberculosis, and a careful study of the history of the case and an exact examination generally render it possible to make sure whether the affection has passed down from the conjunctiva to the nose or vice versa. It is of the greatest importance for the prognosis and treatment to determine whether tuberculosis is confined to the conjunctiva or not. In the former case we would regard the operation of removing thoroughly all the diseased parts as of very great value, since by it the patient may be permanently relieved of his tuberculosis; while in the second case a radical cure is not to be thought of.

Ulcers of the conjunctiva, besides occurring as a result of tuberculosis, are also observed in the following conjunctival affections:

(*a*) As one of the symptoms of a conjunctivitis, an example being the minute ulcers originating in the efflorescences of conjunctivitis lymphatica or those which have given its name to the pustular form of catarrh.

(*b*) After the separation of necrotic portions of the conjunctiva, as in diphtheria, or after burning of the conjunctiva with heat or caustics. Here belong also the eschars produced artificially by the use of too strong applications.

(*c*) As a result of exanthemata; ulcers, for instance, which are derived from a variolous pustule or from the rupture of a bulla of pemphigus upon the conjunctiva.

(*d*) Upon the tarsal conjunctiva there is quite often found a small raw spot, from which rises a little mass of granulations. Here we have to do with a chalazion which has broken through on the inner side of the lid. As a rule, a slender sound can be introduced through the granulations into the cavity of the chalazion.

(*e*) I have seen in some cases on the conjunctiva of the eyeball or the plica semilunaris, ulcers covered with a thick layer of pus, which were of acute origin. These were accompanied by violent inflammatory symptoms in the conjunctiva, and by swelling of the lids and of the lymph-gland in front of the ear, and were associated with quite considerable pain. It seems to me that these should be attributed to infection from without, produced perhaps by the stings of insects or by small infected foreign bodies.

(*f*) Ulcers which have developed from the breaking down of epitheliomata of the conjunctiva.

(*g*) Syphilitic ulcers. Generally we have here to do with those losses of substance which have arisen from the breaking down of an initial sclerosis. These, as a rule, are situated near the free border of the lids, but are also observed in the fold of transition and even in the conjunctiva of the eyeball. The transmission of syphilis appears to take place most frequently by kissing, and in small children also by the practice which many nurses have of moistening the agglutinated edges of the lids with saliva in order to open them. Occasionally, also, syphilitic ulcers have been observed, which were produced by the breaking down of gummata of the conjunctiva (Hirschberg). Syphilitic ulcers of the conjunctiva are among the greatest of rarities.

XI. Pterygium.

24. Symptoms and Course.—A pterygium is a triangular fold of mucous membrane which extends from the conjunctiva of the eyeball to the cornea, either at the inner or the outer side of the latter (Fig.

24). The apex of the triangle lies in the transparent portion of the cornea, and is solidly and immovably united to it. The base of the triangle spreads out in the conjunctiva of the eyeball, and passes into it without there being any sharp line of division between the two. The apex is called the head, the base the body, of the pterygium. The part that lies between the two and corresponds to the margin of the cornea is the neck of the pterygium. Here the limits of the fold of conjunctiva are the most sharply defined, as its borders are rounded in in such a way that a small sound (*S*, Fig. 24) can be pushed beneath them for a short distance. A pterygium of recent origin is succulent, and abounds in vessels which run converging from the base to the apex and impart to the pterygium its red color. In fact, from its similarity in form and vascularity (venation) to the wings of many insects (*Hymenoptera*), the name of pterygium is derived.* The fold of conjunctiva forming the pterygium is tightly stretched, so that there are produced a number of radially disposed furrows or flutings; furthermore, in pterygia which are situated at the inner side of the eye, the plica semilunaris is often quite obliterated and is included in the body of the pterygium (Fig. 24).



FIG. 24.—PTERYGIUM.

A sound, *S*, is carried beneath the edge of the pterygium, *P*. The dotted line shows the way in which the section is made in removing the pterygium. *C*, caruncle. The adjacent plica semilunaris has been flattened out by the tensive force of the pterygium, and is hence invisible. *P*, upper punctum lacrimale.

A pterygium pushes its way quite slowly, with moderate symptoms of irritation, toward the center of the cornea, which, in the course of months or years, it may finally reach or even pass (*progressive pterygium*). Finally, the pterygium comes to a standstill; it grows paler by the gradual disappearance of its vessels, until it is at last converted into a thin, white, tendinous-looking membrane (*stationary pterygium*). It is particularly important on therapeutic grounds to distinguish sharply between these two stages—i. e., the progressive and the retrogressive stages in the development of pterygium: a progressive pterygium is thick, very vascular, and consequently red; a retrogressive pterygium is thin, pale, nearly devoid of vessels, and tendinous.

Pterygium occurs only in elderly people.† It is found most frequently on the inner side of the cornea; when there is one in this spot already, another may form on the outer side also. The two pterygia

* From [πτερύγιον, the diminutive of] πτέρυξ, a wing.

† [But, in this country at least, is sometimes found in comparatively young people.—D.]

may even meet in the center of the cornea. A genuine pterygium is practically never observed at the upper or the lower margin of the cornea; on the other hand, it is not infrequently the case that both eyes are attacked simultaneously by pterygium, so that we sometimes see patients who have four pterygia, one on the outer and one on the inner side of either cornea.

Among the injurious results which a pterygium entails the worst is the damage done to the eyesight. This begins to be produced as soon as the point of the pterygium projects into the pupillary area of the cornea, and it increases in proportion as the point approaches the center of the latter. Moreover, in the progressive stage, pterygium is associated with a condition of constant irritation in the eye; and, in addition, the red membrane forms a striking disfigurement and can also cause a restriction of the mobility of the eye. If, for example, a pterygium is situated on the inner side of the cornea and the eye is meant to be turned strongly outward, the eye may be restrained in its movement by the tension of the pterygium, and therefore fail to move laterally as far as the other or healthy eye, so that binocular diplopia may be produced in consequence of this faulty placing.

A stationary pterygium, which is small and does not extend to the pupillary area of the cornea, does not entail any serious disadvantages to the person who has it. Stationary pterygia of larger size cause, like progressive pterygia, disturbance of vision and restriction of the mobility of the eye.

Etiology.—A pterygium is nothing but a fold of conjunctiva drawn up over the cornea and fastened to it. It originates from the pinguecula, the degenerative process which exists there making its way into the limbus and then gradually upon the cornea itself. The pinguecula, therefore, grows up, as it were, over the cornea, and in so doing draws the conjunctiva after it. The advancing degeneration can be recognized at the apex of a recent pterygium as a narrow, gray, non-vascular, gelatinous-looking zone, which forms the anterior border of the pterygium, and is quite sharply separated from the transparent cornea. Since the pterygium originates in the pinguecula, it is evident why, like the latter, it should occur only at the inner and outer margins of the cornea. And as the pinguecula develops in consequence of the injurious influences which the conjunctiva in the region of the palpebral fissure is exposed to in the course of years, the like is true of pterygium and in a still greater degree. Hence it is found only in elderly people, and in them especially when they are much exposed to wind or dust, as in the case of country people, coachmen, masons, stone-cutters, etc.; while among the well-to-do classes pterygium belongs among the rarities. The forcible traction which the conjunctiva exerts upon the cornea explains the triangular form of the fold, its incurved margin, and its great tension in a horizontal direction.

Treatment.—The treatment of pterygium consists in its ablation by Arlt's method. With a toothed forceps we grasp the pterygium at its neck, where the incurving of its margin permits it to be partially lifted from its bed. Starting from this point we carefully dissect off the head from the cornea, upon which it lies, keeping close to the line of division between the tissue of the pterygium and the cornea. When the whole of the head as far as the limbus has been separated from the cornea, we circumscribe this segment by carrying from the upper and lower margins of the neck two converging incisions into the body of the pterygium (the dotted line, Fig. 24). In this way a rhomboidal piece, containing the head and part of the body, is excised and a raw surface remains, one portion of which lies in the cornea, the other in the conjunctiva of the eyeball. This last is covered by uniting the upper and lower margins of the section by means of one or two interrupted sutures. The wound in the cornea heals by a cicatrix forming over it, in consequence of which a permanent opacity remains. Care in sewing up the conjunctival wound is of the greatest importance, especially in the neighborhood of the limbus, as otherwise the conjunctiva grows anew over the raw surface of the cornea, and thus the pterygium recurs.

Ablation is indicated in every case of progressive pterygium. Even though the pterygium is still small, we can not be sure that it will not grow on into the pupillary area of the cornea. Hence we prefer by performing ablation to guard in time against injury to the eyesight. If the pterygium has approached sufficiently near the center of the cornea to cause disturbance of vision, this disturbance is indeed rendered less by the operation of ablation, but is not completely done away with, since those spots of the cornea, which were occupied by the pterygium, never again become perfectly transparent. In any case, the associated symptoms of irritation, the restriction of mobility, and the disfigurement are removed by the ablation. A stationary pterygium does not necessarily require ablation; in this case we shall be guided mainly by the wishes of the patient with reference to the removal of the disfigurement, etc.

The older writers distinguished a pterygium crassum (vasculosum, carnosum, sarcomatosum) and a pterygium tenue (membranaceum). The former corresponds to the progressive, the latter to the retrogressive pterygium. These designations in fact do not refer to different varieties of pterygium, but to different stages of the same pterygium. A pterygium has been shown to be histologically identical with the conjunctiva of the eyeball, of which indeed it is only a projecting fold. In consists mainly of fibrillar connective tissue, which, as far as the apex, is covered with the epithelium of the conjunctiva. Imbedded in the tissue of the pterygium are found spots which indicate the degenerative process that is the characteristic feature of the pinguecula. Bowman's membrane, in the place where the pterygium covers the cornea, is de-

stroyed; indeed, the uppermost lamellæ of the cornea even are replaced here and there by the tissue of the pterygium. This explains why, even after the ablation of the pterygium, the cornea does not regain its normal transparency.

Arlt deserves the credit of having made the operation for pterygium a success by demonstrating the necessity of closing the conjunctival wound. Previously people had been satisfied with simple ablation, and had so frequently had recurrences after this operation, that with many it had altogether fallen into disrepute. In very broad pterygia it is difficult or impossible to unite the edges of the conjunctival wound by a suture. In that case liberating incisions are made through the adjacent conjunctiva in order to facilitate the process of drawing it down; and, instead of cutting off the point of the pterygium, it may be sewed into the gaps which have been made by the liberating incisions. For patients who are afraid of the knife, Pzokalski has proposed a method of ligating the pterygium.

Pseudo-pterygium (Cicatricial Pterygium).—Sometimes we observe, as a result of inflammatory processes, a fixation of a fold of conjunctiva upon the cornea, giving a picture similar to that of true pterygium. For example, there may be an acute blennorrhœa of the conjunctiva, with great chemosis, and a pretty large marginal ulcer of the cornea. The chemotic protuberance of the conjunctiva becomes applied to the surface of the ulcer and adheres to it. After the inflammation has abated, the swelling of the conjunctiva goes down, the chemotic protuberance disappears; but, in the spot where union of the cornea has taken place, the conjunctiva remains permanently fixed to the latter. We then see a triangular fold formed of conjunctiva extending over the limbus and upon the cornea, and attaching itself there. Ordinarily, at that part of the fold corresponding to the limbus a fine sound can be passed all the way beneath the fold; a sign that the latter is adherent to its bed at its apex only and not throughout its whole extent. Such a pseudo-pterygium is distinguished from a genuine pterygium in that the conjunctiva is adherent to one definite spot upon the cornea, and remains steadily fixed in that spot, and hence in its subsequent course grows neither larger nor smaller. In a genuine pterygium, on the other hand, the conjunctiva is drawn gradually farther and farther up upon the cornea; it has its progressive stage. In its origin and its behavior a pseudo-pterygium is more like a symblepharon than a genuine pterygium.

Pseudo-pterygia are observed not only after acute blennorrhœa, but also after diphtheria, burning by heat and by caustics, the occurrence of prolapse of the iris, the removal of new growths, etc. It is evident that they may develop not only at the outer and inner sides, but at any side whatever of the cornea. The pseudo-pterygia remaining after acute blennorrhœa are usually found above, those produced by burns, etc., most frequently at the lower part of the cornea (the region corresponding to the palpebral fissure).

Small pseudo-pterygia may without disadvantage be left undisturbed; larger ones we generally remove in the same way as genuine pterygia, and unite with stitches the wounds left in the conjunctiva. In those cases in which the pseudo-pterygium is not adherent to the surface of the eyeball at the spot corresponding to the limbus, ablation and the use of the suture may be dispensed with; it is sufficient simply to free the point of the pseudo-pterygium from the cornea, upon doing which the former retracts of itself and disappears by a process of atrophy.

It sometimes happens that an old pannus which has already been trans-

formed into connective tissue, is united to the subjacent cornea only by loose cellular tissue, and thus acquires a certain freedom of movement so that it can be shifted this way and that upon its bed along with the conjunctiva of the eyeball. In this way too, then, a picture similar to that of a pterygium may be produced.

XII. Symblepharon.

25. Symptoms.—By symblepharon * we understand a cicatricial adhesion between the conjunctiva of the lids and the conjunctiva of the eyeball. In that case, when we attempt to draw the lid away from the eyeball, we observe that in one or more places bands extend from the inner surface of the lid to the surface of the eyeball, and that these become tightly stretched and prevent us from drawing the lid away completely. These bands generally look tendinous, more rarely fleshy, and may be attached not only to the conjunctiva scleræ, but also to the surface of the cornea itself. If the adhesion between the two conjunctival surfaces extends so far peripherally as to reach into the fornix, we call this *symblepharon posterius*. If the adhesion does not extend as far as this, so that the cicatricial bands stretch like a bridge between the lid and the eyeball, and we can introduce a sound beneath them and carry it along the fornix between the lid and the globe, it is then called *symblepharon anterius*. This distinction has been established for practical reasons, inasmuch as symblepharon anterius can be readily cured by an operation, symblepharon posterius can be cured with difficulty or not at all. *Symblepharon totale* is a total adhesion between the lids and the eyeball—a condition which occurs but rarely.

Etiology.—Symblepharon develops whenever two opposed spots of the conjunctiva of the lid and of the eyeball have raw surfaces which come into contact with each other, and in consequence become adherent. Such a process of adhesion results of necessity when the two raw surfaces extend up into the fornix and there pass into each other, since two raw surfaces which meet at an acute angle always begin to unite at this angle of junction. Causes which can give rise to the formation of raw surfaces upon the conjunctiva are burns by the action of heat, burns from caustic substances, diphtheria, operations, ulcers of all kinds, etc.

The expression symblepharon is also employed in a somewhat different sense to denote the contraction of the conjunctiva which occurs as a result of its gradual *shrinking*, as, for instance, after trachoma (see page 65). In this case it is not a question of an adhesion between two raw conjunctival surfaces, but of a gradual diminution in size of the conjunctival sac. The folds of the region of transition are first smoothed out; the conjunctiva of the lid extends directly to the eyeball (f_1, Fig. 19 B) and, whenever the lid is drawn away, is tightly

* From *σύν*, together, and *βλέφαρον*, eyelid.

drawn out into transversely disposed folds. In advanced cases the conjunctival sac is converted into quite a shallow grove between the eyeball and the lid. Since contraction of the conjunctival surface in consequence of shrinking always makes itself first apparent by disappearance of the fold of transition, all these cases belong to symblepharon posterius. This kind of symblepharon is observed principally after trachoma; furthermore, in the rare cases of pemphigus of the conjunctiva.

Very light cases of symblepharon produce no bad *results* worth mentioning. When there are more pronounced adhesions, the excursions of the eye are hindered, and thus, in any case, diplopia may be produced just as in the case of pterygium. Inasmuch as with the movements of the eye traction is made at the site of the adhesions, the eye gets to be in an irritated condition. If the adhesions extend into the region of the palpebral fissure they become disfiguring, and if they extend as far as the cornea they may injuriously affect the sight. Sometimes the lids are so fastened down by extensive adhesions that their complete closure is impossible, and lagophthalmus is produced with its consequences that are so baneful to the cornea. Total symblepharon is obviously associated with complete blindness (or at most with quantitative perception of light).

Treatment.—This involves an operation. Cases of *symblepharon anterius* are easily cured. We separate the adhesions between the lid and eyeball with great care, so as not to cut into the sclera nor the tarsus. When the lid has been set free, we must then make it our business to prevent a readhesion of the freshly made raw surfaces, and to make each of these cicatrize by itself. This is effected by repeatedly drawing the lid away from the eyeball, and also by interposing a pledget dipped in oil or smeared with ointment between the lid and the eye.

In *symblepharon posterius* we also begin by separating the adhesions as far back as the fornix. But if we should content ourselves with doing this, a reunion of the recently made raw surfaces would result, starting from the fornix where these surfaces come together. In order to avoid this, one of the raw surfaces must be covered with conjunctiva, so that a place coated with epithelium lies opposite to the raw surface remaining. The wound on the eyeball is the one we select for covering over, because the conjunctiva of the eyeball can readily be displaced, while the conjunctiva of the lid is adherent immovably to the tarsus. We loosen the conjunctiva of the eyeball on both sides of the wound, draw it down over the latter, and unite it by sutures. Especial care must be devoted to uniting the wound in the neighborhood of the fornix. If, after dividing the adhesions, the raw surface upon the eyeball is so large that it can not possibly be covered by conjunctiva, reunion of the symblepharon will result in every case. Hence,

cases of extensive symblepharon posterius, and evidently cases also of symblepharon totale, are incurable. The same is true of symblepharon induced by the gradual shrinking of the conjunctiva.

We sometimes also operate for symblepharon in cases in which the eye has been rendered blind and is shriveled up, for the purpose of making possible the introduction of an artificial eye.

Different methods have been devised to enable us to operate for cases of symblepharon posterius with extensive adhesion. Himly, in an operation analogous to that for syndactylism, first made a preliminary perforation of the adhesion along the fornix, and carried a lead wire through the canal so formed. The latter, after the wire has been in it a pretty long time, becomes covered with epithelium (like the canal made by piercing the lobule of the ear for earrings), so that the symblepharon posterius is changed into a symblepharon anterius, and can be operated upon, like the latter, by simply separating the adhesion. Some have attempted to cover a large loss of substance upon the eyeball, caused by the removal of a symblepharon, by making the conjunctiva that is to be drawn up over it movable by means of liberating incisions, or by fashioning pedicellate flaps out of conjunctiva and attaching them to the wound (Teale, Knapp). Others (Stellwag, Wolfe) have grafted non-pedicellate flaps formed out of bits of mucous membrane from other localities (the conjunctiva of the other eye, the mucous membrane of the lips, or that from the mouth or vagina, or even the mucous membrane of animals) upon the raw spot, and have obtained union. Others again, for covering a loss of substance, take the external skin either in the form of small flaps grafted upon the surface, or as pedicellate flaps which are thrust in between the eyeball and the lid through a fenestra cut through the latter (Kuhnt, Schnellen). Generally speaking, we are obliged to acknowledge that in extensive adhesions all methods have but scanty results to offer, since the symblepharon commonly returns on account of the subsequent shrinking of the conjunctiva.

XIII. Xerosis.

26. Symptoms.—Under the name of xerosis * conjunctivæ we designate an alteration of the conjunctiva, the essential character of which is that the latter is superficially dry and is not moistened by the lachrymal fluid. The surface of the conjunctiva at the xerotic spots is dry, shines like fat and is of whitish color, and looks either like epidermis, or as if it were covered with dried foam. In such places the conjunctiva is thicker, less pliable, and lies in stiff folds. The tears flow over the diseased spots without moistening them. An analogous change is also observed in the cornea, the surface of which looks dull, lusterless, and dry, while the parenchyma of the cornea at the same time is found to have lost its transparency (xerosis corneæ).

Etiology.—The cases in which xerosis is observed are divided into two groups. In the first, xerosis is the result of a local affection of the eye; in the second, it is an accompanying symptom of a general disease.

* From ξηρός, dry.

Xerosis *resulting from a local affection of the eye* is found:

(*a*) In *cicatricial degeneration* of the conjunctiva. It is observed most frequently as the final outcome of trachoma, and also, but more rarely, after diphtheria, pemphigus, burns, etc. It begins in isolated spots, but may ultimately spread over the entire conjunctiva, and over the cornea also. In the latter case, since the xerotic cornea grows opaque, the eye becomes blind. This form of xerosis is incurable.

(*b*) *Deficient sheltering* of the conjunctiva, so that the latter is constantly in contact with the air, can likewise lead to xerosis. This occurs in ectropion and in lagophthalmus (incomplete closure of the lid). In the former case the exposed portion of the tarsal conjunctiva, in the second case that part of the scleral conjunctiva and of the cornea lying in the course of the palpebral fissure, becomes covered with a thickened, dry, epidermoid epithelium, by means of which these parts protect, so to speak, their deeper layers against desiccation. In such cases assistance can be rendered only when it is possible (by operative interference) to provide the exposed conjunctiva or cornea with its normal shelter again.

Xerosis, *resulting from a general disease*, occurs under a light and a severe form:

(*a*) The *light* form is associated with hemeralopia (night-blindness). Simultaneously with the peculiar disturbance of vision (see § 105) there are found on the outer and inner side of the conjunctiva bulbi small triangular spots, which are covered with what resembles fine dried foam, and which are not moistened by the tears (Bitot). This form of the disease attacks adults.

(*b*) The *severe* form is associated with keratomalacia (see § 40). Here also xerosis makes its appearance first in the region of the conjunctiva corresponding to the palpebral fissure, but subsequently it spreads to the cornea, which breaks down into pus. The disease attacks children only, who often die with the symptoms of a severe general disease. It is conjectured that the light and the severe form are but different grades of one and the same disease, the essential nature of which is still unknown to us. The xerosis, which in these cases attacks a hitherto perfectly healthy conjunctiva and cornea, must be looked upon as a consequence of the disturbance of nutrition produced by the disease. Its particular importance to us, therefore, is as a symptom of this general affection, against which, accordingly, treatment must be particularly directed.

The separation, first made by Cohn, of xerosis into a variety dependent upon local causes and one caused by a general disease, corresponds nearly to the ordinary division into xerosis parenchymatosa and xerosis epithelialis. In local xerosis the mucous membrane is diseased in its deeper as well as in the superficial layers (xerosis parenchymatosa); while in xerosis produced by a general disturbance of nutrition the change affects the epithelium only (xerosis epithe-

lialis). Many also make a distinction between xerosis partialis (sive glabra) and xerosis totalis (sive squamosa).

The anatomical changes which form the basis of xerosis principally affect the epithelium. This becomes thickened, and hence whitish, cloudy, and epidermoid. Moreover, it assumes a fatty character, in consequence of which the lachrymal fluid does not adhere to it. To this circumstance the peculiar dry appearance is chiefly owing, for, if the diseased spots are freed from their fat by the application of soap, they become capable of being wetted by the tears (Leber). The fatty character is partly due to the fact that the thickened epithelium is covered by the sebaceous secretion produced by the Meibomian glands. But, in addition to this, the epithelial cells themselves fall a prey to adipose degeneration, so that we find them filled with a countless number of very minute drops of fat.

Kuschbert and Neisser have described as occurring in xerosis a special micro-organism, the bacillus of xerosis. This is found under the form of short rods adhering in great quantities to the surface of the epithelial cells. Whether it is really characteristic of xerosis of the conjunctiva is doubtful, since it has been found in the conjunctival secretion under other conditions as well. In any case, it can not be the special exciting cause of the disease; on the contrary, we must assume that coming from the air it gets upon the conjunctiva, and finds in the epithelium of the latter a soil favorable for its growth, whenever this epithelium has had its nutrition injuriously affected.

What part does the *lachrymal secretion* play in xerosis? The real cause of the dryness of the conjunctiva is not, as has been believed, the deficiency of tears. In the beginning of the disease, as long as only small isolated spots of the conjunctiva are xerotic, we often find actually an increase in the lachrymal secretion. Per contra, xerosis of the conjunctiva has never been known to occur after extirpation of the lachrymal gland. The real cause of the dryness of the conjunctiva is rather the fact that the tears do not adhere to it. Nevertheless it is true that in advanced xerosis the lachrymal secretion diminishes, and may even disappear altogether. As a cause of this phenomenon, Arlt has found in a case of xerosis obliteration of the efferent ducts of the lachrymal gland produced by the great shrinking of the conjunctiva; the lachrymal gland itself being diminished to one third of its normal volume and transformed into a tissue resembling fat. In that form of xerosis, also, which occurs in connection with keratomalacia, there is a striking deficiency in the lachrymal secretion; but here, probably, we have to do with a nervous disturbance—namely, with an absence of the reflex lachrymal secretion, due to depression of the general nutrition.

XIV. Extravasation of Serum and Blood beneath the Conjunctiva.

27. Œdema and also extravasation of blood, if of any great extent, are observed only in the conjunctiva of the eyeball and in the fold of transition, as these, on account of the laxity with which they are fixed to the subjacent parts, can be readily lifted up over quite large areas by fluid. The same thing does not occur in the conjunctiva tarsi, because it is too intimately adherent to the underlying cartilage.

In the conjunctiva of the eyeball we meet with both inflammatory œdema (œdema calidum) occurring in inflammations of the eyeball or the organs near it, and with non-inflammatory œdema (œdema frigidum) resulting from simple transudation of fluid. Since œdema, as a rule, is of importance merely as a symptom of some other affection, treatment will have to be directed to the latter. Should it be desirable to take any special measures against the œdema itself, the most suitable means for this purpose would be a pressure bandage, or, in the case of a tense œdema, scarification of the conjunctiva.

The exudation of blood beneath the conjunctiva of the eyeball is known as *ecchymoma subconjunctivale.* We then see a spot of varying extent and of a vivid-red or dark-red color; sometimes the whole conjunctiva scleræ is suffused with blood. Ecchymosis is easily distinguished from an inflammatory redness of the conjunctiva by its uniformly red coloration, in which no network of vessels can be recognized, and also by its sharp limitation from the unsuffused portions of the conjunctiva, which are ordinarily quite normal and uncolored.

Ecchymoses of the conjunctiva develop after injuries and operations upon the conjunctiva (particularly after squint operations), and, furthermore, in violent inflammations, especially in catarrhal ophthalmia. Spontaneous suffusions in an otherwise healthy conjunctiva are frequent in old people, whose blood-vessels have brittle walls, the rupture of the vessels being often occasioned by great bodily exertion, or by coughing, sneezing, vomiting, great straining, etc. In children, also, spontaneous ecchymoses of the conjunctiva are observed—chiefly after whooping-cough. A special symptomatic significance belongs to those ecchymoses which develop, to all appearance spontaneously, after an injury to the skull. Here we have to do with cases in which a fracture of the base of the skull has occurred, and the blood, as it escapes, gradually oozes forward through the orbit until it lodges beneath the conjunctiva (see § 133).

Subconjunctival ecchymoses become absorbed in from a few days to a few weeks without producing any further serious consequences, and in themselves require no treatment whatever. We generally prescribe compresses of lead-water, more for the purpose of appeasing the patient than of obtaining a more speedy resorption.

Inflammatory œdema is associated with the most various inflammatory affections, such as inflammations of the lids (erysipelas, hordeolum), of the margin of the orbit (periostitis), of the lachrymal sac (dacryocystitis), of the conjunctiva (particularly acute blennorrhœa), of the eyeball itself (purulent keratitis, irido-cyclitis, purulent chorioiditis, and panophthalmitis), and, furthermore, of structures posterior to the eyeball (tenonitis, phlegmon of the orbit). Inflammatory œdema, as also exudations of serum or of blood, is especially apt to occur in old people, whose conjunctiva is eminently extensible and so loosely attached that we observe œdema in this situation sometimes with trifling con-

junctival catarrhs. We commonly find the œdema most pronounced in the region of the palpebral fissure, because here the counter-pressure exerted by the lids is wanting; and not infrequently an œdematous fold of conjunctiva is found in the palpebral fissure, pinched off, so to speak, from the rest by the lids.

Non-inflammatory œdema is caused by hydræmia or by stasis. In the former case it occurs as a symptom of albuminuria, and sometimes then recurs a number of times, but each time rapidly disappears again (œdema fugax). A peculiar sort of œdema is the *filtration-œdema* of the conjunctiva of the eyeball. It is observed after operations or injuries which have produced a perforation in the most anterior sections of the sclera, and arises from the fact that the aqueous from the anterior chamber oozes between the incompletely closed edges of the wound and lodges under the conjunctiva. Accordingly, when cicatrization occurs, the œdema commonly disappears. But if a minute opening remains in the sclera, the œdema too persists—a condition which is designated as cystoid cicatrization (see Fig. 41). Œdema from filtration is found either in the region of the fistulous opening or in the lower part of the bulbar conjunctiva, the fluid sinking in obedience to gravity.

Not infrequently we see in the scleral conjunctiva small bright vesicles, arranged in a row like a string of pearls, or even joined so as to form longer sausage-like swellings. Here we have to do with dilated lymph-vessels that are filled with a clear liquid—that is, with *lymphatic ectasia*. These occur both in inflammation of the conjunctiva and also when the conjunctiva is perfectly healthy.

Ecchymoses of the conjunctiva, free from danger as they are, terrify the patient by their striking appearance, especially if, as is frequently the case, they spread still farther in the next few days after their first development. In these cases the pinguecula stands out with peculiar distinctness, as a bright, white, or yellowish spot upon the red substratum. On the side of the transparent cornea the ecchymosis is limited by a narrow gray border. This is the inner margin of the limbus, which is too closely adherent to the cornea to be lifted up by the blood. In eyes with blue iris, the latter often has its color apparently changed to green in the spot corresponding to the ecchymosis. This is caused by the extension of the blood in a very thin layer (in which it appears green) between the lamellæ of the cornea, so as to make the iris which lies behind it seem green.

The entrance of air beneath the conjunctiva of the eyeball (emphysema) is sometimes observed simultaneously with the escape of air beneath the skin of the lids or into the orbital tissue (see § 115).

XV. Tumors of the Conjunctiva.

28. Both malignant and benign tumors occur in the conjunctiva. The most important form of *benign* tumors is the

Dermoid Tumor.—This is a flat growth of solid consistence, which, so to speak, straddles the margin of the cornea, being situated partly in the conjunctiva and partly in the cornea, with which latter it is immovably connected. It most frequently occurs on the external (temporal) side of the cornea (Fig. 25). Its color is white or reddish, its surface epidermoid and often dry. It is sometimes covered with fine

down, or even with longer hair. Histological examination shows that the growth possesses the composition of the external skin; it consists of a stroma of connective tissue, covered with epidermis, and contains hair follicles, sebaceous glands, and sweat glands. It is, so to speak, an island of skin upon the surface of the eye ball.

FIG. 25.—DERMOID TUMOR OF THE CORNEA AND SUBCONJUNCTIVAL LIPOMA IN A THIRTEEN-YEAR-OLD GIRL.

The dermoid tumor is situated on the outer and lower margin of the cornea, lying to a small extent in the cornea, and more largely in the sclera. The eye has to be turned strongly inward in order to bring the lipoma well into view. The lipoma has a form differing from the ordinary one in that it consists of two lobules, and in addition sends out a process reaching to the outer margin of the cornea. It is everywhere covered by compact conjunctiva which resembles skin, but which nevertheless allows the yellow color of the underlying fat to show through.

Dermoid tumors are always congenital, and are frequently found along with other congenital anomalies, like congenital hare-lip or wart-like appendages of skin in front of the ears. Sometimes they grow still larger after birth. According to Remak, their development, as in the case of the allied dermoid cysts (see § 135), depends upon a fœtal invagination of the external germ-layer. On the other hand, Von Duyse conjectures that they owe their origin to a circumscribed adhesion between the amnion and the surface of the eyeball. The adhesion subsequently is drawn out into the form of a cord, and at length breaks quite in two, its point of attachment to the eye remaining behind as a dermoid tumor.

The chief harm that dermoids do is to produce a considerable disfigurement. If they are large, and especially if they are covered with hair, they cause mechanically an irritation of the eye, and also interfere with vision, in so far as they encroach upon the pupillary area of the cornea. They are removed by a simple process of ablation, which consists in separating the tumor as exactly as possible from the subjacent cornea and sclera. The resulting wound in the cornea should, as far as possible, be covered by drawing the adjacent conjunctiva over it. That portion of the cornea upon which the tumor was formerly situated remains clouded permanently. If remnants of the tumor have been left, the latter can in part form again.

Of *malignant* tumors, epithelioma and sarcoma of the conjunctiva occur. These originate ordinarily in the limbus conjunctivæ, and thence extend both into the conjunctiva and into the cornea.

Epithelioma of the conjunctiva forms a non-pigmented, flat, sessile tumor with a broad base. It remains for a long time confined to the superficial layers of the conjunctiva and cornea, its extension in the

latter often resembling a pannus. The tumor shows a great tendency to superficial ulceration.

The *sarcomata* that start from the limbus are generally pigmented (melano-sarcomata). In opposition to an epithelioma, they grow more in height than in breadth, and are attached to the substratum by only a slender base. They hence form dark-colored, very prominent mushroom-like growths, which often overlie a great part of the cornea, although, if we lift them up, we find the cornea beneath for the most part normal.

Both epitheliomata and sarcomata develop in advanced life, and, if they are not removed, spread steadily; sarcomata, especially, grow, until at length they form gigantic tumors. At last the patient succumbs from exhaustion, or from metastases which form in the internal organs. The tumors must therefore be removed as early and as radically as possible. As long as they are still quite small and superficial, radical removal can be performed with preservation of the eyeball. The tumor is removed as completely as possible, partly with the knife, partly with the sharp spoon, and the spot which it has occupied is thoroughly burnt with caustics, or, still better, with the actual cautery. If complete removal of the growth is no longer possible in this way, the eye, too, must be removed, even though it still possesses visual power.

Of *benign* growths, the following, although of rare occurrence, are also observed:

Lipoma subconjunctivale forms a tumor, situated upon the upper and outer circumference of the eyeball, between the rectus externus and rectus superior muscle, and appearing of a yellowish color as seen through the conjunctiva. It is of triangular form, the sharply defined base of the triangle looking toward the cornea, while the two sides of the triangle, which are directed to the outer side, pass gradually into the orbital fat. If the tumor is small it ordinarily remains concealed beneath the outer canthus, and can be brought into view only by turning the eye strongly inward (Fig. 25). Larger lipomata are visible in the palpebral fissure even when the gaze is directed straight forward, and hence cause disfigurement; but they do no other harm. Microscopical examination shows that the tumor consists of fat-lobules. The conjunctiva that coats it is thickened and of a character resembling that of the skin, and in this regard a lipoma is akin to the dermoids. Like the latter, it is congenital, but sometimes grows to a considerable size at the time of puberty. If it is desired to remove the tumor on account of the disfigurement it produces, we take away from it, after dividing the conjunctiva that covers it, as much of the mass of fat as is visible in the palpebral fissure; a radical removal of all the adipose tissue is unnecessary.

Cysts in the conjunctiva are commonly represented by small vesicles filled with a limpid liquid. Most of these vesicles, and particularly those situated upon the conjunctiva of the eyeball, originate from dilated lymph-vessels (see page 115). In the fold of transition, cysts occur which take their starting-point from Krause's glands of the conjunctiva; in addition, there are also cysts which develop in the conjunctiva from traumatism. Larger cysts situated beneath

the conjunctiva are formed by the cysticercus cellulosæ. The latter is observed for the most part in children or in the young. In such a case the conjunctiva at one particular spot is found permeated with vessels, and forms a nodular protuberance. Underneath may be felt the cyst which, as a rule, can be readily pushed about upon the subjacent parts; in individual cases, however, it is solidly adherent to the subjacent sclera or to one of the ocular muscles. If the cyst has very thin walls, the head of the worm can be recognized as a whitish spot in its interior. It is easy to remove the cysticercus by splitting up the conjunctiva and dissecting out the cyst, which consists of the cysticercus-vesicle inclosed in a capsule of connective tissue that has been formed about the animal.

Under the name of *polypi* of the conjunctiva we understand soft, rarely rather hard, outgrowths attached to the conjunctiva by a pedicle, and having a smooth surface covered with mucous membrane. These originate most frequently in the fold of transition or the conjunctiva of the lids. As a rule, they are so small as not to be disclosed until the lids are everted; sometimes, however, they are large enough to project out between the lids. Larger polypi are frequently ulcerated upon their surface, as a result of the mechanical injuries from which they necessarily suffer. In their nature polypi are small fibromata, which thrust the conjunctiva like a sac before them. This treatment consists in ablation and a subsequent cauterization of their base with the silver-nitrate stick.

Papillomata of the conjunctiva are frequently confounded with polypi, but are distinguished from them by their surface being not smooth, but papillary—that is, nodulated, like a raspberry or cauliflower. They are either provided with a pedicle or are sessile, having a broad base and extending in a flat layer over quite a large section of the conjunctiva. They start most frequently from the region of the caruncle, but can also take their origin from other portions of the conjunctiva, and sometimes several papillomata at once are present in different portions of the conjunctiva. They must be removed very thoroughly, since they are extremely prone to recur.

A third form of tumor, having an external resemblance to polypi of the conjunctiva, are the *granulation tumors*. These, like polypi, form small, mushroom-like, pedicled tumors. Unlike polypi, however, they are not covered by conjunctiva, but consist of naked granulation tissue. They develop in places where a loss of substance exists in the conjunctiva, whether as a result of ulcers (or even large efflorescences in cases of conjunctivitis lymphatica) or as a result of injuries or of operations (most frequently after tenotomies, at the site of the conjunctival wound, and, after enucleation, at the bottom of the conjunctival sac). In the case of chalazia, also, which have broken through the conjunctiva of the lids, we quite often see a granulation mass growing out of the opening. After existing for some time, granulation tumors become more and more constricted at their base by the cicatricial contraction of the surrounding conjunctiva, so that they ultimately fall off of themselves if they have not been previously removed.

The three varieties of tumors above mentioned are often very rich in dilated vessels; in fact, some cases of very vascular polypi have been described as pediculated angiomata of the conjunctiva. It is hence easy to conceive how these tumors can readily give rise to repeated hæmorrhages, especially if they are ulcerated in spots and are mechanically injured, as, for example, by the rubbing

of the lids upon them. Many legends of tears of blood that people have wept may be referred to this cause.

Angiomata of the conjunctiva are, as a rule, those which were originally situated in the lids and have gradually passed over upon the conjunctiva. Primary angiomata are of rare occurrence in the conjunctiva—generally being found in the region of the inner angle of the eye. They are as a rule congenital, and increase in size after birth. With regard to their treatment, see angiomata of the lids (§ 135).

As regards the *malignant tumors*, the epitheliomata and sarcomata, we must distinguish between those which originate in the surrounding structures, especially the lids, and secondarily pass over upon the conjunctiva, and those which are from the beginning situated upon the conjunctiva and are hence to be looked upon as primary conjunctival tumors. These latter originate mostly from the limbus. The predilection shown by epitheliomata for the boundary-line between the conjunctiva and cornea is to be considered as an analogue of the fact that, in other parts of the body also, epitheliomata occupy by preference those spots where one kind of epithelium passes into another, as, for instance, the boundary-line between skin and mucous membrane (anus, lips, margins of the lids, etc.). An additional factor giving rise to the development of epitheliomata at the limbus is probably furnished by the peculiar disposition of the epithelium at this spot, for we find here sometimes, even in the healthy eye, a proliferation of epithelium, in which the latter grows in the form of conical processes into the depth of the tissue.

Sarcomata of the conjunctiva are, as a rule, pigmented. Melanotic sarcomata, as is known, develop in those localities in which pigment is already normally present. They hence occur upon the conjunctiva of the lids, and most of all upon the limbus, two divisions of the conjunctiva, which even under physiological conditions contain pigment. At the limbus, particularly, the quantity of pigment contained is sometimes so considerable in persons of the brunette type that even with the naked eye we notice in it either separate dark-brown spots or a more uniform brown coloration. Spots of pigment occur sometimes also in other portions of the conjunctiva, both of the eyeball and of the lids, and from these spots melanotic sarcomata may subsequently develop.

It is impossible to make a radical removal of epibulbar epitheliomata and sarcomata and at the same time preserve the eye, in cases in which these tumors have so great an extent superficially that the conjunctiva has to be extensively sacrificed; for in that case there would occur as a result of the operation so extensive a formation of cicatricial tissue, with consequent distortion and fixation of the eyeball, that the latter would become unserviceable for purposes of vision, and it would have been better to have extirpated it at the beginning. So, also, the eyeball must be sacrificed in those cases in which the tumor grows down into the depth of the tissues at any one point—a thing which is especially apt to happen along the anterior ciliary vessels. Such an occurrence is often not discovered until after the removal of the superficial growth, or may even not be discovered at all. In the latter case a recurrence in the same locality occurs soon after the apparently radical removal. The following history serves to show the malignancy of these tumors which in the beginning are of such insignificant minuteness:

In the year 1879, a woman, fifty-seven years of age appeared in the eye-clinic, at that time directed by Arlt, having a melano-sarcoma on the right eye-

ball. This had developed from a minute red spot which had already existed fo a series of years, and which had begun growing larger the year before. It ha the dimensions of a large pea, was of reddish-brown color, and was situated i the conjunctiva on the outer side of the cornea. The base of the tumor pro jected from the limbus somewhat into the cornea, but nevertheless did not ex tend into the pupillary area, so that the visual power was perfectly normal. extirpated the tumor by cutting through the conjunctiva at a certain distanc from the edge of the tumor, and then removed the latter as carefully as possi ble from its base. The wound-surface thus formed, which lay for the mos part in the conjunctiva and to a smaller extent in the cornea, was scraped, an then the edges of the wound in the conjunctiva were united by means of suture. Healing followed by first intention, and for a time the patient re mained well. It was not till May, 1886—that is, seven years later—that th patient returned, having again an epibulbar melano-sarcoma on the right eye which, however, this time was situated on the limbus at the inner side of th cornea, and formed a brown tumor half the size of a lentil. The thin cicatri remaining from the first tumor was still present, quite unchanged, at the oute margin of the cornea; the limbus at the upper and lower margins of the corne also was quite normal. For this reason it was impossible to regard the melano sarcoma, now situated at the inner corneal margin, as a recurrence of the tumo removed seven years before from the external corneal margin. In fact, it coul only be referred to a disposition toward the formation of tumors, inherent in th limbus, so that after the removal of a tumor at one spot a similar one develope in another. (The same thing holds good for a case of epithelioma that I ob served, which developed simultaneously and quite independently in both eyes and in both at the inner margin of the cornea.) The small tumor was removed and the place where it had been situated was superficially cauterized with th galvano-cautery loop. Recurrences, however, followed this extirpation in rapi succession. Already four months later, in September, 1886, the woman re turned with a recurrent growth at the upper corneal margin, and upon th removal of this, after another four months, two nodules formed in the conjunc tiva to the inner and lower side of the corneal margin and at some distanc from it. In order the more certainly to remove everything that was diseased, resolved this time to enucleate the eye, although it was still serviceable fo purposes of vision. In spite of this, a solid nodule made its appearance, a early as six months later, at the bottom of the orbit. The woman put off un dertaking the removal of this, and did not come to the clinic until five month later. Meanwhile the glands in front of the ear, at the lower jaw, and on th anterior aspect of the neck, had become enlarged and could be readily felt Although now a radical operation, consisting of a complete exenteration of th orbit and the removal of all discoverable glands, was performed, neverthele only a few months afterward enlarged glands were again observed. Since the (in February, 1890) the woman has succumbed to an extension of the growth t the internal organs.

Fibromata, osteomata, myxomata, and lymphangiomata, although of ver rare occurrence, should also be mentioned as tumors of the conjunctiva.

The *plica semilunaris* and the *caruncle* which is situated upon it participat in the inflammations of the conjunctiva, so that it is unnecessary to treat of th

diseases of these parts separately. Sometimes the little hairs which the caruncle always has upon it are so long as to irritate the eye; in that case the hairs must be epilated. The new formations of the caruncle are designated by the old name encanthis; * benign new formations, such as simple polypoid or papillary outgrowths of the caruncle, are called encanthis benigna; malignant new formations are called encanthis maligna.

* From ἐν, in, and κανθός, angle of the eye.

CHAPTER II.

DISEASES OF THE CORNEA.

Anatomy.

29. The *cornea*, together with the sclera, represents the outer fibrous envelope of the eyeball, of which the cornea forms the transparent portion. Seen from in front, the cornea has the form of a horizontal ellipse, the horizontal diameter of its base, which is twelve millimetres, surpassing the vertical diameter, which is eleven millimetres. It is thinner in the center than at the edges, where its thickness amounts to about one millimetre. Hence it follows that the curvature of the posterior surface is somewhat greater than that of the anterior. The latter has a radius of curvature of 7·5 millimetres. Since the radius of curvature of the whole eye is greater—that is, amounts to twelve millimetres—the curvature of the cornea is greater than that of the rest of the eyeball; the cornea therefore is placed like a watch-crystal upon the sclera. The same comparison also obtains for the method in which the cornea is inserted into the sclera; for, in its posterior layers, the cornea extends farther toward the periphery than in the anterior, where the sclera, as it were, laps over the edge of the cornea (Fig. 17). The microscope, however, does not show any sharp boundary-line between cornea and sclera; on the contrary, the fibers of one pass continuously into those of the other.

The healthy cornea is transparent. Almost all morbid changes of the corneal tissue make themselves known at once by a diminution of this transparency. In advanced age, however, a cloudiness makes its appearance even in the healthy cornea (arcus senilis corneæ or gerontoxon *). This consists of a narrow gray line which runs near the corneal margin, and is concentric with it. It shows itself under the form of a gray arc, first at the upper, soon after at the lower, margin of the cornea; finally the two arcs unite at the outer and inner side of the cornea to form a closed ring. The outer boundary of the arcus senilis is sharply defined, and is separated from the limbus by a strip of perfectly clear cornea; on its inner aspect, or the one turned toward the center of the cornea, on the other hand, the cloudiness gradually shades away until it is lost in the transparent cornea. The cause of the opacity is a deposition of small concrements of a colloid substance in the upper layers of the cornea.

---

* From γέρων, an old man, and τόξον, bow.

The cornea consists of the following layers:

1. The *anterior epithelium* (Fig. 26, *E*). This is a pavement epithelium consisting of several layers; the lowermost cells (foot-cells, Fig. 23, *u*) are cylindrical, then follow rounded cells (Fig. 23, *m*), and finally flat cells (Fig. 23, *o*).

2. *Bowman's membrane* (Fig. 26, *B*). This is a thin, homogeneous membrane intimately connected with the lamellæ of the cornea lying beneath it. It may be said to represent the uppermost layer of the stroma of the cornea, which has become homogeneous and destitute of cells. From the epithelium it is separated by a sharply defined border; and, under pathological conditions as well as after death, the epithelium separates very readily from Bowman's membrane.

3. The *stroma* (Fig. 26, *S*). This is composed of a ground-substance and of cells. The ground-substance in its ultimate constitution consists of fine fibrillæ of connective tissue, united by a cement-substance into flat bundles. The bundles are so applied to one another that lamellæ (Fig. 26, *l*) are produced; by the arrangement of these lamellæ in layers one above another, the cornea is built up. The latter has, therefore, a lamellar structure. The individual lamellæ, however, are not sharply separated from each other, but are connected together by the interchange of bundles at frequent intervals. Hence, when we attempt to strip off the individual lamellæ of the cornea, we find that this can not be done smoothly, but only with the simultaneous laceration of the numerous connecting fibers.



FIG. 26.—CROSS-SECTION THROUGH A NORMAL CORNEA. MAGNIFIED 100 × 1.

E, anterior epithelium; *B*, Bowman's membrane; *S*, stroma, composed of the corneal lamellæ, *l*, and the corneal corpuscles, *K*; *D*, Descemet's membrane; *e*, posterior epithelium; *n*, nerves extending through the epithelium and Bowman's membrane.

In many places between the individual bundles of the cornea, and also between the lamellæ formed from the bundles, open spaces of greater or smaller size exist, which are filled with lymph and are hence called *lymph-spaces* (seen in surface-view in *l*, Fig. 27, and in

cross-section in *K*, Fig. 26). These are connected with one another by numerous minute canals (lymph-canals, Fig. 27, *C*), and in this way constitute a continuous system of hollow passages, or system of lymph-passages, permeating the cornea in every direction. This system is designed for the circulation of the lymph, and is of the greatest importance for the cornea, for, as the cornea does not possess any blood-vessels, it is forced to depend for its nourishment solely upon its system of lymph-passages.

The cells of the stroma of the cornea, the *corneal corpuscles*, are contained in the spaces of the lymph-system, and are of two kinds—non-motile and motile cells. The former are the *fixed corpuscles* of the cornea. They are cells with a large nucleus and a very flat, protoplasmic cell-body, and they lie in the lymph-spaces, to whose anterior or posterior wall they attach themselves (*P*, Fig. 27). Protoplasmic processes extend from their cell-body into the lymph-canals which start from the lymph-spaces. These processes anastomose with the processes of neighboring fixed corneal corpuscles, so that in this way there is formed a system of connected protoplasmic bodies (cells and their processes). We have thus in the cornea two connected systems—a positive one formed of protoplasm, and a negative one consisting of hollow passages (lymph-spaces and lymph-canals). The former system lies wholly within the latter, and, together with it, permeates the entire cornea. The protoplasmic system, however, nowhere completely fills the cavity of the system of passages; the space which is left unfilled is occupied by the circulating lymph.



FIG. 27.—LAMELLÆ OF THE CORNEA (SURFACE-VIEW). (AFTER WALDEYER.)

In contrast with the ground-substance, *g*, which is shaded in the drawing, are the light-colored lymph-spaces, *l*, connected with each other by the lymph-canals, *C*. Lying in the lymph-spaces, without entirely filling them, are the protoplasmic bodies (*P*) of the corneal corpuscles provided with the cell-nucleus, *K*.

The second variety of cells belonging to the stroma are the *motile corpuscles* of the cornea (wandering cells), which were discovered by Recklinghausen. These are nothing more than lymph-corpuscles which have made their way into the cornea, and which move about in its system of lymph-passages. In the normal cornea they are present in very small amount; but whenever any irritation acts upon the cornea they at once increase considerably in number, since they escape from the network of blood-vessels forming the marginal loops and pass into the cornea. These cells play an important part in inflammation of the cornea.

4. *Descemet's membrane* (*D*, Fig. 26) is a homogeneous, hyaloid membrane which forms the posterior boundary of the cornea. Unlike Bowman's membrane, it is quite sharply separated from the stroma of the cornea, from which also it is chemically different. It is very resistant to chemical reagents, and likewise to pathological processes going on in the cornea. When the entire stroma of the cornea has already broken down into pus, we often see the thin Descemet's membrane still for days offering resistance and remaining unimpaired (see § 35).

5. The *posterior epithelium* (endothelium, *e*, Fig. 26). This, under the form of a single layer of flattened cells, coats the posterior surface of Descemet's membrane.

The cornea at its margin abuts against three membranes, the conjunctiva, the sclera, and the uvea (iris and ciliary body). Embryology teaches us that the cornea consists of three superimposed layers, each of which corresponds to one of the membranes adjacent, and may be said to represent its continuation over the most anterior portion of the eyeball. The cornea hence consists of three divisions, a conjunctival, a scleral, and a uveal. According to Schwalbe, the anterior epithelium forms the conjunctival portion of the cornea (the so-called conjunctiva corneæ). Descemet's membrane, together with the posterior epithelium lining it, belongs to the uvea, while the entire stroma of the cornea, together with Bowman's membrane, represents the continuation of the sclera. In the fully developed eye these three divisions are fused into a common whole, although their community of origin with the adjacent membranes still finds expression under pathological conditions; the conjunctival division suffering most of all in diseases of the conjunctiva, the uveal division in diseases of the uvea.

The cornea contains no *vessels*. These cease at the margin of the cornea, forming there at the limbus the network of marginal loops, which is supplied by the anterior ciliary vessels (see page 34, and *q*, Fig. 17). From the marginal loops the blood-plasma passes over into the system of lymph-passages, by which the nutrition of the cornea is effected.

The *nerves* of the cornea arise partly from the ciliary nerves, partly from the nerves of the bulbar conjunctiva. They are very numerous, particularly in the uppermost layers of the stroma, from which the nerve-fibers pass forward through Bowman's membrane into the epithelium as far as the most anterior layers of the latter (Fig. 26, *n*). The cornea is therefore extremely sensitive to the touch. In the induction of narcosis the reflex that follows from touching the cornea (screwing together of the lids) is employed in order to test the depth of the narcosis, since this reflex is among those which are the last to disappear. Lesions of the cornea are particularly painful whenever they affect the uppermost layers which are so rich in nerves, as, for instance,

in the case of exfoliation of the epithelium, by which the numerous fibers of the epithelial plexus of nerves are laid bare.

While the cornea, viewed from in front, appears elliptical, it is circular, if looked at from behind. Hence the elliptical form of the front surface of the cornea is due to the fact that both sclera and conjunctiva overlap it farther above and below than at either side.

There is not yet perfect unanimity of opinion as to the division of the cornea into three layers. Waldeyer holds a different view from that represented in the text, regarding as the conjunctival portion the anterior epithelium, Bowman's membrane, and the most anterior of the lamellæ of the corneal stroma; the uveal portion would then be formed by the posterior epithelium, Descemet's membrane, and the most posterior of the lamellæ of the corneal stroma, so that only the middle lamellæ of the cornea would be left to form the scleral portion.

The older authors ascribed an important part in the nutrition of the cornea to the aqueous humor, which was supposed to be constantly soaking through it, and thus supply it with nourishment and provide for the maintenance of its transparency. From experiments, performed especially by Leber, this view must be considerably modified. An exchange of fluid between the parenchyma of the cornea and the aqueous humor is conceivable as occurring in two ways: by diffusion, which takes place only by means of diosmosis, and by the more rapid process of filtration, in which the fluid passes through comparatively large gaps in the tissue. The first sort of interchange—that, namely, by diffusion—is the only one that takes place in the healthy cornea; and the aqueous humor which gets into the cornea in this way may contribute to the nutrition of its posterior layers. Diffusion may also occur in the reverse direction—that is, from before backward. If, for instance, a solution of atropine is dropped upon the cornea, atropine is found a short time afterward in the aqueous humor. But interchange of fluids by filtration does not occur in the normal cornea. Leber has shown that it is the posterior epithelium which opposes the filtration of fluids. If this is removed, the aqueous humor penetrates in considerable quantity into the cornea, which in consequence becomes cloudy and swollen.

Clinical Examination of the Cornea.

30. An examination of the cornea must have regard to the following points:

1. The *size* and *form* of the cornea. Both may be altered either in consequence of congenital defects or because of morbid processes. Overlapping of the cornea by the limbus to an unusual extent, or the presence of marginal opacities in the cornea, not infrequently simulates a diminution in size or an irregularity of form.

2. The *surface* of the cornea must be examined with regard to its curvature, its evenness, and its polish. In respect to (*a*) the *curvature* of the cornea as a whole, marked anomalies are recognizable at the first glance; slighter changes, however, require more precise examination by means of the reflex images (see page 2). The cornea acts as a convex mirror, the greater the curvature of which the smaller is the reflected

image. In order to be able to judge whether the reflex image given by a particular cornea is of abnormal dimensions, we must compare it with the image reflected from another cornea which is healthy, and most conveniently with that from the cornea of the other eye, in case it is normal. The diagnosis is easy when the curvature varies at different portions of the same cornea (as, for instance, in keratoconus, in which the central portions have a greater curvature than those at the periphery). In such a case we cause the eye to move about in such a way that the reflection of a window opposite falls successively upon different portions of the cornea, and then we see the reflex image becoming larger or smaller according to the varying curvature of the cornea. The *evenness* (*b*) of the corneal surface, together with the perfection of its polish, gives to the normal cornea its brilliant luster. Here again the reflex images afford the best means of testing both of these properties. These images lose their regularity of form at the place where the cornea is uneven; they appear distorted, owing to their outlines being irregularly bowed in or out. The form and extent of the inequality may be deduced from the kind of distortion of the reflex image. By the ophthalmoscope, too, we can recognize inequalities of the corneal surface, on account of the irregular astigmatism which they produce (page 12). The uneven spots upon the corneal surface are either depressions (losses of substance) or elevations. Furthermore, the cornea may be uneven from being wrinkled (rhytidosis * corneæ) or from being entirely collapsed (collapsus corneæ). Both of these conditions occur in cases of great diminution in the tension of the eyeball, hence particularly after the escape of the aqueous or vitreous humors. If (*c*) the *polish* of the cornea is entirely lost, the latter becomes lusterless (dull); it looks like glass which has been breathed upon, or looks as if it had been smeared with grease. The reflex images show their normal size and form but have lost their sharp outline. Lack of luster of the cornea is also caused by the presence of inequalities so minute as to be nearly or quite imperceptible to the naked eye. Hence the cornea may be smooth as a whole, and yet at the same time dull, like the surface of ground glass. On making a careful inspection, especially with a magnifying glass, we can recognize two kinds of roughness upon the cornea, acting as a cause for its lack of luster. In one case we find merely minute depressions in the surface of the cornea, so that the latter looks as if it had been pricked with needles. This state of things arises from the fact that in many places isolated epithelial cells have fallen off, thus leaving minute depressions. In other cases we see the roughness of the cornea produced in the opposite way—that is, by its surface being covered with numerous small particles, in which case the cornea looks as if it were made of shagreen. Here we have to

* From ῥυτίς, a wrinkle.

do with multiple elevations, produced by a lifting up of the epithelium, and occurring under the form of minute vesicles.

3. The *transparency* of the cornea is a property which belongs to its parenchyma, not its surface; which latter, in fact, is only a mathematical concept, an expression for the superficial space bounding the cornea and lying between it and the air.

Dense opacities of the cornea are visible from a distance; but for the recognition of slight opacities, lateral illumination, and often also the use of the magnifying glass, are indispensable. By means of these aids to diagnosis we determine the form, extent, and denseness of the opacity. We make out whether it is found in the superficial or in the deep layers of the cornea, and further whether it is diffuse or is composed of separate small points, spots, or striæ. Many an opacity which appears diffuse when seen with the naked eye proves, when looked at with the magnifying glass, to be compounded of smaller opacities. Such an opacity may subsequently become really homogeneous by the enlargement and confluence of its components.

4. The *sensitiveness* of the cornea is tested by touching it with the end of a thread or a shred of paper. In many diseases the sensitiveness of the cornea is diminished, or is abolished altogether.

I. Inflammation of the Cornea.

General Statement.

31. In the course of an inflammation of the cornea (keratitis*) we observe the following *stages*. The inflammation begins with an *infiltrate* (Fig. 28). Cells in increased number make their appearance within the parenchyma of the cornea, and these constitute the exudate. As a consequence of this the diseased part loses its transparency. The level of the cornea remains normal at this spot, only the epithelium suffers to the extent of losing its polish, so that this portion of the cornea appears dull upon the surface. The clinical signs of the existence of an infiltrate hence are: cloudiness of the cornea, and loss of luster over the clouded portion, but no unevenness



Fig. 28.—Infiltrate in the Cornea. (After Saemisch.) The epithelium, *e*, and Bowman's membrane, *b*, over the infiltrate are preserved.

* From κέρας, horn.

of the surface. The subsequent fate of the infiltrate varies. It may go on to resorption or to suppuration.

(*a*) *Resorption* occurs in those cases in which the accumulation of exudate between the lamellæ of the cornea is not excessive, so that the lamellæ of the cornea are not broken down by reason of its presence, and hence there is nowhere produced any destruction of the tissue of the cornea itself. In this case the resorption of the exudate represents the second or regressive stage of the inflammation, and with it the morbid process comes to a conclusion. In favorable cases, when the cells constituting the exudate have disappeared by resorption, the diseased spots may become perfectly normal once more and regain their transparency (healing without permanent sequelæ—i. e., without opacities). But it may also happen that the stroma of the cornea may not be absolutely destroyed by the deposition of the exudate, and may yet have experienced such an alteration of its structure that, even after the disappearance of the exudate, it never again becomes perfectly transparent. Or it may be that the exudate deposited between the lamellæ of the cornea does not disappear completely by resorption, but in part becomes organized and is left permanently fixed in the cornea. In both of these cases the infiltrate disappears by a process of healing, but leaves a permanent opacity behind. All those cases in which resorption of the exudate occurs without breaking down of the corneal stroma are grouped together under the common name of *non-suppurative keratitis*.



FIG. 29.—CORNEAL ULCER IN THE PROGRESSIVE STAGE. (AFTER SAEMISCH.)

The base of the ulcer is formed by an accumulation of pus-cells, which also push their way some distance in between the lamellæ of the cornea that adjoin the ulcer. At the edges of the ulcer, which are somewhat raised, the epithelium, *e*, and Bowman's membrane, *b*, end as if cut short off.

(*b*) The infiltration goes on to *suppuration*, when the exudation is such as to be no longer compatible with the maintenance of life by the corneal stroma, so that the latter breaks down. The inflammation then enters upon its second stage, that of suppuration, which is associated with a localized destruction of the cornea. These cases of keratitis are known as *suppurative* keratitis. According as the suppuration starts in the superficial or in the deep layers, it develops under the form of an ulcer or of an abscess.

An *ulcer* of the cornea develops whenever the infiltration is greater in the superficial than in the deep layers, and when, consequently, the

process of purulent disintegration begins in the former (Fig. 29). In this way a superficial loss of substance is produced which is recognizable as a depression in the corneal surface. In the beginning, only those parts which are most markedly infiltrated, and hence are the first to break down, correspond to the loss of substance; and surrounding the latter are layers, which likewise are infiltrated with the exudate, although not to as high a degree. Hence both the floor and the walls of the ulcer are still infiltrated, for which reason we call it a *foul* (coated, infiltrated, or *progressive*) ulcer. Later on, the infiltrated portions forming the floor and the wall of the ulcer, so far as they are incapable of living, are also cast off; but those parts of the corneal tissue which have retained their ability to live remain, are freed by a process of resorption from the exudate which infiltrates them, and become once more transparent. The ulcer has, it is true, become somewhat larger



FIG. 30.—CORNEAL ULCER IN THE REGRESSIVE STAGE. (AFTER SAEMISCH.)
The base of the ulcer is formed by the denuded lamellæ of the cornea; a slight increase in the number of cells between them can still be made out. At the edges (*b*) of the ulcer the epithelium, *e*, is beginning to grow out over the base. Newly formed blood-vessels (*g*), lying in the upper layers of the cornea, run to the ulcer.

than before, but the cloudiness surrounding it has disappeared; the ulcer has acquired a smooth, transparent base and edges; it is a cleansed (*regressive*) ulcer (Fig. 30).

Among the clinical signs by which we diagnosticate an ulcer, the most important is the unevenness of the corneal surface, the latter presenting a depression or loss of substance. In foul ulcers this depression is surrounded by clouded corneal tissue, which, moreover, is dull upon its surface; the floor of the ulcer also is gray and uneven. In clean ulcers the cloudiness surrounding them is very slight, or is wanting altogether, and the floor and edges of the loss of substance are smooth and shining; the ulcer gives a mirror-like reflex.

An *abscess* is produced by the infiltration being greatest in the deeper layers, and by inducing purulent liquefaction of the corneal tissue first in this situation. For example, the infiltrate represented in

Fig. 28, if it should increase to the point of producing purulent liquefaction of the corneal tissue, would form an abscess. An abscess is therefore a focus of pus in the cornea, shut in behind and in front by layers of the cornea which have not broken down (Fig. 31, *a*). The clinical signs of a recent abscess consist in an opacity of the cornea, having the yellow color of pus, corresponding to which, however, there is no loss of substance upon the corneal surface, but merely an absence of luster. In the further course of an abscess, to be sure, the layers which lie in front of it always succumb, so that the abscess is ultimately converted into an ulcer and presents the characters of one.



FIG. 31.—SCHEMATIC REPRESENTATION OF AN ABSCESS OF THE CORNEA.

The surface of the cornea is sunken over the abscess, *a*, because the latter is thicker at its edges than in the center. The posterior surface of the cornea is covered by a thin layer of exudate, *b*, which also lines the anterior surface of the iris, *d*, and the anterior capsule of the lens, *e*, and, becoming more pronounced inferiorly, forms there a hypopyon, *c*.

Every keratitis suppurativa entails a loss of substance in the cornea. This must be filled up again by newly formed tissue, in doing which the process enters upon its third stage — that of *cicatrization*. The newly formed tissue is not corneal tissue, but connective tissue, and is accordingly opaque (Fig. 32). Hence suppurative keratitis always leaves a permanent opacity after it. The opacity, indeed, is the principal clinical sign of a cicatrix; for the corneal surface has completely reacquired its luster, because its epithelium is restored to the normal state; and the excavation or loss of substance has disappeared, at most a slight flattening of the surface being present.

Recapitulation.—According to the statements above made, non-suppurative keratitis has two stages: the stage of infiltration and that of resorption. In suppurative keratitis, on the other hand, we distinguish three stages: the stage of infiltration, the stage of suppuration, and the stage of cicatrization (reparation). The stage of suppuration is composed of two periods: the progressive period (foul ulcer) and the regressive period (clean ulcer).

In the clinical diagnosis of the form and the stage of an inflammation of the cornea we proceed in the following manner. We first examine the corneal reflex. *If the surface is dull, we are dealing with a recent affection, and in that case, if there is no loss of substance, with an infiltrate or with an abscess; but if a loss of substance is present, with a foul ulcer. If the surface is lustrous, the affection is an old one; if a loss of substance is present, it is a clean ulcer that we have*

before us; but if no loss of substance is visible, we are dealing with a cicatrix.

32. Vascularization of the Cornea.—In inflammations of the cornea we very frequently observe the development of vessels which grow in upon the cornea from its margin. This occurs most frequently during the *process of healing* of corneal ulcers. At the time when the ulcer begins to become clean, we see vessels starting out from that part of the limbus lying next to the ulcer. These vessels lie in the most superficial layers of the cornea and extend toward the ulcer, whose edges they soon reach (Fig. 30, *g*).



FIG. 32.—CICATRIX OF THE CORNEA. (AFTER SAEMISCH.)
The epithelium, *e*, is everywhere present, but over the cicatrix it is irregular, and in places (at *a*) is thickened. Bowman's membrane, *b*, is wanting at the site of the cicatrix. The latter itself is distinguished from the tissue of the normal cornea by its denser and less regular texture.

Their chief office seems to consist in supplying the necessary material for filling in the loss of substance. Their advent is therefore to be regarded as a favorable occurrence; we know that at the spot where the vessels have reached the ulcer the further progress of the latter is no longer to be apprehended—that, on the contrary, it will there enter upon the process of healing. After the loss of substance has been filled in, the vessels gradually disappear, so that a corneal cicatrix contains fewer and fewer of them as it becomes older. Nevertheless, the blood-vessels never entirely disappear from the large cicatrices.

In other cases the formation of new vessels accompanies the *progress of the inflammatory process*, and hence belongs, like the exudation itself, to the clinical picture of the inflammation. The best example of this is afforded by the vascular form of parenchymatous keratitis (§ 43).

A kind of vascularization differing from both of these varieties is that which forms one of the symptoms of *pannus*. Here the vessels do not lie in the cornea itself, but in a newly formed tissue which is deposited upon the cornea and of which they form an essential constituent (Fig. 22).

It is very important to determine the *situation* of the vessels in the cornea—that is, whether superficial or deep—since by this fact alone we can often diagnosticate what sort of keratitis we are confronted with. The type of superficial vascularization is afforded by pannus, that of deep vascularization by keratitis parenchymatosa.

The signs which enable us to distinguish the two kinds of vascularization from each other may be contrasted as follows:

Superficial Vessels	Deeply situated Vessels
spring from the network of marginal loops of the limbus, and can therefore be followed from the cornea into the limbus, and thence on to the vessels of the conjunctiva.	spring from the vessels of the sclera close to the margin of the cornea, and hence appear to come to an end suddenly at the limbus, as they disappear behind the latter to enter the sclera.
On account of their superficial position are clearly visible and well-defined, and have a vivid red color.	Are not distinctly recognizable, or are even unrecognizable, except as a diffuse red coloration, and have a dirty-red (grayish-red) hue; the reason for both of these appearances being that the vessels are veiled by the clouded layers of cornea lying in front of them.
The vessels branch in an arborescent fashion.	The vessels form fine twigs which run parallel to each other (besom form of branching).
The surface of the cornea is uneven, from the fact that the vessels raise up the epithelium that lies directly over them.	The surface of the cornea is lusterless, it is true, but not uneven.

Participation of Neighboring Organs in the Process.—Every keratitis is accompanied by inflammatory symptoms, the most important of which is—

(*a*) The *injection* of the blood-vessels. The characteristic mark of corneal inflammation is ciliary injection. When the inflammation is great, conjunctival injection also makes its appearance, and may conceal the ciliary injection to a greater or less extent. Very violent suppurative inflammations of the cornea are accompanied by œdematous swelling of the conjunctiva and even of the lids.

(*b*) The iris and even the ciliary body become inflamed in cases of marked keratitis, so that we see the symptoms of *iritis* and *iridocyclitis* set in (see §§ 67 and 68). These accompanying inflammations may be intense enough to bring about the destruction of the eye.

(*c*) *Hypopyon* * is the accumulation of a purulent exudate at the bottom of the anterior chamber (Fig. 31, *c*). It forms a frequent symptom in keratitis suppurativa. We then find collected in the lowest portion of the chamber a yellow mass which, because it is fluid,

* From ὑπό, beneath, and πύον, pus.

is limited above by a horizontal line, and for the same reason is seen to change its place and seek the deeper portions of the chamber when the head is moved. In other cases the mass is viscid or pultaceous, so that when seen from in front it has a border that is convex upward, or it lies quite like a solid ball at the bottom of the chamber and does not change its position with the movements of the head. Hypopyon usually originates both from the cornea and from the iris, the latter being inflamed as well, and both pouring a part of their exudate into the anterior chamber. The quantity of the pus produced in this way varies greatly, ranging from a scarcely perceptible amount lodged in the lower sinus of the chamber up to masses of such size that the entire chamber is filled by the hypopyon. Hypopyon may disappear by resorption, this process taking place the more rapidly the more fluid the hypopyon is. Pretty thick masses of exudation may become organized and lead to occlusion of the pupil, or, in rare cases, to adhesion of the iris to the posterior surface of the cornea.

(*d*) The *subjective* phenomena associated with keratitis are pain and photophobia, together with the lachrymation and spasm of the lids which these conditions cause, and also disturbance of vision—symptoms which are met with in very varying degree.

The *histological processes* occurring in inflammation of the cornea have been the subject of the most zealous investigations, and especially of investigations experimentally conducted, because the attempt was made to study in this field the problem of inflammation in general. For such studies the cornea is particularly adapted on account of its transparency, and also on account of the characteristic form of the fixed elements of its tissue. There is no doubt that in every keratitis there occurs an increase in the number of the cellular elements, whose accumulation causes the cloudiness of the cornea, visible to the naked eye, and finally, if very considerable, terminates in the formation of pus. Nevertheless observers could not agree as to the source of the new cells which made their appearance in the cornea. Some, the leader of whom was Cohnheim, look upon them as white blood-corpuscles which have migrated into the cornea from the vessels of the corneal margin. Others, and especially Stricker, consider them derived from an increase in number of the normal fixed cells of the cornea. I am persuaded from my own investigations that, in the cornea as well as in other tissues, both processes always go on simultaneously. Proliferation of the corneal cells takes place simultaneously with the migration of white blood-corpuscles, so that the new cells which make their appearance in the cornea originate partly in one way, partly in another, without our being able to discover, from the aspect of any particular cell, from which of the two sources it takes its origin.

In the *healing* of the losses of substance produced by inflammation, the regeneration both of the epithelium and of the stroma of the cornea come in for consideration. The epithelium of the cornea is replaced by the growth of the epithelium from the edge of the ulcer. Losses of substances which affect the epithelium only, heal with a perfect restoration to the normal state and without leaving a permanent opacity. On the other hand, every loss of substance of

the corneal stroma is filled up by cicatricial tissue which forms from the bottom and sides of the ulcer. The chief part in this is taken by the fixed cells of the cornea in the immediate neighborhood of the ulcer, as these increase by division, and the cells which thus arise grow into connective-tissue fibers. The tissue thus formed is, however, essentially different from the normal tissue of the cornea (Fig. 32). The regular arrangement of the normal fibers of the cornea is wanting, and so, too, are the stellately branched fixed corneal corpuscles, which are replaced by ordinary connective-tissue cells. Bowman's membrane (Fig. 32, *b*) is never regenerated. The epithelium (Fig. 32, *e*) hence lies directly upon the cicatricial tissue, from which, being thinner in some places and thicker in others, it is separated by an irregular line.

As a consequence of these peculiarities, the cicatricial tissue never possesses the perfect transparency of the normal cornea, and is hence recognizable even with the naked eye as an opacity. After having existed for a long time, the texture of the cicatricial tissue approximates somewhat more closely to the regular structure of the corneal tissue. It accordingly gains in transparency, and a "clearing up" of the opacity is demonstrated to exist, which, however, goes as far as a complete disappearance of the opacity only in the case of quite small and superficial cicatrices.

In deep losses of substance the restoration of the normal epithelial coating does not delay making its appearance until the ulcer itself has been completely filled up by cicatricial tissue. On the contrary, from the moment when the ulcer has become clean the epithelium begins to grow over the latter, and hence begins to cover it at a time when there is no cicatricial tissue present, or only a very thin layer of it (Fig. 30, at *b*). At this time the ulcer (on account of the absence of opaque cicatricial tissue) is still almost completely transparent, and, as a consequence of the restoration of the epithelial covering, is smooth and shining. The formation of cicatricial tissue now goes on beneath the epithelium, and by this process the latter is gradually lifted up to its normal level. In proportion as the layer of cicatricial tissue becomes thicker, the degree of opacity naturally increases; but it would be a very great mistake for the physician to conclude from this fact that the disease was advancing.

The signs before given, having regard to changes in the luster, evenness of surface, and transparency of the cornea, serve for the *diagnosis* of the variety of corneal disease that is present. They are not always, to be sure, found combined in a manner as schematic as has been represented. Some examples may show in what way exceptions to them occur. The opacities that are present upon the cornea may be old, and yet the cornea, because of a coincident increase of tension, may look dull and stippled. The surface of the cornea is not always smooth when there are infiltrates, nor yet when there are cicatrices. In the case of infiltrates, a bulging forward of the surface of the cornea often takes place on account of the deposition of an excessive quantity of exudation; in the case of cicatrices, on the other hand, a flattening may take place in consequence of an insufficient filling in of the loss of substance. In doubtful cases, we must take still other factors into consideration, which may furnish points that will establish our diagnosis. Thus, in the case of a cicatrix, the outline of the opacity is commonly better defined than in the case of a recent opacity due to inflammation. The color of the latter form of opacity passes from gray to yellowish-white and to yellow; cicatrices, on the contrary, present rather a pure white, or, if thin, a bluish-white hue. Recent inflammatory processes are asso-

ciated with attendant inflammatory symptoms (ciliary injection, etc.), which are wanting in the case of cicatrices. By putting all these facts together the right diagnosis can almost always be made.

A *hypopyon* consists chiefly of pus-cells. In regard to the source of the latter, views are no less divided than in regard to the origin of the cells of the exudate within the cornea itself, inasmuch as some will have it that they are derived chiefly from the cornea, others that they come solely from the uvea (iris and ciliary body). Here the truth lies in the mean between the extremes, inasmuch as both organs are implicated in the process. Pus-cells from the infiltrate in the cornea pass through the most posterior layers of the cornea and so get into the fluid of the anterior chamber. Particularly in the case of abscess of the cornea, we often see pus extending in the form of a fine filament down to the hypopyon, from the spot upon the posterior wall of the cornea that corresponds to the abscess. In consequence of this, the hypopyon, when looked at from in front, presents a border that is convex upward; and, furthermore, it is found to be completely agglutinated to the posterior wall of the cornea, upon which it extends upward much farther than it does upon the anterior surface of the iris (Fig. 31, *c*). In a case of this sort we can, looking from above, see for a little distance down behind the hypopyon. Many have located the filament of pus which extends downward from the posterior surface of the cornea, and even the hypopyon which is formed by it, in the interior of the cornea itself, assuming that a descent of pus takes place between the lamellæ of the latter. By such authorities the compression of the pus between the lamellæ of the cornea was given as an explanation for the flattened form of the hypopyon and for the convexity of its upper border; on account of the latter, the hypopyon was compared to the lunula of the finger-nail, and was hence called unguis or onyx (nail). This latter expression, therefore, should denote a descent of pus between the lamellæ of the cornea. Any one can convince himself, while performing incision of a corneal abscess combined with opening of the anterior chamber (after the method of Saemisch), that what is called the onyx lies in the anterior chamber, and is nothing but a hypopyon of peculiar form.

A part of the hypopyon arises from the inflamed uvea. This is proved by the presence of pigment-granules in many of the pus-corpuscles, which have carried the pigment with them from the inflamed uvea. The exudate thrown out by the uvea (iris and ciliary body) first gets into the aqueous humor, which is thus rendered turbid. Then, as the cells afterward sink to the bottom, they assist in the formation of the hypopyon. A portion of the exudate that is suspended in the aqueous humor often likewise attaches itself to the posterior surface of the cornea (Fig. 31, *b*; compare also Fig. 61, *b* and *f*). In such a case we see, apart from the circumscribed opacity corresponding to the focus of inflammation, a diffuse opacity of the entire cornea, caused by the thin layer of exudation on its posterior surface.

The *resorption* of the hypopyon takes place chiefly through the meshwork of the ligamentum pectinatum (§ 61). The rapidity with which absorption proceeds varies exceedingly. In many cases a hypopyon of considerable size disappears so completely, that after twenty-four hours scarcely a trace of it is to be found; in other cases, the hypopyon remains lying at the bottom of the chamber so long that it becomes organized. Sometimes we observe a rapid alternation in the height of the hypopyon which at times decreases, and again increases once more.

The *blood-vessels* which form during the cicatrization of a corneal ulcer appear, in many instances, to persist for a long time in an empty state. For example, suppose that an eye is affected with a cicatrix which is not very recent and which apparently contains only a few vessels or none at all, and that an iridectomy is made upon the eye so that a certain amount of irritation is produced. Then we often see, on the following day, not only the cicatrix but also the adjacent transparent cornea densely permeated by vessels. Since these vessels can not have been formed anew in so short a time, we are forced to assume that the old vessels, although empty, were still present and had again become filled with blood. Furthermore, after non-purulent varieties of keratitis—e. g., after keratitis parenchymatosa—very minute vessels, only visible with the aid of the magnifying-glass, frequently remain, persisting for a number of years, in the deeper layers of the cornea (Hirschberg).

Subdivision of Keratitis.

33. The subdivision of keratitis into keratitis suppurativa and keratitis non-suppurativa corresponds most fully to practical requirements. Every suppurative keratitis, since it is associated with destruction of corneal tissue, leaves behind it a permanent opacity, which in many cases injuriously affects the visual power. On the contrary, so long as purulent dissolution of the cornea has not taken place—that is, in non-suppurative keratitis—a complete restoration of its transparency, and with it of the normal power of vision, is possible, and, in fact, often does take place. Moreover, the above subdivision also corresponds to the essential characters of the corneal inflammations. For it is not merely a matter of accident whether an infiltrate in the cornea goes on to suppuration or to resorption. On the contrary, the forms which tend to the production of suppuration ordinarily present from the very beginning characters differing from those borne by forms in which there is no progress toward suppuration, so that these two categories are distinct not only in their consequences but also in their clinical aspect. In each of the two categories a number of different forms belong, the most important of which are set forth in the following list:

A. *Keratitis Suppurativa.*

1. Ulcer of the cornea.
2. Abscess of the cornea.
3. Keratitis e lagophthalmo.
4. Keratomalacia.
5. Keratitis neuroparalytica.

B. *Keratitis Non-suppurativa.*

(*a*) Superficial forms.

1. Pannus.
2. Keratitis with the formation of vesicles.

(*b*) Deep forms.

3. Parenchymatous keratitis.
4. Deep keratitis.
5. Sclerosing keratitis.
6. Keratitis starting from the posterior surface of the cornea.

A. Suppurative Keratitis.

1. Ulcer of the Cornea.

34. Symptoms and Course.—Every ulcer of the cornea develops from a superficially disposed infiltrate. In the beginning we find one spot upon the cornea cloudy and the surface over it dull (infiltrate). Then the epithelium exfoliates upon the surface of the affected spot, and soon, by the breaking down of the most strongly infiltrated portions of the cornea, a loss of substance forms in the parenchyma of the cornea, so that an ulcer is produced. This is at first surrounded by infiltrated portions of the cornea—a fact which we recognize by the base of the ulcer being gray and uneven, and its walls likewise gray and clouded. The walls of the ulcer are often surrounded for quite a distance by a gray area, or slender gray striæ, extending from the ulcer in different directions into the transparent cornea. This is an unclean or *progressive* ulcer (Fig. 29). In a favorable case, only so much of the corneal tissue breaks down during the further progress of the disease as was from the very beginning too strongly infiltrated to live. In this case the ulcer rapidly becomes clean without attaining great dimensions. But it very often happens that, simultaneously with the breaking down of the parts that are most strongly infiltrated, the inflammatory cloudiness keeps spreading, new portions of the cornea being constantly attacked by the infiltration. And since these, too, break down into pus, the ulcer grows constantly larger. This progressive growth of the ulcer takes place sometimes more in the direction of the depth, sometimes more along the surface. In the former case, perforation of the cornea is to be apprehended; in the second case, larger and larger areas of the cornea may be destroyed and thus extensive opacities be produced. Progressive growth along the surface often takes place chiefly in one direction—a fact which can be easily recognized by a particularly marked gray cloudiness, or even a yellow cloudiness, of the ulcer-wall on the corresponding side. It may even happen that the ulcer keeps constantly advancing in one direction, while on the opposite side it heals just as fast, so that it goes creeping over the cornea (*serpiginous* * ulcer).

The progressive stage of the ulcer is accompanied by symptoms of

* From *serpere*, to creep.

irritation like ciliary injection, lachrymation, photophobia, and pain, which not infrequently reach a considerable height; moreover, in this stage hyperæmia or even inflammation of the iris make their appearance (evidenced by turbidity of the aqueous humor, hypopyon, discoloration of the iris, contraction of the pupil, posterior synechiæ). There are, however, cases of ulceration in which the irritative symptoms are very slight, or are wanting altogether—cases constituting what are called *torpid* or asthenic ulcers—which nevertheless may be very dangerous.

When the infiltration has finally come to a standstill, the ulcer enters upon its *regressive* stage. The tissue that has been destroyed is cast off, that which has not been destroyed becomes transparent once more from resorption of the exudate. The ulcer "cleanses" itself (Fig. 30). A clean ulcer presents a smooth base and edges with little or no opacity, and is chiefly to be diagnosticated by the excavation of the surface of the cornea, which we recognize when examining the corneal reflex. In proportion as the ulcer becomes clean, the associated symptoms of irritation disappear.

After the ulcer has become entirely clean, *cicatrization* begins. Vessels extend from the nearest portions of the limbus to the ulcer, which latter, in consequence of becoming filled with the opaque mass of the cicatrix, becomes again more clouded, but at the same time constantly shallower, until finally it reaches the level of the adjacent nor-

FIG. 33.—KERATECTASIA PRODUCED BY AN ULCER. MAGNIFIED 25×1.
The thinned and protruding cicatrix is distinguished by its denser texture from the adjacent normal cornea. The epithelium, *e*, over it is thickened, while Bowman's membrane, *b*, is wanting. On the other hand, Descemet's membrane, *d*, with its epithelium, is everywhere present—a proof that the ulcer has not perforated.

mal cornea. Not infrequently, however, the new formation of the cicatricial mass comes to a standstill before the loss of substance has been quite filled up, so that the surface of the cicatrix remains permanently a little sunken. When such cicatrices are small they are, on account of the thinness of the cicatricial tissue, almost or quite transparent, and disclose their presence by a flattening of the cornea (*corneal facet*), only discernible upon examination of the corneal reflex. On the other hand, cicatrices not infrequently occur which project above the level of the

surrounding cornea. Such are the cases in which the cornea at the base of the ulcer, having become thinned, does not offer resistance to the intra-ocular pressure, and bulges forward. The bulging may disappear, owing to the contraction of the cicatricial tissue; but it may also remain permanently (*ectactic cicatrix*, keratectasia* ex ulcere, Fig. 33). The formation of ectactic cicatrices is, however, of much more frequent occurrence after perforation of the cornea.

35. Perforation of the Cornea.—The course which an ulcer takes is much more complicated when the latter perforates the cornea. Perforation takes place when the ulcer has penetrated down to the deepest layers of the cornea. The patient suddenly experiences violent pain, and feels a hot liquid (the aqueous humor) gushing out of the eye, after which, not infrequently, the severe pains previously existing subside. Perforation may occur spontaneously or in consequence of a sudden increase of the intra-ocular pressure, such as may be caused by bodily exertion (even, for example, stooping), or by coughing, sneezing, screwing together the lids, crying (in children), etc. The increase in intra-ocular pressure, which develops under these circumstances, is to be referred to two causes: it is partly a result of the increase of blood-pressure (from the straining of the muscles, and also from congestion in the district drained by the superior vena cava), partly produced by direct compression of the eyeball, and particularly by the pressure which the ocular muscles, and especially the orbicularis palpebrarum, at such times exert upon it. The perforation produced by such causes may develop with violent symptoms and entail very damaging results.

After perforation has occurred we find the anterior chamber obliterated in consequence of the escape of the aqueous humor; the iris and, in the region of the pupil, the lens also are applied to the posterior surface of the cornea. If the aperture made by the perforation is of suitable position and size, we see lying in it the iris which has been swept into the wound by the jet of escaping aqueous. The eye feels quite soft.

Perforation is often preceded by a *keratocele*.† For, Descemet's membrane being distinguished by the great resistance which, in comparison with the corneal lamellæ, it offers to the inflammatory process, it often happens that the stroma of the cornea is destroyed throughout its entire thickness by suppuration, while Descemet's membrane still remains resistant. In that case it is protruded by the intra-ocular pressure under the form of a transparent vesicle which is visible upon the floor of the ulcer, or which may even project above the level of the adjacent cornea (keratocele or descemetocele). When this vesicle, too, ruptures, the perforation becomes complete. Sometimes the ulcer heals

* From κέρας, horn, and ἔκτασις, distention, from ἐκτείνειν, to stretch out.

† From κέρας, horn, and κήλη, rupture.

without the keratocele either rupturing or being flattened out. The latter then remains permanently under the form of a vesicle which projects above the surface of the cornea, and which, itself transparent, is surrounded by a cloudy, cicatricial ring.

The direct *effect* of a perforation upon the course of the disease is for the most part favorable, inasmuch as not only the pain and the other symptoms of irritation abate, but the progress of the ulcer also is, as a rule, arrested, and the ulcer rapidly becomes clean. The reason for this favorable influence is probably to be looked for in the fact that after the escape of the aqueous humor the intra-ocular pressure sinks considerably, and the resulting diminution in the tension of the cornea facilitates the circulation in the latter.

The method in which the perforation in the cornea closes again varies according as it is placed in front of the iris or the pupil. If the opening is found *in front of the iris*, as is generally the case, it is quickly covered by the iris, which, after the escape of the aqueous humor, is driven forward as far as the cornea. In this way it becomes possible for the anterior chamber to be restored within a very short time, although, to be sure, the iris at the site of the perforation remains permanently connected with the cornea. If the perforation is quite small, the iris simply applies itself to it from behind and there becomes solidly adherent. In case, however, the perforation is larger, the iris, as a rule, is driven into it by the escaping aqueous humor, and thus a *prolapse* or *hernia* of the iris is produced (Fig. 34). This is represented by a hemispherical prominence which, while recent, has the gray or brown color of the iris. Soon, however, this color is changed because of a layer of gray exudation (*e*, Fig. 34) which covers the prolapse like a cap, and may be removed with a forceps. When the prolapsed portion of the iris is much stretched, the proper color of the iris is lost and the prolapse looks black, because of the retinal pigment on its posterior surface, which appears through the thinned stroma. This is particularly often the case in large prolapses of the iris. The extent of the prolapse of the iris is proportional, first of all, to the size of the perforation. In the worst cases the perforation may comprise the whole cornea, which has suppurated throughout; in that case the iris prolapses through its entire extent (*total prolapse* of the iris, Fig.

FIG. 34.—PARTIAL PROLAPSE OF THE IRIS. SCHEMATIC.

The iris, which is thickened by the process of infiltration, and is covered on its anterior and posterior surface by the exudate, *e*, e_1, rises up between the sharp edges of the margins of the perforation, which are still infiltrated. Peripherally from the prolapse the iris is approximated to the cornea, although here a remnant, *v*, of the anterior chamber still exists.

35). The pupil is then generally closed up by a plug of exudation (*p*). But the way in which the prolapse occurs has also an influence upon its size. If the perforation takes place with great force (e. g., while the patient is straining hard), or if the patient behaves in a restless manner after it has taken place, a relatively larger portion of the iris will be driven into the perforation.



FIG. 35.—TOTAL PROLAPSE OF THE IRIS. SCHEMATIC.

Only the marginal portions, *c*, of the cornea are preserved, and these are still partially infiltrated. Between them bulges the iris, which is driven strongly forward and which consequently is thinned so that the pigment, *i*, upon its posterior surface shines through it and gives the prolapse a blackish hue. The pupil, *p*, is closed by a membrane. The space, *h*, between the iris and the lens is the enlarged posterior chamber Of the anterior chamber only the shallow, slit-like, annular space, *v*, is left. This no longer communicates anywhere with the posterior chamber (seclusio pupillæ).

The *cicatrization* of a corneal ulcer, which is associated with a prolapse of the iris, occurs in the following manner, if the prolapse is left to itself: The prolapsed iris in the first place becomes solidly agglutinated to the walls of the opening caused by the rupture, and wherever it is exposed it is converted by inflammation into a sort of granulating tissue, so that the prolapse soon loses the color of the iris and becomes grayish-red. Subsequently there develops from the proliferating tissue of the iris cicatricial tissue, which first becomes visible under the form of isolated gray bands. By the contraction of these latter, constrictions are formed upon the surface of the prolapse. As the formation of the cicatrix proceeds, these bands become broader, fuse together, and render the prolapse constantly flatter and flatter. Hence in favorable cases the process terminates in the formation of a flat cicatrix situated at the level of the rest of the cornea, and at the site formerly occupied by the bulging prolapse. As, therefore, this cicatrix is mainly a portion of iris which has become cicatricial, the portion of the iris remaining in the anterior chamber naturally is solidly united to it. Such an adhesion of the iris to a corneal cicatrix is called an *anterior synechia.**

Owing to the fact that the iris is drawn forward to the scar, the pupil loses its round shape and is drawn in toward the site of the adhesion (cf. Fig. 163). To what extent this is the case depends upon where the perforation is situated and what part of the iris is prolapsed. In peripherally situated ulcers, it is a portion of the ciliary zone of the iris that prolapses into the corneal wound. In this case the pupil is drawn strongly toward the site of the perforation; it has the shape of a pear,

* From *συνέχειν*, to connect. The term leucoma adhærens (from *λευκός*, white) is also employed to denote a cicatrix of the cornea with anterior synechia.

the sharp end of which is directed toward the site of the synechia. If the perforation is situated near the center of the cornea, the pupillary portion of the iris becomes engaged in it in healing (Fig. 34), and in this case the distortion of the pupil is slight, or entirely absent. If the perforation is so large that the entire pupillary margin of the iris is involved in the prolapse and becomes attached to the cornea in healing, the pupil is permanently closed by the cicatrix that is formed; there are produced occlusio and seclusio pupillæ, together with their destructive consequences.

In the healing of large perforating ulcers of the cornea, the shrinking of the cicatricial tissue is often so great that the corneal cicatrix appears flattened when compared with the normal curvature of the cornea. This flattening, moreover, may extend beyond the cicatricial spot to the portion of the cornea which is still transparent, and which in that case becomes flatter over its whole surface (*applanatio corneæ*). If the cornea has been entirely destroyed by suppuration, so that a total prolapse of the iris has developed, the latter ultimately becomes reduced to a small and perfectly flat cicatrix, which appears in place of the cornea (*phthisis corneæ*). The distinction between applanatio and phthisis of the cornea is as follows: In the former the cornea is still present, although it is in part cicatricial, and thus as a whole is flattened. In the latter, on the other hand, nothing of the cornea is left except a very narrow marginal rim, which generally withstands the destructive process of ulceration. The flat cicatrix which takes the place of the cornea is, in this case, the cicatrized iris.

The healing of a prolapse of the iris with the *formation of a flat cicatrix* must be regarded, even though the latter is opaque, as a relatively favorable outcome of a large corneal perforation. Such an eye, of course, is seriously impaired as regards its function, but yet, after the process has run its course, it remains in a state of quiescence, and generally causes its owner no further trouble. The case is different when healing takes place with the formation of an *ectatic cicatrix*. This occurs in the following manner: The prolapsed iris becomes covered with cicatricial tissue, but this is not strong enough to effect the flattening of the prolapse. Hence the latter becomes consolidated in its original form as a protrusion, and is converted into an ectatic cicatrix with inclusion of the iris (*staphyloma corneæ*). A large-sized perforation-opening and restlessness of the patient favor the formation of such an ectasis. Whenever a prolapse of the iris has become so extensive that it is constricted by the margin of the perforation, and hence has acquired a mushroom shape, the formation of a flat cicatrix, without artificial aid, becomes altogether impossible.

If the perforation in the cornea is not in front of the iris, but lies *in the region of the pupil*, it can not be covered by the iris. Its occlu-

sion in this instance takes place more slowly by an outgrowth of new-formed tissue (cicatricial tissue) from the margins of the opening, until the opening is filled up. In such a case the anterior chamber remains absent for a somewhat longer time, and meanwhile the lens is in contact with the posterior opening in the cornea. The lens may bear away permanent marks of this contact, most frequently in the form of a circumscribed opacity at its anterior pole (anterior capsular cataract; see § 90). If during cicatrization the delicate membrane occluding the opening is repeatedly ruptured (which generally occurs from improper behavior on the part of the patient), the perforation may at length remain permanently open, and a *fistula of the cornea* is formed. This appears under the guise of a small dark point, surrounded by whitish cicatricial tissue; the anterior chamber is absent, the eye is soft. If the fistula of the cornea persists for a long time, the eye gradually perishes. The cornea flattens out, the eye grows softer and softer, and at length goes blind from detachment of the retina. On the other hand, as soon as the fistula closes up, an increase of tension is apt to set in, that may lead to a renewed rupture of the occluding substance, which is still but slightly resistant. An alternation of this sort between an open fistula with softness of the eyeball, gradual closure of the fistula, and a consequent steady increase of pressure until the cicatrix ruptures anew, may be repeated for a long time, until finally a severe inflammation occurs, which leads to the atrophy of the eye, and thus puts an end to the process.

Other bad consequences of perforation of the cornea, which are sometimes observed, are:

(*a*) *Luxation of the Lens.*—After the escape of the aqueous humor, the lens, to reach the cornea, must be pushed forward through the entire depth of the anterior chamber (2·5 millimetres), a movement associated with a considerable degree of stretching of the zonula of Zinn. If the forward movement takes place very suddenly, or if the fibers of the zonula have been rendered fragile by disease, the zonula ruptures. In consequence the lens may assume an oblique position, or, if the perforation is large enough, may even be expelled from the eye.

(*b*) *Intra-ocular hæmorrhages* are the result of the rapid diminution in tension, by virtue of which an increased quantity of blood flows into the vessels of the interior of the eye, which have been thus suddenly relieved of extraneous pressure, and causes their rupture. Hæmorrhage takes place if the perforation occurs very suddenly, or if the eye beforehand was under an abnormally high tension. The latter is the case in glaucomatous and staphylomatous eyes, in which, furthermore, there is generally also a degeneration of the vessels associated with an increased fragility of their walls. The hæmorrhage may be so great that the entire contents of the eyeball are extruded by reason of it; nay, more, the patient may almost be in danger of bleeding to death.

(*c*) Suppuration starting from the cornea may be carried over into the deeper parts of the eye and lead to the destruction of the latter by *purulent irido-cyclitis*, or even by *panophthalmitis*. This occurs principally in the case of extensive destruction of the cornea, especially if, at the same time, the suppuration is of a particularly virulent character, as in acute blennorrhœa or in abscess of the cornea.

The Clearing of Corneal Cicatrices.—The cicatrix, remaining after an ulcer, appears after a long time, as after months or years, less large and less opaque than it was directly after the healing of the ulcer was completed; the cicatrix has partially "cleared up." In this way quite small cicatrices may become altogether invisible. The extent to which clearing takes place depends principally upon two circumstances: upon the thickness of the cicatricial tissue and upon the age of the individual. The deeper the cicatrix penetrates into the cornea, the less it clears up; perforating cicatrices of the cornea, if they are ever so small, remain permanently opaque. (A fine example of this is afforded by the punctures which the discission needle makes, and which remain visible as gray points upon the cornea all during life.) The age of the individual influences the process of clearing, in that the latter makes greater advances the younger the patient is. For this reason cicatrices after blennorrhœa neonatorum often clear up in a wonderful way.

36. Etiology.—With reference to their etiology, all inflammations of the cornea may be divided into two great groups: primary and secondary keratitides. By the former, we understand those which have their starting-point in the cornea itself; by the latter, on the contrary, those which have passed over to the cornea from other structures, and most frequently from the conjunctiva. This distinction, true with regard to keratitis in general, is especially so with respect to ulcers of the cornea.

Primary ulcers of the cornea most frequently owe their development to traumatism. Under this head belong not only injuries in the narrower sense of the word, but also a lesion of the cornea by means of small foreign bodies, by faultily placed cilia, by papillary growths on the free border of the lids, etc. Ulcers, furthermore, develop from corneal abscesses when the anterior wall of the latter is destroyed by suppuration, and also form after the separation of eschars produced by burns or the action of caustics. Other ulcers are dependent upon a disturbance in the nutrition of the cornea, as the ulcers in eyes with absolute glaucoma where the cornea has become insensitive, or ulcers which develop in old cicatrices of the cornea (atheromatous ulcers).

Secondary ulcers are the results of an affection of the conjunctiva. All inflammations of the conjunctiva may be complicated with inflammations of the cornea; and in severe inflammations of the conjunctiva, as in acute blennorrhœa and diphtheria, this is quite the rule.

The direct cause of the formation of ulcers in the cornea, accord-

ing to the present views regarding suppuration, is to be looked for in the majority of cases in the entrance of micro-organisms into the tissue of the cornea. We may have to do in this case either with specific organisms, as in the case of acute blennorrhœa, or with the ordinary pus-cocci (principally the *Staphylococcus*). The latter are always found in the secretion of a conjunctiva affected with catarrh. If, now, through a slight traumatism of any sort, the protective epithelial covering of the cornea is injured at some spot, the door is opened for the entrance of cocci into the tissue of the cornea. In this way are to be explained the small corneal ulcers which occur so frequently in old people, and which are referred to the impact of dust, etc., upon the eye. So slight an injury would, in a normal eye, heal in a very short time, without leaving a trace behind. But if a chronic conjunctival catarrh is at the same time present, the small wound becomes infected by the secretion of the conjunctiva, and consequently an ulcer develops. In people of the working-class ulcers of the cornea occur much more frequently than among the well-to-do classes, because they very often suffer from neglected chronic catarrhs, and at the same time very frequently render themselves liable to injuries of the cornea.

Treatment.—Ulcers of the cornea are very amenable to proper and energetic treatment. They hence in general afford a favorable prognosis if they come under treatment early; in the great majority of cases it is possible to put a stop to their progress, and produce regular cicatrization. The treatment varies according to the stage in which the ulcer comes under treatment.

(*a*) Recent ulcers that are still *foul* (progressive) require, most of all, the consideration of the *causal indication*. In traumatic ulcers any foreign bodies that are still present must in every case be removed. Cilia which are directed against the cornea must be epilated; papillomata of the edges of the lids, when causing trouble in the cornea, must be removed. In the numerous cases in which the ulcer of the cornea is caused by a conjunctival lesion, the treatment of the latter forms, as a rule, the most important part of our therapeutics, and under it, moreover, the ulcer advances toward recovery. Hence, in corneal ulcers resulting from catarrh, trachoma, or acute blennorrhœa of the conjunctiva, we must by no means desist from cauterization of the latter, if it is required by the conjunctival trouble. The only precaution that must be observed is that the caustic application should not come into contact with the cornea itself—a contingency which can be avoided by carefully washing off from the conjunctiva any excess that may be present. Furthermore, we should cauterize with the silver solution only, and not with the copper-stick, which is too irritating, and still less with the acetate of lead, which might lead to the formation of incrustations of lead upon the cornea. Moreover, as long as progressive ulcers are present in the cornea, no irritating collyria, such as the col-

lyrium adstringens luteum and the like, should be instilled, as they would then come into contact with the cornea.

The *indicatio morbi* requires in most cases the application of a bandage. Bandages are distinguished into protective bandages and pressure bandages, according as they are applied lightly or firmly. In recent ulcers a simple *protective bandage* is sufficient. The object of this is to keep the lids closed and at rest without exerting any pressure upon the eyeball. The immobilization of the lids acts chiefly to prevent the floor of the ulcer from being swept by the lids with every movement of winking, which would give rise to constant irritation of the ulcer, and also to pain through contact with the nerve-fibers lying exposed in it. Hence the pains are sometimes cut short at once by the application of a proper bandage. The bandage acts also to protect the ulcer from dust. The dust which is always falling upon the cornea is continually carried off by the movements of the lids; but in the depression which constitutes the ulcer it is not reached by the lids as they sweep over it; it consequently remains lying where it is, and may infect the ulcer. The bandage, as a rule, is to be kept on until the ulcer gets to be clean and becomes lined with an epithelial covering which protects the cornea against exterior influences. When the floor of the ulcer is thinned and shows a tendency to bulge, the use of the bandage must be kept up until the freshly formed cicatrix is sufficiently strong to offer resistance to the intra-ocular pressure.

A contra-indication against the bandage is furnished by a profuse secretion, because the latter would be retained in the conjunctival sac by the closure of the lids, and would remain in constant contact with the ulcer. For this reason, in ulcers resulting from conjunctivitis the bandage must be very often dispensed with. In quite small children, also, the bandage is generally useless, since it soon gets displaced; and a badly applied bandage is more hurtful than to have the eye remain open.

Next to the bandage *atropine* plays the most important part in the treatment of ulcers. It combats the inflammation of the iris, hence diminishes the general state of irritation, and so reacts favorably upon the ulcer itself. It must be instilled as often as is necessary, in order to keep the pupil steadily dilated. With these two remedies alone—the bandage and atropine—we attain our object in light cases. For those ulcers, however, which from the purulent hue or from the strong infiltration of their surrounding parts show a rapidly *progressive* character, we must employ still other remedies. These are, moist warm compresses, iodoform, the actual cautery, and paracentesis of the anterior chamber.

Moist warm compresses are made by taking a very light linen cloth folded several times, which simply covers the closed eye without pressing upon it by its weight. Before being applied, this is dipped in ho'

water and then well wrung out; and it must be changed frequently in order to be constantly warm. The warm compresses are applied every day for an hour or more, and the dressing must be left off each time for the same period. Very finely powdered *iodoform* may be sprinkled upon the ulcer itself. If in spite of these remedies the ulcer is evidently spreading, we must proceed to the operation of *cauterizing* the ulcer by means of the actual cautery (Gayet). For this purpose we use a small sharp-pointed cautery-iron, or the galvano-cautery loop, or Pacquelin's thermo-cautery. With one of these instruments the ulcer is cauterized wherever it shows a gray coating. In the case of extensive ulcers it is not necessary to cauterize the entire ulcerating surface, but it is sufficient to destroy the most infiltrated portion of its margin, at which an advance of the ulcerative process is to be expected. In performing the cauterization we make the cornea insensitive by the repeated instillation of a five-per-cent solution of hydrochloride of cocaine.

Another potent remedy for combating rapidly spreading ulcers is *paracentesis* of the anterior chamber (for the method of its performance see the section of operations, § 155). People were led to do this operation by observing that ulcers after spontaneous perforation generally went on to heal rapidly. In a similar manner, artificial perforation—i. e., puncture of the cornea—performed early, prevents the extension of the ulcer and its threatened rupture. Why should we not wait until the ulcer spontaneously perforates the cornea? Because in the mean time the ulcer keeps enlarging superficially and thus would produce a more extensive opacity, and, furthermore, because after ulcerative perforation of the cornea, a prolapse of the iris almost always develops, leading to the formation of an anterior synechia, while with a properly performed puncture this is not the case.

If perforation is imminent, and we prefer not to bring it about artificially by puncture, we take care to have the patient kept quiet—a thing best done by making him lie in bed, in order that the perforation may take place slowly, and that as little as possible of the iris may be driven into the opening.

(*b*) When *perforation* of the cornea has taken place, treatment has to aim at the following objects: in the first place, that the iris shall not adhere to the cornea, or at least shall do so to the smallest possible extent; in the second place, that a firm and flat (not ectatic) cicatrix shall be formed. The two objects are attained as follows:

1. If the perforation is small the iris does not prolapse into it, but simply becomes applied to its posterior orifice. In such cases, rest, a bandage, and atropine suffice for the treatment. There then remains only a punctiform adhesion of the iris to the corneal cicatrix, and this is often subsequently drawn out into a thin filament. In particularly favorable cases no anterior synechia at all may be produced; for instance, if the iris, before it has become firmly adherent to the site of

perforation, is pushed away from it by the reaccumulating aqueous humor.

2. If—in the case of a prolapse of greater size—the iris has prolapsed, it should be excised. A replacement of the iris into the anterior chamber (reposition) is in most cases impossible of performance, and, even if it should succeed, would have no lasting results, since the iris would continually prolapse again. For the performance of *excision* we first make the cornea insensitive by means of cocaine. Then with a sharp-pointed instrument (conical sound) we separate on all sides the adhesions of the prolapse to the orifice of perforation, draw the iris as far as possible out of the wound with the forceps, and snip it off close to the cornea (Leber). If the operation has been successful, the iris ought no longer to be attached anywhere to the margin of the aperture; on the contrary, there should be a coloboma of the iris with free pillars, as after a regular iridectomy. In this way we obtain a firm cicatrix without inclusion of the iris.

The performance of excision is possible only in recent prolapses (prolapses a few days old), as afterward the prolapsed iris becomes so solidly adherent to the margins of the perforation that a separation of the iris from the latter is no longer feasible. Similarly it is not to be recommended in the case of a very large perforation. In these two cases—i. e.,

3. In old or very extensive prolapses of the iris we abstain from releasing the iris from the cornea; we confine ourselves to the attempt to transform the prolapse into a firm and flat cicatrix. In many cases a pressure bandage applied for a long time accomplishes this end. If we can not attain our object in this way, as is particularly the case when the prolapse is constricted at its base like a mushroom, we must produce flattening of the prolapse by repeatedly puncturing it or by excising a small portion. In the case of a very bulging total prolapse of the iris, it is advisable to split it transversely, and then, after opening the anterior capsule, to expel the lens. If there is a remnant of sound cornea left broad enough for the performance of an iridectomy, this operation is an excellent means for securing the formation of a flat cicatrix.

4. In *keratocele*, the maintenance of rest, the application of a bandage, and ultimately the puncture of the protruding vesicle, are employed.

5. In *fistula of the cornea*, in order to effect its closure, everything must be avoided that might temporarily increase the ocular tension, and thus force the fistula open again just as it is closing. For this purpose we order rest in bed, with the application of a light bandage to both eyes, while at the same time we instill a miotic (eserine or pilocarpine, see § 65) in order to diminish the pressure in the anterior chamber. An iridectomy has a very good effect, but this can be per-

formed only when the anterior chamber has been, at least to some extent, restored. Refreshing of the edges of the fistula by means of cauterization is also employed, but is not without danger.

(*c*) The treatment of ulcers in the regressive period, or *period of cicatrization*, should aim at having the loss of substance completely filled with a resistant cicatrix, and at having the latter rendered as transparent as possible. For the attainment of both objects irritants are employed. We begin cautiously with the weaker remedies, passing gradually, if these are well borne, to the stronger ones. One of the mildest of irritants is powdered calomel; more energetic is the action of the yellow-precipitate ointment (from one to four per cent), the collyrium adstringens luteum,* and tinctura opii crocata.† In applying the yellow-precipitate ointment, we distribute it through the conjunctival sac by rubbing it about with the upper lid—in doing which we at the same time perform a sort of massage upon the clouded cornea. Another irritant remedy that is recommended is vaporization—that is, the application of hot vapor (of water either alone or with the addition of irritant fluids) to the cornea by means of an atomizer, such as is employed for inhalation. It is advisable to continue the application of these irritants for a long time in order to secure the greatest possible clearing up of the cornea, but in so doing the remedies must be changed from time to time, as otherwise the eye gets accustomed to them and they lose their efficacy.

Ulcers of the cornea are among the most frequent affections of the eyes, and special significance attaches to them because the opacities that they leave very often impair the sight. Ulcers of the cornea, if we except those resulting from conjunctivitis lymphatica, are found much more frequently in adults, and especially in elderly people, than in children. It seems that in the later years of life the cornea is less well nourished, and is hence more disposed to disintegrate than in youth.

The physician who is called to a patient with an ulcer of the cornea must, after examining the eye, have acquainted himself not only with the diagnosis but also the *prognosis;* he must tell the patient beforehand to what extent his sight will suffer permanent impairment, in order that the medical treatment may not subsequently be made accountable for this loss. The prognosis for vision depends upon the situation, the extent, and the density of the opacity which the ulcer has left behind it. Small opacities, even when dense, are generally less injurious to vision than those which are less dense but extensive. It is hence less serious for an ulcer to extend into the depth of the tissues than upon the surface. If an ulcer advances in the direction of the center of the cornea, every millimetre causes additional injury to the vision, while an extension

[* See p. 46.]

[† The tinctura opii crocata of the Austrian Pharmacopœia is made by extracting 10 parts of saffron with 100 parts of aqua cinnamomi aquosa (cinnamon-water containing 3 per cent of alcohol) and mixing the solution thus obtained with opium in the proportion of 10 parts of the former to 1 part of the latter.—D.]

toward the corneal margin is almost a matter of indifference. No further disintegration is to be apprehended at those portions of the margin of the ulcer, to which vessels have already penetrated, and so, too, a portion of the cornea, covered by pannus, is protected against suppuration in acute blennorrhœa. In every instance the ulcer is arrested at the limbus, as it never makes its way into this or into the adjacent sclera. The only exception to this is formed by those ulcers which not infrequently develop from the nodules of conjunctivitis lymphatica, situated in the limbus. Even extensive suppuration of the cornea, as in acute blennorrhœa, abscess, etc., always leaves a narrow rim of cornea intact, which, to be sure, is often not of sufficient size to render an iridectomy for the restoration of vision possible.

Corneal ulcers occur under many various *forms*, some of which are well characterized, partly by their etiology, partly by their aspect and course. These may be enumerated as follows:

1. In *conjunctivitis lymphatica*, as well as in *conjunctivitis ex acne rosacea*, we find small, superficial, generally marginal ulcers, which, as a rule, get well rapidly. They are the only ones that go over into the limbus.

2. The *vascular fasciculus* (keratitis fascicularis) is likewise observed in conjunctivitis lymphatica, and is produced by an ulcer making its way from the margin of the cornea farther and farther into the latter, and trailing after it a leash of vessels from the limbus (page 86).

3. *Catarrhal* ulcers are characterized by their crescentic shape, as well as by their position near the corneal margin, and concentric with it.

4. In *pannus trachomatosus* small ulcers frequently occur, which develop from the infiltration at the margin of the pannus. Sometimes along the margin of the pannus a whole series of such ulcers is found, which also may coalesce into one large crescentic ulcer. Other ulcers develop in the midst of the pannus in spots where the infiltration penetrates more deeply into the cornea and leads to ulcerative disintegration.

5. The *central, non-irritative* ulcer occurring in trachoma develops generally in the center of the cornea. It is distinguished by the absence of accompanying symptoms of irritation, so that often the disturbance of vision is the only thing that calls the patient's attention to his trouble. Objectively, the ulcer is distinguished by the fact that even during the progressive period it is but very slightly clouded, so that it scarcely gives any evidence of its presence except the loss of substance that it produces; it may therefore be very easily overlooked if we do not examine the cornea by carefully testing its reflex. It has a tendency to fill up incompletely with cicatricial tissue, so that a central facet remains which causes very great deterioration of sight by the production of irregular astigmatism.

6. Ulcers in *acute blennorrhœa* and in *diphtheria of the conjunctiva* begin relatively often in the lower half of the cornea. They generally spread rapidly, and often lead to destruction of the entire cornea, or even to panophthalmitis.

7. *Traumatic* ulcers of the cornea are, as a rule, small and superficial, and occur for the most part in elderly people. They are located in the zone of the cornea that lies in the palpebral fissure; the upper third of the cornea, which is covered by the upper lid, therefore generally is exempt from them. But besides these ulcers, which run a rapid course and are benign, others also occur—usually after inconsiderable injuries—which, from the beginning, give evidence

of greater malignancy, by having the yellowish tinge of pus, and also by the particularly opaque, yellow, and often somewhat swollen appearance of some portion of their margin; this latter showing the direction in which the ulcer then rapidly advances. Moreover, the symptoms of iritis with hypopyon set in early. These ulcers are closely related in every respect to abscesses of the cornea, in connection with which they will again be considered.

8. *Small marginal* ulcers of the cornea occur frequently in elderly people, especially of the male sex, without any conjunctival lesion or external traumatism being discoverable as their cause. They develop with pretty violent complications, but are scarcely of the size of a pin's head, and heal rapidly without penetrating deeply. They are particularly troublesome from the fact that they are prone to recur, so that many people have to go through with attacks of this kind of keratitis one or more times every year.

9. *Herpes corneæ febrilis* (rarely also *herpes corneæ zoster*, see § 42) may give rise to ulcers formed from the ruptured herpetic vesicles. These have the property of not penetrating deeply, but of being very prone to spread superficially. This superficial extension may take place in two ways: either the ulcer extends in all directions uniformly, in which case we have a large but quite superficial loss of substance everywhere surrounded by a narrow, sharp, usually festooned, gray, and infiltrated margin, which pushes its way farther every day; or extension takes place in certain directions only. In the latter case, from the loss of substance, which originally is small, gray striæ extend on one side or more into the transparent cornea, and grow constantly longer, at the same time becoming forked, and also sending out lateral branches. Thus there is produced in the cornea a very pretty gray figure which is branched like a tree, and often bears nodular swellings at the extremities of its branches—*keratitis dendritica* (Emmert). This branched infiltrate breaks down into an ulcer having the form of a deep, branched furrow, with gray margins inclosing it. Then this ulcer becomes clean and heals, leaving behind it an opacity, whose branched form allows us to recognize, even some time afterward, the nature of the antecedent affection.

10. *Ulcus rodens* (Mooren). A superficial ulcer develops from the margin of the cornea (usually the upper margin) with marked inflammatory complications. From the sound portion of the cornea it is limited by a gray, clouded margin, which is evidently undermined. This latter symptom is characteristic of ulcus rodens. After a short time the ulcer begins to grow clean and to cicatrize, becoming covered with vessels from the limbus. Just when one supposes the process to be nearing complete recovery, a relapse sets in with a return of the symptoms of irritation, and in this the ulcer pushes its way forward somewhat farther in the cornea. So the disease goes on with discontinuous attacks and intervening remissions, until the ulcer has covered the entire cornea. The latter is thus everywhere deprived of its superficial layers, and hence remains permanently clouded throughout its entire extent, so that vision is very greatly diminished. Perforation of the cornea in this affection has never been observed. This rare disease attacks elderly people, and not infrequently invades both corneæ either simultaneously or in succession. It was regarded as incurable as long as people were unacquainted with the cauterization of the cornea by means of the actual cautery. If, however, we destroy the margin of the ulcer by this means, the ulcer itself is sure to be cured.

The vascular fasciculus, keratitis dendritica, and ulcus rodens have the

common trait of creeping along slowly in the cornea, for which reason they are also designated by the name of serpiginous ulcers of the cornea.

11. *Atheromatous* ulcers develop in old cicatrices of the cornea, when the latter have undergone degeneration through the deposition of fat or lime, or when they are exposed to mechanical injuries (as, for example, when at the apex of a corneal staphyloma). These ulcers torment the patient by the frequency of their recurrence and the associated symptoms of irritation; they may also produce perforation of the cornea, and through this panophthalmitis.

12. In eyes which are rendered blind by *glaucoma absolutum*, either purulent ulcers or abscesses of the cornea may develop. These are ordinarily associated with considerable hypopyon, and frequently terminate either in perforation of the cornea with resultant hæmorrhages from the eyeball, or in panophthalmitis. Like atheromatous ulcers, they are caused by insufficient nutrition and innervation of the cornea, an insufficiency already made apparent from the insensitiveness of the latter. With both varieties of ulcers, the enucleation of the blinded eye is sometimes the only remedy that permanently relieves the patient of the tormenting, frequently recurring formation of ulcers.

The treatment of corneal ulcers has very recently made great progress, chiefly because of the introduction of *cauterization* by means of the actual cautery, which we owe principally to Gayet; for those very purulent and infiltrated, rapidly progressive ulcers, in the face of which we were often powerless, are just the ones that by this means are usually at once arrested. The application of the cautery is painless when cocaine is employed, and does not, as might be supposed, cause any marked irritation of the eye. On the contrary, after its application, the pains cease instantly, while the other symptoms of irritation abate. In private practice, when one has no other means to resort to, the head of a probe or of a knitting-needle, heated red-hot, may be employed for cauterization. The chief thing is to make the cauterization extensive enough. Perforation of the thinned floor of the ulcer can, with care, be easily avoided; should it occur, however, it has no bad results beyond what the perforation itself gives rise to, since the hot point is cooled at once by the outpouring aqueous humor. An opacity remains permanently at the cauterized spot; but since we only cauterize such places as would otherwise go on to purulent disintegration, the final opacity is not greater than it would have been in any case.

Among antiseptics, *iodoform* dusted in the form of a fine powder on the diseased spot is of most service; from other antiseptic remedies I have seen no special results accrue. I must say the same of *eserine*, which is employed by many in the place of atropine in purulent ulcers of the cornea, and also in abscesses of the cornea; so far from doing good, it seems to render the condition of irritation of the iris still greater, and leads to the formation of numerous posterior synechiæ. It is more indicated in those cases in which there exists near the margin of the cornea a small perforation, to the posterior aperture of which the iris has become applied after the escape of the aqueous humor. Here we may hope to produce, by means of eserine, so powerful a contraction of the sphincter iridis that the iris will be drawn away from the aperture, and thus the formation of an anterior synechia be prevented. On the other hand, if the site of perforation should be nearer the center of the cornea, so that the pupillary portion of the iris is applied to it, we must employ atropine in order to draw the iris from the opening. If, however, the iris has already fallen through the opening in the cornea, so that a real prolapse exists, neither

atropine nor eserine, as a rule, is able to release the iris from the wound and return it to the anterior chamber; in this case excision of the prolapse, after the method of Leber, is the only remedy. For clearing up corneal opacities, Adler has recommended electrolysis. The electrodes in the shape of two small metallic buttons are placed upon the clouded portion of the cornea, and a weak constant current is made to pass through them. This procedure, which even under cocaine is pretty painful, is probably chiefly applicable to quite superficial opacities.

2. Abscess of the Cornea.

37. The essential character of an abscess of the cornea consists in the fact that the purulent infiltrate is situated in the deep layers of the cornea (Fig. 28), so that by its disintegration a pus-cavity is formed, which is limited both in front and behind by still intact lamellæ of the cornea (*a*, Fig. 36). In this respect an abscess is distinguished from an ulcer, in which the collection of pus lies open anteriorly.



FIG. 36.—SCHEMATIC REPRESENTATION OF AN ABSCESS OF THE CORNEA.

Over the abscess, *a*, the surface of the cornea is sunken in. The posterior surface of the cornea is covered by a thin layer of exudate, *b*, which also covers the anterior surface of the iris, *d*, and the anterior capsule of the lens, *e*, and, becoming more considerable below, forms there the hypopyon, *c*.

Symptoms.—A recent abscess presents itself under the form of a grayish-white or yellowish disk, which occupies nearly or quite the center of the cornea. The opacity of the disk is greater at its edges than in the center; and generally the edges themselves show a particularly well-marked gray or yellow opacity in one special direction. The disk is surrounded by a delicate gray area, and frequently fine, radiating, gray striæ extend from the margin of the disk into the transparent part of the cornea. The surface of the cornea over the disk is dotted, and often at the beginning is raised some distance above the level of the surrounding parts. Soon, however, this spot is seen to be depressed, although not after the manner of a loss of substance as in the case of an ulcer, but simply in the sense of being sunken in or flattened out (*a*, Fig. 36). The rest of the cornea, too, that is not occupied by the abscess is less lustrous, and is occupied by a delicate uniform cloudiness which originates from a layer of exudate on the posterior surface of the cornea (*b*, Fig. 36). These changes in the cornea are always associated with a violent iritis. The aqueous humor is turbid, a hypopyon (*c*, Fig. 36) lies at the bottom of the anterior chamber, the iris is discolored and is fastened by posterior synechiæ to the lens-capsule. Corresponding to the severity of the inflammation are the violent symptoms of irritation: slight œdema of

the lids, intense injection of the conjunctival and ciliary vessels, photophobia, and pain, which latter often reach a very considerable height. Nevertheless there are cases also of torpid abscesses, which are associated with very slight symptoms of irritation.

The subsequent *course* is characterized by the enlargement of the abscess and by its transformation into an ulcer. The enlargement takes place chiefly in that direction, in which the margin is marked by a specially dense opacity—an opacity which not infrequently looks like a yellow crescent placed upon the abscess. As soon as the abscess has expanded to a certain extent, the corneal lamellæ that limit it anteriorly break down; the abscess opens externally. An extensive loss of substance now exists, upon the floor of which the collection of pus lies exposed; the abscess has changed into an ulcer. Soon after this, generally, those lamellæ of the cornea which form the posterior wall of the abscess are also destroyed, so that an extensive perforation of the cornea is produced. The contents of the anterior chamber, consisting of aqueous humor and pus, are evacuated, and a large prolapse of the iris forms.

While the abscess is going through with its process of development, the accompanying iritis keeps on increasing in the same proportion up to the time of perforation of the cornea; the hypopyon, too, keeps growing until it fills the greater part of the anterior chamber; and the pupil is closed by an exudation membrane.

After the perforation of the cornea has taken place, the irritative symptoms generally abate and the abscess itself may now come to a standstill. In other cases, however, the purulent disintegration of the cornea keeps on just the same, so that the latter, with the exception of a narrow marginal rim, is entirely destroyed. Panophthalmitis may even result from the suppuration passing over into the deep parts.

An abscess always leaves a very dense corneal cicatrix which can not be cleared up, and in which the iris is almost always incarcerated. Furthermore, in consequence of the iritis, there are usually left adhesions of the iris with the capsule (posterior synechiæ), and even a closure of the pupil by a membrane (occlusio pupillæ). The corneal cicatrix itself is in favorable cases flat, in unfavorable cases ectatic, so that the abscess ends by forming a staphyloma. If panophthalmitis has followed upon the abscess, a shriveling up of the eye (phthisis bulbi) takes place.

The clinical picture which is characteristic of abscess and by which the diagnosis is made is only present in the beginning of the disease. Its important features are *the disk-like form and central situation of the opacity, the more pronounced opacity of the margin in comparison with the center, the nature of the corneal surface which, at the site of the abscess, shows no loss of substance but only a depression, and finally the early and marked implication of the iris.*

The *prognosis* of abscess is always serious, as, on account of the malignancy of its course, it belongs to the most dangerous of the diseases of the eye, and, if not checked early, it generally ends in the production of blindness through an incurable opacity of the cornea. And even in the favorable cases, which either spontaneously or with the help of art come to a stop early, a dense, centrally situated opacity remains, so that usually the sight can only be restored by the performance of an operation (iridectomy).

38. Etiology.—An abscess originates in infection of the cornea by organisms which set up in it a purulent inflammation. The infection may take place in two different ways: it either comes from without, or it arises from within the body itself, in the blood of which substances that excite inflammation are circulating (metastatic abscesses).

1. Infection originating from without (*ectogenous infection*) presupposes two conditions: first, a lesion of the corneal epithelium, which in the normal state protects the cornea against the entrance of microorganisms; and, second, the presence of pyogenic organisms which find their way to the spot where the epithelium is wanting. Both of these conditions occur in many cases of injury of the cornea. The body which inflicts the injury may itself be the carrier of infection and inoculate the cornea with germs. Much more frequently the injury, by producing a loss of substance in the epithelial covering, simply affords the opportunity for the entrance of infection; the infecting germs being furnished by the secretion contained in the conjunctival sac. The injuries which in this manner lead to the formation of an abscess are, as a rule, very slight, consisting in a simple scaling off of the epithelium. Among such injuries, for example, is the scratching of the cornea with the finger-nail, a thing which children very often do to their mothers who are carrying them in their arms. A rough cloth, a leaf, or a branch grazing the cornea, and small foreign bodies, especially minute fragments of stone, which fly into the eye, likewise produce superficial injuries. According to some, those injuries of the cornea which are associated with contusion of the latter are especially disposed to the formation of an abscess. Even in those cases in which a typical abscess of the cornea has apparently originated spontaneously, it is probable that there has been an antecedent injury, since such slight injuries of the cornea as these are readily overlooked by the patients. Severe perforating injuries, and in a similar way operation wounds, may also in exceptional cases give rise to the formation of an abscess. Associated with the injury, as a second factor in the production of abscess, is the presence of a chronic lesion of the conjunctiva (catarrh or trachoma), or a blennorrhœa of the lachrymal sac (present in about one third of the cases of abscess), by which the infecting secretion is furnished.

The traumatic abscess attacks adults exclusively, and especially

those belonging to the working-class. These are more frequently exposed to injuries of all kinds, and, besides, more often suffer from neglected affections of the conjunctiva and lachrymal sac than the members of the well-to-do classes. Great heat favors the formation of abscesses, which are hence much more frequent in the hot season than in winter. For this reason reapers are not infrequently affected with abscesses, since in cutting the grain they scratch their eyes with its awns, and, besides, they do their work during the hottest days of the year.

In abscesses resulting from acute blennorrhœa and from diphtheria of the conjunctiva, there is likewise without doubt a penetration of phlogogenic germs into the cornea from the conjunctiva.

2. Infection by way of *metastasis*—i. e., by germs which are circulating in the blood (endogenous infection)—forms the basis of those abscesses which occur in acute infectious diseases, such as small-pox, scarlet fever, measles, typhus, etc. The form of abscess that results from *variola* is most frequently observed. In this case it makes its appearance not at the height of the disease but in the stage of desiccation, and, in fact, sometimes even in patients who have already left their beds. Hence it follows that it is not to be regarded as a small-pox pustule that is localized upon the cornea. Metastatic abscesses are found in children as well as in adults, and not infrequently affect both eyes so that total blindness can be produced by them.

Treatment.—In consideration of the rapid progress which an abscess usually makes, and which threatens the entire cornea with destruction, a particularly prompt and energetic interference is required. The treatment is partly medicinal, partly operative.

The *medicinal* treatment is the same as in purulent ulcers of the cornea—namely, the application of a bandage, atropine, iodoform, and moist and warm compresses. At the same time, any lesion of the conjunctiva or lachrymal sac that may happen to be present is to be suitably treated. This treatment is only adapted to the case of small recent abscesses without an excessively large hypopyon. It should be undertaken only under the condition that the abscess is closely watched, so that, in case the latter progresses in spite of it, we may immediately proceed to operative treatment.

Operative treatment must be initiated without delay in all severe cases of abscess, but is also required in the lighter cases when they resist the mild treatment. It consists either in the cauterization of the abscess by means of the actual cautery, or in its incision according to the method of Saemisch. *Cauterization* is performed in the same way as in the case of progressive ulcers of the cornea; special attention must be paid to the destruction of the progressive portion of the margin. Cauterization has the advantage over incision of not causing a perforation of the cornea, and hence of not giving rise to inclusion

of the iris. It is only suitable, however, for those abscesses that have not yet undergone perforation, and in which the hypopyon is not excessively large: for the latter is not removed from the eye by this method; it can disappear from the anterior chamber only by resorption. *Incision* of the abscess (puncture by Saemisch's method, see the section on operations, § 155) is effective in that it opens the pus-cavity freely, diminishes the tension upon the lamellæ of the cornea, and evacuates the hypopyon; it, however, entails the disadvantage of a frequently extensive inclusion of the iris. Incision is suitable for very extensive abscesses, for those in which perforation is imminent, and for those which are associated with a large hypopyon. We should not let the matter rest with a single performance of the incision, but must every day separate anew with a blunt instrument the edges of the wound, as they speedily reunite, and we must keep this up until the abscess begins to grow clean. At the same time that this operative procedure is being performed, the medicinal treatment above mentioned must be continued. Perforation and prolapse of the iris, when once they have occurred, must be treated in the same way as has been given for perforating ulcers (page 148).

According to our present views, purulent inflammations everywhere are, with rare exceptions, to be referred to the presence of Schizomycetes, and especially to the Staphylococci, discovered by Ogston and more accurately described by Rosenbach. In the special case of purulent inflammations of the cornea, the presence of fungi has for a long time been a matter of demonstration, and here too, in the great majority of cases, we have to do with the ordinary pus fungi, in rare cases with fungi of another sort. Thus Leber has found the Aspergillus glaucus in the cornea in a case in which the injury had been produced by a beard of oats; similarly, in a case of injury by a pear, an undetermined species of Hyphomycetes was discovered by Berliner in the inflamed cornea. In both cases the fungus had, without doubt, been introduced into the cornea through inoculation by means of the foreign body which caused the injury. Experiments also for the production of inoculation designedly were made early. Eberth was the first to show that, by making inoculations with fungi in the cornea, fungus colonies developed, which may make their way between the lamellæ of the cornea, so that a cloudiness in the form of a rosette is produced surrounding the site of inoculation. Such cultures were successful when made with septic substances of all kinds, and also with pure cultures of fungi; and, in fact, not only the ordinary fungi of pus, but also cultures of the higher fungi, like Aspergillus glaucus and Leptothrix buccalis, are adapted for this purpose. By inoculations of this sort we usually get severe purulent inflammations, which spread rapidly, and result in purulent iritis or even panophthalmitis, probably on account of the migration of the fungi to the deep portions of the eye.

The micro-organisms, whose presence in the suppurating cornea has been demonstrated, are also without doubt the real exciting cause of the suppuration. Traumatism alone, without infection, does not give rise to suppuration. We may cut, scrape, crush, or, in short, injure in any way, or even cauterize

the cornea of an animal without getting any purulent inflammation of it; in every case simply a gray cloudiness develops, which generally disappears again quickly. But when, by repeatedly touching the conjunctiva with nitrate-of-silver solution, we have artificially produced a conjunctival catarrh, and in this way have given the opportunity for the production of infection, we then see purulent infiltration follow upon these same lesions of the cornea (Thilo). What is true of the cornea of animals is also true of that of man. Provided we avoid infection by cleanliness and antiseptic measures, we can with impunity subject the cornea to operations both light and severe; even contusions of the cornea, such as, for example, are often enough produced in the expression of a cataract, do not always by any means lead to suppuration. But if we undertake the same operation in the presence of a conjunctival catarrh or a suppuration of the lachrymal sac, we risk the loss of the eye from a purulent infection of the wound.

Ulceration and abscess of the cornea are hence varieties of suppuration caused by infection, with this difference between the two, that in an ulcer the suppuration is superficial from the beginning; in an abscess, on the other hand, it begins in the depth of the tissues. Upon this distinction, in part at all events, the difference in course is based. Since in the case of ulcers the infiltrated superficial lamellæ of the cornea soon break down, the focus of suppuration lies bare, and thus presents favorable conditions for healing. In the case of an abscess, the focus of suppuration is shut in, behind and in front, by strong layers of solid corneal tissue, which for quite a long time offer resistance to the destructive action. The pus that is formed can not therefore escape, but remains under a high pressure, which impels it still farther between the lamellæ of the cornea and thus favors the extension of the suppuration. There are, nevertheless, ulcers of the cornea which are closely related to abscesses. These are the traumatic ulcers, mentioned on page 151, which, like abscesses, are distinguished by their color—which is yellow like pus—by their strongly infiltrated margin, and by the early implication of the iris. Like abscesses, they develop in consequence of slight superficial injuries, and the course they run resembles in its severity that of an abscess. There is no doubt that, in their essential nature, these ulcers are identical with abscesses; they are, as it were, abscesses so superficially situated that in an exceedingly short time they are converted into ulcers by the breaking down of the superficial lamellæ of the cornea. They are hence comprised by many authors under the same head as abscesses. Saemisch calls them *ulcus serpens*, on account of the peculiar property of spreading in one special direction; Stellwag designates them as *ulcus septicum*, on account of their development by way of infection; Roser has described them as *hypopyon-keratitis*, because they are regularly accompanied by iritis with hypopyon. The malignant forms of corneal suppuration thus designated differ so very much, both in respect to their appearance and their course, from the various kinds of ordinary corneal ulcers, that we must assume a particular kind of infection for them. Either we have to do with a particularly virulent kind of pus-cocci, or the microbes find more favorable conditions for their multiplication than in the case of the ordinary varieties of purulent keratitis.

One must not conceive of the corneal abscess as a sharply circumscribed cavity filled with fluid pus; the focus of suppuration, on the contrary, is traversed by numerous fibers and lamellæ, the remains of the corneal tissue, so that it presents a kind of reticulum, in the spaces of which small quantities of a

pretty consistent pus are found. That the quantity of the pus, especially in the central portion of the abscess, is very scanty, can be inferred from the fact that the surface of the cornea over the abscess is sunken in. The pus in the anterior chamber also is generally not fluid, but of tough consistence, so that, after the incision of the abscess, it can be drawn out of the eye with the forceps in the form of a viscid mass.

We sometimes see small abscesses which are almost perfectly transparent throughout their greater part, while it is only the edge marking the direction in which the abscess is progressing that shows a marked gray or yellowish opacity. In such a case one might, at first sight, suppose that he were looking at a yellow crescent in an otherwise healthy cornea; it is only in making a more precise examination that one recognizes, adjoining the crescent, a rounded depression of the surface and a corresponding faint opacity. Those abscesses also which are associated with a very large hypopyon are very hard to recognize aright, because the abscess does not show off well upon the yellow background of the hypopyon. In such a case it is often only after puncture of the cornea and evacuation of the hypopyon that it is possible to determine exactly the limits of the abscess. For the connection between abscess and hypopyon, see page 136.

Abscesses sometimes occur in both corneæ simultaneously, especially in small-pox; but two abscesses have never been observed at the same time in the same cornea. In rare instances it has been observed that in a cornea bearing a cicatrix which had originated in an abscess, a second abscess subsequently developed in the portion that still remained transparent.

Exceptionally it happens that an abscess is not converted into an ulcer by the breaking down of its anterior wall, but that resorption of the pus takes place. Nevertheless, even in this case a dense opacity of the cornea remains, which, if the abscess was of great extent, may be associated with vascularization and flattening in the cornea. Such cases are known as *abscessus siccus*.

The treatment of corneal abscess had in general but little success to chronicle until Saemisch substituted the operation of *incision* of the abscess for that of paracentesis, of iridectomy, etc., previously in vogue. In performing the operation, we must take care not to injure the lens and not to let the escape of aqueous take place too suddenly. The hypopyon is either evacuated spontaneously, especially if the patient makes pressure with his lids, or it can be grasped by means of a forceps introduced into the wound, and drawn out. In consequence of the diminution of pressure after the escape of the contents of the anterior chamber, hæmorrhages often take place from the iris, which, already hyperæmic before the operation, now becomes still more distended with blood. This is probably the cause of the violent pain which regularly follows upon the evacuation of the contents of the anterior chamber, although the incision itself is but little felt. After incising the abscess we always get an attachment of the iris to the cornea during healing, which, however, would not have failed to occur, even apart from the operation, in those cases in which incision is indicated at all.

Prophylaxis against the formation of abscesses is possible in the sense of our being able to remove in season the source of infection, as, for instance, the secretion from a lachrymal sac affected with blennorrhœa. If, in such a case, a small erosion of the cornea exists, this is to be treated with special care by the application of disinfectant remedies. Even in cases of metastatic abscesses of

the cornea, prophylaxis undertaken in season would often prevent the infliction of great injury. During an eruption of small-pox the lids are much swollen, and hence are not opened by the patient, and even the physician generally neglects to look at the eye from time to time. In that case, when the swelling of the lids goes down during the stage of desiccation and the patient opens his eyes again, the morbid process in the cornea is often already in progress, and we are just so much behindhand in undertaking the treatment. Horner, therefore, is right in demanding that a physician treating a small-pox patient should prevent the agglutination of the lids by applying a pledget smeared with ointment, should examine the eyes every day, and should cleanse the conjunctival sac with antiseptic solutions. Careful watching will enable us to recognize the very commencement of the corneal disease, which in these early stages, presents the most favorable conditions for treatment. At the time when small-pox was very wide-spread it formed one of the most frequent causes of blindness, so that about one third of all cases of blindness were produced by it. Since small-pox, owing to the introduction of vaccination, has become less prevalent, the blindness due to it has correspondingly diminished. Thus, in France, before the introduction of vaccination, thirty-five per cent—and after its introduction seven per cent—of all the blind lost their eyesight by reason of small-pox (Carron du Villards). In Prussia, before the introduction of compulsory vaccination, thirty-five per cent—after its introduction two per cent—of all the blind people in the country were rendered so by small-pox.

3. Keratitis e Lagophthalmo.

39. Keratitis e lagophthalmo originates from a desiccation of the cornea in consequence of its being insufficiently covered by the lids. The conjunctiva of the eyeball, wherever it lies constantly exposed to the air in the open palpebral fissure, appears reddened, and generally somewhat swollen as well. It secretes a small amount of discharge drying upon the conjunctiva in crusts, which not infrequently also cover the exposed portion of the cornea. After removing the crusts we find the lowermost part of the cornea (for it is this part which is exposed in the palpebral fissure) dry on the surface, dull, slightly depressed, and at the same time clouded and gray. In the subsequent course of the disease the cloudiness becomes more and more intense, until finally disintegration of the superficial layers of the cornea takes place, with the consequent formation of an ulcer. This latter extends below as far as the margin of the cornea, while above it reaches a greater or less distance, according to the extent to which the cornea is uncovered, and ends in a horizontal border. At the same time there exists iritis with hypopyon. The ulcer may heal without perforation, but leaving an opacity behind it, or it may perforate the cornea and thus lead to prolapse of the iris, or even to panophthalmitis.

The *cause* of keratitis e lagophthalmo is the desiccation of the cornea in consequence of the defective closure of the lids (lagophthalmus). This latter arises either from mechanical obstacles, such as contraction of the lids, marked protrusion of the eyeball, etc., or from paralysis of

the orbicularis palpebrarum. In high degrees of lagophthalmus the cornea is uncovered all the time; in lighter cases, on the contrary, in which the closure of the lids is not impossible but only impeded, the danger of desiccation taking place is particularly present during sleep. In daytime, owing to the feeling of dryness of the cornea, the act of winking is pretty frequently excited through reflex action, and thus the cornea is repeatedly moistened. But in sleep the reflex winking of the lids is absent, and hence the cornea is unmoistened by this means and becomes dry wherever it lies exposed in the open palpebral fissure. The desiccation in this case always affects the lowermost part of the cornea, because in sleep the eyeball is turned upward, and hence the lower part of the cornea lies in the palpebral fissure. (An exception is made by those cases in which the eyeball has lost its freedom of movement—e. g., as a result of an exophthalmus, in which case other portions, and particularly the central portions, of the cornea may be exposed to desiccation by being within the palpebral fissure.) The corneal lamellæ, as fast as they become desiccated, die and are cast off by a process of suppuration. Quite the same results ensue if the lids, on account of a clouding of the consciousness, are incompletely closed, as is the case in persons who, in severe diseases, lie unconscious for a long time. If such patients escape with their lives, they may have opacities of the cornea in both eyes in consequence of keratitis e lagophthalmo, or they may lose their eyes altogether.

The *treatment* consists in taking care that the cornea shall be covered by the lids. In this way the development of a keratitis is prevented through prophylaxis, or, if it already exists, the chief condition is afforded for its cure. We must accordingly initiate the proper treatment for the cure of the lagophthalmus (see § 113), and in the mean time, until a cure has been accomplished, take pains to effect a perfect closure of the lids by means of a properly applied bandage. In order to do this, it is generally necessary to fasten the lids themselves together by strips of sticking-plaster before the bandage is applied over the eye.

In slight cases of lagophthalmus it is sufficient to keep the eye bandaged through the night only. But if the lagophthalmus is considerable, or if keratitis has already set in, the eye must be kept bandaged all the time. If the treatment is initiated early, the prognosis is good, inasmuch as the process comes to a standstill as soon as the desiccation of the cornea is arrested.

4. Keratomalacia.

40. Symptoms and Course.—Keratomalacia* occurs only in childhood. The disease begins with night-blindness (hemeralopia). This

* Softening of the cornea, from [κέρας, horn, and] μαλακός, soft.

consists in the patient's visual power being perfectly good in bright daylight, but so very greatly reduced when the illumination is diminished (e. g., in twilight) that they are often no longer in a state to go about alone. In very small children who do not go about alone yet, this symptom naturally can not be made out. In such children, the first thing that strikes us is the dryness of the conjunctiva, which next develops, and which appears under the form of triangular xerotic spots on both sides of the cornea (see page 112). The conjunctiva in these spots is covered with a fine white substance like foam, and seems as if smeared with grease in such a way that the lachrymal fluid can not moisten it. The dryness extends rapidly over the rest of the conjunctiva and also over the cornea. The latter becomes dull, insensitive, and uniformly cloudy. Soon the cloudiness in the center of the cornea increases, a gray infiltrate forming there. This spreads rapidly, takes on the yellow color of pus, and terminates in the disintegration of the cornea—a disintegration which, in bad cases, may take place within a few hours. In the beginning the affected eye is not discolored; afterward, when the cornea is already greatly involved, there appears about the latter a dusky venous injection. The lachrymal secretion is not increased, but rather diminished; moreover, other symptoms of irritation, like photophobia and blepharospasm, are slight or are wanting altogether. The striking contrast between the severity of the corneal affection and the insignificance of the accompanying symptoms of irritation, together with the dryness of the eye, stamps the disease with quite a peculiar character. This affection usually attacks both eyes.

Children suffering from keratomalacia show a disturbance of the general condition, which is generally pronounced even before the outbreak of the eye-trouble, and which afterward grows still greater. The children become strikingly apathetic, have diarrhœa alternating with constipation, sink rapidly, and ultimately many of them die either from exhaustion or from a complicating bronchitis or pneumonia.

The *prognosis* in very small children is bad, as in most cases they lose not only their eyes, but their life as well. In somewhat older children the disease runs a less severe course, so that they escape with their life and get off with smaller or larger cicatrices of the cornea; indeed, the cornea itself may subsequently clear up once more (Gouvea).

Etiology.—Keratomalacia is the result of an insufficient nourishment of the cornea, which evidently is only one of the symptoms of a severe general disease. The real nature of the latter is indeed at present unknown to us, although there are various facts that do not permit us to doubt its existence. Thus the hemeralopia is nothing but the expression of the depressed nutrition of the retina. The latter still performs its functions well when it is acted upon by powerful impressions, such as images made by a strong light. But as soon as the brightness of the images falls below a certain limit, the images of the

object are no longer able to excite the retinal elements, the energy of which has been depressed (torpor retinæ). This condition may be set down to the general apathy of these patients. Another thing that points to a severe general disorder is the rapid decline of strength, which often develops in an altogether inexplicable fashion even in those cases in which the children at the beginning of the disease were apparently healthy.

Keratomalacia develops, as a rule, in consequence of enfeebling influences affecting the children, and acting detrimentally upon their nutrition. Among these influences belong insufficient or unsuitable nourishment (rearing of children by hand), severe diseases like scarlet fever, measles, typhus, etc., and particularly hereditary syphilis. The disease occurs in Russia much more frequently than with us, as there it attacks infants during and after the time of the great fast, because during this period the mothers lose their milk in consequence of fasting. For a similar reason it is frequently observed in Brazil among the badly nourished children of the negro slaves.

Keratomalacia does not occur in adults, although a similar affection does. This latter is constituted by hemeralopia with simultaneous xerosis of the conjunctiva, without, however, there being any implication of the cornea, and without the existence of marked disturbances of the general condition (see page 112). Whether this disease, the development of which likewise is favored by poor nourishment, is identical with the one above described, and represents, as it were, a very mild form of it, or not, has not as yet been decided.

The chief task that *treatment* has to accomplish is to support the child's strength by means of fitting nourishment. In addition we must try to stimulate the vitality of the tissue of the cornea, a thing best performed by means of moist and warm compresses placed upon the eyes. If the apathetic little patients do not close their lids properly, the corneæ must be protected from desiccation by bandaging the eye.

5. Keratitis Neuroparalytica.

41. Symptoms.—The cornea becomes dull and slightly cloudy. Then the epithelium begins to be thrown off, first at the center, then more and more in the direction of the periphery, until at length the entire cornea, with the exception of a marginal rim two to three millimetres broad, is bared of its epithelium. This gives the cornea quite a peculiar appearance, such as is found in no other disease of it. In the mean time the cloudiness of the cornea also has increased. This is most marked in the center, and there is uniformly gray; toward the margin it gradually decreases, and may be resolved by the magnifying-glass into separate gray maculæ. Subsequently the hue of the cloudiness becomes yellowish, hypopyon sets in, and ultimately the cornea in

its center breaks down into pus. Thus a large ulcer forms, which cicatrizes with inclusion of the iris, and generally with flattening of the entire cornea. Not all cases, however, run so severe a course; the keratitis may get well without the occurrence of any purulent disintegration of the cornea, although there always remain an opacity of considerable dimensions, and often, besides, a flattening of the cornea.

The course of the disease is slow, and is characterized by the slightness of the associated symptoms of irritation. There is, indeed, marked ciliary injection but no lachrymation, since the secretion of the lachrymal gland, being produced by reflex action, is diminished or abrogated. If the patients weep, the eye of the diseased side remains dry. Pain, evidently, is absent altogether on account of the simultaneous presence of paralysis of the trigeminus.

The *prognosis* is unfavorable, treatment having very little influence on the course of the disease, which, whether the formation of ulcers does or does not take place, leads, almost without exception, to the production of a dense opacity over the entire cornea, and hence to an almost complete annihilation of the visual power.

Keratitis neuroparalytica has its *cause* in a paralysis of the trigeminal nerve, which induces trophic disturbances in the cornea. The paralysis of the trigeminus also causes the simultaneous arrest of secretion of the lachrymal gland as well as the absence of pain. It is a matter of indifference whether the lesion which causes the paralysis of the trigeminus affects the trunk of the nerve or its nucleus of origin in the brain.

The *treatment* consists in the application of a bandage, warm compresses, and atropine. Besides, we may try electricity, or, following Nieden's recommendation, strychnine (three to five milligrammes by hypodermic injection beneath the skin of the temple).

The three affections of the cornea just described—keratitis e lagophthalmo, keratitis neuroparalytica, and keratomalacia—have been frequently confounded with each other. Thus the keratitis e lagophthalmo, which makes its appearance in patients during the death-agony, has been regarded as a keratitis neuroparalytica, its cause being attributed to the depressed state of the nervous influence. Conversely, some have explained keratitis neuroparalytica and keratomalacia as produced by desiccation of the cornea, and in this way have placed them in the same category with keratitis e lagophthalmo. Many authors deny absolutely the existence of keratitis neuroparalytica as an independent affection. Hence this latter should be the first to receive careful consideration.

The theory of *keratitis neuroparalytica* was founded by Magendie, who found that after section of the trigeminus in animals a keratitis made its appearance. He referred this to trophic disturbances. Snellen and Leuftleben showed that the development of keratitis could be prevented by sewing to the eye a metallic capsule (the lid of a pipe). They hence concluded that the keratitis did not depend upon trophic disturbances, but was to be referred to traumatism; for, as the animal has become destitute of sensation on the side

operated upon, he strikes his eye against everything or rubs it against objects —e. g., against the walls of the cage in which he is confined. But inasmuch as simple mechanical injuries produce only attacks of cloudiness in the cornea, which rapidly pass off and never produce attacks of purulent keratitis like keratitis neuroparalytica, the further assumption had to be made that the cornea, in consequence of the trigeminal paralysis, has a diminished power of resistance against external injuries. Then Feuer, by experiment, proved the incorrectness of this explanation. After section of the trigeminus, the cornea can be injured in any way whatever beneath the metallic capsule sewed on in front of it, without anything but transient cloudiness of the cornea being produced. Hence, after section of the trigeminus, the cornea reacts toward external injuries just as it did before, and the cause of the efficacy of the metallic capsule must be sought for in something besides the prevention of traumatism. Feuer thought that he had found it in the fact that the metal capsule prevents the desiccation of the cornea. For in trigeminal paralysis the act of winking produced by reflex action is abolished; consequently the cornea becomes dry in its central, most exposed portion, and a delimiting suppuration develops about this dried and necrosed area. This sort of keratitis, which Feuer designated with the name of keratitis xerotica, is the alleged keratitis neuroparalytica. He was able to excite just the same sort of inflammation by producing lagophthalmus artificially in animals with an intact trigeminus. For this purpose he sewed the two lids and the nictitating membrane so far back that they could no longer cover the cornea. Hence the efficacy of the metal capsule, after section of the trigeminus, consisted, according to him, only in the fact that it prevents the desiccation of the cornea; for, as the animals strike the capsule against the walls of the cage, they push the lids, to which it is fastened by sutures, in different directions over the cornea [and so moisten the eye]. Hence, too, Feuer was able to obtain the same effect with an open ring of cork, which he sewed in front of the eyes. Then Feuer applied his results to man, and demonstrated that the keratitis which is seen to develop in soporose patients is clinically and anatomically identical with that which is developed in animals and men through imperfect covering of the cornea (keratitis e lagophthalmo). He went too far, however, in denying altogether the existence of a true keratitis neuroparalytica.

There is no doubt that the keratitis which is sometimes in man observed in connection with trigeminal paralysis is in solitary instances caused by desiccation of the cornea, and thus is a keratitis e lagophthalmo. The desiccation is produced by the abolition of the regular movement of the lids and by the deficiency of the secretion of tears. In this way, for instance, are those cases to be explained in which paralysis of the oculo-motor nerve, and consequently incomplete ptosis, exist at the same time with paralysis of the trigeminus, and in which the cornea, as occurs in keratitis e lagophthalmo, is affected only in its lowermost portions which are not covered and protected by the drooping upper lid. But there are cases, nevertheless, which present the characteristic picture of genuine keratitis neuroparalytica as above described—a picture which is altogether different from that of keratitis e lagophthalmo. Moreover, it is developed in those cases of trigeminal paralysis in which the movements of the lids and the moistening of the cornea are perfectly normal, or in which, in consequence of complete ptosis, the cornea is entirely covered by the lid, and is thus protected from desiccation. Furthermore, since the application of a band-

age, which is a sure preventive of keratitis e lagophthalmo, is of no avail against the development of a true keratitis neuroparalytica, the latter can not depend upon desiccation of the cornea. Again, the frequently repeated injuries to which the development of keratitis neuroparalytica in animals has been referred can not be thought of as existing in the case of a human being who takes good care of his eye. Hence we can only explain keratitis neuroparalytica by the assumption of a trophic disturbance. The fact that it does not occur in all cases of trigeminal paralysis is no evidence to the contrary, for the disease may have affected only the sensory and not the trophic fibers of the trigeminus. The trophic fibers, according to the views of different authors, arise from the sympathetic and attach themselves to the medial aspect of the trunk of the trigeminus. In fact, keratitis neuroparalytica has been obtained after sections of the trigeminus affecting only the innermost fibers of the nerve, although, in consequence of the sensory fibers being intact, the cornea and the lids have retained all their sensitiveness. We are therefore obliged to acknowledge the existence of a genuine keratitis neuroparalytica, and to make a sharp distinction between it and keratitis e lagophthalmo.

The confounding of the three forms of keratitis—keratitis e lagophthalmo, keratitis neuroparalytica, and keratomalacia—with each other has been favored by the fact that they display various features in common. Among these are the dryness which the eyes exhibit, and also the insignificance of the irritative symptoms in comparison with the severity of the keratitis, an insignificance shown in the absence of increased lachrymal secretion, of blepharospasm, and often also of pain. And yet the *dryness of the eyes* in these three forms of keratitis is to be referred to very different causes.

(*a*) In keratitis e lagophthalmo an actual desiccation of the cornea from evaporation exists. It affects only the exposed portion of the cornea, and may be relieved by closure of the lids. The desiccation in this case is the one cause of all the subsequent changes.

(*b*) In keratomalacia the cornea is not actually dry, but only looks so, because the lachrymal fluid does not adhere to its surface. This dry appearance is present even when the eye is swimming in tears or when it is kept constantly closed; evidently, bandaging is of no effect against this sort of dryness. It is caused by a fatty metamorphosis of the epithelial cells, which consequently are not wetted by the lachrymal fluid. Moreover, the bacilli of xerosis, discovered by Kuschbert and Neisser, may be found in the altered epithelium.

(*c*) In keratitis neuroparalytica there is neither real desiccation of the cornea, as in keratitis e lagophthalmo, nor a peculiar fatty condition of its surface, as in keratomalacia; on the contrary, the eye looks dry simply because, in spite of the marked inflammation of the cornea, the lachrymation, which we usually see under these circumstances in other cases, is absent. The secretion of the lachrymal gland is in fact diminished or altogether abrogated; nevertheless, the moistening of the eye is quite sufficient, as indeed it is after extirpation of the lachrymal gland.

The *absence of marked symptoms of irritation*, which characterizes these three varieties of keratitis, is accounted for in the keratitis e lagophthalmo of very sick people and in keratomalacia by the general depression of strength, and in keratitis neuroparalytica by the insensitiveness of the eye. The irritative symptoms, which in other cases are put in action through reflex impulses originating in the sensory nerves, are absent in the case of paralysis of the trigeminus.

The three forms of keratitis are hence, in spite of their external similarity, entirely different from each other, and can be readily differentiated by the clinical picture which they present. Keratitis e lagophthalmo occupies, as a rule, the lowermost part of the cornea. Keratomalacia begins in the center of the cornea, and is found only in children who are the subjects of a rapid decline of nutrition. Finally, keratitis neuroparalytica is characterized most of all by the rapid exfoliation of epithelium over the whole extent of the cornea, and does not occur except in conjunction with a trigeminal paralysis which can be diagnosticated at once. The confusion between the three varieties of keratitis just described is furthermore favored by their nomenclature. The designation keratitis xerotica, chosen by Feuer for the keratitis of desiccation (keratitis e lagophthalmo), would be quite a good one if it did not lead to confusion with simple local xerosis of the cornea on the one hand and on the other with keratomalacia, in which xerosis of the conjunctiva and cornea likewise exists. And, as a matter of fact, some authors designate keratomalacia under the name of keratitis xerotica. In order to avoid this confusion, I have dropped the expression keratitis xerotica altogether; and as I do not wish to increase the number of epithets still further by the invention of a new name, I use the old expression keratitis e lagophthalmo for the keratitis of desiccation.

B. Non-suppurative Keratitis.

(*a*) *Superficial Forms.*

42. 1. Pannus.—Pannus consists in the new formation of a tissue resembling granulations directly beneath the epithelium of the cornea. Pannus is to be looked upon as an affection of the conjunctival layer of the cornea (conjunctiva corneæ, see page 125), and in every case is simply one of the symptoms of a conjunctival disease—that is, either of conjunctivitis trachomatosa or conjunctivitis lymphatica. We hence make a distinction between pannus trachomatosus and pannus lymphaticus. For further particulars, see under these two diseases of the conjunctiva.

2. **Keratitis with the Formation of Vesicles.**—Vesicles on the cornea are generally small, and are filled with a limpid liquid. Their anterior wall is very frail, for it is formed simply by the epithelium of the cornea, which is lifted up from Bowman's membrane by serum. More rarely larger-sized blebs (bullæ) occur, the anterior wall of which generally consists of a new-formed connective tissue in addition to the epithelium, and is hence more resistant. The small vesicles are ordinarily present in some numbers, while the large blebs generally occur singly. Violent symptoms of irritation, such as ciliary injection, lachrymation, photophobia, and more especially great pain, are usually present during the development of the vesicle. These, doubtless, are caused by the pulling upon the corneal nerves which pass into the epithelium, and which, in the process of formation of vesicles, are first stretched and finally torn in two. The irritative symptoms ordinarily disappear with the rupture of the vesicles. This occurs so quickly in the case of

small vesicles that we generally do not get a sight of these themselves at all, but only of the subsequent small defects in the epithelium, to the margins of which the epithelium that had been lifted up still adheres in loose shreds. The large blebs, on account of the greater firmness of the anterior wall, are of longer duration. They are not tightly distended, but form a lax, tremulous, somewhat dependent sac. After their rupture the lax anterior wall still lies upon the cornea, and can be readily made out by the way in which it can be displaced by movements of the lids. The sensitiveness of the cornea to touch is ordinarily diminished or entirely abrogated in cases in which there is a formation of vesicles.

There are the following varieties of keratitis with the formation of vesicles:

(α) *Herpes* Febrilis Corneæ* (Horner).—In febrile diseases, especially of the respiratory organs (most frequently in epidemic influenza, next oftenest in bronchitis, pneumonia, ordinary influenza, etc.), less frequently in other febrile diseases, like typhus, intermittent fever, etc., small vesicles often make their appearance on the lips, the alæ of the nose, the eyelids, the ears, etc.† At the same time an eruption of small transparent vesicles, which are associated with violent symptoms of irritation, may occur upon the cornea. These are scarcely the size of a pin's head, and are often disposed in rows or in groups. The vesicles very speedily rupture and leave small losses of substance, the floor of which shows a faint opacity. Generally these soon heal, so that after two or three weeks the disease is over, without leaving any lasting opacity of the cornea. In severe, and especially in neglected, cases, however, large corneal ulcers, which not infrequently have a branching form (keratitis dendritica, see page 152), may develop from the small losses of substance.

There is no doubt that the vesicles upon the cornea are entirely analogous to those which develop upon the skin. Just as the latter are generally present only upon one side of the face, so also the affection of the eyes is usually unilateral in its development, and is, moreover, confined to the same side as the vesicles upon the face. With careful treatment the prognosis is good, as in that case the disease generally gets well without leaving any opacity. The treatment is purely symptomatic, being that which is indicated for corneal ulcers generally—that is, in the main, the employment of a protective bandage and of atropine.

(β) *Herpes Zoster Corneæ.*—This is one of the symptoms of herpes zoster‡ ophthalmicus—that is, zoster which is localized in the region

---

* From ἕρπειν, to creep.

† Hebra's herpes facialis.

‡ = girdle-eruption, from ζωστήρ, girdle. We also speak of it as zona ophthalmica.

of distribution of the trigeminus (see the section on diseases of the lids, § 107). The cornea participates in the morbid process by forming small vesicles, which generally are arranged in groups and rupture speedily, as in the case of herpes febrilis. The subsequent course of herpes zoster is distinguished from that of herpes febrilis by the continuance of the irritative symptoms after the rupture of the vesicles, and by the marked opacity of the parenchyma of the cornea at the spots where the vesicles were situated. It takes some time for the opacities to disappear, nor is it always the case that they disappear completely. Hence the disease runs a chronic course, and often leaves permanent opacities of the cornea after it. Naturally this is even more true of those cases in which large ulcers develop from the vesicles. The insensitiveness of the cornea to touch is especially pronounced in herpes zoster. The prognosis of this variety of herpes, from what has just been said, is less favorable than that of herpes febrilis; the treatment is the same.

(γ) *Keratitis Vesiculosa* (*et Bullosa*).—This variety occurs in eyes the cornea of which is more or less clouded and insensitive; in eyes with a large corneal cicatrix, or eyes which have been rendered blind by irido-cyclitis, or by increase of tension. Either vesicles which are small and of short duration form with the accompaniment of violent inflammatory symptoms upon the cornea (keratitis vesiculosa), or large tremulous bullæ develop, which last for several days before they rupture (keratitis bullosa). In all cases the vesicles show a great tendency to take on frequent recurrences, in each of which the irritative symptoms set in anew.

The cause of the formation of vesicles appears to lie in the abnormal conditions of the lymph circulation which are without doubt present in such eyes. By stasis of the lymph, œdema of the cornea is produced; the œdematous fluid penetrates forward until it gets beneath the epithelium, and then lifts the latter up in places from Bowman's membrane.

The prognosis is so far unfavorable in that the disease frequently recurs, on which account the affected eye, besides being useless for purposes of vision, is the source of constant discomfort to the patient. Treatment should aim at relieving the condition of irritation produced by the eruption of vesicles, and at preventing the recurrences. The former object is attained by opening the vesicles, the smaller ones being pricked, and in the case of the larger ones the anterior wall being removed. In order to prevent a recurrence of the vesicles, we may touch the raw spots occurring upon the cornea after the opening of the vesicles with a nitrate-of-silver solution, or we may remove the most superficial layers of the cornea in these spots. Sometimes we do not put a stop to the recurrences until we have improved the conditions for the nutrition of the eye by means of an iridectomy; we may even find our-

selves compelled to perform enucleation of the diseased eye in order to give the patients ease.

With reference to the forms of keratitis associated with the formation of vesicles there has been a good deal of confusion, partly referable to the lack of clearness in the nomenclature. The two forms of herpes corneæ (herpes febrilis and herpes zoster) are distinguished from keratitis vesiculosa and bullosa by their attacking a cornea which previously was healthy. Stellwag uses the expression herpes corneæ in quite a different sense, designating by this term the efflorescences of conjunctivitis lymphatica when they develop upon the cornea. The expression in this sense, if we wish to employ it at all, should only be used with the express addition of "herpes corneæ according to Stellwag."

Apart from the forms above described, the formation of vesicles upon the cornea is further, in rare cases, observed under special conditions—e. g., as a result of the action of various, and particularly of corrosive, substances upon the cornea, after burns, after a cataract operation beneath the bandage, etc. Cases also occur in which, without known cause, there develop upon a perfectly sound cornea vesicles or bullæ the formation of which we are inclined to attribute to nervous influences, as in the case of herpes febrilis and herpes zoster. Cases of this sort are usually characterized by periodical recurrence. I know one old lady who for twelve years has been obliged to suffer from occasional attacks of inflammation in her eyes, which otherwise are sound. The attack occurs once or twice a year, and affects sometimes one eye, sometimes the other. It is associated with violent pain, great photophobia, and profuse lachrymation. In the first days of the attack the only things found are œdema of the lids, great ciliary injection, and a cornea covered with minute elevations, as if it had been strewn with sand. Then a large transparent bulla develops upon the cornea, after the rupture of which the inflammatory symptoms rapidly abate, and the epithelial defect heals without leaving a trace behind.

In many cases of keratitis in which vesicles had formed upon the cornea it was observed that after the rupture of the vesicles fine filaments adhered to the losses of substance thus produced and hung down loose, for which reason these cases were called *filamentous keratitis* (Leber, Uthoff, Fischer). The filaments, when seen under the microscope, are composed of fine fibers twisted like a rope, and probably consist of coagulated fibrin.

Perhaps the cases of *recurrent erosion of the cornea*, which Arlt first described, belong under the head of keratitis with the formation of vesicles. Here a loss of substance of the corneal epithelium, originating in a superficial traumatism, heals without leaving any mark, only to form again after some time with violent symptoms of irritation. Some authors believe that the formation of a vesicle precedes the recurrence of the loss of substance, while others could not convince themselves of the existence of a vesicle.

A form of superficial keratitis which is related to herpes febrilis corneæ, but is not associated with the formation of vesicles, is *keratitis punctata superficialis*. It begins with the symptoms of an acute conjunctivitis. Changes in the cornea are observed either at the same time or not till some days or weeks afterward. These changes consist in the presence of minute gray spots which, as in the case of herpes febrilis, are often arranged in groups or in short rows. They are sometimes only ten to twenty in number, sometimes very abundant—upward of a hundred. They are either scattered irregularly over

the cornea, or they are chiefly massed together in the central portion; in every case, however, the marginal portions of the cornea are the part least covered by the spots. The spots lie in the most superficial layers of the cornea, which latter looks dull because the epithelium over the spots bulges out in the form of a nodule. The irritative symptoms soon disappear, but the spots, as well as the punctate look of the corneal surface, generally remain for months almost unchanged, and then very gradually disappear. If the spots are not numerous, the sight remains undisturbed; if, however, many spots are present, particularly in the center, the acuity of vision is reduced considerably. Keratitis punctata superficialis is found most frequently in young people, and affects sometimes one, sometimes both eyes. It often begins at the same time with a catarrh of the air-passages, just as herpes febrilis corneæ does, but is distinguished from the latter mainly by the absence of the formation of true vesicles. Hence, too, in keratitis punctata superficialis the superficial losses of substance, which develop from the vesicles in herpes, are wanting, and for the same reason the formation of ulcers in this variety of keratitis is observed only as a rare exception.

(*b*) *Deep Forms of Non-suppurative Keratitis.*

43. These forms have as a common characteristic the development of an infiltrate in the middle and deep layers of the cornea, an infiltrate, however, which shows no tendency toward purulent disintegration, but—generally not till after existing quite a while—disappears again by resorption. When this takes place, the cornea in favorable cases clears up again completely, while in other cases opacities of a varying degree of intensity are left, and are sometimes even accompanied by flattening of the cornea. In keeping with the deep position of the infiltrate in the cornea, the uveal tract, and especially the iris and ciliary body, are almost always implicated.

*3. Parenchymatous Keratitis.**

Symptoms and Course.—This affection may run its course in two ways, according as it begins, in the center or at the margins of the cornea. If the disease invades the *center* of the cornea first, we see small, dim, gray maculæ making their appearance in this situation, and lying in the middle and deep layers of the cornea; the surface of the latter is lusterless and dull. The number of maculæ gradually increases, so that they keep extending farther and farther toward the margin; but they are always massed most thickly in the center, where they frequently become confluent. Since even between the maculæ the cornea is not clear, but shows a fine diffuse cloudiness, the entire cornea may in severe cases ultimately look uniformly gray, like ground glass. As soon as the opacity of the cornea has advanced somewhat farther, vascularization begins by the penetration of vessels into the cornea from different spots upon the corneal circumference. We see

* Synonyms: keratitis interstitialis, keratitis profunda, keratitis diffusa, uveitis anterior.

the vascular trunks coming out from beneath the limbus, because—as opposed to the vessels in pannus—they arise from the deeply situated vessels of the adjacent sclera. They branch in tufts, like a brush, in the deep layers of the cornea, and often appear quite indistinct and of a dirty-red or grayish-red color, because they are covered by the clouded superficial layers of the cornea.

In those cases in which the disease begins at the *margin* of the cornea, the first thing that strikes us is that the latter has grown lusterless and clouded at some spot upon its margin. The cloudiness is deeply situated, and when regarded with the naked eye looks uniformly gray, but with the magnifying-glass can generally be resolved into separate maculæ or dim parallel streaks. Soon similar areas of cloudiness appear at other spots of the corneal margin, and then push their way forward concentrically from all sides toward the center of the cornea. Simultaneously with the appearance of the marginal opacities the corresponding portions of the limbus become injected and the vessels of the corneal margin begin to grow out. The formation of vessels, as far as it originates in the network of marginal loops in the limbus, soon comes to an end, so that the limbus advances only a little way out upon the cornea, where it looks red and swollen ("epaulet-like" swelling of the limbus). On the other hand, the deep vessels, which come out from beneath the limbus, grow farther and farther into the cornea, and follow closely upon the opacity which advances in front of them; it looks as if they were pushing the opacity before them. These vessels have, as in the case of those of the first form, the characters of deeply situated vessels, shown by their penicillate branching and by their dull, dead, grayish-red hue.

When parenchymatous keratitis has attained its acme, the cornea is often so opaque that we scarcely recognize the iris through it. At the same time it loses its luster completely, so that it looks as though smeared with grease (with the magnifying-glass we recognize numerous minute elevations of the epithelium, which make the surface of the cornea rough, as if made of fine shagreen). Sight is reduced to the mere recognition of the movement of the hand before the eye, or to the bare distinction between light and darkness. The process of recovery now begins gradually, starting from the margin, where the cornea first becomes transparent again, while at the same time the vessels grow constantly fewer and fewer. The center of the cornea remains opaque the longest, but finally clears up, too, until only a fine diffuse cloudiness remains, which causes but little impairment of sight. This cloudiness, together with a few very minute blood-vessels which are only visible with the magnifying-glass, can still be made out years afterward, and are certain signs of a parenchymatous keratitis that has once existed.

Parenchymatous keratitis always runs a chronic *course*. The in-

flammatory symptoms keep on increasing for one or two months, until the disease has reached its acme. Then the irritative symptoms very soon abate, and the process of clearing up of the cornea makes at first rapid progress. Afterward, however, it goes on more slowly again, and the center of the cornea in particular remains for a long time opaque, so that sight is not restored until late in the disease. It takes from half a year to a year, or even more, for the cornea to acquire the full degree of transparency which it is possible for it to assume with an inflammation of the given intensity.

All the cases do not run their course in the way described. There are, for example, many lighter cases, in which the changes do not go far, and which hence, too, are completed in a shorter time. Thus the process may go no farther than the formation of a few maculæ, which gradually disappear again without the associated inflammatory symptoms being at any time marked. If the opacity begins at the margin of the cornea, it often remains confined to that section of it from which it originally started. In that case, if it pushes its way farther from the margin toward the center, only a sector, and not the entire cornea, is rendered opaque. Conversely there are also—luckily not often—very severe cases in which dense opacities remain as a permanency. Owing to the inflammatory infiltration, softening of the cornea may be produced, so that the latter gives way before the intra-ocular pressure and keratectasia develops; in this case also the cornea remains permanently opaque, and to quite a marked degree. The worst cases are those in which, by subsequent shrinking of the exudate, the cornea becomes flattened, densely opaque, and of a tendinous appearance, in which case the sight is nearly or quite all lost.

Just as great variations exist in regard to the thickness and extent of the infiltration, so they do also in regard to the *vascularization*. In many cases the cornea is so abundantly vascularized that it looks like a red cloth; in others, on the contrary, it is almost devoid of vessels, and is like white ground glass. Lying between these extremes are numerous cases in which vessels develop from only single spots upon the corneal margin, so that simply a sector of the cornea looks red, or so that only single tufts of vessels are discoverable. Hence we may distinguish between a vascular and a non-vascular form, according to the relations of the vessels. It must be remarked, however, that even in the non-vascular form one or two vessels can generally be made out with the aid of the magnifying-glass.

When we consider how the cases vary both in respect to the opacity and to vascularization, we comprehend why parenchymatous keratitis should present a very varying clinical picture, and hence often offer difficulties in the way of diagnosis for the beginner. But we shall generally be able to make the diagnosis with certainty if we hold fast to those symptoms which are common to all the cases—namely, the deep situa-

tion of the opacity and of the vessels, the typical increase in the infiltration up to a certain, usually considerable, degree, and finally the absence of purulent disintegration, so that the *formation of ulcers never takes place.*

Parenchymatous keratitis is accompanied by *irritative symptoms*, such as pain, photophobia, and lachrymation. These are sometimes very slight, sometimes violent; in general we may say that they are more pronounced, the greater the amount of vascularization with which the keratitis is associated. Furthermore, parenchymatous keratitis is almost always complicated with *inflammation of the uveal tract.* In the lightest cases there is merely hyperæmia of the iris, which makes itself apparent by the failure, complete or nearly so, of the pupil to dilate under atropine. In severe cases there is iritis, which may lead to the formation of posterior synechiæ, the formation of deposits upon the posterior surface of the cornea, and seclusion and occlusion of the pupil. In particularly bad cases a plastic irido-cyclitis develops, which terminates in flattening of the cornea, or even in atrophy of the eyeball.

Parenchymatous keratitis generally attacks both eyes, and more frequently both in succession than both at once. Sometimes there is even an interval of several years between the involvement of the two eyes. Recurrences of the disease take place, but are rare.

The *prognosis* of the disease, from what has been said, is unfavorable as regards its duration, inasmuch as it drags on for months and years, especially if the two eyes are successively attacked. On the other hand, the prognosis in regard to the ultimate outcome must be put down as good, because in by far the greater number of the cases a good, or at least serviceable, degree of sight comes back. By holding up this prospect of recovery the physician must keep up the courage of his patient, who, because of the slow progress of the disease, is very apt to lose all hope of a restoration of his sight.

Etiology.—Parenchymatous keratitis is a disease of youth, appearing, as a rule, between the sixth and the twentieth year of life. It is only the exception that persons before or after this age (sometimes even after the thirtieth year) are attacked. The female sex suffers from it more frequently than the male. The ordinary cause of the disease is syphilis, and especially hereditary syphilis. To prove the existence of hereditary syphilis from the history of the case directly—i. e., by getting the father or mother to confess to syphilis—is often a difficult thing to do. Besides, in most cases it is not at all necessary, since hereditary syphilis can generally be recognized with sufficient certainty from a series of symptoms. In that case, we abstain from questioning the parents in regard to this matter, the more so since it would be a severe reproach to them to have to recognize in their own persons the cause of their children's illness. On the other hand,

it is a good thing to determine by questioning whether many children have died in the family (the mortality of the children of syphilitic parents amounts, on an average, to fifty per cent), whether premature labors, and especially those in which the fœtus is dead or putrefied, have not occurred, etc.

The *symptoms of hereditary syphilis* which patients with parenchymatous keratitis frequently exhibit are as follows:

1. A peculiar formation of the face and cranium. The upper jaws are markedly flat, and the bridge of the nose low and often sunken in. Not infrequently there exists ozæna or blennorrhœa of the lachrymal sac, the latter in consequence of the changes in the nose. The frontal eminences are very prominent. The intelligence of these patients is often abnormal, they being either precocious, or, on the other hand, backward in the mental development.

2. The incisor teeth are abnormally shaped (Hutchinson), so that, instead of a straight edge, they show a semilunar indentation. This change exists only in the teeth of the second dentition, and then most frequently in the upper central incisor teeth. These are often also stunted in their growth as a whole, so that they are either too small or are altogether wanting.

3. At the angles of the mouth we may find fine linear cicatrices as relics of former rhagades; so also cicatrices in the buccal and pharyngeal cavities (especially on the hard and soft palate) point to the existence of antecedent syphilitic ulcerations.

4. Numerous enlarged lymphatic glands can be made out, especially upon the neck. These are small, hard, painless, and with no tendency toward ulceration, by which characters they are distinguished from the lymph glands of scrofulous subjects, which are large and soft, and readily undergo caseation.

5. Swellings of the periosteum (tophi), which are hard and are but little or not at all painful, occur on the long bones. They are most frequently and most easily found upon the anterior border of the tibia. Sometimes a serous inflammation of the knee-joint (hydrops genu) is present; caries is rare.

6. We frequently find hardness of hearing, which, with the outbreak of the keratitis, sometimes increases to absolute deafness.

It is important to look for all of these symptoms, for any one of them by itself is not to be looked upon as conclusive evidence of the existence of hereditary syphilis; and, on the other hand, we ought not to expect to find all the changes above given distinctly marked in the same individual at once. The more carefully we make our investigation, the greater is the number of these symptoms that we are able to establish; so that we arrive at the conviction that by far the greatest number of cases of parenchymatous keratitis are to be referred to hereditary syphilis. In very rare cases this form of keratitis is also observed in

acquired syphilis. A few cases may depend upon scrofula, while in many no cause at all that we can be sure of is discoverable to account for the eye disease.

Treatment.—*Local* treatment during the period of progression consists in combating the inflammation by protecting the eyes from light and by instilling atropine, which latter counteracts the complications arising from the iris. Moist warm compresses often ameliorate the symptoms of irritation, and accelerate somewhat the progress of the disease. In the regressive period, the thing to do is to secure as thoroughgoing a clearing up of the cornea as possible. For this purpose the well-known irritant remedies—like calomel, tincture of opium, yellow-precipitate ointment, hot steam, etc.—are indicated (see page 150). These, however, should only be brought into application when, on making cautious tests, the eye is found to bear them well—i. e., does not fall once more into a profound state of irritation. It is advisable to keep on with these remedies, interchanging them frequently, for a very long time—for months or years. If ectasis of the cornea threatens, it is to be combated by a pressure-bandage, which, if necessary, can be combined with repeated paracentesis of the cornea.

General treatment, in those cases in which hereditary syphilis is the cause, must be directed against the latter. Mercurial treatment, which is of such marked service in acquired syphilis, is here ordinarily less efficient. Since it is at the same time a very energetic method of treatment, it is advisable to apply it in the severe cases only. In adults we had best select the treatment by inunction, in children the internal administration of corrosive sublimate (giving pills of one milligramme, beginning with one a day, and increasing the dose to from six to ten pills a day, according to the age). In doing this we must be mindful to pay careful attention to the condition of the mouth, in order to avoid salivation. In the lighter cases of parenchymatous keratitis we prefer, in place of mercury, a simple corroborative treatment with the simultaneous employment of remedies containing iodine (cod-liver oil with iodine, iodide of iron, and mineral waters containing iodine, the latter especially as a form of after-treatment). Unfortunately, we must say that, in general, treatment is pretty nearly powerless against this disease. Parenchymatous keratitis in many cases, even under the most careful treatment, runs a course that is not essentially different from what would have been the case without any treatment; not infrequently we see the disease while under treatment break out in the other eye, without our being able to prevent the opacity from spreading gradually over the entire cornea in this eye also. The chief use of treatment consists in its combating the complications arising from the uvea, and also in securing a more rapid and more perfect clearing up of the corneal opacities during the period of regression.

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

Up to the present time it has been possible to make an anatomical examination of an eye affected with parenchymatous keratitis in a few cases only. The examination shows dense infiltration of the most posterior layers of the cornea, so that they sometimes appear as if transformed into granulating tissue (*i*, Fig. 37); moreover, in the posterior and middle layers of the section we see numerous newly formed blood-vessels (Fig. 37, *g*). The infiltration at the margin

FIG. 37.—CROSS-SECTION THROUGH A CORNEA WITH PARENCHYMATOUS KERATITIS. MAGNIFIED 100 × 1. (AFTER A PREPARATION OF DR. NORDENSON.)

The stroma, *S*, of the cornea shows an infiltration, which begins in the middle layers, and keeps on increasing more and more posteriorly, so that the deepest layers, *i*, have assumed the aspect of a granulating tissue. On account of the inequality in the degree of thickening of these layers, Descemet's membrane, *D*, is undulated; upon its endothelium there are deposited in places small accumulations of round cells, *r*. In the middle and deep layers of the cornea we see the transverse and longitudinal sections of newly formed blood-vessels, *g*, *g*, while the most anterior layers, and also Bowman's membrane, *B*, and the epithelium, *E*, are normal.

of the cornea is continued into the ligamentum pectinatum, the iris, and the ciliary body. In one case (in a fourteen-year-old boy) I found this region infiltrated with numerous nodules which were composed of small cells and which had a certain resemblance to tubercles, although it was not possible for me to demonstrate the presence of tubercle bacilli or of other micro-organisms.

According to the results of anatomical as well as clinical examination, therefore, parenchymatous keratitis is situated in the most posterior layers of the cornea, which, according to the teachings of embryology, are to be classed with the uvea (see page 125), for which reason Stellwag calls this disease uveitis anterior. It should not, therefore, excite our astonishment if the uvea proper

is also always implicated. To be sure, the participation of the uvea in the inflammation is not always by any means equally pronounced. Minute deposits, which are discovered in making a careful examination of the cornea with the magnifying-glass at the time when the opacity is resolving, are scarcely ever wanting. Besides these, the most frequently occurring complications are posterior synechiæ and also chorioiditic foci; hypopyon, on the other hand, is extremely rare. In many cases the part that the uvea takes is so slight as not to be clinically demonstrable; in other cases, on the contrary, it is so very prominent, as compared with the process in the cornea, that what we have before us is really an irido-cyclitis—the share that the cornea takes in the process being evidenced only by the presence of a few spots of opacity in its deep layers. Thus there exists a continuous series of intermediate forms between typical parenchymatous keratitis and irido-cyclitis e lue hereditaria.

Among the more frequently occurring variations in the clinical picture of parenchymatous keratitis the following may be mentioned: In that form which begins with maculæ in the central portions of the cornea it not infrequently happens that the maculæ at a certain distance from the cornea are placed particularly close together, and thus form a very opaque ring, which still remains visible as a gray circle even when the separate maculæ have coalesced into a continuous mass of cloudiness (hence described by Vossius in brief as keratitis centralis annularis). Allied to these cases are those in which the central part of the cornea becomes particularly opaque through the confluence of the maculæ, and forms a white disk pretty sharply separated from the less opaque, marginal portions of the cornea. I have seen several cases in which this central opacity remained permanently after the marginal portions had cleared up, and formed a dense, white, sharply circumscribed spot in the center of each cornea, just as if a deeply penetrating central ulcer had previously existed. Sometimes the distribution of the infiltration in the cornea is such that the densest opacity occupies the lowest part of the cornea, as if the products of inflammation had arranged themselves in the cornea in obedience to the law of gravitation. In that case the opacity is bounded above by a convex line, or it forms a triangle, the base of which corresponds to the lower margin of the cornea, while its apex looks upward. The permanent opacity which results from this has the greatest similarity to those triangular opacities in the lower part of the cornea which are left by an irido-cyclitis, when an exudate at the bottom of the anterior chamber has remained for a pretty long time deposited upon the posterior surface of the cornea. In irido-cyclitis resulting from acquired syphilis it not infrequently happens that isolated gray maculæ appear in the middle and deep layers of the cornea. These have been described by Mauthner, Hock, Purtscher, and others as *keratitis punctata syphilitica*. This is distinguished from keratitis punctata superficialis (page 171) not only by the etiology, but also by the situation of the maculæ in the deep layers of the cornea, and might therefore be suitably characterized as *keratitis punctata profunda*.

The vessels in parenchymatous keratitis generally lie in the deep layers. Yet it often enough happens that we find, especially with the aid of the magnifying-glass, a few vessels also which evidently arise from the network of marginal loops or from larger conjunctival blood-vessels, and which, therefore, lie superficially in the cornea. All vessels tend toward the center of the cornea, but do not generally reach it, so that here a roundish spot of the size of a millet-seed or more remains devoid of vessels. The vascular portions of the cornea

look red, and, if the vessels are abundant, rise above the level of the non-vascular center; the latter, accordingly—which, in consequence of the marked infiltration, is gray or even yellowish-gray—is depressed. We must not on this account allow ourselves to be led into error and consider the depressed gray spot as an ulcer; for parenchymatous keratitis does not, as a general thing, lead to ulceration. Exceptions to this rule, though rare, do, however, occur. I have seen, in fact, two cases in which perforation had taken place in the center of the cornea.

The anterior chamber in parenchymatous keratitis is often found to be deeper than usual, a circumstance which should not, however, be referred without further consideration to an ectasis of the cornea, a thing which occurs quite rarely. On the contrary, we are in this case ordinarily dealing with a recession of the iris due to the increased secretion of aqueous humor, resulting from the irritation of the iris. This irritation is in part responsible for the fact that, during the existence of the inflammation, frequently no dilatation of the pupil can be obtained by atropine. But here there is evidently another factor that must be considered, and that is that the atropine does not diffuse through the inflamed cornea to the same extent as it does through a sound one, so that it does not in fact get into the aqueous humor in sufficient quantity to dilate the pupil.

The intra-ocular pressure not infrequently shows an alteration in parenchymatous keratitis. Generally it is diminished so that the eye appears softer, although we need not therefore imagine that an atrophy of the eyeball is beginning. An increase of tension is but rarely observed, and, when it is, sometimes occurs years after the inflammation has run its course. I have seen this even in those cases in which no ectasis of the cornea has been left. Perhaps in such a case the increase in tension was to be attributed to the chorioiditis which accompanies many—in fact, most—cases of keratitis parenchymatosa. This chorioiditis is localized in the most anterior segment of the chorioid (chorioiditis anterior), which is covered with numerous—in most cases black—spots. This variety of chorioiditis would probably be set down among the most frequent symptoms accompanying parenchymatous keratitis if the examination with the ophthalmoscope, and hence the determination of the presence of chorioiditis, were not rendered impossible while the inflammation lasted by the cloudiness of the cornea. The making of this examination and diagnosis can only be done when the cornea has cleared up once more after the inflammation has run its course. It is also often possible to make out the existence of peripheral chorioiditis in the other, as yet uninflamed eye. Another and rarer complication of parenchymatous keratitis is a diffuse scleritis in the region surrounding the cornea. This may subsequently give rise to ectasiæ of the sclera.

The typical course of parenchymatous keratitis, and the participation of both eyes in it, early suggested the idea of its being due to a constitutional cause. Thus Mackenzie gave an excellent description of this disease under the name of corneitis scrophulosa, and at the same time gave a number of the accompanying symptoms which he looked upon as signs of scrofula. Hutchinson has the credit of having completed this series of symptoms, and of having at the same time furnished the proof that they belong not to scrofula, but to hereditary syphilis. This novel view was slow in making its way. Many at first would only allow that it was true for a limited number of cases, and hence divided

parenchymatous keratitis into two forms, which they called keratitis scrophulosa and keratitis syphilitica. According to Arlt, the former is characterized by an abundant development of vessels; in the syphilitic form, on the other hand, the vessels are scanty or altogether wanting, while the part taken by the iris is much more prominent. But the more precise our knowledge becomes in regard to the symptoms of hereditary syphilis, the more surely we arrive at the conviction that this disease lies at the root of parenchymatous keratitis, whatever form the latter may exhibit. Parenchymatous keratitis belongs among the latest forms under which hereditary syphilis appears, and is hence, and rightly, regarded as one of the most important and most frequent symptoms of the late hereditary form of the disease.

The following history may serve to show how from different symptoms we get at the diagnosis of hereditary syphilis. A twelve-year-old girl with parenchymatous keratitis of both eyes was brought into the clinic by her mother. The latter declared that she had no knowledge of syphilis either as regards herself or as regards her deceased husband. She only admitted that the latter had led an irregular life. The woman went on to say that she had been pregnant by this man ten times in all. From the first four pregnancies came four children (the eldest at present about twenty-two years old), who are all healthy. The fifth child died at the end of one year, the sixth pregnancy ended in an abortion, the seventh child is the little patient who is brought into the clinic, the eighth child died at the age of nineteen months, the ninth child is living but is always sickly, and the tenth died at the age of six weeks. Then the husband died in consequence of an accident; the woman married a second time, and has had by her second husband two perfectly healthy children. The woman's daughter who was brought into the clinic was deaf; she presented, in addition to the parenchymatous keratitis of both eyes, the characteristic formation of the cranium belonging to syphilitic children. The teeth showed the form described by Hutchinson; numerous small, hard lymphatic glands were found upon the neck. I made the younger sister (the woman's ninth child) come too. She, who is a feeble girl, is not, to be sure, absolutely deaf, but hears very badly, has the characteristic formation of the face and swollen lymphatic glands upon the neck, and the teeth—they are still the milk-teeth—are markedly small and separated by wide interspaces. Externally the eyes look healthy, but in both the periphery of the fundus is found by the ophthalmoscope to be covered with spots, black as ink, lying in the chorioid. The correct interpretation of this history, without doubt, is that the woman's first husband had acquired syphilis after the fourth pregnancy. While, therefore, the woman's first four children enjoy very good health, only two of the children of the six following births are living, and both are sickly, both marked with evident symptoms of hereditary syphilis. When the woman had become pregnant by her second, healthy husband, she had healthy children once more. From the history just submitted, it can be deduced that the examination of the little patient's brothers and sisters may often contribute to the clearing up of the case, inasmuch as we may find in them, too, symptoms of hereditary syphilis, and thus may still further confirm the diagnosis. Moreover, it is not at all rare for two or even three of a set of brothers and sisters to be affected with parenchymatous keratitis.

*4. Keratitis Profunda.**

44. In this a gray opacity develops very gradually in the cornea —ordinarily in its center—an opacity which is situated in the middle and deep layers of the cornea, and over which the corneal surface is gray and punctate, but not depressed. Seen with the naked eye, the opacity looks uniformly gray, while with the magnifying-glass it may be resolved into separate points and maculæ, or into gray interlacing striæ. After the opacity has remained for some time (several weeks) at its acme it begins to slowly abate, without ulceration having taken place. The development of vessels is either entirely absent or is very inconsiderable. The accompanying symptoms of inflammatory irritation are sometimes slight, sometimes pretty violent. The participation of the iris is mostly limited to hyperæmia. The disease lasts from four to eight weeks or more. In the lighter cases it terminates in a complete restoration of the transparency of the cornea, while in other cases diffuse opacities remain permanently in the center of the cornea.

Of the causes of keratitis profunda the following are known: 1. A rheumatic basis, furnished either by a cold or by a preceding articular rheumatism. Arlt has characterized such cases as keratitis rheumatica. These ordinarily run their course with marked inflammatory symptoms, especially with violent pain and photophobia. 2. Intermittent fever in its chronic form of malarial cachexia sometimes results in a keratitis profunda, which is characterized by the absence of marked symptoms of irritation, and also by an unusually chronic course. 3. After injuries, especially contusions, a keratitis profunda not infrequently develops the peculiarity of which is its relatively rapid course and the speedy restoration of the transparency of the cornea. In very many cases the cause of the keratitis profunda remains unknown.

Treatment consists, locally, in the application of a bandage or of protective glasses, and the use of atropine and moist warm compresses, provided these are well borne. After the inflammatory symptoms have run their course, irritant remedies for clearing up the opacity are indicated. The general treatment depends upon the cause that we are able to discover for the keratitis.

5. Sclerosing Keratitis.

This is an accompanying symptom of scleritis (see § 53). If a scleritic nodule is situated near the margin of the cornea, there develops in the adjacent portion of the latter an opacity which is situated in its deeper layers. It has approximately the shape of a triangle, the base of which is situated at the corneal margin, while the rounded

* Synonyms: central parenchymatous infiltration of the cornea, keratitis parenchymatosa circumscripta.

apex looks toward the center of the cornea and becomes gradually lost in the transparent cornea. The opacity thus occupies a sector of the cornea, the base of which corresponds to the scleritic nodule. It is gray or grayish-yellow, and gradually increases in intensity until the cornea at the affected spot has become completely opaque. The surface of the cornea over the opacity is punctate but not depressed; vascularization is either altogether absent or is very slight, and, when it is present, is in the deep layers of the cornea. After the opacity has reached its maximum density, a gradual retrogressive process sets in, without ulceration having taken place at any time. The process of clearing affects the thin edge of the ulcer and its apex, which looks toward the center of the cornea; the greatest portion of the opacity remains permanently and becomes ultimately bluish-white like the adjacent sclera, into which it passes without any sharp line of distinction. It looks, therefore, as if the sclera at the spot where the opacity is found had pushed its way into the region of the cornea—whence the name sclerosing keratitis (Von Graefe). The symptoms of irritation which accompany this form of keratitis are excited less by it than by the scleritis and the inflammation of the uvea depending upon the latter.

Keratitis keeps following up a scleritis which attacks successively different portions of the circumference of the cornea, so that, when the disease runs a pretty long course, peripheral opacities form one after the other at several portions of the cornea. These are situated upon the cornea under the form of triangles, and converge with their apices toward its center. In bad cases the entire periphery of the cornea is sclerosed in this way, so that only a small portion in the center remains transparent.

The treatment is essentially that of the scleritis.

6. Keratitis springing from the Posterior Surface of the Cornea.

When the posterior surface of the cornea is not washed by the aqueous humor, as it is in the normal eye, but an exudate or tissue is brought into apposition with it, the substance of the cornea becomes cloudy. To produce this effect, however, it is necessary that the apposition should be kept up for a pretty long time. Hence this sort of opacity is not generally found in ordinary hypopyon, because the latter disappears too quickly, but is found in those more solid gray exudates which appear in the anterior chamber, particularly in scrofulous and syphilitic irido-cyclitis. Large deposits also, if they remain for a long time, usually leave behind them gray spots upon the cornea. Another thing besides exudates, that gives rise to the same form of keratitis, is the apposition of tissue to the back of the cornea, as in the case of protrusion of the iris, of cysts or other tumors of the iris, which reach to the cornea, and in the case of lenses which have prolapsed into the

anterior chamber. The opacity of the cornea develops at a point corresponding to that spot at which apposition takes place, occurring, therefore, in the case of exudates, most frequently below. The surface of the cornea at this spot is dull, sometimes slightly uneven, and like brawn. The opacity is gray, and, after existing a long time, becomes pretty intense, and is permeated by vessels which lie in the deep layers of the cornea. It never completely disappears, even after the causal lesion has been remedied. The mode of origin of this form of keratitis is probably to be conceived of thus: Contact of the cornea with foreign tissue alters the endothelium of Descemet's membrane. This alone, according to Leber's researches, protects the cornea from the aqueous humor. Now, if the endothelium becomes deficient, aqueous humor can penetrate into the tissue of the cornea, which consequently becomes cloudy.

The clinical pictures under which non-suppurative keratitis makes its appearance are exceedingly manifold. Only a certain number of them can be marshaled under fixed types, as has been done in the foregoing pages. Many, sometimes very peculiar, forms come under observation too rarely for us to be able to build up from them a typical disease-picture; such cases can not at present be utilized for such a purpose except with certain reservations. A few rather more frequently occurring forms may be enumerated here as an appendix to those before described.

7. **Traumatic Striped Keratitis.**—This is observed after incised wounds of the cornea, and most beautifully after the cataract operation. Within the first twenty-four hours after the operation gray striæ make their appearance in the cornea, which, starting from the wound, extend sometimes as far as the opposite margin of the cornea, and are always disposed perpendicularly to the length of the wound. These striæ are particularly observable in those cases in which the lips of the wound have been somewhat contused, as, for example, those in which the delivery of the lens has been difficult. They generally disappear within the first eight days, and only if particularly marked fail to do so until after several weeks. This form of keratitis causes no symptoms of irritation, and does not cause the least disturbance of the healing of the wound. This proves that we do not have to do with a real inflammation. Anatomical investigation has, in fact, shown that in these cases cellular infiltration is altogether wanting, and that there is a dilatation of the lymph-spaces of the cornea, which are distended with fluid (Becker, Laqueur, Recklinghausen). This fluid, having a different refractive power from the rest of the cornea, makes the latter appear cloudy; the striate form corresponds to the arrangement of lymph-spaces which follow the direction of the fibrillæ of the cornea.

A similar striate opacity of the cornea is sometimes observed in cases of detachment of the retina, which have been treated with the pressure bandage. The eye becomes suddenly very soft and the anterior chamber remarkably deep, and in the cornea fine gray striæ show themselves, which cross in different directions, so that the opacity looks like creased tissue-paper. It is probable that folds in the cornea take part in producing this effect.

8. **Deep Keratitis in Irido-cyclitis.**—In every case of marked irido-cyclitis the cornea is not perfectly clear, but slightly dull. But in many cases of severe

irido-cyclitis the participation of the cornea is still more pronounced, an infiltration of gray, or later often of yellowish, color making its appearance in its deep layers. This infiltration, under a process of vascularization, subsequently disappears, although it always leaves a permanent opacity behind it, associated in severe cases with flattening of the cornea. Vision in these cases is almost or quite annihilated, not merely on account of the change in the cornea, but chiefly on account of the products of the irido-cyclitis. These cases, which, to be sure, are very rare, must not be confounded with those cases of parenchymatous keratitis which are associated with marked implication of the uvea.

9. **Deep Scrofulous Infiltrates** occur under the form of extensive gray, subsequently yellow, opacities in the middle and deep layers of the cornea in conjunctivitis lymphatica. They may either proceed to suppurate, or they may go on to resorption, in which case the cornea sometimes clears up in a surprising manner. For a more detailed account, see Conjunctivitis Lymphatica (page 87).

10. **Keratitis Marginalis.**—This rare disease generally affects old people, and occurs for the most part on one side only, rarely on both sides. There forms upon the margin of the cornea, with moderate symptoms of irritation, a gray, later grayish-yellow, or even purulent-yellow opacity, which directly adjoins the sclera and reaches for a distance of about two millimetres into the transparent cornea. This marginal zone of opacity generally embraces from one third to one half of the circumference of the cornea (most frequently the upper part), or in rare instances surrounds the entire cornea. The surface of the cornea over the opacity is somewhat dull, but shows no loss of substance, and never any exfoliation of epithelium. The limbus soon pushes forward, and with its vessels covers the opacity. The irritative symptoms disappear in from one to two weeks, while the marginal infiltrate is transformed into a permanent gray opacity of the cornea. This opacity bears a great resemblance to the arcus senilis, from which it is chiefly distinguished by its not being separated by a transparent zone from the scleral margin, but passing into the latter without any clear line of distinction. Iritis does not occur in connection with this affection of the cornea, nor does ulceration of the cornea, as a rule; only twice have I seen small superficial ulcers develop upon the cornea. On account of the marginal situation of the residual opacity, this form of keratitis is without danger to the sight. I have not found the description of this form of keratitis in the text-books, with the exception of the text-book of Arlt, who describes it in connection with sclerosing keratitis; I have, however, never seen symptoms of scleritis occurring in conjunction with this inflammation of the cornea.

II. Injuries of the Cornea.

45. 1. Foreign Bodies in the Cornea.—The penetration of foreign bodies into the superficial layers of the cornea belongs among the most common of accidents. What is most frequently observed are small particles of iron in the cornea, particularly among mechanics of a certain sort, like locksmiths, blacksmiths, iron-founders, etc. These particles do not look like metallic iron, but vary from dark brown to black; for the particles of iron, which, for example, fly off when iron is being hammered, are heated by the force of the blow so that they are thrown out as sparks. Thus they become oxidized into ferroso-ferric oxide (so-

called iron-scale), and under this form are found in the cornea. If the fragment of iron remains sticking in the cornea, it becomes surrounded very soon by a brown ring, because the portions of the cornea in its immediate vicinity take up the oxidized iron and so turn brown. Fragments of coal are also frequently found in the cornea—for instance, in firemen or in people after a railroad journey—and fragments of stone in stone-cutters, stone-breakers, etc.

Foreign bodies penetrating into the cornea should be removed as soon as possible. If they are superficially situated, it is an easy matter to pry them up with a suitable instrument. For this purpose we use a special needle, which is made broad at its upper end, or an instrument upon the plan of a small gouge. In default of such instruments we may also make use of a sharp sewing-needle or the point of a small knife, employing, of course, the necessary precaution. It is advantageous first to render the cornea insensitive by the repeated instillation of a five-per-cent solution of cocaine. In the case of fragments of iron, besides the foreign body the ring of brown-colored corneal tissue next it should be scraped off.

If the foreign body is not removed in season, its expulsion by suppuration follows. An inflammatory infiltration forms about it, surrounding it in the form of a gray ring. Then the tissue of the cornea in this place breaks down, so that the foreign body becomes loose and ultimately falls out. The resulting ulcer generally becomes rapidly cleansed and heals, leaving a small opacity after it. This process of elimination takes place with marked symptoms of irritation, and especially with hyperæmia of the iris, or even with iritis, which latter makes itself evident by the formation of a hypopyon and of synechiæ. It is only grains of powder or of lime which are known to have the power of remaining in the cornea without exciting suppuration and becoming permanently incorporated in it.

Much more infrequent, but also much more serious, are those cases in which a small foreign body has penetrated into the deep layers of the cornea. In this case, in order to remove the foreign body, it is often necessary to incise the lamellæ of the cornea that lie above it, so as to be able to draw it out with the forceps. If the point of the foreign body projects into the anterior chamber there is the danger that, in attempting to grasp the foreign body, the latter may be pushed in still farther, and may injure with its point the capsule of the lens. In such a case, therefore, the indication sometimes is to make a preliminary opening in the cornea near its margin and to introduce the instrument from this point into the anterior chamber, by which means we press the foreign body from behind forward, so that we can grasp it by its anterior extremity and extract it.

2. **Solutions of Continuity of the Cornea.**—Superficial excoriations of the cornea, which simply produce a loss of substance in the epi-

thelial covering, are known as *erosions*. These belong among the most frequent of injuries, such as one gives himself by scratching the eye with the finger-nail, with a rough cloth, a stiff leaf or twig, etc. Such an injury is commonly accompanied by pretty marked symptoms of irritation, such as photophobia, lachrymation, and especially by violent pain. Examination of the eye shows, besides the ciliary injection, a defect in the epithelium, forming an ulcer, the floor of which is perfectly transparent, so that it is only by taking the corneal reflex that the loss of substance can be discovered. Healing generally takes place within a few days by a complete regeneration of the epithelium, starting from the edges of the epithelial defect; a permanent opacity does not remain. Quite a good deal of significance attaches to these traumatic erosions, from the fact that not infrequently they are the starting-point of an ulcer or abscess of the cornea, especially if an opportunity is given for the production of infection. This latter is particularly apt to be the case when a conjunctival trouble associated with abnormal conjunctival secretion, or when a blennorrhœa of the lachrymal sac, is present.

It is worth remarking that sometimes *recurrences* of corneal erosion take place without any new injury having preceded them (Arlt). After the lesion has been to all appearances fully healed, marked symptoms of irritation set in suddenly several weeks or months afterward without known cause; and a loss of substance is again found upon the cornea in the epithelium at the site of the former injury. Such relapses may occur repeatedly. They have their cause probably in the fact that the epithelium at the original site of injury has never become regenerated in a perfectly normal fashion, so that under the action of any insignificant cause it is again separated and cast off. Perhaps this separation of the epithelium takes place in the form of a vesicle, which ruptures so quickly that we do not get a sight of it, but only of the loss of substance in the epithelium (see page 171).

Erosions are best treated by the application of a simple protective bandage, the use of which should be kept up until the epithelium is completely regenerated. In this measure also is found the best protection against relapses; and if the latter do occur, they require the wearing of the bandage a second time, and that, too, for a sufficiently long period. If marked symptoms of an accompanying inflammation exist, and these are not relieved by the bandage alone, we may instill atropine.

Deeper wounds of the cornea when they heal always leave corresponding opacities behind. Such wounds are particularly dangerous under two circumstances—i. e., when they are infected and when they perforate the cornea. In the former case infiltrates develop in the cornea which may be transformed into ulcers or abscesses. In the latter case prolapse of the iris occurs, provided the wound is large enough. Moreover, the iris or the lens may be injured at the same

time, and lastly there exists, as in all perforating lesions of the eyeball, the danger of an inflammation of the deep parts of the eye, produced by infection, and very frequently ending in the destruction of the organ.

The treatment of recent wounds of the cornea requires us first of all to strive against the production of infection in them. We cleanse the eye with antiseptic solutions, strew the wound with finely powdered iodoform, and, after we have dropped in atropine to combat any iritis that may exist, we apply a protective bandage. If we are dealing with a perforating wound of the cornea, the greatest possible quiet on the part of the patient (rest in bed) is requisite in order to bring about a speedy and solid closure of the wound. If the iris is prolapsed, it should be so excised, after carefully separating it from the lips of the wound, that no iris remains any longer incarcerated in the wound; according to just the same principle that holds good for prolapses of the iris of spontaneous origin. (For more precise particulars in regard to perforating wounds of the cornea, see §§ 54 and 55.)

3. **Injuries of the Cornea by Caustic Agents and by Burns.**—These occur simultaneously with the analogous injuries of the conjunctiva, and are produced by the same causes that these are (see page 100). In fact, in the case of such injuries of the eyeball, it is precisely the part which the cornea takes in the process that is a criterion for the prognosis—for the most harmful consequences of these injuries are the opacities which are left in the cornea. The corroded or burned cornea looks dull and opaque. The extent of the opacity depends upon the extent of the burn, but the intensity of the opacity depends upon the depth to which the corneal tissue has been destroyed. In light cases the color of the opaque cornea is gray, but in severe cases whitish. In the worst cases the cornea is all as white as porcelain, dry upon its surface, and quite insensitive; such a cornea is completely necrotic. In general it is not always easy to estimate from the character of the injury alone how deeply the destructive process has penetrated into the cornea, and hence caution is advisable in giving the prognosis.

The injury is generally followed by sharp pain. It heals by the extrusion of the dead tissue. In the lightest cases, in which the injury has affected the epithelium only, the processes of extrusion and of healing occur very rapidly (as in the frequent cases of burns of the cornea produced by a curling-iron). If the destructive process has made its way into the parenchyma of the cornea, a delimiting suppuration sets in, which leads to the separation of the eschar; the loss of substance thus produced heals, leaving a permanent opacity. If the destructive process has at any point gone through the entire thickness of the cornea, perforation of the latter develops after the separation of the eschar. The iris then prolapses, and the resulting cicatrization unites the iris to the cornea (cicatrix of the cornea with anterior synechia). In a

similar way adhesions often develop between the cornea and the conjunctiva of the lids (symblepharon), provided that a loss of substance is present in the latter also. The treatment of injuries produced by burns and caustics has already found mention under the head of the analogous injuries of the conjunctiva.

III. Opacities of the Cornea.

46. Opacity of the cornea is a constant accompaniment of every inflammation of the latter, and is in this case caused by cellular infiltration of the corneal tissue. This recent inflammatory opacity is of a changeable nature, increasing or diminishing according to the course of the inflammation. From this variety we must distinguish those opacities which are stationary, whether they represent the residua of an inflammation that has already run its course, or have developed gradually without any antecedent inflammation. These stationary opacities, of which alone we shall treat here, we call opacities of the cornea in the narrower sense of the word. They are by far the most frequent cause of poor sight, and hence have a particular claim upon the interest of the physician.

We distinguish stationary opacities of the cornea into those of inflammatory origin and those which have developed without any antecedent inflammation.

(*a*) *Opacities of the Cornea of Inflammatory Origin.*

These are the consequence of a keratitis, either suppurative or non-suppurative. In the first case the tissue of the cornea, which has been destroyed by suppuration, is replaced by cicatricial tissue, and the opacities thereby produced are corneal cicatrices in the proper sense of the word. In this category also are to be counted most opacities which remain after injuries. The cornea may also have opacities remaining after a non-suppurative keratitis, either because its tissue has been so altered by the deposition of exudate which has taken place that it does not even afterward regain its physiological transparency, or because the exudate itself in part becomes organized and thus remains as new tissue in the cornea (an example is a pannus which has been transformed into connective tissue). It is an uncommon thing, relatively speaking, for opacities to occur which are situated in the epithelium only, as, for instance, in those cases in which the epithelium as a result of constant mechanical irritation—in trichiasis—becomes thickened and hence opaque.

The *appearance* of opacities of the cornea varies according to their degree of intensity and their age. Slight opacities appear as translucent bluish-white spots with outlines altogether hazy—*maculæ* or *nubeculæ corneæ*. Well-marked opacities are grayish-white or pure white, and are usually pretty sharply outlined; moreover, in the begin-

ning they are apt to be traversed by vessels which afterward become fewer or disappear altogether. The surface of the opacity generally lies on a level with the adjacent healthy cornea, especially if the opacities are small, although elevation or depression of the surface of the cornea at the site of the cicatrix is also observed. Elevation of the surface is commonly the result of an ectasis of the cicatrix. More rarely it is caused by excessive development of cicatricial tissue, or by thickening of the epithelium upon the surface of the cicatrix. Depression of the surface of the cornea at the site of the cicatrix occurs most frequently in the case of small cicatrices from the incomplete filling up of the ulcer with cicatricial tissue (*facet of the cornea*). In the case of larger cicatrices which have developed in consequence of extensive perforation of the cornea, or more rarely as a result of a severe non-purulent keratitis, a flattening of the entire cornea may follow from the retraction of the cicatricial tissue (*applanatio corneæ*). This is especially apt to occur if a plastic irido-cyclitis has existed simultaneously with the inflammation of the cornea; for, on account of this irido-cyclitis, extensive membranous exudates are deposited in the interior of the eye, which by their contraction diminish the intra-ocular pressure, and so favor the flattening of the cornea.

With many cicatrices *incarceration of the iris* occurs. This is a proof that there has been an antecedent perforation of the cornea; hence such cicatrices are always very thick. It is important to determine in any special case whether a cicatrix of the cornea is or is not connected with the iris, since an incarceration of the iris may entail serious consequences. We recognize the presence of such an anterior synechia by the displacement of the pupil toward the site of the incarceration, and furthermore by the unequal depth of the anterior chamber, which is always shallower near the place where the iris is adherent. In many cases, also, the dark color of the cicatrix gives evidence of the incarcerated iris, the pigment of which shows through the cicatricial tissue. The union between iris and cicatrix is often confined to quite a small spot, so small, sometimes, that only a very fine filament rises from the iris and passes over to the cicatrix in the cornea. At other times broad adhesions exist, and there may even be an incarceration of the entire pupillary margin of the iris in the cicatrix. In this case occlusio and seclusio pupillæ are produced, with their baneful consequences (see § 69).

(*b*) *Corneal Opacities of Non-inflammatory Origin.*

A physiological opacity which at an advanced age makes its appearance in the corneæ of healthy eyes, is the *arcus senilis*, or gerontoxon corneæ, which has been considered under the head of the anatomy of the cornea. Among pathological opacities of non-inflammatory origin the principal one requiring mention is the *zonular opacity of*

*the cornea.** This forms a gray stripe from three to five millimetres broad, which passes straight across the cornea, a little below its center. It develops with extreme slowness, occupying years in its progress; the first parts to appear being the two terminal points of the opaque stripe —that is, the portions of the opacity lying nearest the outer and inner margin of the cornea. These points are always separated from the margin of the cornea by a narrow, transparent zone. Starting from them the opacity gradually pushes its way toward the middle line, where the two parts of it unite, and thus close in the opaque zone which covers the lower half of the cornea. This zone has a well-defined outline on all sides, and is more densely opaque at the margins than in the center. On examining it pretty closely, especially with a magnifying-glass, we ascertain the opacity to be composed of minute white or gray dots which lie quite superficially—in the epithelium or directly beneath it; hence we usually find the surface of the cornea over the opacity roughened, or covered with minute prominences.

Zonular opacity of the cornea generally develops in eyes which have nearly or quite lost their sight in consequence of some intra-ocular affection (irido-cyclitis, glaucoma), and in this case it is practically of little significance. It is only very rarely (and then only in elderly people) that we encounter it in eyes which are otherwise perfectly sound, so that here the corneal opacity itself is the sole cause of the disturbance of vision.

Among the varieties of opacity which do not depend upon inflammation, belong also the *pressure opacity* of the cornea—i. e., that form of opacity which develops in connection with an elevation of the intra-ocular tension. It is a diffuse, smoky opacity, which is most marked in the center of the cornea and gradually diminishes toward its margin. That it is not of inflammatory nature is proved by the fact that, after the disappearance of the rise in tension, it very soon, often in less than an hour, vanishes completely, which would not be possible if it depended upon an inflammatory infiltration of the cornea. In fact, in the case of the pressure opacity we are simply dealing with an œdema of the cornea, which is situated mainly in the epithelium, and which is capable of rapid subsidence.

47. Disturbance of Vision produced by Opacities of the Cornea.—Every opacity which falls wholly or in part within the pupillary region of the cornea results in disturbance of vision; for the sum of the incident rays at the site of the opacity, instead of being all permitted to pass through the cornea, is divided into two parts: one part is absorbed by the cicatrix or is reflected off from it; the other part penetrates through it into the eye. The relation between these two parts depends upon the density of the opacity; the denser it is, the more

* Synonym: band-shaped opacity of the cornea.

refraction, and with it myopia, are produced. In ectatic cicatrices of the cornea the abnormality of curvature is not confined to the cicatrix, but extends to the neighboring transparent portion of the cornea also, so that, as a rule, no portion of the cornea retains its normal curvature. In consequence of the irregular astigmatism, objects appear indistinct, distorted, and often also double or multiple.

The disturbance of vision produced by an opacity of the cornea often entails still other *indirect results*. Among these are strabismus, nystagmus, and myopia. The last named is in many cases only apparent. The patient with corneal opacities brings minute objects unusually close to his eye, in order to have their retinal images as large as possible, and so in a measure make up for their indistinctness. Nevertheless, elongation of the axis of the eye—i. e., true myopia—may ultimately develop in consequence of the great accommodation and convergence necessitated through such an excessive approximation of objects.

Treatment.—The chief task that this has to attend to is to improve the sight. The means employed for this purpose are as follows:

(*a*) *Clearing up of the Opacity.*—In the case of every opacity of recent date we must first try to clear it up as much as possible by the application of irritants (see page 150). In older opacities, which can not be cleared up any further by medicinal means, the next step apparently would be to render the cornea transparent once more by excising the opaque layers with the knife. Such attempts, however, have resulted unsuccessfully, for the loss of substance resulting from the excision of the opacity heals again with the formation of cicatricial tissue —that is, with the formation of an opacity, just as before. Removal of opacities by operation is only indicated when they are situated in the epithelium, since losses of epithelium are made good by normal transparent epithelium. Cases in which removal of the epithelium—*abrasio corneæ*—is indicated, are those in which the epithelium has been thickened by mechanical irritation, as in trichiasis; also in those in which lead, lime, or grains of powder are imbedded in the epithelium; and lastly in zonular opacity of the cornea, provided this attacks an eye that but for it would be able to see. In cases in which the cornea is cicatricial throughout, the attempt has been made to restore the sight by transplantation of the cornea. A circular piece is excised from the opaque cornea, and an equally large piece of a normally transparent cornea (from the eye of a human being or of an animal) is inserted in the opening. The transplanted piece of cornea unites, as a rule, but afterward becomes opaque, and so completely for the most part that the patient gains nothing. Success may be most reasonably anticipated in those cases in which perforation of the cornea has not preceded the formation of the cicatrix. In this case Descemet's membrane is everywhere present, and should, moreover, be preserved in performing

transplantation, the opaque layers of the cornea lying in front of it being removed by means of a small trephine and replaced by a transparent piece of cornea (Hippel).

(*b*) *The optical aids* that may be employed for improving the sight are glasses and the stenopæic slit. The object of the latter is to bring nothing but the transparent part of the cornea into use for vision, and to exclude the portion bearing the opacity, by which means the dazzling due to diffusion is prevented. Glasses may sometimes be of advantage when the opacity is complicated with changes in the curvature of the cornea.

(*c*) *Displacement of the pupil* by means of iridectomy (after the method of Beer) is generally the only means of restoring sight in the case of dense opacities which entirely conceal the pupil. (For the indications and the method of performing this operation, see the section on operations, § 156.)

In large and very white cicatrices of the cornea it is often desirable to do away with the disfigurement that they produce. For accomplishing this purpose, *tattooing of the cornea* (De Wecker) is of service. This procedure depends upon the observation that many bodies, as, for example, grains of powder, may become imbedded in the cornea and remain there permanently. Tattooing consists in giving the white cicatrix a black tint by means of India ink, which is introduced into the cicatricial tissue by being repeatedly pricked in with a needle. The tattooing-needles used for this purpose consist either of a bundle of ordinary sharp-pointed needles (Taylor), or of a single broad needle which is channeled for the reception of the ink (hollow needle of De Wecker).

From the form and position of corneal opacities we may often gather an impression as to the variety of keratitis to which they owe their origin. Thus: (*a*) Maculæ of the cornea originate from small corneal ulcers. They most frequently develop in childhood as a consequence of conjunctivitis lymphatica, and in that case are often distinguished by being situated on the margin of the cornea. Quite characteristic opacities are the elongated ones which are left by a vascular fasciculus. (*b*) Opacities which are slight and diffused, but which are nevertheless spread over the greater part of the cornea, are mostly the result of pannus or of parenchymatous keratitis. In the first case they are situated superficially, in the second case in the depth of the cornea. (*c*) Extensive, tendinous-looking opacities, without incarceration of the iris, in which chalky-white dots are often visible, are observed after severe cases of parenchymatous keratitis. Similar white dots also occur in opacities resulting from corrosion by lime, and in this case depend upon imbedded calcareous particles. Finally, cicatrices with incrustation of lead are also distinguished by a sharply circumscribed, extremely white opacity. (*d*) Marginal, crescentic, or arcuate opacities are the consequence of catarrhal ulcers or of keratitis marginalis; they should not be confounded with an incompletely developed arcus senilis. (*e*) Large, thick cicatrices with inclusion of the iris, which often occupy the whole cornea

except a narrow rim about the margin, are most frequently produced by an abscess of the cornea or by acute blennorrhœa. The same sort of extensive cicatrices also occur after keratomalacia, diphtheria, and burns; in the last two cases cicatrices upon the conjunctiva are never wanting, and conduce to the correct diagnosis. (*f*) Sharply defined punctate or striate cicatrices are the result of traumatism, whether effected by accident or by design (operation). (*g*) Dense, white cicatrices, which occupy the lowermost part of the cornea and terminate above in an almost horizontal border, are caused by keratitis e lagophthalmo. Sometimes we see men in whom such cicatrices are present in both eyes. In this case the cicatrices are usually the consequence of a severe disease, in the course of which a condition of somnolence and a resulting imperfect closure of the lids lasted for some time. (*h*) Opacities in the lowermost part of the cornea having superiorly a triangular outline are the result of a parenchymatous keratitis which, contrary to rule, has become localized in the lower half of the cornea, or are the result of the deposition of an exudate upon the posterior corneal surface. (*i*) Small, bluish-white opacities which are situated at the margin of the cornea and project into the transparent part of it under the form of obtuse-angled triangles, are the residua of a sclerosing keratitis.

Those opacities which are produced by the deposition of an exudate sometimes exhibit an adhesion of the iris to the cornea, and hence belong to those rare cases in which an *anterior synechia exist without a preliminary perforation* of the cornea. The iris is drawn up to the posterior surface of the cornea by the exudate, as it is contracting and undergoing organization, and becomes fixed there. In a similar way anterior synechia without preliminary perforation of the cornea is observed in those cases in which the iris has been pushed forward as far as the posterior surface of the cornea and kept there for some time. The iris in such cases becomes agglutinated to the cornea in spots, and if it afterward, either spontaneously or as the result of an iridectomy, returns to its normal position, these agglutinated parts of it remain attached to the cornea. We then either find the iris extensively adherent to the cornea, or one or two tags arise from it, whose apices are inserted into the posterior corneal surface. The same thing may take place if the anterior chamber has been effaced for some length of time, so that iris and cornea have been directly in contact with each other.

Cicatrices of the cornea are often subjected to subsequent *metamorphoses*. Thus it may happen that cicatrices, originally flat, later become ectatic. Markedly ectatic cicatrices, the most prominent point of which is but incompletely covered by the lids, not infrequently display at this point a xerotic condition of the epithelium, which looks dry and epidermoid. In old, dense cicatrices, yellow spots sometimes develop, caused by the deposition of fat or of concretions of colloid matter. Small, chalky-white specks imbedded in the cicatrix are to be referred to a deposition of lime. In fact, small calcareous plates are frequently thus formed, which, when they become loose, can be picked off with a forceps. In these cases we have to do with different varieties of retrograde metamorphosis, which are referable to insufficiency of nutrition of the dense cicatricial tissue. Such processes may give rise to the softening and ulcerative disintegration of old cicatrices—so-called atheromatous ulcers, which not infrequently induce perforation.

As regards the opacities which are produced by non-inflammatory processes, they are mostly referable to a lowering of the nutrition of the cornea. The *arcus senilis* consists in the deposition of a colloid substance in the more super-

ficial layers of the cornea, close to the limbus; its cause is assumed to be senile atrophy of the limbus, with involution of a portion of the vascular loops contained in it. *Zonular opacity of the cornea* also depends upon a disturbance of nutrition, caused by a lessened ability on the part of the cornea to withstand external injurious influences. The position and extent of the opacity correspond to the palpebral zone of the cornea—i. e., that part of it which lies exposed in the palpebral fissure even when the latter is but slightly opened. Since this form of opacity affects corneæ which have generally been made insensitive already and often opaque, too, by some antecedent disease, it must be assumed that it occurs because these corneæ are unable any longer to withstand properly the external injurious influences to which they are subjected in the region of the palpebral fissure. The anatomical alterations which are the fundamental factors in producing zonular opacity of the cornea consist usually in the deposition of lime-salts in and beneath the epithelium (Dixon, Bock); colloid degeneration has also been observed (Goldzieher).

Congenital opacities of the cornea, although rare, do occur, some being of inflammatory, some of non-inflammatory, origin. The former are caused by a fœtal keratitis. The latter are relatively more frequent, and are found in conjunction with other congenital anomalies of the eye. They are referable to an arrest of development. The fœtal cornea is originally opaque; it acquires its transparency only by degrees. An arrest of this process of transformation leaves the cornea more or less opaque.

The *disturbance of vision by dazzling*, which occurs when an opacity is present in the pupillary region of the cornea, is explained as follows: In the normal eye the images of the objects in the visual field lie upon the retina, side by side and sharply separated from each other, the bright and dark parts in contrast. Now, if by means of a spot of opacity upon the cornea light is diffused uniformly over the whole retina, the distinction between the light and dark portions of the retinal images becomes less striking. The following comparison may illustrate these conditions: In a well-taken photograph all details are seen sharply and distinctly. But if it is rather highly polished, and we look at it obliquely, the glazing shines so that the details of the photograph can no longer be distinguished. As the glazing is perfectly transparent, the rays emanating from the photograph still arrive at our retina and produce there sharp images of the details of the photograph. But in addition there come numerous rays reflected from the surface of the glazing, which so flood the whole retina with light that the sharp retinal images are, so to speak, drowned out.

A man with sound eyes can get an idea of the sensation of dazzling produced by corneal opacities, if, when in a picture-gallery, he looks at a picture which is hung upon a narrow strip of wall lying between two windows. He can scarcely see what the picture represents, and has a very unpleasant sense of dazzling. How is the diffusion of light effected in this case? The normal cornea is not, as is ordinarily assumed, absolutely transparent. We can see this from the fact that a portion of the cornea, which has light concentrated upon it by focal illumination, looks gray, insomuch that the tyro might suppose that there was a pathological opacity of the cornea. The cornea, therefore, always reflects a certain quantity of light. The like is true of the lens, and, generally, of all the refracting media of the eye. In consequence of this imperfect transparency of the refracting media, diffusion of light takes place even in the nor-

mal eye, although, to be sure, under ordinary circumstances, it is too inconsiderable to excite notice. But, in the example given, diffusion exerts such a disturbing effect, because, in proportion to the light reflected from the picture, an uncommonly large amount enters the eye from the two windows, and thus a relatively great quantity of light undergoes diffusion.

IV. Ectasiæ of the Cornea.

Just as in the case of opacities, so also in the case of ectasiæ of the cornea, we must first of all distinguish whether they have been produced by inflammation or not. On the basis of this distinction we make the following subdivision of ectasiæ of the cornea:

Ectasiæ of inflammatory origin . .	Staphyloma, Keratectasia.
Ectasiæ of non-inflammatory origin	Keratoconus, Keratoglobus.

1. *Staphyloma of the Cornea.*

48. Symptoms.—A staphyloma is a protuberant cicatrix originating in a prolapse of the iris, and wholly or in part replacing the cornea. We distinguish accordingly between total and partial staphylomata. In total staphyloma there is found in place of the cornea an opaque, protuberant cicatrix, the base of which is encircled by the margin of the sclera or by the very outermost rim of the cornea, which may still be preserved. In one series of cases the protuberant cornea has the form of a cone (staphyloma totale conicum). In conical staphyloma the protuberance starting from the margin of the sclera rises gradually all the way to its apex. In other cases, however, the protuberance is hemispherical (staphyloma totale sphæricum), and its walls, rising abruptly from the sclera or even overhanging it, are outlined sharply upon the latter (Fig. 39). The spherical is more frequent than the conical form in total staphyloma. Many spherical staphylomata, above all those of recent date, have such a very thin wall that the layer of black pigment (Fig. 39, *i*) on its posterior surface is seen through it, shining with a bluish luster. Such staphylomata accordingly form a slate-colored or bluish-black hemisphere, which in form and color has a certain resemblance to a blue grape, whence the name staphyloma (*σταφυλή*, a bunch of grapes). Afterward thickening of the wall of the staphyloma occurs. If this takes place first under the form of firm isolated bands, by which the surface of the staphyloma is constricted in spots somewhat after the fashion of a blackberry, what is called staphyloma racemosum is produced. Old staphylomata have for the most part a thick white wall, in which usually one or two dark spots may be observed, resulting either from a deposition of pigment or from localized thinning (Fig. 39, *a*). Staphylomata are generally

traversed by one or two pretty large vessels originating from the conjunctiva. On account of the opaqueness of the staphyloma, nothing is to be seen of the deeper parts of the eye. The iris is all taken up into the staphyloma — that is, all of it except its extreme periphery, which is so closely applied to the posterior surface of what remains of the marginal portion of the cornea that there is no longer any anterior chamber.



FIG. 38.—TOTAL PROLAPSE OF THE IRIS.



FIG. 39.—TOTAL STAPHYLOMA OF THE CORNEA WITH CONSECUTIVE ELEVATION OF TENSION, ORIGINATING FROM THE TOTAL PROLAPSE OF THE IRIS REPRESENTED IN FIG. 38.

Out of the iris, *i* (Fig. 38), which has been thinned out in consequence of its protrusion, a thick cicatrix, *N*, has grown, in which a thin spot, *a*, corresponds to the old pupil (*p*, Fig. 38), while on the posterior surface of the cicatrix the retinal pigment of the iris remains as a black coating, *i*. The staphyloma is apparently directly continuous with the sclera, *S*, from which it is separated only by Schlemm's canal, *s*. For, on account of the elevation of tension, the periphery of the iris has been pressed against the cornea so that the anterior chamber (*v*, Fig. 38) has disappeared, and the iris and the marginal portions of the cornea are fused into a single mass which has been incorporated in the staphyloma. As a comparison of the two figures shows, the corneo-scleral margin has had its limits enlarged. Because of this, and also because of the shrinking of the lens, *L*, the zonula has become tightly stretched, and has drawn the atrophic ciliary processes, *c*, inward. The lens is cataractous, shrunken, and has at its anterior pole a pyramidal cataract, *p*.

A partial staphyloma occupies only a portion of the cornea. It rises as a white prominence, usually in the form of a cone (staphyloma partiale conicum); spherical protuberances (staphyloma partiale sphæricum) are pretty rare in the case of partial staphylomata. The relation here, therefore, is the reverse of what it is in the case of total staphylomata. Partial staphyloma usually extends in one direction as far as the margin of the cornea, while in the other direction there is a portion of the cornea of varying extent which is still left, and which, moreover, is generally transparent, so that the iris can be recognized behind it. The iris is drawn forward to the staphyloma, so that the pupil is displaced toward the latter and often partly concealed by it. Indeed, the pupil may be closed up altogether if the whole pupillary margin of the iris is incorporated in the staphyloma (as is the rule in the case of total staphyloma).

Etiology.—Staphyloma constitutes the final outcome of the corneal ulcer with perforation, and is nothing but the prolapsed iris which has become protruded and transformed into cicatricial tissue. The protrusion may be primary or secondary in its development.

(*a*) *A primary protrusion* is produced in the following way: After perforation of the cornea has occurred, the iris becomes prolapsed and bulges forward. The cicatrization which follows, and which in favorable cases produces flattening of the prolapse, is incapable in unfavorable cases of doing away with the protrusion. On the contrary, the prolapsed iris stays protruded at the same time that it is gradually converted into cicatricial tissue; it becomes consolidated while still in a position of protrusion (thus from the prolapse of iris in Fig. 38 is formed the staphyloma represented in Fig. 39). A total or partial staphyloma develops according as a total or partial prolapse of the iris has existed. The causes which oppose the conversion of a prolapse of the iris into a flat cicatrix and favor the formation of a staphyloma are chiefly two: large size of the perforation and improper behavior on the part of the patient. In very small perforations there is no development whatever of staphyloma; and as regards the second point, the chief factors to be considered are, in adults, great physical exertion; in children, crying, and also squeezing together of the lids; and, in both, great straining at stool. The temporary increase of tension induced by this means distends the newly formed and yielding cicatricial tissue; but as the latter has no elasticity, it does not return to its former dimensions after the elevation of tension has disappeared, but remains permanently protruded.

(*b*) We speak of a *secondary protrusion* when a prolapse of the iris at first heals with the formation of a flat cicatrix, which latter afterward bulges out again. The cause of this is frequently supplied by the same injurious influences that have been enumerated above—e. g., by the too early resumption of work by a patient with a recently cicatrized corneal ulcer. The recent cicatrix is still too yielding to offer a proper resistance to the repeated though transitory elevations of intraocular pressure, and so becomes gradually distended.

A staphyloma, accordingly, in its origin is not a bulging of the corneal tissue, but of the iris. It develops from a prolapse of the iris, which is converted into cicatricial tissue—that is, it develops just at the spot where the cornea no longer exists. It would therefore be more correct to speak of staphyloma iridis. In fact, the transition from prolapse of iris to staphyloma is altogether gradual, so that at a certain stage of its development the protrusion in the eye may be equally well denoted as an old prolapse of the iris or as a recent staphyloma.

Consequences of Staphyloma of the Cornea.—The *sight* is always diminished. In total staphyloma it may be reduced to the mere ability to distinguish between light and darkness. In partial staphyloma the degree of sight depends upon the character of the part of the cornea that is still preserved, and also upon the position of the pupil. Even in the most favorable case, in which a part of the pupil happens still to lie behind perfectly transparent cornea, the sight is considerably

reduced by the irregular curvature which is present not only at the site of the staphyloma itself, but to a less degree over the whole cornea. Large staphylomata produce a very striking disfigurement. They also cause trouble by giving rise through mechanical irritation to catarrhal conditions of the conjunctiva, with increased secretion, lachrymation, etc. The closure of the lids is rendered difficult in the case of large staphylomata by the great size of the protrusion; the apex of the latter, being but incompletely covered by the lids, becomes dry (xerotic), or becomes the site of ulcers (atheromatous ulcers). Sometimes the lids are forced so much apart by the staphyloma that ectropion develops.

Among the most important consequences of staphyloma is the *elevation of tension*, which ultimately takes place in most staphylomata, whether total or partial. This is the consequence, not the cause, of staphyloma, which usually develops under normal intra-ocular pressure and merely as the result of an insufficient power of resistance in the wall of the eyeball. Conical staphylomata predispose to the production of elevated tension more than do the spherical ones. In addition to the increase of pressure within the eyeball, perceptible to the touch, elevation of tension finds its chief expression in a diminution of sight, which finally ends in complete blindness. Pain, too, is sometimes associated with the elevation of tension. As soon as the latter has made its appearance, it gives rise to further changes both in the staphyloma and also in the whole eyeball. Thin-walled staphylomata are made to protrude farther and farther by the heightened pressure, and thus suffer an increasing attenuation of their wall, until the latter, from some trifling cause, ruptures at some particularly yielding spot. Then the aqueous humor is discharged in great abundance, and the staphyloma collapses, becomes smaller, and remains so for some time. But the eyeball slowly fills again up to its former volume, and rupture takes place a second time. Thus the process may be repeated a number of times at pretty long intervals, until at length a time comes when perforation of the staphyloma is followed by profuse intra-ocular hæmorrhage, or by severe irido-cyclitis or panophthalmitis. Then the eyeball undergoes atrophy, and by this means a sort of spontaneous cure of the staphyloma takes place. The scleral portion of the eyeball, too, when the elevation of tension has lasted a pretty long time, gives way and becomes distended, especially in young people in whom the sclera is more extensible. In this case we observe both total and partial ectasia of the sclera. In the former, the sclera becomes uniformly distended, the entire eyeball grows larger, and the sclera becomes so thin as to look bluish owing to the way in which the chorioidal pigment shines through it. In the second case, the sclera in the vicinity of the cornea bulges forward under the form of a circumscribed swelling, which appears dark from the pigment shining through it;

intercalary and ciliary staphylomata (see § 56) are developed. Very frequently general and partial ectasia of the sclera are found simultaneously in the same eye, which may thus grow to an enormous size.

49. Treatment.—Stress is chiefly to be laid upon *prophylaxis*. The physician who has to treat an eye with prolapse of the iris must make every endeavor to secure the production of a flat cicatrix. He should not suffer a staphyloma to develop before his very eyes. In this connection, what has been said in regard to prolapse of the iris (page 149) may be consulted. When we have succeeded in effecting the formation of a flat cicatrix we must, while the latter is still recent, take measures to keep it from bulging out again. With this end in view we should refrain from discharging the patient too soon from treatment, and we must most urgently advise him to abstain for a long time from all severe physical exertion. It is often advisable before discharging the patient to perform an iridectomy, whenever this can be done, as by this means the subsequent development of an ectasis is most effectually counteracted.

If we have to do with a staphyloma which has already developed, our treatment must have a different object in view, according as the case in hand is a total or a partial staphyloma. With the former the sight is irreparably lost, since there is no transparent cornea left; we must hence confine ourselves to the relief of the symptoms produced by the staphyloma and also of the disfigurement. With partial staphylomata, our first aim is to improve whatever sight may be left, or at least to preserve it from further injury (by increase of tension). The methods which are employed for the cure of staphyloma are all of an operative character.

(*a*) *Total Staphyloma.*—The simplest procedure is *incision* of the staphyloma. This is done with the expectation that as a consequence of it the staphyloma will collapse, and, because of the retraction of the cicatricial tissue of which it consists, will remain permanently flat. This procedure is evidently crowned with success only when the staphyloma is thin-walled enough to collapse after the incision has been made; it is, therefore, indicated only in those recent staphylomata which are still akin to prolapse of the iris. The incision is made by means of a cataract-knife. The section is made in various ways: either in a rectilinear direction and transversely across the middle of the staphyloma (Küchler), or in a curved direction and concentrically with the lower corneal margin, so that a flap is formed of the wall of the staphyloma. The latter way of making the section has the advantage of causing a marked gaping of the wound, since the flap shortens in consequence of the retraction of the cicatricial tissue. Consequently, the lips of the wound are prevented from rapidly reuniting, in which case the ectasis would soon be reproduced and the incision would have to be repeated. If the wound in the flap should not gape sufficiently, the flap must be

shortened by the removal of a part of it. After the completion of the section, the lens, in case it is still in the eye, must be removed by lacerating the anterior capsule.

Simple ablation of the staphyloma, after the method of Beer, is performed by first separating the lower half of the staphyloma from its base by a curved incision made with the cataract-knife. The flap thus formed is grasped with the forceps, and then the upper half of the staphyloma is cut off from its base by means of the scissors. The lens, which now presents, is removed by opening the capsule. The gap which has been substituted for the staphyloma by the operation gradually becomes closed by means of a firm, flat cicatrix. Beer's method is suitable for old staphylomata with thick walls. It must be mentioned as one of the disadvantages of the operation, that the after-treatment lasts a long time, and requires special caution on the part of the patient. Even in the operation of simple incision, but still more in that of ablation, an opening is produced in the anterior wall of the eyeball, in which opening, after the lens has been removed, the vitreous presents. This is kept back only by the very bulging and tense hyaloid membrane; and if the latter ruptures, as generally happens, a part of the vitreous flows off. A moderate loss of vitreous has no bad result; but if the escape of vitreous is very profuse, violent hæmorrhage may ensue from the interior of the eye. Moreover, the vitreous that hangs out of the wound may become infected by the secretion of the conjunctiva, and thus panophthalmitis may develop. In order, if possible, to avoid the rupture of the hyaloid membrane, or at least any considerable escape of vitreous, great quiet on the part of the patient (rest in bed and avoidance of any bodily exertion) is requisite for quite a long time after the operation. For this reason, in the case of those patients of whom a quiet behavior is not to be expected (so especially in children), ablation had better be conducted according to other methods, in which the opening produced by the ablation is closed by a suture, and the vitreous is thus held back in the eye.

Ablation with the subsequent application of a suture may be done in two ways, the suture being carried either through the borders of the staphyloma or through the conjunctiva (De Wecker). In the former case, we leave, when performing ablation of the staphyloma, a somewhat broader rim above and below, through which we pass the sutures; after the removal of the lens the sutures are tied, and thus the upper is united to the lower lip of the wound. In the second case, at the beginning of the operation we divide the conjunctiva all round the limbus and separate it for some little distance from the subjacent sclera, so that it can be drawn forward to the proper extent. Then we pass the threads through the free ends of the conjunctiva. We draw through its upper and lower margin a number of vertical threads, which subsequently are tied so as to form interrupted sutures. Before the sutures

are drawn tight, we ablate the staphyloma as in Beer's methods, and expel the lens from the eye. Then we close the conjunctival wound by knotting the sutures. We may also apply the suture by passing a single thread in and out all round the margin of the detached conjunctiva, in such a way that the two ends of the thread come out close by each other, and, when they are knotted together, constrict the conjunctiva after the manner of a tobacco-bag (tobacco-bag suture). In this case, too, the ablation of the staphyloma and the delivery of the lens are not done until after the thread has been passed through the conjunctiva. For, after the removal of the lens, there is imminent danger of the expulsion of the vitreous, and hence we ought not to be losing time in applying sutures, but, on the contrary, should have it in our power to close the wound promptly by tying a thread that has been already passed.

Ablation with the application of a suture is, like simple ablation, suitable for all cases of old staphylomata with thick walls, for which incision alone would not be sufficient. It has the advantage over simple ablation of requiring a less troublesome after-treatment.

Those cases of staphyloma of the cornea in which an increase of tension and secondarily an ectasis of the sclera have developed, are in general not adapted for ablation. We should then run the risk of getting a violent hæmorrhage in consequence of the sudden diminution of the previously increased tension. For such cases, in which the eyeball is increased sometimes to quite an enormous size, the only thing feasible is *enucleation*, which relieves the troublesome symptoms and at the same time also the disfigurement, inasmuch as an artificial eye can then be worn in place of the hideous, enlarged eyeball. For the method of performing enucleation, see the section on operations (§ 166).

(*b*) *Partial Staphyloma.*—In this, treatment seeks a threefold object: to improve the sight, to cause flattening of the ectasis, and to prevent the development of an increase of tension, or to do away with it in case it has already set in.

Simple incision, which must be followed up by the application of a pressure bandage for a pretty long time, accomplishes its end only in recent staphylomata, the walls of which are still thin. In older and thicker cicatrices, *excision*, with or without the operation of uniting the edges of the wound by sutures, is to be preferred. But the most approved remedy that we possess against ectatic cicatrices is *iridectomy*. This should be performed in such a way that the incision lies in the sclera and a broad coloboma is produced, reaching to the margin of the iris. We do not select for iridectomy that part of the iris which is drawn into the cicatrix, as we might do with the idea of relieving in this way the incarceration of the iris; an iridectomy at this spot would on technical grounds be very difficult of performance, and often would turn out to be imperfect. We try rather to find for our iridectomy that

spot which corresponds to the greatest improvement that can be made in the vision, the pupil being shifted to a point behind the most transparent part of the cornea. Furthermore, by means of the iridectomy, an increase in tension is prevented from developing, or, if it has already developed, it is done away with. Moreover, in cases of staphylomata with thin walls, a flattening of the ectasis is obtained by the iridectomy, if the eye is kept beneath a pressure bandage for a long time after the operation. In thick-walled and unyielding staphylomata, it is advisable to combine excision with iridectomy. We begin by doing the former, and put off the iridectomy to some weeks later, when the formation of a flat cicatrix has taken place—doing this in order to prevent the renewed bulging of the freshly formed cicatrix.

If we have to do with a partial staphyloma in which, owing to the increase in tension, the sight has been already either in great part or altogether annihilated, no gain in this regard can be expected. Nevertheless, it will be advisable to perform an iridectomy in most cases in order to prevent the further consequences of the increased tension, such as partial ectasis of the sclera, enlargement of the entire eyeball, etc. Of course, iridectomy can be performed in such cases only so long as the anterior chamber is still existent. As soon as the iris, in consequence of the increased tension, has been squeezed against the posterior surface of the cornea and has become cemented to it, the performance of iridectomy has become technically impossible.

It can not be denied that, in spite of the therapeutic means at our command, the cicatrix in many cases keeps constantly bulging anew, the increase in tension returns each time, and thus the eye slowly but inevitably goes blind.

Anatomy of Staphyloma of the Cornea.—The wall of the staphyloma consists of a dense, tough cicatricial tissue, which is traversed by a few vessels, and often contains pigment imbedded in it. The thickness of the wall differs greatly; it varies from the thickness of a sheet of paper to a thickness three times as great as that of the normal cornea, and more. Very thick staphylomata are often as hard as cartilage, and when ablation is performed can scarcely be cut through. Thick and thin spots frequently occur in the wall of the same staphyloma (Fig. 39). The anterior surface of the staphyloma is covered by a thick, irregular layer of epithelium, sometimes containing epithelial pearls. The posterior surface is frequently uneven, on account of the inequality in thickness of the wall. It is covered by a coating of black pigment (*i*, Fig. 39), which is nothing but the retinal pigment-layer of the iris. As, however, this has to be distributed over such a large surface, it is rarefied, so that the epithelial coating shows numerous gaps, and in the center of the staphyloma, corresponding to what was once the pupil, it is often entirely wanting. Through staphylomata with thin walls light can be passed by means of focal illumination, and in this way the pigment-layer can be demonstrated in the living eye. It is easy to see why Bowman's membrane should be wanting on the anterior surface of the staphyloma, and Descemet's membrane on its posterior surface,

since the staphyloma is not cicatrized cornea, but is iris, and corresponds to a spot at which the cornea has been destroyed. It is only at the outlying parts and the edges of the staphyloma, which are formed of the remains of the cornea, that both these membranes can still be demonstrated. This is especially true of a conical staphyloma, in which the adjacent portions of the cornea are extensively involved in the ectasis. In total staphyloma the iris may be wanting altogether, being completely consumed in the formation of the staphyloma (Fig. 39). In other cases a narrow rim of iris is present at the periphery, corresponding to the persistent marginal portion of the cornea. In that case the iris is generally closely applied to the cornea, and is so atrophic as to be reduced almost to its pigment-layer. In partial staphyloma, perfect application of the iris to the cornea is found only in those cases in which the entire pupillary margin of the iris has become involved in the cicatrix; the separation of the anterior from the posterior chamber, that is thus produced, causing the iris to be pushed forward up to the cornea.

As the anterior chamber becomes shallower the posterior becomes deeper; in total staphylomata, the whole large space between the posterior surface of the staphyloma and the lens is to be looked upon as the posterior chamber (*h*, Fig. 39). The ciliary body suffers mainly on account of the increase in tension, which causes it to atrophy, especially if an ectasis of the sclera develops in the ciliary region (staphyloma ciliare). Furthermore, the ciliary processes are sometimes very strongly pulled upon by the fibers of the zonula, and are thus elongated (*e*, Fig. 39).

The lens very frequently suffers changes in the case of staphylomata. In total staphylomata it is often entirely wanting, because it has been discharged from the eye through the pupil at the time when a large perforation existed. If the lens is still present it frequently shows alterations of position, being placed obliquely in consequence of the unequal bulging of the staphyloma. Sometimes we find it partially adherent to the staphyloma, or it vibrates with the movements of the eye, because of the atrophy of the stretched zonula of Zinn. These alterations in the lens favor the development of an increase in tension; for this reason, after performing incision or ablation of the staphyloma, we remove the lens from the eye. Very frequently the lens is rendered opaque either in toto or only at its anterior pole (anterior polar cataract, *P*, Fig. 39). In some few cases we may find the lens greatly diminished in size, or even shrunken into a mere membrane.

The deeper parts of the eye also suffer from the increase in tension. Excavation of the optic nerve, atrophy of the retina and chorioid, and fluidity of the vitreous may develop.

With respect to the *increase of tension* in staphyloma, we not infrequently meet with the view that in it resides the cause of the staphylomatous protrusion. But this is true for only a very small number of cases. Generally it happens contrariwise, that the increase of tension is nothing but the consequence of the ectasis. The latter, in fact, takes place when there is a normal intraocular tension, which the thinned anterior wall of the eyeball is unable to resist, because it consists merely of iris or of new and yielding cicatricial tissue. The exaltations of tension that do occur are at best transient, being produced by bodily exertion, strong pressure, screwing together of the lids, etc. But these must be strongly differentiated from a pathological increase in tension, not only because they are of but short duration, but mainly because they occur

under similar circumstances even in the normal eye and are tolerated with impunity. The permanent increase in tension (so-called secondary glaucoma) which we so frequently find in staphylomatous eyes is hence, with but few exceptions, to be regarded as the consequence and not the cause of the staphyloma.

As a rule, the increase of tension resulting from staphyloma develops quite gradually. But sometimes protrusion of the cicatrix and increase of tension take place simultaneously and in a sudden fashion, as the following example may illustrate: A person has had an abscess of the cornea, which has destroyed the latter in its central part. Under suitable treatment the prolapsed iris is in process of transformation into a flat cicatrix. Then, one morning the patient complains of violent pain which has suddenly developed in the eye. After removing the bandage we find the eye, which the day before was almost free from irritation, now the seat of a dusky ciliary injection. The cicatrix is bulged forward in the form of a cone, the anterior chamber is very shallow, or is altogether done away with, by the iris being pressed against the cornea, which latter looks dull. Small hæmorrhages are visible in the cicatrix or in the anterior chamber. The eye is hard, and very sensitive to the touch. An external cause for this sudden change in the course of healing is generally not discoverable.

In what way does the presence of a staphyloma lead to an increase of tension? In those cases in which the entire pupillary border of the iris is implicated in the staphyloma (that is, in all total and many partial staphylomata), the increase in tension can readily be accounted for by the closure of the pupil (seclusio pupillæ, see § 69). But for those cases of partial staphyloma in which a part of the pupil remains free, it has been impossible to give any thoroughly satisfactory explanation of the increase in tension. Some regard as the cause of it the strain to which the iris is subjected. The resulting irritation of the iris and of the ciliary body is assumed to give rise to an increased excretion of the fluids of the eye. The strain upon the iris results from its being stretched between two points: its point of attachment to the sclera, on the one hand, and the cicatrix to which it is adherent, on the other. In proportion as the cicatrix bulges forward and thus gets its apex farther and farther removed from the corneal margin, the more is the iris put upon the stretch. Arlt from this principle endeavored to explain why conical staphyloma entails an increase of tension much more frequently than the spherical variety. The latter is formed whenever the margins of the perforation shelve off abruptly, so that the cornea even in the immediate neighborhood of the aperture has its normal thickness. If now the prolapsed iris protrudes, the adjacent corneal tissue takes no part in the process. The margins of the prolapse rise at right angles to the adjacent cornea, and thus a spherical staphyloma is formed (Fig. 39). In such a case, the cornea surrounding the staphyloma is not prolonged forward at the time the latter is formed nor afterward either; the iris which lies behind this portion of the cornea is subjected to no strain, because it is fixed to the margin of the perforation, and hence the danger of an increase of the tension is here comparatively slight. If it does occur, it is effected not by the strain upon the iris but by the complete inclusion in the cicatrix of the pupillary margin of the iris and the resulting seclusio pupillæ. A conical staphyloma is the consequence of an extensive ulcer which has broken through in a limited portion of its area only. The margins of the aperture hence slope gradually toward the latter, and on account of their thinness become pressed forward at the same time as the prolapsed iris. The fully

developed ectasis, therefore, consists only in its central portion of the old prolapse of the iris; its outer slope is in great part formed by the thinned-out cornea. For this reason the ectasis does not rise directly from the cornea, but makes a very gradual ascent from the margin of the latter, so that a conical form is thus given to it. In this case, not only the prolapsed iris but also the adjacent cornea, wherever it is involved in the ectasis, is subjected to a process of stretching; and, as the iris is adherent to the cornea at the margin of the perforation, it is stretched along with the cornea, and can thus give rise to an increase in tension. (Opposed to the idea of a strain upon the iris being the cause of an increase in tension is the fact that we do, though rarely, observe cases in which an ectatic cicatrix of the cornea unassociated with involvement of the iris entails all the same an increase in tension.) Others call in the displacement of the sinus of the anterior chamber to account for the increase of tension (see § 85); for at those spots at which the iris is involved in the cicatrix it is drawn well forward, and is consequently applied by its periphery to the anterior border of the sclera and to the adjacent cornea, and closes in the angle of the anterior chamber. This explanation is always to be adopted for those cases in which, on account of an involvement of the whole pupillary margin, seclusio pupillæ is present. In this case the iris is everywhere driven forward by the accumulation of aqueous humor in the posterior chamber, and the sinus of the anterior chamber is thus obliterated all round the circumference.

2. *Keratectasia.*

50. By keratectasia we understand a protrusion of the cornea, which makes its appearance after inflammation of the latter, without, however, any perforation having taken place. The protrusion, therefore, in this case consists of corneal tissue, in contradistinction to staphylomata, in which it is formed of the tissue of the iris. From ectasiæ of the cornea of non-inflammatory origin—i. e., keratoconus and keratoglobus—the inflammatory ectasia of the cornea is distinguished by the fact that the bulging portion of the cornea, in consequence of the inflammation, is opaque.

Inflammation produces protrusion of the cornea by thinning it or by softening it. It produces protrusion by *thinning* in those cases in which an ulcer of the cornea has destroyed the superficial lamellæ of the latter to such an extent that the posterior lamellæ are no longer able by themselves to offer resistance to the intra-ocular pressure (*keratectasia ex ulcere*, Fig. 40). If all the layers as far as the membrane of Descemet have been destroyed, a hernia of this membrane (keratocele) is produced, which may cicatrize in this ectatic form. In this case this hernia persists as a perfectly transparent vesicle which projects above the surface of the cornea, and which is surrounded by an opaque cicatricial ring.

Ectasis of the cornea may also take place because of a *softening* that results from inflammation. Under this head belong the *keratectasia e panno*, which develops when a thick pannus penetrates pretty deeply into the cornea proper, and the keratectasia following paren-

chymatous keratitis. In these cases the cornea protrudes as a whole and uniformly, while in keratectasia ex ulcere it is generally only a local protrusion that exists.

A consequence common to all inflammatory ectasiæ of the cornea is that the protruding portions have very little power of regaining their

FIG. 48.—KERATECTASIA EX ULCERE. MAGNIFIED 25×1.

The thinned and bulging cicatrix. *N*, is distinguished from the surrounding normal cornea by its denser structure. The epithelium, *c*, over it is thickened, while Bowman's membrane, *b*, is wanting in this spot. On the other hand, Descemet's membrane, *d*, along with its epithelium, is everywhere present—a proof that the ulcer has not perforated.

transparency. Accordingly, the prognosis for vision in pannus, keratitis parenchymatosa, etc., must be regarded as essentially more unfavorable as soon as protrusion of the cornea shows itself. In comparison with the marked opacity of the bulging cornea, the alteration of curvature and the resulting alteration of refraction of the eye are of little account. Sometimes keratectasia is followed by increase of tension.

Treatment is powerless against a fully developed keratectasia; it is attended with success only when there is a question of combating a protrusion that is in process of development. The means suited for this latter purpose are repeated punctures of the cornea with the subsequent application of a pressure-bandage, and iridectomy. Very small ectasiæ, as, for example, small keratoceles, we may perforate with a cautery-point and then induce the formation of a flat cicatrix by the long-continued application of a pressure-bandage.

3. *Keratoconus.*

51. Symptoms and Course.—In keratoconus, the central part of the cornea very gradually and without inflammatory symptoms begins to bulge forward in the form of a cone. At first the cornea is perfectly transparent, and its peripheral portions keep their normal curvature. Accordingly, the bulging forward of the center of the cornea, as long as it has not advanced too far, is only recognized by the diminution in size which the corneal reflex undergoes in the central part of the cornea. In the subsequent course of the disease the bulging of the center constantly increases, and the peripheral parts of the cornea are also in-

volved in the conical projection, so that we can perceive the conical shape of the cornea at once, especially upon taking a lateral view of the eye. Last of all, the apex of the cone becomes opaque and uneven in surface.

To the patient the disease makes itself apparent only by the disturbance of vision. The eye becomes apparently myopic, so that all objects have to be brought up very close. Nevertheless, perfectly sharp vision is not attainable by means of spherical concave glasses, because the bulging of the cornea is not spherical, but conical (hyperbolic). By the development of the opacity at the apex of the cone the visual power is, of course, still further depressed.

Keratoconus is a rare disease, which, as a rule, affects both eyes. It begins for the most part between the twelfth and the twentieth year, develops very gradually in the course of years to the height above described, and ultimately, sooner or later, comes to a standstill. A subsidence of the ectasis is not observed; but ulceration or rupture of the cornea is not observed either. Nor does increase in tension, which so frequently develops in inflammatory ectasiæ of the cornea, occur.

The *cause* of the protrusion lies in a progressive thinning of the central portion of the cornea, which consequently give way before the intra-ocular pressure. By what means this thinning is produced is unknown.

Treatment can point to but slight results in this disease. In recent cases that have not yet gone too far, we may try to put a stop to the process by thorough protection of the eye, by general corroborative measures, and by the long-continued instillation of a miotic (eserine or pilocarpine). The marked contraction of the pupil thus produced lowers the tension in the anterior chamber, and thus lessens the burden imposed upon the attenuated cornea. A few cases have been thus put a stop to (Arlt); a like result may perhaps also be attained by iridectomy. Finally, a series of methods aims at the substitution of a resistant cicatrix for the attenuated apex of the cone. For this purpose the latter is destroyed by excision or by cauterization, or by both combined. Since the corneal cicatrix thus obtained lies directly in front of the pupil, a displacement of the pupil to one side by means of an iridectomy is afterward usually required.

4. *Keratoglobus.*

In keratoglobus, the cornea as a whole is larger than normal. It constitutes but one of the symptoms of a general enlargement of the eyeball, which belongs to hydrophthalmus (buphthalmus), for which reason reference must be made to the latter disease (§ 84) for its description.

By many authors the expression staphyloma corneæ is employed in a broader sense, and all ectasiæ of the cornea are designated under this name. In that

case a further division of the term is made by distinguishing the transparent ectasiæ of the cornea, keratoconus and keratoglobus, under the name of staphyloma pellucidum, from cicatricial staphylomata and keratectasiæ.

In *keratoconus*, the thinning of the cornea within the area of the conical protrusion can be demonstrated by the facility with which the apex of the cone can be dimpled by means of a sound. Anatomical examinations have also demonstrated that the cornea may be reduced in its center to a third of its normal thickness (Wagner, Hulke). A keratoconus of slight degree may be readily overlooked, since the cornea is perfectly transparent. The diagnosis, however, can be made even in the earlier stages, not only by examining the corneal reflex, but also by means of ophthalmoscopic examination. If we illuminate the pupil with the ophthalmoscope, we see in the red field of the former an annular shadow which is particularly dark at one spot; this spot changes with the movements of the mirror. In high degrees of keratoconus, in which the apex is already opaque, the distinction from a keratectasia following a central ulcer of the cornea is often very difficult. We must then take into consideration the condition of the other eye. In keratoconus we almost always find the second eye diseased as well, although not ordinarily to the same extent; while a central keratectasia could only by a rare accident be present at the same time in both eyes.

Keratoconus affects the female more frequently than the male sex. Those attacked by it not only see worse in the line of direct vision, but their indirect vision is also impaired, since the rays which enter the eye through the side of the cone are very irregularly refracted. The consequence of this is faulty orientation in going about, such as is not present in simple myopia even of very high degree (Arlt). A moderate improvement of vision can generally be obtained by the use of strong concave spherical glasses, either alone or combined with concave cylinders. In many cases the hyperbolic glasses proposed by Raehlmann do good service. With these, the patient, to see clearly, must look just in line with the optical axis of the glass; they can not, therefore, be used for sidelong vision, and consequently not for going about. The same is true of the stenopæic slit, which, held in the patient's hand close before his eye, facilitates the recognition of small objects, such as fine print.

Tumors of the Cornea.—Tumors which develop primarily in the cornea are among the greatest rarities; for the carcinomata and sarcomata which are observed upon the cornea do not originate there, but in the adjacent conjunctiva, and in fact generally in the limbus. These tumors have been already considered under the head of diseases of the conjunctiva; so also has been the dermoid, a congenital form of tumor, situated partly upon the cornea, partly in the conjunctiva.

CHAPTER III.

DISEASES OF THE SCLERA.

ANATOMY.

52. THE sclera,* together with the cornea, forms the fibrous envelope of the eye, the shape of which is nearly that of a sphere having a constriction corresponding to the base of the cornea. The mean diameter of this sphere (length of the axis of the eye) amounts to twenty-four millimetres. The sclera is thickest in the posterior segment of the eyeball, where it has a thickness of about one millimetre. It gradually diminishes in thickness anteriorly, becoming, however, somewhat thicker in the most anterior segment, because here the tendons of the recti muscles become fused with and reinforce it.

The histological structure of the sclera is very similar to that of the cornea. The sclera consists of fine fibrillæ of connective tissue, which are united into bundles. These run, generally speaking, in two directions—from before backward (meridional fibers), and in a direction concentric with the margin of the cornea (circular or equatorial fibers). Between the bundles are found lymph-spaces which are in part lined with flat cells, thus forming an analogy with the system of lymph-spaces and the corneal corpuscles of the cornea. The tissue of the sclera and of the cornea are hence very similar to each other, and, moreover, at the corneal margin pass into each other without any sharp line of demarkation. They are chiefly distinguished by the arrangement of the bundles of fibers, which is much more regular in the cornea than in the sclera.

The sclera also contains branched pigment-cells, which for the most part are met with only in its deep layers and also along the vessels and nerves which traverse it. In the living eye we often perceive the pigment in the spots where the anterior ciliary veins emerge from the sclera, these spots appearing as small brown points upon the white membrane. Sometimes we find in the human eye larger, slate-colored or light-violet spots upon the sclera due to an abnormal pigmentation. Such pigmentation as this is the rule in many animals. If the sclera is thin, the pigment of the subjacent chorioid is seen as a dark substance shining through it. In this case, which occurs especially in children, the white of the eye has a bluish tint, like thin white porcelain.

---

* From *σκληρός*, hard.

The sclera is traversed by vessels and nerves which penetrate into the interior of the eye, but has itself very few vessels. On the other hand, there are numerous vessels contained in the so-called episcleral tissue, that loose connective tissue which envelops the sclera and in the anterior segment of the eye attaches the conjunctiva to it. In the posterior segment of the eye the optic nerve passes through the sclera, which here apparently has an aperture for the passage of the nerve (foramen scleræ). In reality, however, the inner layers of the sclera are continued as the lamina cribrosa through the foramen scleræ (Fig. 9; for more precise particulars, see § 101).

I. Inflammation of the Sclera.

53. Inflammation of the sclera (scleritis), which belongs among the rarer affections of the eye, is always limited to the anterior segment of the sclera, lying between the equator of the eyeball and the margin of the cornea. It sometimes affects only the superficial layers of the sclera, sometimes the deep layers also. In the first case the disease runs its course without entailing any injury upon the eye; but in the second case it is dangerous to the sight, inasmuch as the inflammation passes from the sclera to the other membranes of the eye. It is hence of practical importance to distinguish between a superficial and a deep form of the disease (episcleritis and scleritis of authors).

(a) *Superficial Form of Scleritis (Episcleritis).*

This form makes its appearance as a localized inflammation, a circumscribed inflammatory nodule forming in the sclera. At the affected spot the sclera, owing to the deposition of exudate, bulges out in the form of a boss, so that a prominence which is sometimes flat, sometimes more acute, and which may reach or surpass the size of a lentil, is found here. This is traversed by vessels which, because deeply situated (episcleral), are violet in color; and it is immovably attached to the sclera, while the conjunctiva, though to be sure injected, can be moved about freely. The nodule feels hard, and is sometimes very sensitive to the touch. Except at the site of the nodule the eye may be perfectly free from injection. The subjective disturbances vary greatly; frequently the disease is associated with but slight discomfort for the patient, while in other cases very violent pain is present, which for a long time deprives the patient of sleep.

In the subsequent course of the disease disintegration and ulceration of the nodules never occur; on the contrary, they always disappear by resorption. After the inflammation has remained at its acme for some weeks, the nodule gradually flattens, becomes paler, and at length disappears completely, after lasting altogether from four to eight weeks. Sometimes it leaves no trace behind it; more frequently, how-

ever, at the spot where it was situated a slate-colored spot is left, and in its place the sclera appears somewhat depressed and the conjunctiva is closely adherent to it (cicatrix in the sclera). In other respects the eye experiences no after-injury from the inflammation.

Scleritis is an eminently chronic disease, since it has the peculiarity of recurring very often. As soon as the first nodule has disappeared—or even earlier—a second one appears upon another portion of the sclera. Sometimes the disease does not cease until nodules have developed, one after another, in the entire circumcorneal space, and at length a zone of gray discoloration is visible entirely surrounding the cornea. By this time the disease has exhausted itself, since a new nodule does not generally develop in the spot where another was situated before. But, before it has gone as far as this, several years may have elapsed, during which the patient with but short interruptions is annoyed by attacks of inflammation. In addition to this the disease very frequently attacks both eyes. The *prognosis* of the superficial form of scleritis is hence unfavorable in respect to the duration of the disease; while with regard to the final outcome it must be stated as favorable, because the capacity of the eye for vision suffers no impairment, even if the process lasts a long time.

Superficial scleritis occurs, as a rule, only in adults, and especially in elderly people. In some cases it appears to be connected with rheumatic or gouty affections; in others its origin is obscure. Treatment avails but little against it. We are able to ameliorate the symptoms and accelerate somewhat the subsidence of the nodules, without having it in our power to prevent the recurrences. Sodium salicylate is given internally, if there are any grounds for the assumption of a rheumatic origin for the disease; otherwise, diaphoretic methods of treatment, derivative remedies in the shape of mildly purgative mineral waters, iodide of potassium, etc., may be recommended. As regards local remedies, we may try to produce more rapid subsidence by means of massage (Pagenstecher). Fat, either without addition or under the form of the yellow-precipitate ointment, is introduced into the conjunctival sac, and the nodule, which can be felt through the lid, is then rubbed and squeezed through the lid by means of the fingers. If the disease is associated with violent pain, we may employ moist and warm compresses, atropine, and local blood-letting (six to ten leeches upon the temple) in addition to the massage; the latter procedure, indeed, in these cases frequently can not be performed because the nodule is too painful. In this event scarification of the nodule (Adamück) or scraping with the sharp spoon (Schöler) has been recommended.

(*b*) *Deep Forms of Scleritis.*

In this form, too, a swelling of the sclera exists, which may make its appearance under the form of isolated prominences, but which more

frequently is not so sharply circumscribed. In the latter case the sclera shows an extensive bluish-red injection, sometimes covering the whole circumcorneal region, and a more uniform swelling not composed of isolated prominences. But the deep is distinguished from the superficial form most of all by the course of the inflammation and by its being communicated to other parts of the eye.

The inflammation in the sclera in this case also does not lead to disintegration of the inflammatory products, but to their disappearance by resorption with the formation of a residual dark-colored cicatrix. In the mean time, however, the sclera has been undergoing considerable attenuation at the site of the cicatrix, so that it is no longer able to offer resistance to the intra-ocular pressure, even though this does not exceed its normal amount. Hence *ectasis* of the diseased spot occurs. This makes its appearance under two forms—either as simple enlargement of the surface, or as a gibbous protrusion of the thinned-out portions of the sclera. In the former case the entire circumcorneal zone of the sclera, which has been colored gray by the scleritis, becomes constantly more and more dilated. Consequently, the cornea, together with the adjacent portions of the sclera, projects farther forward, so that the eyeball becomes elongated in the sagittal direction and pyriform. In the second case, on the contrary, a circumscribed protrusion of the thinned-out spots, raising them above the level of the healthy sclera, is produced, so that there are seen rising about the cornea a number of humps, which, because of their thin walls, show the dark pigment shining through. As these are comprised in the region of the ciliary body, they are called ciliary staphylomata. In both varieties of ectasis there generally occur subsequent elevation of tension, general enlargement of the eye, and finally complete blindness.

Complications affecting other portions of the eye are likewise a peculiarity of the deep form of scleritis. They affect both cornea and uvea. In the cornea, infiltrates, deeply situated, develop, which do not break down into pus but become absorbed again, leaving a permanent opacity (sclerosing keratitis, see page 182). In the iris we find the signs of iritis, mainly under the guise of posterior synechiæ and even of occlusio pupillæ, but never of hypopyon. In the chorioid, the inflammation affects chiefly its most anterior portion, and causes injury to vision chiefly through the accompanying opacities in the vitreous. So in this form of scleritis almost all parts of the eye suffer; and for this reason it must be looked upon as much more dangerous than the superficial form.

Deep scleritis almost always affects both eyes, and, as treatment is unable to arrest it, is prolonged over a course of years. It leads to the formation of dense corneal opacities, to seclusio pupillæ with its baneful consequences, to opacities of the lens and vitreous, to myopia of high degree due to the elongation of the axis of the eye, and finally to eleva-

tion of tension due to the ectasiæ in the sclera. Hence the disease always ends by producing great impairment or even complete loss of sight.

The deep form, in opposition to the superficial variety, mainly affects young people (but not children). It is often found in conjunction with the signs of scrofula, tuberculosis, or hereditary syphilis. In the female sex, which is more frequently attacked than the male by this disease, disturbances of menstruation appear to furnish the exciting cause.

Treatment has very little power over deep scleritis. It has first of all to combat any constitutional affection that may lie at the root of the disease, and for this purpose the preparations of iodine (iodide of potassium, iodide of iron, iodureted mineral waters), or, in case of the disturbances of menstruation, the preparations of iron are employed. As concerns the eye itself, the inflammation of the cornea and iris must be treated in the appropriate way. In the subsequent course of the disease iridectomy is frequently required, either for optical reasons, to place the pupil behind that part of the cornea that is still transparent, or to prevent the elevation of tension which may be excited by the seclusio pupillæ or by the ectasiæ of the sclera. Iridectomy, however, should, if possible, not be performed until after the subsidence of all inflammatory symptoms.

The superficial and the deep variety of scleritis are not at all sharply distinguished from each other, but show many transition forms. We can not, in fact, see in the living eye how far the inflammation penetrates into the sclera. When we make the assumption that in the deep form the inflammation does extend more deeply, we have no direct proof of it; we can only infer this indirectly from the subsequent thinning of the sclera and from the spread of the inflammation to the subjacent uvea. In fact, many authors assume that the real starting-point of the inflammation in this form lies in the uvea, and they call it, therefore, sclero-chorioiditis or uveo-scleritis. All our views, however, in regard to the real location of the disease are of a purely hypothetical nature, since so far no accurate dissection of an eye affected with scleritis has been forthcoming.

Scleritis in the well-marked cases is a very characteristic and easily recognizable disease. In light and abortive cases the diagnosis is sometimes difficult. For instance, a scleritic nodule which is small and situated particularly close to the margin of the cornea, might be taken for an efflorescence of conjunctivitis lymphatica. The following characters may be regarded as distinctive: the scleritic nodule never actually lies in the limbus, and besides is not situated in the conjunctiva, but beneath it, so that the latter can be moved about over it. Lastly, the subsequent course will soon clear up the diagnosis, as the lymphatic nodule is converted by superficial disintegration into a conjunctival ulcer—a thing which never occurs with a scleritic nodule.

In parenchymatous keratitis we sometimes find a coincident, slight but widely diffused, circumcorneal scleritis. Isolated nodules are sometimes also observed in the sclera as a result of syphilis, but a typical recurrent scleritis never arises from this cause.

The gray spots left upon the sclera by the superficial form of scleritis are not ectatic, from which it may be concluded that in this case, at any rate, the sclera is not much attenuated. But whether the dark coloration of these spots depends upon the subjacent chorioidal pigment which shines through the sclera, or whether a deposition of pigment has taken place in the sclera itself, has not so far been certainly determined. In the deep form of scleritis, the sclera in the zone directly adjoining the cornea is frequently of the luster of porcelain, and white with a tinge of violet (Arlt).

Ectasiæ of the anterior segment of the sclera, developing as a result of deep scleritis, are accounted for upon essentially different grounds from ectasiæ, which make their appearance in this region under other circumstances. Distention of the anterior segment of the sclera (ciliary and intercalary staphylomata) is in most cases the consequence of an elevation of the intra-ocular pressure, which, when lasting for a long time, forces the sclera which was originally normal to give way; the attenuation of the sclera is simply a result of its protrusion. In scleritis the facts are reversed. Here the primary event is the attenuation of the sclera; the latter, therefore, gives way, although the intra-ocular pressure is normal and remains so for a long time. The elevation of tension, which finally makes its appearance in this case also, occurs only as a sequel to the ectasis.

II. Injuries of the Sclera.

54. All traumatisms affecting the cornea and conjunctiva are also met with in the sclera. Injuries of the sclera are chiefly of importance when they perforate it completely. The fact that an injury of the eyeball is or is not associated with *perforation* of the tunics of the eye is of great significance, since every injury of the former kind, however insignificant otherwise, is to be regarded as very serious. The reason of this is that there is a possibility of an infection of the interior of the eye taking place at the same time as the perforation; but this almost always leads to a severe form of inflammation that is very destructive to the eye. This is true for perforating wounds of the cornea as well as of the sclera, for which reason the statements made in the following pages may be applied to both.

The most important *symptoms* of the presence of a perforation are:

(*a*) The diminution of the intra-ocular tension. This symptom is particularly valuable in the case of small wounds in the sclera, which are concealed by the ecchymosed conjunctiva, and are hence not directly accessible to inspection. The diminution of tension, of course, lasts only as long as the wound is open.

(*b*) If the perforation has occurred in the region of the anterior chamber, the latter is shallower or altogether obliterated, until the wound closes.

(*c*) In the case of somewhat larger wounds the prolapse of the subjacent structures gives evidence of the presence of a perforation. Most frequently it is the uvea which protrudes from the wound under the form of a darkly pigmented mass. According to the situation of

the wound, the prolapsed portion belongs to the iris, to the ciliary body, or to the chorioid. If the uvea is ruptured, some vitreous is found hanging out of the wound. Very frequently, too, there are extravasations of blood in the interior of the eye, which to be sure, often likewise occur in the case of non-perforating contusions of the eye. Blood extravasated into the anterior chamber generally sinks to the bottom of it soon after the occurrence of the injury, so that, like a hypopyon, it fills up the lowermost part of the chamber and is bounded above by a horizontal line (*hyphæma* *). Blood in the vitreous often makes itself evident by a reddish reflex from the pupil (*hæmophthalmus* †).

Perforating wounds of the sclera are distinguished into clean-cut and lacerated wounds. The former are produced by the penetration of sharp-pointed or sharp-edged foreign bodies; moreover, incised and punctured wounds, produced by accident, and also operation wounds, belong here. Lacerated wounds are most frequently the consequence of a *rupture* of the sclera. This is produced by the action of a blunt instrument upon the eye (contusion)—e. g., by a blow with the fist or with a cane, by the impact of large flying fragments of wood or metal, by a thrust from a cow's horn (not infrequent among farmers), by striking the eye against a projecting corner, etc. The rupture of the sclera is always curved, and lies near the corneal margin and concentric with it. Most ruptures are observed along the upper margin of the cornea. As a rule, the process does not stop at laceration of the sclera, but the subjacent uvea also ruptures, and a part of the contents of the eye, most generally the lens, is expelled. The vitreous is seen hanging out of the wound; the iris, at a point corresponding to the site of the injury, is usually folded backward upon itself, so that at this point it appears to be wanting, and the eye often looks as if the portion of the iris in question had been removed by iridectomy (see § 74). Frequently the conjunctiva over the lacerated sclera, thanks to its great extensibility, remains uninjured. In this case the extruded lens is sometimes found lying beneath the conjunctiva.

The main thing of importance in determining the subsequent *course* of the injury is whether a foreign body has remained in the eye or not, since cases of the first sort run a much more serious course than those of the second. With the latter, the only thing to be considered is the mere healing of the wound; and the fate of the eye depends essentially upon whether healing takes place with or without inflammation.

(*a*) *Healing without inflammation* is to be expected only in the case of clean, non-infected wounds. The most favorable conditions are presented by clean incised or punctured wounds, such as, for instance, are made by operations, where at the same time care is taken that no foreign

* From ὑπό, beneath, and αἷμα, blood. † From αἷμα, blood, and ὀφθαλμός, eye.

tissue, like uvea or vitreous, is introduced into the wound. But even if this latter should be the case, healing without inflammation is still possible, although the edges of the wound can not unite with each other directly, because they are not in contact. The tissue consisting of uvea or vitreous introduced between them is gradually converted into cicatricial tissue, and thus takes part in the definitive closure of the wound. It then, to be sure, always remains attached to the cicatrix, a thing which later on often entails evil consequences. In this way—i. e., by the interposition of a cicatricial tissue taking place between the edges of the wound without inflammation—even lacerated wounds, such as develop, for example, after rupture of the sclera, may, if the case runs a fortunate course, heal, so that the eye remains serviceable for vision. We often observe that the scleral wounds, which lie near the corneal margin and in which the iris or lens-capsule has become lodged, close imperfectly, owing to the fact that, while the conjunctiva does unite over the scleral wound, the latter remains open to a certain extent because the interposed tissues prevent its lips from coming into direct contact. Through the gap aqueous humor constantly exudes beneath the conjunctiva, which either becomes œdematous in the region of the cicatrix or is bulged out in the form of a circumscribed vesicle resembling a cyst. Following Von Graefe, we designate this condition as *cystoid cicatrization* (see page 115). It is chiefly observed after operations (cataract extraction and iridectomy).



FIG. 41.—INCLUSION OF THE IRIS WITH CYSTOID CICATRIZATION AFTER THE EXTRACTION OF A SENILE CATARACT BY GRAEFE'S PERIPHERAL LINEAR SECTION. ENLARGEMENT 13×1.

The iris, *I*, extends from its origin in the ciliary body, *C*, to the inner aperture of the wound, so that here the anterior chamber is contracted into a narrow slit. The iris within the tract of the wound is folded upon itself, the point of flexion corresponding to the exterior surface of the sclera. The pupillary portion, *P*, of the iris, extends from the site of the constriction into the anterior chamber, where it lies free. On its anterior surface may be seen the entrance of a crypt, near its posterior surface the cross-section of the sphincter pupillæ. Besides the iris, the capsule, *k*, of the lens, is also drawn up to the cicatrix, and has become adherent to it. The section by which the extraction was made cuts in two the line of junction between the sclera, *S*, and the cornea, *H*, so that by its anterior half it lies in the sclera, by its posterior half in the cornea. On account of the interposition of the iris, the lips of the wound have not united: in fact, the tract of the wound extends under the form of a cavity, *h*, even into the tissue of the conjunctiva of the limbus, *L*, so that the wound is closed only by a very thin layer of tissue.

(*b*) The healing of scleral wounds is often accompanied by violent

inflammation of the interior tunics. In most cases this owes its development to infection of the interior of the eye. Infection takes place either by means of the very body which causes the injury, it being covered with dirt and thus conveying infectious germs, or secondarily from the fact that the opening in the envelope of the eyeball forms a point of entrance for germs, especially from the conjunctival sac. The interior of the eye is uncommonly susceptible of infection, since it affords a good medium for the cultivation of different kinds of *Schizomycetes*. The inflammatory process mainly affects the uvea. In the acutest cases there is a purulent inflammation of the latter, which leads to suppuration of the whole eye (panophthalmitis). In the less violent cases there is a plastic irido-cyclitis—i. e., the inflammation of the iris and ciliary body produces an exudate which subsequently becomes organized into a false membrane. In this case, too, the eye is generally lost, although it is not destroyed in such a violent fashion as in panophthalmitis, but by a process of protracted inflammation. The exudates which undergo organization shrink and thus gradually diminish the size of the eyeball (atrophy of the eyeball). This outcome of an injury is even more dangerous for the patient than panophthalmitis, since in the former case sympathetic inflammation of the other eye very frequently sets in, which is not the case in panophthalmitis.

55. Foreign Bodies in the Eye.—The presence of a foreign body in the interior of the eye converts every injury, be it ever so insignificant otherwise, into a serious lesion, which, in most cases, entails the destruction of the eye. Hence in every injury attended with perforation we must at once propound the query whether or not there is a foreign body left in the eye. In most cases the history of the case itself supplies points important for the determination of this fact. If, for instance, a person has run a pair of scissors into his eye, we would naturally suppose that there was no foreign body there; conversely, in the case of a man who has had a perforating injury of the eye produced by the explosion of a percussion-cap, or while he was hammering iron, the presence of a foreign body in the eye is extremely probable. The character of the foreign bodies in question varies exceedingly. Most commonly we have to do with fine splinters, the points and sharp edges of which enable them to penetrate the sclera. In this category belong chiefly splinters of metal, splinters of glass, and fragments of stone—less commonly bits of wood, etc. The foreign body may be situated in any part of the eye; indeed, if it has sufficient projectile force, it may even, after traversing the entire eyeball, perforate the sclera a second time on the opposite side, and penetrate into the tissues of the orbit. The precise determination of the place in which a foreign body is located within the eye is generally attended with great difficulties. As a rule, it is only during the time immediately succeeding the injury that it is possible to see the foreign body directly, although even then

inspection of the interior of the eye is often rendered impossible by the presence of hæmorrhages. Subsequently, the difficulty of this inspection is still further heightened by the cloudiness which soon develops in the media and by the exudates which envelop the foreign body and render it indistinguishable. One is often driven to conjectures with regard to the location of the foreign body—conjectures based upon the direction pursued by the body in its flight, the situation of the aperture by which it entered, the sensitiveness of certain portions of the eye to touch, the presence of a circumscribed obscuration (scotoma) in the field of vision, etc.

The *consequences* entailed by the presence of a foreign body in its interior almost always induce the destruction of the eye. It is only in rare instances that a foreign body is tolerated for any length of time in the eye without setting up inflammation, the body itself either remaining free or becoming encapsulated in an organized exudate. But even such eyes as these are by no means secure from a sudden outbreak of inflammation—occurring sometimes years afterward—which causes their destruction. In the great majority of cases the inflammation follows close upon the heels of the injury. Such an inflammation is either a panophthalmitis or a plastic irido-cyclitis, just as in the case of simple perforating injuries; but when a foreign body remains in the eye it is of much more frequent—indeed, of almost constant—occurrence, and, besides, induces much oftener sympathetic disease of the other eye.

The *prognosis* of perforating wounds of the eyeball is deducible from the exposition given above. In every case it is grave, for even the minutest prick made with a fine needle may induce suppuration of the eyeball, if the needle was contaminated with septic substances. As we do not for the most part know whether the body causing the injury was aseptic or not, and as the consequences of an infection of the wound do not set in until several days have elapsed, we must be very cautious in stating the prognosis during the first few days after the injury. In general, the nature of the wound, and the facts as to the presence of a foreign body in the eye, serve to determine the prognosis. With regard to the former, we must take into consideration the situation and extent of the wound, and the condition of its edges; also whether or not the inner tunics of the eye have prolapsed into the wound, and how much, if any, vitreous has escaped. Large wounds with extensive prolapse of the inner tunics of the eye are always followed by inflammation and by shriveling of the eyeball. The question in regard to foreign bodies is often difficult to decide. If there is a foreign body in the eye and it can not be removed at once, the eye is almost always lost. Again, in stating the prognosis, the danger which threatens the other eye, because of sympathetic inflammation, must not be forgotten.

Treatment.—When we get a recent scleral wound to treat, we must

first try to determine whether a foreign body is probably present in the eye or not.

(*a*) Suppose that there is no foreign body in the eye. Then the next inquiry that we make is whether or not there is any prospect of preserving a serviceable eye. In the first case we put the patient immediately in bed, cleanse the wound from any dirt that may adhere to it, and disinfect it by irrigating with an antiseptic solution. If the iris has prolapsed into the wound, which can be the case only in wounds situated in the cornea or in the most anterior portions of the sclera, it must be carefully excised. But if the ciliary body or chorioid projects into the wound, they should not be removed, because, if they were, the vitreous would prolapse. Small wounds soon close of themselves by cicatrization; large, gaping wounds should be united by sutures passed either through the edges of the sclera itself or through the conjunctiva overlying it.

In those cases in which, on account of the excessive extent of the injury, there is no prospect of retaining the eyeball in a serviceable condition, we recommend to the patient the immediate performance of enucleation. By this means he will be saved from a protracted illness as well as from sympathetic involvement of the other eye.

In many cases it is impossible, even for one who has had great experience, to determine beforehand whether an eye is going to be preserved or not. It is then best to wait for some weeks, proceeding, however, to enucleation as soon as the course takes an unfavorable turn. In the latter case enucleation must not be put off too long, as otherwise we might be caught unawares by an outbreak of sympathetic inflammation in the other eye.

(*b*) If there is a foreign body in the eye, the latter is pretty surely lost unless the foreign body can be removed. Every endeavor must be made to accomplish this. For this object it is indispensably requisite to know, at least approximately, the situation of the foreign body. If the wound is still gaping and is large enough, we can pass a well-disinfected instrument in through it, and endeavor to grasp the foreign body. If the wound is not adapted for this procedure, either because it has already closed up or because it presents unfavorable conditions on account of its size or position, it is better to make a new wound, located in the cornea or the sclera, according to the situation of the foreign body. In placing it in the sclera, the region of the ciliary body must be avoided; the section must lie behind the latter, and is best made in a meridional direction (proceeding from before backward), since such wounds gape the least. Through the wound the instruments are introduced in search of the foreign body; but the operation of grasping and extracting it is often attended with great difficulty, and very frequently miscarries. Fragments of iron give the best prospect for removal, since an electro-magnet, the point of which is intro-

duced through the wound into the interior of the eye, may be employed for their extraction.

If there is no prospect of our being able to remove the foreign body, we may, as a matter of experiment, wait awhile to see if possibly it will be tolerated by the eye without exciting inflammation. This is especially apt to be the case when a foreign body is imbedded in the lens; the latter becomes cloudy, and subsequently, when all the inflammatory symptoms have passed off, can be removed along with the foreign body contained in it by a cataract operation. As soon as plastic iridocyclitis has set in, it is advisable not to make any more attempts at removing the foreign body; absolutely the only indication in this case is enucleation.

Injuries of the eye are very frequently followed by *extravasation of blood* into the interior of the organ—into the anterior chamber and the space occupied by the vitreous. Such extravasations are also observed apart from injury, as the result of inflammation or even without any known cause. In the anterior chamber, blood sinks to the bottom and is reabsorbed. In otherwise healthy eyes small quantities of blood may often disappear completely within twenty-four hours. The process of resorption lasts longer when there is much blood in the anterior chamber, and especially when the eye is diseased in other ways as well and its processes of tissue metamorphosis are not normal. The longer the blood remains in the anterior chamber, the darker does its color become. So, in cases in which a hæmorrhage into the anterior chamber has been repeated after the lapse of some time, we see a hyphæma which is composed of two strata of different color; the lower dark stratum corresponds to the first hæmorrhage, the upper bright one belongs to the recently extravasated blood. Very old extravasations of blood sometimes acquire a brown or dirty-green color. If the blood remains a long time in the anterior chamber, it may—especially if there is a coexistent inflammation—serve as the substratum for the formation of new tissue. In this way the good result of operations, such as iridectomy and iridotomy, designed for the restoration of an unobstructed pupil, is often rendered of no effect, as the blood extravasated during the operation covers up the opening that has been made, and subsequently causes its reocclusion by means of a membrane.

Blood extravasated into the vitreous is found there under the form of flocculi or agglomerations. When observed with the ophthalmoscope, these either look simply black or show a faint reddish gleam. If they occupy the anterior section of the vitreous, they may even be recognized with lateral illumination (provided the pupil is widely enough dilated) through the dark-red reflex emitted from the depths of the eye. Blood occurring in the vitreous always requires a long time for its complete resorption; and, if much blood has been extravasated, opacities of the vitreous of considerable size always remain and cause great impairment of vision. In some cases of traumatic hæmorrhages into the vitreous I have observed that, some time after the injury, the coloring matter of the blood all at once became dissolved in the ocular fluids and then was immediately diffused all through the eye. The aqueous humor, too, in such cases was colored red, so that the iris looked as though seen through ruby glass.

Perforating injuries of the cornea are in general less dangerous than those of the sclera. It appears as if they were less readily infected, perhaps because the outflowing aqueous humor washes away again the germs that have been introduced into the wound. For this reason corneal abscesses are observed mainly in consequence of superficial injuries of the cornea and not after deep perforating wounds. The greater danger of perforating wounds of the sclera may also be based upon the fact that by means of such wounds the ciliary body and the chorioid, which are very prone to become inflamed, are laid bare. Finally, the prolapse of the vitreous is also a factor very favorable to the production of infection, since this may be considered as representing a sort of natural cultivation-gelatin, in which micro-organisms thrive most luxuriantly.

Ruptures of the sclera are such severe injuries, because a force that is strong enough to cause the eyeball to break open will produce other lesions in the interior of the eye, such as laceration of the iris, luxation of the lens, extensive hæmorrhages, etc. The iris may even be torn entirely from its insertion, and along with the lens be projected from the eye. In regard to the method of development of ruptures of the sclera, different hypotheses have been proposed to account for them mechanically. We shall adduce here only the explanation given by Arlt. If a blunt instrument strikes the eyeball, the latter, as its contents are incompressible, will be flattened out. In so doing it will become widened in a direction perpendicular to the axis of the thrusting force. If, for example, the force *a* (Fig. 42) acts in a direction perpendicular to the cornea, and has its point of application in the center, *c*, of the cornea, the eyeball would be shortened from before backward, and hence would acquire a proportionately greater equatorial circumference (corresponding to the axis, $b\,b_1$). The sclera would therefore be stretched most at the equator, and would be likely to rupture there (e. g., at *r*). But in most cases the point of application of the force does not lie in the center of the cornea, but in the sclera below, and to the outer side of the cornea; for, in the first place, the margin of the orbit recedes most at this spot, and the eyeball is hence less protected here than in other directions, where it is covered by the projecting margin of the orbit or by the nose. In the second place, the eye, the moment danger threatens it, always rolls upward, so that the cornea (*c*, Fig. 43) looks upward and conceals itself beneath the upper lid. In this case also, then, a force acting from straight in front strikes the eyeball below the cornea and in the region of the sclera. The direction of the force in these cases corresponds to an axis ($a\,a_1$, Fig. 43) which passes into the eyeball from below upward and from without inward; and in the direction of this axis the eyeball is flattened. The greatest expansion of the sclera, then, takes place in the equator, $b\,b_1$, which corresponds to this axis and which in its upper half skirts the upper margin of the cornea, at which spot, therefore, the rupture of the sclera occurs (at *r*). In this way is explained the fact that ruptures of the sclera almost always run close to the upper margin of the cornea and concentric with it.

Lacerations of the sclera, which are incomplete in the sense that only the inner layers of fibers are ruptured, have also been observed; they result in a protrusion of the sclera at the site of the injury (Arlt, Schäfer). *Rupture of the cornea* is very rare; among others, I have seen the following example: A boy, fifteen years old, during work, brought his hand up in such a way as to give his right eye a violent blow with the knuckle of one finger. I found a rip in the cornea, beginning at its upper and inner margin and thence extend-

ing to about its center, where it made an obtuse bend in a horizontal direction. The rip had a length of six millimetres, and, in consequence of its curved course, marked the limits of a flap, whose edge was raised so as to project



FIG. 42.



FIG. 43.

FIG. 42.—CONTUSION OF THE EYEBALL FROM IN FRONT. SCHEMATIC.

The force acts in the direction $a\,a_1$ upon the center of the cornea, c. By it the eyeball is pressed against the firm background, $U\,U_1$, and acquires the flattened form designated by the dotted outline. The greatest expansion of the eyeball occurs in the direction $b\,b_1$, so that the sclera ruptures at r. The forcing back of the iris by the recession of the aqueous humor is represented as occurring in such a way that at its lower side, u, the iris forms a sac-like protrusion directed backward, while at its upper side, o, it is bent straight back.

FIG. 43.—CONTUSION OF THE EYEBALL FROM BELOW. SCHEMATIC.

The force which acts in the direction $a\,a_1$ strikes the eyeball beneath the cornea and presses it against the background, $U\,U_1$, so that it assumes the flattened form indicated by the dotted line. The eyeball suffers the greatest expansion in the direction $b\,b_1$, so that the sclera ruptures at r.

above the level of the surrounding cornea. The iris was wedged into the wound and the pupil consequently drawn toward this side.

In rupture of the sclera there is found either a considerable recession of the iris as a whole or the iris is bent backward at the spot corresponding to the rupture (Fig. 42, *o*); in rare cases, a piece of iris is torn completely away (traumatic coloboma of the iris). With regard to the bending back of the iris, see § 74. The recession of the iris and the deepening of the anterior chamber attendant upon it may occur in all cases in which vitreous has escaped through the wound in the sclera, and the total volume of vitreous has therefore been diminished. In ruptures of the sclera, the lens, together with a part of the vitreous, is often expelled from the eye, so that such an eye is destitute of a lens—aphakic. In rare cases of this sort, the eye, after the healing of the scleral wound, may regain serviceable sight, if, like eyes that have been operated upon for cataract, it is provided with a strong convex glass. A farmer once presented himself at my clinic who had been gored first in one eye and then, some years afterward, in the other also, by a cow's horn. In both eyes there was a healed-up rupture of the sclera to the inner side, with an apparent regular coloboma of the iris

(in reality, the iris at the site of rupture was bent backward and hence was invisible). Both lenses were absent, but the fundus was healthy and with cataract-glasses the sight was very good. This man, therefore, may be said to have had a double extraction performed by the cow, and that, too, with more success than many operators are accustomed to have with their operations.

The unfavorable prognosis which perforating wounds of the sclera generally offer holds good, at least in part, even for those cases in which, to begin with, there is a smooth healing of the wound. Such eyes which often recover from the injury with the restoration of good sight, nevertheless not rarely become blind afterward because of secondary changes, which are the consequences of the cicatrix in the sclera. Among these consequences is the traction which the part of the uvea that is atached to the cicatrix undergoes, and by which permanent symptoms of irritation, repeated attacks of inflammation, and even sympathetic irido-cyclitis of the other eye, may be set up. In scleral wounds which lie farther back, in the region of the retina, the latter may become attached to the cicatrix. By subsequent contraction of the cicatricial tissue the retina is drawn more and more into the cicatrix, and thus is loosened from its bed; the eye grows blind from detachment of the retina (Von Graefe). In this way, too, many eyes are destroyed which have been operated upon with apparently brilliant success by section of the sclera, as for the extraction of a foreign body or of a cysticercus. A further danger accrues to the eyes from the fact that the scleral cicatrices later on readily become ectatic, and lead to the formation of scleral staphylomata and also to increase of tension.

The prognosis must be stated as almost absolutely unfavorable when a *foreign body* has been left in the eye. A series of cases, to be sure, is known in which a foreign body has been carried about in the eye for years without causing injury. But, in comparison with the excessive frequency of such injuries, the number of these cases is infinitesimally small; and even in these cases the safety of the eye is by no means to be considered as permanently assured. As an example, the following case that I observed may be adduced: A young lady of twenty-five years of age was injured by the percussion-cap of a child's gun exploding near her eye. A piece of the copper case of the cap penetrated into the left eye through the cornea; it could be seen lying upon the lowermost part of the iris. The immediate consequence of the injury was an iritis, which, however, after some weeks got well, leaving several synechiæ. From that time on the eye remained free from inflammation and had good visual power. The piece of metal, which had a length of about one millimetre, could always be seen lying upon the iris, only it gradually assumed a black color. It was not until ten years after the injury that the sight began to diminish, and the patient was tormented by photopsia; she also complained that fixed objects seemed to move and looked bent, so that straight lines, for example, appeared wavy to her. The eye was still free from inflammation, but, after being examined for quite a long time, showed a slight ciliary injection. Examination with the ophthalmoscope could not demonstrate any changes except that the fundus in its lower half was not as beautifully red as it was above, but was of a light grayish color. It was hence taken for granted that here was a detachment of the retina in its very earliest stage. The traction thus produced upon the retina accounted for the photopsia, and the undulatory movement of the retina accounted for the apparent movement of objects, while the curved appearance of straight lines was referable to the differences of level existing in the detached retina. Conjecturally the

retinal detachment was produced by an old exudate which lay upon the ciliary body and the most anterior portion of the retina, and which by its gradual shrinking drew the retina farther and farther forward. Since then I have not had an opportunity of seeing the patient again, but the subsequent course of the case may be predicted with great probability. The retinal detachment will have become total; afterward an irido-cyclitis will have probably developed out of the condition of ciliary irritation of the eye, so that after some time the eye would become completely blind, would grow softer, and would be the site of frequently recurring attacks of pain and inflammation. Perhaps, too, the other eye would be attacked by sympathetic inflammation.

Leber has determined, by a series of experiments upon animals, the reason why the presence of a foreign body in the eye regularly results in a severe inflammation. This inflammation is either excited by the presence of micro-organisms which make their way into the interior of the eye from the conjunctival sac, either along with the foreign body or subsequently, or it is the consequence of a chemical irritation of the tissues produced by those foreign bodies which are not chemically indifferent. For example, purulent inflammation could be produced by bits of copper, and still more by particles of mercury, which were introduced aseptically into the anterior chamber. Hence, such inflammation does not necessarily presuppose the penetration of *Schizomycetes* into the eye. Observations upon man agree in general with the facts obtained by experiment. Whether a body which penetrates into the eye is well borne by it or not depends upon the following circumstances: 1. First of all, upon the fact of its being *aseptic* or not. 2. Upon its *chemical* character. Chemically indifferent bodies (such as, for instance, fragments of glass), if they get into the eye aseptically, are the ones most likely to remain there without producing any further ill effect. The contrary is true of the foreign bodies that are of most frequent occurrence—i. e., fragments of metals. These almost always set up a severe inflammation, which can not, however, in most cases be referred to their septic character. In fact, metallic fragments (for instance, such as fly off while the metal is being hammered) are often raised to a red-heat immediately before they penetrate into the eye, and are thus disinfected. They owe their property of exciting inflammation to the fact that they become oxidized in the tissues of the eye, and thus act as chemical irritants. This is the case with iron, and still more with copper; metals which, like lead and the noble metals, are innocent in this regard, are of comparatively rare occurrence in the eye. 3. The *volume* of the foreign body is of influence, inasmuch as the larger the foreign bodies are, the less readily are they tolerated; for, while small foreign bodies speedily become fixed in the eye, larger ones readily undergo changes of place during movements of the eye, especially if they are of high specific gravity, as in the case with pieces of metal. By such displacements of the foreign body the surrounding tissues are mechanically irritated. 4. The individual tissues vary in respect to their *tolerance* of foreign bodies. The uvea, and especially the iris and ciliary body, exhibit the greatest reaction to injury of any kind. The lens, on the contrary, possibly on account of the sluggishness of its tissue metamorphosis, is the part of the eye in which foreign bodies are relatively the best borne. If, for example, a small fragment of iron has become imbedded in the lens, the latter, to be sure, becomes clouded, but suppuration frequently fails to take place. In such a case sometimes the lens is afterward colored brown by the oxide which is formed, and thus gives evidence of the foreign body con-

cealed in it; in this way small fragments of iron may even in time be entirely dissolved.

Perforating injuries of the eye are very frequent in the working-class, and furnish a large contingent of the blind. This is particularly the case in regions where many industries are carried on. The following report of Cohn gives a good idea of the frequency of the injuries to which the eyes of many workmen are exposed: Among twelve hundred and eighty-three workers in metals employed in six factories, each man received on an average from two to three eye-injuries in a year. Of course, the great majority of these injuries were of a slight character; most, indeed, consisted merely in the penetration of small metallic particles into the surface of the cornea, which were, for the most part, removed at the factory itself. About half of the workmen were compelled to seek medical aid; thirty-six suffered a partial impairment of sight, and sixteen (that is, 1·2 per cent of the whole number) each lost one of their eyes altogether. Is there, then, no protection against these frightfully frequent injuries of the eyes? Certainly, and moreover a very simple one—namely, the wearing of protective spectacles. These are made of glass, or, that they may not be easily broken, of mica or of fine wire net. Unfortunately, the use of these protective spectacles has, up to the present time, always encountered great opposition on the part of the workmen who require them.

The attempt to remove the foreign body which has penetrated into the eye often has great difficulties to cope with, and very frequently is unsuccessful. No fixed rules can be laid down for the procedures to be employed for this purpose, as almost every individual case has its peculiarities and calls for an operation devised specially for itself. For fragments of iron the *electro-magnet* is employed. This was first used for this purpose by McKeown. The form of electro-magnet most employed is the following, devised by Hirschberg: About a rod of soft iron is wound a spiral coil of copper wire, not too thin, the two ends of which are connected with a powerful galvanic element. The ends of the iron rod, which project somewhat beyond the spiral, are a little bent and end in a blunt point, adapted for introduction into the interior of the eye. For this latter purpose we enter either through the wound itself, in case this is large enough and is still open, or we make an incision in a suitable situation in the cornea or sclera, according to the location of the foreign body.

III. Ectasiæ of the Sclera.

(*a*) *Partial Ectasia.*

56. Partial ectasia of the sclera is represented by a circumscribed protrusion under the form of a dark prominence or swelling. The sclera at this spot is thinned, so as to be readily dimpled with the point of a sound; in consequence of the thinning, the chorioidal pigment appears through it, and imparts to the ectasia a dark, slate-gray, or bluish-black color. By means of focal illumination, light can often be made to pass through the sclera at the ectatic spot, and the coating of pigment on its inner surface can be seen through it. According to the situation of the ectasia, various forms of it are distinguished—namely:

1. *Anterior Ectasiæ* (anterior scleral staphylomata).—These occupy the portion of the sclera adjoining the cornea (Figs. 44 and 45). They appear in the beginning under the form of small, dark spots, which afterward become larger and bulge out. When several lie close together they become confluent, forming a large swelling which surrounds the cornea like an arch or ring. The limbus, under the form of a somewhat depressed gray line, forms the boundary between the ectasia and the cornea. When the latter is also opaque and ectatic, the sharp line of demarkation between scleral and corneal ectasis is often lost, and both ectasiæ unite to form a single protuberance occupying the anterior segment of the eyeball. It often happens that an anterior scleral staphyloma exists, or, at all events, has its chief development, on one side only. Then the base of the cornea at this side is pushed forward, so that the entire cornea is made to lie obliquely. If, for instance, the scleral staphyloma occurs on the inner side, the cornea looks outward instead of straight forward (Fig. 45, *b*).

2. *Equatorial Ectasiæ* (equatorial staphylomata).—These are dark prominences in the region of the equator of the eyeball. They can only be seen if the eyeball is turned strongly to the side opposite the staphyloma. They occur at either one or more spots upon the equator, but never surround the entire eyeball like a ring, as is frequently the case with anterior scleral staphylomata.

3. *Posterior Ectasiæ.*—These occupy the posterior segment of the eyeball, and can not, therefore, be seen in the living eye. In respect to origin and significance, they are essentially distinct from anterior and equatorial staphylomata of the sclera. There are two kinds of posterior scleral ectasiæ: α. The *staphyloma posticum Scarpæ.* This consists in a thinning and protrusion of the sclera at the posterior pole of the eye to the outer side of the optic-nerve entrance. If the ectasia takes on greater dimensions, the optic nerve is also involved in it (§ 145). This form of ectasia, as Arlt was the first to discover, is the most frequent cause of short-sightedness, because owing to the recession of the sclera the eyeball undergoes an elongation of its sagittal axis (axial myopia). The diagnosis of a posterior staphyloma can be made in the living eye only by demonstrating the existence of a high degree of myopia and of the accompanying changes in the ophthalmoscopic picture (§ 78). β. *Posterior scleral protuberance of Ammon.* This does not, like posterior staphyloma, lie just at the posterior pole, but below it. Contrary to the case of the other ectasiæ of the sclera, it is not acquired but congenital, being formed in consequence of an incomplete closure of the fœtal ophthalmic cleft. It is found simultaneously with the formation of a fissure (coloboma) in the chorioid and frequently, also, with coloboma of the iris (see §§ 77 and 81).

Acquired ectasiæ of the sclera are designated under the name of staphylomata of the sclera, as has been done in the preceding lines, but

the expression staphyloma is not applied to the congenital scleral protuberance of Ammon.

(*b*) *Total Ectasia of the Sclera.*

This consists in a uniform dilatation of the entire sclera, so that the eyeball is enlarged in toto. The sclera is everywhere thinned and the chorioidal pigment shows through it, so that it has a bluish-white appearance. Total ectasia can only develop in youth when the sclera is still everywhere yielding; the sclera of adults is so rigid that it can protrude only at certain weaker spots, and hence it admits of only partial ectasiæ. Total ectasia occurs most frequently at the same time with staphyloma of the cornea or with anterior scleral staphyloma. Then by the combination of the two kinds of ectasia a very extraordinary enlargement of the eyeball sometimes develops. Much more rarely a second, pure form of scleral ectasia is observed, in which the eye shows simply a uniform enlargement in all its dimensions—an enlargement in which the cornea also participates (megalocornea). This condition is characterized as hydrophthalmus or buphthalmus (βοῦς, ox, on account of the resemblance to the large eyes of oxen). Hydrophthalmus is either congenital or is acquired in early childhood, and is probably analogous to the glaucoma of adults, under which disease, therefore, hydrophthalmus will be treated of in detail (see § 84).

Etiology.—Every ectasia of the sclera is the result of a disproportion between the intra-ocular pressure and the resistance of the sclera. Either the tension of the eye is pathologically heightened or the tenacity of the sclera is diminished. The former is much the more frequent cause of scleral ectasiæ (if the posterior scleral staphyloma in myopia is excepted). Scleral ectasiæ develop slowly, and the disproportion between the tension of the eye and the resistance of the sclera must persist for a pretty long time before it can make the sclera become ectatic.

(*a*) The result of *elevation of the intra-ocular tension* is that every square millimetre of the interior surface of the sclera has to bear the same increase of pressure. If the sclera possessed the same constitution throughout it would, in case it yielded to the pressure at all, expand in a perfectly uniform fashion. But some portions of the sclera are constructed less solidly than others, and these give way first to the increased pressure. These less tenacious spots are those in which the sclera has nerves or vessels passing through it into the interior of the eye, and in which, therefore, it is perforated and thinned. Chief among these places is the lamina cribrosa, and next those portions of the sclera where the venæ vorticosæ and the anterior ciliary vessels perforate it. At the site of the lamina cribrosa the sclera is reduced to a thin membrane, riddled with holes like a sieve, which, under increased pressure, bulges out backward. This bulging, however, is not

counted among the staphylomata of the sclera, but is designated as an excavation of the optic nerve, because the head of the optic nerve recedes simultaneously with the lamina cribrosa (§ 82). Equatorial staphylomata develop at those spots where the venæ vorticosæ perforate the sclera, and anterior scleral staphylomata at the spots where the anterior ciliary vessels are transmitted. The other, more resistant sections of the sclera remain unchanged, even under increased intra-ocular pressure; it is only in children, in whom the sclera is capable of expanding as a whole, that total ectasia develops.

The most frequent causes of the elevation of intra-ocular pressure are glaucoma, seclusio pupillæ, and ectatic cicatrices of the cornea. In glaucoma, in which the venæ vorticosæ are the main seat of congestion and inflammation, equatorial staphylomata generally develop; seclusio pupillæ and staphylomata of the cornea, on the contrary, in which the inflammation expends itself upon the most anterior sections of the eyeball, mostly induce anterior ectasiæ of the sclera.

(*b*) The result of *diminished resistance of the sclera* may be that the latter is unable any longer to withstand even the normal intra-ocular pressure. Diminished resistance develops in consequence of inflammations of the sclera, and hence occurs in the deep form of scleritis, which leads to anterior scleral ectasiæ (page 214); it also occurs when tumors (malignant new growths, gummy or tuberculous nodules) develop in or beneath the sclera. Injuries of the sclera also diminish its tenacity, and hence the cicatrices after penetrating wounds (and especially after ruptures) of the sclera very frequently become ectatic. Scleral ectasiæ arising in this way lead subsequently to elevation of the intra-ocular pressure, which then, however, must be regarded not as the cause, but as the result of the ectasis, even though it does contribute to make the latter still larger. Here, then, the same process that occurs in ectasiæ of the cornea (page 205) is repeated. Posterior scleral ectasiæ are likewise referred to a diminution in the resistance of the sclera. With regard to the development of staphyloma posticum, the cause of it has been assumed to be partly a congenital weakness of the sclera in its posterior portion, partly a softening of it through inflammation of the adjacent chorioid. With respect to Ammon's scleral protuberance, the idea is held that the fœtal ophthalmic cleft is filled up with a sort of intermediary tissue which does not possess the firm texture of the normal sclera, and hence gives way before the ocular pressure.

Consequences of Scleral Ectasiæ.—In anterior and equatorial staphylomata of the sclera the sight is at length completely destroyed through rise of tension. If the ectasia does not come to a stop, the enlargement of the eyeball keeps growing greater and greater. The eyeball projects far beyond the palpebral fissure, can be covered but incompletely by the lids, and is extremely disfiguring. Conjunctival catarrh, lachryma-

tion, and blepharospasm develop as a result of the mechanical irritation. Finally, some light injury suffices to cause the rupture of the staphyloma at a particularly thinned-out spot. The greater part of the liquefied vitreous is evacuated, and in consequence a violent hæmorrhage may take place, and the eye may undergo destruction with the symptoms of panophthalmitis.

Staphyloma posticum, if it enlarges, causes a considerable increase in the short-sightedness, without, however, inducing elevation of tension and the other deleterious consequences of anterior and equatorial staphylomata. The scleral protuberance of Ammon remains stationary and entails no injurious consequences.

Treatment.—It is only anterior and equatorial, and not posterior, ectasiæ of the sclera that are amenable to treatment. In the former, which, in the great majority of cases, have developed in consequence of an increase of tension, the main indication is iridectomy, provided that it is still technically practicable. Inasmuch as this operation diminishes the intra-ocular pressure, it puts a stop to the further enlargement of the scleral ectasiæ (and in especially favorable cases even causes diminution in the size of an ectasia already existing), and likewise preserves the sight, so far as it still exists, from total destruction. If, as indeed is generally the case, iridectomy is on technical grounds no longer practicable, there is nothing else left to do but enucleation, in case the eye distresses the patient by its size, its painfulness, or the disfigurement it causes.

The *anatomical structure* of scleral staphyloma is essentially different from that of staphyloma of the cornea. While the latter consists of cicatricial tissue which replaces the cornea that has been destroyed, a scleral staphyloma is formed of the sclera itself, which has not ceased to exist at the site of the ectasis, but is simply thinned, so that often it is no thicker than a sheet of paper. In posterior staphyloma the thinning is uniform; in anterior and equatorial staphylomata we often find that the thinning is not uniform, and commences suddenly, owing to the abrupt disappearance of the inner layers of the sclera at the margin of the ectasis. The sclera then in the spot where it bulges looks as if it had been gnawed into from the inner side, and thus deprived of its innermost layers. Probably this occurs from the fact that the innermost layers of fibers of the sclera, in consequence of the great stretching to which they are exposed, first rupture at some spot and then gradually separate from each other (Czermak and Birnbacher). The uvea is always solidly adherent to the inner surface of the ectasia, and is here so atrophic that scarcely anything is left of it but its pigment-layer, which forms the dark coating of this inner surface.

Dissection of ectatic eyeballs shows that anterior scleral staphyloma may be of two kinds—*ciliary* or *intercalary staphyloma*. The former (Fig. 44) belongs to that part of the sclera, the inner surface of which is coated by the ciliary body; the latter (Fig. 45), on the other hand, develops in that narrow portion of the sclera which is situated in front of the ciliary body, between it and the margin of the cornea; for the anterior border of the ciliary body, and hence, too, the root of the iris, as it springs from the ciliary body, do not correspond to the

sclero-corneal junction, but lie somewhat behind it—that is, the most anterior portion of the sclera, which lies in front of the root of the iris, belongs to the anterior chamber. But, although it is just in this portion that an intercalary staphyloma develops, the iris does not lie behind the latter but in front of it,

Fig. 44.

Fig. 45.

Fig. 44.—Staphyloma Ciliare. After Pagenstecher.

The eye is bisected horizontally. Surrounding the cornea there is an ectasia, *c*, of the sclera, which attains its greatest breadth at the temporal side, *t*; and on the nasal side, *n*, is narrower and less prominent, for which reason the cornea appears displaced toward the nasal side. The inner surface of the ectasia is coated with the elongated ciliary processes, the iris is invisible because it is pressed against the posterior surface of the cornea, which hence looks pigmented in black. The retina and chorioid have been to some extent separated from their bed by the dissection; in the retina, groups of punctate hæmorrhages, *b*, are observable. The head of the optic nerve, *o*, shows a deep excavation due to pressure.

Fig. 45.—Staphyloma Intercalare.

The eyeball is horizontally bisected and is drawn of somewhat more than the natural size. The ectasia, *s*, of the sclera is interposed on the nasal side, *n*, between the ciliary body, *c*, and the cornea, *h*, so that the latter is displaced toward the temporal side. The inner surface of the ectasia is covered with pigment, which represents the remains of the root of the iris which has become adherent to the thinned sclera; this pigment, in consequence of being spread over so large a surface, shows numerous gaps. Toward the outer side the ectasia constantly diminishes in breadth, so that, at the spot where the temporal wall of the eyeball, *t*, has been cut through, nothing but a very narrow interspace is observable between the ciliary body and the iris, a condition due to that agglutination of the root of the iris to the sclera which characterizes an increase of tension. In the bisected optic nerve, the normal conical contraction of the intra-scleral section, *i*, can be recognized; and, in the retina, can be seen the fovea centralis, *f*, and the expansion of the retinal vessels.

just as in the case of ciliary staphyloma. This comes to pass in the following way. The formation of the ectasia is preceded by increase of tension, which causes the most peripheral portion of the iris to be pressed forward and to become united with the sclera (see § 85 and Figs. 73 and 74). Hence that part of the iris lying free in the anterior chamber is given off from the sclera at a point farther forward than usual. Looked at with the naked eye, it seems as if the insertion of the iris had been pushed forward, up to the sclero-corneal junction or beyond it. Now, an intercalary staphyloma develops in that region of the sclera which is united with the periphery of the iris (from *a* to *b* in Fig. 74), and hence lies between the real origin of the iris at the anterior border of the ciliary body and its apparent origin at the spot where the portion of the iris that is still free commences (Fig. 83, *b*). The inner surface of an intercalary staphyloma, then, is coated with a layer of pigment (*s*, Fig. 45), which is nothing but the completely atrophic root of the iris that has become united to the sclera. In an eyeball which has not been dissected, the distinction between a ciliary and an intercalary staphyloma is more difficult to effect than in an anatomical preparation, but may still be made from the following diagnostic points: In intercalary staphyloma the anterior ciliary vessels are seen emerging from the

sclera at the posterior border of the ectasia, in ciliary staphyloma at its anterior border. A thin ciliary staphyloma usually transmits light, and so admits of our recognizing the elongated ciliary processes as black striæ on its inner surface (*c*, Fig. 44).

Ectasis of the sclera usually entails still further changes in the interior of the eyeball. In consequence of the enlargement of the ring formed by the ciliary body, the iris becomes stretched and atrophic, and may even in places be separated from its insertion (spontaneous iridodialysis). The same is true of the zonule of Zinn, which, through atrophy, gets to be so deficient that the lens becomes tremulous or even undergoes luxation. The ciliary body, chorioid, retina, and optic nerve become atrophic; the latter generally presents a deep excavation due to the increase of tension (*o*, Fig. 44).

Ulcers and Tumors of the Sclera.—The sclera is but little liable to become inflamed, and still less are the products of its inflammation liable to undergo purulent disintegration; thus, for example, ulceration of scleritic nodules is never observed. Ulcers which originate in the adjacent part of the cornea are always arrested as soon as they reach the sclera; nor are ulcers of the conjunctiva any more likely to extend to the sclera beneath them. Hence ulcers in the sclera are among the greatest of rarities. They originate from injuries associated with infection and also from the disintegration of new growths (gummata, tuberculous, and leprous nodules, malignant new growths).

New growths, too, occurring primarily in the sclera are extremely rare; although, of course, tumors originating in other parts of the eye do pass over to the sclera. Fibromata, sarcomata, and osteomata are the primary tumors that have been observed in the sclera.

CHAPTER IV.

ANATOMY AND PHYSIOLOGY OF THE UVEA, EMBRYOLOGY OF THE EYE.

I. Anatomy.

57. If we carefully remove the sclera and cornea from an eyeball, we have presented to us the iris, ciliary body, and chorioid in connection. Together these form the middle tunic of the eye, which takes the shape of a sphere, colored dark-brown by the pigment which it contains. In front this has a large aperture, the pupil; behind it has a small one, the opening designed for the transmission of the optic nerve. On account of the similarity of the dark sphere, hanging upon the optic nerve as upon a stalk, to a grape (*uva*), the middle tunic of the eye has received the name of uvea, and also of uveal tract.

(*a*) *Iris.*

The iris* is a disk-shaped membrane, perforated in the center by the pupil.† By its peripheral or ciliary border it springs from the anterior surface of the ciliary body. From this point it stretches over the lens, its central or papillary border lying upon the anterior capsule, and gliding upon it with the movements of the pupil (Fig. 47). By lying in this way upon the lens, the iris obtains a firm support. Hence, when the lens is absent or has lost contact with the iris, the latter is seen to tremble or vibrate with movements of the eyeball (tremulousness of the iris, *iridodonesis* ‡). Since the umbo of the lens lies farther forward than the spot where the iris originates in the ciliary body, the iris forms a shallow cone, whose apex, directed forward, is cut off by the pupil. The shallower the anterior chamber becomes through advancement of the lens, the greater is the altitude of this cone; if, on the other hand, the lens is absent, the iris extends in a plane.

In looking at the iris with the naked eye, or, still better, with the

---

* Iris on account of its rainbow-shape, not on account of its color.

† Pupilla properly means girl; perhaps so called because in the pupil one sees a diminutive image of himself reflected from the cornea. So, also, in old German works the pupil is named "Kindlein" (= little child). In Greek, too, the pupil is called κόρη, girl, from which the expressions coreclysis, coreplasis, etc., are derived.

‡ From ἶρις and δονέω, I vibrate.

magnifying-glass, we recognize in it delicate markings, which are formed by elevations and depressions of its anterior surface (relief of the iris, Fig. 46). Sharp and clear in the normal eye, these markings are blurred or absolutely indistinguishable in an inflamed or atrophic iris, so that they constitute an important sign in iridic affections. The markings are chiefly formed by radially directed, projecting ridges, which are nothing but the blood-vessels lying in the stroma of the iris, and running from the ciliary to the pupillary margin. Near the latter they interlace with a ring of circular ridges—the lesser circle (circulus minor) of the iris (*k*, Fig. 46). This latter divides the iris into two zones: that lying to the periphery of the circulus minor is the ciliary zone (*C*); that lying to the central side of it is the much narrower pupillary zone (*P*), which is often distinguished from the ciliary zone by a different coloration. Along the circulus minor may be noticed pit-like depressions (crypts, *c*) in the surface of the iris. Similar but much smaller openings in the anterior surface also exist at the periphery of the iris, close to its root; but these are not perceived in the living eye, partly because they are too small, partly because they are concealed by the margin of the sclera, which projects in front of them. It is only in blue eyes, especially in children, that this peripheral perforated zone becomes apparent as a dark, almost black, circle (*p*) close to the root of the iris. The pupillary margin of the iris is seen to be lined by a narrow black fringe (*r*), which stands out with especial prominence in eyes affected with cataract; for it contrasts much more forcibly with the white background of the clouded lens than with the black of the pupil of a normal eye.

FIG. 46.—ANTERIOR SURFACE OF THE IRIS. MAGNIFIED 6×1.

P, pupillary zone; *C*, ciliary zone; *r*, fringe of retinal pigment; *k*, lesser circle; *c*, crypt; *f*, contraction groove; *n*, nævus; *p*, peripheral dark zone.

Microscopical Anatomy.—The *stroma* of the iris consists essentially of numerous vessels running in a radial direction from the ciliary to the pupillary margin. The vessels are inclosed in a thick adventitia, and are surrounded by a loose mesh-work of branched and pigmented cells, which fill up the interspaces between them. The vessels, together with the cellular mesh-work, form the stroma of the iris, which consequently is a very loose, spongy sort of tissue. Close to the pupillary margin of the iris the muscle which closes the pupil—the *sphincter iridis*—is found imbedded in the stroma (Fig. 47, *sp*). This is a flat band of smooth muscular fibers, one millimetre broad, lying close to the posterior surface of the iris.

On the *anterior surface* of the iris the stroma is lined with a coating of endothelium. This, which is a continuation of the endothelium



Fig. 47.

of Descemet's membrane, covers the entire anterior surface of the iris as far as the pupillary margin. It is deficient only at those spots which correspond to the crypts, including both those at the pupillary (Fig. 47, *cr*) and those at the ciliary (*c*, *c*) margin. These crypts, therefore, form apertures which lead into the interior of the tissue of the iris and place its tissue-spaces in free communication with the cavity of the anterior chamber. This arrangement favors the rapid change in volume of the iris in the alternating movements of the pupil, since it enables fluid to pass rapidly from the tissue of the iris into the anterior chamber and vice versa. The *posterior surface* of the stroma of the iris is covered by the posterior limiting membrane and the retinal pigment-layer. The former consists of very even, tense fibers, which extend in a radial direction from the ciliary to the pupillary margin, and hence have been regarded as the dilator pupillæ. Physiologically speaking, the function of a dilator does really belong to the posterior limiting membrane, since the pupil is actively dilated by its contraction. Nevertheless, we are dealing in this case not with a muscular but with an elastic traction, for, inasmuch as the fibers of the posterior limiting membrane possess no nuclei, they can not be regarded as smooth muscular fibers. To the posterior limiting membrane succeeds the retinal pigment-layer, which coats the posterior surface of the iris. It extends to the pupillary margin, round which it turns so as to appear a little on the anterior surface of the iris (Fig. 47, at *p*), and so forms that black fringe which we perceive along the pupillary margin, when looking at the eye from in front. The pigment-layer consists of two strata of epithelial cells (*v* and *h*, Fig. 47), which pass into each other at the pupillary margin. The two together, as embryology teaches us, represent the continuation of the retina to its termination at the pupillary margin. This layer of the iris is therefore designated as the retinal layer (pars retinalis iridis sive pars iridica retinæ), in contradistinction to the anterior layers belonging to the uvea, which are comprised under the name of pars uvealis iridis (Schwalbe).

Explanation of Fig. 47.—Meridional Section through the Anterior Portion of the Eye. Magnified 16×1. The boundary between cornea, *C*, and sclera, *S*, is marked at its posterior surface by the cross-section of Schlemm's canal, *s*. Anteriorly it is covered by the limbus conjunctivæ, *L*; farther back the cross-section of an anterior ciliary vein, *ci*, is seen in the sclera. The iris is attached by the ligamentum pectinatum, *l*, to the inner posterior wall of Schlemm's canal. On the anterior surface of the iris may be recognized the orifices of the crypts both in the circulus minor (*cr*) and in the periphery (*c*), also the contraction-furrow, *f*. The posterior surface of the iris is covered with a sheet of retinal pigment which turns forward sharply like a spur at the pupillary margin, *p*. At one spot the posterior layer, *h*, of the pigment has separated so that the anterior layer, *v*, can be seen isolated. Close to the pupillary margin, the cross-section, *sp*, of the sphincter pupillæ is visible. From the posterior wall of Schlemm's canal rises the ciliary muscle, consisting of longitudinal fibers, *M*, and circular fibers, *Mu*; the transition from one portion to another is effected by the radial fibers, *r*. At the anterior margin of the circular portion is seen the cross-section of the circulus anteriosus iridis major (*a*). Upon the ciliary muscle are situated the ciliary processes, *P*, which are covered by the two layers of the pars ciliaris retinæ, namely, by the pigmented cellular layer, *pe*, which is the continuation of the pigment-epithelium, *Pe*, and by the non-pigmented layer, *pc*, the continuation of the retina proper, *R*. The flat part of the ciliary body, the orbiculus ciliaris, *O*, extends to the ova serrata, *o*, where the chorioid, *Ch*, and the retina, *R*, begin. Upon the orbiculus lie the fibers of the zonule of Zinn, *z*, which farther forward pass into the free portion, z_1, of the zonula and there inclose the cavity of the canal of Petit, *i*. The lens, *D*, shows at its equator, besides the attachments of the zonular fibers, the cross-section, *k*, of the circle of nuclei.

The *color* of the iris, which is either light (blue or gray) or dark (brown), is caused by the iridic pigment. There are two kinds of pigment in the iris: one lies in the branched cells of the stroma, and is hence called the stroma-pigment; the other fills up the epithelial cells of the retinal pigment-layer (retinal pigment). Upon the proportion between the amount of pigment deposited in these two the color of the iris depends. The retinal layer of the iris always abounds in pigment, while the amount of stroma-pigment that the iris contains varies greatly. When the stroma contains little pigment, the retinal pigment shows through the thin iris, and by interference appears blue. This is due to the same phenomenon that always causes a dark background to appear blue when looked at through a more or less opaque medium. Thus, for instance, through a delicate skin the veins look blue. If the stroma is deficient in pigment, but pretty thick and compact, the iris appears gray. And, finally, the greater the amount of brown stroma-pigment that the iris contains, the more this pigment becomes visible and makes the iris appear of its own brown color, while the retinal pigment-layer, which lies behind, is more and more concealed by the stroma-pigment and withdrawn from view.

Not infrequently there exist in an iris, which is but slightly pigmented as a whole, one or two isolated accumulations of pigment in the stroma. These then stand out as dark (rust-colored, brown, or black) spots in an otherwise gray or blue iris (nævi iridis, Fig. 46, *n*). The presence of a pretty large number of them gives the iris the appearance of a tiger-skin.

Exceptionally, cases occur in which the iris has no pigment either in its stroma or in its retinal layer. Such an iris belongs to albinos; it is transparent, and, on account of its numerous vessels, has a delicate, grayish-red color.

The examination of the iris in the living eye shows us, besides the details of relief mentioned above, a number of concentric curved lines near the ciliary margin of the iris (*f*, Fig. 46). They are particularly well seen in a dark iris with a contracted pupil, when by their light color they show off well upon the brown background. These are the *contraction furrows* of the iris; so called because, as the iris becomes narrower during the dilatation of the pupil, its anterior surface is disposed in folds, and depressions between the folds (*f*, *f*, Fig. 47) form these furrows, at the bottom of which the stroma of the iris generally contains less pigment. When the pupil contracts these folds are smoothed down, and the furrows open out and are then easier to be seen. With the varying dilatation and contraction of the pupil we also notice a change in the fringe of pigment upon the pupillary margin: the more contracted the pupil is, the broader this becomes; on the other hand, when the pupil is strongly dilated, it disappears entirely. When the pupil is very much contracted, we not infrequently observe even in normal eyes a faint tremulousness of the iris (iridodonesis), which otherwise occurs only in dislocation of the lens. This is due to the fact that with a contracted pupil the posterior chamber is deeper and at the same

time the greatly dilated iris is considerably thinned—circumstances both of which favor wavering of the iris.

The *retinal pigment-layer* is composed of two strata of cells, the recognition of which, however, is rendered very difficult by their profuse pigmentation. The two strata can be clearly distinguished from each other only in the embryo (and sometimes also in the new-born infant); we can then also establish the fact that they are the continuation of the two layers of the retina upon the posterior surface of the iris. The anterior stratum of pigment (*e*, Fig. 47) arises from the pigment-epithelium of the retina; the posterior (*h*) from the retina proper. In the adult eye a separation not infrequently takes place between the two strata, because they are not attached with the same degree of firmness to the iris. While the anterior stratum is very intimately adherent to the posterior surface of the iris, the posterior stratum readily becomes separated from it (in Fig. 47 the separation has resulted accidentally from the dissection). When adhesions of the posterior surface of the iris to the capsule of the lens (posterior synechiæ) are torn away, the posterior stratum is left as a black coating upon the anterior capsule, while the anterior stratum remains upon the iris. So, too, we can easily remove the posterior stratum from the iris by penciling, while leaving the anterior stratum behind upon the iris. Then, in making a microscopical examination of the iris that we have penciled, we find the anterior stratum intimately connected with the posterior limiting membrane. Indeed, it used to be counted as forming a part of the latter, investigators regarding the nuclei of the pigment-cells as the nuclei of the fibers of the posterior limiting membrane —structures which they were hence disposed to look upon as smooth muscular fibers. In this way they arrived at the erroneous assumption of there being a muscular dilator pupillæ. And, indeed, there are still other facts which appear to support this assumption. In the first place, there is the presence in many animals of such a dilator consisting of striated muscular fibers. Then, there are all those facts which speak for the existence of an active dilatation of the pupil—e. g., the fact that, by instilling atropine into an eye, the pupil of which is already dilated in consequence of paralysis of the oculo-motorius, we obtain still further retraction of the iris. Again, if in consequence of iritis the pupillary margin is fixed to the anterior capsule of the lens by two adjacent points, the portion lying between the two synechiæ retracts so strongly under atropine that the pupil in this spot looks as if cut out in the form of a horseshoe. The fact, too, that posterior synechiæ can be torn away by means of atropine is another one belonging in this connection. Without doubt, therefore, the existence of an active dilatation of the pupil must be conceded; but this, in accordance with anatomical facts, must be looked upon not as a muscular but as an elastic traction.

As is universally known, the color of the iris changes in the first years of life. Most children are born with a deep-blue iris. The stroma contains but little pigment and is still very thin, so that the posterior pigment-layer is seen through it, having a bluish look. With increasing age the stroma becomes thicker and thicker. If, while this is taking place, the pigmentation does not increase, the iris simply becomes of a light blue or gray; but if, simultaneously, there is an increase of the pigment of the stroma, the iris takes on a brown color. The transformation of a blue iris into a brown one is sometimes confined to a part of the membrane, so that a brown sector is seen in an otherwise light-colored iris. Moreover, the iris of one eye may be blue and that of the other



FIG. 48.—HORIZONTAL SECTION OF THE ORBIT. SCHEMATIC. MAGNIFIED 2×1.

brown. The color of the iris is always proportioned to the pigmentation of the rest of the body. The dark races always have a dark iris.

(*b*) *Ciliary Body.*

58. The ciliary * body is brought into view when the eyeball is bisected, and the vitreous, the lens, and the retina are removed, so that the uvea is everywhere exposed. The spot where the retina is torn away anteriorly is marked by a jagged line—the ora serrata (*o*, *o*, Fig. 48). Corresponding to this there is a change in the coloration of the uvea, which behind this line is brown (chorioid), in front of it black (ciliary body; cf. Fig. 45, *c*). At the anterior margin of the black zone rise the ciliary processes, about seventy in number. These are conspicuous not only on account of their projecting forward, but also because of their lighter color. This latter is an artificial effect; the ciliary processes are covered, like the rest of the ciliary body, with black pigment, which, however, in the process of removing the vitreous, is separated from the apices of the ciliary processes and leaves them of a light-gray color. The anterior zone of the ciliary body, bearing the ciliary processes, is called the folded part of the ciliary body—corona ciliaris (c_1, Fig. 48); back of this is the posterior part of the ciliary body—orbiculus ciliaris (*or*)—which is smooth and of a uniform black color.

If we strip off the entire uvea from the cornea and sclera, we get a view of the outer side of the ciliary body. This is covered by a layer of gray tissue—the ciliary muscle.

Longitudinal sections (carried in a meridional direction, Fig. 47) are the ones best adapted for accurate study of the ciliary body. In such sections the ciliary body appears triangular. Its shortest side looks forward, and at about its center gives origin to the iris. The two long sides of the triangle look inward and outward. The inner side bears the ciliary processes (*P*, Fig. 47), while the outer side is formed by the ciliary muscle (*M*).

Explanation of Fig. 48.—The nasal wall of the orbit is formed by the lamina papyracea (os planum) of the ethmoid, *L*, the lachrymal bone, *T*, and the frontal process, *F*, of the superior maxilla. The last two bones bound the fossa sacci lacrimalis, in which lies the lachrymal sac, *S*. The bony walls of the orbit are coated by a periorbita (periosteum), *P*, from which the palpebral ligaments take their origin. The internal palpebral ligament, *l*, divides into an anterior limb, *v*, and a posterior limb, *h*, which together inclose the lachrymal sac. From the posterior limb arise the fibers of Horner's muscle, *H*. *le*, external palpebral ligament; *fi* and *fe*, the slips of fascia, likewise originating from the periosteum, going to the internal rectus muscle, *I*, and the external rectus, *E*. The skin, *N*, of the dorsum of the nose passes into the lower lid, at whose free border are seen the cilia and the orifices of the Meibomian glands, *m*; between the two extends a gray line, *i*. At the inner extremity of the lid lies the inferior punctum lacrimale, *p*, and farther along in the conjunctival sac the caruncle, *c*, and the plica semilunaris, *n*. From the eyeball, the lower half of which is exhibited, the lens and along with it the vitreous humor have been taken out, and the pigment-epithelium has been removed by penciling. The anterior chamber, *k*, the iris, *ir*, and the ciliary body, consisting of the corona ciliaris, c_1, and the orbiculus ciliaris, *or*, are visible. Back of the ora serrata, *o*, is the chorioid with its veins which are aggregated into vortices, *v*. *f*, fovea centralis retinæ; c_{11}, central vessels of the optic nerve, *O*, entering it at *e*.

---

* From *cilia*, lashes, because of the fine, radiating folds. The ciliary body is also called *cyclon* (hence cyclitis), from κύκλος, a circle.

Microscopical Anatomy.—If we examine the separate layers of the ciliary body, proceeding from without inward, we first come upon the *ciliary muscle.* This was discovered by Brücke, and was denoted by the name of tensor chorioideæ. It consists of two portions, distinguished by the differing direction of their muscular fibers. (*a*) The external portion contains the longitudinal or meridional fibers—that is, those running from before backward (*M*, Fig. 47). As these are the ones first discovered by Brücke, they are also called Brücke's portion. The longitudinal fibers arise from the external fibrous tunic of the eye, at the boundary between the cornea and sclera (at *l*), and run straight backward to a point at which they gradually are lost in the external layers of the chorioid (*Ch*). (*b*) The second portion of the ciliary muscle lies to the inner side of the first, and contains those fibers which have a circular course, and which, hence, in sections made meridionally, are seen in cross-section (*Mu*, Fig. 47). They are designated as Müller's portion, from their discoverer, Heinrich Müller. The two varieties of fibers merge into one another repeatedly.

The *ciliary processes* (*P*, Fig. 47) are placed upon the ciliary muscle. They consist of a connective-tissue stroma, which, along with branched pigment-cells, contains an extraordinary number of blood-vessels, so that the ciliary processes must be regarded as the most vascular portion of the entire eyeball. The inner surface of the ciliary body is covered by three layers. The first of these is a homogeneous membrane, the hyaline lamella of the ciliary body. Succeeding this is a layer of pigmented cells, the pigment-epithelium (*pe*); and, lastly, a single stratum of non-pigmented, cylindrical cells (*pc*) forming the most superficial layer—i. e., the one that adjoins the vitreous humor. The last two layers are the continuation of the retina, which here has become reduced to a double row of cells—i. e., a pigmented and a non-pigmented row, and they are hence called the *pars ciliaris retinæ.* All three layers pass over upon the posterior surface of the iris, the deepest layer, or hyaline membrane, being continued into the posterior limiting membrane of the iris, while the layers of pigmented and non-pigmented cells are converted into the two strata of the retinal pigment-layer of the iris (pars iridica retinæ, *v* and *h*).

The place where the *iris and the ciliary body are attached to the sclera* deserves particular attention. We can readily convince ourselves that the iris does not arise from the sclero-corneal junction, but farther back, so that the most anterior portion of the sclera is still in the confines of the anterior chamber. The connection between the sclera and the root of the iris is made by means of loose tissue which arises at the margin of the cornea, and from this point extends backward to the root of the iris (Fig. 47, *l*). This tissue, which is called the *ligamentum pectinatum*, fills up the angle between the iris and the corneo-sclera, so that this angle is rounded off into a sinus—the sinus of the anterior

chamber. Histologically, the tissue of the ligamentum pectinatum is composed of superimposed lamellæ, which start from the margin of Descemet's membrane and run backward to a point at which a part of the longitudinal fibers of the ciliary muscle abuts against them. These lamellæ, thin and perforated like a sieve, form, when superimposed, a spongy tissue. Directly to the outer side of them, just at the boundary between the cornea and sclera, is observed an open space (Fig. 47, *s*), corresponding to Schlemm's canal, the inner wall of which is thus formed by the ligamentum pectinatum.

The iris and ciliary body take part in the formation of the two chambers of the eye. The *anterior chamber* is bounded in front by the cornea, behind by the iris and in the region of the pupil by the anterior capsule of the lens, and at its margins by the tissue of the ligamentum pectinatum, beneath which lie Schlemm's canal and the anterior border of the ciliary body. Even under normal conditions the depth of the anterior chamber is variable. It is greatest in the eyes of the young, and diminishes with advancing age. Myopic eyes have a deep anterior chamber, hyperopic eyes a shallow one. Even in the same eye the depth of the anterior chamber varies, as it becomes shallower during the accommodative act from the protrusion of the anterior surface of the lens. The *posterior chamber* is produced by the iris not being in contact with the capsule of the lens by its whole posterior surface, but only by its pupillary margin. Thus an open space is left between the iris and the lens, which increases in depth from the pupillary to the ciliary margin of the iris, and hence in cross-section has a triangular shape. This space, the posterior chamber of the eye, is bounded in front by the iris and to the outer side by the ciliary body, while its inner and posterior wall is formed by the lens (*D*, Fig. 47) and the zonule of Zinn (z_1, Fig. 47), the latter bridging over the interspace between the lens and the ciliary body. The two chambers communicate only by means of the pupil.

The *ciliary muscle* is composed of smooth muscular fibers, which do not present a compact mass but are disposed in flat bundles, which are separated by connective tissue, and which anastomose repeatedly with each other so as to form a sort of plexus. For this reason there is no well-marked separation between the two portions of the ciliary muscle; on the contrary, the longitudinal fibers by a very gradual transformation become bent so as to take a circular direction. Those bundles which effect the transition from fibers of one direction to those of another have been denoted by the name of radial bundles (*r*, Fig. 47). Like the longitudinal fibers they arise from the wall of Schlemm's canal, but, unlike them, they do not extend outward and backward, but directly backward, and pass into the circular fibers.

The proportion between longitudinal and circular fibers varies according to the refractive state of the eye. In hypermetropic eyes the circular fibers are strongly developed, while in myopic eyes they are present in much smaller numbers (see § 145, and Figs. 151, 152, and 153).

The region of the *angle* (or *sinus*) *of the anterior chamber* demands particular consideration, both because of its complicated anatomical relations and also because of its importance with regard to the metabolic processes and the diseases of the eye. This region was studied in the eyes of animals before fore it was in human eyes, and hence names were selected at that time which are still in vogue, although they are not appropriate for the human eye. Thus Hueck introduced the name ligamentum pectinatum, because he found in the eyes of the Ungulata that, upon stripping the iris from the sclera, the tissue that united these parts projects in a series of ridges resembling the teeth of a comb. The triangular space between the sclera and the root of the iris which is filled by the ligamentum pectinatum is also called Fontana's space, because Fontana was the first to describe the rather large cavities which are found in many animals between the lamellæ of the ligamentum pectinatum.

The ligamentum pectinatum is covered by the endothelial layer which passes over it from the posterior surface of Descemet's membrane to the anterior surface of the iris. Through the gaps in the lamellæ of the ligamentum pectinatum the endothelium passes from the surface of the ligament into the deeper parts of it, and supplies all the lamellæ and trabeculæ of this spongy tissue with an endothelial lining.

When the iris and the ciliary body are stripped off from the corneo-sclera, the ligamentum pectinatum comes away with them. It thus shows the close interrelation between it and the uvea, a relation, moreover, that is also proved by embryology, according to which both the ligamentum pectinatum and its derivative, Descemet's membrane, belong to the uvea. Hence, embryologically speaking, the uvea forms a perfectly closed hollow sphere, consisting of the chorioid, ciliary body, iris, ligamentum pectinatum, and Descemet's membrane.

By stripping off the uvea, together with the ligamentum pectinatum, from the corneo-sclera, an opening is made into Schlemm's canal, the inner wall of which is formed by the ligamentum pectinatum. It is then visible as an open channel running along the boundary between the cornea and sclera—scleral channel. Besides this, the ligamentum pectinatum covers in a part of the anterior surface of the ciliary body, which therefore, within these limits, likewise belongs to the region of the anterior chamber. Hence inflammatory products, and especially pus (under the form of hypopyon), may pass from the ciliary body directly into the anterior chamber, traversing the tissue of the ligamentum pectinatum as they do so. New growths also sometimes take this path, starting from the ciliary body and growing forward into the anterior chamber in the region of its sinus.

It was a good while before people got a correct idea of the anatomical relations existing in the region of the anterior and posterior chamber, and even at the present time we very frequently find drawings which represent these relations incorrectly. The existence of the posterior chamber was for a long time contested, it being supposed that the iris came into contact with the lens by its whole posterior surface. If this were the case, the anterior chamber would present quite a different shape, since it would have to be much deeper at its periphery than it is. This state of things is actually observed in those pathological cases in which the iris is adherent throughout by means of an exudate to the capsule of the lens. The iris is then found to be retracted at its periphery much more than usual (see Fig 60). The existence of a posterior chamber in the normal eye can be demonstrated by freezing a recently extracted eye:

upon opening it, we see a ring-shaped piece of ice (the frozen liquid of the posterior chamber) lying between iris and lens.

(*c*) *Chorioid.*

59. The chorioid * is that part of the uvea which lines the posterior section of the eye from the ora serrata to the aperture for the optic nerve. If we observe it in situ, after opening the eyeball and removing the vitreous together with the retina, its inner surface appears smooth and uniformly brown. Then, if we try to strip it off from the sclera, we notice that at several spots it is attached more firmly than at others. The most intimate connection is at the margin of the aperture for the optic nerve; in addition, loose attachments exist in the places where vessels and nerves enter the chorioid from the sclera, and especially in the region of the posterior pole (region of the posterior ciliary arteries) and of the equator (venæ vorticosæ). When, after tearing away these connections, we have separated the chorioid from the sclera, we get a view of the outer surface of the chorioid, which has a shaggy appearance on account of the shreds of membrane adhering to it.

Microscopical Anatomy.—The chorioid consists of five layers, which succeed one another in the following order, proceeding from without inward:

1. The *suprachorioid* (*s*, Fig. 49) consists of numerous fine non-vascular but richly pigmented lamellæ lying between the chorioid proper and the sclera (*sc*). Upon stripping these latter apart these lamellæ are torn in two, and are left hanging partly upon the inner surface of the sclera, partly upon the outer surface of the chorioid, which thus acquires the rough, shaggy aspect above mentioned.

2. The *layer of large vessels* (Haller) (*H*, Fig. 49). These are chiefly veins, which are placed very close to each other and anastomose repeatedly. The intervals between the vessels (intervascular spaces) are richly supplied with pigment-cells (*p*), and are hence of a brown color. This layer, accordingly, gives the same appearance upon a surface-view as if we were looking at a plexus of bright lines (the vessels) upon a dark ground (Fig. 48). This is a picture which we often have the opportunity of seeing with the ophthalmoscope in the living eye (tesselated fundus, see page 16 and Fig. 68).

3. The *layer of medium-sized vessels* (Sattler) (Fig. 49, *S*), which is very thin and but slightly pigmented.

4. The *layer of capillaries* (*chorio-capillaris*, or membrana Ruyschii —although it was not discovered by Ruysch—*R*, Fig. 49). This consists

* From χοριοειδής—i. e., like the χόριον (= Lat., *corium*). This latter word signifies "skin," and not merely the epidermis, but also the envelope (chorion) of the embryo in utero; and, in fact, it is the latter that the chorioid resembles, from its abundant supply of vessels. This word is also erroneously written choroid or choroïd.

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

almost exclusively of capillaries which have a very wide bore, and at the same time are so closely packed together that the interspaces between the capillaries are often narrower than the capillaries themselves. This layer contains no pigment.

5. The *lamina vitrea* (*G*, Fig. 49), a homogeneous membrane coating the inner surface of the chorioid.

We may briefly summarize the structure of the chorioid in the following way: The chorioid consists mainly of vessels which are ar-



FIG. 49.—CROSS-SECTION THROUGH THE CHORIOID. MAGNIFIED 175 × 1.

The chorioid consists of the suprachorioid, *s*, the layer of large vessels, *H*, the layer of medium-sized vessels, *S*, the chorio-capillaris, *R*, and the lamina vitrea, *G*. In the layer of large vessels are recognizable arteries, *A*, veins, *V*, and pigment-cells, *p*. The inner surface of the chorioid is covered by the pigment-epithelium, *P*, its outer surface by the sclera, *sc*.

ranged according to their caliber in three superimposed layers, in such a way that the largest vessels lie farthest to the outside, the smallest vessels farthest to the inside. The purpose of this arrangement is easily comprehended, since the chorioid is in great part designed for the nourishment of the tissues lying to the inner side of it (retina and vitreous). Hence the minutest vessels, the capillaries, from which the nutrient plasma of the blood exudes, must lie upon the inner surface of the chorioid. The vascular part of the chorioid is covered on either side by a non-vascular layer—i. e., to the outside by the suprachorioid, to the inside by the lamina vitrea. All the layers of the chorioid, with the exception of the two innermost ones—the capillary layer and the lamina vitrea—contain pigment inclosed in branched pigment-cells (Fig. 50). To its abundant supply of pigment the chorioid owes its dark-brown color. The inner surface of the chorioid is covered by the pigment-epithelium (*P*, Fig. 49) which lies upon the lamina vitrea. This, too, was formerly reckoned in with the chorioid, because it remains attached to it after the retina has been stripped off; embryologi-

cal researches, however, have shown that it really belongs to the retina. It consists of regularly hexagonal cells, each of which has an unpigmented nucleus, while the protoplasm contains an abundance of pigment-granules (Fig. 51). From this the entire layer acquires a dark-brown color.

FIG. 50.—PIGMENT-CELLS OF THE STROMA OF THE CHORIOID. MAGNIFIED 400 × 1.

They are branched, anastomosing, connective-tissue cells, with numerous pigment-granules and an unpigmented nucleus.

The uvea in all of its parts is very rich in *nerves*. The ciliary nerves get to the uvea by piercing the sclera near its posterior pole. They form in the chorioid, and particularly in the ciliary muscle, a dense plexus, in which numerous ganglion-cells are intercalated. The iris is also very rich in nerves, but contains no ganglion-cells. The iris and the ciliary body contain, in addition to the motor nerves designed for the ciliary muscle and the muscular apparatus of the iris, a very great number of sensory nerve-fibers which arise from the trigeminus; hence inflammation of these parts is frequently attended with great pain. The chorioid, on the contrary, seems to possess no sensory nerves, since inflammation of this membrane runs its course without producing any sensations of pain.

The chorioid is continuous with the flat part of the ciliary body (orbiculus ciliaris), which possesses essentially the same structure as the chorioid, and is distinguished from it only by a somewhat different arrangement of the blood-vessels, and also by the absence of the chorio-capillaris, which ends at the ora serrata. The difference in color between the brown chorioid and the black orbiculus (Fig. 48), so striking to the naked eye, is not referable to a difference in the pigmentation of this part of the uvea, but to a difference in the pigment-epithelium which covers it and which belongs to the retina.

FIG. 51.—PIGMENTED EPITHELIAL CELLS OF THE RETINA. MAGNIFIED 500 × 1.

They are hexagonal epithelial cells, with pigment-granules and an unpigmented nucleus.

All the pigment contained in such quantities in the interior of the eye belongs to two categories: 1. In the tissue of the uvea itself there are everywhere found branched cells, of the character of the connective-tissue cells, containing pigment (Fig. 50). There are the pigment-cells of the stroma, and the pigment contained in them is called *stroma pigment*, or, because it lies in the uvea itself, uveal pigment. 2. The inner surface of the uvea is everywhere coated with a layer of pigmented cells, belonging to the retina and having the character of epithelial cells (*pigment-epithelium*, Fig. 51). This pigment, which hence lies not in the uvea but to the inner side of it, is called the retinal pigment.

These two kinds of pigment are further distinguished by their minute

structure. The pigment in the stroma-cells of the uvea consists of small amorphous masses; but the pigment granules in the cells of the pigment epithelium are short, rod-shaped structures, which should probably be regarded as small crystals, such as occur, very distinctly marked, in some of the lower vertebrates.

The pigmentiferous cells, including both those of the stroma and those of the pigment epithelium, are similar in all eyes, but the amount of pigment which they contain varies greatly. To this fact is due the inequality in the pigmentation of eyes; if the cells contain no pigment whatever, the eye is albinotic.

II. Circulation and Metabolism of the Uvea.

(*a*) *Blood-Vessels.*

60. Three systems of blood-vessels exist in the eye—that of the conjunctiva, that of the retina, and that of the uvea (ciliary system of vessels). The *arteries* of the ciliary system are: 1. The posterior ciliary arteries. These arise from the ophthalmic artery, and enter the interior of the eye through the sclera in the region of the posterior pole. The majority of them pass at once into the chorioid (short posterior ciliary arteries, *c*, *c*, Fig. 52). Two of them, however (the long posterior ciliary arteries, *d*, Fig. 52), run, one on the outer side, the other on the inner side, between chorioid and sclera as far forward as the ciliary muscle Here each divides into two branches, which run in a direction concentric with the margin of the cornea, and unite with the branches of the artery of the opposite side to form an arterial circle, the circulus arteriosus iridis major (Fig. 52, *h*, and Fig. 47, *a*). This gives off the arteries for the iris, which extend radially from its ciliary to the pupillary margin (Fig. 52, *i*). Shortly before they reach the latter they form by anastomoses a second, smaller vascular circle, the circulus arteriosus iridis minor or the small circle of the iris (Fig. 52, *k*). 2. The anterior ciliary arteries come from in front, arising from the arteries of the four recti muscles (Fig. 52, *e*). They perforate the sclera near the margin of the cornea and assist in forming the circulus arteriosus iridis major. The short posterior ciliary arteries are therefore designed mainly for the chorioid, the long posterior ciliary arteries and the anterior ciliary arteries for the ciliary body and the iris.

The arrangement of the veins is essentially different from that of the arteries. In the chorioid the capillary network of the chorio-capillaries (Fig. 52, *f*) is fed by the arteries. The blood from this flows off through a very great number of veins that keep uniting to form larger and larger trunks, disposed in groups each comprising a number of veins which tend toward a common center. At this center a sort of vortex is produced by the veins coming together from all sides (Fig. 48 shows a surface-view of two such vortices, *v*). These vortices, the number of which amounts to four at least, usually more, lie somewhat behind the equator of the eye; from them are given off the venæ vor-

ticosæ, which, perforating the sclera in a very oblique direction, carry off the blood to the outside (Fig. 52, *l*).



FIG. 52.—BLOOD-VESSELS OF THE EYE (SCHEMATIC, AFTER LEBER).

The *retinal system of vessels* is derived from the central artery, a, and the central vein, a_1, of the optic nerve, which give off the retinal arteries, b, and the retinal veins, b_1. These end at the ora serrata, *Or*.

The *system of ciliary vessels* is fed by the posterior short ciliary arteries, c, c, the posterior long ciliary arteries, d, and the anterior ciliary arteries, e. From these arise the vascular network of the chorioidal capillaries, f, and of the ciliary body, g, and the circulus arteriosus iridis major, h. From this last spring the arteries of the iris, i, which at the smaller [inner] circumference of the latter form the circulus arteriosus iridis minor, k. The veins of the iris, i_1, of the ciliary body, and of the chorioid are collected into the vasa vorticosa, l; those veins, however, that come from the ciliary muscle (m) leave the eye as anterior ciliary veins, e_1. With the latter, Schlemm's canal, n, forms anastomoses.

The *system of conjunctival vessels* consists of the posterior conjunctival vessels, o and o_1. These communicate with those branches of the anterior ciliary vessels which run to meet them—that is, with the anterior conjunctival vessels, p—and form with these the marginal loops of the cornea, q. *O*, optic nerve; *S*, its sheath; *Sc*, sclera; *A*, chorioid; *N*, retina; *L*, lens; *H*, cornea; *R*, internal rectus; *B*, conjunctiva.

In the ciliary processes the arteries break up into a great number of twigs, which pass over into thin-walled veins (*g*, Fig. 52). These constitute the greater part of the ciliary processes, which, accordingly, consist mainly of vessels. The larger veins which are formed by the union of these vessels, and also most of the veins of the ciliary muscle pass backward to the venæ vorticosæ. The veins that come from the iris (i_1, Fig. 52) likewise pass to the venæ vorticosæ. Hence almost all the venous blood of the uvea empties into the latter. A portion of the veins coming from the ciliary muscle (*m*, Fig. 52), however, take another course, as they pass out directly through the sclera and thus come into view beneath the conjunctiva, near the margin of the cornea (anterior ciliary veins, Fig. 52, e_1). In their course these correspond to the anterior ciliary arteries; it is they that principally constitute the violet vessels which we see running backward beneath the conjunctiva in ciliary injection or in congestion within the eyeball (glaucoma). The anterior ciliary veins anastomose with the conjunctival veins, and also with Schlemm's canal. The latter is a venous sinus running along the sclero-corneal junction (Fig. 52, *n*; Fig. 47, *s*).

(*b*) *Lymph-Passages.*

61. If we disregard the conjunctiva, there are no lymphatic vessels in the eye. They are replaced by lymph-channels and lymph-spaces. We distinguish the lymph-passages into anterior and posterior.

1. *Anterior Lymph-Passages.*—The lymph of the anterior section of the eye is collected into two large lymph-spaces—namely, the anterior and the posterior chambers—which communicate by means of the pupil. The outflow of lymph from these spaces takes place by its discharge from the posterior chamber through the pupil into the anterior chamber; thence it filters through the mesh-work of the ligamentum pectinatum into the subjacent Schlemm's canal (Fig. 53, *S*), and from there gets into the anterior ciliary veins (*c*) with which Schlemm's canal is in direct communication.

2. *Posterior Lymph-Passages.*—These are as follows: (A) The hyaloid canal, or central canal of the vitreous (Fig. 53, *h*), which extends from the point of entrance of the optic nerve forward as far as the posterior pole of the lens. During the development of the eye this canal lodges the hyaloid artery, which in the fully formed eye disappears, while the canal remains. It has its outlet in the lymph-spaces of the optic nerve. (B) The perichorioidal space (*p*, Fig. 53) is the space between the chorioid and sclera. It is continued along the vessels which pass through the sclera, especially the venæ vorticosæ (*v*), and thus communicates with (C) Tenon's space (Fig. 53, *t*, *t*), which lies between the sclera and Tenon's capsule. The outflow of lymph from all these spaces takes place into the lymph-passages, which spread out along the optic nerve. These latter are (D) the intervaginal space, which is

found beneath the sheaths of the optic nerve (*i*, Fig. 53), and (E) the supravaginal space, which surrounds the sheaths of the optic nerve.

By far the greatest amount of lymph leaves the eye through the anterior lymph-passages. These, therefore, are the more important; their impermeability leads to serious changes in the eye (glaucoma), while up to the present time nothing certain is known in regard to disturbances of the function of the posterior lymph-passages.



FIG. 53.—LYMPH-PASSAGES OF THE EYE. SCHEMATIC.

S, Schlemm's canal; *c*, anterior ciliary veins; *h*, hyaloid canal; *p*, perichorioidal space, which communicates by means of the venæ vorticosæ, *v*, with Tenon's space, *t*, *t*; *s*, supravaginal space; *i*, intervaginal space; *e e*$_1$, continuation of Tenon's capsule upon the tendons of the ocular muscles (lateral invagination).

The blood-vessels and lymph-passages of the eye, the abundance of which corresponds to the active metabolism going on in the eyeball, belong for the most part to the region of the uvea. It is this fact which determines the part played by the latter; for, while the firm corneo-sclera serves for the protection of the eye exteriorly and the retina for the perception of light, to the uvea is allotted the task of providing for the nourishment of the eyeball. Such is the abundance of blood-vessels which it contains that it really consists mainly of them; and by this fact its great tendency to become inflamed is accounted for.

The separate branches of the ciliary system of vessels anastomose repeatedly with each other—a circumstance which favors the compensation of circulatory disturbance. Thus, for instance, in glaucoma, in which the outflow of venous

blood through the venæ vorticosæ is impeded, we see the anterior ciliary veins taking their place and carrying off larger quantities of blood than usual.

The ciliary vessels likewise supply the sclera with blood, giving off a few minute twigs to it as they pass through it. The number of blood-vessels in the sclera, however, is very small. Nevertheless, in the immediate neighborhood of the entrance of the optic nerve, from two to four branches of the short posterior ciliary arteries enter the sclera and form in it by anastomoses an arterial ring, *Zinn's scleral circle of vessels*, surrounding the foramen for the optic nerve. This is of importance for the nutrition of the optic nerve, because numerous little branches go from it to the optic nerve and its sheaths, and anastomose with the branches of the central artery of the nerve. It is here, then, that the only connection between the ciliary and the retinal system of vessels exists.

We owe our knowledge concerning the lymph-passages chiefly to Schwalbe. For their study we make use of injections into the tissue of the dead and also of the living eye. Thus we find in what directions fluids penetrate most readily in and between the tissues of the eye. But to justify us in regarding the spaces thus exhibited as lymph-passages, proof must also be brought to show that they are coated by a continuous layer of endothelium; and this, too, Schwalbe has established in the lymph-spaces which he discovered.

(*c*) *Nourishment of the Eye.*

62. The secretion of the fluids of the eye, and also the nourishment of its tissues, take place mainly through the vessels of the uvea.

The *aqueous humor* is a limpid liquid, which in the normal state contains only an excessively small amount of albumin. It is produced by the iris and the ciliary processes, the latter playing the more important part in the process; for, in cases of congenital or acquired deficiency of the iris, the aqueous is still secreted in normal amount. The aqueous secreted by the ciliary processes arrives first into the posterior chamber, from which it enters through the pupil into the anterior chamber. Here it again leaves the eye by way of the ligamentum pectinatum and Schlemm's canal. The secretion of aqueous appears to take place quite rapidly, so that it is continually renewed. We can see this from the quickness with which any abnormal matter—e. g., blood—contained in the anterior chamber disappears from it. Still more quickly does the secretion of aqueous go on when the latter has been evacuated —e. g., by puncture of the cornea. The anterior chamber is restored as early as a few minutes afterward, as we have frequent opportunity of observing during operations. The rapid reproduction of aqueous is favored by the fact that after its escape the ocular tension is reduced much below the normal. Hence the blood pours in greater quantity into the vessels of the iris and ciliary body, thus relieved of their external pressure, and these expand proportionally and allow fluid to transude from them in greater abundance.

The *cornea* is nourished mainly by the network of marginal loops of the limbus, and to a small extent also by the aqueous humor which

makes its way into it by diffusion. The other two non-vascular tissues of the eye, the *lens* and the *vitreous*, are entirely dependent upon the uvea for their nourishment. They obtain nutrient material mainly from the ciliary body, perhaps also from the anterior section of the chorioid. Hence in diseases of these parts we very frequently see cloudiness of the lens and cloudiness and liquefaction of the vitreous, making their appearance as an expression of the disturbance in the nutrition. The process of tissue metamorphosis in the lens appears to be very slow, since pathological changes in it (opacities) often either remain stationary for an exceedingly long time or extend but slowly. The *retina*, it is true, has its own vessels, which, however, are situated simply in its inner layers and do not suffice for its nourishment. The retina, therefore, especially in its outer layers, is dependent upon the chorioid, whose chorio-capillaris indeed is almost directly adjoining. The chorio-capillaris, furthermore, must be credited with accomplishing the continual regeneration of the used-up visual purple.

(*d*) *Intra-ocular Pressure.*

63. For the purpose of simplifying the study of the conditions of pressure, we may leave the lens out of consideration, and think of the eyeball as a capsule filled with fluid. The capsule is the fibrous corneo-sclera, which has only a very small degree of elasticity. The fluid contained in the capsule exerts upon the inner surface of the latter a pressure which, in accordance with the laws of hydrostatics, is transmitted with the same intensity in every direction, and hence presses with the same weight upon every unit of surface of the wall. A square millimetre of the posterior surface of the cornea has therefore the same pressure to bear as a square millimetre of any portion of the sclera.

The *intensity* of intra-ocular pressure depends upon the relation between the capacity of the capsule and the amount of its contents. If the former becomes smaller or the latter greater, the pressure rises, and vice versa. Under physiological conditions, the capacity of the capsule—i. e., the volume comprised by the cornea and sclera—undergoes such inconsiderable variation that it may be neglected, and the capacity regarded as constant. The variations in intra-ocular pressure are hence referable to changes in the amount of matter contained in the eyeball, which may be increased or diminished. For example, the pressure at once sinks considerably when the aqueous has been evacuated by puncture of the cornea.

Those portions of the contents of the eyeball whose amount is variable are the aqueous, the vitreous, and most of all the blood that circulates in the vessels of the inner tunics of the eye. Every increase or decrease of blood-pressure in these vessels must result in a corresponding change in the ocular tension. Other causes, too, such as changes in the

form and volume of the iris and ciliary muscle, the pressure of the lids and of the exterior muscles of the eye upon the ball, etc., can alter it. One might therefore be inclined to believe that it was subject to considerable variations. But, on the contrary, observation teaches us that the intra-ocular pressure under normal conditions is pretty *constant*. In fact, a regulation of the tension is effected by the circumstance that the outflow of the fluid of the eye through the lymph-channels (excretion) changes in such a way that variations of pressure are at once compensated for. For example, the pressure in the whole vascular system, and consequently in the eye as well, may be elevated as the result of great muscular effort. The intra-ocular pressure is thus heightened; but proportionately more of the intra-ocular fluids which are subjected to this increased pressure are forced out of the eye through the excretory channels, so that the pressure very soon sinks again to its normal level. The converse would occur in a case in which the pressure has been diminished (e. g., in consequence of an escape of the aqueous humor); then more blood flows into the vessels of the uvea, now subjected to less pressure, and a more copious outflow of fluids into the interior of the eye (secretion) is the result. But at the same time the outflow of ocular fluids through the lymph-channels (excretion) is diminished, because the pressure to which the ocular fluids are subjected is less. In this way the normal pressure is very soon restored.

The practical estimation of the tension of the eye is performed by palpating the eyeball through the closed lids, just as if we were intending to test for fluctuation. Even under normal conditions the ocular tension varies within certain limits in different individuals; in general, the eyes of elderly persons feel harder than those of the young. Hence very slight pathological changes of tension can only be recognized with certainty as morbid, when we can make use of the second, normal eye of the same man for purposes of comparison; greater alterations of pressure, however, make themselves evident at once. It has been agreed to denote the normal tension by the expression *Tn* (*T* = tension or tone). Of increased tension (hypertonia) we distinguish three degrees: $T+1$, $T+2$, and $T+3$, which are arbitrarily selected, and indicate approximately: tension noticeably increased—greatly increased—hard as stone. Similarly, we employ for diminished tension (hypotonia) the designations $T-1$, $T-2$, and $T-3$.

The intra-ocular pressure plays an important part both under physiological conditions and also in diseases of the eye, and has hence been the subject of numerous investigations, chiefly experimental. For its exact measurement a manometer has been employed, one arm of which is connected with a cannula, the other being introduced into the eye. In this way it has been found that in the healthy human eye the average pressure equals that of a column of mercury twenty-six millimetres high; under pathological conditions (glaucoma) the pressure may exceed seventy millimetres (Wahlfors). This method of meas-

urement, however, is practically inapplicable on account of its being dangerous for the eye. Tonometers of various construction have therefore been devised, which measure the intra-ocular pressure by being simply placed upon the eye and impinging against it; but none of these instruments have so far found their way into practice.

In the assumption above made, that the eyeball is represented by a capsule filled with liquid, the lens and its retaining ligament, the zonula of Zinn, are left out of consideration. These two together form a diaphragm dividing the interior of the eyeball into a smaller anterior and a larger posterior section. It is hence possible that the pressure is not the same throughout the whole interior of the eye, as is assumed above, but that its action is different in the anterior chamber from what it is in the cavity of the vitreous, since the diaphragm bears a part of the pressure. Under ordinary circumstances, to be sure, this is not the case, since the zonula, owing to its elasticity, gives way toward the side of less pressure, and hence, in general, the pressure in all parts of the eye may be regarded as equally great. Nevertheless, a difference in pressure may be developed when the zonula is tightly stretched, as is the case, for example, immediately after the evacuation of the aqueous, when the lens pushes forward to the cornea and so tightens the zonula. Then the pressure in the anterior chamber is practically nothing, while the pressure in the vitreous maintains a certain height. In this case the difference in pressure induces increased filtration of fluid from the vitreous in the anterior chamber—a circumstance which contributes to the more speedy replenishment of the chamber, and at the same time causes the liquid which collects again to be more albuminous than that which has been evacuated. In this way is the fact accounted for that even in the dead eye the anterior chamber fills up again within a short time after the aqueous has been evacuated, this being effected by means of the fluid that passes into it from the vitreous (Deutschmann). Repeated punctures of the anterior chamber, therefore, cause more rapid tissue-metamorphosis in the vitreous, and hence prove useful in many cases of disease of the latter.

With regard to the nourishment of the *lens*, it is assumed that nutrient material starting from the ciliary body and the anterior part of the chorioid enters it in the region of its equator. Inside of the lens the fluid circulates probably in clefts which lie between the fibers of the lens in the anterior and posterior cortical layers, and which under pathological conditions may become visible as stellate opacities. The lymph leaves the lens probably through the anterior capsule and empties into the anterior chamber (Samelsohn). This is conjectured from observations of which I will adduce one made by myself. A locksmith's apprentice had a small fragment of iron pass through his cornea into the lens. No inflammation resulted, but an opacity of the lens developed, and this gradually assumed a yellowish-green color. This was referable to the gradual oxidation of the iron fragment and to the diffusion of the oxide thus formed throughout the lens. Then a circle of rust-colored points, corresponding approximately to the margin of the dilated pupil, formed upon the posterior surface of the anterior capsule. We may conclude from this that the liquids circulating in the lens usually left the latter at these points, and in so doing carried with them comparatively large quantities of the iron oxide, which became fixed in the lens capsule.

As regards the *retina*, various facts indicate that it is likewise dependent in part for its nourishment upon the chorioid, and particularly upon the most an-

terior layer of the latter—i. e., the chorio-capillaris. This layer extends forward only as far as the retina itself, or at least its complicated structure, does—that is, as far as the ora serrata. Again, at that spot where the retina displays its functions most actively—i. e., in the region of the macula lutea—the capillary loops of the chorioid are most densely disposed; and, lastly, there are many animals in which the retina has no vessels whatever, and hence evidently can be nourished only by the chorioid. The outflow of lymph from the retina takes place through the lymph-sheaths surrounding the retinal vessels.

III. Participation of the Uvea in the Visual Act.

64. The *iris* forms a diaphragm, which, as in the case of many optical instruments, is interposed between the refracting portions of the eye. It has a double task to perform: it prevents an excessive amount of light from entering the eye and so dazzling it and injuring the retina, and it cuts off the marginal rays. If these rays that pass through the periphery of the cornea and of the lens, and which, being less regularly refracted, would impair the sharpness of the retinal image. In order to be perfectly impermeable to light, the iris has a pigment-layer on its posterior surface. The iris has the advantage over the artificial diaphragms of optical instruments that its size is variable and can be adapted to circumstances. For this purpose there exist contracting fibers (sphincter pupillæ) and dilating fibers (posterior limiting membrane). Moreover, the vessels of the iris must be considered as also taking part in this process, since by their distention the iris becomes broadened and the pupil consequently contracted, and vice versa.

The *contraction* of the pupil is governed by the oculo-motor nerve, which supplies the sphincter pupillæ (and also the ciliary muscle) through the ciliary ganglion and the ciliary nerves. By stimulation of the oculo-motor nerve, contraction of the pupil is produced; by its section or paralysis, dilatation of the pupil.

Dilatation of the pupil is dependent upon the sympathetic, which derives the fibers destined for the pupil from the cilio-spinal center of the cervical spinal cord. Irritation of this center or of the cervical sympathetic produces dilatation, and paralysis of it contraction of the pupil.

The *reaction* of the pupil takes place involuntarily and unconsciously. It is either reflex, in which case the stimulus is transmitted from centripetal nerve-channels to the nerves of the iris, or it is associated, in which case the pupillary fibers of the oculo-motor nerve are set into action simultaneously with other fibers of the same nerve.

The stimulus to *reflex reaction* of the pupil is set in action—

1. By *light*. This produces contraction of the pupil, while conversely in the dark the pupil dilates. The reflex arc in this case passes through the optic nerve to the nucleus of the oculo-motor nerve and along the latter to the eye. The reaction for light always affects both eyes—i. e., if the light falls into one eye alone, the pupil of the

other eye also always contracts (consensual reaction). The reaction takes place in both eyes in exactly the same way—that is, appears at the same time and reaches the same pitch. The reaction of the pupil to light is exceedingly sensitive, and is employed with great advantage to determine objectively whether an eye has any sensation of light or not (particularly in children, malingerers, etc.).

2. Toward *sensory stimuli*, no matter what part of the body they affect, the pupil reacts by *dilating*. Hence, in deep sleep, and also in profound narcosis, in which sensory stimuli no longer produce reflexes, the pupil is very much contracted, dilating, however, the moment that waking from the sleep or from the narcosis occurs. Strong psychic stimuli—e. g., fright—in like fashion produce dilatation of the pupil.

The *associated reaction* of the pupil always consists of a *contraction*. It occurs—

1. In *convergence* (synergy with the internal recti).

2. In *accommodation* (synergy with the ciliary muscle). Since under physiological conditions every act of accommodation is accompanied by a corresponding convergence, and the contraction of the pupil keeps pace with both, we have here as a regular thing a uniform consentaneous action of the sphincter pupillæ, the ciliary muscle, and the internal rectus. These muscles are all supplied by the oculo-motor nerve, so that their associated action depends upon a simultaneous excitation of those bundles of fibers of this nerve which supply them. This simultaneous excitation is facilitated by the fact that the groups of ganglionic cells from which these three bundles of fibers arise lie in immediate juxtaposition in the brain—that is, in the most anterior part of the oculo-motor nucleus (see Fig. 54, and § 123).

Since the pupil reacts to stimuli of so many kinds and varying so greatly in degree, it is in a state of constant motion. It oscillates on both sides of a mean width, which is always the same for both eyes. Inequality of the pupils is always a pathological phenomenon. The mean width of the pupil differs with the individual and also alters with the age. Very greatly contracted in new-born infants, the pupil soon becomes more dilated, and then becomes smaller again in manhood, and still more in old age. In old people also the reaction of the pupil becomes sluggish, in consequence of the unyielding character of the tissue of the iris, and especially of the sphincter (rigidity of the sphincter).

65. Reaction of the Pupil to Poisons.—There is a series of alkaloids which produce either dilatation of the pupil (mydriasis) or its contraction (miosis).* These substances are accordingly distinguished

* From μείωσις, contraction; hence miosis, and not myosis, as it is generally written (Hirschberg). The derivation of μυδρίασις is uncertain. This word was already used by the ancients to signify dilatation of the pupil, and also the blindness that was so frequently associated with it.

into mydriatics and miotics. They always act upon the ciliary muscle in the same manner as upon the sphincter iridis. The most important of the mydriatics is atropine, the most important of the miotics are eserine and pilocarpine.

1. *Atropine* paralyzes the sphincter and the ciliary muscle, and hence results in dilatation of the pupil and also in inability to see clearly near by. The dilatation of the pupil is a maximum one. If, in the case of a dilatation of the pupil caused by oculo-motor paralysis, atropine is instilled, the pupil becomes still more dilated. This proves that atropine, besides producing paralysis of the contracting fibers, causes also stimulation of the dilating fibers. The effect of the atropine makes its appearance in from ten to fifteen minutes after the instillation, and soon reaches its maximum. Commencing with the third day it begins to decrease again, but does not disappear completely until after the lapse of a week. The instillation of atropine, therefore, causes the patient a disturbance of pretty long duration, and hence should be employed only when there is good reason for it.

In practice, a one-per-cent solution of sulphate of atropine is most frequently employed. If it is desired to obtain a particularly intense effect, a granule of the atropine salt in substance is placed in the conjunctival sac, where it is dissolved by the tears, and affords a concentrated solution. In this case we must be on the lookout for symptoms of general poisoning, which do not ordinarily develop with the instillation of the one-per-cent solution. These symptoms consist in a troublesome sense of dryness in the throat, nausea, reddening of the face, and subsequently faintness, or even loss of consciousness, and acceleration of the pulse. In case of marked poisoning also the pupil of the other eye, which has not been treated with atropine, is dilated. The poisoning is effected by the entrance of the atropine into the nose along with the tears and its absorption in excessive quantity by the nasal mucous membrane. Hence we may preclude the development of poisonous symptoms, especially in applying atropine in substance, by preventing the tears from running down into the nose. For this purpose we draw the lower lid for a short time away from the eyeball, so that the tears are poured out upon the cheek, or we compress the lachrymal sac with the finger. In serious cases of poisoning, a subcutaneous injection of morphine is indicated as the antidote.

We are not to conceive of the action of atropine upon the pupil in the same light as if it had got by absorption into the circulation, as is the case when it is administered internally. For in this case the pupils of both eyes would necessarily be dilated, while, as a matter of fact, the dilatation of the pupil occurs only on the side in which the instillation has been made. The action, accordingly, is a local one, and takes place from the atropine passing through the cornea by diffusion and getting into the aqueous humor so as to act directly upon the iris.

We can prove this by a simple experiment, by dropping atropine into one eye, and, as soon as the pupil has dilated, evacuating the aqueous by paracentesis. If, then, this aqueous is introduced into the other eye, it excites a dilatation of the pupil in the latter—a proof that it contains atropine. In a similar way is the action of the other mydriatics and miotics upon the iris to be explained.

2. *Eserine* (also called *physostigmine*) has an action exactly the opposite of that of atropine, since it places the iris and the ciliary muscle in a state of tonic contraction. Consequently, miosis develops so that the pupil is about the size of a pin's head, with adjustment of the eye for the near point, as if marked myopia were present. We generally apply sulphate of eserine in one-per-cent solution. This solution, when freshly prepared, is colorless, but after some days becomes red, although without losing its activity. The instillation of eserine produces, simultaneously with the changes in the iris, a feeling of great tension in the eye, and often also headache and even nausea, so that with many persons it can not be employed. For this reason *hydrochloride of pilocarpine*, prescribed in a one- to two-per-cent solution, is recommended as a miotic for ordinary use. Its solution keeps better than that of eserine, and does not act as powerfully as the latter, but is not accompanied by any unpleasant complications. Eserine is best reserved for those cases in which pilocarpine is ineffectual.

The action of miotics is of shorter duration than that of the mydriatics, and is also less powerful. Hence a pupil contracted by eserine or pilocarpine can be dilated by atropine, but a pupil dilated by atropine can not be contracted by a miotic.

3. *Cocaine* dilates the pupil, and hence would seem to call for mention in this place, although, strictly speaking, it does not belong to the mydriatics proper—that is, the dilatation of the pupil by cocaine is not produced, as in their case, by its action upon the contracting or the dilating fibers of the iris, but by a contraction of the blood-vessels of the iris. The dilatation of the pupil is therefore only a moderate one, and the reaction of the pupil to light persists; moreover, mydriatics and miotics still produce an effect. If cocaine is instilled into an eye the pupil of which has been dilated by atropine, the dilatation increases somewhat in consequence of the anæmia of the iris which then ensues; hence the mydriasis produced by the simultaneous action of atropine and cocaine is the most considerable that can possibly be attained. The accommodation is not paralyzed by cocaine, but only somewhat weakened.

Besides acting upon the iris, cocaine produces also the following effects: The conjunctiva becomes very pale, and at the same time the patient has a feeling of cold in the eye. The palpebral fissure is more widely open and the act of winking is less frequent, so that the cornea may readily become dry upon its surface. Sometimes the eye is pro-

truded somewhat forward, and the intra-ocular tension slightly diminished. The practically important phenomenon, however, is the anæsthesia shown by the superficial tissues of the eye (cornea and conjunctiva).

The effects of cocaine are best explained upon the assumption that it acts as a stimulant to the fibers of the sympathetic. The contraction of the vessels thus produced causes the paleness of the conjunctiva, and also the diminution in size of the iris. The contraction of the superior and inferior palpebral muscles (see § 106), which are also supplied by the sympathetic, is the cause of the dilatation of the palpebral fissure. Whether the anæsthesia of the surface of the eyeball is to be referred to its bloodless state or not, has not yet been determined with certainty. Owing to this anæsthesia the reflex movements of the lids are abrogated.

Cocaine was introduced into ophthalmology by Koller, and is employed under the form of the hydrochloride in a two- to five-per-cent solution. Its most frequent use is to produce anæsthesia for the performance of operations (see § 152); in addition, it is instilled to ameliorate the pain in superficial inflammations, especially of the cornea, and also to diminish photophobia and blepharospasm. It may also be employed to dilate the pupil for examination with the ophthalmoscope.

Besides the physiological forces (muscular and elastic fibers) which alter the width of the pupil, there are purely mechanical factors which require consideration in this connection. This is the case, for instance, with the contraction of the pupil that regularly occurs when the aqueous escapes. This contraction is of practical importance in the performance of many operations. When, for instance, we perform discission of cataract through the cornea, we take care not to let the aqueous escape, since the consequent contraction of the pupil would expose the iris to greater pressure from the swelling lens. That this contraction owes its origin to purely mechanical causes, is deduced from the fact that it occurs even in the eye of a dead man when the aqueous is evacuated.

Dilatation of the pupil manifests itself by a sense of dazzling. Sometimes the patients also allege that objects appear smaller (micropsia). This phenomenon, however, does not depend upon the dilatation of the pupil, but upon the paralysis of accommodation, which is generally present at the same time, and is therefore also observed when the latter alone is present. (For its explanation, see under paralysis of accommodation, § 131.) Conversely, in contraction of the pupil, sometimes—i. e., if spasm of accommodation is at the same time present—objects appear larger (macropsia). Moreover, obscuration of vision is often complained of, because less light enters the eye through the contracted pupil. In very marked miosis, whether occurring after the employment of miotics or appearing spontaneously (e. g., as the result of tabes), the pupil is frequently found to be irregular and slightly angular, although no synechiæ exist.

The *reaction of the pupil to light* is a very valuable sign of the existence of perception of light: in the first place, because it is exceedingly sensitive; and, secondly, because it demonstrates the existence of perception of light independently of the statements of the patient. Its usefulness is still further enhanced

by its disclosing in the pupils of both eyes (through the consensual reaction) the perception of light by one eye. How is this consensual reaction effected? From the retina of each eye (e. g., the right eye, *R*, Fig. 54) fibers pass through the chiasm partly into the right, partly into the left optic tract (Fig. 54, *T* and T_1). From these the stimulus is transmitted directly to both right and left oculo-motor nucleus (*K* and K_1); then each nucleus sets up a contraction of the pupil on its own side. The consensual reaction, therefore, is really as direct as is the pupillary reaction of the illuminated eye itself.

The connection between the oculo-motor nuclei of the two sides furthermore serves to maintain the simultaneity of their action. The result of this is that under normal conditions both pupils must be of equal diameter, even if only one of the eyes is exposed to the impact of light, or if the sensitiveness of the two eyes to light is different. Inequality of the pupils (anisocoria) is always pathological. For the reasons given it can never take its origin from the centripetal fibers (optic-nerve fibers), but is always caused by a disturbance in the centrifugal channels (oculo-motor nerve and its center).

In testing the perception of light by the reaction of the pupils, we must not lose sight of the fact that there are cases in which, although the perception of light is present, the reaction is absent; and, conversely, cases in which, with good reaction, there is yet no perception of light.

(*a*) The cases in which the pupil does not react to light, although the perception of light is present, are frequent. The iris may be paralyzed either artificially by mydriatics, or by disease, such as oculo-motor paralysis or paralysis of the nerves of the iris due to increase of tension or to inflammation. In the same category belong those cases in which the iris is mechanically prevented from moving by adhesions to the posterior capsule of the lens or to the cornea. In all these cases, however, consensual reaction of the pupil takes place in the other eye, provided that that is healthy. The test for the perception of light in such a case, then, would be performed by alternately exposing to light and screening the eye to be tested, and meanwhile watching the pupil of the other eye for any movements that it might make. The absence of the reaction to light can also be caused by an interruption in the course of the reflex arc. This occurs in spinal diseases, and most of all in tabes dorsalis. In these cases the pupil is either found to be perfectly immobile, or its reaction for accommodation and convergence is retained, while the reaction for light has disappeared (Argyll-Robertson phenomenon). In the latter case the reflex arc running from the optic nerve to the oculo-motor nucleus is interrupted (in Fig. 54, somewhere between *S* and *K*—e. g., at *m*), while the connections of the centers for the pupil, for accommodation, and for convergence, which adjoin each other in the oculo-motor nucleus, are undisturbed. The reflex immobility of the pupil in tabes dorsalis is generally combined with a marked contraction of the pupil (so-called spinal miosis), but it also is found at times with a normally wide or even with a dilated pupil.

(*b*) It also happens that the reaction of the pupil to light is present, without there being any perception of light. This occurs when the lesion is situated high up in the optic tract. The fibers of the optic nerve ascend to the cerebral hemispheres and terminate in the cortex of the occipital lobe (*B*, Fig. 54). But, some time before this takes place, those fibers (*m*) of the reflex arc, which pass to the center for the pupillary movements, branch off from the optic tract. If, then, the optic tract is interrupted above the place where they

are given off (e. g., at *e e*), stimulation of the optic nerve-fibers no longer reaches the cerebral cortex and hence excites no perception, and yet the pupillary re-



FIG. 54.—SCHEMATIC REPRESENTATION OF THE OPTIC TRACTS.

The field of vision common to the two eyes is composed of a right half, *G*, and a left half, G_1. The former corresponds to the left half, *l* and l_1, of the two retinæ, the latter to the right half, *r* and r_1. The boundary between the two halves of the retina is formed by the vertical meridian. This passes through the fovea centralis, *f*, in which the visual lines drawn from the fixed point, *F*, impinge upon the retina. The optic nerve-fibers arising from the right half, *r* and r_1, of the two retinæ (indicated by the dotted line) all pass into the right optic tract, *T*, while the fibers belonging to the left half, *l* and l_1, of the two retinæ pass into the left optic tract, T_1. The fibers of each optic tract for the most part pass to the cortex of the occipital lobe, *B*, forming Gratiolet's optic radiation, *S*; the smaller portion of them, *m*, goes to the oculo-motor nucleus, *K*. This consists of a series of partial nuclei, the most anterior of which sends fibers, *P*, to the pupil (sphincter iridis); the next one sends fibers, *A*, to the muscle of accommodation; and the third sends fibers, *C*, to the converging muscle (internal rectus, *i*). All three bundles of fibers run to the eye in the trunk of the oculo-motor nerve, *Oc*. Division of the optic tract at *g g* or at *e e* produces right hemiopia; and in the former case there would be no reaction to light on illuminating the left half of either retina. Division of the chiasm at *s s* produces temporal hemiopia. Division of the fibers, *m*, abolishes the reaction of the pupil to light, but leaves the sight and also the associated contraction of the pupil in accommodation and convergence unaffected.

flex is still regularly produced. The same thing would happen if the cerebral cortex itself were through some lesion incapacitated for performing its functions. Such cases, in which blindness exists, even though the examination of the eye gives negative results and the reaction of the pupil to light is preserved, are, to be sure, very rare, so that under these circumstances our first thought would be of simulation, and we would examine for this first.

In general, the pupil dilates upon the application of sensory stimuli. An exception to this rule is when the stimuli act with intensity upon the eye itself. In this case the pupil contracts, and does so in consequence of the hyperæmia of the iris produced by the stimulus (see § 67). The pupil also reacts with great sensitiveness to stimuli which start from the central organs of the nervous system—its reaction usually taking the form of dilatation. Hence the behavior of the pupil plays an important part in the diagnosis of diseases of the brain. A difference in the size of the pupils is very frequently found in the subjects of mental disease.

Atropine is such an efficient mydriatic that exceedingly small quantities—the millionth part of a gramme—suffice to dilate the pupil. Sometimes all that is necessary for us in order to get a dilatation of our own pupils is to instill atropine into another person's eye, and in so doing moisten our fingers and then through carelessness touch our own eyes with them. Dilatation of the pupil may also be produced by the internal use of atropine or of drugs which contain it. The most frequent occurrence of this sort is when patients who take belladonna internally complain of being dazzled, and of not seeing well near by in their work. We find in such cases moderate dilatation of the pupil and diminution in the power of accommodation.

With many people there exists an *intolerance* of atropine. This manifests itself in various ways : (*a*) By the development of toxic symptoms, such as dryness in the throat or nausea, with even small doses. This is especially apt to occur after the long-continued use of atropine. (*b*) By the production of a catarrh (atropine-catarrh), which is usually characterized by the formation of numerous follicles. Here, again, a pretty long-continued use of atropine is required to produce the effect. (*c*) In many persons a single drop of atropine is enough to bring on marked redness and swelling of the lids, looking like an attack of erysipelas. In these and similar cases the atropine must either be simply abandoned, or be replaced by another mydriatic, according to circumstances. Among the other mydriatics that we are acquainted with are homatropine, duboisine (also called hyoscyamine), hyoscine, and gelsemine. Hyoscine acts the most powerfully—even more powerfully than atropine—but as it produces toxic symptoms even more readily, it is employed only in exceptional cases. Of the alkaloids mentioned, only two are at all in frequent use, namely, duboisine and homatropine. Sulphate of *duboisine* acts like atropine, and is employed instead of it in those cases in which the latter is not tolerated. *Homatropine* hydrobromide has a feebler and, what is most important, a less enduring action than atropine, its effects lasting for scarcely more than about five hours. It is hence a valuable agent when a transient dilatation of the pupil for purposes of examination of the eye is all that is required.

Among miotics, *pilocarpine* in particular is employed for many different purposes and by two entirely different methods—locally by instillation into the eye, and internally in the shape of a hypodermic injection. In the first way it

is much employed for contracting the pupil, and especially for diminishing the intra-ocular pressure in glaucoma. In its subcutaneous application it produces great diaphoresis and salivation, for which reason it exerts a powerful effect in furthering the resorption of pathological exudations. Hence it is employed in this way: 1, In violent acute inflammations, especially in iridocyclitis and in retrobulbar neuritis; 2, for clearing up recent opacities of the vitreous; 3, in detachment of the retina. It is contra-indicated in pregnancy, and also in heart troubles.

Both the mydriatics and the miotics may be introduced into the eye in the form of an ointment, instead of in solution. Small gelatin disks containing a certain quantity of the alkaloid are also made, which, when introduced into the conjunctival sac, become dissolved and so develop their activity.

What effect do mydriatics and miotics exert upon the *intra-ocular pressure?* So far, observers have not arrived at concordant results in regard to this matter, but at least this much has been proved by experiments, that in the healthy eye the alkaloids cause only very insignificant variations of tension. The case is altogether different when elevation of tension exists, or there is a tendency to it; then atropine may raise the tension very considerably, while eserine and pilocarpine noticeably diminish it.

The function of the *ciliary body* is twofold, inasmuch as it consists of the ciliary processes and the ciliary muscle. The former, on account of their abundant supply of vessels, afford nutrient material for adjacent structures, like the vitreous and the lens, and secrete the aqueous humor. The ciliary muscle presides over accommodation (see § 140). It acts in harmony with the sphincter pupillæ, and, like it, is paralyzed by mydriatics, thrown into spasm by miotics.

The function of the *chorioid* is likewise chiefly that of a nutrient organ for the retina, vitreous, and lens. The chorioid takes part more directly in the act of vision, inasmuch as it supplies the visual purple, and also because its pigment, together with the pigment epithelium, forms the dark coating of the interior of the eye.

IV. Development of the Eye.

66. The eye develops from an invagination which forms on both sides of the first cerebral vesicle. This invagination, which is called the *primitive ocular vesicle* (Fig. 55 *A*, *a*), remains in connection with the cerebral vesicle by means of a pedicle, which, at first broad, afterward more narrow, becomes subsequently the optic nerve. Its surface is covered by the ectoderm (*E E*), which shows a thickening, *c*, at a point corresponding to the summit of the ocular vesicle. This, the first germ of the lens, becomes folded upon itself by reason of the more rapid growth of the ectoderm at this spot, and forms an everted pouch directed toward the ocular vesicle (*L*, Fig. 55 *B*). This pouch afterward becomes shut in in front so as to form a closed sac, the lens vesicle. The lens is accordingly an epithelial structure, being a derivative of the external germinal layer, and in the beginning consists of a hollow vesicle, which afterward becomes filled up by the growth of its

cells and is converted into a solid sphere. In proportion as the ectoderm at the site of the primitive lens pushes against the ocular vesicle, the surface of the latter is indented, and at length gets to be completely invaginated. Thus a flask-shaped structure with double walls is formed out of what was once a round sack (*a*, *a*, Fig. 55 *B*). This is called the *secondary ocular vesicle*, which is hence the primitive ocular vesicle that has been invaginated and thus, so to speak, reduplicated. From the ocular vesicle is subsequently formed the retina, which thus must be looked upon as an isolated portion of the brain itself. The exterior and interior layer of the secondary ocular vesicle become differentiated early. The exterior layer (*p*, Fig. 55 *B*) takes up pigment, and sub-



FIG. 55.—SCHEMATIC REPRESENTATION OF THE DEVELOPMENT OF THE EYE.

A, EARLIER STAGE. The primitive ocular vesicle, *a*, is a protrusion from the first cerebral vesicle, *b*, from which it is separated by a shallow constriction. It is surrounded by the cells of the mesoderm, *M*, and at its summit is slightly indented by a thickening, *c*, of the ectoderm, *E E*.

B, LATER STAGE. The separation of the ocular vesicle, *a a*, has advanced so far that it is connected with the brain only by a slender pedicle, *o*, which subsequently becomes the optic nerve. The ocular vesicle is converted by the sinking in of its anterior wall into a flask-shaped structure, which has two walls, an anterior thick wall, *r*, and a posterior thin one, *p*. From the thickening of the ectoderm, *E E*, the lens-vesicle, *L*, has been formed. *M*, mesoderm.

sequently becomes the pigment-epithelium, which therefore is rightly counted in with the retina. The interior layer (*r*) soon gets to surpass the exterior one considerably in thickness; its cells acquire a radial arrangement and develop into the retina proper. The anterior margin of the ocular vesicle, where the two layers become continuous, corresponds to the margin of the pupil in the fully developed eye (Fig. 56). From the exterior layer are formed the pigment-epithelium of the chorioid and the ciliary body (*e*, Fig. 56), and also the more anterior (e_1) of the two layers of pigment upon the posterior surface of the iris. The interior layer forms the retina (*r*); farther forward it forms the non-pigmented stratum of cells of the pars ciliaris retinæ, covering the ciliary body (*C*), and lastly, quite in front, it forms the posterior sheet of the retinal pigment-layer of the iris (r_1).

At the time when the indenting of the ocular vesicle by the lens takes place, the latter completely fills the cavity of the vesicle, no vitreous as yet existing. This latter is essentially connective tissue, and is derived from the mesoderm, which surrounds the ophthalmic vesicle (Fig. 55, *M*), and which makes its way into the interior of the latter through an opening—the *fœtal ocular fissure*—in its lower side. Even as early as the time when the ocular vesicle is undergoing invagination in the form of a flask we notice that at its lower side the wall of the flask is not as high or as protuberant as elsewhere (Fig. 55, *B*), and that in one spot it is altogether deficient. Here, then, a fissure-like defect exists in the wall of the flask (Fig. 57, *s*), a defect which is continued backward upon the pedicle of the ocular vesicle (the optic nerve) in the form of a furrow (Fig. 57, s_1). Through this fissure the mesoderm gradually grows from the outside into the interior of the eye, pushing its way in between the retina and the lens, separating them from each other, and itself becoming transformed into the vitreous. Subsequently the margins of the fissure unite so that the eye again forms a closed vesicle. The vitreous is thus cut off from its connection with the portions of the mesoderm which lie without, and which produce the uvea and the sclera. The channel in the optic nerve, which represents the continuation backward of the ocular fissure (Fig. 57, s_1), is also filled in by mesodermal tissue. When, then, the margins of the channel afterward become united in the same way as is the case with the fissure in the eyeball itself, this tissue, which is derived from the mesoderm, is shut up within the axis of the optic nerve, and retains none of its former connections save those existing anteriorly with its continuation, the vitreous. This tissue afterward develops into the central vessels (Fig. 56, *c*) of the optic nerve with their en-



FIG. 56.—SCHEMATIC SECTION THROUGH AN EMBRYONIC EYE. AFTER SCHWALBE.

The external envelope of the eye, formed by the mesoderm, consists of the cornea, *H*, and the united sclera and chorioid, *CS*. At the junction of *CS* and *H*, two projections, the iris, *i*, and the ciliary body, *C*, extend into the interior of the eye. The secondary ocular vesicle which is inclosed within these envelopes consists of two layers, the retina, *r*, and the pigment-epithelium, *e*. These two extend forward as far as the posterior surface of the iris, where they form the anterior layer, e_1, and the posterior layer, r_1, of the retinal pigment of the iris. Posteriorly, the inner layer alone is continued into the optic nerve, *O*. The central artery of the optic nerve, *c*, gives off vessels, *h*, to the outer layers of the vitreous, *g*, and then continues its course as the arteria centralis corporis vitrei, c_1, to the posterior pole of the lens, *L*. There it breaks up into the branches of the vascular network which, as the membrana capsularis, *ca*, covers the posterior surface and as the pupillary membrane, *p*, the anterior surface of the lens.

velope of connective tissue, and these are continued forward into the vitreous as the vessels of the latter. The vessels in the embryonic eye are, in fact, disposed as follows: The branches of the central artery of the optic nerve spread out in the outermost layers of the vitreous (Fig. 56, *h*), and afterward become the retinal vessels lying in the innermost layers of the retina. One branch, however, of the central artery, the arteria centralis corporis vitrei or arteria hyaloidea, runs straight forward through the vitreous to the posterior pole of the lens, lying in the central canal of the vitreous (canalis Cloqueti, c_1, Fig. 56). Arriving at the posterior pole of the lens, it divides into branches which form a vascular network enveloping the entire lens. That portion which coats the posterior surface of the lens is called the membrana capsularis (*ca*, Fig. 56). In the place where the latter passes over to the anterior surface of the lens new vessels join it, derived from the anterior surface of the iris (*i*). These arise from the circulus arteriosus iridis minor and pass over the edge of the pupil to the vascular membrane which incloses the lens, and which, in the region of the pupil, bears the name of the membrana pupillaris (*p*). Among the vessels passing from the iris to the lens are also veins which must provide for the transportation of the venous blood from the entire vascular membrane of the lens, including both the membrana pupillaris and membrana capsularis, since there is no vein corresponding in course to the hyaloid artery.

FIG. 57.—SCHEMATIC REPRESENTATION OF THE FŒTAL FISSURE OF THE EYE.

The flask-shaped structure, *a*, forming the eye has on its under side the fœtal fissure, *s*, which is continued upon the optic nerve as an open groove, s_1; *a* is almost entirely filled by the lens, *L*.

The chorioid, sclera, and cornea are developed from the mesoderm which envelops the ocular vesicle. The iris grows out from the anterior margin of the chorioid.

CHAPTER V.

DISEASES OF THE IRIS AND OF THE CILIARY BODY.

I. Inflammation.

67. The iris and the ciliary body form a continuous whole, inasmuch as the iris springs from the ciliary body; both, moreover, are supplied by the same blood-vessels. It is hence quite easy to understand that both organs are very frequently diseased at the same time. Unmixed inflammation of the iris (iritis) or of the ciliary body (cyclitis) is rare; in most cases we have to do with a combination of the two (irido-cyclitis). For practical reasons, however, it is advisable first to describe the symptoms of iritis and of cyclitis separately, and then show what sort of clinical picture is produced by their combination.

Symptoms of Iritis.—The symptoms of iritis are partly referable to the hyperæmia of the iris, partly to the formation of exudation.

Hyperæmia of the iris manifests itself chiefly by the discoloration which causes a blue or gray iris to appear greenish—a change which is particularly striking when comparison is made with the iris of the other eye, in case this is healthy. In dark eyes the discoloration is less pronounced. Sometimes, with the aid of a magnifying-glass, we can clearly distinguish the separate dilated blood-vessels under the form of red striæ or maculæ. The other changes found concern the pupil, which is contracted, and does not react as well as usual. The contraction is a necessary result of the dilatation of the iris through the increased fullness of the vessels; besides, there is a spasm of the sphincter produced by the irritation. For these reasons the reaction of the iris to light is diminished, and atropine also acts less promptly and less thoroughly. The hyperæmia of the iris is accompanied by ciliary injection, photophobia, and increase of the lachrymal secretion.

The symptoms of congestion just described may exist by themselves without symptoms of exudation, in which case we do not speak of iritis, but merely of hyperæmia iridis. This is observed as a result of the same causes as iritis itself, in case the irritation is not great enough to provoke actual inflammation. Pure hyperæmia of the iris is most frequently seen in corneal affections, and particularly in case of small ulcers or foreign bodies in the cornea. Hyperæmia of the iris, provided it is not the precursor of an iritis, disappears without leaving any lasting traces of its presence.

Exudation takes place partly into the tissue of the iris itself, partly into the surrounding cavities, the anterior and posterior chambers, and is accordingly characterized by varying symptoms:

1. *Exudation into the tissue of the iris* makes the latter, as it is filled with an abundance of round cells, appear swollen and thicker than usual. The *discoloration* is still more pronounced than in simple hyperæmia, the distinct markings of the anterior surface of the iris being obscured. A factor that contributes to this obscuration in many cases is the deposition of an exudation-membrane covering the anterior surface of the iris (*d*, Fig. 36). It is easy to understand that the rigid and swollen iris should react but insufficiently to light; the pupil is greatly contracted.

2. *Exudation into the anterior chamber* manifests itself first by *turbidity of the aqueous*, in which numerous exudation-cells are suspended. The turbidity is best recognized upon the dark background of the pupil, which in this case looks gray instead of being a pure black. Gradually the formed constituents floating in the aqueous sink to the bottom of the chamber, where they form a *hypopyon*. (For more precise particulars see page 136.) When there is very great hyperæmia, rupture of the blood-vessels in the iris may take place with an extravasation of blood, which also sinks to the bottom of the anterior chamber (hyphæma).

The exudate is often precipitated from the aqueous upon the anterior surface of the capsule of the lens (*e*, Fig. 36), where it is usually continuous with the above-mentioned exudate, which covers the anterior surface of the iris. If this exudate becomes organized, a membrane is produced which closes the pupil and is connected with the pupillary margin of the iris (*o*, Fig. 59). This is called a pupillary membrane, and the condition thus brought about is called *occlusio pupillæ*. It is evident that this condition must result in a very considerable impairment of vision.

3. Exudation poured out into the *posterior chamber* is not accessible to direct observation, but manifests itself only by the adhesions which it causes between the iris and the capsule of the lens (*posterior synechiæ*). These adhesions principally develop at the spot where the iris and the capsule of the lens are in contact—i. e., at the pupillary margin. They form at the time when the iritis is at its height, and when, therefore, the pupil is greatly contracted. When, after the iritis has run its course, the pupil tends to resume its usual mean width, this is only possible over the area in which the pupillary margin has remained unattached. The portions which are adherent to the capsule of the lens can not retract, but project toward the center of the pupil under the form of fine or coarse dentations. The pupil thus acquires an irregular shape which is still more obvious if atropine is instilled; for, as the iris then retracts strongly at its unattached por-

tions, the synechiæ stand out in the clearest possible way (*a* and *b*, Fig. 58). Atropine is hence a very valuable agent for the diagnosis of posterior synechiæ.

In the formation of posterior synechiæ, it is not the stroma of the iris, but the layer of retinal pigment (*h*, Fig. 47) covering its posterior surface, that becomes adherent to the capsule of the lens. When the iris tends to contract, the pigment layer is held back at the points of adhesion, and is thus exposed to view more extensively than usual. Hence in dilatation of the pupil, especially by atropine, the tags jutting out into the pupil look brown. From the traction exerted by the iris, rupture of the synechiæ may result. This sometimes is effected spontaneously by the traction which is constantly being made upon the adhesions during the ceaseless movements of the iris; for the most part, however, rupture is produced artificially by the instillation of atropine. In that case we see, at the spot where the synechia has been set free, a brown spot remaining upon the anterior capsule of the lens. This is the pigment layer whose pathological adhesion to the capsule of the lens is firmer than its physiological connection with the tissue of the iris. If several synechiæ have been ruptured, we find remains of them in the shape of a corresponding number of brown dots arranged in a circle upon the anterior capsule of the lens (Fig. 58, between and adjoining *a* and *b*). This circle is narrower than the mean diameter

FIG. 58.—POSTERIOR SYNECHIÆ AND THE REMAINS OF A PUPILLARY MEMBRANE. MAGNIFIED 2×1.

The pupil has been dilated by the instillation of atropine. The dilatation, however, is unequal, because the upper part of the pupillary margin is fixed by means of adhesions to the anterior capsule of the lens. At *a* there is a slender synechia which is drawn out into a fine black point; at *b*, on the other hand, is found a broad and but slightly elongated adhesion, such as frequently occur in syphilitic iritis. Between the synechiæ and by the side of them, the capsule of the lens is covered with minute black dots arranged in a semicircle. They correspond to the situation of the pupillary margin when the pupil was contracted and have been left by the rupture of the adhesions. From the lower part of the iris a filament, *c*, runs straight upward. This arises from the trabeculæ of the circulus iridis minor, and passes in the region of the pupil to the anterior capsule of the lens, where it is attached to a small, round, capsular opacity. This filament is not a posterior synechia, but a remnant of the fœtal pupillary membrane. It does not prevent the iris from retracting properly under atropine, but is simply stretched and drawn out thin itself.

of the pupil, because the synechiæ were formed at the time when the pupil was contracted by iritis. The dots of pigment never disappear, and hence during the whole life give evidence of an iritis that has once existed.

If the adhesion of the iris to the capsule of the lens is not confined to single points, but comprises the whole extent of the pupillary margin, we speak of an *annular posterior synechia*. No projecting tags

are then apparent, because the iris is no longer able to retract at any spot, the pupil remaining unchanged all the time, even after the instillation of atropine. There is generally a brown fringe (pigment) or a gray fringe (exudate) investing the pupillary margin. An annular synechia is seldom formed all at once; it is for the most part the result of a number of recurring attacks of iritis, which little by little



FIG. 59.—SECLUSION AND OCCLUSION OF THE PUPIL. MAGNIFIED 5×1.

The iris is adherent by its entire pupillary margin to the lens, and is pushed forward. The posterior chamber, *h*, is thus made deeper, the anterior chamber, *v*, shallower, especially at the peripliery where the root of the iris, *a*, is pressed against the cornea by the increase of tension. In consequence of the traction made upon the iris, its retinal pigment is beginning to separate (at *s*) and to be left upon the capsule of the lens. The pupil is closed by an exudate-membrane, *o*, by the contraction of which the anterior capsule is thrown into folds. In the lower part of the anterior chamber there is matter, *p*, precipitated upon the posterior surface of the cornea. In consequence of the increase in tension, both the ciliary processes, *c*, and the ciliary muscle, *m*, are atrophic and flattened. The cortex of the lens has undergone cataractous disintegration, and at *r* is separated from the capsule by liquor Morgagni; the nucleus, *k*, of the lens is unaltered.

produce a more and more extensive adhesion of the iris to the lens. The direct consequence of an annular synechia is the shutting off of the anterior from the posterior chamber—shutting off of the pupil (*seclusio pupillæ*, Fig 59).

The two sequelæ of iritis, shutting off of the pupil (seclusio pupillæ) and shutting up of the pupil (occlusio pupillæ), very often occur together owing to the fact that the exudate which attaches the pupillary margin to the lens may also extend over the entire pupil. But they may also occur separately and then have very different consequences. Occlusion of the pupil occurring by itself produces very great diminution of sight, without, however, entailing any dangers for the future. Seclusion of the pupil in itself does not affect the sight, if the pupil is free from membrane, but subsequently induces changes (increase of tension) which cause blinding of the eye.

If the exudation into the posterior chamber is very great, it leads to adhesion of the posterior surface of the iris to the lens, not only at its pupillary margin but through its whole extent; there is produced adhesion of the whole surface of the iris, or *total posterior synechia* (Fig. 60). Such an excess of exudation, however, does not occur in simple

iritis, but only when there is a simultaneous cyclitis, and it will therefore be described more particularly under the latter head.

68. Symptoms of Cyclitis.—Exudation from the ciliary body, apart from the infiltration of the tissue itself, takes place into the anterior chamber, the posterior chamber, and the vitreous:

1. The exudate produced by the ciliary body can get into the *anterior chamber* in two ways: either directly, in case there is implication of the most anterior portion of the ciliary body—i. e., that covered by the ligamentum pectinatum and lying at the confines of the anterior chamber; or indirectly, from the exudate being deposited first in the posterior chamber and then carried along with the aqueous through the pupil into the anterior chamber.

The exudates which are most characteristic of cyclitis are the *precipitates* upon the posterior surface of the cornea. These are small dots, no bigger than a pin's head, of a light gray or brownish color, which lie upon the posterior corneal surface (*p*, Fig. 59, and *P*, Fig. 61). They were formerly thought to be located in the cornea itself; but if by puncturing the cornea the aqueous is allowed to escape, some of the deposits may be seen to disappear too, being swept away with the aqueous—a proof that they simply lie upon the posterior surface of the cornea. If the deposits are large, but few of them are generally present, and they are then commonly scattered irregularly over the cornea. The smaller the deposits, the more numerous they generally are. They then occupy the lower half of the cornea, in which they cover a surface having the shape of a triangle. The base of the triangle corresponds to the lower corneal margin, and its apex is directed upward toward the center of the cornea. It is frequently observed that the deposits diminish in size from the base toward the apex of the triangle.

The peculiar arrangement of the deposits is readily explained by their mode of origin. The deposits are conglomerations of cells, agglutinated into masses by means of fibrin (Fig. 61). At first they are suspended in the aqueous, and by the movements of the eye are thrown against the posterior surface of the cornea and adhere to it. In so doing they arrange themselves according to weight, the largest being lowest down. The triangular shape of the arrangement is a result of the movements of the eyeball, by which the deposits are cast upon the cornea. We have only to think of what happens when we throw sand through a wire screen or shake grain in a sieve. The little fragments of stone or of grain always form a pointed figure with the point, which contains the finest particles, running upward, while successively coarser particles follow in order below. The same is the case with the deposits. By their peculiar arrangement the deposits are generally easily distinguishable from macular opacities in the cornea itself (in keratitis punctata, see pp. 171, 179). Other distinguishing marks are the

clearer outline and frequently the brownish color of the deposits, which, moreover, do not lie at different depths like maculæ in the cornea itself, but lie all in the same plane—that is, on the posterior surface of the cornea.

That the deposits actually originate in the ciliary body and not in the iris is proved by the cases of pure cyclitis, in which deposits are present in abundance, although all symptoms of inflammation on the part of the iris are wanting.

The exudate from the ciliary body, deposited in the anterior chamber, may also appear there under the form of hypopyon, just as in



FIG. 60.—TOTAL POSTERIOR SYNECHIA. VERTICAL SECTION THROUGH THE EYE. MAGNIFIED 5×1.

The iris is adherent by its posterior surface to the anterior capsule of the lens and also to the anterior surface of the ciliary body. The posterior chamber consequently is obliterated and the anterior chamber deepened at its periphery, *b*; at this spot the iris is strongly retracted and at the same time is here the most thinned through atrophy. The exudate connecting the iris with the lens also stretches as a thin membrane, *p*, across the pupil. The hull of exudate, *s*, springing from the ciliary body, envelops the posterior surface of the lens and by its shrinking draws the ciliary processes toward the center. As a result of this, a separation of the ciliary body, *c*, from its bed has already taken place below, and in the intermediate space are seen the disjoined lamellæ of the suprachoroid membrane, *a*. The pigment-epithelium, *f*, of the ciliary processes has undergone proliferation. At the lower part of the cornea there is a zonular opacity, *g*. The lens is swollen and is opaque throughout; there is no hard, undisintegrated nucleus (i. e., it is a soft cataract).

iritis. But what particularly characterizes cyclitis are the gray or grayish exudates that develop in many cases and which appear to grow out in the form of spongy masses from the sinus of the chamber, and that not merely below, but also from other directions.

2. *Exudation into the posterior chamber*, if extensive, leads to the adhesion of the whole posterior surface of the iris to the anterior capsule of the lens (*total posterior synechia*, Fig. 60). We recognize the presence of the latter chiefly from the altered form of the anterior chamber. The exudate, as it shrinks, draws the iris everywhere up to the anterior surface of the lens, so that the posterior chamber is completely obliterated. The anterior chamber is hence proportionately deeper, and most of all at the periphery, where the iris is displaced

farthest backward (*b*, Fig. 60). Great recession of the root of the iris is hence a sign of cyclitis.

3. Exudation *into the vitreous* appears under the form of opacities of the vitreous, which can be made out with the ophthalmoscope if the condition of the refracting media permits. Moreover, they manifest themselves by a corresponding diminution of the vision. In severe cases, an exudation of large size exists in the anterior division of the vitreous (*s*, Fig. 60), and under favorable circumstances can be seen with lateral illumination as a gray mass behind the lens. The sight is thus almost completely abolished, and atrophy of the whole eye is subsequently produced by the shrinking of this mass of exudation.

The *tension* of the eye, which in iritis is usually unchanged, often shows an alteration in cyclitis. It is not infrequently found to be elevated in the beginning of the cyclitis, in consequence of the increase in the amount of matter contained in the eyeball due to the deposition of the exudate; indeed, such a great elevation of tension may be developed that blindness is produced by it. In the later stages of cyclitis, on the contrary, diminution of the intra-ocular pressure is more frequent, and is the result of the shrinking of the exudate while in process of organization.

Both iritis and cyclitis are associated with *symptoms of inflammatory irritation*, consisting of ciliary injection, photophobia, lachrymation, and pain. Their intensity is regulated by the greater or less acuteness with which the case runs its course. Chronic cases occur in which inflammatory symptoms are wanting altogether, so that the eye is at no time reddened or painful; on the other hand, there are cases of irido-cyclitis in which the pain reaches an absolutely intolerable pitch and is associated with vomiting and a febrile movement. Sometimes the pain sets in with special violence at night (particularly in syphilitic iritis and irido-cyclitis).

Vision is always diminished through turbidity of the aqueous or through exudation in the region of the pupil or in the cavity of the vitreous.

Differential Diagnosis between Iritis and Cyclitis.—We speak of *iritis* if the symptoms enumerated above are present, and there is no direct proof of the participation of the ciliary body in the inflammation. That the ciliary body is pathologically altered in most cases of apparently simple iritis is put beyond a doubt by anatomical investigations. But, since we can not see the ciliary body directly, slight changes in it escape diagnosis. We hence make the diagnosis of *irido-cyclitis* only in those cases in which in addition to the symptoms of iritis positive evidences of involvement of the ciliary body are also present. This is the case—

1. When the inflammatory symptoms reach a considerable pitch,

and especially if œdema of the upper lid is associated with them—a thing which does not occur in simple iritis.

2. When the eyeball is painful to the touch in the ciliary region.

3. When deposits are present upon the cornea, or when the marked retraction of the periphery of the iris leads us to infer the existence of a total posterior synechia.

4. When the disturbance of vision is more considerable than one would expect from the opacities within the confines of the anterior chamber. We are then justified in inferring the existence of opacities in the vitreous causing diminution of vision.

5. If the tension is altered—either elevated or lowered.

The participation of the ciliary body in the inflammation of the iris makes the disease a far more serious one and renders the prognosis worse. Not only is the inflammation more violent, but it induces changes which are much more difficult to remedy. The exudates, such as posterior synechiæ and pupillary membranes, produced by iritis in the confines of the anterior chamber, may be attacked successfully by operative procedures. But the exudates left by cyclitis in the vitreous, so far as they do not become absorbed spontaneously, are in no way susceptible of removal. Severe cyclitis leads to destruction of the eye (atrophy of the eyeball)—a thing that never occurs with iritis alone.

Simple cyclitis * without iritis occurs but seldom, and that only in the chronic form. The inflammatory symptoms are slight or absent, the iris is of normal appearance, and the pupil is generally somewhat dilated. The chief symptoms are the presence of deposits upon the cornea and opacities in the vitreous.

Inexperienced physicians often fail to recognize slight cases of iritis, considering it as catarrh on account of the injection of the eyeball that coexists with it. The treatment then employed, such as the application of the silver-nitrate solution or the instillation of irritating collyria, commonly aggravates the iritis. We can avoid this mistake if in every case we pay careful attention to any discoloration that there may be in the iris (particularly by comparing it with that of the other eye), and also to the dimensions of the pupil, which in an eye with iritis is contracted. Moreover, a slight turbidity of the aqueous can be recognized, even in the early stages, from the fact that the pupil has not the same pure black look as in the other eye. On the other hand, the mistake is often made of considering an inflammatory glaucoma as an iritis on account of the ciliary injection and the discoloration of the iris—a mistake which is the more disastrous because in glaucoma great harm is done by the instillation of atropine. Here, besides the testing of the tension, our chief means of guarding against mistakes is the examination of the pupil, which in iritis is always more contracted, in glaucoma always more dilated, than usual.

A peculiar appearance is furnished by the presence of a pretty large *fibrinous* exudate in the anterior chamber, such as is at times observed in every sort

* The serous iritis of authors.

of acute iritis. If, for example, much fibrin is deposited in the aqueous, it may become coagulated into a uniformly gray, translucent mass (hence the name gelatinous exudate and also lenticular exudate, because with its rounded edges it sometimes looks like a half-transparent lens that has been dislocated into the anterior chamber). The exudate speedily shrinks, since the fibrin in contracting expels the liquid from its meshes (for which reason we also speak of it as a spongy exudate). After a few days the exudate has either completely disappeared or it has been reduced to a thin pellicle lying in the pupil and often still connected with the pupillary margin by one or two slender filaments.

It happens sometimes that posterior synechiæ develop in the presence of a dilated, instead of contracted, pupil ; as, for example, when they form in an eye under the influence of atropine. In this case the margin of the pupil becomes adherent to the capsule of the lens at some peripherally located spot, so that afterward, when the pupil assumes its mean width, the synechia is marked, not by a projecting process, but by a re-entrant angle.

For the diagnosis of *seclusio pupillæ*, the employment of atropine is indispensable. It often happens that the pupillary margin is thought to be adherent to the capsule all round, when, nevertheless, upon the employment of atropine it retracts at one small spot. At this unattached portion, which is most frequently situated above, there is thus formed a curved or horseshoe-shaped indentation of the pupillary margin. Similarly we may infer the existence of a small opening if, after the case has been under observation for a long time, no protrusion of the iris takes place, since in true seclusio pupillæ such protrusion never fails to appear. Of course, we must be able to exclude the existence of a total posterior synechia, in which case evidently protrusion of the iris could not take place.

Seclusio pupillæ appears to occur frequently without there being any simultaneous formation of membrane in the pupil (occlusio pupillæ). This, however, is only apparent, as a rule. Upon careful examination we usually notice that the gray fringe of exudate which runs along the adherent pupillary margin projects far into the pupil, becoming gradually thinner as it does so, so that perhaps only the center of the pupil appears to be quite free. And yet if, after performing an iridectomy, we compare the pupil with the pure black coloboma, we can almost always convince ourselves that really no part of the pupil is quite free from a membrane. Much more frequently than seclusion without occlusion, the converse—i. e., occlusion without seclusion—occurs. That is, there is a membrane in the pupil, and sometimes quite a thick one, which is not connected with the pupillary margin all round, but only at separate spots.

The presence of a well-marked reaction of the pupil to light is not altogether conclusive evidence against the existence of seclusio pupillæ. If the tissue of the iris is not yet atrophic, and a fair perception of light at the same time exists, the anterior layers of the iris, when the illumination is varied, move quite perceptibly over the fixed posterior pigment-layer.

The *deposits* upon the posterior surface of the cornea are easily overlooked, because they are often so excessively minute. We should, therefore, in every case in which there is a suspicion of the existence of an affection of the uveal tract, look for them with a strong magnifying-glass. They are found not only in affections of the ciliary body but sometimes also in those of the most anterior sections of the chorioid. The following is an interesting case of this sort: A girl, twenty two years of age, was taken sick with varicella, the pocks of

which covered her entire body in great numbers. While still confined to her bed, she noticed a redness in her left eye. This passed off in a few days, but the sight of this eye had by that time become obscured. Some days after, I found the eye perfectly free from discoloration and the lower half of the cornea exhibiting a very faint opacity. Under a magnifying-glass this opacity resolved itself into innumerable, very minute deposits. The pupil was rather more dilated than in the sound eye, and readily permitted examination with the ophthalmoscope, which showed a slight opacity of the vitreous in its anterior section, and in the extreme periphery of the portion of the fundus visible with the ophthalmoscope a white spot of exudation of about the size of the optic disk. Subsequently the vitreous cleared up; the spot of exudation, which in the beginning had quite indistinct outlines, became more sharply circumscribed and was gradually transformed into a pigmented area with an atrophic white spot in its center. This exudate in the chorioid was evidently the real focus of inflammation from which the opacities in the vitreous and the deposits had started. The disease itself must be regarded as a very light case of the metastatic chorioiditis which is sometimes observed in consequence of infectious diseases. I have quite frequently found minute deposits in eyes in which a soft cataract had been operated upon by discission, and was consequently swelling up and undergoing absorption at the time. Other evidences of inflammation were wanting, and the subsequent course in these cases furthermore was favorable.

In severe cases of irido-cyclitis (especially of sympathetic origin) blanching of the cilia on the lids of the affected eye is sometimes observed.

Results of Anatomical Examination in Irido-cyclitis.—Exudation *into the tissue of the iris* is characterized by the presence of numerous round cells in the latter, the quantity of which increases with the intensity of the inflammation. Often they are not distributed everywhere alike, but collect in certain spots, especially along the vessels, so that circumscribed nodules of exudation are produced. This state of things is most strongly marked in syphilitic inflammation, in which the nodules are often so large that they can be seen with the naked eye (papulæ iridis). Within the ciliary body the cellular infiltration is much more profuse in the vascular ciliary processes than in the ciliary muscle.

The *free exudate*, deposited in the anterior chamber, in part sinks to the bottom of the chamber and forms a hypopyon, in part attaches itself to the walls of the chamber—that is, to the cornea, the iris, and the capsule of the lens (Fig. 36, *b*, *c*, *d*, and *e*). The thin coating of exudate, which covers the posterior surface of the cornea (Fig. 61, *b* and *f*), causes the latter in recent cases of iritis to appear slightly and uniformly clouded. It generally disappears with the subsidence of the inflammation; only in rare cases is the layer of exudation so considerable (especially in the lower half of the cornea) that it afterward becomes organized and leads to the production of a lasting opacity of the cornea.

The *deposits* are conglomerations of round cells containing interspersed pigment-granules (*P*, Fig. 61). They lie upon the endothelium of Descemet's membrane, which, at first, is perfectly normal and not till afterward becomes destroyed beneath the aggregations formed by the cells of the deposit (*e*, Fig. 61). The endothelium, therefore, has no more to do with taking an active part in the formation of the deposit than any other part of the cornea. Accordingly, the terms formerly employed to designate the deposits, such as keratitis punctata,

descemetitis, aquacapsulitis, hydromeningitis,* which impute their place of origin to the cornea and more particularly to Descemet's membrane, are inapplicable. In exceptional cases scattered deposits are also found in the pupillary area, both upon the iris and upon the anterior capsule of the lens. After lasting for some time the cells of the deposit undergo fatty degeneration and



FIG. 61.—DEPOSIT UPON THE POSTERIOR SURFACE OF THE CORNEA. MAGNIFIED 140×1.

The posterior surface of the cornea, *C*, is covered by Descemet's membrane, *D*, and the endothelium, *e*. The latter, which as a whole is of normal character, is wanting at the spot where the deposit, *P*, is situated. This deposit forms an accumulation of cells with interspersed pigment-granules which are partly free and partly inclosed in the round cells. In the place where no deposits are situated the posterior surface of the cornea is covered by a layer of exudation consisting of two strata, an anterior one, *b*, composed of round cells, and a posterior one, *f*, formed of coagulated fibrin.

are absorbed, while the pigment-granules are left behind. Hence many deposits are seen to take on little by little a darker color until at length nothing but minute black specks are left at the place where they were situated.

The exudate which is poured out upon the anterior surface of the iris displaces the endothelial membrane present there. The fate of this exudate depends upon its character. In the lighter cases, in which it consists chiefly of coagulated fibrin with only a few round cells, it disappears completely by resorption. In severe cases, the exudate is richer in cells and subsequently becomes organized. We then find the iris atrophic and covered by a thin membrane of connective tissue. The same is true of the exudation deposited upon the anterior capsule in the pupillary area, and of the exudates in the posterior chamber and in the cavity of the vitreous; in the light cases they are absorbed, in the severe ones they become organized into membranes, as will be more precisely described in treating of the different modes of termination of irido-cyclitis.

An *anatomical classification* of irido-cyclitis has been based upon the varying anatomical characters of the exudate. In general, the exudates which are very poor in cells and are incapable of undergoing organization are called serous, those which are rich in cells and lead to the formation of adhesions and of membranes are called plastic. Purulent exudates are those which contain very numerous cells with a fluid intercellular substance. Nevertheless, to classify irido-cyclitis, upon the basis of differences of this sort, into a serous, a plastic, and a purulent variety, is a procedure that has its difficulties and can not be strictly carried out. In the first place, several kinds of exudation are often present at the same time; for instance, a purulent exudation constituting a hypopyon, and a plastic exudation forming synechiæ and pupillary membranes. In the second place, the sort of exudation present is by no means indicative of the severity of the case and of its clinical course. Purulent iritis—i. e., iritis

* Descemet's membrane was called capsula aquæ, or, in Greek, *hydromeninx*, because it was supposed to secrete the aqueous humor.

with hypopyon—often runs a very mild course and is less to be dreaded than a plastic iritis which leaves adhesions after it. Purulent cyclitis, on the other hand, in which the purulent exudate is deposited in the vitreous, almost always entails loss of the eyesight. A term to be altogether rejected is that of serous iritis, which is used by authors for those cases in which deposits are present while synechiæ are absent. The deposits, however, are certainly not serous exudates, and, any way, these cases are to be looked upon as ones of cyclitis, not of iritis. Because of all these reasons, it seems to me better to classify irido-cyclitis, not according to the kind of exudation, but according to the etiology, as will be done later on.

In irido-cyclitis, the microscope generally establishes the fact of a participation of the deep parts of the eye in the inflammation. The chorioid suffers the most injury, so that, when evident signs of its implication are present, we speak of irido-chorioiditis. But the retina too and the optic disk are almost never free from pathological changes in irido-cyclitis, although these changes are often too insignificant to be demonstrable by clinical examination alone.

69. Course and Termination of Iritis and Cyclitis.—With regard to the *course*, a distinction is made between acute and chronic cases. The former are associated with marked inflammatory symptoms, but run a quicker course. But even in the acute cases—if we except the very lightest ones—it takes four months or more before the inflammation entirely subsides. The first signs of a change for the better in the inflammation are the decrease of the injection and of the pain, and especially the prompt action of atropine, while at the acme of the inflammation the pupil is so spasmodically contracted that atropine has little or no effect.

Chronic cases run their course with few or absolutely no symptoms of inflammation. The patients, in the latter case, become aware of the existence of their trouble only at a comparatively late period, and then only from the increasing disturbance of vision. Chronic iritis (irido-cyclitis and irido-chorioiditis) is not infrequently protracted over a course of years.

Inflammations of the iris and of the ciliary body often show a great tendency to *relapse*. Formerly the chief cause for the recurrence of the inflammation was supposed to lie in the posterior synechiæ left by the first attack of iritis. It was believed that in the constant movement of the pupil traction was continually made upon the iris at the places of adhesion, and thus a new source of inflammatory irritation was provided. But it has been demonstrated that relapses are to be apprehended only in certain cases of posterior synechiæ. If, for instance, anybody has had an ulcer of the cornea, and, as a result of it, an iritis from which there are some synechiæ remaining, he need never fear having a relapse of his iritis. But another man who has got synechiæ as the result of an iritis with a constitutional basis (e. g., a syphilitic or rheumatic iritis) can very readily have recurrences. We hence conclude that what produces the recurrences is not the synechiæ, but the

continuance of the same constitutional cause that was accountable for the first attack of iritis; and, as a matter of fact, we sometimes see a syphilitic patient suffering from a recurrence of his iritis even when the first attack has got well without leaving any synechiæ; or we see a recurrence affecting, not the eye that was previously diseased, but the other eye which has hitherto been sound. The recognition of the fact that one or two synechiæ are in themselves of no great significance has had an important practical result; the numerous operative methods designed for the division of synechiæ have now been entirely given up.

Recurrences of iritis are often less severe than the primary inflammation; but, as they are pretty frequently repeated, and as they leave a new exudate after them each time, they ultimately lead to serious changes, such as seclusio and occlusio pupillæ.

The *outcome* of inflammation may be a perfect cure in light cases. The synechiæ rupture, leaving behind bits of pigment attached to the anterior capsule, which are unproductive of injury to the eye. The hypopyon disappears by resorption. The deposits generally persist for a long time (for months), until they also are removed by resorption. In many cases they leave at the spot where they were situated a permanent opacity of the cornea in the shape of a gray speck, or the pigment that is contained in them remains permanently as a black dot. Slight opacities of the vitreous may also disappear completely by resorption.

In most cases, however, permanent *sequelæ* remain after iritis and cyclitis. These are—

1. *Atrophy of the Iris.*—This rarely develops after a single attack of acute iritis; generally it is the result of repeated recurrences or of chronic inflammation. It is characterized by a bleached-out, gray, or grayish-brown aspect of the iris (resembling gray felt or blotting-paper); the delicate markings of the anterior surface have disappeared, and in their stead dilated vessels can often be recognized as reddish spots upon the iris. The pupillary margin is thinned down, often looking as if it had been frayed out; the reaction of the iris is lost. The great friability of the atrophic iris often renders the correct performance of iridectomy impossible.

The most frequent and important sequelæ are the exudates and adhesions which remain after nearly every case of iritis or irido-cyclitis. Among these are—

2. *Posterior Synechiæ.*—These, if only a few are present, cause no special injury to the eye, and also produce little or no impairment of sight. Very much worse is the annular posterior synechia or *seclusio pupillæ*. By this the communication between the anterior and the posterior chamber is obliterated. The aqueous secreted by the ciliary processes can no longer pass through the pupil into the anterior chamber; it hence collects in the posterior chamber, pressing the iris forward (Fig. 59). A nodulated protrusion of the iris is thus produced,

which finally reaches as far forward as the cornea, while the pupil is represented by a crater-shaped retraction of the pupillary margin which is attached to the lens capsule. In consequence of being so greatly stretched, the iris becomes atrophic. When this condition has lasted a certain time, elevation of the intra-ocular pressure (secondary glaucoma; see § 87) is added. The increased hardness of the eye can be established by palpation; the anterior ciliary veins are dilated, the cornea is dull and less sensitive to touch, the sight fails, with a decrease in the field of vision starting from the nasal side, until at length the perception of light is entirely abolished. Then the formation of scleral ectasiæ takes place in the blinded eye in the shape of anterior and equatorial staphylomata of the sclera. Seclusio pupillæ, accordingly, if it is not remedied in time, infallibly leads to blindness.

3. *Pupillary Membrane* (*occlusio pupillæ*).—This causes an interference with vision, the degree of which depends upon the thickness of the membrane.

4. *Exudates behind the Iris.*—These lie either between the iris and the lens (total posterior synechia) or between the ciliary body and the lens and upon the posterior surface of the latter. In severe cases they form a coherent fibrous mass which completely envelops the lens, and which, on account of its solidity, is called the cyclitic shell (*s*, Fig. 60). This has a great tendency to shrink. In total posterior synechia there is evidently no nodulated protrusion of the iris—on the contrary, the anterior chamber in the beginning is unusually deep at the periphery owing to the retraction of the iris (*b*, Fig. 60). Afterward, when atrophy of the eye sets in, the anterior chamber often becomes shallower again, because iris and lens together are pushed forward. The exudates which lie behind the lens in the vitreous (*c*, Fig. 62) cause by their contraction a diminution of volume of the vitreous; the eyeball then becomes softer. The shrinking of the vitreous (*g*, Fig. 62) results in detachment of the retina (*r*) from the chorioid; in part also this detachment is produced by direct traction, since the shell of cyclitic membranes as it shrinks attaches itself to the inner surface of the retina and draws it out of its bed. In consequence of the detachment of the retina, complete blindness ensues. This state of things, consisting of diminished tension of the eyeball, with decrease in its size and with complete blindness, is known as *atrophy of the eyeball.* An atrophic eyeball presents the following picture: The whole eye is smaller and of slightly quadrangular shape. The four recti muscles, stretching across the equator of the eyeball, press the sclera in somewhat at this spot, and hence produce flattening at the four sides. With the higher degrees of atrophy quite deep furrows are formed, so that the eyeball has the form of a bale of goods grooved by the cord with which it is tied. The cornea is smaller, often opaque and flattened; at other times, again, transparent, but abnormally protuberant or thrown into

folds. The atrophic iris is either pressed quite against the posterior surface of the cornea, or an anterior chamber still exists. In the latter case, we find the chamber bounded behind by a firm diaphragm in which the iris, which is imbedded in the shell of exudate, is often but indistinctly recognizable. If the pupil is still distinguishable, a mem-

FIG. 62.—ATROPHY OF THE EYEBALL. IN PART AFTER WEDL-BOCK.

The eye is smaller and of irregular shape, chiefly from the folding of the sclera behind the points of attachment of the ocular muscles, the rectus internus, *ri*, and the rectus externus, *re*. The cornea, *C*, is diminished in size, flattened, and folded especially on its posterior surface. At its inner border it bears the depressed cicatrix, *N*, which was produced by the injury. The anterior chamber is shallow; the iris, *i*, is thickened and forms an unbroken surface, because the pupil is closed by exudate. Behind the iris lies the shrunken lens, *l*, and behind this is the great shell of cyclitic membrane, *c*, the shrinking of which is the cause of the atrophy of the eyeball. By reason of this shrinking, the ciliary processes, the pigment-layer of which has markedly proliferated, are drawn in toward the center, and, together with the adjacent chorioid, *ch*, are detached from the sclera; between the two structures are seen the disjoined lamellæ of the suprachorioid membrane, *a*. The retina, *r*, is detached and folded in the form of a funnel, which incloses the remains of the degenerated vitreous. The subretinal space, *s*, is filled with a fluid rich in albumin. The optic nerve, *o*, is thinner than usual and atrophic.

brane and the opaque lens are found in it. The eye is softer, and is often sensitive to the touch. In the later stages markedly hard spots (ossified exudates) may sometimes be felt through the sclera.

Atrophy develops gradually through a course of months and years. The inflammation and the pain, which have been present for a long time, disappear when the atrophy is complete. But even then secondary attacks of pain occur, especially if the eye harbors a foreign body, or if ossification of the exudate takes place.

5. *Opacity of the Lens.*—This develops in consequence of the disturbed nutrition of the lens. If merely a few synechiæ are present, it is rarely observed; on the other hand, it is observed with proportionately great regularity when seclusio pupillæ has existed for a long time, and particularly so in those severe cases in which the lens is completely swathed in cyclitic exudates. Such a cataract is denoted by the name

of cataracta complicata or cataracta accreta (= grown fast to—i. e., grown fast to the iris). In atrophic eyeballs the lens is always opaque, and generally shrunken as well.

The *protrusion of the iris* does not take place uniformly, but with the formation of projecting prominences separated by constrictions. The latter represent the more resistant, radial fibers which do not give way before the pressure of the aqueous until afterward. The condition in which the iris is found protruding in a greater part of its circumference, while one sector of it remains in its normal situation, is generally referable to the fact that at this spot an adhesion of the surface of the iris to the lens exists, preventing its protrusion. It would, therefore, be a mistake to select just this spot for performing an iridectomy, although on other accounts it would seem to be very suitable for such a purpose, because of the greater depth of the chamber there. If the iris has been pushed forward as far as the cornea, it may become agglutinated to the latter in places, and in this way anterior synechiæ may be produced without there having ever been a perforation of the cornea (see page 195).

Atrophy of the iris can progress to such an extent that the iris becomes transparent, or even so far that complete gaps form in it. *A spontaneous formation of gaps* in the iris is also sometimes observed when occlusio pupillæ makes its appearance in early childhood. The iris is then fixed not only at its ciliary, but also at its pupillary margin, being attached to the membrane that exists in the pupil. As the eye grows, the iris is stretched constantly more and more between its two points of attachment until atrophy and finally dehiscence in spots occur. In this way, through the formation of an opening, the sight may be spontaneously restored. In like fashion, the formation of gaps (or even the separation of the iris from the ciliary margin) may take place in cases in which the iris was attached to a cicatrix of the cornea in childhood.

It should be remembered that seclusio and occlusio pupillæ develop not only as the result of irido-cyclitis but also in connection with the larger perforating ulcers of the cornea if the margin of the pupil is involved through its whole extent in the cicatrix. In this case, too, the usual consequences of seclusio pupillæ make their appearance; the iris is pressed forward as far as the cornea, and an increase in tension takes place, as is so often observed in staphyloma of the cornea (see page 205).

The *cornea* in irido-cyclitis suffers harm through the deeply situated infiltrates that may form in it (see page 184), through the deposition of exudate (deposits, hypopyon), or through the contact of the iris, which when lasting a long time produces corneal opacity (page 183). In the stage of atrophy of the eyeball a zonular opacity frequently forms upon the cornea. Keratitis bullosa and vesiculosa also often make their appearance in eyes which are blinded by irido-cyclitis.

The *anatomical changes*, after an irido-cyclitis has run its course, manifest themselves under microscopical examination as follows: The atrophic iris is thinner than usual, and consists chiefly of fibrillary connective tissue. The cells of the stroma with their slender branches have been transformed in great part into coarse, round cells filled with pigment; masses of pigment also are often found lying free in the tissue. The vessels are in part obliterated and the nerve-trunks also have disappeared. The sphincter pupillæ and the retinal pigments are the parts which remain the longest. The ciliary body, including

both the ciliary muscle and the ciliary processes (Fig. 59, *c*), is aso found to be atrophic in old cases. The two innermost layers of the ciliary processes, however, often undergo proliferation, the two strata of cells of the pars ciliaris retinæ growing extensively into the cyclitic exudates and taking part in their formation (*f*, Fig. 60). By the traction which the masses of exudate, as they shrink, exert upon the ciliary processes, the latter are greatly elongated, so that their apices project well toward their posterior pole of the lens; when the traction is still greater, the entire ciliary body is pulled out of its bed (*c*, Fig. 60). This traction upon the ciliary body is one of the causes of the continuous or constantly recurring sense of pain, which exists in so many cases of old irido-cyclitis and sets the patients almost frantic; and it may also give rise to sympathetic disease of the other eye. The exudates themselves consist in the recent state of round cells and of an interstitial substance of fibrin, in varying proportions. The exudates afterward become organized into false membranes, the round cells turning into spindle cells and ultimately into connective-tissue fibers. In this way a very tough tissue is produced, which grates when cut through, and which rightly bears the name of shell ("Schwarte"). On account of this tenacity it puts great difficulties in the way of any attempts at the formation of a pupil. In cases in which the irido-cyclitis has been produced by a foreign body, the latter not infrequently is found imbedded in this shell of exudate. Besides the above-mentioned tissue constituents there are often found in the exudation-membranes new-formed blood-vessels which have developed from the neighboring organs, the iris and ciliary body, and also pigment which takes its origin from the retinal pigment-layer of the iris and of the ciliary body. The lens which is inclosed in the exudation-membranes forms with these a rigid diaphragm separating the anterior from the posterior section of the eyeball. The lens becomes opaque and disintegrates, its capsule ruptures, and masses of exudate penetrate into the capsular sac. If these masses afterward become ossified, the picture—to be sure only an apparent one—of ossification of the lens may be developed.

By the subsequent shrinking of the exudation-membranes softening and diminution in size of the eyeball—*atrophy of the eyeball*—are produced. The anterior chamber becomes narrower, because the shell of exudate which is stretched between the ciliary processes and arches over the posterior surface of the lens (*s*, Fig. 60), as it shortens tends to become approximated to a straight line (*c*, Fig. 61), and in so doing presses the lens forward. In other cases, on the contrary, the cicatricial traction may manifest itself more in a backward direction, so that the anterior chamber becomes deeper. Through the same force of traction cicatrices in the cornea or in the sclera, with which the exudates are connected, are drawn steadily inward (*N*, Fig. 62); hence the depression of cicatrices after injuries or operations is always to be considered a bad omen for the course of the disease. The traction of the exudates furthermore causes detachment of the retina (*r*, Fig. 62) and often, too, detachment of the ciliary processes and even of the chorioid (*ch*). The cavity of the vitreous is reduced to a small space (*g*) lying directly behind the lens. The space beneath the retina (*s*) and also beneath the chorioid, wherever detached (*a*), is filled with an albuminous transudation and often also contains extravasated blood. In advanced atrophy, the sclera (*S*) is thrown into folds and is thickened in spots. The shell of exudate not infrequently becomes ossified later on and, if the chorioid has participated in the process of exudation,

the whole back part of the eye may be occupied by a shell of bone. The optic nerve is atrophied to a thin strand of connective tissue.

70. Etiology of Iritis and Cyclitis.—Iritis and cyclitis are either primary or secondary in their development. In the first case, the original site of the disease is in the iris or ciliary body itself; in the second case, there is an affection of neighboring parts, which has been transmitted to the iris and the ciliary body (e. g., in iritis with abscess of the cornea). Primary inflammation of the iris and ciliary body as well as of the uvea in general is caused in the majority of cases by a deep-seated general disease, such as syphilis, scrofula, etc.; and many of those cases which at present we still regard as purely local inflammations and which, because their origin is unknown to us, we designate as idiopathic, certainly belong in the same category. In proportion as our knowledge of the interdependence of morbid phenomena increases, the group of so-called idiopathic inflammations of the uvea will melt away. Among the primary iritides the only ones of undoubtedly local nature are traumatic and sympathetic iritis.

We may, therefore, classify the inflammations of the iris and the ciliary body with reference to their etiology according to the subjoined scheme. In it, as well as in the subsequent description, the expression "iritis" stands for the sake of brevity as the representative of iritis, cyclitis, irido-cyclitis, and irido-chorioiditis—that is, for all inflammations which predominantly affect the anterior part of the uvea:

- A. Primary iritis.
  - Iritis in consequence of general diseases.
    1. Iritis syphilitica.
    2. Iritis scrofulosa.
    3. Iritis tuberculosa.
    4. Iritis rheumatica.
    5. Iritis gonorrhoica.
    6. Iritis in acute infectious diseases.
    7. Iritis diabetica.
  - Iritis as a local affection.
    8. Iritis idiopathica.
    9. Iritis traumatica.
    10. Iritis sympathica.
- B. Secondary iritis.

A. **Primary Iritis.**—1. *Syphilitic Iritis.*—Syphilis is by far the most frequent cause of iritis, since at least half of all the cases of iritis are referable to it. For the most part, it is *acquired* syphilis that we have to do with. The diagnosis of syphilitic iritis is very easy in those cases in which the characteristic formation of nodules (iritis papulosa) is present. The nodules have a yellowish-red color, are of the size of a pin's head or larger, and are situated either on the ciliary or the pupillary margin of the iris, but never between the two zones in the midbreadth of the iris. The nodules afterward disappear again by resorption without any purulent disintegration taking place. At the places where they were situated, broad and solid synechiæ are left, and there

is often also a circumscribed atrophy of the tissue of the iris. At other times no distinct nodules are found, but several portions of the pupillary margin are greatly swollen, or at all events there are unusually broad synechiæ which do not yield to atropine (*b*, Fig. 58). Finally, in many cases iritis syphilitica presents absolutely no characteristic marks; the diagnosis, then, can be certainly established only through the demonstration of the existence of syphilis, or through the favorable action of antisyphilitic remedies.

Syphilitic iritis generally belongs to the secondary stage of syphilis. It makes its appearance soon after the first eruptions upon the skin (macular or papular), for which reason we may compare the nodules in the iris to papules or to condylomata, and may designate the iritis as iritis papulosa. In most cases, the time when the iritis first appears is comprised within the first year after the infection has taken place. More rarely the iritis breaks out in the later stages of syphilis, and is then not associated with the formation of nodules. In exceptional cases, however, nodules do show themselves in this late form also and they must then be regarded as gummata (iritis gummosa). These are observed both in the iris and the ciliary body. They may attain great dimensions, break through the envelopes of the eyeball, and bring about the destruction of the eye.

Iritis also occurs in consequence of *hereditary* syphilis, although by no means as frequently as after acquired syphilis. Parenchymatous keratitis, dependent upon hereditary syphilis, is often associated with iritis. Sometimes it happens that the iritis becomes, comparatively speaking, very conspicuous, while the keratitis attains but a slight degree of prominence; and there may even be iritis without any keratitis whatever. Iritis due to hereditary syphilis is a disease of childhood and youth, while iritis resulting from acquired syphilis is usually observed only in adults.

Syphilitic iritis is very frequently associated with diseases of the posterior section of the eye—that is, with inflammation of the chorioid, retina, and optic nerve. Moreover, it displays a great tendency to recur.

2. *Iritis scrofulosa.*—This bears in its appearance and course much resemblance to iritis due to hereditary syphilis. It is often marked by the presence of large, lardaceous-looking deposits or by lardaceous exudation masses, which appear to grow out from the sinus of the chamber. It is found in the ages of childhood and youth in scrofulous persons, and also in those suffering simply from anæmia.

3. *Iritis tuberculosa.*—See § 75, Tumors of the Iris.

4. *Iritis rheumatica.*—This occurs in persons who have been ill with articular rheumatism (arthritis rheumatica). It is the form of iritis which has the greatest tendency to recur. From the fact that in many cases the recurrences of the iritis coincide with recurrences of

the rheumatism (attacks of swelling in the individual joints), the connection between the two is demonstrated. Iritis also occurs as a result of arthritis deformans and arthritis urica [gout].

5. *Iritis gonorrhoica* develops in those cases in which gonorrhœa has given rise to a general infection. This latter runs a course similar to that of acute articular rheumatism. First the knee-joint is attacked by inflammation, which may afterward migrate to the other joints also; associated cardiac complications may even occur. This disease is known as gonorrhœal gout [rheumatism]. Iritis does not generally set in until after the outbreak of the arthritis and frequently attacks both eyes, as in fact is also the case with the other iritides caused by a general lesion. Just as the gonorrhœal lesion of the joints is very similar to articular rheumatism, so also gonorrhœal iritis resembles in external features the rheumatic variety. Like the latter, too, it has very frequent recurrences, with which is frequently associated a renewal of the discharge from the urethra or a return of swelling in the affected joints.

6. *Iritis in Acute Infectious Diseases.*—Among these relapsing fever is the chief one in which iritis forms a frequent complication. It is usually protracted in its course, but ultimately goes on to a cure. Iritis is observed, but far more rarely, in variola, typhus fever, pneumonia, etc.

7. *Iritis diabetica.*—This is often associated with copious exudation into the anterior chamber (hypopyon), but on the whole runs a favorable course (Leber).

71. 8. *Iritis idiopathica.*—Under this head are comprised those cases in which the inflammation apparently develops spontaneously in the iris, without its being possible to make out the presence of any local cause (traumatism, etc.), or if a constitutional affection. In many cases a cold is charged with being the cause of the iritis, but in most instances the cause remains obscure.

Acute idiopathic iritis is generally unilateral; it attacks none but adults, and those, in most cases, of the male sex. The iris of the adult man is much more prone to be inflamed than is the iris of the child. In childhood, therefore, iritis is rare anyway, and it does not occur at all as an idiopathic affection; on the contrary, if no local cause (traumatism, sympathetic ophthalmia, transmission from the neighboring parts) is present, the existence of a constitutional affection can always be demonstrated.

Chronic idiopathic iritis generally appears under the form of *iridochorioiditis chronica* (also called iritis serosa). This disease is associated with but very slight symptoms of inflammation; injection of the eyes and pain are present only now and then, and with but little intensity when they do exist; frequently the only complaint that the patients make at all is in regard to the steadily increasing disturbance of vis-

ion. Examination of the eye shows posterior synechiæ which slowly increase in numbers until finally seclusion of the pupil is developed. Almost always too there is a thin membrane present in the pupil. The iris becomes atrophic early, and afterward, when seclusion of the pupil develops, bulges forward in nodular projections. Hypopyon is never present, but instead there are very frequently fine deposits which point to the implication of the posterior division of the uvea, an implication which also manifests itself through the presence of opacities in the vitreous. As these opacities continually increase in number and the vitreous at the same time becomes liquefied, the latter is finally converted into an opaque, mucilaginous liquid. Subsequently opacity of the lens is added, and atrophy of the chorioid and retina sets in. The interference with vision in these eyes is, therefore, always much greater than the optical obstructions in the anterior division of the eye (deposits, membrane in the pupil) would lead one to expect. This disease, which really affects all parts of the eyeball, in most cases terminates in complete blindness. In consequence of the seclusio pupillæ, increase of tension sets in with blindness from excavation of the optic nerve; afterward the eyeball may become ectatic. In other cases, blindness takes place under the guise of a gradually developing atrophy of the eyeball; the eye becomes softer, and the retina undergoes total detachment.

Chronic irido-chorioiditis almost always attacks both eyes. It runs so slow a course that years pass before complete blindness makes its appearance. It is a disease of advanced age. and is one of the most frequent causes of incurable blindness in elderly people. The cause of it appears in many cases to be seated in bad nutritive conditions, or in early cessation of the menses; but very often cases occur in patients who, apart from their eye trouble, are perfectly healthy.

9. *Iritis traumatica.*—The causes of this are injuries of all kinds, especially if perforation of the eyeball has taken place, and particularly if a foreign body is left in the eye. Operations upon the eyeball are, of course, to be counted among the injuries, and of these those which are most dangerous with regard to iritis and irido-cyclitis are the ones which affect the vicinity of the ciliary body (cataract operations). Injuries are the most frequent cause of those severe cases of irido-cyclitis which terminate in atrophy of the eyeball.*

With traumatic iritis and irido-cyclitis in the wider sense of an inflammation produced by direct injury to the iris, may be also enumerated the following cases: Iritis frequently develops when, after opening the lens-capsule, the masses of lens matter as they swell come into direct contact with the iris and press against it. The same is the case when there is pressure made upon the iris by a lens which is obliquely placed or completely dislocated. Finally, there might also be adduced

* For further particulars see page 219.

in this connection those cases in which an intra-ocular tumor or cysticercus in a certain stage of development sets up a violent irido-cyclitis.

The exciting cause in cases of traumatic iritis of the sort just adduced may be of three kinds: either mechanical injury (traction, contusion), chemical irritation (e. g., in the case of contact with swollen portions of the lens or in the case of a cysticercus); or, finally, infection from without. The last-named cause is without doubt the most frequent.

10. *Irido-cyclitis sympathica.*—When inflammation is carried from an eye suffering with irido-cyclitis over to the other side and attacks the other eye, which has hitherto been sound, the disease produced in the latter is designated by the name of sympathetic inflammation. This inflammation, like the primary one, makes its appearance under the guise of an irido-cyclitis.

In the majority of cases iritis sympathica is preceded by a *prodromal stage.* The patient notices that during the performance of fine work he is suddenly obliged to stop because the work grows indistinct before his eyes; after a period of rest he is again able to continue his work. This interference with vision is caused by a weakness of the accommodation. Another symptom of the prodromal stage is sensitiveness to light, and also, though not often, violent pain, the latter appearing sometimes at a portion of the eye which is symmetrically placed with reference to the diseased portion of the other eye. These symptoms are also denoted by the name *sympathetic irritation.* They may, in rare cases, exist for years without inflammation supervening. In most cases, however, after a short time (from a few days to a few weeks) they pass over into manifest inflammation.

Sympathetic inflammation declares itself by a development of the objective symptoms of irido-cyclitis together with an increase of the subjective troubles just described. Ciliary injection, contraction of the pupil, discoloration of the iris, and the formation of synechiæ are found. Deposits are almost never wanting, while, on the other hand, hypopyon is not ordinarily present; minute opacities show themselves in the vitreous. These changes sometimes set in insidiously, sometimes suddenly with great photophobia and considerable pain. In the severest cases the very first attack of inflammation induces annular or total posterior synechia and occlusion of the pupil; in less severe cases it is possible, with suitable treatment, to effect after many weeks the disappearance of the inflammation, although a number of synechiæ are left behind. Unfortunately, a recurrence of the inflammation occurs almost without exception after an interval during which the cure is apparently complete. By reason of this and subsequent recurrences the eye at length is destroyed, either as the result of increase of tension (due to seclusio pupillæ) or of a slowly developing atrophy. Those cases are

to be classed as the exceptions which run so favorable a course that the patient gets off with a single attack of inflammation, and retains an eye with serviceable sight. Since the severe cases are by far the most frequent, sympathetic irido-cyclitis must be regarded as one of the most serious forms of inflammation of the eye, and as one which almost always terminates in blindness.

The affection of the first eye, which gives rise to a sympathetic inflammation, is always an irido-cyclitis, and is, in fact, almost without exception, an irido-cyclitis traumatica, due to a penetrating injury of the eyeball. All cases of traumatic irido-cyclitis are not equally fraught with peril for the second eye. To be regarded as particularly dangerous are: (1) Those cases in which the injury has affected the region of the ciliary body, and particularly if it has left the iris or the ciliary body incarcerated in the cicatrix. For this reason, unsuccessful cases of Graefe's cataract operation have become a frequent cause of sympathetic inflammation. (2) Cases in which a foreign body has been left in the eye.

The *point of time* at which the greatest danger of the transmission of the inflammation exists is when the irido-cyclitis in the injured eye is at its height. Hence sympathetic inflammation makes its appearance, in most cases, from four to eight weeks after the injury to the first eye has taken place. Later than this, when the traumatic irido-cyclitis has subsided and the eye has fallen a prey to atrophy, there need be generally no fear of sympathetic inflammation so long as the atrophic eye is free from inflammation and is not painful, either spontaneously or to the touch. The danger for the other eye does not develop again until the atrophic eye becomes once more the seat of inflammation and of pain—an event which, to be sure, very frequently occurs. The most usual cause for these recurring attacks of inflammation is the persistent presence of a foreign body in the eye or the continual shrinking and ultimate ossification of the exudates. In this way an eye which has been carried for many years in an atrophic state without causing trouble may suddenly become the cause of a sympathetic inflammation. While, therefore, the minimum period for the development of sympathetic irido-cyclitis is a few weeks (the shortest period hitherto observed is two weeks), no limits can be set to the maximum period; sympatnetic inflammation has been seen to appear forty years and more after the injury of the first eye. An eye which has been destroyed in consequence of injury is therefore a constant source of danger to the other eye.

It is not necessary for the injured eye to be perfectly blind for it to excite sympathetic inflammation. Cases occur in which the eye has retained a remnant of visual power after the injury and the irido-cyclitis following it, and has yet given rise to sympathetic inflammation. In that case it may happen that the sympathetically affected eye un-

dergoes complete destruction, while the injured eye is still used to see with.

It is important to know—especially with reference to prognosis and treatment—under what conditions sympathetic inflammation of the second eye occurs only as a rare exception, and hence is generally *not* to be apprehended. These conditions are: 1. Phthisis corneæ, due to suppuration of the cornea (after abscess, acute blennorrhœa, etc.). 2. Staphyloma of the cornea. 3. Glaucoma absolutum. 4. Phthisis bulbi after panophthalmitis.

In what way does the *transference* of the inflammation from one eye to the other take place? This question has not, up to this time, been definitely decided. Mackenzie was the first to direct the attention of physicians to the dependence of the inflammation of the second eye upon that of the first. His idea of the method of transmission was that the inflammation made its way backward along the optic nerve and passed over along the chiasm to the optic nerve of the other side, in which it traveled forward. This explanation was afterward given up, because the inflammation in the second eye made its appearance, not under the guise of an optic neuritis, but under that of an irido-cyclitis. Now, as the uvea is supplied by the ciliary nerves, the path of transmission was regarded as being in them. The ciliary nerves of the two sides are not connected with each other directly, as is the case with the optic nerves through the chiasm; hence the transmission of inflammation in this case can not be conceived of as a direct one. On the contrary, we should have to assume that the ciliary nerves starting from the inflamed eye cause an irritation in the nerve-center, which is transmitted like a reflex to the ciliary nerves of the other side and to their termination in the eye.

Recently many (Leber, Deutschmann, and others) have returned to the old theory of transmission through the optic nerves. It is supposed that, through the injury of one eye, micro-organisms are introduced into it and multiply there. Then they are supposed to travel along the optic nerve and its sheaths from one eye across to the other and to excite inflammation in the latter.

B. **Secondary Iritis and Irido-cyclitis** are the varieties which develop through transference of the inflammation from neighboring organs to the iris and ciliary body. Inflammations of the cornea are the lesions that most frequently give rise to it; and among these it is chiefly the suppurative keratides that are apt to be very frequently complicated with iritis. Of the varieties of scleritis, it is the deep form which leads to inflammation of the iris and the ciliary body. More rarely, inflammations pass forward from the posterior section of the eye to the iris. Under the head of inflammations of this sort belong chorioiditis and detachment of the retina. The iritides thus produced are usually of a lighter sort or are chronic, sluggish forms. Finally, we may also put down to the account of sec-

ondary iritis the cases of iritis traumatica, already adduced, in which the iris is not affected by direct traumatism, as the iritis in swelling of the lens, in luxation of the lens, in intra-ocular tumors, cysticercus, etc.

That form of *syphilitic iritis* which is associated with the formation of nodules is generally designated under the name of iritis gummosa. For it was believed that these nodular exudates were necessarily to be regarded as gummy tumors on account of their sharply circumscribed form, which gives them sometimes just the appearance of small neoplasms. If we conformed to this view we should have to ascribe this form of syphilitic iritis to the tertiary stage of syphilis, which is characterized by circumscribed exudates (gummata) resembling new formations. But in so doing we should be contradicting clinical observation, which shows that iritis with the formation of nodules, always sets in at the same time with the phenomena of the secondary stage. We are hence justified in comparing the nodules in the iris with the papules and condylomata, which also belong to this stage, and in designating the iritis as iritis papulosa or condylomatosa (Widder). Another argument against the gummy nature of the nodules in the iris is the fact that they never break down nor suppurate, as gummata are apt to do. True gummata of the iris do exist, however, but they are extremely rare.

Microscopical examination has proved that even in those cases of syphilitic iritis in which no nodules are visible to the naked eye, these may nevertheless exist, being simply too small to project perceptibly above the surface of the iris and become visible. They give evidence of their presence by the marked swelling of the margin of the pupil at a circumscribed spot or by a particularly broad and firm adhesion of the margin to the capsule of the lens. These appearances should therefore always excite a suspicion of the presence of syphilitic iritis.

In addition to these signs the diagnosis of syphilitic iritis will, of course, always have to be based upon the history of the case or upon the demonstration of the presence of syphilis in the patient. But should we call every iritis which has no characteristic marks syphilitic, simply because it occurs in a syphilitic person? In the majority of cases, to be sure, we should be right, since syphilis is, in fact, the most frequent cause of iritis; but still a syphilitic patient may also acquire an iritis from any other cause whatever. In the absence of other guides, the indication in every case is to initiate an antisyphilitic treatment. This will, in most cases, cause rapid improvement in iritis of syphilitic origin, while other kinds of cases are but little or not at all affected; from which fact a conclusion may be drawn as to the source of the iritis. The effect of antisyphilitic treatment is also of assistance in making the diagnosis in those cases in which we are in doubt as to whether a nodule in the iris is of syphilitic nature or must be regarded as a new formation (sarcoma, tubercle).

Syphilitic iritis also occurs during intra-uterine life; the children then come into the world with the remains of it, such as synechiæ, occlusion of the pupil, atrophy of the iris, and even atrophy of the eyeball.

Sympathetic Ophthalmia.—The symptoms of *sympathetic irritation* which generally precede the inflammation are regarded by many as something entirely different from the latter and having no connection with it. They are thought to be produced through the ciliary nerves, while the transmission of the inflammation takes place through the optic nerves. It is adduced as a proof of the essential difference between irritation and inflammation that the former is cer-

tainly and permanently relieved by the enucleation of the eye originally affected, while this operation is powerless against sympathetic inflammation. On the other hand, it can not be denied that in very many cases the symptoms of inflammation develop so gradually and imperceptibly from the symptoms of sympathetic irritation that no sharp line of distinction can be drawn between the two, and the inflammation appears only in the light of an exacerbation of the prodromal irritation.

It is supposed that the sympathetic disease may appear not only in the form of an irido-cyclitis, but also under some other guise. The greatest variety of affections have been described as sympathetic. Among non-inflammatory affections, cases of paralysis of accommodation, of amblyopia, and of blepharospasm have been adduced as sympathetic ; among inflammatory affections in the posterior division of the eye, neuritis, chorioiditis, and glaucoma; and in the anterior division of the eye, conjunctivitis and keratitis. Most of these accounts are to be received with great caution, because observers have often gone too far in taking the sympathetic nature of the disease for granted. The fact that an eye has been destroyed through traumatism by no means justifies us in regarding, without further proof, any subsequent disease of the other eye as sympathetic. This assumption should be made only when such disease presents the characteristic clinical picture of sympathetic irido-cyclitis, or when, upon the enucleation of the eye first diseased, the symptoms in the second eye recede too rapidly to be accounted for upon any other assumption than that the affection of the second eye was caused by that of the first. The converse of this inference does not hold good—that is, the fact that enucleation of the first eye does not influence the course of the disease in the second is no argument against the sympathetic nature of the lesion; indeed, it is a well-established fact that when sympathetic ophthalmia has once broken out, enucleation of the eye first diseased is not generally able to cause much change.

Can an irido-cyclitis of *non-traumatic origin* be transmitted to the other eye? We very often see irido-cyclitis develop spontaneously first in one eye, then in the other. But we must not therefore at once conclude that the inflammation has been transmitted from one eye to the other. It may be that we have to do with a deeply seated common cause, generally of constitutional nature, which makes itself felt first upon one eye, then upon the other. Nevertheless, undoubted cases of sympathetic inflammation have also been observed without any antecedent traumatism or perforation of the envelopes of the eyeball. In this category belong the instances of irido-cyclitis in the case of intra-ocular tumor and of cysticercus, in which the presence of a constitutional disorder as the common cause of the disease of the two eyes can be excluded. The fact deserves mention that the wearing of an artificial eye over an atrophic stump may be the source of sympathetic inflammation through the iritation which it causes.

In regard to the *method of transmission* of the inflammation, the view that it takes place by the way of the optic nerves is steadily gaining adherents. This view is chiefly based upon the experiments of Deutschmann. In animals, it is not possible to excite by the injury of one eye a sympathetic inflammation in the other. Hence Deutschmann has employed another method, namely, the injection of cultivations of fungi (epecially of the *Staphylococcus*) either into the eye itself or beneath the sheath of the optic nerve. He found that the fungi traveled from the site of injection along the optic nerves to the brain. At the base of the brain they made their way to the optic nerve of the other side, and

passed down upon this to the eye. Here they set up an inflammation in the form of a neuritis of the intra-ocular end of the optic nerve, and with this, in one or two cases, an irido-cyclitis was associated. The animals, moreover, speedily perished from general infection. Whether the inflammation which Deutschmann produced in this way in the second eye is identical with sympathetic inflammation in man has not yet, to be sure, been certainly established. We shall hence have to wait for further proof before we can accept as perfectly certain the theory of the transmission of the inflammation by way of the optic nerves.

72. Treatment of Iritis and Cyclitis.—In every case of iritis and cyclitis it is incumbent upon us, on the one hand, to combat the local symptoms (*indicatio morbi*); on the other, to remove the causes lying at their foundation (*indicatio causalis*). In many cases in which an etiological factor is not demonstrable, we are thrown back solely upon the symptomatic treatment.

1. *Symptomatic Treatment.*—Atropine is the most important remedy in iritis. Inasmuch as it contracts the iris, it necessarily diminishes the amount of blood in its vessels, and hence directly counteracts the hyperæmia. By paralyzing the sphincter it fulfills a second indication which requires every inflamed organ to be put at rest; the constant to-and-fro movement of the pupil is completely arrested by atropine. The third action of atropine consists in its rupturing posterior synechiæ which already exist and in its counteracting the formation of new ones, through the dilatation of the pupil that it causes. The amount of atropine administered must be carefully regulated according to the degree of the intensity of the iritis. During the period of increase of the inflammation it is usually difficult to obtain dilatation of the pupil, because a spasm of the sphincter exists. In this case we must instill atropine several times a day. If this does no good, we place a little granule of atropine in substance in the conjunctival sac (for the necessary precautions, see page 258); this is better than to instill the solution too frequently, by doing which irritation of the conjunctiva (atropine catarrh) is readily set up. By the simultaneous employment of cocaine the action of atropine may be heightened. When the inflammation is abating, atropine is simply instilled often enough to keep the pupil constantly dilated.

In cases of irido-cyclitis in which the implication of the ciliary body is particularly prominent, and also in cases of pure cyclitis, atropine is not always well borne. For, in proportion as the iris becomes narrower and its vessels can contain less blood, the vessels of the ciliary body are overdistended, since they have to take up the blood which finds no lodgment in the iris. Hence, in such cases, we must be very cautious in the use of atropine, and must suspend it whenever we find that the pain increases after the instillation. So also, when an irido-cyclitis is combined with elevation of tension, the atropine must be stopped and, if necessary, replaced by a miotic.

In violent inflammation, moist warm compresses or poultices afford the best results, especially for the relief of pain. Cold compresses are generally not well borne, and are suitable only for recent cases of traumatic iritis. Extensive bloodletting by means of six to ten leeches applied to the temple, or by a Heurteloup's artificial leech, may very greatly diminish the inflammatory symptoms in the bad cases; not infrequently directly after such a bloodletting the pupil for the first time yields to the action of atropine, while before this it had remained in a constant state of spasmodic contraction. The production of profuse diaphoresis often has a very marked effect. This can be obtained by the hypodermic injection of pilocarpine (one to four centigrammes at a dose), or by the administration of a hot tisane with from one to two grammes of sodium salicylate. The sweating may be repeated daily or every other day.

Operative procedures are for the most part indicated more in the sequelæ of iritis than in recent inflammation. Paracentesis is performed whenever increase of tension sets in. It may also be tried in cases of long-persisting inflammation which will not yield to other remedies. As the aqueous escapes, the deposits upon the cornea are often washed out with it, and their escape can be facilitated by rubbing the cornea; but the removal of such deposits is not the proper aim of paracentesis. Iridectomy is performed only in very exceptional cases while inflammation still exists, being done either because in no other way can a stop be put to the inflammation or on account of an increase of tension. Much more frequently it is done as a prophylactic in cases of recurring iritis to prevent further recurrences. And, in fact, in many cases, an end is put once and for all to recurrences by this means; in other cases, however, this successful result fails to occur.

A proper *regulation of the mode of life* in iritis requires first of all protection from the light, not only on account of the photophobia that is generally present, but also because light excites the pupil to contraction. For the latter reason the protection against light must be applied to both eyes, since with the contraction of the pupil of one eye that of the other also tends to contract. The patient is kept in a moderately darkened room, or is made to wear dark goggles. This is better than a bandage, which it would be difficult to apply to both eyes. The patient should be moderate in eating and drinking, and should abstain from spirituous beverages. Care should also be taken to secure bodily rest by the avoidance of all physical exertion and in severe cases by rest in bed. The healthy eye should not be strained by reading, etc. Moreover, it is important to see that the bowels move easily.

2. *Causal Indication.*—With reference to the etiological factor, *syphilitic iritis* gives the most favorable prognosis, since it generally yields promptly to an energetic antisyphilitic treatment. The chief requisite is promptness of action, since we are dealing with a lesion in

which a few days may produce great and lasting damage (by the formation of a seclusio or occlusio pupillæ). Hence mercury is selected, and this is best applied in the form of inunction (two to four grammes of blue ointment being rubbed in daily). The inunctions should be kept up until the diseased eye has become perfectly free from discoloration and then potassium iodide (up to three grammes a day) may be used for after-treatment. In iritis due to hereditary syphilis less value is attributed to specific antisyphilitic treatment and more to the strengthening of the organism as a whole.

In *iritis rheumatica* sodium salicylate is administered, although not always with success. This drug also does good service sometimes in iritis gonorrhoica and iritis diabetica. In the former variety I have also employed with advantage the oil of gaultheria (fifteen drops per diem in capsules).

In *iritis traumatica* the causal factor is first of all to be done away with, in case it still continues to act. Foreign bodies are to be removed from the iris; portions of the iris that are much contused or are incarcerated are to be excised. A swelling or luxated lens causing iritis must be removed from the eye. To combat the inflammation of the iris, besides atropine iced compresses are employed in cases which are very recent. With respect to those traumatic iritides which follow an operation, the most important part belongs to prophylaxis. This consists in strict antisepsis during the operation; and, as a matter of fact, since this has been employed such iritides have become much more rare.

Irido-cyclitis sympathica, too, is very amenable to prophylaxis, while, when it has once broken out, it often resists treatment of every kind.

(*a*) The only certain *prophylactic treatment* of sympathetic inflammation consists in the enucleation of the eye which might give rise to it. This is the case in every eye which has been made blind by injury and is painful either spontaneously or upon pressure. Most emphatically requiring enucleation are eyes which are suspected to contain a foreign body A contra-indication to enucleation is present only when the injured eye has still a serviceable residue of visual power or can get it through an operation. When this is not the case, enucleation should, under the circumstances above given, be performed without delay. In extreme cases, if the patient can not bring himself to consent to enucleation, it is permissible to wait until the prodromal symptoms of sympathetic disease make their appearance, since even in this stage enucleation is generally still able to prevent the outbreak of sympathetic inflammation.

(*b*) When sympathetic ophthalmia has already broken out, the effect of enucleation is uncertain. In the lighter cases it appears to exert a favorable influence upon the course of the sympathetic inflam-

mation; in severe cases, on the contrary, it is often of no use and appears sometimes actually to increase the inflammation in the second eye. Hence we wait for an abatement of the inflammatory symptoms in the second eye before performing enucleation.

The sympathetic inflammation itself is to be treated according to general rules. Of especial importance is the protection of the diseased eye from light, which is most perfectly attained by long-continued bandaging of the eye. Operations generally give a bad result, since they start up the inflammation again, so that the newly formed pupil is once more closed by fresh exudate. Hence operations are done only when it is absolutely requisite (e. g., when done on account of increase of tension); other operations, such as, for example, an iridectomy for optical purposes, are put off as long as possible, preferably for years.

73. Treatment of the Sequelæ of Iritis and Irido-cyclitis.—*Isolated posterior synechiæ* can often be ruptured by the employment of atropine Here it is not so much a long-continued action as a very energetic one that is required, and this is most certainly secured by placing atropine in substance in the conjunctival sac. Still more effectual sometimes is the alternate use of miotics and mydriatics, the pupil being first contracted with eserine, then suddenly and energetically dilated with atropine. But since the iris is made hyperæmic by eserine, attempts of this sort must not be made until some time has elapsed since the occurrence of the iritis.

It is frequently possible to rupture synechiæ which are narrow and drawn out into a point, while broad synechiæ (such as occur after syphilitic or sympathetic iritis) withstand all attempts.

Annular posterior synechia (seclusio pupillæ) demands iridectomy unconditionally, the object being to restore the communication between the anterior and posterior chambers. The operation is often difficult on account of the shallowness of the anterior chamber (due to protrusion of the iris), and also on account of the atrophy of the iris. Accordingly, we must often be contented if we succeed in making a small opening in the iris. Then the anterior chamber, in consequence of the restoration of the connection between the two chambers, regains its normal depth, so that a second iridectomy can be performed later under more favorable conditions.

In simple seclusio pupillæ, the iridectomy is made upward; if occlusion is at the same time present, it is made inward. The latter rule also holds good for those cases in which occlusion alone exists (see § 166).

Total posterior synechia also requires iridectomy, which, however, is often void of result, as on account of the adhesion between the surfaces of the iris and the lens it is frequently impossible to excise a sufficiently large piece of the iris, or because the pigment-layer of the iris, which has grown fast to the lens, remains attached to it. In such

cases the only thing to be done is to remove the lens, too, even if it is still transparent (Wenzel's extraction). If the lens is atrophied or absent, iridectomy is indicated (see § 158).

Too much caution can not be inculcated in regard to the senseless employment of *atropine*, which, unfortunately, is still carried on by many general practitioners, who instill atropine in every kind of eye disease. In many cases—e. g., in conjunctival catarrh—atropine is not only superfluous, but also causes the patient annoyance through the disturbance of vision connected with its use; and in eyes which have a tendency to glaucoma, atropine may actually inflict great injury by determining an attack of acute glaucoma. Accordingly, atropine should be employed only upon quite specific indications, and should be applied no oftener than is requisite to obtain just the result desired. Even in iritis atropine is useless if the pupillary margin is adherent to the capsule throughout, and the iris hence can not retract.

If, after an iritis, one or two posterior synechiæ are left which do not rupture when atropine is energetically employed, we abstain from further treatment of them, since they generally do no harm to the eye. At the present time we have entirely desisted from releasing them by operation (corelysis). When, however, an annular synechia is present, we ought not to let it stay, but must make an *iridectomy*. This is also indicated in those cases in which the seclusion of the pupil is not yet indeed complete, but is on the verge of being so, only one small spot of the pupillary margin being free from it. For if we are dealing with a chronic irido-cyclitis, we can count upon this small spot soon becoming adherent too, and in that case it is better not to wait for the development of complete seclusion of the pupil. It is particularly advisable not to do so if the patient lives far from the physician, and might perhaps let the proper moment for the iridectomy pass by.

In cases of chronic irido-chorioiditis, iridectomy is not only mechanically efficient by removing the seclusio pupillæ, but it also has a favorable influence upon the entire nutritive condition of the eye. The vitreous clears up and the sight improves, often for quite a long time. If an operation is done upon eyes which have already begun to grow softer—that is, are on the road to atrophy—the eye in favorable cases fills out again, and the ocular tension becomes normal.

In cases of iritis after injury the lens is very frequently found to be wounded too, and consequently opaque and swollen. In such cases the removal of the lens should not be undertaken unless an imperative indication for it exists—e. g., when the swelling of the lens must be regarded as the cause of the iritis, or if it produces elevation of tension. Otherwise it is better to put off the extraction of the lens till a time when all the inflammatory symptoms have subsided, because, if this is not done, an exacerbation of the existing inflammation might be caused by the operation.

Although enucleation generally affords a sure safeguard against sympathetic inflammation of the other eye, nevertheless a series of cases is known in which, in spite of enucleation, inflammation has subsequently made its appearance. In every instance it has set in within a short time—from a few days to a few weeks—after the enucleation.* It must probably, therefore, be assumed that at the time of the enucleation the transfer of the inflammation had already begun. Yet even in this case enucleation does not fail to exert a favorable

* The longest interval so far observed has been thirty-two days (Snell).

effect, since in the great majority of these cases the sympathetic inflammation runs an unusually favorable course, probably because the removal of the first eye prevents the constant emission from it of new impulses for the production of inflammation.

II. Injuries of the Iris.

74. In addition to what has already been said in the previous sections in regard to injuries of the iris and their consequences, the following special varieties of injury, which are most frequently observed after contusions of the eye, may be mentioned:

1. Under the name of *iridodialysis* * is designated the separation of the iris from the ciliary body. We then find on one side, at the ciliary margin of the iris, a black crescent which is formed by the separation of the iris from its insertion at this spot, so that we can look into the interior of the eye (Fig. 63). When the separation is pretty considerable, the edge of the lens (*l*), the ciliary processes (*p*), and the fibers of the zonula of Zinn stretching between the two can be recognized by means of lateral illumination in the gap that is thus produced.

Fig. 63.—Iridodialysis. Magnified 2×1.

The pupillary margin at *a* is made to slope off in a straight line. At a point corresponding to this spot the iris is separated from the ciliary body and is narrower and somewhat folded. In the interval between the iris and the margin of the cornea are seen the margin of the lens, *l*, and the apices of the ciliary processes, *p*; the fine radiating striation between the two structures corresponds to the zonula of Zinn. *k*, circulus iridis minor; *c*, contraction furrows.

The pupil has lost its round form, owing to the fact that the pupillary margin toward the side of the iridodialysis has shortened so as to occupy the chord of an arc instead of the arc itself (Fig. 63, *a*). The cause of this inward displacement of the pupillary margin lies in the fact that the separated portion of the iris is stretched in a straight line by the contraction of the sphincter. By this means it is withdrawn from its insertion in the ciliary body, and its reunion with the latter is rendered forever impossible. The sight is but little affected by iridodialysis; the only thing being that, if the eye is not accurately focused, monocular diplopia may occur, due to the formation upon the retina of an image both by means of the pupil and also of the peripheral opening (see § 123).

Iridodialysis may occur to any extent, from a scarcely perceptible tear to complete separation of the iris from its ciliary attachment. In

* From Ἶρις, iris, and διάλυσις, separation.

the latter case the iris becomes folded up into a ball which sinks to the bottom of the chamber, and which by the next day has shrunken into an inconspicuous little gray mass. If a rupture of the sclera has been at the same time produced by the injury, the separated iris may be expelled altogether from the eye through the scleral wound. In both cases complete absence of the iris, *irideremia** or *aniridia*† *traumatica.*, is produced.

2. *Radiating lacerations* which start from the pupil. These may extend to the ciliary margin, so that the pupil at the site of laceration appears to be prolonged in the form of a pointed Gothic arch to the margin of the cornea. Such large lacerations, however, are rare. Generally the pupillary margin is simply torn into a little, and the laceration gapes so slightly that it is discovered only upon careful examination, especially with the aid of a magnifying-glass. Such small lacerations are the most frequent cause of the dilatation of the pupil (*mydriasis traumatica*) which develops after contusions and which is founded upon the weakening or paralysis of the sphincter due to the laceration. This iridoplegia may disappear entirely in favorable cases, but in others a moderate dilatation of the pupil remains permanently. The ciliary muscle, too, may be paralyzed by a contusion, as manifested by the diminution of the amplitude of accommodation (recession of the near-point).

3. *Introversion of the iris* (Ammon) consists in the bending backward of the iris in such a way that it gets to lie upon the surface of the ciliary body (*o*, Fig. 64). The iris is then invisible in its ordinary position, just as if it were wanting there. Total introversion of the iris is very rare. Partial bending backward of the iris is more frequently observed, especially in scleral ruptures at the place corresponding to the rupture. Here the iris seems to be wanting, and a coloboma appears to exist just as if an iridectomy had been made (see page 217). In rupture of the sclera, however, a piece may really be torn out of the iris, so that a true *coloboma traumaticum* is formed.

Injuries of the iris are generally accompanied by hæmorrhage into the anterior chamber. The blood which arises from the ruptured vessels of the iris sinks rapidly to the bottom of the chamber (*hyphæma*), and for the most part disappears by resorption within a few days. Then, and not before, are we able to investigate completely the damage which the iris has suffered from the injury, and we find perhaps an iridodialysis or radiating lacerations. But often even then it is impossible to discover a solution of continuity in the iris, and so the source of the bleeding remains unknown. In many of these cases the blood is supposed to come from a laceration of Schlemm's canal (Czermak).

Treatment.—If the symptoms of irritation after the injury are par-

---

* From ἶρις and ἐρημία, loneliness, want. † From ἀ privative, and ἶρις.

ticularly marked, we apply iced compresses for several days; in other cases it is sufficient to keep the injured eye under a bandage and to insure quiet on the part of the patient, secured, if need be, by rest in bed. If an iridodialysis can be made out, we instill atropine in order that the contracting sphincter shall not draw the iris farther away from its point of attachment; in radiating lacerations, however, atropine is contra-indicated, because it would make the lacerations gape still more. Iritis is generally not to be apprehended after injuries of the iris not connected with perforation of the membranes of the eye. With reference to the treatment of perforating injuries, see page 221.

Iridodialysis is sometimes unintentionally produced in operations upon the iris. If the eye that is being operated upon makes a violent movement at the moment when the operator grasps the iris with the forceps, the iris may by this means be separated from its insertion to a varying extent, or even be torn out of the eye. Great hæmorrhage into the anterior chamber is always the result of this unfortunate accident. In iridectomy done on account of occlusion of the pupil, iridodialysis may also be produced in the following way: The operator grasps the iris and tries to draw it out of the wound. To effect this it ought first to be set free from the pupillary membrane. But if the connection between the latter and the iris is very firm, the two do not separate, but the membrane and also the iris of the opposite side follow the course of the traction, so that an iridodialysis is produced upon the side opposite the iridectomy. Hence, in such cases, the iris ought always to be first released from the pupillary membrane by lateral movements of the forceps before it is drawn out of the wound.

FIG. 64.—INTROVERSION OF THE IRIS. SCHEMATIC.

The cornea is flattened, and consequently the aqueous is pushed backward by the force which acts upon the center of the cornea, *c*, in the direction $a\,a_1$. As a result of this, the iris in its lower part, *u*, bulges out in the form of a sac, but at its upper part, *o*, is completely reversed, so as to point straight backward. (See also the explanation of Fig. 42, p. 224.)

Iridodialysis is produced in a non-traumatic way, when neoplasms of the ciliary body grow out into the anterior chamber so as gradually to push the iris away from its insertion (cf. also page 233).

To *account for* the above-described traumatic changes in the iris, two factors have to be taken into consideration. The first is based upon the flattening which the cornea undergoes through the contusion, and through which its circumference and consequently also the circle of insertion of the iris become larger. (See in Fig. 64 the eye denoted by the dotted line.) If this enlargement takes place suddenly, the iris can not adapt itself to it and tears away in places from its insertion, so that iridodialysis is produced (Arlt). The second factor

consists in the circumstance that the blow which strikes the cornea and flattens it out also pushes the aqueous backward. The latter tends to recede and pushes against the posterior wall of the anterior chamber, which in the area of the pupil is formed by the lens and in the rest of its extent by the iris. The latter, when pushed backward, finds a support in the lens except at its marginal portion which lies outside of the margin of the lens. Here the posterior chamber is deepest and is bounded posteriorly only by the feeble zonula of Zinn. The periphery of the iris, therefore, forms the most yielding spot in the posterior wall of the anterior chamber and the one which is the first to give way before the pressure of the receding aqueous. Hence the iris is bulged out backward by the aqueous in the form of a sac extending as far as the zonula, or, if this ruptures, even into the vitreous (Fig. 64, *u*). The direct consequences of this dislocation of the iris are threefold: marked stretching of the fibers of the iris in a radial direction; dilatation of the pupil; and, finally, in extreme cases, rupture of the zonula. The first factor may result in iridodialysis. The sudden dilatation of the pupil may cause radiating lacerations of the sphincter and consequently paralysis of the latter. The rupture of the zonula causes tremulousness, subluxation, or luxation of the lens. If the dilatation of the iris is of a sufficiently high degree, the lens, which is no longer held in place by the zonula, may slip through the pupil into the anterior chamber, where it is then held captive by the iris, which again contracts behind it (luxation of the lens into the anterior chamber). Finally, the sac-like inversion of the periphery of the iris may be so extensive that the iris at one spot is completely reversed and points straight backward (Fig. 64, *o*), and introversion of the iris is produced (Förster).

III. Tumors of the Iris and Ciliary Body.

75. 1. *Cysts of the Iris.*—Serous cysts occur in the iris, which are filled with a clear substance, and which develop within the stroma of the iris, so that their walls are formed by rarefied iris-tissue. They develop after penetrating wounds of the eyeball, and grow very gradually until they have reached the posterior surface of the cornea, and fill at least half the anterior chamber. Then elevation of tension is superadded, and in consequence of this the eye becomes entirely blind To prevent this, the cysts must be removed in season by an operation. This is performed by making an incision at the margin of the cornea at a point corresponding to the cyst; the forceps is entered through the incision, and the cyst, together with the adjoining iris, is drawn out and excised. Often complete removal is not possible, in which case a recurrence of the cyst is to be expected, which will require a new operation.

2. *Tuberculosis of the Iris.*—This is observed in children and young people. It occurs as disseminated (miliary) tuberculosis and as conglobated (solitary) tubercle—i. e., either in the form of small nodules or as a larger growth resembling a neoplasm. Eyes attacked by tuberculosis of the iris are usually lost, but cases of spontaneous recovery have also been observed. In consideration of this fact, we at first con-

fine ourselves, in the lighter cases, to an expectant treatment, in which the hygienic management of tuberculosis must play the chief part. But if the disease, nevertheless, keeps on and blindness is impending, it is better to remove the eye by enucleation, that it may not be the source of a further extension of the tuberculosis.

3. *Sarcomata.*—Sarcomata of the iris are for the most part pigmented, brown tumors, which grow at first very slowly, afterward more rapidly, until they fill the anterior chamber, and finally, breaking through the envelopes of the eye, extend their growth exteriorly. Sarcomata of the *ciliary body* remain for a long time unnoticed, since they are covered by the iris. It is not until they have reached a certain size that they are seen as a brown projection behind the iris, or are recognized by their growing forward into the anterior chamber. This latter process takes place at the angle of the chamber, where they push the iris away from its insertion (iridodialysis). With regard to their subsequent course, sarcomata of the iris and the ciliary body resemble those which spring from the chorioid, to which reference must be made for particulars (§ 80). The only treatment for these tumors is radical removal, which should be performed as early as possible. Very small sarcomata of the iris can be removed by iridectomy, those parts of the iris which bear the nodules of the tumor being excised. Larger sarcomata of the iris, and also sarcomata of the ciliary body, require enucleation of the eye without delay.

Serous cysts of the iris are a very rare affection. They appear under the form of grayish, transparent vesicles whose anterior wall usually shows still one or two fibers of rarefied iris-tissue, and also some pigment. When they have reached the posterior surface of the cornea, they flatten out upon it, while the cornea at the point of apposition becomes cloudy, as it always does when in contact with foreign tissue. Meanwhile the cyst has already reached the pupillary margin of the iris and pushes it forward into the pupil, so that the latter becomes kidney-shaped, and afterward even reduced to a slit. Moreover, the cyst keeps extending backward, too, and thus induces obliquity and afterward opacity of the lens. All these factors give rise to disturbance of vision, which, to be sure, is frequently unnoticed by the patient, whose vision has already been impaired by the injury.

Still more rare than serous cysts are the *pearl-cysts*, which are distinguished from the serous cysts by their contents, which are pultaceous, tallowy, or like gruel; in rare cases hairs are also found in them.

Microscopical examination of the cysts has proved that their walls are formed by iris-tissue, while their inner surface is lined with epithelium, which secretes the serous contents of the cyst; in the pearl-cysts the pultaceous contents are formed by the epithelial cells which are constantly thrown off from the inner surface and undergo fatty disintegration.

How do cysts arise? Normally there are nowhere in the iris either glands or epithelium, so that the ordinary retention-cysts are not to be thought of. The epithelium must have been brought into the iris from outside. How this is possible is clear to us when we remember that cysts of the iris develop, as a

rule, only after penetrating injuries. By means of the body which causes the injury some epithelium from the outside is torn off of the edges of the lids, the conjunctiva, or the cornea, or perhaps a cilium is torn off with its follicle, and these are carried into the eye. There they are deposited in the anterior chamber, or perhaps in the tissue of the iris itself. The epithelium implanted here finds favorable conditions for its nutrition and keeps on growing; afterward a cavity forms inside of it through the accumulation of fluid, which pushes the epithelial cells apart and converts them into a coating for the newly formed cyst-cavity (Buhl, Rothmund). In support of this explanation, which up to this time appears to be the best one, experimental implantations of fragments of living tissue have been made in the chamber of the eye (Doremaal, Goldzieher). The introduced tissue becomes vascularized by the vessels of the iris and grows to a certain size, after which it undergoes regression. An attempt has been made to account for the development of the cysts in another way. De Wecker assumes that a part of the posterior chamber is converted into a sac by means of posterior synechiæ, and afterward through accumulation of liquid dilates into a cyst-cavity. According to Alt, anterior synechiæ also can produce sacculations of this sort. Everbusch thinks that at first, in consequence of the injury, a separation of the innermost lamellæ of the ligamentum pectinatum takes place (e. g., through the extravasation of blood beneath it). This separation keeps going on in a centripetal direction, so that the tissue of the iris is gradually forced apart as far as the pupillary margin into two layers, the walls of the cyst. With regard to the rare cases of spontaneous—i. e., non-traumatic—cysts of the iris, Schmidt-Rimpler conjectures that they arise from a closure of the orifice of a crypt with subsequent accumulation of fluid in its cavity. Not to be confounded with the cysts of the iris are the *cysticercus vesicles*, which in very rare cases are observed in the anterior chamber. They either lie free in the latter or are attached to the anterior surface of the iris.

Tuberculosis of the iris is a very rare disease, which, however, is well understood, as it can be produced experimentally. Cohnheim has shown that tuberculous iritis can be set up by the introduction of tuberculous masses into the anterior chamber. The tuberculous masses (fragments of excised tuberculous lymphatic glands, granulations removed from tuberculous joints by scraping, etc.) must be aseptic—i. e., free from pyogenic germs—as otherwise, upon their inoculation into the anterior chamber, violent irido-cyclitis or even panophthalmitis would be produced, by which the eye would be destroyed. It is safer, therefore, to employ pure cultures of tubercle bacilli for the inoculation. The fragments of tuberculous tissue, when introduced into the anterior chamber, excite there a slight irritation, which, after a few days, disappears again. As the fragments of tissue themselves are also rapidly absorbed, the eye soon appears perfectly normal again, as if the inoculation had remained without result. But in twenty or thirty days afterward the eye begins to become red once more, and the phenomena of iritis make their appearance; at the same time small gray nodules are noticed in the iris. These increase in number, become confluent, afterward fill the anterior chamber, and finally break their way through to the outside. Generally the animal experimented on afterward perishes from the development of general tuberculosis due to infection starting from the eye. Tuberculous iritis is employed as a means of demonstrating the tubercular nature of excised pieces of tissue, for which purpose we introduce the latter into the ante-

rior chamber of a rabbit's eye, and see if tuberculous nodules develop after the usual period in the iris.

The tuberculosis of the iris experimentally introduced in animals is a primary tuberculosis, but tuberculosis of the iris in man is secondary—i. e., has originated from another tuberculous focus somewhere in the body. As a matter of fact, in most cases of tnberculosis of the iris, signs of tuberculous disease in other organs (lungs, lymphatic glands, bones, etc.) are also found. In many cases, to be sure, the patients appear to have been perfectly healthy up to the time of their eye trouble, but even in these cases a primary tuberculous focus (e. g., caseous bronchial glands), although not demonstrable clinically, must be assumed to exist—in fact, the iris, on account of its protected situation, can not be infected by tubercle bacilli from without, as, for example, the conjunctiva can, in which primary tuberculosis is not so very rare. Direct tuberculous infection of the iris would be conceivable only as a consequence of penetrating wounds—a thing which I have actually observed in one instance.

Disseminated tuberculosis of the iris occurs in man under the form of an iritis, which presents as its characteristic feature the small, gray, transparent nodules spoken of. These are in a state of constant change, some disappearing while others are being newly formed. Recovery may finally take place; more frequently, however, atrophy of the eyeball occurs in consequence of plastic irido-cyclitis. The disease often appears on both sides. Removal of individual nodules through excision by an iridectomy of the portion of iris bearing them is generally useless, since new nodules form afterward in other parts of the iris.

The *solitary tubercle* has hitherto been observed only upon one side. It either develops simultaneously with the miliary nodules, or, more frequently, without them and without any symptoms of iritis, so that it resembles a neoplasm; indeed, it was at first described as such by Von Graefe, under the name of *granuloma*, because Virchow, who made the anatomical examination of the tumor, designated it as granulation-tissue. Its subsequent course seems at first to confirm the diagnosis of a neoplasm, since the tumor keeps growing constantly, and finally, perforating the cornea near its margin, forms a proliferating mass outside. But then, instead of a larger tumor developing from this, which keeps growing on indefinitely, the tumor breaks down, so that ultimately nothing is left of the eyeball but an atrophic stump. Haab was the first to bring proof of the fact that these tumors, formerly designated as granulomata, are tubercles. As far as treatment is concerned, however, this mistake in diagnosis would be of little significance, since enucleation is indicated alike in the case of a neoplasm and in that of a granuloma. The eye which bears a granuloma is, in fact, lost for purposes of vision, and may become the source of a general tuberculous infection. Solitary tuberculous tumors have also been observed in the ciliary body.

There are cases in which, owing to the formation of nodules in the iris, the clinical picture of a disseminated tuberculosis is simulated, while another disease is at the bottom of them. So it is in the rare cases of iritis with the formation of nodules in leukæmia and pseudo-leukæmia. Similar cases, furthermore, are those in which nodules have formed in the iris with violent inflammatory symptoms some months after the hair of a caterpillar had got into the eye. Examination of the excised nodule shows that it contains caterpillar-hairs, which have bored their way through the cornea and into the iris (Pagenstecher, Weiss, Wagenmann).

The name of granuloma of the iris has also been bestowed upon granulating prolapses of the iris when they develop into small, mushroom-shaped growths. It is better not to use this designation; it gives rise, on the one hand, to confusion with the tubercles called granuloma, and, on the other hand, to the incorrect assumption that the thing in question is a neoplasm.

Benign tumors, called *melanomata*, occur in the iris. They are found under two different forms: The first consists in the outgrowth of a blackish tumor from the stroma of the iris into the anterior chamber. This kind of melanoma arises from the proliferation of the pigmented stroma-cells of the iris. The second kind of melanoma has its seat at the pupillary margin of the iris. It develops from the cells of the retinal pigment-layer at the spot where it is reflected upon the anterior surface of the iris at the edge of the pupil. Here small black nodules develop which project into the pupil. Sometimes, in consequence of the alternating movements of the pupil, they become separated from the pupillary margin and then lie free in the anterior chamber. A feature common to both kinds of melanoma is that they are benign tumors which reach only a certain size. Nevertheless, cases are known in which pigmented sarcomata have afterward developed from melanomata of the first kind.

The *differential diagnosis* of tumors of the iris sometimes presents difficulties. A *non-pigmented* nodular tumor in the iris may be a syphilitic growth (papule or gumma), a solitary tubercle, or an unpigmented sarcoma. The distinguishing marks are as follows:

1. The sarcomata contain most vessels; the syphilitic growths have fewer, the tuberculous masses scarcely any vessels passing through them. In the case of the tubercles, small gray tuberculous nodules of characteristic appearance are sometimes found in the neighborhood of the large tumor.

2. Papules of the iris are situated only at its pupillary and ciliary margins —never at other spots—while other tumors may take their origin from any point whatever of the surface of the iris.

3. With syphilitic and tuberculous tumors, iritis appears earlier than with sarcomata.

4. Tubercle is found, as a rule, only in people under twenty, while both the other kinds of tumors usually occur after that age.

5. Particular importance must be attached to the general examination of the patient, with the purpose of determining whether symptoms of syphilis or tuberculosis are found in other organs. In doubtful cases it is justifiable to initiate an energetic mercurial treatment, from the result of which a conclusion may be drawn as to the nature of the tumor.

Among the pigmented tumors, pigmented sarcomata and melanomata (of the first variety) resemble each other exceedingly. They can be distinguished with certainty only by determining, from the previous history or from observation, whether a process of growth exists or not.

As tumors of very rare occurrence may be mentioned: Vascular tumors (Mooren, Schirmer); myomata (Lagrange) and myo-sarcomata (De Wecker and Iwanoff, Dreschfeld, Deutschmann) springing from the ciliary muscle; and, lastly, lepra nodules (Bull and Hansen).

IV. Disorders of Motility of the Iris.

76. Disorders of motility of the iris manifest themselves in diminished reaction of the latter, but chiefly in alteration of the diameter of

the pupil. This alteration is particularly striking when the disease affects but one eye, so that a difference in the pupils (*anisocoria* *) results. This is always to be regarded as a pathological condition, since in the normal state the two pupils are of the same size under all circumstances. The pathological alterations of the diameter of the pupil comprise dilatation (mydriasis), and contraction (miosis) of the pupil. Either of these conditions may be brought about by spasm (active or spastic states) or by paralysis (passive or paralytic states). Spastic mydriasis is produced by active contraction of the fibers which dilate the pupil; paralytic mydriasis, on the contrary, by paralysis of the sphincter. The converse is true of miosis. Spastic miosis is to be referred to contraction of the sphincter; paralytic miosis to paralysis of the fibers which dilate the pupil.

(*a*) *Mydriasis.*

Spastic mydriasis accompanies conditions of cerebral irritation of the most widely differing kinds.

Paralytic mydriasis is far more frequent. It is caused by paralysis of the fibers of the oculo-motor nerve, whose branches innervate the intrinsic muscles of the eye—i. e., the sphincter pupillæ and the ciliary muscle. These two muscles are hence generally found to be paralyzed simultaneously. The oculo-motor paralysis may be a diffused one—i. e., affect several or all of the branches of the nerve—or it may be confined to the pupil (either alone or in conjunction with the muscle of accommodation). Such isolated paralyses occur—1. In the beginning of chronic cerebral diseases. 2. In syphilis. 3. Through the action of poisons. Among these belong, first of all, the alkaloids known as mydriatics. Paralysis of the pupil and of accommodation also occur in case of poisoning by the toxic principles of putrefaction (rotten meat, fish, sausages, etc.). 4. After diphtheria (cf. § 151).

Paralyses of the pupil and of accommodation, occurring after contusions and in case of increased tension, are accounted for by an entirely local lesion of the sphincter and the muscle of accommodation. In the case of contusions, besides the concussion, small lacerations and extravasations of blood into the muscles are also met with. In the case of increased tension the paralysis is produced by the pressure upon the nerves, with which is very soon associated atrophy of the muscular fibers themselves.

The dilatation of the pupil in complete blindness (amaurosis) is not to be regarded as a disorder of motility of the iris, but simply as a physiological cessation of the pupillary reflex when the perception of light is deficient.

---

* From ἀ privative, Ἴσος, equal, and κόρη, pupil.

(*b*) *Miosis.*

Spastic miosis is observed in beginning meningitis. The greatest degree of spastic miosis is produced by the alkaloids which contract the pupil (miotics); other poisons, such as opium, chloral, and nicotine, also cause contraction of the pupil, though in less degree.

Paralytic miosis is one of the most important symptoms of paralysis of the cervical sympathetic. Moreover, it very frequently accompanies spinal lesions, especially tabes dorsalis *Spinal miosis* is very often distinguished by the fact that the pupil has ceased to react to light, while it still contracts synchronously with accommodation and convergence (Argyll-Robertson phenomenon; see page 261).

Enlargement and diminution of the pupil in themselves cause no considerable interference with vision if they are not combined with paralysis of accommodation. Hence they are but seldom, in themselves, the subject of treatment; their chief significance lies in their being an important symptom of a deeply seated and wide-spread disorder. This latter, therefore, as a rule, is alone the object of treatment. Paralytic mydriasis may be treated symptomatically by miotics and electricity.

Paralysis of the sympathetic is characterized by a series of symptoms which Horner was the first to describe fully. The pupil is contracted through paralysis of the fibers which dilate it—a fact which is particularly manifested in the non-dilatation of the pupil when the eye is shaded. The palpebral fissure is smaller in consequence of drooping of the upper lid. This moderate ptosis is caused by the paralysis of the smooth muscular fibers in the upper lid (the musculus palpebralis superior described by Müller), which are supplied by the sympathetic. The eyeball itself often seems to have sunk back into the orbit and to be less tense. An important symptom is the difference in the fullness of the vessels on the two sides of the face. In a recent paralysis the face is redder and warmer on the paralyzed side; afterward, the opposite is the case, the paralyzed side being paler, cooler, and no longer sweating (a thing easily made out in men by the hat-lining, which is stained with sweat on one side and not on the other). The causes of sympathetic paralysis are usually the coarser lesions of the nerve in the neck, such as injuries of an accidental nature (among others, those resulting from a fracture of the clavicle), or those inflicted in the extirpation of tumors, or pressure by tumors (most frequently goitre or enlarged lymphatic glands). Among central diseases lesions of the spinal cord, such as tabes or injury of the uppermost part of the cervical cord, have been observed as the cause of sympathetic paralysis. In many cases it is impossible to find a cause. The paralysis, in addition to the inconsiderable disfigurement due to the slight ptosis, causes no annoyance, and not infrequently is first discovered accidentally by the physician.

Under the name of *hippus* is designated a pathological condition which consists in a constant and rapid change in the diameter of the pupil. Since even

under physiological conditions the pupil never remains quite at rest, it is hard to draw the line between physiological and pathological inquietude of the pupil, and many believe that a genuine hippus does not exist.

For disorders of motility of the ciliary body, see under the anomalies of accommodation (§ 151).

V. Congenital Anomalies of the Iris.

77. 1. *Membrana Pupillaris Perseverans* (persistent pupillary membrane).—This consists of a gray or brown tissue which lies upon the anterior capsule of the lens in the region of the pupil, and is usually connected with the iris by brown filaments. Very frequently only

Fig. 65.—Remains of the Pupillary Membranes.

This rises under the form of a small filament, *c*, from the circulus minor iridis, and runs to the pupil, in the center of which it becomes attached to a small, round, white capsular opacity. In spite of the filament, the lower half of the iris has retracted widely under atropine, so that the filament is greatly elongated; but the upper part of the iris is prevented by two posterior synechiæ (*a* and *b*) from submitting readily to the action of atropine. (See explanation to Fig. 58.)

those filaments are present which run from one portion of the pupillary margin to the opposite, and thus bridge over the pupil, or which pass from the iris to the capsule of the lens. They bear a great resemblance to the posterior synechiæ remaining after iritis, but do not, like the latter, rise from the pupillary margin itself, but outside of it, from the circulus iridis minor, which lies on the anterior surface of the iris (*c*, Fig. 65), and which, as embryology shows (see page 267), gives off the vessels for the pupillary membrane.

Fig. 66.—Congenital Coloboma of the Iris. Enlarged 2×1.

The pear-shaped pupil is encompassed by the sphincter, which grows more and more narrow below, so that at the lowest part of the coloboma it is no longer visible; on the other hand, the black fringe belonging to the retinal pigment of the iris is here proportionately broader. The contraction-furrows of the iris are only present in its upper part.

2. *Coloboma* Iridis.*—Congenital coloboma of the iris is always situated below. The pupil is continued downward to the margin of

* From κολόβωμα, mutilation.

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

the cornea, growing narrower all the time, so that it has a pyriform shape with the apex at the lower margin of the cornea (Fig. 61). The sphincter lines the margin of the pupil together with the coloboma as far as the apex of the latter. Congenital coloboma is thus distinguished from the artificial one made by iridectomy. In the latter the sphincter is wanting in the course of the coloboma, because it has been excised; it is seen to end with sharp edges at the boundary between pupil and coloboma (cf. Fig. 161, *a* and a_1). Coloboma of the iris is very frequently combined with coloboma in the chorioid and in the ciliary body (see § 81), and sometimes also with a small indentation of the edge of the lens (coloboma of the lens) at the spot corresponding to the coloboma in the iris.

3. *Irideremia* (*aniridia*).—The iris may be wanting either altogether or all except a small residual portion. This defect is frequently complicated with congenital opacities in the cornea or in the lens.

4. *Ectopia Pupillæ.**—Even in the normal eye the pupil is not precisely in the center, but is usually placed a little below and to the inner side of it. While usually this can be noticed only upon careful examination, there are cases in which the displacement is so great as to be obvious at once; indeed, the pupil may be situated quite excentrically, in the neighborhood of the corneal margin. The displacement has been observed to occur in different directions, and is frequently complicated with a corresponding dislocation of the lens (ectopia lentis).

The congenital anomalies above described are found, for the most part, on both sides. They are apt to be inherited, so that they are frequently found in several members of the same family; they are often also met with in conjunction with other congenital anomalies. For the latter reason the disturbance of sight is often much more considerable than would be expected from the optical conditions. In such eyes there frequently exists very great myopia, hypermetropia, or astigmatism, or deficient development of the retina or of the whole eye itself, the latter being considerably smaller than usual (microphthalmus).

Persistent pupillary membrane is of comparatively frequent occurrence in new-born infants, but afterward disappears, except in the few cases in which remnants of it persist during the whole life. The brown filaments stretching from the pupil to the capsule of the lens are blood-vessels which have been obliterated and enveloped in pigment. They do not hinder the free movement of the pupil. Moreover, under atropine the pupil dilates ad maximum without suffering any change in its roundness, because the filaments are so extremely extensible. In this fact is presented a further mark distinguishing the pupillary membrane from the synechiæ acquired through inflammation.

Congenital *coloboma* of the iris occurs under different forms. Besides the pear-shaped colobomata above described there are sometimes observed some in which the pupil has the shape of a key-hole, as in artificial coloboma. A special

* Also called *corectopia*, from κόρη, pupil, ἐκ, out of, and τόπος, place.

variety is the bridge coloboma. In this the pupil is separated from the coloboma by a narrow thread of iris-tissue, which stretches like a bridge from one pillar of the coloboma to the other. Incomplete colobomata are of comparatively frequent occurrence; there is then simply a shallow indentation of the pupillary margin, or the portion of the iris corresponding to the coloboma is distinguished by a different color, which is generally due to the absence of the anterior layers of the iris at this point.

Cataract, and generally cataract of a complicated, inoperable character, frequently develops in eyes affected with coloboma of the iris. If I may be allowed to judge from one case whose course I have myself observed, this is effected in the following way: The retina, which is adherent to the margin of the coloboma, undergoes the same sort of traction that it does when adherent to a scleral cicatrix (see page 225). In consequence of the traction, detachment of the retina takes place—at first only at the edge of the coloboma, but afterward in the whole extent of the retina. The clouding of the lens, then, is to be regarded simply as the consequence resulting in the usual way from the total detachment of the retina.

The formation of a coloboma is accounted for upon the ground of incomplete closure of the fœtal ocular fissure; but, as this lies at the lower side of the eyeball, congenital colobomata are likewise directed downward. (For a more precise account, see under Colobomata of the Chorioid, § 81.) This explanation, of course, does not apply to those extremely rare cases of congenital colobomata which are not situated below. I myself, a short time since, saw a congenital coloboma of the ordinary pear-shape, which was directed upward.

In regard to the frequent congenital anomalies in the coloration of the iris, see § 57.

CHAPTER VI.

DISEASES OF THE CHORIOID.

I. Inflammation of the Chorioid.

78. Inflammation of the chorioid (chorioiditis) produces exudates which, as in the case of every other inflammation, may either disappear again by resorption or may go on to suppuration. Hence we distinguish between chorioiditis non-suppurativa, commonly known as chorioiditis exudativa, and chorioiditis suppurativa. If the inflammation



Fig. 67.—Chorioiditis Disseminata. (After De Wecker.)

That the chorioiditis has attacked a myopic eye can be recognized from the atrophic crescent which incloses the papilla upon the temporal side. The crescent is sharply defined by the scleral ring on the side of the papilla, and by the pigment ring on the temporal side, and shows everywhere remains of the chorioidal vessels and also of pigment. The chorioiditic foci occupy chiefly the equatorial parts of the fundus. They are white, with a lining of pigment of greater or less width; many also have spots of pigment in their interior. The retinal vessels are perfectly distinct as they pass across the spots and their pigment—i. e., they lie in front of the latter.

remains confined to the chorioid proper, as is especially apt to be the case in the non-suppurative forms, all exterior signs of inflammation are absent. The eye looks normal externally, and the disease manifests itself to the patient only through the disturbance in sight—to the physician, only through ophthalmoscopic examination. But if the disease passes over to the anterior portion of the uvea it becomes recognizable exteriorly through the symptoms of cyclitis and iritis (*irido-*

chorioiditis). This extension of the disease forward is the rule in violent inflammations, and hence in the suppurative forms.

A. Chorioiditis Exudativa (*non-suppurativa*).

Symptoms.—Exudative chorioiditis appears for the most part under the form of isolated foci of inflammation scattered over the chorioid (Figs. 67 and 68). While still recent they appear, when seen with the ophthalmoscope, as yellowish, indistinctly outlined spots which lie beneath the retinal vessels upon the red fundus oculi. The yellow matter is the exudate, which hides the red of the normal chorioid. In proportion as the exudate disappears by resorption the chorioid again comes into view, but in an altered state; it is atrophic, deprived of its pigment, and in part converted into cicatricial connective tissue. Hence, after the disappearance of the yellow exudate, the diseased spot is seen to become of a lighter color. Where the chorioid has grown altogether atrophic, a white spot exists, because the white sclera is seen through it; in other cases remains of the vessels and of the pigment are recognized in the white cicatrix. Afterward the pigment often proliferates, so that the chorioiditic spots appear lined with black pigment or covered with black spots (Fig. 67). The decolorized or pigmented spots remaining after chorioiditis may properly be characterized as cicatrices of the chorioid.

It is easy to see that the retina, which directly adjoins the chorioid, is also sympathetically affected in those spots where the chorioid is diseased. If the implication of the retina is particularly prominent, we speak of retino-chorioiditis. Moreover, the exudates from the chorioid pass not only into the superimposed retina, but also through the latter into the vitreous. Opacities of the vitreous thus produced are hence an almost constant accompaniment of chorioiditis.

It is the implication of the retina and vitreous which causes *disturbances of vision* of various kinds, and thus directs the patient's attention to the eye. The vision is diminished as a whole on account of the cloudiness of the vitreous and the hyperæmia of the retina. But in those spots in which inflammatory foci exist, sight may be entirely abolished, so that insular defects (scotomata) are present in the field of vision (see page 25). Owing to the fact that the retina over the focus of inflammation is pushed forward and its elements are brought out of their normal situation, objects whose images fall upon the retina may appear distorted (metamorphopsia); straight lines, for instance, appear bent in various directions. As long as the inflammation is recent, symptoms of irritation of the retina manifest themselves; subjective sensations of light (photopsia) exist, such as spots before the eyes, sparks and balls of fire, etc. These phenomena cause the patient annoyance and anxiety, sometimes to an extreme degree. When, after the subsidence of the inflammation, atrophy of the chorioid and of the

superimposed layers of the retina has taken place, the phenomena of deficiency—i. e., gaps in the field of vision—take the place of the phenomena of irritation. The influence which the scotomata exert upon the sight in general depends primarily upon the place they occupy in the fundus. Peripherally situated scotomata cause but little disturbance of vision, even when they are pretty numerous; and if they occur only in one or two places they usually escape the patient's notice altogether. On the other hand, when a scotoma occupies the site of the yellow spot the disturbance of vision is as great as in the preceding case it is trivial; direct vision is then destroyed, and the eye becomes unserviceable for fine work. The first case would be met with in the chorioiditis represented in Fig. 67, the second in Fig. 68.

The *course* of the chorioiditis is chronic, it taking many months for the foci of exudation to be converted into atrophic spots. The opacities of the vitreous last even longer—often, in fact, permanently. But chorioiditis is chiefly dangerous because of its tendency to recur, in consequence of which new foci of inflammation are constantly developing in the chorioid, so that the latter is finally covered all over with old and recent spots. With this is ultimately associated atrophy of the retina and optic nerve, so that obstinate cases of chorioiditis terminate in partial or total blindness. When the affection of the chorioid is well advanced, cloudiness of the lens (cataracta complicata) is almost always associated with it.

Etiology.—Exudative chorioiditis is a frequent disease, which is observed at all ages. Among its most ordinary causes is syphilis, both acquired and hereditary. As a result of the latter, cases also of congenital chorioiditis have been observed. Chorioiditis may also be caused by general disorders of nutrition of various sorts, such as anæmia, chlorosis, scrofula, etc. In many cases of chorioiditis the cause remains obscure.

Myopia is frequently complicated with changes in the chorioid, it being only a rare exception to find the latter normal in myopia of a high degree (Fig. 68). The changes in the chorioid in this case are, to be sure, less those of a chorioiditis proper than those of a primary atrophy of the chorioid, caused by the stretching which the latter must necessarily undergo, when the entire posterior segment of the sclera bulges backward, as is the case in extreme myopia.

Treatment.—The *treatment* of chorioiditis must have regard mainly to the etiological factor. When this is readily amenable to therapy, as is the case with syphilis, favorable results are promptly attained—in fact, syphilitic chorioiditis offers the best prognosis, inasmuch as by an energetic antisyphilitic treatment speedy improvement in most cases, and often even an entire cure, can be obtained. To be sure, we are not able to prevent the frequent recurrences which may still lead ultimately to the destruction of the eye.

The treatment of the local changes must be based upon the production of a rapid resorption of the exudate in the chorioid and the retina and also in the vitreous. Suitable remedies for this purpose are the iodide of potassium or, when necessary, a treatment by inunction, which, even in non-syphilitic cases, can do good service through its absorptive action; furthermore, diaphoresis by means of pilocarpine or sodium salicylate. In marked hyperæmia of the fundus, bloodletting may be performed by the application of six to ten leeches behind the mastoid process. With this is enjoined what is called the "regimen of the eyes"—that is, the avoidance of any straining of the eyes, and the protection of them from light by dark glasses or, when necessary, by rest in a darkened room.

The distinction between recent exudates and old atrophic spots in the chorioid is based upon the following signs: Exudates are of a yellow or yellowish-white color, do not have a sharp outline, and present to view no chorioidal vessels; retinal vessels, which by chance run over them, show by their bending that a projection of the retina exists here, due to the prominence formed by the exudate. The atrophic spots are pure white, and have an irregular but sharp outline, often formed by a pigmented band. Pigment-spots also lie in the white spot itself; sometimes, indeed, the growth of pigment becomes so excessive that the spots finally become entirely black. Moreover, remains of the chorioidal vessels are visible within the atrophic area. They not infrequently present thickened, white-looking walls, or are even quite obliterated and converted into light-colored cords.

There are cases in which the atrophy affects only the pigment-epithelium, which gradually disappears. Then the stroma of the chorioid, with its vessels and pigmented intervascular spaces, is exposed to view, and there is developed the picture of a tessellated fundus (Fig. 68), such as is also observed as a physiological condition. Besides occurring in certain forms of chorioiditis, this also occurs in glaucoma, in myopia of high degree, in retinitis pigmentosa, etc. In old people, quite small, brilliantly white spots, often surrounded by a dark fringe, are sometimes found in the chorioid. They correspond to acinous outgrowths of the lamina vitrea of the chorioid, over which the pigment-epithelium has undergone destruction.

Chorioiditis occurring in *isolated foci of inflammation* is distinguished, according to the location of the latter, into different forms:

1. *Chorioiditis centralis* is characterized by the deposition of a mass of exudate directly in the region of the macula lutea, and thus causes a central scotoma. The most frequent course of it is myopia, which, if of high degree, leads late in life, almost without exception, to changes in the yellow spot, which are mainly of an atrophic nature (Fig. 68). Inflammatory changes at this spot are often found in syphilis, and also after injuries—especially contusions—of the eyeball. Finally, a disease of the macula is observed in old people, which usually affects both eyes about equally, and is referable to senile changes.

2. *Chorioiditis disseminata* is characterized by numerous round or irregular spots which are scattered over the fundus (Fig. 67). This is an eminently chronic form, in which, in the usual course of events, new spots are being formed all the time. Ultimately, the chorioid is studded all over with such spots,

which in many places become confluent, so that in old cases a great extent of the fundus often looks whitish. The sight may, nevertheless, still be pretty good, if only the region of the macula lutea remains intact. In the beginning of the disease hyperæmia of the retina and optic nerve exists, but later both become atrophic. The papilla takes on a dirty grayish-red color and loses its sharp outline (chorioiditic atrophy), the retinal vessels are fewer and are greatly contracted. A special form of chorioiditis disseminata is the chorioiditis areolaris, first described by Förster. In this the first foci developed in the vicinity of the yellow spot, while the subsequent ones make their appearance at a constantly increasing distance from the latter. The most recent foci, therefore, are always those situated at the periphery. The behavior of the individual spots is directly the reverse of the ordinary course of chorioiditic patches; the most recent spots are entirely black, and afterward grow slowly larger, and at the same time become decolorized from the center toward the edge, so that at last they are almost entirely white.

3. *Chorioiditis anterior* deposits its foci of exudation at the periphery of the chorioid. These foci are therefore readily overlooked if we neglect to examine the most anterior portions of the fundus with the ophthalmoscope. Chorioiditis anterior is quite frequent, and is sometimes combined with a chorioiditis surrounding the papilla. In young persons, chorioiditis anterior often occurs in consequence of hereditary syphilis; usually the periphery of the fundus is studded with roundish, ink-black spots (see page 180). In old people, simple pigmentary changes are frequently found in the anterior portions of the chorioid.

The variety of chorioiditis which is spread *diffusely* over the whole chorioid is always combined with a coincident affection of the retina, and is therefore ordinarily known as retino-chorioiditis or chorio-retinitis. In the typical fashion in which it was first described by Förster this occurs in syphilis. In recent cases the retina appears clouded, and, furthermore, the entire fundus is veiled by a fine punctate cloudiness of the vitreous; moreover, circumscribed exudates may also be present in the chorioid and the retina. In the later stages the cloudiness of the retina disappears, to be replaced by atrophy; at the same time a migration of pigment under the form of numerous black spots takes place into the retina, especially at its periphery, so that there is produced a picture very similar to that of retinitis pigmentosa.

The changes in the chorioid in *myopia* consist in an atrophy of the chorioid close by the papilla and in foci of disease at other spots of the chorioid, particularly in the region of the macula lutea.

(*a*) Atrophy of the chorioid at the border of the optic disk is given the name of *staphyloma posticum*. This properly denotes a protrusion of the sclera backward; it is, however, used in a wider sense for the atrophy of the chorioid, which is the consequence of this protrusion. First, there appears at the external side of the papilla a narrow, light-colored crescent—the atrophic crescent (Fig. 67). Afterward this spreads out so as to assume the form of a cone or a triangle with a blunt apex—conus (Jäger). Finally, the atrophy passes from the outer side of the optic nerve along its upper and lower margin to its inner side also, so that the papilla is finally surrounded on all sides by atrophic chorioid (annular staphyloma, Fig. 68). This is generally broadest on the external side, from which it started. In the atrophic area the fundus is either a pure white, if the chorioid there has completely disappeared and the sclera comes

into view, or remains of chorioidal tissue, such as vessels and pigment, are still present in it in varying quantity (Fig. 68).

Sometimes two or even three contrasting zones exist in the staphyloma, which differ from each other in their pigmentation, and which bear witness to the fact that the formation and enlargement of the staphyloma have taken place at different periods. By proliferation of the pigment, brown or even black crescents are formed. The line separating the staphyloma from the healthy cornea is often sharply defined, especially if formed by a pigmented margin

FIG. 68.—FUNDUS IN MYOPIA OF HIGH DEGREE. (IN PART AFTER WECKER.)

The papilla is oblong-oval and has a physiological excavation to the outside of the point of entrance of the retinal vessels. It is surrounded by atrophic chorioid, the staphyloma posticum. This is very broad on the temporal side, and there consists of two divisions; the outer, more pigmented one, showing with especial distinctness the remains of the chorioidal vessels. On the nasal side, the staphyloma is narrower, is lined by a fringe of pigment, and is of irregular contour. In one of the outlying portions is noticed a posterior ciliary artery which enters the chorioid from the sclera. The rest of the fundus is tessellated in such a way that the vascular network of the chorioid is clearly recognized. The region of the macula lutea is occupied by chorioiditic changes, consisting partly in an overgrowth of pigment (the small, black specks), partly in atrophy (the white patches).

(Fig. 68). In other cases a sharp border-line is absent, a circumstance which indicates that the staphyloma is in process of growth, so that an advance in the myopia is to be apprehended. In the case of pretty large staphylomata the papilla looks reddened and displays an elliptical shape, the short axis of the ellipse coinciding with the largest diameter of the staphyloma. Accordingly, when the staphyloma is broadest to the outside, as is usually the case, the papilla forms an upright ellipse (Fig. 68). This change of shape must be in part referred to the fact that the papilla, being pushed back at one side, is seen in perspective foreshortening; but in part also to the fact that the chorioid, which on the outer side has moved away from the margin of the papilla, has been drawn over it on the inner side (Weiss; see § 145).

The size of the staphyloma is, broadly speaking, in direct proportion to the degree of myopia, but variations from this rule very often exist in the individual cases—e. g., great myopia without atrophy of the chorioid, and vice versa. Not infrequently staphylomata are also found in emmetropic and even in hypermetropic eyes.

White crescents are also observed at the *lower* border of the papilla. These resemble in their appearance the acquired crescents due to myopia, but have an altogether different significance. They are congenital (probably being connected with the fœtal ocular fissure, which likewise lies on the lower side of the eyeball), and are associated frequently with astigmatism, almost always with incomplete acuity of vision.

With the annular staphyloma of the myopic eye should not be confounded cases of atrophy of the chorioid about the papilla from other causes. Under this latter head belong atrophy after chorioiditis, and also the atrophy in cases of glaucoma, the so-called halo glaucomatosus.

(*b*) The changes of the chorioid in the region of the *macula lutea* make their appearance when the myopia has reached a high degree. Both light-colored and pigmented spots are found, and not infrequently also white branched lines (Fig. 68). The spots gradually enlarge, and finally coalesce to form pretty large atrophic patches, which may even ultimately become united with the staphyloma surrounding the papilla. In such cases of extreme myopia, almost the entire posterior section of the interior of the eye is converted into a great white patch. Moreover, hæmorrhages occur in myopic eyes, and that, too, preferably at the site of the yellow spot. It is the changes in the macula lutea which, with the detachment of the retina, represent the greatest danger for the extremely myopic eye. They do not, like detachment, threaten the eye with complete blindness, but they render it unserviceable for any sort of fine work. Besides, they are much more frequent than detachment of the retina, inasmuch as only a few of the excessively myopic attain any considerable age without being affected with these changes.

Bloodletting. — In recent cases of chorioiditis with hyperæmia of the retina the abstraction of blood is recommended above, and that by the application of leeches behind the mastoid process. While bloodletting has pretty much disappeared from general practice, in ophthalmology it has remained in use up to the present time, and rightly, too, since in suitable cases striking and undeniable advantage is often seen to accrue from it. The abstraction of blood may be made with natural leeches or with Heurteloup's artificial leech. In the former case, six to ten leeches are applied; in the employment of the Heurteloup, its glass cylinder is filled once or twice with blood. The point of application is either the temple or the skin behind the mastoid process. If we are dealing with inflammations of the conjunctiva, the iris, or the ciliary body, the temple is selected, because the vessels of the conjunctiva empty into the veins of the face, and, moreover, the anterior ciliary veins communicate freely with the veins of the conjunctiva. In deep-seated affections, like chorioiditis, retinitis, neuritis, or inflammation in the orbit, the abstraction of blood is performed behind the mastoid process, because an emissary vein of Santorini (passing through the mastoid foramen), which carries off blood from the transverse sinus, empties here; and the latter is connected with the cavernous sinus, into which the ophthalmic veins pour their contents.

Non-purulent *irido-chorioiditis* runs either a chronic or an acute course. The chronic cases have already been considered under the head of iritis idiopathica; they are the ones which are known under the name of irido-chorioiditis serosa, and which gradually induce blindness, partly through seclusio pupillæ, partly

through degeneration of the vitreous (see page 287). The acute cases (irido-chorioiditis plastica) form a transition between this and irido-chorioiditis suppurativa.

B. Chorioiditis and Irido-Chorioiditis Suppurativa.

79. In suppurative chorioiditis there is produced a large exudate containing numerous cells, which is deposited beneath the retina and into the vitreous, where it can be seen through the pupil, in case the media are transparent enough, as a deeply situated yellow mass. The inflammation, which is violent, almost always spreads rapidly to the ciliary body and the iris, so that we have then to do with an irido-chorioiditis, which is associated with correspondingly violent external symptoms of inflammation.

Symptoms.—When the irido-chorioiditis is at its height the lids are markedly swollen with œdema; the conjunctiva is intensely reddened and likewise very œdematous, so that it often forms a chemotic swelling round the cornea. The latter is dull, and has a slight diffused cloudiness. The aqueous, too, is cloudy, and shows a hypopyon deposited at the bottom of the anterior chamber. In the iris are found signs of a violent inflammation, such as discoloration, swelling, and posterior synechiæ. If the cloudiness of the cornea and the aqueous permits, a yellowish reflex is recognized in the pupil, arising from the exudate behind the lens. Simultaneously with these appearances violent pains exist in the eye and its vicinity, sight is completely lost, slight fever is often also present.

The *course*, in the less violent cases, is of such a character that after a few weeks the inflammatory symptoms gradually abate. The eye, whose tension in the beginning was elevated through the great amount of exudation, becomes softer and soon smaller also, and at length passes into a state of atrophy. But in the violent cases *panophthalmitis* develops through an extension of the inflammation to the tissues surrounding the eyeball. The œdema of the lids increases so much that the eye can scarcely be opened. The eyeball, in addition to the appearances of irido-chorioiditis above described, displays marked protrusion (exophthalmus) combined with abolition of its motility. The pains are almost intolerable, and tormenting photopsiæ are not infrequently present. High fever exists and vomiting frequently occurs, especially at the beginning of the disease. These symptoms keep on until the purulent exudation in the interior of the eye makes an exit for itself by breaking through the sclera. Perforation takes place in the anterior division of the sclera. The conjunctiva is seen to bulge forward at some spot, showing the yellowish, discolored sclera through it, until finally sclera and conjunctiva are perforated and the purulent contents of the eyeball are slowly extruded. After perforation has occurred the pains soon cease, the eye becomes softer, and ultimately

shrinks up to a small stump (*phthisis bulbi*). It takes at least six to eight weeks for this result to be attained and for the eye to become perfectly free from pain.

From what has just been said, panophthalmitis is distinguished from simple suppurative irido-chorioiditis by the appearance of two additional symptoms—protrusion of the eyeball and purulent perforation of the envelopes of the eye. The protrusion is due to the extension of the inflammation to the retro-bulbar tissues, and particularly to Tenon's capsule; the result is marked inflammatory œdema (but not suppuration) in this spot, and a consequent pushing forward of the eyeball. The violent pains are excited by the traction which the nerves undergo, both in the eyeball itself, which is distended with exudate, and also within the orbit, where it is due to the protrusion of the eyeball.

Etiology.—Chorioiditis suppurativa is produced by the infection of the chorioid by pyogenic matter. The infection may originate from the outside or have its source in the body itself.

Infection *from the outside* (*ectogenous infection*) occurs—

(*a*) Most frequently from penetrating injuries of all kinds. In this category belong unsuccessful operations.

(*b*) From the progression inward of suppuration from without, in the case of perforating ulcers or abscesses of the cornea, and from prolapses of the iris that are covered with pus.

(*c*) As a process starting from a cicatrix of the cornea with inclusion of the iris, when the cicatrix is thinned. Under this head belong the incarcerations of the periphery of the iris, which not infrequently remain after cataract operations. Infection takes place in these cases from the germs penetrating through the thin cicatrix into the interior of the eye, its development being particularly favored by sudden stretching or bursting open of the cicatrix.

Infection by carriers of infection, which arise from the *organism itself* (*endogenous infection*), takes place—

1. Through embolism, septic substances from a focus of suppuration getting into the circulation and sticking fast in the vessels of the chorioid. In this way *metastatic chorioiditis* develops. This is one of the symptoms of pyæmia, most frequently of that form which makes its appearance in the puerperal period as puerperal fever.

2. By transfer of the inflammation from the meninges in meningitis, particularly in cerebro-spinal meningitis. These cases are observed chiefly in children, and are distinguished by their comparatively mild course, so that in rare cases some small degree of sight even is still retained.

3. By transfer of inflammation from behind forward in phlegmons in the orbit and in thrombosis of the orbital veins.

The *prognosis* of suppurative chorioiditis is absolutely unfavorable

for the eye itself, inasmuch as the sight, and, for the most part, the shape of the eye as well, are lost. In those cases in which the chorioiditis is simply one of the symptoms of pyæmia or meningitis, there is also, of course, danger for the life of the patient.

Treatment is unable to change the course of suppurative chorioiditis. It must confine itself to ameliorating the patient's sufferings. We combat the pain with moist and warm compresses and with narcotics. If we are sure that it is a case of panophthalmitis, we may open the eye by a free incision of the sclera in its anterior division. The tension is thus diminished, the evacuation of the suppurated contents of the eye is accelerated, and thus the pain and the course of the disease are cut short. When the eye at last becomes shrunken it usually remains quiescent, and also admits of an artificial eye being worn over it. Should, however, secondary inflammatory phenomena set in, as they may exceptionally do, in the shrunken eye, its enucleation is indicated.

Anatomical examination shows, in suppurative chorioiditis, dense purulent infiltration of the chorioid, which thus has its thickness increased to several times the usual amount. The retina over the affected part of the chorioid is also found infiltrated with pus-cells, and consequently thickened; afterward, it is partially or entirely detached from the chorioid by means of the purulent exudation. The vitreous is gradually converted into a homogeneous mass of pus. In metastatic chorioiditis the infecting plug in the chorioidal vessels can also frequently be demonstrated by microscopical examination (Virchow). Such emboli may also get into the retinal vessels, and then result in suppurative retinitis, which presents the same clinical picture in its course as suppurative chorioiditis. Since in metastatic affections of this sort infected emboli may occur within the blood-vessels in other parts of the eye also, it is best to comprise all these cases under the name of metastatic suppurative ophthalmia.

Metastatic ophthalmia is for the most part a complication of the severe cases of pyæmia, to which the patients usually succumb, so that in general it has an evil prognostic significance. Nevertheless, exceptional cases occur in which the pyæmia runs a relatively light course, and produces no demonstrable metastases besides those in the eye. Thus, after the extraction of teeth, complicated fractures, etc., unilateral and bilateral blindness have been observed, due to metastatic ophthalmia, without a localization of the pyæmic affection in any other quarter being demonstrable. In children, suppuration of the umbilicus, and sometimes also vaccination, may give rise to pyæmia with metastatic ophthalmia. Besides occurring in pyæmia, a suppurative chorioiditis, which is without doubt likewise of metastatic origin, also occurs in rare cases in other acute infectious diseases, as in typhus, variola, scarlet fever, malignant anthrax, influenza, and ulcerative endocarditis.

Most cases of *panophthalmitis* are caused by injury. If the latter is of such a character that the eye is extensively opened, the purulent exudate may be discharged through the wound, and does not have to wait till the sclera is perforated, which always requires a long time. Yet not infrequently even in these cases, in which the purulent exudate pushes out through the wound, perforation of the sclera by pus is also seen to take place as usual. Panophthal-

mitis after severe injuries must, from a certain point of view, be regarded as a more favorable outcome than a plastic irido-cyclitis. The former, to be sure, causes more violent pain and leads to a greater degree of swelling of the eye; but when it has run its course the patient has a lasting respite. Plastic irido-cyclitis, on the other hand, often for years has after-attacks of inflammation, and may also give rise to sympathetic disease of the other eye, if the patient does not make up his mind to the performance of enucleation at the proper time.

Apart from simple incision of the sclera, different methods have been attempted for cutting short the course of panophthalmitis, particularly enucleation and the ablation of the anterior section of the eye, with scooping out of the contents of the eyeball. Enucleation is to be rejected, for, devoid of danger as it is under other circumstances, in panophthalmitis it sometimes results in purulent meningitis, with a fatal issue. It must be assumed that by the operation the blood and lymph passages in the orbit are freely opened, and thus made accessible to infection. Whether the scooping out (exenteration or evisceration) of the suppurating eye is a less dangerous procedure is questionable, since cases of death after this operation have also been observed (Schulek). It must, however, be noted that some cases have been known in which fatal meningitis has succeeded a panophthalmitis without any operative interference.

Differential Diagnosis of Suppurative Chorioiditis.—There are cases of suppurative chorioiditis which might be confounded with neoplasms in the eyeball. This is possible whenever the inflammation runs so sluggish a course that all external signs of inflammation are wanting. The eye is not discolored, the iris is normal, the aqueous and lens are clear. The lens and iris are pressed forward by the exudation in the vitreous, and the anterior chamber is made shallower. The pupil is dilated, and permits the exudate to be seen deep down in the vitreous. Sometimes the exudate is even visible from a distance as a vivid, light-colored (whitish or yellow) reflex from the pupil (*amaurotic cat's-eye* [Beer]). Just the same phenomena may be produced by new formations in the vitreous, and particularly by gliomata arising from the retina (see § 100), for which reason many cases of the sort described above have been designated as pseudo-gliomata. The most important distinctive mark lies in the tension of the eye. This, in genuine glioma, is normal in the beginning, and afterward is increased; in pseudo-glioma, on the contrary, diminution of tension soon sets in, which precedes the shrinking of the eye. Then the subsequent course renders the true state of the case perfectly clear, inasmuch as glioma afterward breaks through the sclera and keeps on growing, while in pseudo-glioma the eye keeps constantly growing smaller. But now in glioma it is requisite to remove the eye as early as possible, and it is therefore not right to wait a long time in doubtful cases until the diagnosis can be determined with certainty. In so doing, we should be putting our patient's life in jeopardy. Hence, in doubtful cases, we perform enucleation. Even if it should then turn out that the case was one of pseudo-glioma, the patient has not lost much by the enucleation, since the eye is already blind and would be much shrunken. The question of a confusion with glioma, moreover, only comes up for consideration in such cases of sluggish suppurative chorioiditis when occurring in children, since it is only in the latter that glioma of the retina is found. The causes of pseudo-glioma are most frequently meningitis, also the acute exanthemata, and finally injuries, particularly those attended with the presence of a small foreign body in the inte-

rior of the eye. One or two cases of pseudo-glioma have turned out on dissection to be tuberculosis of the chorioid.

Atrophia et Phthisis Bulbi.—Both expressions are employed for diminution in size of the eyeball due to shrinking. We speak of atrophy when the diminution in size takes place slowly through the shrinking of exudates in the interior of the eye, as occurs chiefly in plastic irido-cyclitis. Under the name of phthisis bulbi we designate the rapid shrinking of the eyeball, due to suppuration of its contents and their evacuation through the perforated sclera, this being the issue of panophthalmitis. In atrophy the diminution in size is kept within moderate bounds, while in phthisis the eyeball may be reduced to the size of a hazel-nut, or less. In the atrophic eyeball the individual membranes, being still present, although in a very altered condition, are drawn upon by the shrinking exudate, and thus give rise to repeated attacks of inflammation and also to sympathetic disease of the other eye. In the phthisical eyeball the inner tunics of the eye have, all except some scant remains, been destroyed by suppuration; the small stump usually remains quiescent, and causes no danger to the other eye. An atrophic eyeball must therefore generally be enucleated, while a phthisical stump can usually be permitted to remain. In atrophy and in phthisis alike the optic nerve subsequently becomes completely atrophic, so that it ultimately forms a thin cord consisting simply of connective tissue. This takes place in consequence of the general law that nerve-trunks atrophy when their terminal expansions have been destroyed (ascending atrophy).

Detachment of the Chorioid.—This is frequently found in the dissection of enucleated eyes, while in the living eye it but rarely comes under observation. In shrunken eyes the chorioid—and the ciliary body, too—are very frequently found to be detached by the exudates which are present in the interior of the eye, and which exert a centripetal traction in all directions (*a a*, Fig. 62). A detachment of the retina, usually total, is never wanting in these cases. Since we are dealing with eyes which are already blind, the detachment of the chorioid has a practical interest only in so far as traction upon the ciliary nerves is produced by it; for this induces conditions of irritation in the blinded eye, and possibly sympathetic disease of the other eye.

It is a rare thing to see with the ophthalmoscope a detachment of the chorioid in an eye still capable of vision and with transparent media. Since the separated chorioid is covered by the retina, the detachment of the former manifests itself under the guise of a detachment of the latter, with the addition that we can recognize through the retina the characteristic branching of the vessels in the chorioid. If this symptom is wanting, the detachment of the chorioid can not be distinguished from a simple detachment of the retina. Separations of this sort can be caused by serous exudation or hæmorrhages beneath the chorioid, or by the development of a sarcoma in its external layers.

Rupture of the Chorioid.—This is produced through the action of a blunt instrument upon the eyeball (contusion). Immediately after the injury the blood extravasated into the vitreous usually prevents a clear view of the interior of the eye. After the absorption of the blood the rupture of the chorioid, which ordinarily lies in the neighborhood of the papilla, is discovered. Sometimes

there is only one, sometimes there are several lacerations. They form long, yellowish-white streaks, as the edges of the laceration in the chorioid separate from each other and allow the white sclera to be seen between them. The streaks generally have a curved shape, with the concavity toward the papilla; they are broadest in the center, and taper off to a sharp point at the ends. The edges of the light streaks have an irregular black coloration, due to the growth of the pigment. The retinal vessels run without any change over the streaks, a proof that the retina is unruptured.

II. Tumors of the Chorioid.

80. Among malignant tumors occurring in the chorioid is *sarcoma*, which in most cases is pigmented (melano-sarcoma). The clinical symptoms which sarcoma of the chorioid presents change so during the development of the tumor that four stages can be distinguished in the course of the disease.

In the *first stage* the tumor is small, and manifests itself only in ophthalmoscopic examination by detachment of the retina at the site of the tumor. The patient notices a disturbance of vision in the shape of a defect in the visual field, corresponding to the site of the tumor. Afterward the detachment of the retina becomes total (Fig. 69, *N*), and thus the eye, which externally still looks normal, becomes completely blind. In the further growth of the tumor a time occurs when increase of tension suddenly sets in. The sarcoma thereupon enters the *second stage* of its development—that of increased tension. Externally the eye presents the appearances of inflammatory glaucoma (§ 83). Marked injection of the eyeball exists, the cornea is dull and clouded, the anterior chamber shallow, the iris discolored, the pupil dilated and immobile, and the tension of the eye to palpation is considerably elevated. If the media are sufficiently clear, the gray reflex of the detached retina can be seen deep down behind the pupil. Later on, the lens becomes clouded, so that the clinical picture of glaucoma absolutum with cataracta glaucomatosa is produced. From the time when the symptoms of inflammatory glaucoma set in the patient suffers with pain; very frequently it is by this that he has his attention first called to his trouble. Since the picture presented by the affected eye corresponds completely to the complex of symptoms of



Fig. 69.—Sarcoma of the Chorioid. (After Leber.)

The tumor, *G*, rises out of the chorioid, *C*, which everywhere lies in contact with the sclera. The retina, *N*, on the contrary, is detached entirely from its bed under the form of a folded funnel. It retains its connection only with the papilla behind, and with the chorioid along the ora serrata, *O*, in front.

inflammatory glaucoma, the correct diagnosis in this stage is to be made with difficulty, or not at all.

The *third stage* is that of the growth of the tumor upon the outside. The symptoms are different, according as the tumor breaks through the sclera in its anterior or in its posterior division. In the former case, dark, hard prominences are seen developing in the circumference of the cornea, and the diagnosis can readily be made. If, however, the tumor first grows through the sclera posteriorly, the nodules of the tumor are invisible, and do not give evidence of their existence until afterward, through the gradually increasing protrusion of the eyeball (exophthalmus). As soon as the tumor has broken through the envelopes of the eyeball to a sufficient extent the pain usually abates, since the great tension in the eyeball then ceases. But, to make up for this, the extra-ocular masses of tumor, freed from the intra-ocular pressure that constrained them, grow so much the quicker. First the orbit is entirely filled by the tumor, afterward the latter projects from the orbit, as big as an apple or as the fist. From the orbit the tumor is continued to the neighboring parts, particularly to the brain. At its exposed portions the tumor ulcerates and gives rise to frequent hæmorrhages.

The *fourth stage* is that of the generalization of the tumor by the development of metastatic nodules in the internal organs, most frequently in the liver.

Years usually pass before the sarcoma has run through the four stages just pictured. The first and second stages last a long time, while afterward the growth of the tumor becomes continually more rapid. The patient dies either from exhaustion, in consequence of the suppuration and hæmorrhage from the tumor, or succumbs to the extension of the latter into the brain or to the metastases in the internal organs.

The *prognosis* of sarcoma of the chorioid is absolutely unfavorable for the life of the patient if the eye is not removed early. But even then the prognosis is by no means to be regarded as perfectly favorable. Apart from the fact that the eye itself in every case is lost, both local recurrences in the orbit and also metastases may develop even after its removal, the germs for their development having been already scattered abroad earlier, although, at the time when the eye was removed, they were too small to be demonstrable. Sarcoma of the chorioid is hence to be regarded as one of the most malignant of diseases—one which, in very many cases, ends in death. Sarcomata of the iris and ciliary body behave, in respect to their course and ultimate outcome, like sarcomata of the chorioid.

Sarcoma of the chorioid is a rare disease. It is found most frequently between the fortieth and sixtieth year; in childhood it is of extremely rare occurrence. This gives a means of distinguishing it

from the gliomata which spring from the retina, and which in part present symptoms like those of sarcomata, but which occur in childhood exclusively. A malignant neoplasm developing in the eyeball will, therefore, have to be regarded in all probability as a glioma in a child and as a sarcoma in an adult.

The *treatment*, as long as the neoplasm is still confined to the eyeball, consists in enucleation, which should be performed as early as possible. In doing it, we cut off the optic nerve as far back as possible, to meet the contingency of the degeneration having already passed over upon it. If the neoplasm has already grown out of the eyeball, everything diseased must be removed according to surgical rules. The surest method in this case is exenteration of the orbit—i. e., the removal of the entire contents of the orbit, together with the periosteum.

Sarcomata of the chorioid consist either of round cells or of spindle-cells, or are tumors made up of a mixture of both. They are almost always pigmented (melano-sarcomata); non-pigmented sarcomata (leuco-sarcomata) are among the rarities. Very often they contain many wide blood-vessels. Sarcomata develop from the external layers of the chorioid (layer of large and of medium-sized vessels) and grow inward toward the vitreous space, pushing the retina before them. In the beginning the retina lies everywhere in contact with the surface of the tumor, so that with the ophthalmoscope a sharply circumscribed gibbous detachment of the retina is found, beneath which often can be recognized the vessels of the chorioid or of the tumor. In this case the diagnosis of sarcoma is easily made. But afterward, probably in consequence of the disturbance of circulation in the chorioid produced by the tumor, an accumulation of fluid takes place between the chorioid and the retina. The latter is thus detached over a greater area than corresponds to the tumor, and does not permit the latter to be seen through it any more; ultimately, the detachment becomes total. In this stage, since the detachment of the retina has lost its characteristic appearance, the diagnosis can not for the most part be made with certainty. The tension of the eye affords one diagnostic point, being usually diminished early in simple serous detachment of the retina, while in detachment due to a tumor it is at first normal and afterward increased (Von Graefe). It is an additional argument for the existence of sarcoma if the anterior ciliary veins are found markedly dilated upon one side or the other. In this way these give evidence of the situation in the chorioid occupied by the sarcoma, which, in the area affected, prevents the blood of the anterior division of the uvea from flowing out through the vasa vorticosa, so that it must make its way through the anterior ciliary veins. At length the increase in tension reaches such a degree as to produce the complex of symptoms of inflammatory glaucoma. If the detachment of the retina is not already total, it gets to be so now, and the eye becomes completely blind. The point of time at which the glaucomatous attack sets in does not depend directly upon the size of the intraocular tumor. The increase in tension does not arise from the fact that the tumor occupies a certain space in the interior of the eye, for this call for additional space is compensated for by a corresponding decrease of the vitreous. The increase in tension is based upon the congestion which the tumor produces in the veins of the chorioid, and by which increased transudation of fluid takes

place into the interior of the eye. Elevated tension is, therefore, often seen with quite small tumors, while at another time the tumor may have already filled up a large part of the eye without exciting the symptoms of glaucoma. When the glaucomatous attack has set in, the eye looks as if it had been blinded by primary glaucoma, and the diagnosis can not be made with certainty. The existence of a sarcoma will be suspected if the patient states that the eye was already entirely blind before the outbreak of the inflammation, for in primary glaucoma blindness usually does not precede the attack, but follows it. Besides, we examine the second eye; if one eye is completely blinded by primary glaucoma, the second eye will rarely be found quite normal.

In rare cases the second (inflammatory) stage of formation of the tumor does not present the symptoms of glaucoma, but of a violent plastic iridocyclitis. As a result of this, the eye becomes softer and shrinks up so far as the tumor contained in it permits. The latter thus is retarded in its growth within the eyeball—a fact which does not prevent it from growing outside afterward, and producing metastases.

Perforation and growth upon the outside become manifest before the tumor has yet filled the whole interior of the eyeball, and are effected by the gradual growth of the cells of the tumor through the sclera, the cells usually following out preformed passages. We hence find the tumor growing out along the optic nerve and its sheaths, or utilizing the points where the anterior or posterior ciliary vessels or the vasa vorticosa emerge.

The metastases in remote organs arise through embolism. The blood-current detaches cells from the tumor and carries them into other parts of the body, where they develop into independent tumors.

Carcinomata and also adenomata have been observed as a great rarity in the chorioid, but only as secondary tumors, as metastases from carcinoma in other organs (especially in the thoracic glands).

Tuberculosis of the Chorioid.—In the chorioid, as in the iris, tuberculosis occurs under the two forms of disseminated and of solitary nodules. The diagnosis between them is made with the ophthalmoscope.

(*a*) *Disseminated* or *miliary* tuberculosis of the chorioid was first described by Jäger. Small maculæ of pale-reddish color are seen in the fundus, which even within a short period of examination—within a few days—grow distinctly larger and increase in number through the appearance of new maculæ. By this circumstance they are distinguished from the chorioiditic foci of inflammation, which change very slowly; besides, the pigment-changes, so frequent in chorioiditis, are wanting in tubercles of the chorioid. Ordinarily only a few such spots are present, although sometimes as many as twenty or thirty of them can be counted in the eye. Anatomical examination has proved that the spots seen with the ophthalmoscope correspond to nodules of a mean diameter of one millimetre, which possess the typical structure of tubercle nodules (Manz).

Miliary tuberculosis of the chorioid forms one of the symptoms of general miliary tuberculosis (Cohnheim). It has essentially a diagnostic interest; as in doubtful cases of acute miliary tuberculosis, it may assist in establishing the diagnosis. In chronic tuberculosis of the lungs, the intestine, etc., it is not ordinarily observed.

(*b*) *Solitary* or *conglobated* tubercle of the chorioid makes its appearance

under the form of a neoplasm. With the ophthalmoscope a rather large, light-colored tumor is seen in the chorioid; it is an argument for its tuberculous nature if smaller light spots (tubercle nodules) are found in the chorioid in its vicinity. The tumor may afterward grow through the sclera to the outside, and there break down. Anatomical examination shows that it consists of a great number of smaller miliary nodules, which have coalesced to form one pretty large tumor. In the center of the latter caseation takes place. The solitary form of tuberculosis of the chorioid is a very rare disease, pre-eminently affecting young people. It runs a chronic course, and accompanies chronic tuberculosis of the internal organs, especially of the brain. There are, however, cases in which, besides the tuberculous nodule in the eye, no focus of tubercle can be clinically demonstrated to exist in the organism.

The prognosis of solitary tubercle of the chorioid is bad, since the eye in any case is lost, and in most cases also life is endangered through the presence of tuberculous disease in other parts. The treatment consists in the enucleation of the eye, a procedure which is especially indicated in those cases in which the chorioidal tubercle appears to form the only tuberculous focus. Enucleation in this case has as its primary object the prevention of any further diffusion of the tuberculous virus.

III. Congenital Anomalies of the Chorioid.

81. Coloboma of the Chorioid.—In this affection the ophthalmoscope shows a brilliant white area in the red fundus below the optic-nerve entrance. This area is oval or obtusely triangular, and has sharply defined edges, often colored dark with pigment. Within the area of the coloboma, which is depressed below the level of the rest of the fundus, may be recognized some vessels and pigment (Fig. 70).

Coloboma of the chorioid is a circumscribed defect in the chorioid and retina, in the confines of which the sclera lies exposed, and is hence visible as a white surface. Coloboma of the chorioid is frequently found along with coloboma of the iris, and also with other anomalies of the eye. Such eyes are often smaller than usual (microphthalmus). Sometimes, indeed, eyeballs are found which are only as large as a pea or a millet-seed, and which lie entirely in the back part of the orbit, and are not discovered in an examination made upon the living subject. In this way absence of the eye (anophthalmus) is simulated. Whether a true anophthalmus—i. e., a condition in which, while the orbit is present, there is not even a rudiment of the eyeball—does occur or not, has not so far been determined.

The eyesight suffers in coloboma of the chorioid because, in the first place, the coloboma corresponds to a defect in the visual field. Moreover, even the direct visual acuity is usually defective because the eye, as a whole, has had its development deranged. In the higher degrees of microphthalmus the sight is reduced to the mere differentiation of light from darkness.

Coloboma of the chorioid is in a marked degree transmissible by

inheritance, and that, too, not infrequently in conjunction with other congenital malformations of the body.

Even the smallest colobomata are much larger than the optic disk; and the large colobomata are so extensive that their anterior border can no longer be seen with the ophthalmoscope, because it lies too far forward. So, too, they may extend so far backward that they involve the papilla. The latter, in that case, is generally changed in shape and appearance—sometimes so much so that its situation is recognized only through the intimation afforded by the place of origin of the retinal vessels. The surface of the coloboma lies deeper than the rest of the fundus, and often shows channeled depressions or prominent ridges.

FIG. 70.—LOWER HALF OF AN EYE WITH CONGENITAL COLOBOMA OF THE IRIS, CILIARY BODY, AND CHORIOID.

In the iris, whose posterior surface is seen in the figure, is recognized the prolongation of the pupil, running out in a sharp point to the lower ciliary margin. In the corresponding spot, the ciliary processes are wanting; the processes immediately adjoining this gap are higher and longer than the rest, and, as they diverge backward, inclose a triangular, very darkly pigmented area. Still farther backward there exists in the wall of the eyeball a deep excavation of oval form, whose edges are sharply defined and in part overhanging. Upon the floor of the excavation is seen the sclera, covered simply by a very thin, transparent pellicle, in which run several vessels. The posterior pole of the oval formed by the coloboma of the chorioid is directed toward the fovea centralis, *f*.

The vessels which are seen in the coloboma are partly those which belong to the retina, and which pass with it over the coloboma, partly those originating in the latter itself. The latter must be regarded as posterior ciliary vessels.

In rare cases large, white, depressed areas have been observed not below, but to the outside, of the optic nerve, in the region of the yellow spot. These have likewise been looked upon as congenital malformations—colobomata of the macula.

The formation of colobomata occurs also in the optic nerve. Either a deep depression is found in the lower part of the latter or the entire optic-nerve entrance is enlarged to several times its usual size, and the vessels coming out from it are, as it were, forced apart. Colobomata of the optic disk are met with either alone or in conjunction with colobomata of the chorioid. The congenital crescents on the lower side of the disk, which are the usual concomitant of congenital amblyopia (see page 318), should also probably be regarded as rudimentary colobomata of the optic disk.

Anatomical examination of an eye affected with coloboma of the chorioid shows externally a protrusion of the sclera, situated below the optic nerve, the scleral protuberance first described by Ammon (see page 228). Corresponding to this, in the inner membranes of the eye, is the coloboma visible with the ophthalmoscope (Fig. 70). Within this, microscopical examination reveals, for

the most part, only a thin pellicle composed of connective tissue, the remains of the fused chorioid and retina. The origin of such a coloboma is referable to the fœtal ocular fissure. This exists at the lower side of the secondary ocular vesicle—the flask-shaped structure of the embryonic eye—and is designed for the admission of the mesoderm into the interior of this structure (Fig. 57, see page 266). Later on, this fissure ought to close again without leaving any trace of its presence. But if the closure takes place incompletely, a coloboma is formed. The walls of the retinal fissure, in this case, do not grow together directly, but are connected by thin, intermediate tissue. In consequence of the patency of the retinal fissure, the growth of the chorioid over the external surface of the retina is interfered with, so that at the site of the fissure retina and chorioid alike are wanting, or are replaced by connective tissue. Lastly, the development of the sclera, too, fails to take place in normal fashion in the affected spot; it is thin and yielding here, and bulges out beneath the intra-ocular pressure, and in this way the posterior scleral protuberance originates. The original site of the coloboma is hence in the retina, and the disturbance of development in the adjacent chorioid and sclera is consecutive. The fœtal ocular fissure is furthermore continued as a furrow upon the pedicle of the ocular vesicle, which is afterward the optic nerve. By incomplete closure of this furrow the colobomata of the optic nerve are formed.

Coloboma of the iris is to be explained as a derivative of coloboma of the chorioid. The iris grows out from the anterior margin of the rudimentary chorioid at a time when the fœtal ocular fissure is already closed; hence the iris in no stage of its development has a fissure. But when the chorioid suffers a derangement of development at the site of the retinal fissure, this derangement may be transmitted to the iris, which will hence fail to grow out in normal fashion from the chorioid at the affected spot. Hence the iris here is wanting (coloboma of the iris). This condition may persist, even if the fissure in the retina and chorioid afterward closes completely, so that then a coloboma of the iris is produced without a coexisting coloboma of the chorioid.

In many cases the incomplete closure of the ocular fissure entails still more serious derangements. The intermediary tissue closing in the fissure bulges out into quite a large sac, which is appended to the eyeball, while the latter itself is retarded in its development, and is much smaller than usual (microphthalmus). The tissue connecting the sac and the eyeball may become elongated and at the same time contract into a thin cord, so that finally we have a large bladder to which the eyeball, reduced to the size of a pea, or even less, is attached by means of a long pedicle. In this manner those cases originate in which there is apparently anophthalmus, and at the same time a dark, transparent cyst is formed in the lower lid (Arlt).

The explanations of the origin of colobomata contain much that is yet hypothetical and unaccounted for. Moreover, there is no unanimity of opinion as to the real cause preventing the regular closure of the ocular fissure—whether there is a simple arrest of development, or whether an inflammation in the region of the fissure is accountable for it. Still smaller is our knowledge in regard to the origin of colobomata in the macula lutea.

Albinism consists in the absence of the physiological pigment. Albinos have yellowish-white flaxen hair and also white eyebrows and lashes. The iris is light gray, and appears reddish by transmitted light, while the pupil has a

vivid red luster. With the ophthalmoscope the blood-vessels of the retina and chorioid are seen with perfect distinctness running upon the almost white fundus, with which the papilla is contrasted by its dark, grayish-red color. Albinotic eyes are photophobic, and hence see better in the dusk; their visual acuity is always reduced; and nystagmus, frequently combined with a pretty high degree of myopia or with strabismus, is constantly present. Albinism is congenital and often inherited. In albinotic eyes the pigmentiferous cells of the uvea and the retina are present, just the same as in the normal eye, only they contain no pigment. All sorts of transition forms exist between complete albinism and normal pigmentation.

CHAPTER VII.

GLAUCOMA.

General Considerations.

82. The essence of glaucoma lies in the *increase in the intra-ocular pressure*, from which all the other essential symptoms of glaucoma can be deduced (Von Graefe). In one series of cases the increase in pressure sets in without our being able to discover any reason for it in an antecedent disease of the eye (*primary glaucoma*). In other cases, on the contrary, the increase in pressure is the result of some other disease of the eye (*secondary glaucoma*). Primary glaucoma, accordingly, has increase in tension as its first and most important symptom, from which all the rest of its phenomena arise—it is glaucoma proper, the glaucoma par excellence. In secondary glaucoma, on the contrary, the increase in tension is only a consequence of other pathological conditions—is an accessory, as it were. The clinical picture of secondary glaucoma, therefore, is exceedingly polymorphous, varying according to the different affections which form the basis of it. While genuine or primary glaucoma always affects both eyes, although not always at the same time, secondary glaucoma remains confined to the eye which, through being diseased, has given rise to the increase in tension.

The *consequences* of increase of tension, inevitably occurring if it lasts a long time, are excavation of the optic nerve, and reduction, with ultimate annihilation, of the sight.

Excavation of the optic nerve is dependent upon the recession of the lamina cribrosa. By the latter we understand that part of the sclera which lies at the point of entrance of the optic nerve into the eye, and which is perforated by numerous foramina designed for the passage of the bundles of fibers of the nerve (Fig. 9). The lamina cribrosa is that part of the fibrous tunic of the eye (corneo-sclera) which has the least tenacity, and hence gives way first to increased ocular pressure, which it does by bulging backward. But at the same time the optic-nerve fibers, set in the foramina of the lamina cribrosa, also recede, so that the surface of the optic nerve itself sinks back (*e*, Fig. 71 *B*). Upon ophthalmoscopic examination the papilla appears depressed below the level of the adjacent fundus—slightly at first, afterward a good deal—so that the margins of the papilla dip down steeply, or are even overhanging. This condition is recognized chiefly by the bending or actual

interruption of the blood-vessels at the spot where they pass from the retina over the edge of the papilla and dip down into its depth (Fig. 71, *A*). The nerve-fibers, too, like the blood-vessels, undergo flexion or interruption at the edge of the papilla. This interruption, together with the high pressure to which the nerve-fibers are exposed in the interior of the eye, causes them to atrophy. Accordingly, in the later



FIG. 71.—GLAUCOMATOUS EXCAVATION OF THE OPTIC NERVE. MAGNIFIED 14 × 1.
Cf. the normal optic nerve in Fig. 9, p. 14.

A, OPHTHALMOSCOPIC PICTURE OF THE PAPILLA.—The papilla is bounded by a sharp, overhanging edge, at which the arteries, *a*, and the veins, *v*, of the retina appear to stop with their ends bent over the edge. This is due to the fact that their continuation on the floor of the excavation is often displaced somewhat laterally as compared with the portion situated in the retina; moreover, the vessels within the excavation are seen but indistinctly. In the outer half of the excavation are seen the gray dots of the lamina cribrosa. The zone, *h*, of the fundus, adjoining the papilla, is decolorized (halo glaucomatosus).

B, LONGITUDINAL SECTION THROUGH THE HEAD OF THE OPTIC NERVE.—This shows a deep excavation, *e*, on the floor of which only a few remains of the nerve-fibers, *b*, are visible. The central vessels, *c*, ascend upon the retina, *r*, at the nasal margin of the excavation; the innermost layer (fiber-layer) of the retina is considerably diminished in size through atrophy. *ch*, chorioid; *s*, sclera. The volume of the trunk of the optic nerve has been considerably reduced through the atrophy of the bundles of nerve-fibers, *n*. As a result of this, the interspaces between the sheaths of the optic nerve (the pia sheath, *p*, the arachnoid sheath, *ar*, and the dural sheath, *d*) are dilated, especially on the temporal side.

stages, we see that the papilla is not only depressed, but is also bleached out and of a bluish-white color, because the nerve-fibers have been destroyed and the clear white lamina cribrosa is exposed. The atrophy of the optic-nerve fibers is also the most important cause of the decrease of visual power which accompanies the elevation of tension. Impairment of both direct and indirect vision occurs. The former finds its expression in the gradual diminution of the acuity of central

vision, the latter in the limitation of the field of vision—a limitation which begins, in the majority of cases, on the nasal side, as the temporal side of the retina becomes insensitive first. Finally, complete blindness supervenes.

Primary glaucoma is a common disease, constituting about one per cent of all cases of eye-disease. Its accurate recognition is of the greatest importance for the general practitioner, the more so because here prompt and proper therapeutic interference can save everything, but a false diagnosis and improper treatment may destroy everything. Unfortunately, we still constantly get under observation many cases of glaucoma which have not been correctly diagnosticated by the general practitioner, and which come to the ophthalmologist only when assistance is no longer possible. Cases of inflammatory glaucoma are often confounded with iritis or irido-cyclitis, and are accordingly treated with atropine, which has a particularly injurious action in glaucoma. Cases of glaucoma simplex which present no external symptoms of inflammation are not infrequently regarded as commencing cataract, and the patients are put off in expectation of the cataract's becoming ripe, so that they delay until it is too late for iridectomy.

Glaucoma has been known from antiquity. Of course, it is only the inflammatory variety that has been thus known, since the non-inflammatory variety can be diagnosticated by the ophthalmoscope alone. Hence this second variety was lumped together with the other kinds of blindness, which are produced by diseases of the deeply situated membranes of the eye, and which have no external manifestations, under the common name of amaurosis. Inflammatory glaucoma was usually regarded as having a connection with gout, and was hence called ophthalmia arthritica. The first to recognize the increase in tension as the most important symptom of glaucoma were Mackenzie, and particularly Von Graefe. Heinrich Müller, a man deserving the greatest praise in all that relates to the pathological anatomy of the eye, was the first to demonstrate anatomically the pressure-excavation of the optic nerve (1856); soon afterward it was accurately diagnosticated in the ophthalmoscopic picture by Weber and Förster. Mackenzie, starting from the fact of the increase of tension, had already attempted to effect the cure of glaucoma by repeated puncture of the cornea, without, however, obtaining any lasting result. Such a result was first obtained by Von Graefe, who, in the year 1856, employed iridectomy for the first time in glaucoma, after having found it efficient in various other diseases of the eye. This was one of the most pregnant discoveries in ophthalmology, and one which will for all time redound to the glory of Von Graefe. We have only to remember that formerly every case of glaucoma inevitably led to blindness, and that now, thanks to iridectomy, the majority of glaucomatous patients can be cured. How many thousands there are who formerly would have been forced to sink year by year irretrievably into the night of blindness, but who now are saved for vision through Von Graefe's discovery!

With reference to *excavation of the optic nerve*, three varieties are distinguished—the physiological, the atrophic, and the glaucomatous. The *physiological excavation* (Fig. 72 *A*) originates from the fact that the bundles of fibers of the optic nerve, when separating from each other so as to curve into the retina, do so, not in the plane of the retina, but behind it; the lamina cribrosa, however, is in its normal situation. The physiological excavation is always

partial—i. e., even if it is very large it never takes up the entire papilla, because a certain space close to the edge of the papilla must always be occupied by the nerve-fibers which are passing over into the retina (page 13, and Figs. 5 and 9). The *atrophic excavation* (Fig. 72 *B*) is caused by the disappearance of the nerve-fibers which exist as the papilla of the optic nerve in front of the lamina cribrosa, the latter remaining in its place. The atrophic excavation is total—i. e., extends over the entire papilla, but always remains shallow, for at most it can only attain a depth equal to that at which the lamina cribrosa lies behind the inner surface of the retina. In the atrophic excavation, the papilla is at the same time bleached white on account of the disappearance of the nerve-fibers. The physiological and the atrophic excavations have this in common, that the lamina cribrosa remains undisplaced; as the lamina cribrosa forms the floor of the excavation, the depth of the latter is confined within narrow limits. The

FIG. 72.—THE THREE KINDS OF EXCAVATION OF THE OPTIC NERVE.—SCHEMATIC.

A, PHYSIOLOGICAL EXCAVATION.—Funnel-shaped, partial, with normal lamina cribrosa.
B, ATROPHIC EXCAVATION.—Bowl-shaped, total, with normal lamina cribrosa.
C, GLAUCOMATOUS EXCAVATION.—Ampulliform, total, with the lamina cribrosa bulged out posteriorly.

glaucomatous excavation (Fig. 72 *C*) is distinguished from the preceding kinds, first of all, by the fact that it originates in a recession of the lamina cribrosa; it can hence attain a much more considerable depth than they. The glaucomatous excavation comprises the entire papilla, which, in the beginning, still shows the red coloration of health. Later on, the nerve-bundles are destroyed by atrophy, so that the papilla becomes white, and displays exposed upon its floor the lamina cribrosa. With this is associated a still further increase in the excavation, the depth of which is increased by a space equal to the thickness of the destroyed papilla of the optic nerve.

The *ophthalmoscopic signs* distinguishing the three kinds of excavation are, therefore, as follows: A partial excavation is physiological, a total one is pathological, and either atrophic or glaucomatous. The atrophic excavation is shallow, and the papilla, at the same time, very white. The glaucomatous excavation may be shallow or deep, according as it has existed for a longer or shorter time. In a shallow glaucomatous excavation the papilla is found to have still a good color—a feature which distinguishes it from the atrophic excavation. If the excavation is deep and total, it can only be a glaucomatous one, whatever color the papilla may have. In practice, the distinction between the individual forms of excavation is sometimes very difficult to make.

The *ophthalmoscopic picture* of a glaucomatous excavation of the optic nerve shows the papilla to be paler, and, in advanced cases, bluish or greenish white.

A shadow is seen running along the margin, while the center of the excavation is the part lightest in color. On the floor of the excavation may be recognized the gray dot-marks of the lamina cribrosa (Fig. 71, *l*). The vessels do not emerge at the center, but, for the most part, close to the inner margin of the papilla. At the spot where they pass over the edge of the papilla to go to the retina they show a bending, or, in deep excavations, an interruption, of their course. If the edge of the excavation is overhanging, the ascending portion of the vessel may be completely concealed behind it, so that the blood-vessels arising from the vascular entrance seem to disappear at the edge of the papilla to emerge again in the retina at some other spot. It is only in the inverted image that the course of the vessel can be seen distinctly in its whole extent at once; in the erect image, the vessels on the papilla and those in the retina are never seen clearly at the same time, since they lie at different depths and hence have a different refraction. That is, if the adjustment is made for the vessels in the retina (Fig. 71, *a* and *v*), the vessels on the floor of the excavation (Fig. 71, *v*) look quite pale and hazy, and vice versa. The vessels in the excavation have, as compared with those in the retina, a myopic refraction, and hence, to be seen distinctly, require a correspondingly strong concave glass. From the difference in refraction between the margin and the floor of the excavation, the depth of the latter can be estimated (see page 18), and by repeated measurements of this sort we can determine whether, as time goes on, the depth of the excavation is increasing or diminishing. In the inverted image, the difference of level manifests itself only by parallactic displacement (page 18). The caliber of the arteries is contracted, while the veins are distended and tortuous—in fact, sometimes there is a whole convoluted mass of vascular loops lying on the floor of the excavation. These changes of vascular caliber are easily accounted for by the action which the increase of pressure exerts upon the vessels of the vascular entrance, permitting less blood to enter the arteries of the retina, and, on the other hand, obstructing the outflow of blood from the veins. The former, therefore, are filled too little, the latter are filled too much. We very often observe a pulsation in the veins, and not infrequently, also, a pulsation in the arteries within the papilla. (For the explanation of this, see page 15.) When glaucomatous excavation has lasted for a long time, the papilla is usually found to be surrounded by a white or yellow area, which is the expression of an atrophy of the chorioid about the papilla (halo glaucomatosus, Fig. 71, *h*). The rest of the fundus in the later stages often presents a tessellated appearance (Fig. 68).

The condition of the sight is not always in direct proportion to the depth of the excavation—in fact, it is not the recession of the lamina cribrosa as such that affects the vision, but the atrophy of the optic nerve, which, though produced by it, does not always by any means keep pace with the formation of the excavation. Thus we sometimes see cases with deep excavation and yet with normal visual acuity and a large field of vision. On the other hand, by a very considerable increase in pressure—as in glaucoma fulminans—the sight may be completely extinguished within a few hours by paralysis of the optic-nerve fibers without there being any excavation of the optic nerve, because the time is too short for it to be formed. Accordingly, in forming a judgment as to the acuity of vision, we must be guided rather by the color of the papilla and the caliber of the retinal arteries than by the depth of the excavation, since atrophy of the nerve-fibers makes itself known mainly through the pallor of the papilla.

I. Primary Glaucoma.

83. Primary glaucoma, also called simply glaucoma, sets in with varying symptoms. If the pressure rises suddenly to a considerable height, inflammatory symptoms are excited; on the contrary, these symptoms are wanting when the increase in tension develops gradually and keeps within narrow limits. Accordingly, an inflammatory and a non-inflammatory form of glaucoma (glaucoma inflammatorium and glaucoma simplex) are distinguished.

A. Glaucoma Inflammatorium.

Inflammatory glaucoma runs a typical course, especially in the acute cases (glaucoma inflammatorium acutum), which, therefore, will be first described. In the course of inflammatory glaucoma the following stages are distinguished:

(1) *Stage of Prodromata.*—The prodromal stage, which in most cases precedes the inflammatory attack, is characterized first of all by attacks of obscuration of vision. The patient declares that during these attacks he does not see as well, having at the same time the feeling as if there was a cloud or smoke concealing objects from him. If there is a light in the room, he sees a ring about it having the colors of the rainbow. During the attack there frequently exists a feeling of tension in the eye, or a dull frontal headache. If the physician examines the eye during such an attack, he finds the cornea a little dull and diffusely clouded, like glass that has been breathed upon. The cloudiness is greatest at the center, smallest at the periphery, and, on account of its uniformity of distribution, causes considerable disturbance of vision. It also produces the appearance of a colored ring about a luminous flame—an appearance similar to that which, for instance, we see when, on a cloudy winter night, we look through the frost-covered window-panes at a gas-flame in the street. The anterior chamber is somewhat shallower through advancement of the iris; the pupil is more dilated than usual and reacts sluggishly; the tension of the eye is distinctly increased. Frequently, too, slight ciliary injection is present.

Such an attack ordinarily lasts several hours, after which the eye returns once more completely to the normal condition, both as regards its appearance and as regards its function. The attacks at first make their appearance at pretty long intervals (of months or weeks); later on, they become constantly more frequent. Often specific causes for their existence can be demonstrated, such as hearty meals, lateness in going to bed, causes of emotional excitement (among others, card-playing), etc. In many cases they return, even without cause, periodically, sometimes even every day, so that the patient, for example, declares that he always sees through a cloud in the morning, and commencing

with the afternoon begins to see clearly, or vice versa. If the attacks come on in the evening, they always cease when the patient falls asleep; even in the daytime an attack may be cut short by his going to sleep.

In the intervals between the prodromal attacks the sight of the eye is normal; but the patient complains that, to see near by, he has to employ stronger and stronger glasses—rapid increase of presbyopia through diminution of the power of accommodation (see § 142).

The prodromal stage sometimes lasts only a few weeks, sometimes is protracted over months or even years. In the latter case, the eye gradually undergoes definite changes, so that it is no longer normal even in the intervals between the attacks. The eye acquires externally the glaucomatous aspect, and an excavation likewise forms in consequence of the oft-repeated increase of pressure. Consequently the sight itself is no longer perfect even during the time in which no attacks occur (transition to glaucoma inflammatorium chronicum).

(2) The second stage is that of *glaucoma evolutum*, which is ushered in by the *attack of acute glaucoma*. This sets in suddenly, after the prodromal stage has lasted a longer or shorter time. The cause of an acute attack—in case such a cause is discoverable at all—is like those which determine the prodromal attacks. Chief among them are to be mentioned states of congestion of the venous system, especially those due to enfeeblement of the heart's action; also mental emotions, particularly those of a depressing character; and, lastly, dilatation of the pupils. For the last-named reason a drop of atropine in an eye which is predisposed to glaucoma may excite an attack.

The acute attack manifests itself by violent pain radiating from the eye along the first and second branches of the trigeminus. The patient complains of pains in the head, the ears, and the teeth, which may reach an intolerable pitch. They deprive him of appetite and sleep; not infrequently vomiting and fever likewise set in. Simultaneously with the appearance of the pain the visual power falls rapidly away, so that only large objects—such as, for instance, the hand moved to and fro before the eye—can be recognized. The field of vision is considerably narrowed, and mostly on the nasal side. Objective examination shows the appearances of a violent external inflammation—œdema of the lids, and œdema or even chemosis of the conjunctiva, which is greatly congested. The injection, in accordance with its pre-eminently venous character, has a dusky-red color. The cornea is punctately dotted, has a pronounced smoky cloudiness, and is almost or quite insensitive to touch. The anterior chamber is shallower, the iris is discolored and narrowed. Consequently, the pupil is dilated; very often, too, it is oval and eccentrically situated, the narrowing of the iris being then particularly great in special spots—most frequently above. The reaction of the iris is abolished. From the pupil we get a grayish-

green reflex.* Ophthalmoscopic examination is impossible, on account of the marked cloudiness of the cornea. The tension of the eye is considerably elevated.

It may be seen that the symptoms of the acute attack are the same as those belonging to the prodromal attack, except that they are much more pronounced and are accompanied by inflammatory phenomena (injection, œdema of the lids and conjunctiva, and pain). The prodromal attacks may therefore be regarded in the light of abortive attacks of glaucoma, which retrocede before they have developed to their full height. But at length an onset of this sort takes place, which rises to the height of an acute attack, after which a perfect return to the normal is no longer possible. The tension now remains permanently elevated, and the eye retains the glaucomatous aspect.

The *course* of the attack of inflammatory glaucoma is that after some days or some weeks—according to the severity of the attack—improvement, or even an apparent cure, sets in. After some days the pain diminishes in violence and afterward disappears altogether. The eye becomes free from discoloration, the cornea clears up, and the sight becomes better again. If the sight was still normal before the attack, it may improve to such an extent that the patient can still read and write; but the more the sight has been injured before the attack by a prodromal stage of long duration, the smaller is its improvement after the decline of the attack. We may say in general that after an attack has been suffered from, the vision never again reaches the same height that it had before this occurred. The attack, furthermore, leaves behind it objective changes in the eye, which, at the first glance give proof of the sort of disease that is in it. The overdistention of the anterior ciliary veins remains; the anterior chamber is shallower and the iris is narrower, is turned to a slate-gray color, and reacts sluggishly or not at all; the tension is permanently increased. We then say that the eye exhibits the habitus glaucomatosus. Ophthalmoscopic examination, which becomes feasible again after the cornea has cleared up, shows at the optic-nerve entrance the signs of hyperæmia, which really is only one of the evidences of the general hyperæmia during the inflammatory attack. The excavation of the optic nerve is not present directly after the attack, because for its formation quite a long period of increased tension is requisite; it hence does not develop until later on. It is only in those cases in which there has been a long preceding stage of prodromata that the excavation is present during the attack. After the subsidence of the attack the eye remains quiescent for quite a long time, and the patient gives himself up to the hope of a perma-

* Hence the name "green cataract" (*grüner Staar*). In Greek, sea-green is called γλαῦκος, whence glaucoma. This reflex, however, is a characteristic by no means restricted to glaucoma. It is always found when the pupil is dilated, and at the same time the media are not completely transparent.

nent cure. Then a new attack sets in. This, as far as inflammatory symptoms and pain are concerned, is usually less intense than the first, but results in a still further reduction of the sight. Inasmuch as new attacks now constantly follow each other, at shorter or longer intervals, the sight at length becomes entirely extinct. The disease has then entered upon the

Third stage, that of *glaucoma absolutum.* The eye is completely blind, and presents the following picture: Contrasting with the porcelain-like, bluish-white sclera are the distended anterior ciliary veins, which unite round the cornea to form a bluish-red circle of dilated vessels. The cornea is shining and transparent, but insensitive; the anterior chamber is very shallow. The iris is reduced to a narrow gray marginal band, which in places is almost entirely concealed by the limbus, and which at its pupillary margin is encircled by a broad black border. The dilated and rigid pupil is greenish, or of a dirty gray. The optic disk is deeply excavated, the eye as hard as stone.

Later on, degenerative changes make their appearance in the blinded eye, which are designated under the name of *glaucomatous degeneration.* The cornea becomes cloudy and covered with peculiar glassy-looking deposits. Upon the sclera dark ectatic prominences—most frequently in the region of the equator (equatorial staphylomata)—present themselves to view; the lens becomes cloudy (cataracta glaucomatosa). Although the eye has now been blind for a long time, the patient still constantly believes that he perceives light, especially under the form of a luminous cloud, which on some days is more pronounced, on other days less so. These subjective luminous appearances for a long time uphold the patient in the belief that he will be able to regain his sight. Furthermore, attacks of pain keep making their appearance at various intervals in the blinded eye.

The final outcome in glaucoma is usually atrophy of the eyeball. After the eye has been hard for years it at length becomes softer, smaller, and atrophic. In other cases, abscess of the cornea develops with perforation and consecutive irido-cyclitis, or even panophthalmitis, together with phthisis bulbi. Not till the glaucomatous eye has become shriveled does it allow its unfortunate possessor to have any lasting rest.

The course of glaucoma with a violent attack of inflammation, here pictured, corresponds to that form which is designated as *glaucoma inflammatorium acutum.* In the severest cases, which Von Graefe has described under the name of *glaucoma fulminans*, incurable blindness, in conjunction with the most violent symptoms of inflammation, may develop within a few hours. Of much more frequent occurrence than these cases, which luckily are rare, are those which run a less acute and typical course than belongs to acute glaucoma. These cases are designated as *glaucoma inflammatorium chronicum.* Here no pronounced

inflammatory attack takes place; on the contrary, the prodromal stage passes imperceptibly into the stage of inflammation, the eye growing gradually red and sensitive, the cornea acquiring a smoky cloudiness, the iris becoming atrophied. The pain is neither so violent nor so continuous as in acute glaucoma. Often this sort of chronic course does not set in until after the first attack of inflammation, no complete retrogression of the inflammatory symptoms succeeding the latter. The final outcome is the same as in acute inflammatory glaucoma; and, anyhow, no sharp line of distinction exists between the two forms.

Glaucoma almost always attacks both eyes. Nevertheless, they are but rarely affected at the same time; it more frequently happens that the disease of the second eye follows months, or even years, after that of the first. The experienced physician, however, even in those cases in which one eye is still perfectly healthy, will frequently recognize in the latter a certain disposition toward glaucoma. This manifests itself in a shallow anterior chamber, a somewhat dilated and sluggish pupil, and a relatively high, even though not yet pathological, tension of the eye. With this there exist, usually, a hypermetropic state of the refraction and diminution of the range of accommodation.

Inflammatory glaucoma is a disease of advanced life; it is found most frequently between the fiftieth and seventieth year. It does not occur in childhood and youth. It attacks women more than men, especially women in whom the menopause occurs before the time. A *disposition* toward inflammatory glaucoma appears to belong principally to hypermetropic eyes, whereas strongly myopic eyes are to be regarded as having almost complete immunity against the disease. Furthermore, rigidity of the vessel walls (arterio-sclerosis), habitual constipation, and premature cessation of the menses, predispose to glaucoma. Among Jews, inflammatory glaucoma is much more frequent than among Christians. Furthermore, there are many families in which glaucoma is inherited.

A characteristic feature of glaucoma is the frequent, often periodical, *variations in the course* of the disease. These are afforded by the transient obscurations of vision occurring in the prodromal stage, by the inflammatory attacks recurring at intervals in the inflammatory stage; even after the blindness is complete, there is still a constant alternation of bright and dark days, according to the patient's subjective luminous impressions.

The *character of the pupil* has a very great influence on the phenomena of glaucoma. Its contraction has a favorable effect, since it generally diminishes the tension in glaucoma, while dilatation of the pupil, on the contrary, increases the tension. Hence miotics have the power of cutting short the prodromal attacks, and of ameliorating the symptoms even in the inflammatory attack. The fact that the prodromal attacks can be cut short by the patient's going to sleep is probably also referable to the marked contraction which the pupil undergoes in sleep. Mydriatics, on the contrary, can excite an inflammatory attack in an eye that is predisposed to it, and that not only the pow-

erful mydriatics, like atropine, but also homatropine and even cocaine. We should always, therefore, take care that there is no suspicion of the existence of glaucoma, before making an instillation of a mydriatic in the case of an elderly man. If, however, we have had the misfortune to set up in this way an attack of inflammatory glaucoma, it may be possible, by the prompt and energetic instillation of eserine, to cause the attack to disappear, and that perhaps permanently.

It is a fact frequently observed that iridectomy, done in a glaucomatous eye, may give rise to an inflammatory attack in the second eye, if it is already predisposed to glaucoma. Nevertheless, it is not the operation as such, but the associated mental and physical depression which, as on other occasions, may here, too, excite a glaucomatous attack. The operation itself is not needed to produce this result. One day a lady came to me with a recent inflammatory attack in both eyes. She had a few days before had her first attack of glaucoma in the right eye, and had consulted Prof. Arlt for it. When he explained to her that an operation was necessary, she experienced such a violent fright that she got an inflammatory attack in the second eye while returning from the consultation in her carriage. Probably there are two factors that act together in the case of violent emotional disturbances—the interference with the circulation and the dilatation of the pupil that results from reflex action. In an operation upon a glaucomatous eye, pilocarpine or eserine may be instilled into the second eye to prevent the outbreak of glaucoma in it; even this precautionary measure, however, does not afford complete security.

In the *acute inflammatory attack* the *pain* radiates from the eye into the whole of one side of the head, so that sometimes the patients are not for a moment aware that the pain is proceeding from the eye, but complain of violent "rheumatic" headache. If the attack has been accompanied by marked swelling of the lids, a history of erysipelas may be given. One should not allow himself to be led astray by such declarations as these, but should form his decision in accordance with the results of the objective examination. The principal thing that this examination makes us cognizant of is the dull and uniformly cloudy look of the cornea. Some have supposed, especially in former times, that this cloudiness was also in part located in the aqueous humor and in the vitreous. As to the cloudiness of the vitreous, no proof whatever of it has been presented. An argument for the existence of cloudiness in the aqueous is the fact that not infrequently after it has escaped (in the performance of iridectomy), the pupil looks blacker than before. The main cloudiness, however, is situated in the cornea. Another important symptom of glaucoma is the dilatation and rigidity of the pupil, and by this we are guarded against any confusion with iritis or irido-cyclitis, since in these diseases the pupil is contracted.

In the *stage of glaucomatous degeneration* various changes are observed in the *cornea*. (*a*) Most frequently together with marked cloudiness of the corneal parenchyma there are found brawny or hyaline deposits upon the surface of the cornea. (*b*) Vesicles develop upon the cornea, owing to the fact that the epithelium, either by itself or along with the newly formed deposits, is lifted from its bed by serous exudation—keratitis vesiculosa and bullosa (page 170). (*c*) Zonular opacity of the cornea (page 191); and (*d*) ulcers and abscesses of the cornea, frequently leading to perforation (page 153), are observed. As a result of the latter, violent hæmorrhages may take place from the interior of the eye, or severe purulent inflammation succeeded by shriveling of the eyeball.

These affections of the cornea, so various in character, are referable in part to the alteration in nutrition produced by the disturbance in the lymphatic circulation, partly to the paralysis of the corneal nerves, manifested in the complete insensitiveness of the surface of the cornea to touch. In consequence of these changes, the cornea becomes less capable of resisting external injuries.

In the course of glaucomatous degeneration the *lens* always becomes cloudy (cataracta glaucomatosa). From this lenticular cloudiness, produced by the glaucomatous process, is to be distinguished that form which occurs only as an accident in the glaucomatous eye, and which is designated as cataracta in oculo glaucomatoso. Thus, simple senile cataract, traumatic cataract, etc., may be present in a glaucomatous eye. The distinction between cataracta glaucomatosa and cataracta in oculo glaucomatoso is made by observing the appearance of the cataract and by testing the vision. Cataracta glaucomatosa is distinguished by its marked distention, its bluish-white color, and the vivid silky luster of its surface, while cataracta in oculo glaucomatoso has the appearance corresponding to its origin and its nature. In the first form of cataract the eye, as a result of the glaucomatous process, is completely blind, and hence an operation for cataract is useless. In the second case, if the glaucoma is not too far advanced, such a degree of sight (perception of light) may still exist as promises a good result from the extraction of the cataract. The extraction, however, should in no case be performed immediately; on the contrary, the increase of tension should first be done away with by an iridectomy, and this may be succeeded four weeks later by the cataract operation. If we should extract a lens, without taking any such preliminary precaution, in an eye affected with increase of tension, we would run the risk of losing the eye through severe intra-ocular hæmorrhage (see page 144).

B. Glaucoma Simplex.

84. In glaucoma simplex the increase of tension sets in very gradually, so that no inflammatory phenomena are produced. The eye either looks quite normal externally, or it gives evidence of its lesion through the greater prominence of the distended anterior ciliary veins, and also through a somewhat dilated and sluggish state of the pupil. The tension of the eye is shown by palpation to be elevated, but not to any considerable degree. Often on the first examination no increase of tension is found at all; it is not until we examine the eye repeatedly, and especially at different times of the day, that we succeed in demonstrating that the tension is elevated. At these times a slight, smoky cloudiness of the cornea is also sometimes present, such as appertains to the prodromal attacks of inflammatory glaucoma. Finally, there are cases of glaucoma simplex in which the tension is never found distinctly increased.

In consideration of the fact that in glaucoma simplex marked external symptoms, and sometimes, indeed, any manifest increase of tension are wanting, we are thrown back upon the ophthalmoscopic examination for the establishment of the diagnosis. Such an examina-

tion shows the presence of a total excavation of the optic nerve, the depth of which corresponds to the duration of the process.

The subjective symptoms of glaucoma simplex, since the inflammatory attacks and the pain are wanting, consist almost exclusively of the disturbance of vision. This manifests itself by gradual diminution of the sight, and in many cases also by transient slight attacks of obscuration, like those belonging to the prodromal stage of inflammatory glaucoma. The decrease in vision expresses itself in the contraction of the field of vision, as well as in the diminution of the central visual acuity. The latter often develops late, when the field of vision has already become very small, so that not infrequently the patients are still in a condition to read or carry on fine work, while they are scarcely able to go about any longer alone (see page 21). Before this point is attained, generally a long time (even many years) has elapsed, inasmuch as the reduction of vision takes place very slowly and gradually. For this reason the patient himself often does not become aware of the existence of his disease until late. The blinded eye may either remain always sound externally, or those inflammatory attacks which are characteristic of inflammatory glaucoma may occur—often, indeed, before the blindness has become complete. Glaucoma simplex, accordingly, not infrequently changes into inflammatory glaucoma.

Glaucoma simplex always attacks both eyes. In contradistinction to inflammatory glaucoma, it sometimes occurs in young people, and attacks men as frequently as women. It is also found in myopic eyes, which have a sort of immunity against inflammatory glaucoma.

Hydrophthalmus.—Hydrophthalmus is a disease of childhood. The eye is of unusual size (hence called buphthalmus, ox-eye; see page 229). The sclera is bluish, in consequence of the uveal pigment appearing through it; the cornea is larger and more bulging than normal (keratoglobus), and either clear and lustrous or, as in inflammatory glaucoma, dull and diffusely clouded. The anterior chamber is unusually deep, the iris is tremulous, and the papilla, after the process has lasted a pretty long time, is deeply excavated. The tension of the eye is considerably increased.

The disease may come to a stop spontaneously, or may continue until it produces blindness. In the former case, the increase of tension subsides after a time; the enlargement of the eyeball persists, indeed, but does not increase, and the eye retains a moderate degree of sight, the amount of which is mainly dependent upon the condition of the optic nerve. In the second case, the enlargement of the eye keeps on —sometimes until quite extraordinary dimensions are attained—and in the mean time complete blindness ensues.

The disease is either congenital or develops in the first years of in-

fancy, and generally in both eyes. Heredity plays an important part in its production. The nature of the disease has not yet been fully cleared up, but increase of tension is certainly the most important factor in it, leading, on the one hand, to the enlargement of the eye, and, on the other hand, to blindness through excavation of the optic nerve. For this reason hydrophthalmus is known as the glaucoma of childhood. Its difference in external appearance from the glaucoma of adults is accounted for in the main by the physiological properties of the eye in childhood. The extensibility of the sclera in childhood renders it possible for the heightened pressure to result in enlargement of the eye as a whole. In the eye of the adult, however, the rigidity of the sclera permits of its expansion through increase of pressure only at its weakest spot—namely, at the lamina cribrosa.

In hydrophthalmus the expansion of the membranes of the eye is due to the fact that an increased pressure is acting upon their inner surface. Hence we can comprehend that the lens does not share in this enlargement, since it has to bear the pressure upon its external surface. The lens, therefore, is the only part of the hydrophthalmic eyeball that retains its normal dimensions—in fact, it not infrequently falls behind them. Hence the lens is too small in comparison with the surrounding parts, and the space between the margin of the lens and the ciliary processes keeps growing larger and larger. Thus the zonule of Zinn undergoes an elongation which leads to its partial atrophy. Hence in hydrophthalmus of pretty high degree we always find defective fixation of the lens, manifested in tremulousness of the latter and of the iris, and not infrequently inducing subsequent changes of position (luxation) of the lens, with their disastrous consequences.

The relation of glaucoma simplex to glaucoma inflammatorium has been the subject of manifold discussions. Since glaucoma simplex, on account of the absence of inflammatory symptoms, is entirely different externally from glaucoma inflammatorium, it was not recognized as glaucoma at all until the discovery of the ophthalmoscope. Even Von Graefe did not originally place glaucoma simplex under the head of glaucoma, but designated it as amaurosis with excavation of the optic nerve. Jäger held to this view until the last, looking upon glaucoma simplex as an optic-nerve lesion sui generis—a "glaucomatous" optic-nerve lesion. At the present time, however, the majority of ophthalmologists place glaucoma simplex under the head of glaucoma proper, since it has in common with it its most essential symptom, the increase in tension. The interconnection of simple and inflammatory glaucoma is also proved by the numerous intermediate varieties which form a continuous transition from simple to inflammatory glaucoma, so that no sharp line of distinction can be drawn between the two.

To these transition-forms belong, for example, the cases of glaucoma simplex with periodical obscuration of vision, and which are accompanied by transient cloudiness of the cornea, and often also by dull headache. Even in pure cases of glaucoma simplex, a constant headache sometimes exists, the dependence of which upon the glaucomatous process is proved by the fact that it dis-

appears after iridectomy. A glaucoma simplex, later on in its course, often passes into acute or chronic inflammatory glaucoma, and cases also not infrequently occur in which, after inflammatory glaucoma has developed in the eye first affected, glaucoma simplex is present in the one which is affected afterward.

The interconnection of the two forms of glaucoma, shown from the above-mentioned facts, has been doubted because in many cases of glaucoma simplex no evident increase of tension is demonstrable. In these cases we must assume that the lamina cribrosa is particularly yielding, so that it is forced backward by a pressure which does not perceptibly rise above the normal limits. Such cases, to be sure, are not always clearly distinguishable from simple atrophy of the optic nerve with unusually deep atrophic excavation. In doubtful cases the testing of the color-perception may furnish a diagnostic guide. In atrophy of the optic nerve, color-blindness makes its appearance early, while in glaucoma the ability to distinguish colors is retained for a comparatively long time.

Theories of Glaucoma.

85. All the essential symptoms of glaucoma can be accounted for as being the results of the increase in pressure. The recognition of this fact by Mackenzie, and particularly by Von Graefe, was the most important step made in establishing the theory of glaucoma.

The elevated intra-ocular pressure has, as its first result, a disturbance of the circulation of blood in the eye, the essential character of which is that of a *venous stasis*. The heightened tension, that is, brings about a compression of the veins in the interior of the eye, and especially in the vasa vorticosa, which, on account of their oblique course through the sclera, are particularly exposed to the influence of the intra-ocular pressure. The blood flowing away from the uvea is hence compelled, in great part, to travel through the anterior ciliary veins; these are consequently dilated, and, in old cases of glaucoma, form a vascular circle of closely set veins about the cornea. In glaucoma simplex the symptoms of obstructed circulation are confined to this dilatation of the anterior ciliary veins and to the ophthalmoscopically visible distention of the retinal veins. But in inflammatory glaucoma, in which the increase in tension and with it the disturbance of circulation set in suddenly, these changes induce the phenomena of *inflammatory œdema* in the same way as the incarceration of a hernia, for example, results in inflammatory œdema of the incarcerated coils of intestine. Inflammatory œdema is characterized by hyperæmia of the tissues and marked swelling, due to their serous infiltration, while—in contradistinction to plastic inflammation—exudates and the adhesions produced by them are wanting. Accordingly, the symptoms of acute inflammatory glaucoma, so far as they affect the uvea, for example, differ greatly from the clinical picture of an irido-cyclitis; posterior synechiæ are only exceptionally observed in it, and exudations of greater degree, such as hypopyon, pupillary membrane, etc., are never observed. This absence of exudation, in spite of the violent external symptoms of

inflammation, is, in fact, just the characteristic feature of inflammatory œdema. This œdema finds different expression in the different portions of the eye:

1. The *corneal cloudiness* of glaucoma is an œdema of the cornea, as has been proved by anatomical investigation. From this can be understood the suddenness of development of the corneal cloudiness, and also the promptness of its recession upon reduction of the pressure—e. g., after puncture of the cornea, or iridectomy. If we were dealing with an inflammatory infiltration of the cornea—i. e., with a keratitis—it could not possibly disappear again within a few hours.

2. *Inflammatory œdema of the iris* manifests itself mainly by discoloration and by the obliteration of the details of its structure. The anterior chamber becomes shallower, because the lens is pressed forward, together with the iris, in consequence of the elevation of pressure in the vitreous chamber. Added to this there is a displacement forward of the attachment of the iris—that is, the greatly swollen ciliary processes press the root of the iris forward, so that it is applied to the most anterior portion of the sclera and to the margin of the cornea (Fig. 73). Consequently, the iris appears to take its origin farther forward (Figs. 73 and 74). The ciliary nerves are compressed and paralyzed by the high intra-ocular pressure; thus originate the insensitiveness of the cornea and the paralysis of the iris (iridoplegia), with dilatation and loss of reaction of the pupil. The dilatation afterward increases in consequence of the atrophy of the iris, which develops as a result of the pressure exerted upon the latter.

FIG. 73.—IRIS AND CILIARY BODY IN RECENT INFLAMMATORY GLAUCOMA. MAGNIFIED 9×1.

The ciliary process, *c*, is so greatly swollen that it pushes the root of the iris forward and presses it against the sclera, *S*, and the cornea, *C*. The sinus of the anterior chamber, which should lie somewhat behind Schlemm's canal, *s*, is thus closed. The ciliary muscle shows the pronounced development of the circular muscular fibers (Müller's portion), characteristic of the hypermetropic eye.

3. The redness and clouded appearance of the papilla of the *optic nerve* during the inflammatory attack are caused by hyperæmia combined with some œdema; the excavation which subsequently takes place is the direct result of the elevation of pressure.

4. The violent *pain* in inflammatory glaucoma is excited by the compression of the extremely numerous sensory nerves of the ciliary body and the iris.

Thus all the objective symptoms of glaucoma are accounted for by

the one fact of the increase in tension. The *disturbance of vision*, too, is the result of the heightened intra-ocular pressure, which causes it in different ways, according as we are dealing with inflammatory glaucoma or glaucoma simplex. In *inflammatory glaucoma* the disturbance of vision is brought about by—

(*a*) The glaucomatous opacity of the cornea, which affects chiefly central vision, and that, too, to a marked degree, on account of the uniformity of its diffusion.

(*b*) The ischæmia of the retina, due to the compression of the retinal arteries, by which is caused the contraction of the field of vision. This compression makes itself felt first in those sections of the arterial channel in which the blood-pressure is lowest. But, since the blood-pressure in the vessels is less the farther we get away from the heart, the terminal expansions of the arteries lying in the periphery of the retina are first affected by the compression. Hence the periphery of the retina first becomes insensitive to light, a thing which manifests itself by contraction of the field of vision. Moreover, the ischæmia does not become apparent in all parts of the retina at once or in equally high degree. Since the papilla of the optic nerve, and with it the point of entrance of the retinal vessels, lie to the nasal side of the posterior pole of the eye, these vessels have a greater distance to travel in going to the temporal margin of the retina than to the nasal margin. The former is therefore first affected by the ischæmia, so that the limitation of the field of vision begins generally at its nasal margin.

FIG. 74.—IRIS AND CILIARY BODY IN OLD INFLAMMATORY GLAUCOMA. MAGNIFIED 9×1.

The dotted line gives the outline of the iris, I_1, and the ciliary body, c_1, in the normal condition. The root of the iris is adherent to the sclera, *S*, and the cornea, *C*, wherever it has been pressed against them by the ciliary body. The attachment of the iris is hence displaced forward and lies in front of Schlemm's canal, *s*. So, too, the sinus of the anterior chamber is displaced from *b* to *a*. Wherever the iris has become adherent, it has been thinned through atrophy, so that in places—*b*, for example—it consists of scarcely anything more than the pigment-layer. Even the free portion of the iris, *I*, appears in consequence of its atrophy narrower than the normal iris, I_1. Over the pupillary border, *e*, the retinal layer of pigment turns forward farther than usual, and the sphincter pupillæ, *p*, also shares to some extent in this process of revolution. The ciliary body has again become removed from the iris, and in fact more so than in the normal condition, so that it is now separated from the iris by a broad interval. The atrophy affects both the ciliary muscle, *m*, and the ciliary process, *c*.

Both the opacity of the cornea and the acute ischæmia of the retina belong solely to inflammatory glaucoma, and it is they which are the principal cause of the very great reduction of sight during the acute attack of glaucoma. They are of transitory nature, disappearing again as the elevated tension abates, and at the same time with their disap-

pearance an improvement of the acuity of central vision and an enlargement of the field of vision set in.

(*c*) In the third place, the acuity of vision is diminished by direct pressure upon the optic-nerve fibers and their consequent atrophy—atrophy which takes place during the formation of the glaucomatous excavation. The disorder of vision thus produced is permanent, since the atrophy of the optic-nerve fibers is irreparable.

In *glaucoma simplex* the two first-named factors are wanting. The disorder of vision is here caused solely by the excavation and simultaneous atrophy of the papilla of the optic nerve.

Explanation of the Increase of Tension.—Easy as it is to deduce the symptoms of glaucoma from the elevation of tension, it is quite as difficult to account for the origin of the latter, and thus explain the true nature of glaucoma. Of the many theories which have hitherto been propounded upon this subject, no single one is satisfactory in every respect. Only the most important of them will be adduced here, and that mainly with the object of showing upon what circumstances increase of tension in general depends.

The intra-ocular pressure is determined by the relation between the internal capacity of the envelopes of the eyeball and the quantity of its contents. If the former increases or the latter diminishes, the pressure is elevated. An alteration of the internal capacity of the envelopes of the eyeball can not be brought in to account for the increase of pressure, since the volume of the envelopes of the eyeball, as a whole, is unalterable. In advanced life, to be sure, the sclera is not only more rigid, but also a little contracted; but the diminution in volume so caused is extremely slight. We must, therefore, look for the cause of the elevation of tension in an increase in the amount of the contents of the eyeball, the envelopes of the eyeball being at the same time not sufficiently elastic to adapt themselves to their increased contents by a process of dilatation. The amount of matter contained in the eyeball depends, on the one hand, upon the quantity of ocular fluids which are constantly being secreted by the blood-vessels, and, on the other hand, upon the quantity of fluid which leaves the eye again through the lymph-passages; it corresponds, that is, to the relation between inflow and outflow, between secretion and excretion. A disturbance of this relation must exist for a permanent increase to take place in the amount of matter contained in the eyeball. The inflow may be increased without a corresponding increase of the outflow, or the outflow may be diminished without a corresponding reduction in the inflow; and increased inflow and diminished outflow might also exist simultaneously. Most of the older theories of glaucoma were based upon the idea of an increase of the inflow:

(1) Von Graefe assumed the existence of an increased excretion of fluid by the vessels of the chorioid as a result of inflammation of the

latter Since the ophthalmoscopic symptoms of chorioiditis are generally wanting in glaucoma, Von Graefe, to get over this difficulty, assumed the existence of what he called a serous chorioiditis, the nature of which was supposed to consist in a serous transudation without any coarser anatomical changes.

(2) Donders ascribed the increased secretion on the part of the chorioid to the influence of the ciliary nerves. He looked upon glaucoma simplex as the type of glaucoma because it was not complicated with inflammation. Hence he could not consistently look for the cause of the increased excretion of fluid in an inflammation of the chorioid. Rather, he supposed it to originate in an irritation of the chorioidal nerves, as a sort of neurosis of secretion, just as, for example, increased secretion takes place in glands upon irritation of certain nerves.

(3) Stellwag referred the elevation of tension not to increased excretion of fluid, but directly to the increase of blood-pressure in the vessels of the interior of the eye. The pressure which the blood exerts on the vessel walls is transmitted to the structures adjacent—that is, to the refracting media (particularly the vitreous), on the one hand, and to the sclera, on the other. It thus forms an important item of the total sum constituting the intra-ocular pressure, so that its elevation has as its direct result an increase in the ocular tension as a whole. The interior vessels that come under consideration in this connection belong principally to the uvea, that being the most vascular portion of the eye. The elevation of the blood-pressure in the vessels of this part is therefore, according to Stellwag, the direct cause of glaucoma. It makes its appearance in consequence of obstructions to the circulation, which affect mainly the region of the vasa vorticosa, and are brought about by diminished elasticity and shrinking of the sclera; for those sections of the vasa vorticosa which pass with a very oblique course through the sclera are liable to compression whenever the latter shrinks.

Against these theories the objection must be made, first of all, that an increase in the inflow or an over-distention of the vessels can not by themselves account for the increase in tension, since, if the conditions are otherwise normal, an increase in the contents of the eyeball is immediately compensated for by the increased outflow. If a few drops of liquid are injected into a healthy living eye, and the intra-ocular pressure is thus increased, it returns to the normal again after a short time, since a correspondingly greater amount of liquid flows off through the lymph-channels. Hence, to account for the elevation of tension we must, in the first place, look for some obstruction to secretion, by which an increased amount of liquid is retained in the eye. The most important of the glaucoma theories that are based upon the idea of a diminution in the outflow of liquids is that of—

(4) Knies and Weber. According to this, the ciliary processes

swell up in consequence of venous stasis, so that they press with their apices against the posterior surface of the iris (Fig. 73). The marginal portion of the iris is thus displaced so far forward that it becomes applied to the most anterior portion of the sclera and to the margin of the cornea, and later on becomes adherent to them. This change manifests itself in the apparent advancement of the point of attachment of the iris. The normal sinus of the anterior chamber (Fig. 74, *b*) no longer exists (obliteration of the sinus); the iris becomes applied to the inner surface of the ligamentum pectinatum, and compresses its loose meshwork into a solid fibrous tissue. Thus the most important exit for the ocular fluids—that which leads through the ligamentum pectinatum into Schlemm's canal (see page 250)—is closed, and consequently an excess of fluid is retained in the eye.

Even this theory, which at present counts perhaps the most adherents, is not free from objections. The most important of these is that in many cases of glaucoma simplex, and, very rarely, in cases of inflammatory glaucoma also, the apposition of the iris to the sclera and cornea is not present at all, but, on the contrary, the sinus of the chamber presents its normal relations. So far, therefore, no explanation of glaucoma has yet been propounded which would be satisfactory in every respect. The reason for this is perhaps to be looked for in the statement that all cases of primary glaucoma probably do not develop in the same way, so that *one* explanation could not possibly fit all cases. And, in particular, it might be possible that glaucoma simplex and inflammatory glaucoma would have to be referred to different causes.

Anatomy of Glaucoma.—In the *cornea* the cause of the cloudiness is found to be œdema. The most anterior of the lamellæ of the corneal stroma are pushed apart by fluid; but the fluid is especially apt to be found under the form of minute drops, between Bowman's membrane and the epithelium, and also between the epithelial cells themselves. These cells are hence pushed apart and lifted up, so that the surface of the cornea becomes slightly uneven and dull, often looking like shagreen. When the elevation of the epithelium takes place over a pretty large area, small vesicles are formed upon the surface of the cornea.

In the *sclera* an increase in density has been demonstrated, and also a fatty degeneration of the fibers, which look as if sprinkled with minute drops of oil.

The *aqueous* is more albuminous, and coagulates readily in the air and in hardening fluids.

The most important changes affect the *uvea*. In recent inflammatory cases it presents the appearances of inflammatory œdema—i. e., infiltration with an abundant, readily coagulable liquid, while white blood-corpuscles that have emigrated from the vessels are present in but scanty numbers; but what strikes one most of all is the marked distention of the venous vessels, in consequence of which extravasations of blood are produced in many spots. The ciliary processes in particular, which of all the structures of the eye possess the most veins, are greatly swollen through the turgidity and distention of the vessels. Squeezed in between the sclera and the margin of the lens, the ciliary processes push forward and press the root of the iris against the sclera and the cornea (Weber).

By a process of simple adhesion (according to Knies, by adhesive inflammation), the periphery of the iris remains permanently connected with the sclera and cornea (peripheral anterior synechia), even when later on the ciliary processes retract again away from the iris (Fig. 74). This retraction takes place in consequence of the atrophy which, after the subsidence of the early inflammatory symptoms, sets in in all parts of the uvea. In the iris, the atrophy finds expression in its becoming narrower and thinner. Rigid connective tissue, from which the blood-vessels have for the most part disappeared, takes the place of the delicate network of anastomosing cells. In the vessels which are still present the walls are thickened, and the lumen is thus contracted or even entirely obliterated (Ulrich). The muscular bundles of the sphincter pupillæ, too, become atrophied. The part which is best preserved is the retinal pigment-layer, which, by the great shrinking of the anterior layers of the iris, is drawn continually farther and farther forward over the edge of the pupil (ectropion of the pigment-layer; Fig. 74, *e*). Hence, in looking from in front we find the margin of the pupil encircled by an uncommonly broad black rim, which sometimes covers half the breadth, or even more, of the surface of the iris. The atrophy attains its greatest height at the root of the iris—i. e., at that part which is adherent to the sclera and cornea (Fig. 74, *b*). In old cases nothing of the iris is left in this spot but the retinal pigment-layer, and also one or two of the larger vascular trunks. These remains of the iris are intimately adherent to the wall of the eyeball; the ligamentum pectinatum is condensed into a tough, fibrous tissue; and, finally, even Schlemm's canal disappears.

The ciliary body diminishes in size through atrophy, so that it draws away again from its contact with the iris, and afterward becomes flatter and flatter, until at length it scarcely forms any projection at all (Fig. 74, *c*). The atrophy affects the ciliary muscle as well as the ciliary processes. In the chorioid the atrophy finds expression in the obliteration of the blood-vessels and the rarefaction of the pigment, so that the chorioid is finally in some spots reduced to a thin, transparent pellicle. This sort of atrophy of the chorioid takes place most of all in the neighborhood of the papilla, and by it there is formed the halo glaucomatosus visible with the ophthalmoscope (*h*, Fig 71, *A*). The atrophy also reaches a high degree in the spots where the vasa vorticosa pass from the chorioid into the sclera. The chorioid here grows fast to the sclera, which becomes thinned, and, together with the chorioid, protrudes as an equatorial staphyloma. In the vasa vorticosa themselves is found proliferation of the vascular endothelium, leading to contraction, or even obliteration, of the lumen of the veins (Czermak and Birnbacher).

The *lens*, according to the investigations of Priestley Smith, is too large in proportion to the surrounding parts, on the one hand, because the volume of the lens increases with the age in any case, and, on the other hand, because in glaucoma we are dealing chiefly with hypermetropic eyes, the dimensions of which are generally less than the normal. In consequence of this disproportion, the edge of the lens pushes too close to the ciliary processes, for which reason the latter, when swollen, must give way forward, so as to press against the iris.

At the *optic-nerve entrance* the particularly striking feature is the displacement of the lamina cribrosa. This is condensed by the compression of its layers, and is displaced backward, so that not infrequently it even gets to lie behind the outer surface of the sclera (Fig. 71, *e*). The excavation of the papilla thus produced contains upon its floor atrophic nerve-fibers and also connective

tissue (Fig. 71, *b*). Large excavations get to have overhanging edges (become ampulliform), because the short canal in the sclera, which is designed for the optic nerve, and which is laid bare by the excavation, is wider behind than in front (see Fig. 9). In consequence of the destruction of the head of the optic nerve, the retina and the trunk of the optic nerve also atrophy; the latter becomes thinner, as a whole, and presents an enlargement of its connective-tissue trabeculæ at the expense of its bundles of nerve-fibers (Fig. 71, *n*).

Precise as is our information in regard to the anatomical changes above described, and many others, too, in glaucoma, we must be correspondingly cautious in the interpretation of their significance, if we are bent upon looking for the anatomical cause of glaucoma. Most of these changes, if not all, are simply the result of the increase of pressure—as is, without any doubt, the case with regard to the atrophy of the tissue and the excavation of the optic nerve. To find those changes which precede the increase of tension and cause it, we should have to examine the eye in the earliest stages of glaucoma—a thing the opportunity for which has hitherto been but very rarely offered us. Indeed, most of the glaucomatous eyes that have been examined are those which have been enucleated in the stage of glaucoma absolutum because they were painful.

Treatment of Primary Glaucoma.

(A) OPERATIVE TREATMENT.

86. Glaucoma passed for an incurable disease until Von Graefe discovered the curative action of iridectomy. Afterward still other methods of operating in glaucoma were devised, none of which, however, have been able to displace iridectomy.

I. *Iridectomy*, the technique of which will be described in the section on operations (§ 156), must satisfy certain conditions, if it is to be efficient in combating glaucoma. The wound should lie in the sclera, not in the cornea; and the excision of the iris should be carried to the ciliary margin, and be as broad as possible. Inclusion of the iris in the wound after the operation should be avoided by careful reposition of the iris. If possible, the iridectomy is made upward, so that the coloboma may be covered by the upper lid, and not cause trouble through the dazzling due to irregular refraction. But frequently it is precisely in the upward direction that the iris is very atrophic, in which case its excision is not only difficult, but also, as experience shows, is less efficient; in that case we are compelled to choose another place for forming the coloboma. In glaucoma simplex iridectomy is easily performed, while in inflammatory glaucoma it often presents considerable difficulties on account of the cloudiness of the cornea, the shallowness of the anterior chamber, the rottenness of the iris, and also on account of the great painfulness of the parts.

As regards the *time for performing the operation*, it is best to operate as early as possible. In inflammatory glaucoma the operation should be done in the prodromal stage, in case the patient can make up his mind to it. If he wait until the inflammatory attack, we can

not tell how severe it is going to be, and, in any case, we operate then under less favorable conditions. Under all circumstances the operation is demanded in the prodromal stage when the other eye is already rendered blind by glaucoma; in this case, too, the patient will more readily comprehend the necessity of the operation. When an eye has already been rendered blind by glaucoma, the restoration of sight is no longer possible by an operation; but yet one is often performed to relieve the painfulness of the eye, or to prevent the development of glaucomatous degeneration.

In glaucoma simplex it is not a question of interfering within a few days or weeks, as is often the case in inflammatory glaucoma, but even here the operation should not be long deferred; the earlier we operate, the better results we obtain.

The *success* of an operation in respect to vision can be estimated approximately beforehand, if account is taken of what morbid changes can and what can not be removed by the operation. Iridectomy reduces the intra-ocular pressure to the normal amount. By it the glaucomatous cloudiness of the cornea and the disturbance of vision produced by it, as well as the disturbance of vision caused by the compression of the retinal vessels, are removed. But the excavation and the atrophy of the optic-nerve fibers associated with it either do not abate at all or do so in but very slight degree, so that the disturbance of sight, so far as it is dependent upon them, persists. From these facts is deduced the action of iridectomy in the separate forms of glaucoma:

(*a*) In *inflammatory glaucoma* the result of the operation in recent acute cases is extremely favorable. The pain accompanying the glaucomatous attack ceases a few hours after the operation, the cornea in the next few hours or days becomes clear and sensitive once more, and the other inflammatory symptoms likewise speedily disappear. The sight, which during the attack was very much reduced through the cloudiness of the cornea and the compression of the retinal vessels, increases very considerably after the disappearance of these factors. If it was still normal before the attack, it becomes almost normal again after the operation. But if a long prodromal stage with the formation of an excavation has preceded the attack, both the acuity of direct vision and the visual field have already ceased to be normal some time before the attack, and will then be more imperfect still after the operation. We may accordingly put it down as a rule in acute inflammatory glaucoma that a degree of sight is secured by iridectomy, *which is somewhat, but not much, smaller than it was before the last inflammatory attack.* In a few cases, to be sure, the result of the operation is not so favorable, since, in spite of the operations being correctly performed, the increase of tension keeps up or sets in again anew. In these cases it is generally possible to attain our end by a second operation (iridectomy or sclerotomy).

Finally, there are cases in which, in spite of all attempts at operative interference, complete blindness supervenes. These unfavorable cases, however, are rare in acute glaucoma; so that, as a rule, one may count upon a good result for the operation, and one, too, which is lasting.

In chronic inflammatory glaucoma we must estimate with respect to the prognosis of the operation how much of the disturbance of vision present is to be charged to the cloudiness of the media, and how much is due to the excavation and atrophy of the papilla of the optic nerve. The former portion is removed by the operation, the latter not.

(*b*) In *glaucoma simplex* the result of the iridectomy is less pronounced and also less permanent than in inflammatory glaucoma. The visual disturbance in the variety of glaucoma simplex, in which the media are clear, is caused solely by the changes in the papilla of the optic nerve. Since the operation can not remove these changes, it is impossible to restore by means of it the normal acuity of vision. The operation can only do away with the increase in tension, and thus put a stop to the progress of the process; it accordingly gives greater promise of a permanent good result the more pronounced the increase in tension is. The rule is that the sight is *maintained in statu quo* by the operation, or, at most, is slightly improved. In many cases a repetition of the operation is necessary in order to obtain even this result, or the failure of sight goes on unchecked in spite of the operation. This may even take place when, in consequence of the iridectomy, the intra-ocular pressure has become permanently normal. We then assume that an atrophy of the optic-nerve fibers, when once initiated, keeps on progressing in spite of the reduction of the intra-ocular pressure. Of particularly unfavorable character are those cases in which the iridectomy actually exerts a bad influence upon the sight, the latter falling away very rapidly after the operation, so that blindness sets in earlier than it would have done without the operation. Sometimes inflammatory symptoms and pain make their appearance just after the operation, when they were not present before. The eye feels hard directly after the operation, the anterior chamber fails to reform, and the eye becomes blind rapidly and with symptoms of violent pain. These cases, which, to be sure, are rare, are known as *glaucoma malignum*.

The *prognosis* of iridectomy in glaucoma, then, is as follows: In inflammatory glaucoma the operation acts favorably upon the inflammation and upon the eyesight, and its good results are permanent; it is hence unconditionally indicated. In glaucoma simplex only the maintenance of the status quo is to be counted upon. In a certain number of cases the operation is unsuccessful or actually does harm. Nevertheless, as without an operation the eye will certainly grow blind, iridectomy is indicated in glaucoma simplex too—at least in those cases in which an evident increase of tension is demonstrable. We endeavor to perform

the iridectomy as early as possible, for the more advanced the disease is, the more uncertain is the result of the operation.

The *reason why* iridectomy diminishes the tension has so far not been discovered, since, indeed, the cause of the increase of tension itself is still unknown to us. In an eye the tension of which is normal, the latter is not diminished by an iridectomy; for instance, if an iridectomy is made on account of an opacity of the cornea, the eye does not therefore become permanently softer. It is only the pathologically heightened tension that iridectomy reduces. Of the many reasons that have been given for this action in reducing tension, one only will be here adduced, because it has given rise to a new operative procedure. De Wecker was the first to express the opinion that in iridectomy the section in the sclera was of greater importance than the excision of the iris. He considered the significance of the scleral incision to lie in the fact that by means of it a cicatrix was introduced into the sclera, which allowed fluid to filter through it, as the normal sclera does not do. This filtration cicatrix, in his opinion, afforded a substitute for the obliterated ligamentum pectinatum. From the view that iridectomy owes its efficacy to the section in the sclera, sclerotomy has taken its origin.

2. *Sclerotomy* consists in making in the sclera an incision, which is placed as far as possible in the periphery of the anterior chamber, and in which no iris is excised (for the technique, see § 155). There is no doubt that sclerotomy, too, which for a time was very much practiced, has permanently cured many cases. For the most part, however, the cure has not been definitive, so that an iridectomy has had to be resorted to subsequently. At the present time, therefore, most operators perform sclerotomy only in those cases in which iridectomy can not be performed for technical reasons, or in which an iridectomy has been already done without success.

3. *Enucleation* is indicated when an eye which has been rendered perfectly blind by glaucoma is continually painful, and an iridectomy is either impossible of performance on technical grounds, or has been already performed without success. In this case enucleation is done simply with the object of relieving the pain, and may, in suitable cases, be replaced by optico-ciliary neurotomy (see § 167).

(B) MEDICINAL TREATMENT.

The miotics, eserine and pilocarpine, are powerful agents in combating increase in tension. They act only when the iris is capable of contracting satisfactorily; hence, in old cases of glaucoma with a completely atrophic iris they are useless. Their action is accounted for upon the supposition that by the contraction of the pupil the iris is stretched in a radial direction, and so is drawn away from the wall of the eyeball to which it has been applied, so that the sinus of the

chamber again becomes free. Unfortunately, the effect of miotics upon the ocular tension is not lasting, inasmuch as it vanishes with the disappearance of the miosis. The miotics can not, therefore, cure glaucoma permanently, and thus dispense with iridectomy; they are, however, valuable auxiliary remedies in the treatment of glaucoma.

In the prodromal stage of glaucoma miotics are employed to cut short the prodromal attacks. If the patient instills a miotic at the commencement of the attack, the latter comes to an end in about half an hour. Thus we can for a long time prevent the prodromal attack from rising into an acute inflammatory attack. Nevertheless, we should not protract the prodromal stage in this way until excavation of the optic nerve with permanent impairment of sight sets in. As soon as this threatens, we must proceed to iridectomy.

During the acute inflammatory attack also miotics reduce somewhat the elevated tension, and thus ameliorate the pain and contribute to the disappearance of the glaucomatous cloudiness of the cornea. In this way it becomes more feasible to put off the operation for a few days, if circumstances require it. Moreover, the operation is rendered easier of performance, since the iris, very narrow before, becomes broader through the contraction of the pupil.

In glaucoma simplex the action of miotics is dubious, and the more so the less pronounced the increase of tension is.

The mydriatics are as prejudicial in glaucoma as the miotics are useful. The other methods of medicinal treatment in glaucoma, which formerly were very numerous, are now obsolete. Care should be taken to restrain the emotions and avoid constipation.

Iridectomy is often difficult to perform in inflammatory glaucoma, so that the excision of the iris does not always turn out to have been done correctly. Luckily it is precisely in inflammatory glaucoma that even a less successfully performed iridectomy is usually followed by the effect desired. Above all, we must avoid injuring the capsule of the lens, an event which might easily happen from the narrowness of the iris and the shallowness of the anterior chamber. Such an eye would be almost certainly lost, since the injured lens swells up, and thus gives rise anew to increase of tension.

Iridectomy in inflammatory glaucoma is usually followed by hæmorrhage into the anterior chamber and into the retina. The sudden diminution of the pressure, the fact that we are operating in a very hyperæmic eye, and the degeneration of the vessel walls are all accountable for this. The blood in the anterior chamber is sometimes uncommonly slow in being absorbed, because the normal channels of outflow are stopped up. The retinal hæmorrhages cause no special harm, except when one of them happens to involve the exact region of the yellow spot.

On account of the great tension of the glaucomatous eye, the edges of the wound after iridectomy do not close up as well as in the case of other iridectomies—e. g., those made for optical purposes. Hence, more frequently than is otherwise the case, we get, instead of direct union of the edges of the wound,

healing with the interposition of an interstitial tissue, as a consequence of which ectasis of the cicatrix or cystoid cicatrization is readily produced.

In glaucoma simplex it sometimes happens that iridectomy has for its immediate result a marked reduction in the sight. This is to be apprehended when the field of vision was so very much contracted before the operation that its limits at one spot reached nearly up to the point of fixation. Then a slight intussusception of the confines of the visual field carries them beyond the point of fixation, so that central vision is lost. Hence the rule is to do iridectomy as early as possible, while the field of vision is still large.

Views differ in regard to the efficacy of iridectomy in glaucoma simplex. Von Graefe estimated the number of definitive cures produced by the operation at rather more than half the cases; in one quarter of the cases relapses occurred, which were cured only by a second iridectomy, while in the rest of the cases blindness gradually set in in spite of the operation. Only in two per cent of all the cases did the operation have actually a bad effect. Since then reports in regard to the curative effects of iridectomy in glaucoma simplex have been published by different authors, as by Hirschberg, Sulzer, Nettleship, Charles Stedman Bull, Gruening, etc. Most of these statistics prove, in harmony with the statements of Von Graefe, that in about half the cases the operation has put a stop to the progress of the disease. Dr. Laska has collected my own observations upon this point, and from them the following results have been obtained: Out of thirty-nine cases, iridectomy had a favorable result in nineteen—that is, in about one half, the sight either being kept stationary or actually improving; but in twenty cases the eyesight failed in spite of the operation, either from the subsequent reappearance of the elevation of tension, or even without this taking place. The value of these statistics, small as they are, lies in the fact that only cases that had been under observation a pretty long time were accepted in making them up. The mean period of observation amounted to five years in the nineteen cases that were cured; several of these had been followed up for more than ten years.

In hydrophthalmus, iridectomy is associated with greater danger than in the glaucoma of adults, and that mainly because of the defective condition of the zonula. By reason of this, when, after the escape of the extremely abundant aqueous, the lens is driven forward, rupture of the zonula, and hence escape of vitreous through the wound, may take place. Another source of danger consists in the fact that we are dealing with children, of whom quiet behavior after the operation is not to be expected. Nevertheless, a series of favorable results have been recorded, the hydrophthalmus having been arrested by the iridectomy.

II. Secondary Glaucoma.

87. By secondary glaucoma we understand an increase of tension which appears in the course of other diseases of the eye, and as a consequence of them. Accordingly, the increase of tension here forms the complication of an already existing affection, although, all the same, it entails the results peculiar to itself, just as in the case of primary glaucoma. If it is associated with inflammatory symptoms, it produces in the cornea, the iris, etc., the changes belonging to inflammatory glaucoma. In other cases it manifests itself merely through the increase

in tension perceptible to the touch, and also through the pressure-excavation of the optic nerve with the disturbance of sight that is caused by it, namely, the contraction of the visual field and the diminution in central vision. Moreover, its termination in blindness and in degeneration of the eyeball is the same as in primary glaucoma.

The clinical picture of secondary glaucoma varies according to the disease which it accompanies. The affections of the eye leading to increase of tension are as follows:

1. *Ectasiæ of the cornea and the sclera.* Of the former, it is above all those connected with inclusion of the iris—i. e., the staphylomata—that almost universally lead to secondary glaucoma. It is only the exception that ectasiæ without inclusion of the iris, such as keratectasia ex ulcere or keratectasia after pannus or after keratitis parenchymatosa, give rise to increase of tension. Of scleral staphylomata, those which occur after rupture of the sclera may entail increase of tension, and so also may the ectasiæ that develop after scleritis. Most ectasiæ of the sclera, however, are the result, not the cause, of the increase in tension.

2. *Fistula of the cornea*, if it closes after existing a long time.

3. *Irido-cyclitis* may increase the tension through causing abundant exudation into the interior of the eye.

4. *Seclusio pupillæ*, whether originating in adhesion of the entire pupillary margin to the capsule of the lens or in the inclusion of the former in a cicatrix of the cornea. Seclusio pupillæ leads to the accumulation of aqueous in the posterior chamber and to consequent protrusion of the iris, which is accompanied by increase of tension.

5. The *lens* becomes a cause of secondary glaucoma in two ways—by being luxated and by being swollen. All forms of luxation are of significance in this regard; but the most dangerous cases are those in which the lens is wedged into the pupil or lies wholly in the anterior chamber. Sudden swelling of the lens after injury or operation may likewise cause increase of tension, especially if we are dealing with elderly people, whose sclera is rigid.

6. *Intra-ocular tumors*, like sarcomata and gliomata, in a certain stage of their development excite the symptoms of secondary glaucoma.

7. *Hæmorrhages into the retina* are the expression of changes in the vessels or disturbances of circulation, which sometimes lead to elevation of tension. This is most frequently the case in old people with arterio-sclerosis; the elevation here usually makes its appearance under the form of inflammatory glaucoma—glaucoma hæmorrhagicum.

8. *Chorioiditis* and *myopia* of a high degree often give rise to an increase of tension under the form of glaucoma simplex.

The *treatment* of secondary glaucoma must above all endeavor to remove the cause lying at the foundation of the elevation of tension. For instance, in seclusio pupillæ the communication between the two chambers should be restored by means of an iridectomy, a dislocated or

swollen lens should be removed, if possible, and so on. For the symptomatic treatment of the increase of tension itself, the means at our command are paracentesis of the cornea and iridectomy. The former diminishes the pressure by means of the evacuation of the aqueous, but does so only temporarily, so that it is suited simply to those cases in which the increase of tension is foreseen to be of short duration—e. g., in swelling of the lens and in irido-cyclitis. The paracentesis may be repeated several times, according to the demands of the case. A lasting elevation of tension can be combated only by iridectomy. Glaucoma hæmorrhagicum gives the most unfavorable prognosis. Here we can not count with certainty upon the effect of the iridectomy, since sometimes the latter is immediately succeeded by blindness coming on rapidly and with violent pain. Eyes which contain a new growth, or which are both blind and painful, require enucleation.

Diminution of the intra-ocular pressure (*hypotonia*) is found in very diverse affections of the eyeball. It is always a sign that the contents of the eyeball have diminished in volume. Hence a high degree of diminution of tension is observed when, after the perforation of the eyeball, either the aqueous has flowed away or the lens or vitreous has escaped. This may be the result of an injury or of the spontaneous rupture of an ulcer. If the perforation in healing leave a fistula or a cystoid cicatrix, through which aqueous continually escapes, the softness of the eye may persist for a long time (even many years). After the use of a bandage which has been too tightly applied, we find the eye softer for a short time, because, under the increased pressure due to the bandage, an increase in the outflow of fluids from the eye has taken place. So, too, the eye becomes very soft when the volume of the vitreous is diminished by shrinking of exudates—that is, in those cases in which atrophy of the eyeball occurs after irido-cyclitis. Hence a progressively increasing softness of the eyeball in the course of an irido-cyclitis is an ominous symptom. Slight degrees of decrease of tension accompany many cases of inflammation of the cornea, both suppurative and non-suppurative, and also occur not infrequently after slight injuries (erosions) of the cornea, especially if these were associated with a contusion. Of the affections of the deep parts, detachment of the retina is particularly associated with diminution of tension. Finally, slight degrees of the latter are found in paralysis of the sympathetic, and also after the instillation of cocaine.

Cases occur which are known as *ophthalmomalacia*, or essential phthisis, in which diminution of tension appears spontaneously, without known cause. The eye suddenly becomes very soft, smaller, and injected, and not infrequently there are marked photophobia and neuralgic pain associated with the condition. This state of things may last for hours or days, when it gives place to the normal condition. In many instances such attacks recur at intervals (intermitting ophthalmomalacia). The cause of this rare disease in many cases has remained unknown; in other cases there has been an injury preceding it. The prognosis is good, as the ophthalmomalacia usually leaves no ill results behind.

CHAPTER VIII.

DISEASES OF THE LENS.

Anatomy.

88. The lens (crystalline body, lens crystallina) lies between the iris and vitreous, and, together with the zonula, divides the eye into a smaller anterior and a larger posterior section—the cavity of the chambers and the cavity of the vitreous. It is a transparent and colorless structure of lenticular shape, the anterior surface of which is less, the posterior surface more curved (Fig. 36). In the lens we distinguish an anterior and a posterior pole, and the rounded edge, or equator, at which the anterior and posterior surfaces of the lens come together. The sagittal diameter (thickness of the lens) amounts in the adult man to five millimetres, the equatorial diameter to nine millimetres; moreover, a small increase of volume of the lens takes place in the later years of life.

The lens lies within the circle formed by the ciliary processes, but in such a way that its equator is distant about one half millimetre from the apices of the processes. The interspace between the ciliary body and the equator of the lens is called the circumlental space. The posterior surface of the lens is imbedded in the fossa patellaris of the vitreous. The lens is kept in position by the suspensory ligament (ligamentum suspensorium lentis), or zonula of Zinn.

If after rupturing the zonula we take the lens out of the eye, we find it, in the first place, inclosed in a transparent capsule—the capsule of the lens. If after removing the capsule we try to crush the lens of an adult between the fingers, the softer peripheral masses separate, while the harder central portion remains uncrushed between the fingers. The former form the cortex, the latter the nucleus of the lens (see Fig. 59, *r* and *k*). These are distinguished not only by their consistence, but also by their color. The cortex is colorless, while the nucleus has a yellowish or brownish hue. The nuclear layers owe their greater consistency and also their coloration to a process which is known as sclerosis, and which consists mainly in a loss of water. The sclerosis commences in the center of the lens, and begins even in childhood, but advances so slowly that it is not until the age of twenty-five that a distinct, although still small, nucleus is present. Through the continu-

ous progress of the sclerosis from the center to the periphery of the lens, the nucleus steadily increases in size as the years go on, and the cortex diminishes in like proportion, so that at length, at a very advanced age, almost the entire lens is converted into nucleus, or is sclerosed. There are many individual differences in this regard, so that persons of the same age have lenticular nuclei of different size. The size of the nucleus is of practical importance in the operation for cataract.

The sclerosed portion of the lens is hard and rigid, incapable of changing its shape. Hence, the further advanced the sclerosis of the lens is, the less able is the latter to make that alternating change in its shape which is requisite for the act of accommodation. For this reason the faculty of accommodation diminishes with advancing age (presbyopia; see § 142).

The nucleus reflects more light than the non-sclerosed part of the lens. Hence, the pupil in elderly people, whose lens has a large nucleus, is no longer of such a pure black as in youth. It gives a gray or grayish-green reflex, which by the inexperienced is easily confounded with beginning cataract.

FIG. 75.—STELLATE FIGURE OF THE POSTERIOR SURFACE OF THE LENS. DRAWN FROM A LENS HARDENED IN MÜLLER'S FLUID. MAGNIFIED 2×1.

From the posterior pole of the lens start three primary rays, one of which is directed straight downward, the other two inward and upward and outward and upward. These divide into their branches so near their origin, in this case, that the Y-shaped figure is here not at once obvious.

Histology of the Lens.—The lens consists of fibers having the form of long, prismatic, six-sided cords. They are closely applied to each other, and are held together by a cement substance. The fibers begin and end upon the anterior and posterior surfaces of the lens, along lines which radiate from the anterior and posterior poles (Fig. 75). Here they form a Y-shaped figure—the stellate figure of the lens—which can be recognized in the living eye in adults by means of lateral illumination. The three rays of the stellate figure branch, and thus divide the lens into a number of sectors whose apices meet in the region of the anterior and posterior poles of the lens. In pathological cases—i. e., in opacity of the lens—the sectors often stand out very distinctly. The fibers of the nucleus are distinguished from those of the cortex by their being slenderer and having finely crenated edges. The transition from nucleus to cortex is quite gradual, no sharp line of distinction existing between the two.

The capsule of the lens (*l*, Fig. 76) is a homogeneous membrane, which is thicker upon the anterior than it is upon the posterior surface of the lens. The anterior capsule of the lens is further distinguished by having a single layer of cubical epithelial cells, the epithelium of the lens (*e*, Fig. 76). This plays an important part in the growth of

the lens, as the fibers of the latter originate from the cells of the capsular epithelium. If we follow the epithelium of the anterior capsule toward the equator, we see that the epithelial cells rise higher and higher, until finally they are converted into long fibers, the fibers of the lens (Fig. 76, *f*). As the cells became elongated their nuclei recede from the capsule into the interior of the lens, so that a zone is found along the equator, in which there are numerous nuclei lying in the lens-substance itself. This nuclear zone, as it is called (*k*, Fig. 76; cf.



FIG. 76.—NUCLEAR ZONE OF THE LENS. (AFTER BABUCHIN.)

l, lens-capsule. The epithelial cells, *e*, by a process of gradual elongation, grow out into the lens-fibers, *f*, with the nuclei, *k*.

also Fig. 47, *k*), represents that district of the lens in which the growth of the latter takes place. This growth occurs by a process of apposition, new epithelial cells constantly growing out into lens-fibers, which are placed outside of and next to the older lens-fibers. The fibers lying in the center of the lens are thus the oldest, and the most exterior fibers are the youngest. The reason for nuclei not being present outside of the nuclear zone in the interior of the lens is that the nuclei disappear from the older lens-fibers. As regards the manner of its growth, therefore, the lens is an epithelial structure, like the hair, nails, and teeth. And, in fact, embryology shows that the lens originates from an invagination of the external germinal layer (see page 264).

The zonule of Zinn consists of delicate, homogeneous fibers, which take their origin from the inner surface of the ciliary body, beginning at the ora serrata. The fibers at first are in contact with the surface of the ciliary body (*z*, Fig. 47), but leave it at the apices of the ciliary processes, and, becoming free, pass over to the edge of the lens (free portion of the zonula; z_1, Fig. 47). As they do this, they diverge so as to go partly to the equator of the lens itself, and partly in front of and behind the equator to the capsule of the lens, with which they become fused. The space, triangular on cross-section, included between the fibers of the zonula and the equator of the lens, is called the canal of Petit (*i i*, Fig. 47). It is connected with the posterior chamber by means of slit-like gaps between the separate fibers of the zonula.

The optical function of the lens consists in its bringing the rays that have been already made convergent by the cornea still closer together, so that they unite upon the retina. For this purpose the

refractive power of the lens has to be less or greater, according as the rays are parallel or divergent when they fall upon the eye. This alteration in the refractive power (accommodation) is produced by a change of shape of the lens (see § 140).

In regard to the metabolism of the lens, see pages 253 and 255.

I. Opacities of the Lens.

A. General Considerations.

89. Opacities of the lens, called cataract,* may be situated in the lens itself or in the capsule. Accordingly, we distinguish lenticular and capsular cataracts; by the combination of the two is produced capsulo-lenticular cataract.

The *objective symptoms* of lenticular opacity vary according to its extent and its intensity—partial opacities often requiring for their recognition lateral illumination or the use of the ophthalmoscope, and, if the opacities lie far in the periphery, artificial dilatation of the pupil being necessary in addition. By reflected light (with focal illumination) the lenticular opacities present themselves under the form of gray or white spots or striæ. These often exhibit shapes which have a connection with the structure of the lens—e. g., the shape of sectors or radii. By lateral illumination it can be determined at what depth the opacities are situated in the lens. Opacities of the anterior capsule are distinguished by the brilliant white hue and very superficial situation; sometimes they form a distinct prominence upon the anterior surface of the lens. When seen with the ophthalmoscope—that is, by transmitted light—the lenticular opacities do not appear white, but dark, like black dots or striæ, which stand out in contrast with the red hue of the pupil (see page 7). Commencing, slight opacities of the lens can only be recognized by means of the ophthalmoscope. Far-advanced opacity of the lens can be recognized at once with the naked eye by the change of color of the pupil, which is white or a gray of varying degrees of brightness.

The *subjective symptoms* of opacity of the lens consist in a disturbance of vision, the degree of which depends upon the situation and the nature of the opacity. Patches of cloudiness that are small, sharply circumscribed, and at the same time as opaque as possible—as, for example, anterior polar cataract—cause little or no impairment of the sight. Larger opacities disturb the sight to a considerable degree, and, moreover, torment the patient by the production of peculiar phenomena, such as muscæ volitantes and polyopia. The seeing of *muscæ volitantes* (mouches volantes) consists in the patient's noticing black specks in the field of vision, which, however, if caused by opacities of the lens,

* Waterfall, from καταῤῥήγνυμι, I pour down.

change their place only with the movements of the eye, and hence (in contradistinction to opacities of the vitreous) always occupy the same spot in the field of vision. They become objects of cognition by casting a shadow upon the retina, which is perceived by the latter. Multiple vision (*polyopia monocularis*) causes the patient to see the same object double and multiple. It can sometimes have a very disturbing action, as a case related by Becker shows. A lamplighter in the castle of a prince, when he lighted the candelabra and chandeliers in the salons the evening before a soirée saw thousands of lights, which confused and frightened him to such a degree that he got the idea that he was dealing with a ghost. The reason for the polyopia is found in the optical irregularities which develop in the lens as it grows opaque (irregular lenticular astigmatism), so that the lens throws upon the retina not one but several images of the same object. These phenomena often bring the patient to a physician at a time when as yet no considerable diminution of the sight exists.

The diminution in visual acuity depends, with regard to its degree, upon various circumstances. It is greater when the opacity is diffuse, less when it is sharply circumscribed, so that quite clear interspaces are found between very opaque spots. The case is the same as with a window-pane, through which nothing can be distinguished when it is uniformly covered with watery vapor; although, if a wire screen is placed in front of the otherwise clear pane, we can still see pretty well through it. The interference with vision is also greater when the opacity is situated in the central portions of the lens than when it occupies the periphery. In the latter case, in fact, the sight may be perfectly normal; this being particularly the case as long as the opacities continue to lie completely behind the iris. The sort of illumination with which the best vision is obtained also depends upon the situation of the opacities. With a central opacity the sight is better when the pupil is dilated, because the still transparent, peripheral portions of the lens are then used for seeing. Persons thus affected, therefore, see better when the illumination is reduced, as in the evening twilight; they have *nyctalopia*. In such a case the vision can also be improved by the artificial dilatation of the pupil by means of atropine. The reverse occurs when the opacities occupy the periphery of the lens. Then vision is better when the pupil is contracted, so that the opacities are covered by the iris. Such patients try to get a bright light, and see better by day than by night—*hemeralopia*.

Later on, as the opacity increases, the sight becomes more and more reduced, the muscæ volitantes and the polyopia disappear, and the patient grows blind. But, even when he has lost the ability to distinguish objects (qualitative vision), he has still always left him the perception of light—the distinction between light and darkness or quantitative vision. The examination of the perception of light (see

§ 156) is of great importance with regard to the prognosis of a complete opacity of the lens. If the perception of light is deficient or entirely wanting, this proves the existence of a complication on the part of the retina or the optic nerve, in which case an operation for cataract would have little or no result.

In former times when focal illumination and the opthalmoscope were unknown, one, in making diagnosis of commencing cataract was thrown back chiefly upon the subjective symptoms, especially myodesopsia (the seeing of muscæ volitantes), which was therefore much more exactly studied and followed up than at present. At that time it was quite possible for pupillary membranes, which made the pupil appear gray or white, to be regarded as opacity of the lens, and they were therefore called cataracta spuria. We shall not fall into this mistake if we observe the connection which a pupillary membrane almost always has with the margin of the pupil, and which is particularly marked when we call in the aid of atropine. But, even with all our present auxiliaries, it is often impossible to say whether the lens behind a dense pupillary membrane is transparent or opaque.

Myopia often develops in the beginning of senile cataract. In this case we are dealing with elderly people, who formerly saw well at a distance and used convex glasses for reading; and who then began to notice that they could read fine print again without glasses, and are perhaps very much pleased at this so-called "second sight." That, as an off-set to this, they do not see as well at a distance as formerly, often escapes their notice. Examination of the eye with glasses shows that it has become myopic, so that the near point has got back again to the reading distance. This myopia is ascribable to an increase in the density of the lens while the cataract is beginning to form, an increase by which the refractive power of the lens is heightened.

An opacity of the same character causes more disturbance of vision when it is situated at the posterior than at the anterior pole of the lens; for the nodal points of the eye—i. e., those points through which all rays entering the eye without undergoing refraction (principal rays) must pass—lie close to the posterior pole of the lens.

The *anatomical changes* forming the basis of lenticular opacity have been chiefly studied in senile cataract. Becker is the one who by his profound researches has done the most to advance our knowledge of the development of cataract.

Cataract begins by the separation of the lens-fibers from each other at certain spots, so that fissures are produced filled with liquid (Fig. 77, *s*). These are formed first at the boundary line between the nucleus and the cortex, and particularly in the region of the equator of the nucleus. It is assumed that these dehiscences are caused by the shrinking of the nucleus, that is associated with sclerosis, when this shrinking proceeds too rapidly for the cortex to adapt itself to the diminished volume of the nucleus. The liquid contained in the fissures coagulates into drops or spheroidal bodies (spheres of Morgagni; *M*, Fig. 77). The lens-fibers themselves, which bound the fissures, are at first still normal and hence transparent. The fluid which collects between them may at first be transparent too, and nevertheless the spots look cloudy, because the fluid in the fissures has a different refractivity from that of the lens-substance itself. So, too, a white opaque foam is produced when we mix transparent air with equally transparent water by agitation. Afterward the lens-fibers themselves

become cloudy. They look at first as if sprinkled with fine dust, owing to the accumulation in their interior of a fatty substance in extremely minute drops. At the same time that the lens-fibers get cloudy, their caliber becomes uneven, because they swell up in spots (*q*, Fig. 77). In this way bodies that are large, vesicular, and frequently nucleated (vesicular cells; *b*, Fig. 77) are produced. Finally, the lens-fibers break down completely, so that from the lens-tissue is formed a pultaceous mass consisting of drops of fat, spheres of Morgagni, remains of lens-fibers, and an albuminous liquid (Fig. 77, *z*). As the lens-fibers break down, the connection between them and the capsule, which is a very inti-



FIG. 77.—CATARACTA CAPSULO-LENTICULARIS. ENLARGED 170×1.

k, anterior capsule of the lens; *e*, epithelium, occurring at e_1 in several layers because of proliferation; *l*, normal lens-fibers; *v*, light-colored vacuoles (drops of liquor Morgagni) between *l* and the epithelium. The fissures originating through the separation of the lens-fibers are filled with a granular mass (coagulated fluid), *s*, which in places forms the spheres of Morgagni, *M*. The lens-fibers themselves are swollen up (*q*), or transformed into vesicular cells (*b*), or entirely disintegrated (*z*).

mate one in the normal lens, is loosened, and a liquid (the liquor Morgagni) collects in open spaces between the lens and capsule (at *v* in Fig. 77, appearing under the form of separate vacuoles, but at *r*, Fig. 59, accumulated in greater amount and separating the capsule from the cortex). By this process the removal of the lens from the capsule, as has to be done in a cataract-operation, is facilitated.

The nucleus of the lens is transformed by the sclerosis of the lens-fibers into such a resistant mass that generally it remains unchanged in the midst of the disintegrating cortex (*k*, Fig. 59). Hence the nucleus of a cataractous lens is usually not essentially different from the nucleus of a healthy lens of the same period of life (Becker). But, if there is no hard nucleus present yet, the disintegration of the lens is complete (Fig. 60).

The subsequent changes in the opaque and disintegrated lens consist in the first place in a gradual resorption of the pultaceous lens-masses. In this way lenticular opacities may clear up again; not, to be sure, in the proper sense of the word, by the opaque lens-fibers becoming once more transparent, but by the disappearance of the opaque parts. The sclerosed nucleus resists resorption

as it does disintegration. Cholesterin is not infrequently excreted in the cortex in tabular crystals, which are sometimes large enough to be visible to the naked eye as shining points. Lime salts may be deposited in the pultaceous lens-masses.

Capsular opacity is not situated in the capsule itself, which never becomes opaque, but is deposited upon the capsule. Opacities of the anterior capsule are caused by an opaque tissue which is found on the inner surface of the capsule; between it and the lens (Fig. 78). This tissue takes its origin from a pro-



FIG. 78.—ANTERIOR CAPSULAR CATARACT. MAGNIFIED 40×1.

The capsular cataract forms a projection upon the anterior surface of the lens, covered by the capsule, *k*, which is unchanged and simply thrown into folds. The capsular epithelium, *e*, loses its regularity at the border of the cataract, its cells being increased in number and separated by the cataract from the capsule, so as to form for a short distance the posterior boundary of the cataract. The cataract consists of a fibrous tissue, with cells lying in the spindle-shaped gaps between the fibers. Succeeding the cataract posteriorly is liquor Morgagni, *M*, which is coagulated into a pulverulent mass, separating the capsule from the cataractous layers of the lenticular cortex.

liferation of the capsular epithelium. The cells of this latter increase in number so that a multiple layer of them is formed (Fig. 77, e_1). From this layer there is formed by the growth of the epithelial cells into elongated fibers a sort of fibrous tissue which looks like connective tissue, but still is not true connective tissue, since it has originated from epithelium. By the interposition of this tissue between the capsule and the lens a distinct elevation is formed upon the anterior surface of the lens.

The opacities of the posterior capsule lie, as a rule, upon its posterior surface.

Inflammation of the lens—*phakitis**—does not exist. Inflammatory elements, such as round cells, occurring in the lens, do not originate in it, but enter the lens from the outside through an opening in the capsule.

B. Clinical Forms of Cataract.

90. Every opacity begins at first at some special spot in the lens (partial cataract). It may remain permanently limited to this spot (partial stationary cataract), or it may gradually spread over the whole lens and lead to total cataract (progressive cataract).

(A) PARTIAL STATIONARY CATARACTS.

1. *Cataracta Polaris Anterior.*—A small white dot is seen at the anterior pole of the lens. Anatomical examination has proved that it corresponds to an opaque tissue lying beneath the anterior capsule and

* From φακός, lentil.

between it and the lens—that is, that we are dealing with a capsular cataract (Fig. 78). Hence this form of opacity is also called anterior central capsular cataract. If the opaque layer of tissue is thick enough to form a distinctly visible conical projection, we speak of pyramidal cataract (*p*, Fig. 39). Anterior polar cataract may be either congenital or acquired. The former variety has its cause in an interference with the development of the lens, the precise nature of which has not been determined. The acquired form develops in childhood exclusively, and then because of perforating ulcers of the cornea (most frequently in consequence of blennorrhœa neonatorum). When the ulcer undergoes perforation and the aqueous escapes, the lens pushes forward so that its umbo is applied to the posterior aperture of the perforation. Thus, partly by mechanical means, partly through the direct contiguity of the inflamed cornea, an irritation is set up in the epithelium of the anterior capsule, so that it proliferates and forms an opaque tissue beneath the capsule. Afterward the ulcer heals, the anterior chamber is reconstituted, and we then have a central opacity of the cornea and a central capsular cataract.

Anterior polar cataracts of small area may exist without giving rise to any essential disturbance of vision, this being caused more by the opacity of the cornea than by that of the capsule. Treatment, none.

2. *Cataracta Polaris Posterior.*—This consists of a small white dot at the posterior pole of the lens, which, on account of its deep location, is generally to be discovered only with the ophthalmoscope. It belongs to the posterior capsule, upon the posterior surface of which it is deposited (hence also called posterior central capsular cataract). Posterior polar cataract is congenital, and dates from the time when the hyaloid artery passed through the vitreous to the posterior pole of the lens (see page 267 and Fig. 56). When this disappears incompletely, some of its tissue remains upon the posterior capsule. Hence, we sometimes find posterior polar cataract simultaneously with persistence of the hyaloid artery. The interference with vision is inconsiderable when the cataract is small. Treatment, none.

The anterior and posterior polar cataracts are capsular, while the partial stationary cataracts about to be mentioned are all lenticular.

3. *Circumscribed Opacities of Various Kinds in the Lens itself.*—In this category belongs central cataract, a small spherical opacity directly in the center of the lens. The cataracta fusiformis, or spindle-shaped cataract, consists of an opaque line which runs in the axis of the lens from the anterior to the posterior pole, and presents a spindle-shaped swelling at a point corresponding to the center of the lens. In cataracta punctata, extremely minute white dots are found, either distributed uniformly through the whole lens or united in a group in the anterior cortical layer. Besides these here mentioned, numerous other forms of circumscribed stationary lenticular opacities are known, all of

which, however, occur so rarely that they do not need to be minutely described here. All these opacities are sharply circumscribed, and are sometimes of very regular and graceful shape; they are congenital, and are mostly found in both eyes. They are often inherited, although the same forms of cataract are not always met with in the different members of the same family. Eyes affected with cataracts of this sort not infrequently present other congenital malformations too, or are found in individuals whose whole development, mental or physical, is incomplete. Most of these opacities in themselves cause little impairment of the sight, which, however, is often defective for other reasons.

4. *Perinuclear (or Zonular, or Laminar) Cataract.*—This is the most frequent form of cataract in children. After dilating the pupil, we see a gray, discoid opacity in the lens, surrounded by a perfectly transparent marginal portion (Fig. 79). The diameter of the opaque disk is



Fig. 79.



Fig. 80.

Fig. 79.—Lamellar Cataract seen by Reflected Light. Magnified 3×2.

The iris, *I*, has retracted under atropine. The opacity forming the lamellar cataract is denser at the margin than at the center. The riders are depicted in the upper half, but are left out below to show how the lamellar cataract looks without them. Between the margin of the opacity and the margin of the pupil, *P*, is a black interspace corresponding to the transparent periphery of the lens.

Fig. 80.—Lamellar Cataract in Cross-section. Schematic. Magnified 2×1.

The layers, *s*, placed between nucleus and cortex, are opaque, but the adjacent layer is so only in the equatorial region, *r*, so that riders are formed.

sometimes larger, sometimes smaller, and so, too, consequently, is the width of the peripheral, transparent zone (Fig. 79, *P*). Upon examination with the ophthalmoscope, the cataract appears as a dark disk, surrounded by the transparent and therefore red and illuminated periphery of the pupil. The darkness of the disk is greater near the edge than in the center, by which circumstance a zonular cataract is distinguished from a solid opacity, which, as it affects the nucleus too, would necessarily be densest in the center. Along the outline of the opacity, which usually is sharply defined, small opaque dentations are not infrequently found, called riders, projecting from the margin of the cataract into the transparent periphery, like the spokes on the steering-wheel of a steamship (in Fig. 79 represented only in the upper half of the cataract).

Lamellar cataract is caused by an opacity of the layers lying between the nucleus and cortex (Fig. 80, *s*), while these two themselves are transparent (Jäger). The riders on the periphery of the lamellar cataract originate from the fact that a second layer, peripherally situated with regard to the first, is beginning to become opaque, doing so first only at isolated spots corresponding to the equator of this first layer (*r*, Fig. 80). These partial opacities embrace the equator of the inner opacity in front and behind; they ride upon it, as it were, whence the name riders.

Lamellar cataract almost always affects both eyes. Its time of origin falls within the first years of life. It is found, above all, in those children who have suffered from convulsions (Arlt). Such convulsions are mostly caused by rickets, and especially by the rhachitic changes in the skull (craniotabes). The teeth at the same time are irregularly formed, often being represented simply by cubical or irregular stumps, which are covered unevenly by enamel or in places are entirely denuded (rhachitic teeth). Lamellar cataract, therefore, stands in etiological connection with rickets (Horner). Inheritance of lamellar cataract is of not infrequent occurrence.

Perinuclear cataract is stationary as a rule, although there are cases in which it gradually develops into a total opacity of the lens. This is especially to be expected if riders are seen on the margin of the opacity, since these warrant us in the conclusion that the opacity is making its way into the peripheral layers.

The degree of interference with vision, due to lamellar cataract, does not depend upon the diameter of the opacity, for lamellar cataracts of even small diameter are always large enough to occupy the whole pupillary area of the lens, so that the transparent peripheral zone is always entirely concealed behind the iris when the pupil is not dilated. Hence, as far as vision is concerned, the degree of saturation of the opacity is the only thing that has to be considered. As this latter varies greatly, all gradations are found between almost normal sight and considerable impairment of vision.

Treatment is required for lamellar cataract only when the interference with vision is considerable. In these cases there are two ways to choose from for improving the sight by operative means. The transparent periphery may be exposed and rendered available for vision by means of an iridectomy, or the lens may be removed altogether. The latter is accomplished in young people by discission; in older ones, in whom a hard nucleus is already present in the lens, by extraction. Each of these procedures has its definite indications, its advantages, and its disadvantages.

Iridectomy is proper only when the peripheral, transparent zone of the lens is pretty broad. It retains for the patients the possibility of seeing at a distance and near by without glasses, but causes disfigurement by depriving the pupil of its round shape, and also gives rise to

dazzling. It is only of transient benefit in those cases in which the lamellar cataract passes into total opacity of the lens. On the other hand, removal of the lens produces a radical cure, and, if done by discission, leaves a round and mobile pupil; but it renders the patient exceedingly hypermetropic, and deprives him of the power of accommodation, so that he is compelled always to make use of glasses. Hence, in the choice of operative methods, we usually proceed as follows: If signs of the progress of the cataract are present (riders or a demonstrable gradual diminution in visual power), the removal of the cataract is unconditionally indicated If a stationary condition of the cataract is to be expected, we perform iridectomy when the transparent periphery of the lens is broad enough to make distinct vision possible; otherwise, we remove the lens. In order to establish the availability of the periphery of the lens for vision, the visual acuity is determined, first with the pupil contracted, and then after its artificial dilatation by means of atropine. If the visual acuity is considerably increased in the latter case, iridectomy is indicated; otherwise, removal of the lens.

5. *Cataracta Corticalis Anterior et Posterior.*—In this there is found in the anterior or posterior cortical layer of the lens a stellate or rosette-shaped figure, the center of which corresponds to the pole of the lens, while its rays are directed radially toward the periphery. Anterior cortical cataract is much rarer than the posterior variety; sometimes both are found together. The two forms of cataract occur generally in those eyes which suffer from affections of the deep parts, like chorioiditis, retinitis pigmentosa, fluidity of the vitreous, etc.; the disturbance in the nutrition of the lens, thus produced, induces the formation of an opacity in it. The interference with vision is usually considerable, since it is caused not only by the opacity of the lens, but also by the involvement of the fundus. Anterior and posterior cortical cataracts remain stationary for many years and then at length pass into total opacity of the lens. They accordingly constitute a transition between the stationary and the progressive forms of cataract. When they have induced total cataract, they afford a bad prognosis for the operation on account of their being complicated with a lesion of the fundus.

An *anterior polar cataract* is sometimes joined by a filament of connective tissue with a central cicatrix of the cornea. This takes its origin from the time when the lens was applied to the cornea after the perforation of the ulcer. The lens and cornea were then glued together by a mass of exudation, which may afterward become organized and be drawn out into a long filament when the anterior chamber is reconstituted. Generally the filament ends by rupturing, but exceptionally it may persist all through life and connect the corneal cicatrix with the anterior pole of the lens. There are cases of anterior polar cataract in which the corneal cicatrix that is left by the ulcer does not lie in the pupillary

area, but in the periphery of the cornea. Hence, it follows that the perforation must have occurred at some point not directly in the center of the cornea. In fact, to produce the cataract, it is enough that the lens as it pushes forward after perforation has taken place should apply itself by its umbo to the posterior surface of the cornea, even though the latter itself is sound.

Corneal opacities acquired in very early childhood often clear up to an extraordinary degree, so that in anterior polar cataract it is not always a dense cicatrix, but often only a slight cloudiness of the cornea, that is found. If this latter is overlooked, the method of development of the cataract might become a matter of doubt.

Anterior polar cataract, through subsequent contraction of the newly formed tissue, sometimes causes a folding of the adjacent portions of the anterior capsule, visible upon examination with a magnifying-glass. This folding may afterward lead to an opacity of the lens itself (total cataract); in some cases I have seen a unilateral lamellar cataract develop in this way.

Perinuclear cataract is found in individuals who, in childhood, have suffered from rhachitis and from convulsions due to it. For this reason Horner has promulgated the view that the rhachitic interference with nutrition, besides affecting the bones, affects epithelial structures too, especially the teeth and the lens, which in its development has much in common with the teeth. Upon this supposition, those layers of the lens would become opaque that are formed during the period when the nutrition is being disturbed by rhachitis; while at a later period, after the disappearance of the rhachitis, normal transparent layers of lens-substance are again deposited. If this is correct, we are not only able to understand why lamellar cataract presents a shell-like opacity, but we can also from the opacity draw a conclusion as to the point of time at which the lamellar cataract was formed; for, since at the time of its development the opaque zone was the most peripheral layer of the lens, its size would give us the volume which the lens had at the time when the lamellar cataract was formed. But from the size of the lens we can deduce the age at which the lamellar cataract developed. Accordingly, the smaller the equatorial diameter of the opaque disk, the less must we assume this age to be. Other means for determining with certainty the point of time at which the lamellar cataract has developed we do not as a rule possess. An undoubted case of congenital lamellar cataract is known (Becker), and as undoubtedly the development of a lamellar cataract in a child of nine has been observed (De Wecker). In most cases, probably, the formation of the cataract occurs within the first years of life, at the time at which convulsions also make their appearance in children; generally, though, the cataract is not discovered until later. For the persons affected with it are not blind, but are simply weak-sighted; hence the affection from which they suffer does not generally make itself apparent until the time when greater demands are made upon the eyes—that is, in the first years of instruction at school.

Deutschmann, Beselin, Lawford, and Schirmer have made anatomical examinations of lamellar cataracts. These showed that within the opaque layer numerous small gaps filled with liquid (vacuoles) are present between the lens-fibers. In addition, larger fissures occur surrounding the nucleus like a shell.

Lamellar cataract does not always present a uniformly gray disk, but frequently exhibits a complicated structure. Densely opaque dots or graceful figures are often noticed in the anterior or posterior opaque layers, or markedly opaque sectors are contrasted with the less opaque matter in their vicinity.

Again, while the riders correspond to partial opacities of a neighboring layer, the latter may also be opaque through its entire extent so as to surround the inner opaque layer like a cloak, while at the same time separated from it by a thin transparent stratum. Thus there originate double or even triple lamellar cataracts.

People suffering from lamellar cataract are often myopic; for, on account of the indistinctness of the retinal images, they are compelled to bring objects closer to the eye in order to make up in size of the retinal image what it lacks in clearness. From this apparent myopia a real one usually develops subsequently, because, through the habit of constantly looking at objects near by, the posterior wall of the eyeball becomes stretched and the axis of the eyeball elongated.

Cataracta corticalis anterior and *posterior* are sometimes observed after injury of the lens, and that both when the lens-capsule is opened and also in simple contusion of the lens without opening of the capsule. The stellate form of opacity in the cortex develops in the days immediately succeeding the injury, and may either rapidly pass over into complete opacity of the lens, or may remain stationary, or may even disappear again. The rapid development of these opacities, as well as the fact that they can disappear, indicate that they do not consist in a clouding of the lens-fibers themselves. Probably what occurs is a distention of the preformed cavities (lymph-spaces; Schlösser; see p. 255) in the lens with fluid, which may disappear from them again.

(B) PROGRESSIVE CATARACTS.

91. Progressive cataracts begin as partial opacities, which steadily extend until at length they occupy the entire lens. This is true, with the qualification that the portions of the lens already sclerosed—that is, the nucleus—ordinarily remain exempt from opacity. Hence, opacity of the lens in all its parts occurs only in young persons whose lens as yet has no hard nucleus; in older people the nucleus generally remains transparent. The time required for a lenticular opacity to involve all the parts that are capable of becoming opaque at all, varies very greatly. There are cases in which a transparent lens becomes completely opaque within a few hours, while other cataracts require many years before they can become total.

We distinguish in the course of a progressive cataract four stages, which are best marked in the most frequent form of cataract, senile cataract. To this form, therefore, the following description mainly applies:

First Stage. Cataracta Incipiens.—Opacities occur in the lens, between which are found spots that are still transparent. The shape of the opacity is most frequently that of sectors (so-called spokes), the base of which looks toward the margin, and their apex toward the poles of the lens.

Second Stage. Cataracta Intumescens.—In proportion as the lens becomes more opaque, it contains more and more water, and hence swells up. This increase in volume of the lens is recognized by the increasing shallowness of the anterior chamber. As long as the opacity

has not reached to the anterior capsule, the iris throws a shadow upon the lens. To see this, a light is held near the eye and to one side of it. Then a black shadow is seen on the side of the pupillary margin that is turned toward the light (Fig. 81 *A*). This arises from the fact that the opaque layer of the lens upon which the iris casts its shadow lies some distance behind the iris. This opaque layer acts like a screen which receives the shadow of the iris. An observer, looking at the eye from in front, sees then that portion of the shadow which does not lie behind the iris itself (*a b*, Fig. 81 *B*). This portion of the shadow becomes narrower the nearer the opacity approaches the iris, and finally disappears altogether when the opacity reaches the anterior capsule.

Fig. 81 A.



Fig. 81 B.

Fig. 81 A.—Shadow of the Iris seen from in Front.

The crescentic shadow appears on the side of the pupillary margin which is turned toward the source of light, *L*.

Fig. 81 B.—Shadow of the Iris upon the Lens in Schematic Cross-section.

The inner layers of the lens are supposed to be opaque, the peripheral ones transparent. The source of light, *L*, throws upon the surface of the opacity a shadow from the iris, whose central border is at *b*. An observer, looking from a point straight in front of the eye, sees a portion of this shadow, of the width *a b*, running at the side of the pupillary margin of the iris.

The distended lens has a bluish-white color and a marked silky luster of the surface, and shows very clearly the stellate markings of the lens.

During the stage of intumescence the opacity of the lens becomes total. As soon as this has taken place the lens begins gradually to lose water, so that it returns once more to its former normal volume. The lens then enters upon the—

Third Stage (*Stage of Maturity*). *Cataracta Matura.*—The anterior chamber is once more of normal depth, and the iris no longer casts a shadow—a proof that the opacity of the lens has become total. The lens has lost its bluish-white, iridescent look, and has a dull-gray or brownish color; the radial markings of the stellate figure of the lens are still for the most part recognizable. A mature cataract has the property of separating readily from its connection with the capsule. This is caused partly by the fact that the disintegration of the lens-fibers has proceeded straight up to the capsule, partly by the fact that the lens, formerly enlarged, has diminished again in volume, and thus the connection between the surface of the lens and the capsule is

loosened. The lens then lies in its capsule like a ripe fruit in its rind (Arlt); and thus it has become ripe for operation, since it is of great importance that the cataract should be capable of removal from its capsule without any portions of the lens remaining behind. These would form a new opacity in the pupil—a secondary cataract—and thus render the result of the operation doubtful.

Fourth Stage. Cataracta Hypermatura.—The further metamorphosis of a mature cataract consists in the complete disintegration of the opaque lenticular mass. This becomes converted into a pultaceous substance, which no longer shows any trace of the original structure of the lens, its formation out of sectors, etc. Hence, in a hypermature cataract we either see no markings at all, or nothing but irregular spots—no radii nor sectors. The consistence possessed by a hypermature cataract depends upon whether the gradual loss of water, which began after the intumescence of the cataract and reduced the latter to its normal volume, keeps on or not. If the loss of water continues, the pultaceous mass which is produced by the disintegration of the lens-fibers becomes more and more inspissated. It dries up along with the nucleus of the lens into a flat, cake-like mass; the anterior chamber consequently becomes deeper and deeper. This is the ordinary form of hypermature senile cataract.

If the loss of water ceases after the lens becomes entirely opaque, the lenticular mass grows more fluid in proportion as it breaks up into constantly smaller parts. If this process goes on in a young person, in whom there is no hard nucleus in the lens, the latter becomes liquefied through and through, so that the lens consists of a milky fluid (*cataracta fluida* sive *lactea*). If this metamorphosis affects an old lens, the nucleus, which has failed to become opaque, also escapes disintegration, and sinks under the form of a heavy compact mass to the bottom of the liquefied cortex. The cataract has then a homogeneous white appearance, corresponding to the milky cortex, and in its lower portion presents a brownish shading, which is bounded above by a semicircular line, and which corresponds to the upper half of the dark nucleus. As the latter alters its position with the movements of the head, the brownish shadow can also be seen to change its place. This form of cataract is known as Morgagnian cataract (*cataracta Morgagni*).

A liquefied lens, however, does not remain permanently unaltered, but inspissation of the fluid occurs later on through the gradual loss of water, the disintegrated lens-masses being at the same time in part resorbed. In this way the lens constantly diminishes in volume until, in cases in which no nucleus has been present, it is transformed into a thin, transparent membrane (*cataracta membranacea*). In children, in whom resorption is carried especially far, the opaque lenticular masses disappear altogether in places. The two layers of the lens-capsule, which has remained transparent, come into apposition, and thus

there are formed perfectly transparent spots in the opaque lens, recognizable by reflected light as black gaps in the white pupil. The child begins to see again, a sort of spontaneous cure of the cataract having occurred.

When a hypermature cataract has lasted a long time, changes set in which lead to complications: (*a*) Cholesterin, or lime-salts, are deposited in the lens-mass. The former is recognizable with the naked eye under the form of shining points in the opaque lens. Calcification of the lens (*cataracta calcarea* sive *gypsea*) takes place chiefly in complicated cataracts. It is characterized by a peculiar coloration, varying from chalk-white to yellow. (*b*) The anterior capsule becomes thickened by proliferation of the capsule-cells, so that out of a simple lenticular cataract there is formed a *cataracta capsulo-lenticularis*. The capsular opacity presents itself under the form of a dense, white, irregular spot upon the gray or brownish surface of the lens, usually occupying the central part of the anterior capsule, over an area about corresponding to the pupil. (*c*) The lens becomes tremulous. The shrinking of the hypermature cataract affects not only its thickness, but also its equatorial diameter. In proportion as the latter diminishes in size, the zonula of Zinn is stretched, and thereupon undergoes a corresponding atrophy of its fibers. Consequently, the attachment of the lens becomes imperfect, so that the lens shakes with the movements of the eye (*cataracta tremula*). Spontaneous luxation even of the lens may take place through partial or total rupture of the zonula. In consequence of these changes an operation for hypermature cataracts is often more difficult, and gives rather less favorable results than the operation in the stage of maturity.

As the diagnosis of the stage of a cataract is that which determines the question of the performance of an operation, and hence is of great practical importance, the distinguishing signs of the separate stages will be summed up in the following brief words:

1. Cataracta incipiens. Anterior chamber of normal depth; transparent spots still to be found in the lens between isolated opacities.

2. Cataracta intumescens. Anterior chamber shallower; iris usually casting a shadow; lens bluish-white and having a silky luster; markings of the stellate figure of the lens very distinct.

3. Cataracta matura. Chamber of normal depth; no shadow cast by the iris; markings of the stellate figure of the lens still recognizable.

4. Cataracta hypermatura. Anterior chamber of a normal depth; no shadow cast by the iris; surface of the lens appearing quite homogeneous (in the case of liquefaction), or showing irregular dots and spots in place of the radial markings of the lens-star.

According to their *consistence*, total cataracts are distinguished into hard and soft (*cataracta dura* et *mollis*). This has reference to the nucleus of the cataract. By soft cataract, therefore, we understand

one having no distinct hard nucleus (Fig. 60), while those cataracts are known as hard which inclose a hard nucleus, although the cortex is soft (Fig. 59). The nucleus, in fact, does not usually become subject to cataractous changes, and therefore retains its natural consistence. The distinction between hard and soft cataract is made chiefly from a practical point of view. For the extraction of cataract from an eye a section must be made, the dimensions of which depend mainly upon the size of the nucleus. The wound must be large enough for the nucleus to pass easily through it, as otherwise the nucleus either can not be removed from the eye at all, or, as it is squeezed violently through the wound, it crushes the lips of the latter. The soft cortex is stripped off from the nucleus, as the latter passes through the wound, and can subsequently be readily removed from the eye by stroking; it is unnecessary, therefore, to pay any regard to it in making the section. Hence, in soft cataracts a small wound (simple linear extraction) suffices, while in hard cataracts the wound must be longer, in proportion to the size of the nucleus.

For these reasons it is of importance before undertaking an operation to diagnosticate whether the cataract contains a hard nucleus, and if so, about how large it is. For this purpose we must take into account the age of the patient and the appearance of the cataract. The age is to be considered, inasmuch as the development of the nucleus is in direct proportion to it in healthy, and hence also in cataractous, lenses. Cataracts of children and young people have no nucleus; in older persons the nucleus is in the main larger the more advanced the age is. Nevertheless, it is not to be forgotten that very considerable individual variations occur with regard to the size of the nucleus. A careful inspection of the cataract, however, enables us to see the nucleus directly. It can be recognized upon lateral illumination as a dark reflex emanating from the depth of the lens. From this we can estimate its size, and from its color estimate its consistence also. The darker—reddish or brownish—the nucleus is, the harder (and usually, too, the larger) is it.

It may happen that the sclerosis of the lens has advanced so far that it has been entirely, or all except a small residue, transformed into a nucleus. It is then converted into a hard, dark-brown, transparent mass. The pupil looks black, and it is only on careful inspection—especially with the aid of lateral illumination—that we recognize that it is of a peculiar dark brown. This condition is known under the name of *cataracta nigra*. Properly speaking, it is not a cataract in the true sense of the term, but a far-advanced senile alteration of the lens—a total sclerosis of it. Such lenses are always large and hard, and require a large section for their removal.

The opacities which make their appearance in the beginning of the development of a cataract possess most frequently the following forms:

1. Opaque *sectors* (radii) which look grayish-white by reflected light, black by transmitted light, and whose apices converge toward the pole of the lens. They correspond to the natural grouping of the lens-fibers into sectors. Sometimes they are broad and triangular, sometimes narrow, being occasionally represented by nothing but slender radii. That form of cataract in which the lens is traversed by numerous, very slender radiating lines is found chiefly in myopic eyes. The clouding of the sectors begins in their periphery, where they are visible with the ophthalmoscope long before their apices project into the region of the pupil and impair vision.

2. A *diffuse, smoke-like cloudiness* occupies the central portion of the lens. It belongs to those layers which directly inclose the nucleus. This sort of opacity disturbs the sight much earlier and to a much greater extent than do the opaque radii, because, in the first place, they are from the start found in the pupillary area; and, secondly, because they are diffuse and do not have any spots that are quite transparent.

3. We find, as an extremely frequent occurrence, in the eyes of old people, an opaque ring which lies near the equator of the lens, and which, on account of its resemblance to the arcus senilis of the cornea, was named by Ammon the *arcus senilis* (sive *gerontoxon*) *lentis*. It does not impair vision, since it lies wholly behind the iris, and shows little tendency to spread.

Generally, in commencing senile cataract, several or even all of the above-mentioned forms of opacity are met with.

4. In young people, cataract often begins in the form of irregular, macular or cloud-like opacities.

How long a time does it take for a cataract to become ripe? The *progress* of a cataract is sometimes rapid, sometimes slow, the latter especially in senile cataract, which not infrequently remains in an almost unchanged condition for years. Hence, if we find in an elderly patient the first stages of a cataract which as yet produces no interference with vision worth mentioning, the indication is, in the interest of the patient, not to frighten him by communicating his condition to him, as he perhaps may enjoy sufficiently good vision for several years yet to come. For our own security we may communicate the discovery to some person intimately connected with the patient. Sometimes the lenticular opacity progresses by fits and starts—a cataract which has remained unchanged for quite a long time becoming almost completely mature within a few months or even weeks.

For these reasons it is for the most part impossible to answer with precision the patient's question as to when the cataract will become ripe. The following diagnostic points may serve for an approximate determination: The lenticular opacity develops the more rapidly the younger the person is. Light-colored cataracts become matured more rapidly than dark ones, and those with broad radii more rapidly than those with slender radii. A cataracta nigra can never become matured in the ordinary sense of the word, since it is not a cataract proper but a sclerosis of the entire lens which may be said to have been converted in toto into a nucleus, and hence always preserves a certain degree of transparency. For the laity a criterion of the ripeness of a cataract—i. e., of its readiness for operation—is the fact that the eye is no longer in a condition to count fingers. This does not hold good for dark cataracts, which generally do not become so opaque that the patients can not perceive the larger-sized objects. Nevertheless, these can be operated upon with good results, since the

lens has been transformed into a hard, horny, translucent mass which can readily be shelled out cleanly from its capsule.

The rapidity of ripening is also influenced by the etiology of the cataract. Certain cataracts, such as diabetic, traumatic, and glaucomatous cataracts, furthermore complicated cataracts, particularly those resulting from detachment of the retina, are distinguished by their rapid rate of progress. The time required for ripening can be most readily determined, at least in the case of senile cataract, when the other eye already contains a ripe cataract and the time that this has taken to develop is known, since presumably the rate of advance of the cataract is the same in both eyes.

The intumescence of the maturing cataract is caused by the swelling of the cortex. It is, therefore, more distinctly pronounced the softer the cataract is, since then there is much cortex; on the other hand, it is altogether wanting in the dark, hard cataracts which consist of scarcely anything but nucleus. For the same reason, too, the ordinary phenomena of hypermaturity do not occur in the latter; instead of undergoing further disintegration, the horny lens remains unchanged, or, at most, thickening of the capsule is added.

By a combination of thickening of the capsule with various degrees of consistence of the lens, special varieties of cataract are produced. A liquefied lens in a thickened sac-like capsule is called *cystic cataract* (*cataracta cystica*). By the term *cataracta arida siliquata* is understood a shriveled cataract within a thickened capsule; deriving its name (dry, silique-shaped or pod-like cataract) from its similarity to a dried pod (sĭlique).

By the shriveling of the cataract in the stage of hypermaturity the anterior chamber becomes deeper, until finally the iris, instead of projecting forward in the shape of a cone, lies in a plane. If the diminution in the size of the cataract keeps on, the iris is not drawn backward so as to form a funnel, except when it is joined to the lens-capsule by posterior synechiæ. Otherwise the iris remains stretched in a plane, and the shriveling lens becomes farther and farther removed from the iris, so that the latter, deprived of its support, becomes tremulous. A dark interspace is then seen between the iris and the lens, and the iris again throws a shadow upon the latter. This shadow must not, of course, be confounded with that which is found in immature cataract. Nor should the black rim of pigment on the margin of the pupil, seen in every case of cataract, be regarded as the shadow cast upon the iris. It is easily distinguished from a shadow by its appearance, and also by the fact that it is visible not only at the side toward the light, but all round the iris.

In the stage of hypermaturity in which the opaque layers become thinner through resorption, the sight often increases a little, so that, for example, the fingers can be again distinguished. Really serviceable vision sometimes comes on in young people, when the resorption goes on so far that spots are formed which are perfectly transparent. In senile cataract, in which a hard nucleus is present, it is extremely rare for a spontaneous restoration of sight to occur, although it may take place in the following ways: (*a*) By the resorption, in exceptional cases, not only of the cortex but also of the nucleus to such an extent that nothing but slight opacities remain. (*b*) By the formation of a Morgagnian cataract, and the subsequent transformation of the fluid portion of the cataract into a clear, transparent liquid. Then the upper part of the pupil is transparent and black, while the brown nucleus is seen lying in its lower part. These cases are not so very rare, only they were not formerly correctly diagnosticated. I my-

self, since I have begun to pay attention to the subject, have seen six such cases which formerly I would probably have looked upon as cataracts which had become diminished in size and luxated downward. Afterward the transparent liquid, and even the nucleus itself, may be resorbed, so that only a thin membrane is left. (*c*) By spontaneous dislocation of the lens, so that the pupil again becomes partly or entirely black.

Operations upon hypermature cataracts give rather less favorable results than those performed at the time of maturity. The chief disadvantages of operating in the stage of hypermaturity are: 1. Prolapse of the vitreous during the operation, on account of the defective condition of the zonula. 2. Retention of the thickened and opaque capsule. Since this can not disappear by subsequent absorption, as the opaque lenticular masses may do, it forms a permanent secondary cataract. 3. The possibility of the products of the disintegration of the lens-substance, especially cholesterin, coming into direct contact with the iris, and exerting such an irritating action upon it that iritis develops. I once operated by discission upon a shriveled cataract which contained scarcely anything else between the two layers of capsule but a large amount of cholesterin crystals. After the anterior capsule had been opened, the crystals poured into the anterior chamber, where they could be seen floating about like glistening points in the aqueous and afterward sinking to the bottom after the fashion of a hypopyon. Although the operation itself was done without the iris receiving any mechanical injury, a severe irido-cyclitis nevertheless ensued, in consequence, I suppose, of the irritation of the iris due to the cholesterin.

To what has been said in regard to the nucleus of the lens and its behavior in cases of cataract, exceptions occur. There are cases of cataract in children, in which the lens, instead of being soft, has quite a hard nucleus or even has a wax-like consistence throughout. On the other hand, cases of senile cataract have been observed without nucleus. In exceptional cases, the nucleus and not the cortex may be the first part to become opaque in the lenses of adults (*cataracta nuclearis.*)

C. Etiology of Cataract.

92. 1. *Cataracta Congenita.*—The cause of this is either a disturbance of development or an intra-uterine inflammation of the eye. Both the stationary partial cataracts (particularly anterior and posterior polar cataract) and the progressive forms of cataract may be congenital. Congenital cataracts are usually bilateral and often inherited. Heredity, however, makes its influence felt in non-congenital cataracts also, and, in fact, even in senile cataract; there are families in which many of their members (and that, too, for the most part at an uncommonly early age) become blind from senile cataract.

2. *Cataracta senilis* is by far the most frequent form of cataract. Indeed, it occurs very frequently in old people, but not so regularly as to be regarded as a physiological attribute of age—as the turning gray of the hair is, for example—but as a pathological process. It usually does not make its appearance until after the fiftieth year of life, but is exceptionally observed in the years between forty and fifty. The fact of a cataract occurring in an elderly person does not of itself justify the

diagnosis of senile cataract. An old man may get a cataract in consequence of traumatism, etc. Hence, to establish this diagnosis, it must be demonstrated that neither in the eye nor in the body in general are there diseases which might account for the development of the cataract, so that the latter can only be attributed to the effect of age. Senile cataract always affects both eyes, but rarely at the same time, so that generally one eye is in advance of the other in respect to the development of its cataract.

3. *Cataract due to General Diseases.*—The most frequent of these is diabetic cataract. This mainly develops when the amount of sugar in the urine is high, and usually matures rapidly. It is always bilateral. In this category are also to be set down perinuclear cataract depending upon rickets and cataract due to nephritis.

4. *Cataracta Traumatica.*—All injuries which make an opening in the lens-capsule result in opacity of the lens. If a fresh, transparent lens is taken out of its capsule and laid in water, it absorbs water abundantly and in so doing becomes opaque, swells, and finally breaks up into layers through a process of cleavage. Precisely the same thing takes place in the living eye through the imbibition of aqueous by the lens, when the capsule has been opened through traumatism, so that the aqueous comes into direct contact with the lens-substance. When the traumatism affects the posterior capsule, the vitreous acts in the same way as does the aqueous.

The opening of the capsule usually occurs through direct injury inflicted by means of a punctured or incised wound, through the penetration of a foreign body, and also designedly through an operation (discission). Contusions of the eyeball also, which do not perforate its tunics, may cause opacity of the lens. In many of these cases it is likely that rupture of the capsule, probably in the region of the equator of the lens, is caused by the contusion. But this does not exclude the possibility of lenticular opacity being caused by simple concussion without the capsule being opened—the opacity in that case evidently not depending upon imbibition of aqueous.

The development of cataract after injury of the capsule proceeds in the following way: As early as a few hours after the injury the lens is found to be clouded in the vicinity of the capsular wound. Soon swollen lens-fibers protrude through the capsular wound, so as to project under the form of gray flocculi into the anterior chamber, and these later on break off and fall to the bottom of the chamber. While the prolapsed masses of lens-substance are becoming gradually smaller through resorption and finally disappear, new flocculi keep protruding through the capsular wound. At the same time the opacity spreads farther and farther in the lens itself, so that usually within a few days the lens is opaque throughout. The subsequent course varies. In favorable cases the eye remains free from inflammatory symptoms.

New portions of the lens keep coming through the capsular wound into the anterior chamber, where they undergo resorption. In this way the lens may disappear completely by absorption, so that the pupil becomes clean and black, and thus a spontaneous cure of the cataract takes place. In most cases, however, resorption comes to a stop earlier from reclosure of the capsular wound. Then opaque portions of the lens still remain in the shrunken capsular sac and form a shriveled cataract, which requires an operation for the restoration of sight.

In the unfavorable cases traumatic cataract is complicated sooner or later with inflammation. This, for the most part, like the cataract itself, is to be regarded as the direct consequence of the traumatism, by which the membranes of the eye (particularly the uvea) either suffer a severe mechanical injury or undergo infection. Then the clouding of the lens and the inflammation (irido-cyclitis) go on at the same time. In other cases the inflammation is the result of the cataract, the lens as it swells pressing upon the iris and irritating it to the point of inflammation. The inflammation leads to the adhesion of the opaque lens to the neighboring parts, especially the iris and ciliary body (*cataracta accreta*), and by this adhesion the operation for the cataract is rendered difficult. In the severest cases the inflammation is so violent that alone it suffices to destroy the eye, either through panopthalmitis or through plastic irido-cyclitis terminating in atrophy of the eyeball.

Increase of tension may also be caused by a swelling traumatic cataract. These cases are less dangerous if they come under the observation of a physician, since the increase of tension can be done away with by timely interference (by paracentesis of the cornea, by removal of the lens, or by iridectomy). But if such a case is not treated, the sight is usually destroyed through excavation of the optic nerve.

5. *Cataracta Complicata.*—By this term we mean cataracts occurring as the result of other diseases of the eyeball. As the lens draws its nutrient material from the surrounding tissues, it is easy to understand how in disease of the latter the transparency of the lens may suffer. The affections of the eyeball most frequently leading to the formation of cataract are: (*a*) violent inflammations in the anterior sections of the eye, such as extensive suppuration of the cornea (particularly that produced by abscess) and irido-cyclitis; (*b*) sluggish inflammations in the posterior sections of the eye, such as chorioiditis (particularly irido-chorioiditis chronica), myopia of high degree, retinitis pigmentosa, detachment of the retina; (*c*) glaucoma in the stage of glaucoma absolutum (*cataracta glaucomatosa*).

The diagnosis that a cataract is complicated may be made in those cases where there is a disease of the anterior section of the eye, simply by the external examination of the eye. Morbid changes may be made out in the cornea or iris, and also adhesions between these organs and the cataract. But if the pathological changes which have led to the

production of opacity in the lens appertain to the deeper portions of the eye, they may not be visible from the outside. Even in such cases, however, the cataract often shows itself to be complicated by its peculiar appearance. Thus in chorioiditis and retinitis pigmentosa, stellate anterior and posterior cortical cataracts are found (see page 372); and total cataracts are often distinguished by being liquefied or calcified, by the thickening of the capsule, by the assumption of a yellow or green color, by tremulousness of the lens, etc. If the cataract presents nothing exteriorly that points to its being complicated, the only way in which the diagnosis can be made is by examining the perception of light, a thing which should be done in every case. Such examination will often demonstrate the perception of light to be deficient or altogether wanting in complicated cataract.

It is of practical importance to recognize the fact that a cataract is complicated, because by this fact the prognosis and treatment are influenced. The prognosis is less favorable than in uncomplicated cataracts, both because the operation is more difficult to perform, and because the result, as far as sight is concerned, is less successful. Moreover, complicated cataracts often require special methods of operation. Many complicated cataracts are not susceptible of being operated upon at all.

In exceptional cases *congenital cataracts* are not discovered immediately after birth, but only when the child is some weeks or months old. For new-born children have very narrow pupils; and, moreover, keep their eyes shut most of the time because they sleep so much, so that no notice is taken of the fact that their pupils are not black. Then, too, as such young children do not fix their eyes upon objects, the fact that they do not see is not obvious. Partial congenital cataracts, if they do not cause any notable impairment of sight, are often not noticed until the patient is of a pretty mature age, or perhaps are never discovered at all. Not a few congenital cataracts are complicated, as can be seen from the changes found at the same time in the iris, especially posterior synechiæ. They are hence the result of a fœtal iritis. The formation of the cataract must in many cases be dated pretty far back in intra-uterine life, since children sometimes come into the world with cataracts that have already become shriveled. Here, therefore, the entire process of ripening and of shriveling has been evolved in utero.

Endeavors have been made, hitherto in vain, to discover some general disturbance of nutrition as the cause of *senile cataract*. Deutschmann thought that in a number of cases a simultaneously existing albuminuria, Michel an atheromatous degeneration of the carotid, should be regarded as the cause of the opacity of the lens. Larger statistics have not confirmed these conjectures. Both albuminuria and atheroma of the larger vessels have been found to be very frequent in old people generally, and quite as frequent in those who do not suffer from cataract as in cataractous patients. As little are we justified in believing that senile cataract occurs especially in decrepit old men. On the contrary, it is very often found in perfectly robust persons; and, moreover, those individuals who are affected with senile cataract remarkably early (in the years

between forty and fifty) are by no means prematurely aged in other respects. It hence seems as if senile cataract must be ascribed to purely local causes. In the process of transformation of the inner layers of the lens into nucleus (sclerosis) these layers diminish somewhat in volume. Under normal conditions this process of shrinking is conducted so slowly and gradually that the cortical layers are able to adapt themselves to the diminished volume of the nucleus. But, if the shrinking goes on with exceptional speed or irregularly, there may be produced undue traction and subsequent separation of those layers of the lens which lie between nucleus and cortex. In this situation fine fissures are formed in which fluid accumulates; afterward the adjacent lens-fibers themselves become opaque, and thus afford the initial impulse which leads to the opacity of the entire lens (Förster).

It was formerly believed that the cause of *diabetic cataract* was to be looked for in the abstraction of water; for if a fresh, transparent lens with uninjured capsule is laid in a solution of sugar (or even a solution of salt), the lens becomes clouded, owing to the fact that the solution absorbs water from the lens with avidity. If the opaque lens is then put back in plain water, it again becomes clear. The same experiment can also be performed upon living animals. The blood in the vessels of a frog is replaced by a solution of sugar or salt, whereupon the lenses become opaque. Then, if the frog is put back again into water, the lenses clear up once more. Upon the basis of these experiments it was assumed that in diabetes the fluids of the eye, and particularly the aqueous, act, on account of the amount of sugar they contain, by withdrawing water from the lens, so that the latter becomes opaque. This view appeared to be confirmed by the fact that diabetic cataract occurs only when the amount of sugar in the urine is great. More recent analyses of the aqueous in diabetics have, however, shown that the amount of sugar contained in it is very small, much smaller than the amount necessary in the experiments to produce opacity of the lens. Hence, although it is not to be denied that the altered composition of the fluids of the eye is accountable for diabetic cataract, nevertheless, the action of this factor is not to be conceived of simply as an abstraction of water, but more complicated disturbances in the nutrition of the lens, the nature of which is not yet exactly known, must be supposed to exist. A form of cataract which really depends upon the abstraction of water is probably that which sometimes makes its appearance in the last stage of cholera.

The prognosis of diabetic cataract, as far as the operation upon it is concerned, is less favorable than in senile cataracts, because in diabetes wounds show less tendency to heal, and, moreover, diabetes predisposes to iritis. Hence, if we have to operate upon a diabetic cataract, we wait until by suitable treatment the amount of sugar in the urine has been reduced to the lowest possible point. In diabetic cataracts which have not advanced too far sometimes a partial disappearance of the opacities have been observed, after a successful treatment of the diabetes (by the Carlsbad water-cure). These cataracts, therefore, are the only ones—and they only in exceptional cases—which can be improved by medicinal treatment.

An interesting example of opacity of the lens, due to an altered composition of the nutrient fluids, is *naphthalinic cataract*. This is produced when naphthalin is administered to rabbits. Retinitis develops first with opacities of the vitreous, and subsequently a cataract forms (Bouchard). Another way of producing cataract experimentally is to diminish the temperature of the lens by

laying ice upon the eye (Michel). Stein has set up opacity of the lens in young Guinea pigs by putting the animals in the resonator-box of a tuning-fork which was kept in constant vibration. After they had stayed several days in the box, a partial cataract developed, which afterward cleared up again spontaneously. In this case the cataract was probably produced by the fact that the vibrations of the tuning-fork caused slight, but frequently repeated, concussions of the lens. To concussion of a coarser sort are perhaps referable those cases of cataract developed after various sorts of convulsions. To this category belong epileptic, hysterical, and eclamptic convulsions. Lamellar cataract—which develops in children after convulsions—is also, according to Arlt, a direct consequence of concussion of the lens. Perhaps, too, the cases in which cataract forms in ergotism and rhaphania depend upon the convulsions which frequently accompany these diseases. After a stroke of lightning a development of cataract is observed which is variously referred to the concussion, to the evolution of heat, and lastly to the chemical (electrolytic) action of the electric spark. According to experimental investigations by Hess, electric shocks produce in animals the death of the cells of the capsular epithelium—a fact which would supply the reason of the formation of cataract in these cases.

In *traumatic cataract* it is the rule that the opacity of the lens becomes total, spreading rapidly from the site of the wound in the capsule to the rest of the lens. Exceptionally, however, cases are observed in which the opacity of the lens remains partial or indeed actually disappears again. For this to occur, the capsule wound must be very small, so that it closes quickly and the aqueous has no longer access to the lens-fibers. Most favorably situated in this regard are those capsular wounds which lie behind the iris, by the adhesion of which to the wound the latter is very soon closed up. In such cases it may happen that a circumscribed opacity remains only at the site of injury, or, if a foreign body, has penetrated the lens, along the track of the wound. By resorption of the opaque portions the opacity itself may even in part clear up again. Sometimes, too, as a consequence of injury, stellate anterior or posterior cortical cataracts develop which may likewise remain stationary or even retrogress (see page 374).

D. Treatment of Cataract.

93. Every sort of medicinal treatment is ineffectual against cataract. An improvement of the sight may be obtained by means of atropine in those cases in which the opacity occupies principally the pupillary area of the lens. In that case, after dilatation of the pupil, the peripheral transparent portion of the lens can be employed for vision.

The popular remedies and quack medicines which are alleged to have been of assistance in cataract are mostly such as contain belladonna, and act favorably upon the sight in the way just mentioned. The improvement thus obtained, however, is transient, disappearing as soon as the peripheral layers are implicated in the opacity by the progress of the cataract. A cure of cataract can be secured only by operative means. The indispensable prerequisite for this is that the light-perceiving parts (retina and optic nerves) should be healthy, a matter which is determined by careful testing of the light-perception (see § 156).

The methods of operation in vogue are mainly discission and extraction. Discission is chiefly adapted for the cataracts of young people which do not yet contain a solid nucleus. It can be performed in every stage of the growth of the cataract, and hence, too, in partial opacities of the lens. Moreover, discission is indicated in membranous cataract, not to effect their absorption, which would be impossible, but to tear a hole in them (dilaceration). The indications for extraction will be given at the same time with the description of the methods for performing it (§§ 161, 162). If possible, it is to be performed only when the cataract is ripe. In immature cataracts, layers of transparent cortex remain adherent to the capsule, and afterward become opaque, so that a secondary cataract is formed. Different operative methods have been proposed to accelerate the process of ripening, among which Förster's (iridectomy with massage of the lens, § 157) is the most employed.

Cataracts which are congenital or which develop in childhood should be operated upon as early as possible. Children can be subjected to the operation of discission with good results at the age of a few weeks. If the cataract is not operated upon, the development of the retina is arrested and amblyopia ex anopsia is produced. Consequently, the good result of a cataract-operation that is performed at a later date is comparatively small as far as vision is concerned.

In traumatic cataract our first thought should be to combat the inflammation which usually follows the injury. Iced compresses are of the most service against this impending inflammation, and also against the great swelling of the wounded lens. Removal of the opaque lens should be performed at once only when through its own great swelling it is itself the cause of inflammation or of increase of tension. Otherwise, it is better to put off the operation until later, lest the inflammatory symptoms be aggravated or brought on anew by it. If we wait a long time, often a great part of the cataract is absorbed spontaneously, so that instead of extraction a simpler operation (discission) can be performed. So, too, in complicated cataract associated with inflammatory symptoms we had better await the decline of the inflammation before operating, unless imperative indications compel us to an earlier performance of the operation.

An eye which has been operated upon for cataract is, in consequence of the loss of the lens (aphakia), hypermetropic to a marked degree, and has, moreover, lost its power of accommodation, so that distinct vision can be obtained only by suitable convex glasses.

Shall we operate upon an eye affected with a mature cataract if the other still sees well? In the case when the beginning of the development of a cataract is already present in the second eye this question is evidently to be answered in the affirmative. To know whether we shall also operate when the second eye is perfectly healthy and gives us no reason to anticipate the forma-

tion of a cataract, we must ask what gain the patient would derive from a unilateral cataract-operation. How is vision performed with two eyes, one of which has its lens and the other has not? In that case a very great difference exists between the refraction of the two eyes—that is, a marked degree of anisometropia. Binocular single vision is still possible, but the images are never sharp and distinct in both eyes at the same time. The plan that naturally suggests itself of correcting the aphakic eye by a corresponding convex glass, and thus making both eyes alike, proves to be impracticable (see § 150); but, though the patient is not able to use the operated eye for distinct vision at the same time with the other, he yet derives from it the advantage of an enlargement of the field of vision. In one-eyed people the field of vision for the single eye is limited toward one side by the nose, while the man who sees with two eyes has a binocular field of vision which stretches very far toward both sides. An eye which has been operated upon for cataract furthermore, even though it never wears a proper convex glass, nevertheless retains all its functional capacity, so that it can at once take the place of the other eye in case that should become unserviceable. It is, therefore, a reserve for the future. If we had left the cataract with the idea of not operating upon it until something had happened to the other eye, we might perhaps be obliged to operate upon a very hypermature cataract under unfavorable conditions.

Historical.—Cataract was already well known to the ancient Greek and Roman physicians. On account of the gray appearance of the pupil, they denoted it by the name of glaucoma, which word in the course of time has changed its meaning. The ancients also knew the operation for cataract, which they performed by depressing the opaque lens into the vitreous by means of a needle (depressio cataractæ). Nevertheless, they had an erroneous conception of the nature of the disease, in that they located the opacity not in but in front of the lens. This latter body, bright as crystal, the most obvious thing when the eyeball is opened, was considered by the ancients to be the true seat of vision, the percipient organ, such as now we know the retina to be. According to this view, the loss of the lens would necessarily entail complete blindness; but since the ancients knew that in the operation for cataract the opacity is removed from the pupil, and nevertheless the sight is not lost, but, on the contrary, is restored, they could not consistently regard the opacity as located in the lens. They thought the opacity which they depressed into the vitreous was situated in front of the lens. They believed that it originated from the pouring out of an opaque liquid between the iris and lens, and hence they called cataract hypochyma (ὑπό, beneath, and χέω, I pour) or suffusio, suffusion. Since it was imagined that the opaque liquid fell down from above in front of the lens, the name cataracta (cataract), which still is usually employed, came into use in the middle ages. The German word "Staar" is likewise very old. The expression staraplint (Staarblind) occurs as early as the eighth century. It means really eyes which are starr (rigid)—i. e., fail to follow objects because they do not see them. Cataract is known as "grauer Staar," on account of the gray color of the pupil, to distinguish it from "schwarzer Staar"—i. e., those varieties of blindness in which the pupil remains black (blindness due to disease of the fundus of the eye). "Grüner Staar" is glaucoma.

Our knowledge as to the true nature of cataract dates from the beginning of the last century. Even before this one or two savants, like Mariotte and Boerhaave, recognized the real situation of the opacity, without their doctrines,

however, obtaining general acceptance. In the year 1705, Brisseau, a French surgeon, had the opportunity of performing an autopsy upon the body of a soldier who had a mature cataract in his eye. Brisseau performed depression of the cataract upon the cadaver and then opened the eye, when he found that the opacity which he had depressed into the vitreous was the lens. He laid his observations, together with the conclusions drawn from them, before the French Academy, but obtained no credence. The Academy confuted him by holding up the doctrines of Galen in regard to cataract. It was not till three years later, when new proofs had been brought, that the Academy recognized the new doctrine, which soon found general acceptance.

II. Changes of Position of the Lens.

94. Changes of position of the lens always have their anatomical cause in changes of the zonula of Zinn. This in the normal eye is tightly stretched, and holds the lens so firmly that the latter remains perfectly immovable even with the most violent motions of the head. Hence, any tremor of the lens, and still more any displacement of it from its natural position, presuppose a relaxation of the firmness of this attachment. Such a relaxation can take place either from a simple elongation and loosening of the fibers of the zonula, or from their complete destruction. Changes of this sort may affect either single spots or the entire circumference of the zonula.

The *objective symptoms* of a change of position differ according as the lens is only displaced a little (subluxation), or has left its place in the fossa patellaris altogether (luxation).

(*a*) *Subluxation* may consist in the lens being placed a little obliquely, so that one edge of it looks somewhat forward, the opposite one somewhat backward. This is recognized from the unequal depth of the anterior chamber. Another sort of subluxation is produced by lateral displacement of the lens, so that it no longer lies in the center of the fossa patellaris. In this case, too, the anterior chamber is unequally deep. If, for example, the lens is somewhat depressed, the anterior chamber would be found to be deeper in its upper half, shallower below (Fig. 82). Besides, when the pupil is dilated (and, if the displacement is marked, without this) we can see the edge of the lens. This, in the example above selected of depression of the lens, would run transversely across the pupil forming an arch, which is convex upward. That part of the pupil which is situated above it and which has no lens (Fig. 82, *a*) would be a deep black, while the lower part (*l*) which contains the lens would be of a delicate gray. This arises from the fact that even the most transparent lens reflects some light. Really, therefore, the normal pupil is not perfectly black, but of a very dark gray—a fact which one can convince himself of in those cases in which, through displacement of the lens, one part of the pupil is aphakic, and therefore is of a pure black.

In both cases—that is, both in obliquity and in lateral displacement of the lens, conditions which are often combined—there occurs in movements of the eye tremor of the inadequately attached lens and with the lens of the iris also (iridodonesis).

(*b*) *Luxation* of the lens consists in its leaving the fossa patellaris altogether, either by prolapsing into the anterior chamber or by receding into the vitreous.

A lens luxated into the anterior chamber is readily recognizable from its shape. This is more convex than usual because the lens is no



FIG. 82.—SUBLUXATION OF THE LENS. SCHEMATIC.

The lens has sunk so far downward that its upper edge is visible in the pupil. In consequence of the relaxation of the zonula, it is much bulged out, and is in contact by its lower border with the ciliary processes; moreover, the lower half of the iris is pressed forward by it. Above, on the contrary, the anterior chamber, through recession of the iris, is abnormally deep. Of the beam of rays emitted by the luminous point *o*, a portion goes through the aphakic part, *a*, of the pupil; these rays, on account of the absence of the lens, are insufficiently refracted, so that they come to a focus behind the retina at *f*, and form upon the retina a diffusion-circle, *b*. That portion of the beam passing through the section, *l*, of the pupil, which contains the lens, undergoes excessive refraction on account of the increased convexity of the lens, so that the rays intersect in front of the retina at *f*, and form upon the retina a diffusion-circle, b_1. This latter gets to lie below the fovea centralis (and below the diffusion-circle *b*), because all rays passing through the lens undergo a deviation downward on account of the prismatic action of the latter. Thus two images of the point *o* are produced upon the retina (monocular diplopia).

longer kept flat by the tense zonula. It therefore assumes its maximum convexity, as it does upon the strongest effort of accommodation. If the lens is transparent, its edge appears like a curved line of golden luster, so that it looks as if a great drop of oil were lying in the anterior chamber. The anterior chamber is deeper, especially below, where the iris is pressed backward by the lens.

Luxation of the lens into the vitreous occurs more frequently than luxation into the anterior chamber. The anterior chamber then is deep because of the recession of the iris, which is tremulous. The pupil is of a pure black. The lens itself, if opaque, may sometimes be recog-

nized deep down even with the naked eye; in most cases, however, the ophthalmoscope is required in order to discover it. It is either attached to some spot of the fundus by means of exudate, or it floats about freely in the vitreous (*cataracta natans*).

Every dislocation of the lens entails a considerable *disturbance of vision.* If the lens still lies within the pupillary area, the eye becomes very myopic, because the lens assumes its maximum convexity on account of the relaxation of the zonula. Added to this is a considerable degree of astigmatism, arising from the fact that the lens, either from lying obliquely or being laterally displaced, refracts the light with unequal strength in the different meridians (regular astigmatism); or the refractive power may even vary in different sections of the same meridian (irregular astigmatism). The astigmatism attains its maximum when the lens is so greatly displaced that its edge is visible in the pupil, the latter thus consisting of a portion which does, and of one which does not, contain the lens. In such a case, moreover, double vision—monocular diplopia—is present; for the marginal portions of the lens act like a prism, whose refracting edge corresponds to the equator of the lens. By reason of this, the rays passing through the lens are deviated, so that two images (b and b_1, Fig. 82) of one object (o) are formed upon the retina. Neither of these is distinct. The image (b) produced by the aphakic portion of the pupil corresponds to that formed by a very hypermetropic eye, and would require a convex lens to make it distinct. The image (b_1) appertaining to that part of the pupil which contains the lens is that of a myopic eye, and could be made distinct by means of a concave lens. Furthermore, disturbance of vision may be produced by the development of opacity in the subluxated lens.

In luxation of the lens into the vitreous the eye acts like an aphakic one, and, if no further complications are present, see well with the correcting convex glasses. Indeed, in the old method of cataract-operation by depression, there was actually a luxation of the lens into the vitreous, designedly produced.

Dislocations of the lens usually entail secondary *consequences* which may be extremely disastrous to the eye. Subluxations often in time change into complete luxations, the vibrating lens constantly pulling upon the zonula and gradually causing it to atrophy. While subluxated lens often remain transparent for a long time, luxated lens usually soon become opaque. Often, to be sure, dislocated lens are opaque to start with, this being particularly the case in spontaneous luxations. The worst complications are those arising from the implication of the uvea. The latter is so irritated by the dislocated lens pushing and striking against it that irido-cyclitis develops, and this may even give rise to a sympathetic affection of the other eye. Increase of tension (secondary glaucoma) also frequently makes its appearance in consequence of dislocation of the lens. The most dangerous form is luxation of the lens

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

into the anterior chamber. In this case the cornea becomes opaque wherever the lens is applied to its posterior surface, and the eye, for the most part, undergoes speedy destruction through irido-cyclitis or increase of tension. On the other hand, luxation of the lens into the vitreous is the form best tolerated, especially if the lens, as time goes on, becomes smaller through resorption. In fact, in the depression of cataract, one used to count upon this tolerance of the eye toward the lens when depressed into the vitreous.

With respect to *etiology* a distinction is made between congenital and acquired dislocations of the lens.

(*a*) *Congenital* dislocations consist in a lateral displacement (subluxation) of the lens, which is known as *ectopia lentis*. The displacement is caused by the fact that the zonula is of unequal width in different directions. Most frequently the lens is found to be displaced upward, the fibers of the zonula being shortest above, longest below. For the most part, too, the volume of the lens is somewhat smaller. In after-years the ectopia usually increases, and even passes over into a condition of total luxation. Ectopia of the lens is ordinarily present in both eyes and symmetrically in both. Very often it is of hereditary origin.

(*b*) The *acquired* dislocations of the lens develop either as the result of trauma or spontaneously. *Traumatic* dislocations are principally caused by contusion of the eyeball (for the mechanism of the luxation, see page 302). Every variety of subluxation and luxation may be thus produced, according as the zonula is simply torn into or is entirely torn through. If the tunics of the eye are ruptured, the lens may even be expelled entirely from the eye. Among traumatic luxations in the more extended sense of the word may be reckoned those which develop when perforation of a corneal ulcer takes place very rapidly; in this case if the perforation is only large enough, the lens may even be discharged through it externally. *Spontaneous* dislocations take their origin from a gradual softening and disintegration of the zonula. The lens then owing to its weight sinks gradually deeper and deeper, and at length undergoes complete prolapse into the vitreous. The atrophy of the zonula occurs as a result of liquefaction of the vitreous in myopia of high degree and in chorioiditis. Again, the shrinking of a hypermature cataract may cause stretching of the zonula with consequent atrophy of it, and thus give rise to spontaneous dislocation of the lens, so that the sight which has been abrogated by the cataract is restored without an operation. If for any reason the zonula is already atrophic, the final impulse leading to total luxation is frequently afforded by a very insignificant traumatism—in fact, even by bending over, sneezing, etc.

Treatment in those cases in which the dislocation of the lens entails no further injurious consequences besides the disturbance of vision,

consists in the prescribing of suitable glasses. In those cases in which the symptoms of irido-cyclitis or of secondary glaucoma are caused by the displacement of the lens, extraction of the latter, if feasible, is indicated. Extraction is most readily performed in luxation of the lens into the anterior chamber; in this case, too, it is absolutely necessary, since otherwise the eye is lost. In subluxation, the removal of the lens is often difficult or even miscarries altogether, because prolapse of the vitreous occurs on account of the defective structure of the zonula. The extraction of a lens floating in the vitreous is impossible. In cases in which the removal of the lens is difficult or impossible, we may try to combat the inflammation or the increase in tension by means of an iridectomy, which in the case of the subluxation of the lens is made at the spot at which the iris has been pressed forward by the lens and thus irritated. If an eye which is already blind is the seat of inflammation and pain due to luxation of the lens, enucleation is the best means of relieving the pain and averting the danger of sympathetic affection of the other eye.

A transparent, luxated lens looks differently, according as we regard it by reflected or transmitted light. By reflected light the lens appears of a delicate gray, and its edge has a golden luster, almost as if it were a luminous body—that is, the rays of light which, coming from in front, enter the marginal portions of the lens, undergo total reflection at the posterior surface of the latter: for at this spot they pass from a denser medium (the lens) into a rarer medium (the vitreous), and hence are refracted away from the normal of incidence; but as, at the edge of the lens, they fall upon the posterior lenticular surface very obliquely, they undergo total reflection. They accordingly do not continue their course into the interior of the eye, but return to the observer, who therefore sees the edge of the lens shine. By transmitted light—in examining with the ophthalmoscope—the edge of the lens for the same reason appears black, because the rays which come back from the fundus to the lens are, at a point corresponding to the edge of the latter, thrown back again into the eye by total reflection.

If the lens has prolapsed into the anterior chamber, it produces through irritation of the iris a spasm of the sphincter iridis. The pupil consequently contracts, so that the return of the lens into the posterior chamber is cut off. It may even happen that on account of this spasm the lens is held tight at the moment when it is endeavoring to make its way through the pupil into the anterior chamber. The lens is then jammed in the pupil, and consequently violent symptoms of irritation are at once set up; but there are also cases in which the lens can slip through the pupil so easily that it is found sometimes in front of, sometimes behind, the iris. Sometimes the patient is able to produce this change of place voluntarily. He can bring the lens into the anterior chamber by bending his head forward and shaking it, while to bring the lens back again behind the iris he has to lie upon his back. In this case, of course, we are always dealing with lenses of diminished diameter, which can pass through the pupil without difficulty. In many instances such movable lenses are still attached to the zonula, which is then greatly elongated. If in such a case we were obliged to extract the lens, we would first bring it into the anterior chamber by

the appropriate manœuvre. Then if we cause the pupil to contract behind the lens by employing a miotic, we have, as it were, imprisoned the lens in the anterior chamber, and will be able under ordinary circumstances to remove it with ease. To be sure, these cases in which the lens shows such a great capacity for making excursions belong to the rare exceptions. The rule is, that a lens luxated into the anterior chamber stays there, and, in consequence of the violent inflammation which it excites, becomes attached by exudates to the cornea and iris. The former becomes opaque wherever the lens touches it, and may also ulcerate in the same spot; ultimately the eye is destroyed by irido-cyclitis with subsequent atrophy. In other cases the increase in tension, which almost always sets in, leads to ectasia of the sclera in its anterior portion or to a general enlargement of the eyeball.

The disturbance of vision which develops in subluxation of the lens, so far as it consists of myopia and regular astigmatism, can be corrected by glasses, but the irregular astigmatism can not be. If the dislocation of the lens is so great that a part of the pupil is aphakic, we have the choice of correcting either the aphakic portion of the pupil with a convex glass or the portion of the pupil that contains the lens with a concave glass. We recommend to the patient the form of correction which gives the better visual acuity. Sometimes, for the sake of better correction, it is indicated to enlarge the aphakic portion of the pupil by an iridectomy, and so make the eye like one destitute of a lens.

Spontaneous dislocation of the lens not infrequently occurs in ectasiæ either of the eyeball as a whole or of its anterior segments—hence in hydrophthalmus, in staphylomata of the cornea, and in anterior staphylomata of the sclera. The luxation takes place because, as a result of the bulging out of the wall of the eyeball, the space between the edge of the lens and the ciliary body becomes enlarged, so that the zonula is stretched and finally atrophies. It may even happen that the lens has become adherent to a corneal cicatrix, so as to be more and more obliquely placed as the cicatrix expands. So, too, the lens is sometimes drawn out of its place by exudates in the vitreous, which attach themselves to its posterior surface and afterward shrink. Lastly, the dislocation of the lens due to tumors (gliomata and sarcomata) pressing upon it may be also mentioned in this connection.

By *lenticonus* is meant a rare, usually congenital, anomaly of the lens, which presents a conical prominence upon its anterior (in extremely rare cases upon its posterior) surface.

CHAPTER IX.

DISEASES OF THE VITREOUS.

Anatomy.

95. The vitreous (corpus vitreum) is a transparent, colorless, gelatinous mass which fills the posterior cavity of the eye. On its anterior aspect it has a depression (the fossa patellaris), in which rests the posterior surface of the lens. By its other aspects the vitreous is applied to the ciliary body, the retina, and the optic nerve.

The vitreous consists of a clear liquid substance inclosed in the meshes of an equally transparent reticulum—the framework of the vitreous. It is traversed from behind forward by a canal, its central canal (canalis hyaloideus, canalis Cloqueti), which begins at the papilla of the optic nerve and extends to the posterior pole of the lens. During fœtal life the hyaloid artery runs in it; in the fully developed eye it probably serves as a lymph-channel (see page 250). The vitreous contains cells, the cells of the vitreous, which have a varying (round or branched) shape, and are found particularly in its outer layers. They are to be regarded as emigrated white blood-corpuscles which have traveled into the vitreous (Schwalbe). The external envelope of the vitreous is formed by the structureless hyaloid membrane. Considered from the point of view of its development, the vitreous is to be regarded as a sort of watery—so to speak, dropsical—connective tissue. It is only in the fœtus that it has vessels, from which afterward the retinal vessels are formed (see Fig. 56). In the fully developed eye the vitreous is destitute of vessels, and hence is dependent for its nutrition upon the surrounding tissues, principally the uvea. Accordingly, affections of the inner membranes of the eye, such as retinitis and chorioiditis, always result in an implication of the vitreous.

Diseases of the Vitreous.

1. **Opacities.**—These are sometimes small and sharply circumscribed, sometimes of large size. The former, which make their appearance under the form of dots, flocculi, threads, or membranes, are what are called opacities of the vitreous in the narrower sense (*opacitates corporis vitrei*). The patient himself perceives them entoptically, seeing black specks of various shape (muscæ volitantes) floating before

his eyes (*myodesopsia*)*. In addition, there is a diminution of the visual acuity, which is the more pronounced the larger the opacities are.

The *cause* of opacities of the vitreous are generally exudates deposited there in the course of inflammations of the uvea or retina; but hæmorrhages, taking place from these membranes into the vitreous, either spontaneously or as the result of injuries, may also give rise to opacities of the latter.

The *prognosis* depends upon the size and the age of the opacities. Recent opacities of the vitreous may be absorbed, so that the vitreous becomes perfectly clear again. Old opacities, on the contrary, usually resist all treatment. As regards extravasations of blood, the smaller ones may be completely absorbed, but large-sized ones always leave considerable and permanent opacities.

The *treatment*, which is successful only in recent cases, consists in the employment of remedies which accelerate absorption. Among these are potassium iodide or other remedies containing iodine, mercury, diaphoretics (pilocarpine or salicylate of sodium), and mild purgatives. Of the last named, saline purgatives, especially the saline mineral waters—e. g., of the Kreuzbrunnen of Marienbad—are particularly employed. Repeated paracentesis of the anterior chamber may also be of service by stimulating the tissue-metamorphosis of the eye.

Large-sized exudates which sometimes fill the vitreous are either of plastic or purulent nature, and are found in irido-cyclitis, chorioiditis, and panophthalmitis. They may be seen, if the media are otherwise clear enough, by lateral illumination under the form of gray or yellowish masses situated behind the lens. The plastic exudates become organized, shrink up, and thus lead to atrophy of the eyeball, while the purulent exudates are for the most part evacuated externally, after perforating the sclera, and terminate in phthisis bulbi.

2. **Liquefaction of the Vitreous (Synchisis† Corporis Vitrei).**—When observing opacities of the vitreous with the ophthalmoscope, we see that most of them float about freely in the vitreous. It follows from this that the framework of the vitreous must have been destroyed, so that this body itself is converted into a perfectly liquid mass. In operations we often have an opportunity of directly convincing ourselves of the liquefaction of the vitreous, which we see flowing out under the form of a tenacious, usually yellow-colored liquid. Instead of the vitreous being liquefied itself, it may present an accumulation of fluid upon its surface by which it is forced away from the retina. This is most frequently the case in the most anterior and posterior divisions of the vitreous (*anterior* and *posterior detachment of the vitreous*; see *v* and *h*, Fig. 150). Liquefaction and detachment of the vitreous, like opaci-

* From μυῖα, a fly, and ὄψις, vision; hence properly written myiodesopsia.

† From σύν, together, and χέω, I pour.

ties, are always the result of disease of the adjacent membranes, which are concerned in maintaining the nutrition of the vitreous—that is, they are found in retinitis, chorioiditis, myopia of high degree, etc.

The most important consequence of liquefaction of the vitreous consists in the gradual diminution in volume, which the altered vitreous may undergo, an occurrence which manifests itself in a diminished tension of the eye. In such cases, detachment of the retina and afterward even atrophy of the eyeball may supervene. Another consequence of the liquefaction is one which concerns the zonula, which becomes softened and atrophic. By this a tremulous condition of the lens, and later on even its spontaneous dislocation are produced.

3. **Foreign Bodies in the Vitreous.**—These usually excite violent inflammation—irido-cyclitis or panophthalmitis—by which the eye is destroyed. In exceptional cases it happens that a foreign body is tolerated, so that it may be seen for years, either free or enveloped in an exudate, within the otherwise clear vitreous. To be sure, even in these cases inflammation may set in, even after a long time has elapsed, and destroy the eye. Foreign bodies which have but recently entered the vitreous we try to remove as soon as possible. The chief ones that afford a prospect of doing this successfully are splinters of iron, since magnets may be employed for their removal (see page 227), while the removal of other foreign bodies is usually effected only by a happy accident. If violent inflammation has already set in, there is usually nothing left to do but to perform enucleation to avert a sympathetic affection.

Among foreign bodies in the broader sense may also be reckoned lenses luxated into the vitreous and also the cysticercus, both of which, like foreign bodies in the proper meaning of the word, give rise to severe inflammation. The cysticercus may be removed by a section made in the sclera. If this is not done in season, or if it is not successfully performed, the eye is gradually destroyed by irido-cyclitis, and eventually has to be enucleated on account of the constantly occurring inflammatory attacks and of the danger of sympathetic inflammation.

Under normal conditions the hyaloid artery is no longer present even in the eye of the new-born infant. In exceptional cases, however, remains of it may persist during life. These present themselves usually under the form of a gray filament, which stretches from the papilla out into the vitreous, and may even reach up to the posterior pole of the lens. Posterior polar cataract occurs in connection with it. In many animals—e. g., in the frog and in many snakes and fishes—the vessels of the vitreous persist during life.

The embryonic vitreous contains a great abundance of cells, and is hence opaque. The cells afterward disappear, but opaque remnants of them remain in the vitreous, and may be perceived entoptically as *muscæ volitantes*. These physiological opacities of the vitreous appear under the form of transparent filaments or of strings of pearls or of small flocculi, which move not only with the eye, but also spontaneously. We see this very readily if we look suddenly upward

and then hold the eye still, when the opacities sink slowly down. They are thus distinguished from the entoptic images which are produced by opacities in the lens, as these always remain in the same place in the field of view. Physiological muscæ volitantes are not at all obvious, so that most men are not aware of their existence in their eyes. To perceive them we look at a uniformly illuminated surface —for instance, the sky. They are usually better perceived by myopic eyes. As soon as such muscæ volitantes become so distinct as to continually force themselves upon the attention and to become troublesome to the patient, they excite the suspicion of their being pathological opacities of the vitreous. To discover them the ophthalmoscope is used. If we are dealing with faint opacities, we have to employ the mirror of weak illumination, and also often artificial dilatation of the pupil. Seen with the ophthalmoscope, opacities of the vitreous appear like dark dots or filaments or membranes floating about in the vitreous. Very minute opacities afford the picture of an extremely fine stippling of the vitreous ("vitreous dust"). If the opacities are still more minute, they can no longer be perceived as discrete points; nothing but a uniform obscuration of the fundus is observed (diffuse opacity of the vitreous). The more numerous the opacities are the more hazy the fundus appears, the pupil at the same time looking redder than usual (as any bright background appears red behind a cloudy medium—e. g., the rising sun on a cloudy morning). With very dense opacities, nothing is got with the ophthalmoscope but a feeble red reflection from the pupil, or the latter may even be perfectly dark.

A particular variety of opacities of the vitreous is formed by *cholesterin crystals*. Their smooth surfaces reflect the light so strongly that when seen with the ophthalmoscope they look like golden spangles floating about in the vitreous, or like a shower of gold falling to the bottom (*synchisis scintillans*). These crystals are sometimes found in eyes that are otherwise healthy (especially in elderly people), without causing any essential disturbance of vision.

Opacities of the vitreous are exudates which, so far as they do not undergo resorption, become organized into membranes, cords, or even pretty large masses of connective tissue. In this way a new formation of blood-vessels may even take place, which run from the retinal vessels into the vitreous, and can be appreciated there by means of the ophthalmoscope. Exudates in the vitreous do not originate in the latter itself, but from an inflammation of the membranes (uvea and retina) surrounding it. The disturbance of vision which is set up by a recent cyclitis, chorioiditis, or retinitis, is in large part attributable to the opacity of the vitreous, which exists at the same time. Primary inflammation (hyalitis) of the vitreous, which not only is devoid of vessels, but also contains scarcely any cellular elements, can be assumed to exist in only a very few cases —e. g., when a small foreign body is situated in the midst of the vitreous, and there becomes the center of a focus of inflammation.

Opacities also form as the result of *hæmorrhages* into the vitreous. These occur after injuries and also spontaneously in chorioiditis, retinitis, and myopia of high degree, and, furthermore, are not infrequent in old people with atheromatous vessels. Sometimes, too, in eyes which are otherwise healthy hæmorrhages into the vitreous are observed, which appear spontaneously, recur repeatedly, and permeate the vitreous so thoroughly that even quantitative perception of light is abrogated. This affection is observed chiefly in young men, sometimes in conjunction with frequent attacks of epistaxis. A cause for the repeated hæmorrhages is usually not discoverable. If the hæmorrhages recur

frequently, the vitreous never clears up again perfectly, but masses of connective tissue ultimately form in it, so that the sight remains seriously and permanently affected.

The disturbance of vision caused by opacities of the vitreous is regulated by their total amount. Isolated flocculi in the vitreous may coexist with normal visual acuity. When the opacities are numerous, the statement is often made by the patients that their sight shows great variations within short periods of time. This fact is also noticed when tests of the vision are made. While at first the patient, when placed before the card with the test-types, does not begin to see the large letters, he can sometimes distinguish even the small letters after he has had his gaze fixed upon them for a pretty long time. Then all at once he sees much worse again. This comes from the mobility of the opacities, which, when the gaze is kept steadily fixed for a long time, sink to the bottom of the vitreous, so that the central portions of the latter become clear; then any great movement of the eye stirs them up again.

The *entozoa* occurring in the vitreous are the Filaria oculi humani and the Cysticercus cellulosæ. Of the former but very few cases have so far been known. The *cysticercus*, too, is not frequent; while in some countries, especially in North Germany, it is pretty often seen, in others, like Austria,* it is an extremely rare thing for it to be observed. The cysticercus is the scolex of the Tænia Solium. For a patient to acquire a cysticercus, the eggs of the tænia must have got into his stomach. This may take place from the fact that the patient himself harbors a tænia, joints of which find their way into his stomach. Here they are digested and the eggs contained in them set free. Most patients, however, who suffer from the presence of a cysticercus do not have a tænia themselves. Hence, the eggs of the tænia must get into the stomach from outside along with the food (and most frequently with the drinking-water). In the stomach embryos develop from the eggs, having hooklets, by means of which they penetrate the stomach-walls and get into the blood-vessels. The blood-current then carries them into different parts of the body, where they again leave the vessels, bore into the tissues, and there grow into cysticerci. In the eye the cysticercus first develops beneath the retina, detaching it from the chorioid. When it has reached a certain size it perforates the retina and gets into the vitreous; but it may also enter the vitreous directly (from the blood-vessels of the chorioid).

---

* [And America.—D.]

CHAPTER X.

DISEASES OF THE RETINA.

Anatomy and Physiology.

96. The retina is a thin membrane which in the living eye is perfectly transparent and of a purplish-red color. This latter depends upon the visual purple contained in the rods (Boll). After death the retina becomes very rapidly opaque, and, as at the same time the visual purple is bleached out under the influence of light, the retina in the eye of a cadaver appears under the form of a white, very frail membrane. In the living retina, too, pathological changes manifest themselves at once by a loss of transparency, just as is also the case with the other transparent tissues like the cornea, lens, and vitreous. Thanks to this property, we discover even minute alterations in these organs very early.

There are two points that are particularly prominent in the retina when in situ. One is a small white disk, which lies to the inner side of the posterior pole of the eye, and from which the vessels of the retina emanate; this is the point of entrance or head of the optic nerve, the *papilla nervi optici*. The second spot occupies precisely the posterior pole of the eye, and is distinguished by its delicate yellow color. It is hence called the yellow spot, the *macula lutea*. In its center is found a small depression, the fovea of the retina, or *fovea centralis* (*f*, Fig. 48). If we try to lift the retina from the subjacent chorioid by means of a forceps, we see that it is connected with its bed only at two places. One of these is the head of the optic nerve, the other is the anterior border of the retina. The latter is formed by a zigzag line, and hence bears the name of the *ora serrata* (*o o*, Fig. 48). The same line also corresponds to the boundary between the chorioid and ciliary body, and extends farther forward on the nasal than on the temporal side. Except at the two spots just named, the retina everywhere simply lies upon the chorioid without being attached to it.

A histological examination of the retina shows that it arises from the optic nerve, the fibers of which spread out in all directions and form the innermost layer of the retina, the fiber-layer. From this latter the fibers pass through the different layers of the retina as far as its external surface, where they end in the rods and cones. The stratum

of rods and cones, therefore, being the termination of the optic-nerve fibers, is the light-perceiving layer of the retina. In order that the rays of light should get to it, they must pass through all the other layers, which are placed in front of it. Vision, therefore, can be perfect only when these layers are absolutely transparent, so that light undergoes regular refraction on its way to the most posterior (most external) layers. All opacities of the retina consequently affect the sight, even though the terminal percipient elements may be perfectly healthy.

With regard to the minute structure of the retina, which is very complicated, reference must be made to the text-books of anatomy and histology. It need only be mentioned here that the retina is composed of two kinds of tissue, the nervous tissue and the supporting tissue. The function of the latter is to maintain and support the extremely delicate nervous tissue in the proper position. The relative proportion of the two tissues changes in inflammation and particularly in atrophy of the retina, the nervous elements being destroyed while the supporting tissue becomes increased in quantity, so that the retina ultimately consists entirely of the latter.

The depression at the site of the fovea centralis arises from a thinning of the retina, the inner layers of the latter being here entirely absent. Furthermore, the retinal fovea is also distinguished by the fact that the most external layer here and also in the entire region of the yellow spot consists only of cones. The rods do not begin until at the border of the macula lutea, and as we pass toward the ora serrata, grow more and more numerous, while the number of cones diminishes in like proportion.

The membrane here described—the retina, in the narrower sense of the word—develops from the inner layer of the secondary ophthalmic vesicle (page 265 and Fig. 55 *B*, *r*). From the outer layer of the vesicle (Fig. 55 *p*) is developed the pigment-epithelium (page 246), which therefore must, on embryological grounds, be counted in with the retina (in the wider sense of the term). It lies upon the chorioid at the outer side of the retina, and, because it remains behind when the retina is removed from the chorioid, was formerly regarded as belonging to the latter. The connection between the retina and pigment-epithelium consists in the fact that the cells of the latter send minute ciliform processes in between the rods and cones; in these processes lie the minute crystals of the brown retinal pigment.

The cessation of the retina at the ora serrata is apparent only; the microscope shows that under a simpler form it extends still farther, even up to the edge of the pupil. It therefore lines the inner surface of the ciliary body and the posterior surface of the iris. The portion of the retina lying upon the ciliary body is called the pars ciliaris retinæ. In the area occupied by this portion, the external layer of the retina, or pigment-epithelium (Fig. 47, *p e*), is more darkly pigmented,

so that this division of the interior of the eye is characterized by a particularly dark color (*o r*, Fig. 48). The inner layer of the retina—the continuation of the retina, in the narrower sense of the word—is here reduced to a single stratum of cylindrical cells (*p c*, Fig. 47). At the spot where the two layers of the retina pass over upon the iris, the difference between them becomes even less marked than before, since now the cells of the inner layer too are filled with pigment-granules. Thus the two layers in conjunction form a uniformly pigmented stratum, which, as the pars iridica retinæ (retinal pigment-layer of the iris), covers the posterior surface of the iris up to the margin of the pupil, about which the two layers turn and then unite (see page 237).

The retina has its own *system of blood-vessels*, which is almost entirely separate from the adjoining system of ciliary vessels. It is formed by an expansion of the arteria and vena centralis nervi optici, which break up into branches in the optic papilla. These branches subdivide in the retina as far as the ora serrata without anastomosing together (see Fig. 52, a, a_1, and b, b_1; Fig. 5 represents the branching of vessels in the retina as seen with the ophthalmoscope). At the papilla alone, minute communications exist between the retinal and the ciliary vessels (see page 252). The retinal arteries are hence to be regarded as terminal arteries (Cohnheim). Consequently, disturbances of circulation in the retina, arising from contraction or plugging of a vessel, can not be compensated for by means of a collateral circulation.

Within the retina, the vessels lie only in the inner layers, so that the external layers of the retina are non-vascular, and are hence in part dependent for their nutrition upon the neighboring chorio-capillaris. This is particularly true of the fovea centralis, within the confines of which the retina contains no vessels at all.

Function of the Retina.—The objects of the outer world throw their images upon the retina. It is the function of the latter to convert the rays of light, of which the images are composed, into nervous stimuli. What takes place, accordingly, is a transformation of one sort of motion —the vibrations of the luminous ether—into another, namely nervous excitation. This is without doubt simply another sort of motion of such a nature as to be transmissible within the nerve-fibers to the brain, a property which is not possessed by the vibrations of the luminous ether. The place in which the conversion of luminous vibrations into nerve-excitation occurs is the rods and cones. In what way this conversion takes place is not known, but we do know that a part of the vis viva, which the luminous vibrations represent, is used up in the production of chemical and physical changes, which we are able to follow. The chemical changes consist in the transformation of the visual purple, contained in the rods and which was discovered by Boll, into a colorless substance by the action of light (Kühne). It is very probable that besides the visual purple still other "visual substances"—i. e.,

substances which undergo chemical changes under the influence of light—exist in the retina, but that such changes are not accompanied by alterations of color, and have accordingly thus far escaped discovery. The physical changes partly consist in an increase in the strength of the electric current which normally passes from the retina to the brain (Holmgren), partly are motile phenomena of a less subtle sort, which we perceive both in the cells of the pigment-epithelium and in the rods and cones. In the cells of the pigment-epithelium, the pigment-granules, when the eye is in the dark—that is, in a condition of rest—lie in the most posterior part of the cell close to the nucleus; but if light impinges upon the retina, these granules push their way forward into the ciliform processes which extend between the rods and cones. In the rods and cones themselves, a process of contraction combined with shortening takes place under the influence of light.

The part of the retina that is the most completely equipped for vision is the fovea centralis. Within it the terminal elements, which here are exclusively cones, are more densely set than in any other portion of the retina. Each one of them here has probably a special nerve-fiber all to itself, which connects it with the brain, while in the peripheral parts of the retina it is always the case that several terminal organs are conjointly continuous with one single nerve-fiber. Thus the fovea centralis becomes that part of the retina which has the most delicate perception. And so, when we wish to get an exact perception of an object, we place our eyes in such a position that the image falls upon the fovea; we "fix" the object.

I. Inflammation of the Retina.

97. The retina is often the seat of disturbances of circulation, such as anæmia and hyperæmia, which latter frequently gives rise to hæmorrhages into it. The most extreme degrees of disturbance of circulation occur in consequence of embolism of the central artery and thrombosis of the central vein. In both cases the affected eye is made blind.

Inflammation of the retina (retinitis) is characterized first of all by a diffused cloudiness of the organ. The cloudiness varies very greatly in intensity, although in general it is greatest in the vicinity of the papilla, because here the retina is thickest. Consequently, the outlines of the papilla become indistinct and the vessels in the retina hazy. In addition, circumscribed exudates occur in the retina, usually under the form of brilliant-white, sharply defined maculæ. Retinitis is always associated with hyperæmia of the retina, evidenced by distention and tortuosity of the vessels, and often also by extravasations of blood. By the passage of the exudate from the retina into the vitreous, opacities of the latter organ are produced.

The function of the retina is impaired in proportion to the intensity

and extent of the inflammation. In the lightest cases vision may be normal, so that the patients complain simply of the presence of a light-colored cloud before their eyes. But for the most part vision is very considerably reduced, both because of the changes in the retina itself and because of the accompanying opacities in the vitreous. Circumscribed exudates cause fixed scotomata in the field of vision.

The course of retinitis is always pretty sluggish. It is only in the lightest cases that the inflammation abates completely within a few weeks, and then the visual acuity may once more become perfectly normal. But for the most part it takes several months for all the inflammatory symptoms to disappear from the retina, while the sight remains permanently impaired. Severe and, more particularly, recurrent inflammations of the retina lead to atrophy of it, pigmentation frequently occurring at the same time (through migration of pigment from the pigment-epithelium). When atrophy of the retina has once made its appearance, the sight is always abolished, either completely or all except a small remnant, and its restoration is no longer possible.

In the *etiology* of retinitis, general affections play the principal part. Retinitis appears but rarely as a local lesion, most often as the symptom of an internal disease, which is often first discovered by means of it. In such cases the inflammation of the retina is usually bilateral. According to their etiology, the following varieties of retinitis are distinguished:

1. *Retinitis Albuminurica.*—This often gives such a characteristic picture that from it alone the diagnosis of albuminuria can be made. The most characteristic appearance is a sort of stellate crown which is composed of brilliant-white spots and has the macula lutea as its central point. Every form of kidney-disease which results in albuminuria may be complicated with retinitis, but the one most frequently so complicated is the atrophic kidney. The violence of the retinitis bears no fixed proportion to the intensity of the kidney-disease nor to the quantity of albumin in the urine. The like is true of the subsequent course; the retinitis may improve while the lesion of the kidney increases, or vice versa.

2. *Retinitis Leucæmica.*—In leukæmia a striking phenomenon besides the symptoms of retinitis is the light-yellow color of the fundus which in the normal eye is red. This is caused by the lighter color of the leukæmic blood which circulates in the vessels of the choroid.

3. *Retinitis diabetica* is a pretty rare complication of diabetes (thus offering a contrast to cataracta diabetica, which so frequently accompanies diabetes). Retinitis has also been observed several times in oxaluria.

4. *Retinitis Syphilitica.*—Syphilis is one of the most frequent causes of inflammation of the retina. Syphilitic retinitis occurs both

alone and also very frequently in conjunction with a syphilitic iritis. It affords a good prognosis, in so far that it is very amenable to an energetic anti-syphilitic treatment. But yet it displays a very great tendency to recur, so that in many cases, in spite of proper treatment, partial or complete blindness supervenes.

5. *Retinitis Hæmorrhagica.*—By this is meant a form of retinitis which is associated with very abundant hæmorrhages into the retina, and is probably referable to an affection of the retinal vessels. It frequently becomes complicated later on with glaucoma (glaucoma hæmorrhagicum; see page 359).

6. *Retinitis Idiopathica.*—Under this name are grouped all those cases of retinitis which either have a purely local cause (e. g., dazzling by excess of light) or occur without known cause. There is no doubt that many of these cases will by and by show themselves to be among those which are caused by a disease in some other part of the body.

The *treatment* must be directed both against the causal lesion and against the local affection of the retina as well. The first indication is most readily fulfilled in cases of syphilitic retinitis, where an energetic treatment by inunction in most cases results in rapid improvement. The symptomatic treatment consists in the prevention of all injury to the eye by keeping the patient from any kind of work and by protecting the eye from too bright light either through the use of dark glasses or in severe cases by confinement in a darkened room. When the overdistention of the retina with blood is very great, blood-letting in the region of the mastoid process is indicated (see page 318). To combat the inflammation, and also to cause resorption of the exudate and restoration of the transparency of the vitreous, mercury, potassium iodide (both remedies being used in non-syphilitic as well as in syphilitic cases), saline purgatives, and diaphoretic treatment are employed.

Before we go more minutely into the subject of pathological changes in the retina, we must make ourselves acquainted with a congenital anomaly which by the inexperienced is frequently considered pathological. This is the *presence of medullated nerve-fibers* in the fiber-layer of the retina. The normal retina is perfectly transparent, because the optic-nerve fibers lose their medullary substance before passing through the lamina cribrosa, and hence when inside of the retina itself are transparent; but in exceptional cases after passing through the lamina cribrosa they regain their medullary substance through more or less of their extent. (In many animals—e. g., in rabbits—this is the rule.) Since the medullated fibers are opaque, there is found in these places a brilliant-white spot which terminates at the edge of the papilla and splits up at the periphery into white fibers, so as to have a flame-like look. The retinal vessels are in places covered by the masses of white fibers.

Hyperæmia of the retina may be either of arterial or of venous nature. The former accompanies all inflammations of the retina and also of the neighboring tissues, particularly the uvea, and is characterized by a quite pronounced distention and tortuosity of the arteries. Venous hyperæmia manifests itself by

dilatation and great tortuosity of the veins, while the arteries are often thinner than usual. It is produced by congestion in the veins consequent upon their compression. The compression is mostly located in the optic papilla, as in the case of glaucoma, where the increased intra-ocular tension squeezes the veins into the excavated papilla, or in the case of optic neuritis, in which the swelling of the papilla compresses the veins. Venous hyperæmia also occurs as one of the symptoms of a general venous congestion, particularly in diseases of the heart.

Hyperæmia of the retina leads to the production of *hæmorrhages* into its substance. Extravasations of blood into the retina are frequently found on examination, and occur in all sorts of sizes and shapes. Extravasations situated in the fiber-layer of the retina have striate or flame-like shapes, because the exuded blood spreads along the fibers. Hæmorrhages situated in the deeper layers of the retina or between it and the chorioid are of rounded or irregular shape. The extravasations are most frequently located in the neighborhood of the larger vascular trunks. The causes of retinal hæmorrhages are—

1. General fragility of the walls of the vessels. This is found very frequently in old people with atheromatous vessels, particularly if they have a heart-lesion at the same time. In such cases the retinal hæmorrhages are not infrequently the precursors of cerebral apoplexy.

2. Local disease of the retinal vessels or of the adjacent vessels of the chorioid. Under this head must be reckoned those hæmorrhages which occur so frequently in excessively myopic eyes in the region of the yellow spot. With the occurrence of such a hæmorrhage central vision is often permanently destroyed.

3. Overdistention of the blood-vessels by circulatory disturbances, such as active and passive hyperæmia of the retina and embolism of the central artery or thrombosis of the central vein or of their branches. In new-born infants retinal hæmorrhages are frequently found as a consequence of the disturbances of circulation which occur within a child's skull during the act of birth. In this category, furthermore, belong the retinal hæmorrhages which very frequently take place in glaucomatous eyes as a result of iridectomy. Moreover, the varieties of retinal hæmorrhage adduced under the next head may in part be caused by stoppage of the smaller vessels—e. g., the hæmorrhages in sepsis by emboli composed of masses of fungi.

4. An altered character of the blood making its influence felt upon the walls of the vessels. Under this head belong retinal hæmorrhages in extreme anæmia, particularly in pernicious anæmia, in leukæmia, scurvy, purpura, sepsis, albuminuria, diabetes, oxaluria, intermittent fever, relapsing fever, poisoning by phosphorus, extensive burns of the skin, etc.

5. Rupture of the blood-vessels due to trauma.

Retinal hæmorrhages undergo resorption very slowly, requiring weeks and months, during which they are frequently seen to take on a white color. They ultimately disappear without leaving a trace of their presence or they leave decolorized whitish, rarely pigmented, spots in the fundus. Whether a scotoma is left at the affected spot or not depends upon the degree to which the hæmorrhage has lacerated the tissue of the retina.

Embolism of the central artery was first observed by Von Graefe. The patient is made aware of his disorder by sudden and complete blindness, which appears at once upon the obliteration of the artery. If immediately afterward an examination is made with the ophthalmoscope, the signs of an extreme arterial

anæmia of the retina are found. The larger arteries are narrowed down to thin filaments, the smaller ones have become invisible. The veins, on the other hand, are not markedly contracted except upon the papilla itself; the latter appears paler. Within a short time, often within a few hours, the retina, becoming dead, loses its transparency. It becomes of an opaque milky white, most markedly so in the vicinity of the papilla and also within the confines of the yellow spot. At a point corresponding to the latter a vivid red spot stands out upon the cloudy-white background. There has been much discussion as to whether this is a hæmorrhage, or is caused by the fact that in the region of the fovea centralis the red chorioid is seen through the clouded retina because the latter is thinnest in this spot—the red of the chorioid being supposed to appear particularly pronounced from contrast with the clouded white tissues surrounding it. I have repeatedly convinced myself that both explanations are true. I saw this particularly well marked in one case in which several bright-red recent hæmorrhages were placed alongside of the dark-red spot that was due to the effect of contrast.

Later on, the cloudiness of the retina vanishes; it regains its transparency, but becomes perfectly atrophic. The optic papilla has grown whiter, the blood-vessels both upon the papilla and in the retina are few, thin, and filamentous. The blindness persists and is permanent.

Instead of affecting the central artery, the embolism may affect only a branch of it. In that case the visible alterations are limited to that portion of the retina which draws its blood-supply from the obliterated vessel. The blindness, too, corresponds then simply to the part of the retina that is diseased—that is, appears under the form of a defect in the visual field, one half of the latter or a sector of it being destroyed.

Embolism occurs in all those disorders which give rise to the entrance of clots into the circulation, and most of all in affections of the heart. The possibility of a cure exists only in very recent cases, before the death of the retina has taken place. The retina might then regain its function if we could succeed in restoring the circulation in it. The only way in which this can be accomplished is for us to try to drive the plug lodged in the central artery on into its smaller branches, where it will do less harm. With this object in view, we evacuate the aqueous by paracentesis of the cornea. In consequence of the sudden diminution of intra-ocular tension thus produced, the blood tends to flow into the eye in increased quantity, and may thus push the embolus forward if it is not too tightly fixed in its position. In addition, we try to favor the washing away of the embolus by performing massage of the eye. In this way it has been possible to restore the circulation in the retina, and with it the sight in some few cases, in which the lesion was still very recent.

What is known clinically under the name of embolism of the retinal arteries corresponds to those cases in which there are no infected emboli in question; hence, no inflammation occurs, but only the results of the mechanical cutting off of the blood-supply. The retina, being no longer nourished, simply dies. It does not indeed become necrotic, because it still obtains a supply of nourishment from the adjacent chorio-capillaris of the chorioid, although this does not suffice to keep up the function of the retina. But infectious emboli also may get into the retinal arteries, as sometimes happens in pyæmia. Then a suppurative retinitis develops, the suppuration from which extends to the other structures of the eyeball, so that the clinical picture of panophthalmitis is produced.

These cases accordingly run a course just like that of metastatic chorioiditis (see page 319).

The ophthalmoscopic picture of embolism is the expression of changes which set in when the supply of arterial blood is cut off from the retina. It is hence not confined to embolism of the central artery, but is found in occlusion of it in general, due to other causes as well. Among these causes belong thrombosis of the artery, also compression of it within the trunk of the optic nerve consequent upon hæmorrhage or inflammatory infiltration in the latter, and, finally, a solution of the continuity of the artery occurring when the optic nerve is cut or torn through in front of the point where the central vessels enter it.

Thrombosis of the central vein, which was first anatomically demonstrated by Michel, is characterized by the circumstance that all the retinal veins are enormously distended with blood, while the arteries are so attenuated as to be scarcely discoverable. The blood escapes from the turgid veins at many spots, so that the entire fundus is covered with hæmorrhages. These continually recur anew, and with their recurrence the sight which from the start has been greatly reduced is at length utterly destroyed. Like embolism, thrombosis, too, may be confined to a branch of the central vein, in which case also the changes in the fundus are present only in that district of the retina which corresponds to the region of distribution of the occluded vein.

Thrombosis of the central vein occurs for the most part in elderly persons suffering from a cardiac affection or from atheroma of the vessels; but an inflammation in the orbit may also lead to thrombosis of the central vein, probably through the development in the orbital veins of thromboses, which subsequently extend into the central vein. In this way cases of blindness are sometimes produced in the course of facial erysipelas. The erysipelatous inflammation of the skin has a tendency to penetrate in spots into the deeper parts, and there set up either infiltrations or phlegmons. Hence, abscesses of the lids, abscesses in the orbit, and, through transmission to the brain, even purulent meningitis, are observed as sequels of facial erysipelas. If, then, a case of erysipelas is complicated with inflammation of the cellular tissue of the orbit, it is sometimes found, after the erysipelas has run its course and the swelling of the lids has abated, that the eye is blind. The ophthalmoscope shows atrophy of the optic nerve with extreme attenuation of the blood-vessels. According to an observation of Knapp's, we are dealing in this case with a thrombosis of the central vein, consequent upon the inflammation of the retrobulbar cellular tissue. The blindness that is due to erysipelas may affect both eyes.

Anæmia of the retina may either develop suddenly or gradually. Its sudden development may take place as a result of occlusion of the vessels (hence, above all, in embolism of the central artery) or through their compression, as in the case of sudden increase of tension. Spasm of the retinal arteries also occurs, particularly in acute poisoning by quinine—that is, in cases in which large doses of quinine have been administered, sudden blindness (and usually deafness, too) sometimes supervene. The blindness abates again, but a certain degree of enfeeblement of sight, and more particularly a contraction of the field of vision, generally remain. Ophthalmoscopically, we find pallor of the optic nerve, and as a special feature a very great attenuation of the retinal vessels. Much more frequent than acute anæmia of the retina is that form of anæmia which sets in gradually as a consequence of retinal atrophy. The vessels of the retina then

become gradually attenuated, and may ultimately be transformed into white strands empty of blood or may vanish altogether.

In retinitis the inflammation frequently passes over to the optic papilla, and, on the other hand, an inflammation of the latter may extend far into the retina. In both cases we speak of *neuro-retinitis*, the etiology of which, therefore, is the same as that of retinitis and neuritis. Inflammation may also extend from the chorioid to the retina, so that the latter presents distinct ophthalmoscopic signs of inflammation. These cases are denoted by the special name of *retino-chorioiditis* (chorio-retinitis), although it must be maintained, for the present at least, that in every case of chorioiditis an implication of the portions of the retina immediately adjacent can be made out.

Among the inflammations of the retina, *retinitis albuminurica* is the one best characterized. In addition to the general signs of retinitis, such as haziness of the retina and of the outline of the papilla, distention of the retinal arteries, and hæmorrhages, it is particularly distinguished by the white patches in the fundus, whose pure white, often silvery, appearance depends upon fatty degeneration of the retinal elements and of the cells of the exudate. The white spots are found chiefly in two places—in a certain area surrounding the papilla and in the macula lutea. In the former situation they not infrequently form a zone of spots, which is usually interrupted at a point corresponding to the macula lutea. The latter, on the other hand, is occupied by small white stipplings radially disposed, so that a pretty, stellate figure is formed with the fovea centralis at its center. Very often the star is incomplete, the rays being fully formed only on certain sides of it. Even then, however, the picture is always characteristic enough for us to be able from it alone to deduce the presence of an affection of the kidney; but cases of retinitis albuminurica also occur which are distinguished by no special features, so that the etiology is determined only by the examination of the urine. Such an examination should therefore be made in every case of retinitis.

The connection between the kidney-lesion and the retinitis seems to consist in the development of a disease of the walls of the vessels in the retina in consequence of the altered composition of the blood, a disease which results in inflammation and degeneration of the retina itself (Duke Karl Theodor). Retinitis albuminurica is of evil prognostic significance, since the patients suffering from it usually succumb in a short time (as a rule, within less than a year) to the disease of the kidney.

In nephritis disturbance of vision may also occur under the form of a transitory blindness without any retinitis being present. The patient declares that everything suddenly becomes dark before his eyes; the disturbance of sight increases so quickly that the blindness gets to be complete within a few hours or a day. After one or more days the sight is gradually restored. Simultaneously with the attack of visual disturbance other nervous symptoms exist, such as headache, vomiting, dyspnœa, loss of consciousness, and convulsions—in short, the symptoms of uræmia. The blindness is therefore known as *uræmic amaurosis*. The fact that the reaction of the pupil to light is in most cases preserved in spite of the complete blindness proves that the location of the affection can not be in the eye or in the optic nerve, but higher up—that is, in the brain, which is poisoned by the excretory matters contained in the blood. Uræmic amaurosis is distinguished from the disturbance of vision due to retinitis albuminurica partly by the negative result of ophthalmoscopic examination, partly

by the course. Uræmic amaurosis sets in suddenly and is complete, while in retinitis albuminurica the sight is gradually reduced and is seldom annihilated entirely. The blindness, however, is permanent, while the blindness due to uræmia again gives place to normal vision, provided the patient does not succumb to the uræmic attack. Of course, the possibility of a uræmic amaurosis occurring in a patient already suffering from retinitis is not excluded.

Retinitis due to *dazzling* is produced most frequently by looking at the sun. It is particularly observed after eclipses of the sun in people who have tried to follow them with glasses that have not been blackened sufficiently or with the naked eye. I have also seen it produced after gazing too long at the electric arc-light. The ophthalmoscope shows pigment changes in the macula lutea, upon which the image of the sun has been cast. Corresponding to this spot there exists a central scotoma, which for the most part remains permanently. We must not confound with the retinitis due to dazzling that variety of inflammation of the eyes which is produced by the action of snow (snow-blindness) or by the electric arc-light. This, in addition to transitory symptoms of dazzling, consists mainly in a violent conjunctivitis (see page 102).

In retinitis there is sometimes a new formation of blood-vessels which grow out from the retina into the vitreous. In rare cases an abundant and very vascular tissue develops in this way from the retina and projects out into the vitreous (*retinitis proliferans* [Manz]). It appears that the determining cause for this is sometimes found in extensive hæmorrhages into the retina and vitreous.

II. Atrophy of the Retina.

98. Atropy of the retina is the result of its protracted inflammation, or is the final outcome of an embolism or a thrombosis of the retinal vessels. Atrophy is characterized most of all by the stenosis of the retinal vessels, which in severe cases may amount to complete obliteration, so that the vessels are either transformed into white strands or have become altogether invisible. The retina may look otherwise unchanged and transparent, or it may bear traces of the antecedent inflammation. In every case the signs of a secondary atrophy can be made out upon the papilla as well; its outline is indistinct and it is of a pale, dirty-gray color (retinitic atrophy of the papilla).

A special variety of atrophy which runs a very chronic course is the *pigmentary degeneration of the retina* (also called *retinitis pigmentosa*). This is marked by such characteristic subjective symptoms that the diagnosis can almost be made from them alone. The persons affected with this disease, even when still young, complain that they see worse whenever the illumination is reduced, and particularly at night (hemeralopia). This state of things increases with the age, so that finally the patients are no longer able to go about alone at night, while in the daytime they still see quite well. The cause of this phenomenon is disclosed by the examination of the field of vision. In the beginning of the disease the field of vision, when taken under good illumination, proves to be nearly normal, while, when the illumination is reduced, it appears very much contracted. We must conclude from this that the

peripheral portions of the retina are under-sensitive, so that under good illumination they still perform their function but do not react to weaker stimuli, such as feebly illuminated images afford. Later on, the field of vision shows itself so contracted, even under full illumination, that the capacity of orientation suffers, and the patient can scarcely guide himself alone even in daytime. At the same time direct vision may still be so good that the patient is able to do fine work. Finally, central vision too is lost, so that complete blindness supervenes. This ordinarily is not the case until late in the sixth decade or later.

Ophthalmoscopic examination shows, as the most prominent symptom of the disease, the presence of small black spots in the retina ("spotted retina"). These are of branched shape, so that they have been compared to bone-corpuscles or spiders; they are connected with one another by their processes, and occur especially along the blood-vessels. In the beginning of the disease they occupy only the most anterior portion (periphery) of the fundus; as time goes on, new spots keep forming farther and farther back, until at length they reach the macula lutea and the papilla. In the same ratio the signs of atrophy of the retina and the papilla become steadily more distinct and more prominent. Accordingly, what takes place is a gradual degeneration of the retina associated with a migration of pigment from the pigment-epithelium. The degeneration begins at the periphery and advances toward the center. In the same way, too, the retina gradually loses its function; the affected portions of it at first are simply less sensitive than before, being still stimulated to action by a pretty strong light; later on they become completely insensitive.

The disease attacks both eyes. It develops in childhood, and would seem to be congenital in many cases, although it usually is not discovered until some time after birth. Inheritance plays a great part in its production; retinitis pigmentosa occurs frequently in brothers and sisters, and also in several successive generations. The female members of the family are less frequently affected than the males. It is often found at the same time with other congenital anomalies, like deafness, mental weakness, hare-lip, or supernumerary fingers or toes, or with malformations of the eye, with persistent hyaloid artery, posterior polar cataract, etc. After it has lasted a pretty long time, posterior cortical cataract usually develops. In almost a third of the cases the disease occurs in individuals descended from consanguineous parents. Herein apparently lies the explanation of the fact that pigmentary degeneration of the retina is so frequently associated with other congenital anomalies, since these latter also occur as a result of the consanguinity of the parents.

Treatment is powerless against pigmentary degeneration of the retina, and the prognosis, therefore, is bad, since complete blindness inevitably supervenes—though not, to be sure, until after the lapse of many years.

The black spots in pigmentary degeneration of the retina are not always like bone-corpuscles, but sometimes are also rounded or irregular, like the black spots in chorioiditis. Their characteristic distinguishing mark lies not so much in their shape as in their situation, which must be assigned to the retina. This is recognized from the fact that the retinal vessels, wherever they run by the black spots, are covered by them; hence, the spots must lie in front of the vessels—i. e., in the inner layers of the retina. (In the case of pigment-spots in the chorioid we can distinctly follow the retinal vessels in their course over the spots.) Spots of pigment in the retina are not, however, limited to pigmentary degeneration of the latter; on the contrary, the migration of pigment into the retina may take place ultimately in every case of retino-chorioiditis. This is particularly the case in syphilitic retino-chorioiditis, in which the pigment in the retina can, moreover, assume the bone-corpuscle shape, so that a picture quite similar to that of pigmentary degeneration may be produced (Förster). In chorioiditis, however, there are also usually present atrophic changes (white spots) in the chorioid, which are wanting in retinitis pigmentosa. Nevertheless, there are cases in which the diagnosis is very difficult, and can only be made with the aid of the previous history and the careful testing of the function.

Not only is pigmentation of the retina not confined to pigmentary degeneration of this part, but, on the other hand, such degeneration is not necessarily associated with the presence of pigment. There are cases of what are called retinitis pigmentosa without pigment, in which the retinal degeneration takes place in a manner otherwise typical, but without the migration of pigment into the retina.

For treatment in pigmentary degeneration of the retina we may try potassium iodide, hypodermic injections of strychnine, the constant current, diaphoresis, and the like. We do this more for the satisfaction of the patient than anything else, for, although we do sometimes obtain an improvement of the sight, it is only a transient one.

The *anatomical changes* found in inflammation and in atrophy of the retina are as follows:

In inflammation the signs of inflammatory œdema exist, or those of a cellular infiltration due to extravasated white blood-corpuscles. The changes at the same time observed in the retina itself are: 1. Fatty degeneration both of the nervous elements and of the supporting tissue of the retina. 2. Thickening (sclerosis), especially in the nerve-fibers of the fiber-layer. Both the changes mentioned constitute the principal cause of the brilliant-white spots occurring in many cases of retinitis (particularly in retinitis albuminurica). 3. Hypertrophy of the supporting tissue, which becomes the more prominent in proportion as the inflammation passes over into atrophy. 4. Thickening of the walls (sclerosis) of the blood-vessels, leading to the contraction of their lumen or even to their obliteration. 5. The migration of pigment-cells from the pigment-epithelium into the retina, where they may undergo spontaneous multiplication.

When, after protracted inflammation the retina has become perfectly atrophic, it consists of a reticulum which is derived from the supporting tissue and which contains pigment-cells, but from which the nervous elements have disappeared without leaving a trace of their presence. The blood-vessels are in great part obliterated and converted into solid strands of connective tissue.

III. Detachment of the Retina.

99. Detachment of the retina (*ablatio* sive *amotio retinæ*) can be recognized from the following ophthalmoscopic changes: At the spot where the retina is detached from its bed it has lost its transparency; consequently, we do not see in this situation the red background which corresponds to the chorioid, but a delicate gray membrane which rises above the level of the normal fundus and projects forward into the vitreous. It is recognized to be the retina by the fact that the retinal vessels can be followed from the papilla out into the membrane. At spots corresponding to the folds of the detached retina these vessels show sharp bends, and in some places are even entirely concealed from view. If, as is generally the case, fluid is found beneath the detached retina, the latter forms numerous folds, which shake tremulously with the movements of the eye; i. e., the retina undulates. But if the retina is lifted out of place by a solid body—e. g., a neoplasm—the folds and the tremulousness are absent; the detachment forms a sharply defined prominence, rising steeply from the fundus.

Externally the eye looks normal, only the anterior chamber is often strikingly deep and the tension is also diminished.

The detachment of the retina is at first partial—i. e., is confined to one portion of the retina. It may develop at any spot whatever of the retina, but usually (in case it is caused by fluid) changes its place afterward, for, as the sub-retinal fluid sinks on account of its weight, it depresses the detachment gradually to the lower part of the eye; hence detachments of the retina are most frequently found low down, although their original situation may very often have been at a different spot in the fundus.

Every detachment of the retina has a tendency to enlarge and finally become total. In the latter case we find the retina pushed forward as a whole, and connected with its bed at two points only—at the papilla and at the ora serrata. Then the detached retina forms a plaited funnel, beginning at the papilla and opening out in front, a shape which Arlt has well compared to that of the flower of a convolvulus (see Figs. 62 and 69).

The subjective symptoms of detachment of the retina consist in the disturbance of vision which it causes. This is characterized most of all by a limitation of the field of vision, which is often perceived as a positive phenomenon by the patient. A dark cloud lies over a part of the field of vision, corresponding in location to the detached portion of the retina, which has partially or entirely lost its sensitiveness to light. If, as is so frequently the case, the detachment lies below, the patient complains of a dark curtain which veils from him the upper parts of objects. For instance, he does not see the head of a man standing in front of him. Hence, the examination of the field of vision is of great importance for

the diagnosis of detachment of the retina. Direct vision is preserved as long as the detachment has not yet extended to the site of the macula lutea. In total detachment there is absolute blindness.

Etiology.—The retina simply lies upon the chorioid without being connected with it anywhere except at the papilla and the ora serrata. In the dissected eye it can be lifted from its bed with the greatest ease. In the living eye the retina is kept pressed against the chorioid by the vitreous. A detachment of the retina, therefore, is possible only when either the pressure exerted by the vitreous ceases to act, or when the retina is pushed from its bed by a force greater than this pressure.

(*a*) The former variety of detachment occurs when through *disease of the vitreous* the pressure exerted by it is diminished or becomes absolutely negative—i. e., is converted into a traction. This occurs: 1. When a pretty large quantity of vitreous has escaped, in the case of injuries or of operations; 2. When shrinking of the vitreous is produced on account of some disease of it. The most frequent cases of this sort are those in which the formation of exudates has taken place in the vitreous in irido-cyclitis or irido-chorioiditis. When these exudates become organized and shrink they draw the retina, to whose surface they are attached in places, away from the chorioid. This form of detachment, it is true, can not be seen with the ophthalmoscope, but can be readily diagnosticated by means of the softening of the eyeball and the contraction of the field of vision. The form of detachment of the retina that is visible with the ophthalmoscope, and which occurs without any antecedent inflammation, is most frequently found in connection with high degrees of myopia. In this case it is a fibrillary degeneration of the vitreous which must be regarded as the cause of the detachment. A similar fibrillary condition of the vitreous, which is dependent upon senile changes, is probably at the bottom of that variety of retinal detachment which sometimes occurs in elderly persons without any other cause.

(*b*) Much less frequent are those cases in which the separation takes place in consequence of an *active propulsion* of the retina away from the chorioid. The causes of such a propulsion are: 1. An acute process of exudation from the chorioid, as occurs in purulent chorioiditis and in phlegmons in the orbit. 2. Hæmorrhage from the chorioidal vessels, whether spontaneous or due to injury. 3. Tumors of the chorioid or of the retina, and also a cysticercus developing beneath the retina.

The *treatment* in those forms of detachment which are caused by an exudation of fluid beneath the retina must seek to secure the resorption of the sub-retinal fluid. This is accomplished by diaphoresis (for producing which we make use of hypodermic injections of pilocarpine and sodium salicylate), by mild purgatives, by preparations containing iodine, and also by a pressure-bandage applied with moder-

ate firmness; at the same time the patient should keep to his bed. This treatment must be kept up for several weeks at least. When these remedies have failed us, or when from the start we are dealing with a saccate detachment produced by the copious exudation of fluid, we may try to evacuate the sub-retinal fluid by puncture of the sclera (see § 155). The puncture is made at the spot where the detachment is most pronounced, for which purpose the site and extent of the detachment must have been precisely determined beforehand with the aid of the ophthalmoscope. Only as much fluid is allowed to escape as will flow off spontaneously. After the operation, the patient should keep his bed for from one to several weeks, with a light pressure-bandage on the eye. By these methods of treatment it is generally possible in recent and not too extensive cases of separation of the retina to obtain an improvement of the sight by partial reattachment of the retina, and in especially favorable cases even to cause the detachment to disappear completely. Unfortunately, it is only in the rarest cases that these good results are lasting. As a rule, after some time the separation develops anew, and ultimately in spite of all our therapeutic endeavors becomes total, so that the prognosis of retinal detachments in general must be characterized as very unfavorable. The cause of the recurrences lies in the fact that no treatment is able to do away with the lesion which usually lies at the bottom of the trouble—namely, the shrinking of the vitreous, by which the freshly attached retina is constantly withdrawn again from its bed. In inveterate cases or in total detachment of the retina, we had better abstain from any form of treatment.

In total detachment of the retina, cataract usually develops later on, the eye becomes soft, and a slight degree of atrophy of the eyeball supervenes. Moreover, a sluggish form of iritis is not infrequent in eyes with detachment of the retina.

When the retina is detached by means of a neoplasm, enucleation of the eye must be performed. A cysticercus occurring beneath the retina, may be extracted by an incision into the sclera, and the eye may thus be preserved in a condition serviceable for vision.

One of the most important ophthalmoscopic symptoms of separation of the retina is the prominence of the detached portions as compared with the rest of the fundus. In the area of the detachment, therefore, a high degree of hypermetropia exists, from which we can calculate, by determining the refraction with the erect image, how far the retina is pushed forward. Not infrequently it lies so close behind the lens that it can actually be seen by lateral illumination when the pupil is dilated; a gray membrane, with the characteristic retinal vessels, being recognized deep down in the eye.

In detachment of the retina from the chorioid, the pigment-epithelium remains in its place upon the latter. The retina, accordingly, has a light, rather transparent gray color and a dull luster; this, with the way in which it is thrown into folds and undulates, suggests the comparison to a gray silk or satin fabric. If some blood is mixed with the sub-retinal serum, the color of the detachment

acquires a greenish tinge. After it has been detached some time, the retina becomes entirely atrophic and at the same time once more transparent. The retinal vessels over the area of the detachment are characterized not only by their marked tortuosity, but also by their darker color.

The recognition of a detachment is not infrequently made difficult or impossible by turbidity of the media, and most often of the vitreous or lens. In this case the diagnosis must be based mainly upon two factors—upon the field of vision and the intra-ocular tension. If the former is found to be contracted, and at the same time the tension is reduced, detachment of the retina is usually present—as, for example, happens in old cases of irido-cyclitis, irido-chorioiditis, and complicated cataract. The two symptoms above mentioned in these cases give warning that complete blindness and atrophy of the eyeball are imminent. The diminished tension has its cause in the diminution of volume of the shrinking vitreous; the deepening of the anterior chamber must also be referred to the same cause, the lens then sinking backward. These two symptoms, accordingly, are wanting in those cases of retinal detachment which arise from an active propulsion forward of the retina. This point is of particular importance in determining whether a detachment of the retina is of a simple serous nature or is caused by a neoplasm; in the first case, the tension is diminished, in the second it is elevated (Von Graefe).

The retina, when but recently separated, retains for some time its sensitiveness to light, and, if it soon becomes reattached, may resume its function perfectly. Thus there is a possibility afforded of a cure of the detachment in respect to function as well as in other regards. Not infrequently an apparent cure occurs in the course of a retinal detachment, owing to the fact that the detachment which has occupied the region of the macula lutea descends beneath it. As the macula now regains its function, the sight increases considerably, while the detachment still continues, although in another place.

In the beginning of a detachment of the retina, objects frequently appear crooked (metamorphopsia), in consequence of the oblique position of the percipient retinal elements. Photopsia, too, is often caused by the traction upon the retina, and often gives the first warning of the advent of the detachment.

Not infrequently a rent is found in the separated retina (*ruptura retinæ*). People were formerly disposed to look upon this as the result of the detachment, it being supposed that the delicate retina, being deprived of all support, was lacerated in the movements of the eye through agitation of the subretinal fluid. But, according to the investigations of Leber and Nordenson, it seems as though, on the contrary, the laceration of the retina preceded its separation. It results from the fact that the vitreous, as it shrinks, by pulling upon the retina, tears it; then fluid from the vitreous may pass through the rent, get beneath the retina, and at once detach it over quite a large area. In this way, moreover, the sudden development of most detachments would be accounted for.

IV. Glioma of the Retina.

100. Glioma is the only neoplasm which occurs in the retina. It is found only in children. In a case of it the patients notice that a bright, whitish, or golden-yellow reflex emanates from the pupil, which sometimes even is noticeable at a distance. For this reason the disease was called by Beer *amaurotic cat's-eye;* amaurotic, because the eye is

blind; and cat's-eye, because it shines like cats' eyes in the dark. If such an eye is examined by focal illumination, we recognize as the cause of the reflex a light-colored nodular mass (the degenerated retina) situated behind the lens and covered over with minute vessels.

The *subsequent course* of the glioma shows the same stages that we have learned to recognize in the case of chorioidal tumors (see page 324). In the first stage, inflammatory symptoms are absent; the disease manifests itself only in the bright-colored reflex and the blinding of the eye. The second stage is characterized by the supervention of increase of tension. The eye becomes irritated and painful, and the child begins to suffer. Afterward, in the third stage, the tumor grows out from the eye, first of all along the optic nerve, then in other places as well, particularly through the cornea or in its vicinity. The eye at length is transformed into a large, ulcerated, painful, and readily bleeding mass, which fills the whole orbit and projects out between the lids. In the fourth stage the tumor spreads to remote organs. Through transfer by continuity it passes along the optic nerve to the brain; and by way of metastasis it spreads to the neighboring lymphatic glands and also to the most various internal organs (most frequently to the liver). The children finally die either from exhaustion or from the spread of the neoplasm to vital organs, especially the brain. The course of the disease from its very outset to its fatal termination usually extends over several years.

Glioma, as a rule, attacks only one eye, although numerous bilateral cases have also been seen. It is found in children only, and mostly before the fifth year of life. Often it is observed at such an early age that its beginning must be regarded as taking place in fœtal life. This, as well as the fact that several children in the same family are one after another affected with glioma, would argue that the cause of it in many cases is to be looked for in a congenital failure of development.

Treatment consists in the promptest possible removal of the neoplasm. So long as the growth is still confined to the eyeball, it is sufficient to enucleate the latter, in doing which we take the precaution to divide the optic nerve as far back as possible. In such cases we may hope for a permanent cure. When the tumor has perforated the eyeball and is growing outside of it but is still confined to the orbit, complete removal of the neoplasm can still be attained through exenteration of the orbit (see § 167). But in this case rapid recurrences both in loco and in the neighboring lymphatic glands seldom fail to occur. Nevertheless, even in such cases the operation is indicated, because by the removal of the local focus of disease the child is spared much suffering.

From what has been said, the *prognosis* is favorable only when the operation is performed very early.

Glioma retinæ (Virchow) is composed of small cells and a soft basement substance. The cells consist of a large nucleus surrounded by a very scanty amount of protoplasm which in many spots possesses minute processes. The interstitial substance in which the cells are imbedded is half fluid, so that the whole tumor is of a very soft consistence. Glioma, in contradistinction to intra-ocular sarcomata, is never pigmented. It develops from the two granule-layers of the retina and mainly from the inner granule-layer. The overgrowth of the retina leads to its irregular thickening, and consequently to folding and detachment of it; but in many cases, as the annexed illustration (Fig. 83) shows, the detachment may for a long time remain confined to a small circumscribed spot. Neoplasm-germs pass from the degenerated retina both into the chorioid and into the vitreous, where they subsequently develop into small independent nodules (*k*, Fig. 83).

FIG. 83.—GLIOMA OF THE RETINA. MAGNIFIED 2 × 1.

The glioma has spread over the entire extent of the retina. The latter on its nasal side, *n*, has been completely consumed in the formation of the new growth, while on the temporal side, *t*, the external retinal layers are still in places preserved (at *a*). The pseudo-formation also covers the optic papilla, *N*, into the excavation of which it penetrates. In the anterior segment of the eyeball lie isolated nodules, the largest of which, *k*, is connected with the ora serrata. The anterior segment of the eyeball shows the effects of the increase of tension; that is, shows on the nasal side the application of the root of the iris to the sclero-corneal junction, while at the point corresponding to this on the temporal side the precursor of a staphyloma intercalare can be perceived under the form of an excavation, *b*.

That a congenital morbid disposition very often lies at the bottom of glioma is shown by the following interesting observation which I once made: A mother brought her four-year-old son into the clinic with a glioma of the right eye. According to her statement, this had only existed for a year, but it was already far advanced; the eyeball, as a whole, was very much enlarged, and the pseudo-growth was growing out from it into the orbit. The entire orbital contents were removed, but nevertheless the child died half a year afterward with brain symptoms, while at the same time a new tumor could be felt in the orbit. Some months afterward the mother brought the next child, a two-year-old boy, with the statement that he had been blind in the right eye since birth, although it was only recently that she had noticed an enlargement of the eye. This child likewise had a glioma of the right eye, and also died of a recurrence about a year after the operation had been performed. Soon afterward the woman brought me her last child, then only a few months old, full of fear lest this one, too, might be the victim of the same frightful disease, because she had noticed in its left eye an appearance varying from the usual. This child, however, did not have a glioma, but a typical, congenital coloboma of the iris downward as well as a coloboma of the chorioid.

The features of amaurotic cat's-eye may be produced not only by glioma, but also by exudates into the cavity of the vitreous. Such cases are often hard to distinguish from glioma, and are hence designated by the name of pseudo-glioma (see page 322).

INJURIES OF THE RETINA.—*Ruptures* of the retina occur in consequence of contusions of the eyeball, even without perforation of the remaining tunics of the eyeball; but these cases of isolated laceration of the retina are extremely rare. The retina is much harder to tear than the chorioid, since in ruptures of the latter the retina is generally found to be uninjured. Less infrequent are the spontaneous ruptures of the retina in detachment of the latter.

A transient alteration of the retina after contusion of the eyeball is the *commotio retinæ*, described by Berlin. This is characterized by a milk-white cloudiness of the retina, which occupies either the vicinity of the papilla or that part of the retina which corresponds to the point at which the effect of the blow was felt. In many cases also the spot diametrically opposite is found to be clouded. The clouding of the retina disappears after some days, and with it also disappears the disturbance of vision which it produced. Probably the condition in question is one of œdema of the retina.

CHAPTER XI.

DISEASES OF THE OPTIC NERVE.

Anatomy.

101. The optic nerve (nervus opticus) collects its fibers from the retina, and passes from the eye through the orbit and through the optic foramen into the cavity of the skull. Hence, three divisions are distinguished in the optic nerve: (*a*) The intra-ocular termination, which is found within the sclera, (*b*) the orbital portion from the eyeball to the optic foramen, and (*c*) the intra-cranial portion from the optic foramen to the chiasm.

(*a*) *Intra-ocular Division of the Optic Nerve.*—To get to the retina from outside, the optic nerve must pierce the chorioid and sclera. The spot where this takes place lies a little to the inner side of the posterior pole of the eye (Fig. 48). The opening in the sclera through which the optic nerve leaves the eye is called the foramen scleræ, and properly presents itself under the form of a short canal; the segment of the optic nerve lodged in this is its intra-scleral portion. Considered more precisely, a complete aperture for the optic nerve exists neither in the sclera nor in the chorioid, but the two membranes conduct themselves as follows: The external lamellæ of the sclera, which occupy about two thirds of its thickness (Fig. 84, *sa*), are not perforated by the optic nerve at all, but are reflected backward upon it to form its sheaths. The innermost lamellæ (*si*, Fig. 84) of the sclera, on the contrary, stretch over the foramen scleræ, and are perforated by numerous openings designed for the passage of the separate bundles of optic-nerve fibers. Consequently, the optic nerve in this spot is traversed by numerous septa of tough connective tissue. The chorioid, too (*ch*, Fig. 84), stretches in a modified form transversely through the optic nerve. Together with the inner layers of the sclera it forms the lamina cribrosa, which bridges over the foramen scleræ, and is so called because it is everywhere perforated by the bundles of fibers of the optic nerve.

If we look at the optic-nerve entrance in longitudinal section, we see that at its point of entrance into the sclera it is narrowed down in a conical shape (Fig. 84), so that the spot corresponding to the lamina cribrosa is the slenderest portion of the optic nerve. This narrowing

of the optic nerve appears still more marked when we consider that at the site of the lamina cribrosa the connective-tissue septa are particularly numerous and of large size. The space left for the nervous con-



FIG. 84.—HEAD OF THE OPTIC NERVE.

A, OPHTHALMOSCOPIC VIEW.—Somewhat to the inner side of the center of the papilla the central artery rises from below, and to the temporal side of it rises the central vein. At the temporal side of the latter lies the small physiological excavation with the gray stippling of the lamina cribrosa. The papilla is encircled by the light scleral ring (between *c* and *d*), and the dark chorioidal ring at *d*.

B, LONGITUDINAL SECTION THROUGH THE HEAD OF THE OPTIC NERVE. Magnified 14 × 1.—The trunk of the nerve up to the lamina cribrosa has a dark color because it consists of medullated nerve-fibers, *n*, which have been stained black by Weigert's method. The clear interspaces, *se*, separating them correspond to the septa composed of connective tissue. The nerve-trunk is enveloped by the sheath of pia mater, *p*, the arachnoid sheath, *ar*, and the sheath of dura mater, *du*. There is a free interspace remaining between the sheaths, consisting of the subdural space, *sd*, and the subarachnoid space, *sa*. Both spaces have a blind ending in the sclera at *e*. The sheath of dura mater passes into the external layers, *sa*, of the sclera, the sheath of pia mater into the internal layers, *si*, which latter extend as the lamina cribrosa transversely across the course of the optic nerve. The nerve is represented in front of the lamina as of light color, because here it consists of non-medullated and hence transparent nerve-fibers. The optic nerve spreads out upon the retina, *r*, in such a way that in its center there is produced a funnel-shaped depression, the vascular funnel, *b*, on whose inner wall the central artery, *a*, and the central vein, *v*, ascend. The chorioid, *ch*, shows a transverse section of its numerous blood-vessels, and toward the retina a dark line, the pigment epithelium; next the margin of the foramen for the optic nerve and corresponding to the situation of the chorioidal ring, the chorioid is more darkly pigmented. *ci* is a posterior short ciliary artery which reaches the chorioid through the sclera. Between the edge of the chorioid, *d*, and the margin of the head of the optic nerve, *c*, there is a narrow interspace in which the sclera lies exposed, and which corresponds to the scleral ring visible with the ophthalmoscope.

stituents of the optic nerve is hence very considerably reduced at this spot. How, then, is it possible that the bundle of nerve-fibers can go through this narrow passage? A glance at the longitudinal section of a fresh

optic nerve gives the explanation of this. Such a section shows the nerve to be white as far as the lamina cribrosa, while in front of it it is of a translucent gray. The white hue of the optic nerve in its extra-ocular portion depends upon the fact that the optic-nerve fibers here are medullated, and therefore opaque (in Fig. 84 they appear black, in consequence of being stained with hæmatoxylin, after Weigert's method). In their passage through the lamina cribrosa the nerve-fibers lose their myelin, and consequently become transparent; hence, the translucent, gray appearance of the head of the optic nerve. With the loss of the myelin the diameter of each individual nerve-fiber diminishes very considerably, so that their aggregate amount finds room in the narrow foramina of the lamina cribrosa.

The *lamina cribrosa* plays an important part in pathological processes. In the first place, it is the weakest spot of all the tunics of the eye, being here constituted only by the innermost layers of the sclera (together with a few lamellæ of the chorioid), which, moreover, are perforated by the foramina for the bundles of fibers of the optic nerve. Hence, in case of increase of tension, this spot is the first to give way. In the normal eye the lamina cribrosa runs straight, or with but a slight backward curvature, across through the optic nerve. With increase of tension, it recedes more and more, and thus forms the glaucomatous excavation. A second reason for the production of pathological changes lies in the fact that within the foramen scleræ and particularly within the limits of the lamina cribrosa, the optic nerve is tightly inclosed between firm, fibrous walls, a thing that occurs at no other spot in its course. Here, therefore, when swelling of the optic nerve takes place, constriction and strangulation of it may readily occur. The foramen scleræ, accordingly, in this case play a part like that which the fibrous ring of the hernial orifice does for the viscera lying in front of it.

That portion of the optic nerve situated in front of the lamina cribrosa in the interior of the eye itself is the *head of the optic nerve* (papilla nervi optici). It is the part of the optic nerve which even during life can be seen by means of the ophthalmoscope. The name papilla was selected by the older authors under the erroneous impression that the head of the optic nerve represented a projection into the interior of the eye. This, however, is only the case in pathological conditions—e. g., in inflammatory swelling of the papilla. In the normal state, the latter is perfectly flat, so as to lie in the same plane as the retina, or it actually has a central depression (*b*, Fig. 84). This latter arises from the fact that the fibers of the optic nerve begin to separate from each other, not at the level of the retina but below it, so that a funnel-shaped depression is produced from which emerge the central vessels of the optic nerve. This is the normal vascular funnel, which quite often expands into a pretty extensive depression, the physiological excavation.

(*b*) *Orbital Division of the Optic Nerve.*

The optic nerve on its way from the eye to the foramen opticum makes an S-shaped bend (*o*, Fig. 48). Owing to this, the eyeball can move freely within wide limits. The movements of the eye take place about a center of rotation which lies nearly in the center of the eyeball. Hence, when the cornea is turned toward one side, the posterior pole of the eye goes about as far to the opposite side. For all excursions of the cornea there are corresponding ones, as large in extent but in the opposite direction, of the posterior pole, for which reason the latter must be freely movable. If now the optic nerve were stretched in a straight line between the eyeball and the optic foramen, it would keep the posterior segment of the eyeball fast in its place, and hinder the movements of the whole eye. We see a confirmation of this in those cases in which the optic nerve is put on the stretch by protrusion of the eyeball from the orbit. The more pronounced the exophthalmus, the greater is the restriction of the motility of the eyeball. In the normal state, the optic nerve, on account of its S-shaped curvature, is longer than the distance between the eye and the optic foramen, so that it can undergo extension and thus follow the changes of place of the posterior pole of the eye.

The orbital portion of the optic nerve consists of the trunk of the nerve and the sheaths enveloping it.

(*a*) The *trunk* of the optic nerve is composed of nerve-fibers and connective tissue. The nerve-fibers vary greatly in caliber and are extremely numerous, their amount being estimated at about half a million. Lying between the fibers as a supporting substance is the neuroglia tissue. The nerve-fibers are combined into bundles (*b*, Fig. 85) which run parallel to one another, and anastomose together by a mutual interchange of fibers. Between the bundles lies the connective tissue which furnishes the supporting framework for the entire optic nerve. It forms thick or thin septa which are everywhere connected and traverse the entire optic nerve (*s*, Fig. 85). Between the outer surface of a nerve-bundle and the inner surface of the septa is found a space which acts as a lymph-cavity.

(*b*) The *sheaths* of the optic nerve are three—an internal, a middle, and an external one. As these originate from the three enveloping membranes of the brain, they are designated by the names of the pial, arachnoid, and dural sheaths (Axel Key and Retzius). The inner or pial sheath (*p*, Figs. 84 and 85) closely embraces the trunk of the optic nerve. From it the bands of connective tissue, which form the septa, pass into the interior of the nerve; and with them pass the blood-vessels. The external or dural sheath (*du*, Figs. 84 and 85) is much thicker than the internal sheath, and surrounds the nerve loosely. By reason of this, a pretty broad space—the intervaginal space—is left

between it and the internal sheath. The middle or arachnoid sheath (*ar*) was not discovered until recently. It had escaped observation before, because it is a very delicate pellicle which for the most part is intimately attached to the dural sheath. The middle sheath is united by manifold trabeculæ of connective tissue to the external and internal sheaths. It divides the intervaginal space into two portions, the subdural (*sd*) and sub-arachnoid (*sa*) space, which communicate with the cerebral spaces of the same names. These appear particularly prominent in Fig. 90, where they are pathologically dilated by an accumulation of fluid. The surfaces of the sheaths, turned toward these

FIG. 85.—CROSS-SECTION OF THE OPTIC NERVE, WITH ATROPHY OF THE PAPILLO-MACULAR BUNDLE (MADE 4 MM. BEHIND THE EYEBALL). MAGNIFIED 15 × 1.

The optic nerve is enveloped in the dural sheath, *du*, the arachnoid sheath, *ar*, and the pial sheath, *p*. Between the first and second is found the subdural space, *sd*; between the second and third, the arachnoid space, *sa*. On the outer and upper side of the center of the section is seen the central artery, *ca*; and more centrally is seen the central vein. These are surrounded by the cross-sections of the nerve-bundles, *b*, which are separated from each other by the septa, *s*, of connective tissue. At the temporal side, a wedge-shaped segment, *pm*, is distinguished from the rest of the cross-section of the nerve by its paler color. This corresponds to the atrophic papillo-macular bundle. Within the confines of it the cross-sections of the nerve-bundles are narrower and the septa of connective tissue are broader.

spaces, are provided with a coating of endothelium, so that these spaces are lined completely with endothelium, and must be regarded as lymph-spaces (Schwalbe).

Upon the eyeball the three sheaths become united to the sclera. The external and middle sheaths pass into the outer two thirds of the sclera (Fig. 84, *sa*); the inner sheath goes to the innermost lamellæ of the sclera (Fig. 84, *si*), which form the lamina cribrosa, and it is also connected with the chorioid. The intervaginal space has a blind ending situated within the sclera (Fig. 84, *e*). Posteriorly the three sheaths are continuous with the corresponding membranes of the brain.

The *blood-vessels* pass from the pial sheath into the optic nerve. In addition, in the anterior portion of the orbital division there are found the central vessels of the optic nerve. The central artery is a branch of the ophthalmic artery; the central vein empties into the superior ophthalmic vein or directly into the cavernous sinus. Both vessels enter the optic nerve at a distance of ten to twenty millimetres behind the eyeball (Fig. 84, *e*) and run in the axis of the nerve as far as the papilla, where they divide into the retinal vessels.

(*c*) *Intracranial Section of the Optic Nerve.*

The optic nerve leaves the orbit through the optic foramen. The latter really forms a short bony canal (canalis opticus), which contains besides the optic nerve only the ophthalmic artery (lying on the inner side of the optic nerve). Owing to the fact that the optic nerve within the canalis opticus is tightly inclosed by the bony walls of the latter, this section, just like the intra-scleral portion of the optic nerve, possesses a particular predisposition for morbid affections. Such affections consist in inflammation, in compression of the nerve through thickening of the bone, and in its contusion and laceration in case of fracture of the bony wall of the canal.

The intracranial portion of the optic nerve extends from the optic foramen to the chiasm; is therefore short (scarcely one centimetre). It is flattened and is enveloped only by the pial sheath, since the other two sheaths after passing through the optic foramen become united with the two outer membranes of the brain.

Continuation of the Fibers of the Optic Nerve to the Cerebral Cortex.

The two optic nerves join together in the chiasm, where they form an intimate anastomosis, and then on the posterior side of the chiasm make their appearance again as the optic tracts. The chiasm lies in the optic groove of the body of the sphenoid bone, directly in front of the infundibulum. Starting from the chiasm the optic tracts pass backward, diverging as they go, and, winding about the crus cerebri, arrive on either side at the external and internal geniculate bodies (into which last, however, they do not penetrate). From this point the optic fibers pass to the most various parts of the brain. Two bundles of fibers are of particular importance—the fibers (Fig. 86, *m*) which go to the nuclei of the oculomotorius, *K*, and the fibers, *S*, which pass to the cerebral cortex, *B*. The former regulate the movements of the ocular muscles and the reflex action of the pupils; the latter render possible the perception of the object seen. The fibers of the optic tract which are destined for the cerebral cortex pass through the optic thalamus and through the posterior portion of the internal capsule (Gratiolet's optic radiation) to the cortex of the occipital lobe, and mainly to that division of it which is known as the cuneus.

They here terminate in the ganglion-cells of the cortex, within a district which is known as the optical area of the cortex, or the visual sphere (Munk). Within the ganglion-cells the excitation set up in the optic-nerve fibers is transformed into sensation (sensory perception), so that it is here that the object seen comes within the domain of consciousness. In the ganglion-cells which have once been subjected to excitation permanent changes remain (memories), which become so intense, particularly upon a pretty frequent repetition of the same excitation, that by means of them we are able to reproduce in our consciousness an object formerly seen (optical memory-pictures). Upon destruction of the cerebral cortex, excitations of the optic-nerve fibers either fail altogether to become objects of consciousness or on account of demolition of the optic memory-pictures they no longer evoke the recollection of anything already known. Objects are seen, to be sure, but are not recognized. These cases are known as cortical or psychical blindness.

We have still to study more exactly the course of the fibers of the optic nerve in the *chiasm* itself. It is not a complete but only a partial decussation (*semi-decussation*) of the fibers that takes place here. In order to understand the arrangement of the fibers it is best to start from the eyeball in making our examination. Let us suppose a sagittal plane (*V*, Fig. 86), passing through the fovea centralis (*f*), to be drawn through the retina (*R*) of the right eye. The fovea divides the retina into two halves, a right or temporal half (*r*) and a left or nasal half (*l*). The fibers (indicated by dotted lines in the figure) which spring from the right half pass backward into the optic nerve (*O*), and go, keeping all the while upon the right side, to the right optic tract (*T*). The sum of these fibers is hence known as the non-decussating bundle. But the fibers which proceed from the left half (*l*) of the retina of the right eye pass over to the left side in the chiasm, so as to be found in the left optic tract (T_1). They form the decussating bundle. The like is true of the fibers belonging to the left eye. They all lie together in the left optic nerve (O_1), and become separated in the chiasm; the fibers coming from the left half of the retina pass into the left optic tract, those from the right half of the retina into the right optic tract. Each optic tract therefore contains fibers from both eyes. The right optic tract consists of the non-decussating fibers from the right half of the retina of the right eye and the decussating fibers from the right half of the retina of the left eye. Accordingly, the right halves of both retinæ (r and r_1), and so the left halves of both visual fields (G_1), belong to the right tract. Hence, the perception of all objects situated to the left of the median line is conveyed along the right optic tract to the cortex of the right hemisphere; the latter is thus designed for the apprehension of the left half of the external world. The converse is true of the left hemisphere. Thus the nerve subserving the sense of sight is in harmony with other nerves, all of which terminate in the hemisphere of

the opposite side. This is the case both with centripetal and centrifugal nerves. What we touch with our left hand becomes an object of



FIG. 86.—SCHEMATIC REPRESENTATION OF THE OPTIC TRACTS.

The field of vision common to the two eyes is composed of a right half, G, and a left half, G_1. The former corresponds to the left half, l and l_1, of the two retinæ, the latter to the right half, r and r_1. The boundary between the two halves of the retina is formed by the vertical meridian. This passes through the fovea centralis, f, in which the visual lines drawn from the fixed point, F, impinge upon the retina. The optic nerve-fibers arising from the right half, r and r_1, of the two retinæ (indicated by the dotted line) all pass into the right optic tract, T, while the fibers belonging to the left half, l and l_1, of the two retinæ pass into the left optic tract, T_1. The fibers of each optic tract for the most part pass to the cortex of the occipital lobe, B, forming Gratiolet's optic radiation, S; the smaller portion of them, m, goes to the oculo-motor nucleus, K. This consists of a series of partial nuclei, the most anterior of which sends fibers, P, to the pupil (sphincter iridis); the next one sends fibers, A, to the muscle of accommodation; and the third sends fibers, C, to the converging muscle (internal rectus, i). All three bundles of fibers run to the eye in the trunk of the oculo-motor nerve, Oc. Division of the optic tract at $g\ g$ or at $e\ e$ produces right hemiopia; and in the former case there would be no reaction to light on illuminating the left half of either retina. Division of the chiasm at $s\ s$ produces temporal hemiopia. Division of the fibers, m, abolishes the reaction of the pupil to light, but leaves the sight and also the associated contraction of the pupil in accommodation and convergence unaffected.

consciousness through excitation of the cortex of the right side of the cerebrum, and destruction of a certain portion of the latter entails a loss of the voluntary movements of the left arm. The sense of sight appears to form an exception to this rule, since each eye is connected with both hemispheres. This exception ceases to exist if we distribute the visual sensations in accordance with the halves of the field of vision to which they correspond. *Everything which the observer sees on the left side of him becomes an object of consciousness through excitation of the cortex of the right occipital region, and vice versa.*

The fact of semi-decussation affords the explanation of an important variety of visual disturbance, *hemiopia.** Let us suppose that the continuity of the left optic tract (Fig. 86, T_1) is interrupted at any spot—e. g., at g, g. In this case the left halves of both retinæ (l and l_1) would be cut off from their connection with the cortex of the left hemisphere. The right half, G, of the fields of vision of the two eyes would be wanting, so that only the left halves of all fixed objects would be seen. In like manner, the left halves of both visual fields would be lost upon destruction of the right optic tract. Hemianopia thus originating is called *homonymous* or lateral (Fig. 87). The same thing, of course, would also happen if the destruction did not affect the optic tract itself, but a spot placed higher up (e. g., e, e)—in fact, even the cerebral cortex



FIG. 87.—HOMONYMOUS HEMIOPIA. (AFTER SCHWEIGGER.)
The areas which have been left white correspond to the left halves of the visual fields, *R* and *L*, of the right and left eye, which are still intact: *t*, temporal; *n*, nasal side.

itself. Homonymous hemiopia, therefore, is always indicative of a lesion which lies to the central side of the chiasm and upon the same side as the blind half of the retinæ.

If the chiasm is divided by a sagittal section (s, s, Fig. 86) into a right and left half, all the decussating fibers are severed, while the non-decussating bundles remain intact. Since the decussating bundles supply the inner halves l and r_1) of the two retinæ, these portions of

* From ἡμισυς, half, and ὄψ, vision. By many authors the terms hemianopia or hemianopsia, formed by the interposition of an ἀ privative, are employed.

the retina would be thrown out of use, and thus the outer (temporal) half of the two visual fields would be suppressed. This form of visual disturbance is therefore called *temporal* hemiopia (Fig. 88). The same



FIG. 88.—TEMPORAL HEMIOPIA. (AFTER SCHWEIGGER.)
The areas left white correspond to the nasal halves of the visual fields, *R* and *L*, of the right and left eye, which are still intact: *t*, temporal; *n*, nasal side.

thing might also be caused by a lesion (e. g., a tumor) existing in the anterior or posterior angle of the chiasm, where decussating fibers alone are situated.

The hypothesis of a *semi-decussation* of the optic nerves was made by as remote an observer as Newton, who was led to it by the observation of certain cases of hemiopia. In fact, hemiopia can not be adequately explained in any other way than upon the assumption of a semi-decussation. This assumption, therefore, passed for a well-established fact until it was attacked upon the basis of anatomical investigations (by Biesiadecki, Mandelstamm, and above all by Michel). In man the fibers of the optic nerve, which in some parts are very minute, are so intimately interlaced that it is not possible to follow them with certainty on their way through the chiasm. Accordingly, observers turned for information to comparative anatomy, which presents us in animals with much simpler conditions. The simplest case occurs in fishes, in which the two optic nerves either merely cross over each other (in the bony fishes) or in which one optic nerve passes through a slit in the other (in the herring). In the amphibia and birds the conditions are more complicated, but are still always easy to make out. In them each optic nerve divides into a number of flat bundles, which all pass over to the other side, interlacing with the bundles of the opposite side as they cross, in the same fashion as the intertwined fingers of two hands when clasped together. There is no doubt, therefore, that in the lower vertebrates a complete decussation of the optic nerves exists; the only mistake that has been made is in concluding from this fact that we are justified in assuming the same condition to hold good for the higher vertebrates also.

Gudden has the credit of having definitely demonstrated by his experiments the true state of the case in the higher vertebrates. He employed for this purpose the method of an artificially induced atrophy. When a portion of the body is removed, the nerve-fibers which run to it become atrophied (ascending atrophy). This atrophy rises higher and higher toward the brain, the younger the person is and the longer the time that has elapsed since the removal of the

portion of the body in question. So also atrophy of the trunk of a nerve down to its termination sets in when the nerve is cut off from its connection with its central organ by the division of its root (descending atrophy). Methods based upon both of these principles were applied by Gudden to the organ of vision, inasmuch as he performed either enucleation of one eye or division of one optic tract, and studied the course of the consequent atrophy. If the right eye is enucleated in a new-born puppy, and some time afterward the animal is killed and examined, the right optic nerve is found to be completely atrophied; it consists of a thin strand of connective tissue without a trace of nerve-fibers. If complete decussation of the optic nerves took place in the chiasm, this complete atrophy would necessarily be continued into the optic tract lying on the opposite or left side, while the optic tract of the right side would be perfectly intact. This, however, is not the case; in the left optic tract there is still a slender bundle of nerve-fibers which has escaped atrophy. This can only originate from the left optic nerve, and must, accordingly, be a non-decussating bundle. So also in the apparently normal right optic tract there is found a thin bundle of atrophic fibers which must spring from the right optic nerve, and which corresponds to the non-decussating bundle of the right side. Hence, in the dog a semi-decussation does exist, although the decussating is much more pronounced than the non-decussating bundle. In rabbits this disproportion is still more marked. In them the non-decussating bundle is so attenuated that at first it escaped Gudden's notice altogether. On the other hand, in man the non-decussating bundle approximates the decussating one in size, the former containing about two fifths, the latter three fifths of all the optic-nerve fibers. In default of experiments, accident rendered the determination of this relation possible in man. Opportunities were had of holding autopsies on men of advanced age who had lost one eye in childhood. In such subjects it was found that the complete atrophy of the single optic nerve was distributed between the two optic tracts in such a way that the tract of the opposite side was always somewhat more atrophied than that of the same side. Hence the following statement may be made of the facts of the case: *In the lower vertebrates complete decussation of the optic nerves takes place; in many of the higher vertebrates a partial decussation exists, the partial character of which is the more pronounced the nearer akin the animal is to man.*

We comprehend the reason of the foregoing fact if we start from the law that the optical perception of all objects which are situated on the right side of the body is effected by means of the left cerebral hemisphere, and vice versa. In the lower vertebrates, and in fact even in most birds and mammalia, the eyes are placed so much on one side of the head that the animal is unable to see any point whatever with both eyes at once. The fields of vision of the two eyes are perfectly distinct. The right eye sees nothing but those objects which are situated on the animal's right side; accordingly, the fibers of the optic nerve originating from this eye must all pass to the left hemisphere, for which reason complete decussation of the optic nerves takes place. In the higher vertebrates —e. g., in the dog—we begin to find the eyes placed farther forward. Objects straight in front of them situated in and close to the median line can therefore be seen by both eyes at once, so that in this locality the fields of vision of the two eyes partially overlap, and there exists a small common (binocular) field of vision. The right eye, to be sure, is mainly designed for the vision of objects situated on the right side of the body, but it also, by means of the extreme

temporal portion of its retina, presides over a small area to the left of the median line. The optic-nerve fibers springing from this portion of the retina must go to the cortex of the right cerebral hemisphere, because they transmit the impressions of objects lying upon the left side of the body. These fibers constitute the non-decussating bundle; and this latter is small, because the area of retina corresponding to it is of but slight extent.

Lastly, in man both eyes lie in the frontal plane, so that almost all objects are seen with both at the same time. Accordingly, the visual fields of the two eyes are to a large extent coincident, so that there is formed a large binocular field of vision (the area left white in Fig. 89). Each eye sees objects both upon the right and upon the left side of the body, for which reason one part of the fibers of the optic nerve belonging to it go to the right, another part to the left hemisphere. To be sure, the visual field of each eye extends farther to the temporal than to the nasal side (see page 23 and Fig. 14). Hence, it follows that the nasal half of the retina is larger than the temporal, and as the fibers which spring from the former pass over in the chiasm to the opposite side, the

FIG. 89.—BINOCULAR FIELD OF VISION. (AFTER MÖSER.)

The undotted line, *L*, bounds the visual field of the left eye, the dotted line, *R*, the visual field of the right. The median portion of the two visual fields overlap to an extent shown by the surface left white. This is, accordingly, the binocular field of vision, all objects in which are seen by both eyes at the same time. In its center lies the point of fixation, *f*, and at either side of the lattter the blind spots, *r* and *l*, of the right and left eye. Adjoining either side of the binocular field of vision are the temporal divisions of the two visual fields (the shaded areas in the figure), objects in which are seen with one eye alone.

number of decussating fibers in the optic nerve is necessarily somewhat larger even in man than the number of those which do not decussate. The way in which the optic nerves decussate, therefore, depends upon the relation of the fields of vision of the two eyes. If the two fields are completely separated, total decussation exists. If there is a binocular field of vision, semi-decussation takes place, and this is the more pronounced the larger the binocular field of vision.

Hemiopia in the more extended sense of the term exists not only when an entire half of each visual field is wanting, but also when there is a deficiency which, though smaller, occupies a symmetrical position in the visual fields of the two eyes (incomplete hemiopia, Wilbrand). In this case, too, there is a lesion of the fibers of the optic nerve above the chiasm, only now simply a portion instead of all the fibers of one tract (or of its continuation to the cortex) is destroyed. It very often happens in typical hemiopia that the field of vision is not divided exactly in half, the vertical border of the field bending out a little at the site of the point of fixation (Fig. 87), so that the portion of the field of vision corresponding to the macula lutea is preserved intact. We must conclude from this that the macula lutea—in contradistinction to the rest of the

retina—is supplied throughout its whole extent by fibers arising from both hemispheres. The favorable character of this arrangement is in accordance with the functional importance of this region of the retina. We shall see later on that the number of fibers which are destined for the macula lutea is also extremely large.

How are the nerve-fibers coming from the different parts of the retina situated within the trunk of the optic nerve from the eye to the chiasm? Our knowledge in regard to this problem dates from very recent times, and has been worked out from the examination of pathological cases—e. g., in a case of optic-nerve disease a deficiency in the visual field is made out during life; upon autopsy a lesion is found in a certain portion of the trunk of the nerve. We are then justified in assuming that the bundle of nerve-fibers which give evidence of lesion appertain to that region of the retina which corresponds to the defect in the field of vision.

The *fibers of the optic nerve* upon entering the interior of the eye spread out like a sheaf to form the most internal (most anterior) layer of the retina. The fibers which are situated along the margin of the papilla terminate in the vicinity of the latter. The nearer the fibers lie to the axis of the optic nerve the greater is the distance that they have to traverse in the retina in order to reach the level of the next layer of the retina—the ganglion-cell layer—with which they are continuous. Accordingly, the following may be enunciated as representing the state of the case: Those fibers which come from the peripheral portions of the retina lie in the center of the optic nerve, while those which rise from the central regions of the retina lie along the margin of the nerve. It is deserving of mention that the bundles of nerve-fibers situated nearest the margin of the nerve—i. e., directly beneath the pial sheath—regularly undergo atrophy in advanced life. The same is true of the bundles of nerve-fibers adjoining the central vessels. Those fibers which supply the retina from the macula lutea to the papilla (the so-called *papillo-macular region*) take on a special form of arrangement. In that division of the optic nerve which adjoins the eyeball, they are aggregated in the form of a sector whose apex is directed toward the center of the nerve, while its base corresponds to the outer margin of the latter (the paler-looking bundle, *pm*, in Fig. 85). Farther back the arrangement changes, so that these fibers get to lie in the axis of the nerve (Samelsohn, whose statements were subsequently confirmed by others, such as Nettleship, Vossius, Bunge, and Uthoff). The sector occupied by the papillo-macular bundle amounts to about one third of the entire cross-section of the optic nerve. This is very large, when we consider that the corresponding region of the retina constitutes but a small fraction of the entire retinal surface. This relation, in fact, is in harmony with the predominant importance of this region of the retina. It gives support to the assumption that each one of the terminal elements in the macula lutea is connected with the brain by a nerve-fiber of its own, so that excitations of this element are conveyed to the brain, isolated from others, while in the peripheral portions of the retina probably a number of terminal elements are continuous with one common fiber.

Our knowledge in regard to the course of the optic fibers can be applied practically, inasmuch as it enables us to determine precisely the *situation of a lesion* in the optic tract. In this instance we are dealing with cases in which a defect exists in the visual field without the ophthalmoscope showing any disease of the deep tunics of the eye, so that the defect must be referred to some break

in the conduction. In all cases in which the defect in the visual field is contained in one eye only or in which, while there are defects in both eyes, they are not symmetrically situated, the lesion must be seated in the optic nerve itself—that is, in front of the chiasm—since all interruptions on the farther side of the chiasm result in the production of symmetrical defects in the visual fields. For the same reason complete blindness of one eye, the other one being intact, must be referred to an affection in front of the chiasm. Central scotomata correspond to an affection of the papillo-macular bundle. In temporal hemiopia the lesion is seated in the chiasm itself. Homonymous hemiopia, or less extensive but still symmetrical defects in the field of vision, depend upon a disturbance above the chiasm. If, in addition, there is loss of the reflex movement of the pupil when light is thrown upon the blinded portion of the retina (Wernicke's hemiopic pupillary reaction), the break in the conduction must lie below the spot at which the fibers to the oculo-motor nucleus are given off—i. e., they must lie in the optic tract itself; but, if the pupillary light-reflex is intact, the lesion is to be located higher up—e. g., in the optic thalamus, in the internal capsule, or even in the cortex of the brain itself. Finally, a cortical lesion must be assumed to exist for those rare cases in which there is hemiopia only for the color-sense or for the light-sense, while the field of vision for the space-sense (that is, of the visual field taken by the ordinary method of examination) is normal; for the channels of these three varieties of perception have in all respects a common course, and only in the cortex of the brain become separate, so as to terminate in distinct centers.

I. Inflammation of the Optic Nerve.

102. Inflammation of the optic nerve (neuritis optica) may make its appearance at any spot whatever of the nerve. Of course, it is directly visible in the living eye only when the optic papilla, which is accessible to ophthalmoscopic examination, is involved. Such cases we designate as neuritis intra-ocularis or, on account of the changes in the papilla, as papillitis (Leber). From them are to be distinguished those cases in which the inflammation is located in a portion of the optic nerve which is situated farther back (neuritis retrobulbaris). Since in this case the focus of inflammation can not be seen, its existence must be inferred from the other symptoms.

(*a*) *Neuritis Intra-ocularis.*

Symptoms and Course.—Neuritis of the papilla of the optic nerve manifests itself externally by no signs except that the pupils are dilated, to correspond with the diminution or absolute abrogation of the sight. Ophthalmic examination shows in the papilla the following evidences of inflammation (Fig. 90, *A*). The color of the papilla is altered, being either white, gray, or reddish, and it is often mottled with white spots or with extravasations of blood (*h*). The boundary-lines of the papilla become indistinguishable, the exudation extending beyond them into the adjoining retina; hence, too, the papilla appears of greater diameter than normal. The blood-vessels of the retina are altered, the arter-

ies (a, a) being thinner, while the veins (v, v) are distended, in consequence of the compression of the vessels by the swollen optic nerve. The veins of the retina become exceedingly tortuous, especially at the



FIG. 90.—OPTIC NEURITIS (CHOKED DISK).*

A, OPHTHALMOSCOPIC VIEW OF THE PAPILLA. Magnified 14 × 1.—The papilla appears considerably enlarged and without distinct outline. It is of a grayish-white color, clouded, and covered with radiating striæ which extend into the adjoining retina. The retinal arteries, a, a, are contracted, the retinal veins, v, v, are exceedingly dilated and tortuous, and both are hazy in places. Adjoining the papilla, radially disposed, striate, red spots (hæmorrhages), h, are found in the retina.

B, LONGITUDINAL SECTION THROUGH THE HEAD OF THE OPTIC NERVE.—This is greatly swollen, so as to project above the level of the adjacent retina and form at the base an annular tumefaction, the neuritic swelling, n. There is a cellular infiltration, particularly along the minuter blood-vessels, e, for which reason the latter stand out with a special prominence. The retina, r, is thrown into folds about the circumference of the papilla, in consequence of the swelling of the latter; the chorioid, ch, and the sclera, s, are normal, as is the optic nerve posterior to the lamina cribrosa. Here there simply exists a dilatation of the intervaginal space, i, through accumulation of fluid, in virtue of which the greatly folded arachnoid sheath, ar, is especially well marked; du, dural sheath; p, pial sheath.

* Compare with this the normal optic nerve in Fig. 84, page 421.

spot where they pass down upon the retina over the edge of the swollen papilla; and wherever their coils dip pretty deeply into the clouded tissues they look hazy, or seem to suffer an actual interruption in their course. The most important symptom is the swelling of the papilla, manifested by its prominence above the surrounding retina.

The subjective symptoms consist in a disturbance of vision. This in most cases is very considerable; when the neuritis is severe, complete blindness is usually present. Nevertheless, cases of marked swelling associated with normal sight do also occur (in choked disk). Contraction of the field of vision is frequently found, sometimes under the form of hemiopia.

Neuritis runs a chronic course. It takes months for the inflammatory phenomena to disappear, and then they are replaced by the symptoms of atrophy. The papilla grows paler, its outlines become once more clearly visible, and the vessels upon the papilla and in the retina are narrowed. This so-called neuritic atrophy is the more pronounced in proportion as the preceding neuritis was the more intense. Whether the vision grows better again after the inflammation has run its course, or remains permanently enfeebled, or is annihilated, depends upon the degree of the atrophy. In any case, the prognosis of neuritis is serious.

Etiology.—Like the rest of the intra-ocular affections, neuritis is but rarely a local lesion; on the contrary, it usually originates in some deep-seated affection, and for this reason is almost always bilateral in its development. The diagnosis of neuritis is therefore of importance, not only for the oculist, but also for every physician engaged in the treatment of internal disorders, as it affords him aid that is indispensable for the diagnosis of many diseases.

The causes of neuritis are:

1. *Brain Diseases.*—These are by far the most frequent cause of optic neuritis. The brain lesion leads to disease of the optic nerve, either through producing engorgement or through transfer of the inflammation. (*a*) *Engorgement* is chiefly of moment in those diseases of the brain which lead to an elevation of the pressure within the cranial cavity—i. e., most frequently in tumors of the brain and in hydrocephalus. A brain tumor, as a result of its growth, arrogates constantly more and more space to itself within the cranial cavity. Hence, as the skull is unyielding, an increase in the intra-cranial pressure arises, by virtue of which a portion of the cerebro-spinal fluid is squeezed out of the cranial cavity. This fluid finds an egress partly in the direction of the spinal cord, partly in that of the optic nerve. The spaces between the sheaths of the optic nerve which communicate with the lymph-spaces between the membranes of the brain are dilated by an accumulation of fluid (hydrops vaginæ nervi optici, Fig. 90, *i*; Stellwag). Upon this fact is based the following theory of Schmidt and Manz in regard to the origin of neuritis. In consequence of accumulation of

fluid in the intervaginal space, a stasis of lymph occurs in the trunk of the optic nerve itself, particularly in the region of the lamina cribrosa, the lymph-spaces of which communicate with the intervaginal space. The œdema of the lamina cribrosa causes a compression of the central vessels—a compression which makes its influence felt sooner and to a higher degree in the central vein of the optic nerve than in the central artery. As there is constantly pouring into the papilla through the artery a quantity of blood which can not be completely carried away again by the contracted central vein, venous engorgement of the optic nerve and consequently swelling of the latter are developed. This swelling of the nerve leads to its incarceration at the spot where it fits so tightly in the foramen scleræ, and consequently extreme œdema develops in the strangulated papilla. Neuritis having this origin is hence not to be regarded so much in the light or an inflammation proper as of an inflammatory œdema, and is accordingly designated by the name of engorgement neuritis, or *choked disk*. It accordingly constitutes a very important symptom of increase of the cerebral pressure. (*b*) *Direct transmission* of inflammation from the brain to the optic nerve must be assumed to exist chiefly in those cases in which an inflammation exists in the brain itself, and particularly at its base, as is, for example, generally the case in tuberculous meningitis. Here the inflammation is transmitted along the optic nerve and its sheaths to the papilla (*neuritis descendens*).

2. *Syphilis* is a frequent cause of neuritis. The optic nerve may be attacked by the syphilitic affection directly. In other cases it becomes affected indirectly, owing to the development in the cranial cavity or in the orbit of inflammations or of tumors resulting from syphilis, which compress the optic nerve or in some other way cause its implication.

3. Acute infectious febrile diseases, such as typhus fever, measles, scarlet fever, small-pox, diphtheria, pneumonia, and intermittent fever.

4. Disturbances of nutrition of various kinds—for instance, those resulting from albuminuria, diabetes, scrofula, disorders of menstruation, pregnancy, and the puerperal state.

5. Acute anæmia after great loss of blood, the most frequent variety being that due to hæmorrhage from the stomach and to metrorrhagia. In these cases blindness usually does not set in until some days after the hæmorrhage, and is generally incurable.

6. Lead-poisoning.

7. Heredity. There are families the members of which are attacked by neuritis without there being any special cause for it. Such a neuritis usually affects only the male members of the family, and these are generally attacked by it at the same age (as a rule at about the twentieth year).

8. Marked chilling of the body.

9. Affections of the orbit such as inflammations or new growths in the orbit or tumors developing upon the optic nerve itself. These are the only cases in which neuritis can with certainty be regarded as a purely local disease.

The *treatment* of neuritis must be directed first of all against the lesion which forms the basis of it. Local treatment, in addition to a suitable regimen of the eyes, consists in the abstraction of blood at the mastoid process, in diaphoretic measures, and in the administration of absorbent remedies, such as iodide of potassium, mercury, etc.

Simple *hyperæmia* of the optic nerve is a frequent occurrence. It is not only a constant accompaniment of all inflammations of the retina and chorioid, but is found in connection with violent inflammations in the anterior division of the eye—e. g., in irido-cyclitis. If an inflammation of the retina is associated with pretty marked involvement of the optic nerve, or if, on the other hand, an inflammation of the optic papilla has extended so as to occupy quite a large area of the retina, the picture of *neuro-retinitis* is produced. Almost all forms of retinitis as well as of neuritis which have been described in the foregoing pages may appear under the form of neuro-retinitis. In connection with tumors of the brain, a special form of neuro-retinitis occurs, the peculiarity of which consists in the fact that together with the phenomena in the optic papilla minute splashes of silvery luster are visible in the region of the macula lutea, so that a picture resembling that of retinitis albuminurica is produced.

Von Graefe was the first to distinguish the inflammations of the optic nerve accompanying diseases of the brain into the neuritis of engorgement and descending neuritis. The marks distinguishing the two in the ophthalmoscopic picture are as follows: In the choked disk of engorgement neuritis the swelling is very considerable, but suddenly ceases at the edge of the disk, since the changes are confined to the latter. The engorgement furthermore manifests itself in the frequently enormous distention of the retinal veins. In neuritis descendens the swelling is slight and so is the distention of the veins, and the exudation, made patent by the cloudiness and discoloration of the disk, comes more into prominence. The exudation, moreover, extends beyond the edge of the disk into the adjacent retina, so that the disk appears enlarged; frequently the picture of neuro-retinitis is produced. Nevertheless, the two forms of neuritis are not so widely separated as the theory demands, since numerous transition forms occur between choked disk and descending neuritis. For this reason, and also on the basis of anatomical investigations, the purely mechanical explanation of choked disk, such as the theory of Schmidt-Manz affords, has been repeatedly questioned, and other hypotheses have been propounded to account for its development. In reality, the fact appears to be that a process of engorgement does actually play an important part in the production of congestive neuritis, but that inflammatory processes in the trunk and in the sheaths of the optic nerve likewise participate in its production.

The diseases of the brain which are complicated with optic neuritis are partly focal, partly diffuse affections. Among the former, it is mainly the *tumors of the brain* which result in neuritis, usually under the form of choked disk. Neuritis in this case is so frequent—it is said to be wanting in only 10 per cent, according to others in 20 to 30 per cent of cerebral tumors—that it forms one of their most important symptoms. This symptom is the more

deserving of consideration inasmuch as a cerebral tumor may often run its course for a long time without producing any other positive symptoms—e. g., it may simply cause headache, or even this may be wanting. *Accordingly, in every case in which there is a suspicion of the existence of a cerebral affection, the fundus of the eye should be examined with the ophthalmoscope.* This is the more necessary, since choked disk sometimes fails to manifest itself by any disturbance of the vision. This is explained by assuming that in choked disk —in the beginning at least—there is simply a state of œdema. The disturbance of vision is accordingly produced by compression of the nerve-fibers due to the œdematous swelling. The degree of this compression, however, can not by any means be determined from the ophthalmoscopic appearance, so that normal sight may be present along with a neuritis which with the ophthalmoscope appears, very pronounced. In many of these cases the blindness does not come on till later, sometimes not till the advent of neuritic atrophy.

Neither the size nor the situation of the new growth is of importance in determining the development of a choked disk. Choked disk has been seen with tumors which scarcely reached the size of a walnut; at other times neuritis is absent, although the tumors are very large. Similarly, neuritis is found both with tumors which lie in the neighborhood of the optic tracts and with those which are far removed from them—e. g., in the cerebellum. Moreover, with tumors of the brain there may occur not only engorgement neuritis, but also descending neuritis and primary atrophy of the optic nerve. Descending neuritis takes place when the tumor excites, in its immediate neighborhood, an inflammation which is transmitted to the optic nerve. Primary atrophy may be produced by the fact that the tumor exerts a direct pressure upon the chiasm or the optic tracts, and thus causes their effacement; or an accumulation of fluid may take place in the third ventricle in consequence of the tumor, so that the greatly distended anterior inferior extremity of the ventricle presses upon the chiasm. In this way amaurosis develops with cerebral tumors, either without any ophthalmoscopic evidence at all or under the guise of a primary atrophy.

Among the focal affections of the brain which may, although but rarely, cause neuritis must be enumerated foci of softening, abscesses, thrombosis of the sinuses, aneurisms, apoplexies, and cysts (among these cysticercus and echinococcus cysts). Among the diffuse affections, disseminated sclerosis, acute and chronic meningitis, and hydrocephalus give rise to neuritis. The two affections last named, together with tubercles of the brain, are the most frequent cause of neuritis in children. Frequently such children are not brought to the oculist until later in life, when he finds a neuritic atrophy as the cause of the blindness, and can determine from the history of the case that a severe cerebral affection has preceded it. This form of blindness is incurable. Not to be confounded with it are those rare cases in which children become blind without known cause and without any ophthalmoscopic change in the fundus. This variety of blindness, the cause of which is at present unknown, sometimes gets well (Nettleship). Some cases of neuritis due to hydrocephalus are known in which a continual dropping of fluid (cerebro-spinal fluid) takes place from the nose. Neuritis also occurs sometimes in malformations of the skull (particularly the kind known as peaked skull—"Thurmschädel") and injuries of the skull (especially fractures of the base, with consequent meningitis).

Neuritis has also been observed as a rare complication in spinal diseases, particularly in acute myelitis.

(*b*) *Retro-bulbar Neuritis.*

103. Retro-bulbar neuritis is located in the orbital division of the optic nerve. Hence, upon ophthalmoscopic examination, we find in the papilla either no changes at all or changes that are insignificant and not characteristic; but later, after the disease has subsided, the signs of atrophy frequently make their appearance in this spot. This is the case when destruction of the fibers of the optic nerve has taken place within the region occupied by the focus of inflammation. The peripheral portions of the divided fibers then undergo an atrophy, which is slowly transmitted to the papilla, where it becomes visible with the ophthalmoscope (descending atrophy). Owing to the absence of distinct ophthalmoscopic changes in the recent cases, retro-bulbar neuritis must be diagnosticated from the other symptoms, and mainly, in fact, from the way in which the vision is affected. In a few cases the disturbance of vision may increase to the point of complete blindness, but in most cases is confined to the central portions of the visual field which are supplied by the papillo-macular bundle. There is, therefore, a central scotoma in the field of vision.

Retro-bulbar neuritis is either acute or chronic in its development. The chronic cases usually depend upon chronic poisoning, particularly that produced by tobacco (tobacco amblyopia). In general, retro-bulbar neuritis affords a good prognosis, since in cases which are not too far advanced the sight can be brought back again to the normal.

The *acute* form of retro-bulbar neuritis is characterized by the suddenness with which the disturbance of vision develops. This failure of sight in the severe cases may attain such a degree within a few days that all perception of light is abolished. Externally, the diseased eye looks normal; at most the pupil is dilated. The ophthalmoscope, too, shows scarcely anything besides some distention of the retinal vessels.* These symptoms are often accompanied by violent headache or by dull pain in the orbit, the latter being aggravated if the patient moves his eye or if the attempt is made to push it back in the orbit. Sometimes both eyes are attacked by this disease at the same time.

The disease usually goes on to a complete or partial cure. In the first case the sight becomes normal again, in the second case a central scotoma generally remains. A pretty long time (one or more months) is required for the process of healing. In a few cases, however, the total blindness remains permanent, so that it is impossible to state the prognosis with certainty at the beginning of the disease.

The known causes of acute retro-bulbar neuritis are great chilling of the body, excessive exertion, acute infectious diseases, such as measles, influenza, angina (Von Graefe), suppression of the menses, lead-poisoning. I have sometimes seen the disease develop in gentlemen who had become very much heated in hunting and then were driven in open carriages in the cold. I once saw it

* Sometimes, on the contrary, ischæmia of the retina is present when the central vessels have undergone compression at the inflamed spot in the optic nerve.

result from excessive exertion in a young man who, under the stimulus of a bet, had covered a very great distance upon a velocipede in one day; on the next day he had a bilateral retro-bulbar neuritis. The hereditary form of neuritis may also appear under the guise of acute retro-bulbar neuritis. The treatment of the disease is that of neuritis in general. In the acute stage energetic diaphoresis proves particularly efficient.

Chronic retro-bulbar neuritis has as its typical representative tobacco amblyopia (amblyopia nicotinica), which originates in chronic poisoning by nicotine. It was first described by Arlt as retinitis nyctalopica, because the symptom of nyctalopia was the one that struck his attention most forcibly. Arlt's statements in regard to the symptoms, course, and treatment of the disease are still correct to-day; but Arlt was ignorant of the cause of the disease, which he referred to the effect of dazzling by a bright light.

Tobacco amblyopia makes itself evident only by the disturbance of vision, and this sets in so gradually that the patients are for the most part unable to tell exactly when it begins. At first medium-sized print can still be read, afterward the reading of ordinary print becomes impossible. The reduction in the visual acuity is almost always the same in both eyes—a fact which distinguishes this from other intra-ocular affections, such as cataract, chorioiditis, atrophy of the optic nerve, etc., in which the two eyes are usually affected to a different degree. The symptom of nyctalopia is particularly characteristic. The patient declares that he sees much better in the evening than in the daytime; indeed, in recent cases he often imagines that in the evening he still sees as well as he he used to do, and that it is only in the daytime that he has a troublesome cloud which dazzles his sight. Objective examination shows that really in most cases no observable improvement takes place when the illumination is reduced; but the annoying sense of dazzling is done away with, so that the patient believes that he sees better. In some cases, however, I have been able to make out a real improvement in the sight upon diminishing the illumination. One of these patients read finer print and read it better when he put on dark-gray goggles than he could do with the naked eye. Another patient, a coachman, could still recognize in the evening the numbers of the houses to which he had to go, while in the daytime he no longer was able to do it. Many patients also declare that they can not recognize red colors, particularly of small objects, as well as they used to do. Their acquaintances, they find, look ill because their cheeks appear to them to be of a waxen yellow.

Objective examination shows but slight ophthalmoscopic changes. In recent cases the papilla is usually somewhat hyperæmic; in the older cases, on the contrary, it has grown paler in its temporal half. But these changes are so little pronounced that one may say that the result of examination is negative. Examination of the vision shows a moderate diminution of the visual acuity, which has its cause in a central scotoma. This scotoma forms a horizontal oval, extending from the macula lutea to the blind-spot, and corresponding, therefore, to the maculo-papillary region of the retina. At first there is simply a color-scotoma. No gap is found in the field of vision if it is tested by means of a white object; but a red or green mark undergoes a change of color in the region of the scotoma. It appears less highly colored than in the other portions of the field of vision, and later on appears perfectly colorless. Later still, the red mark is not seen at all within the area of the scotoma, and finally the white mark, too, disappears in this portion of the visual field; the scotoma has now

become absolute (see pages 26 and 27), and the vision has become reduced to the lowest point that it can reach in this disease. The outer limits of the visual field always remain normal, and complete blindness is therefore not to be apprehended, but direct vision is destroyed, and with it the ability to carry on any fine work. Owing to the chronic course of the disease, it takes a series of months for the sight to be reduced as low as this; and, moreover, this extreme reduction does not occur in every case.

The cause of tobacco amblyopia is the excessive use of tobacco, whether by smoking or chewing. The disease is hence found almost exclusively in the male sex, and in them not generally until middle life. It would thus appear as if the resistance to nicotine diminishes with age. The quantity of tobacco which is sufficient to bring on a tobacco amblyopia varies according to the susceptibility of the individual, in many cases comparatively small amounts of tobacco having sufficed for this purpose. The cheap varieties, which are usually richer in nicotine, and also moist tobacco, are more dangerous than the better, dry qualities. The abuse of spirituous beverages, which, to be sure, is very usual with great smokers, favors the development of tobacco amblyopia; but it also occurs in smokers who abstain altogether from alcoholic drinks.

Treatment consists, first of all, in abstinence from tobacco, and it is probable that in light cases this alone is sufficient to effect a cure. To accelerate the cure we employ iodide of potassium internally or hypodermic injections of strychnine or pilocarpine. In addition, we prescribe a suitable regimen for the eyes. Recent cases in which middle-sized print can still be read, and in which the scotoma has not yet become absolute, afford a good prognosis, since a perfect cure is usually obtained, although one to two months are required for it. In older cases, in which even quite large print can no longer be read and the scotoma is absolute, a complete cure is for the most part impossible.

Other toxic agents may like nicotine lead to retro-bulbar neuritis through a process of chronic poisoning, and that, too, with symptoms which are the same as those of tobacco amblyopia or which are very similar. The most prominent agent in this category is alcohol. Besides, I once treated a patient who from his youth up had smoked stramonium-leaves in great quantities on account of asthmatic attacks, and who from this cause had acquired an amblyopia with a central color-scotoma (the man was neither a smoker of tobacco nor a drinker). Lastly, in this connection must also be mentioned cases of chronic poisoning by lead, by disulphide of carbon (in caoutchouc-factories), by chloral and other poisons, and also by diabetes.

We are indebted for the first anatomical discoveries in regard to chronic retro-bulbar neuritis to Samelsohn, who found an interstitial neuritis in that portion of the trunk of the optic nerve which lies within the optic canal. The inflammation was limited to the fibers of the papillo-macular bundle, whose situation and course within the optic nerve it was thus possible to determine.

Strychnine.—This was first recommended by Nagel for the treatment of lesions of the optic nerve. It exerts an excitant action upon the optic nerve, so that even in normal eyes it produces a slight, although not permanent, increase in the visual acuity and enlargement of the field of vision (Hippel). For therapeutic purposes, a one-half-per-cent solution, of which a quantity equal to one half or the whole of the contents of a Pravaz syringe—i. e., as much as 5 mgr. [= $\frac{1}{13}$ grain] of strychnine per dose—is injected once a day beneath the skin of the temple. It acts best in disturbances of vision unattended by changes visi-

ble with the ophthalmoscope, especially in hysterical and neurasthenic forms, which, however, generally afford a good prognosis anyway. In serious lesions of the optic nerve, as in progressive atrophy, we often obtain with it an improvement in the sight and especially an enlargement of the field of vision; but these changes are commonly not permanent.

II. Atrophy of the Optic Nerve.

104. Atrophy of the optic nerve develops either as a primary affection or as secondary to an antecedent inflammation. We accordingly distinguish between simple and inflammatory atrophy.

(*a*) *Simple* (primary or genuine or non-inflammatory) atrophy is distinguished by the papilla becoming paler, and at length perfectly white or bluish-white, and also becoming sharply defined and slightly excavated (atrophic excavation; see page 335); the gray dots of the lamina cribrosa are visible more distinctly, and over a larger area; the more minute blood-vessels of the papilla itself have disappeared, while the retinal vessels are not markedly altered (in contradistinction to inflammatory atrophy, in which the latter are narrowed, too). As the atrophy increases, the sight is reduced until there is complete blindness. The *causes* of simple atrophy of the optic nerve are: 1. Spinal affections, particularly tabes dorsalis, which is by far the most frequent cause of the simple form of optic-nerve atrophy. This atrophy usually develops in the initial stage of tabes at a time when the ataxic symptoms are slight or absent, and the diagnosis of tabes is not yet readily made. It is therefore a fact of great value to us that we know two other symptoms, which, moreover, usually make their appearance very early. One of these symptoms regards the pupil, which no longer reacts to light (Argyll-Robertson phenomenon; page 261), and is generally also greatly contracted (spinal miosis; page 308). The other symptom, discovered by Westphal, is the absence of the patellar reflex. Spinal atrophy of the optic nerve always affects both eyes, although not necessarily both at the same time. It advances slowly but surely until there is complete blindness, and hence has rightly earned the name of progressive atrophy. 2. Among affections of the brain, disseminated sclerosis and progressive paralysis of the insane are complicated with atrophy. Moreover, tumors or other focal affections may induce simple atrophy of the optic nerve by compressing the nerve itself or its continuation within the skull. In this case the atrophy is propagated gradually from the site of the break in the line of conduction down to the intra-ocular extremity (descending atrophy). 3. The break in the line of conduction may also evidently be located nearer the periphery—i. e., in the orbit where the optic nerve may be thrown into a state of atrophy through inflammation or injury or as a result of compression by tumors. 4. In many cases of simple atrophy of the optic nerve the cause remains obscure.

(*b*) *Inflammatory atrophy* of the nerve is the form which occurs as the final result of a neuritis or a retinitis (neuritic or retinitic atrophy). Inflammatory atrophy is distinct from the simple variety in its ophthalmoscopic features as well as its origin, because in it the papilla is traversed by connective tissue formed by an organization of the exudate. In *neuritic* atrophy the papilla is at first of grayish-white color, and its margins are slightly hazy; the veins are very distended and tortuous. Afterward the papilla becomes of a pure white or bluish-white, but we do not see the lamina cribrosa exposed to view, as in simple atrophy. The papilla is now sharply defined, but is often smaller than normal, and irregular, as though it had been shrunken; both arteries and veins are contracted, and are frequently inclosed within white streaks. In *retinitic* atrophy the papilla looks clouded and of a dirty grayish red. Its outlines are faint, and the vessels are greatly thinned, and often have entirely disappeared.

The *prognosis* of atrophy of the optic nerve is in general unfavorable. Cases of simple atrophy for the most part lead to complete blindness. Inflammatory atrophy affords a somewhat better prognosis, since the amount of sight which the neuritis or retinitis has left is usually permanently preserved. *Treatment* consists primarily in the management of the causal disease. For the lesion of the optic nerve itself potassium iodide, mercurials, injections of strychnine, and the constant current applied to the eye itself, are employed; unfortunately, however, with but slight success.

The disturbance of sight in atrophy always affects not only direct vision, but also the visual field, which is found to be diminished. Sector-shaped defects or concentric contraction of the visual field are the most frequent forms under which this occurs. Color-blindness also sets in early: first for red and green, and last of all for blue, which color, therefore, is recognized the longest. By this circumstance atrophy is distinguished from glaucoma simplex, which sometimes shows much resemblance to it, but which is not ordinarily associated with color-blindness until late in its course.

Simple atrophy is found most frequently in middle life. In children it almost never occurs; the atrophy of childhood is, as a rule, neuritic. Men are more frequently attacked by simple atrophy than women, a fact which is dependent upon the greater predisposition of the male sex to spinal affections.

Injuries of the Optic Nerve.—The optic nerve may be injured within the orbit by means of penetrating foreign bodies, stab-wounds, shot-wounds (particularly those produced by fine shot), etc. As a result of this break in the line of the conduction, blindness—partial or complete according to the severity of the lesion—is present immediately after the injury. With this there are at first no ophthalmoscopic changes that can be demonstrated in the optic papilla. It is not until later, after weeks have elapsed, when the descending atrophy has traveled down from the site of injury to the optic papilla, that the latter becomes paler and presents the picture of simple atrophy. It is only when the optic nerve has been injured so far forward that the central vessels are at the same time divided that characteristic ophthalmoscopic symptoms can be

made out at once. In such cases there develops immediately after the injury a picture analogous to that of embolism of the central artery. The arteries of the papilla and retina are bloodless, and the retina soon becomes clouded—a sign of its death.

Indirect injuries of the optic nerve occur not infrequently in consequence of injuries of the skull by the impact of a blunt object (a blow or fall upon the head, etc.). In such cases there is partial or complete blindness associated with the symptoms of a severe injury of the skull (the signs of concussion of the brain or of fracture of the base of the skull). Such blindness may be unilateral or bilateral. It has been demonstrated by the investigations of Hölder and Berlin that in these cases we are dealing with indirect fractures of the walls, particularly of the upper wall, of the orbit, which fractures are continued into the optic canal, so that the optic nerve in the latter is crushed or lacerated. Several weeks or months afterward there is developed in the papilla the picture of simple atrophy. These cases of blindness are incurable.

Tumors of the Optic Nerve.—The optic nerve may be affected with tumor-formation, either primarily or secondarily. The latter most frequently happens through the growth of intra-ocular tumors, such as sarcoma of the chorioid and glioma of the retina, backward along the optic nerve. Primary tumors of the optic nerve are rare. They comprise fibromata and sarcomata with varieties (myxosarcoma, psammosarcoma, gliosarcoma, etc.) of the latter, springing from the interstitial supporting tissue or the sheaths of the optic nerve. Pure neuromata, originating from the nerve-fibers, have up to the present time not been observed with certainty in the optic nerve, but there have been seen some cases of tuberculous granulation-tumor. Primary tumors of the optic nerve begin generally in youth, and grow very slowly. They cause a form of exophthalmus, which is distinguished from that occurring with other orbital tumors by the fact that the lateral displacement is either entirely absent or is at all events insignificant. The mobility of the eye remains good for a comparatively long time; on the other hand—and this is a characteristic sign—blindness sets in very early. With the ophthalmoscope we find at first neuritis with the venous engorgement particularly marked; afterward atrophy. Treatment consists in extirpation of the tumor; in doing which we may, under certain circumstances, leave the eye in its place.

Anatomy of Affections of the Optic Nerve.—*Inflammation* of the optic nerve starts from its connective-tissue portions—that is from the sheaths and the connective-tissue septa. In the sheaths there is found, besides the dropsical condition already mentioned, actual inflammation with a formation of a cellular exudate (perineuritis; Stellwag, H. Pagenstecher). Within the trunk of the optic nerve the inflammation attacks the septa, which show thickening with multiplication of their nuclei (interstitial neuritis). Owing to this, the bundles of nerve-fibers, which are inclosed by them, are compressed and undergoing atrophy, are destroyed. Accordingly, in neuritis the nerve-fibers act mainly a passive part.

In *engorgement neuritis* the inflammatory symptoms are limited to the papilla, while the trunk of the optic nerve back of the lamina cribrosa suffers little or no change. In the first place, the papilla is found to be greatly swollen by an accumulation of œdematous liquid, so that it projects like a mushroom into the interior of the eye, and is thickened at its base so as to form an actual tumefaction (neuritic swelling, Fig. 90, *n*). The retina is pushed to one side and

thrown into folds by the enlarged optic nerve. Besides the œdema there are also found extravasations of blood, swelling of the nerve-fibers, and the evidences of a scanty cellular infiltration, particularly along the blood-vessels (Fig. 90, *e*). Later on the cellular exudation becomes more and more prominent, and in the subsequent course of the disease leads to a new formation of connective tissue within the papilla, due to organization of the exudate. By the subsequent shrinking of the connective tissue the fibers of the optic nerve are rendered atrophic, and the picture of neuritic atrophy of the optic nerve is produced. We then find in place of the papilla a network of connective-tissue strands, and among them blood-vessels whose walls are thickened.

Simple atrophy of the optic nerve occurring in spinal lesions first makes its appearance in insular spots; isolated foci of disease, which appear gray upon cross-section, showing themselves in the trunk of the optic nerve. In this case we are dealing with the same gray degeneration which exists in the posterior columns of the spinal cord in tabes. The nerve-fibers lose their white medullary substance, and are transformed into extremely minute fibrillæ, and it is due to this fact that the entire tissue acquires its gray and translucent appearance. Between the remains of the nerve-fibers are found cells filled with granules of fat; symptoms of inflammation proper, however, are wanting.

The anatomical condition found in descending or ascending atrophy is similar to that occurring in gray degeneration of the optic nerve. The atrophy reaches its highest degree in those cases in which the eyeball has been completely destroyed, the optic nerve in this instance shrinking in the course of time to a thin strand consisting simply of connective tissue.

Disturbances of Vision without Apparent Lesion.

105. The expressions amblyopia* (weak sight) and amaurosis† (absolute blindness) are in use as terms to designate disturbances of vision. The former designation is now applied only to those cases in which the weakness of sight can not be relieved by suitable glasses. For instance, a myope who sees badly with the naked eye, but possesses the full amount of visual acuity with the correcting concave glass, is not amblyopic but simply myopic. Under the name of amaurosis were formerly known those cases of blindness in which the eye had externally a normal appearance, so that this designation was equivalent to the expression "black cataract" ("schwarzer Staar"). The ophthalmoscope has thrown light upon these cases, which are for the most part referable to affections of the chorioid, the retina, and the optic nerve. At the present day the expressions cerebral amaurosis and spinal amaurosis are used in the old sense; those cases being designated by these names in which blindness has set in as a result of diseases of the brain and spinal cord, while the external appearance of the eye is normal. But the word amaurosis is also employed at present in a wider sense as equivalent to total blindness, even when the eye shows external changes. Thus we say of an eye blinded by irido-cyclitis that it is amaurotic.

---

* Properly blunt-sightedness, from ἀμβλύς, blunt, and ὤψ, sight.

† ἀμαυρός, dark.

Thanks to the refined methods of examination with glasses, but most of all thanks to the ophthalmoscope, it is at present possible in most cases to discover the cause of weak sight or of blindness. Nevertheless, there does remain a small number of cases in which we are unable even now to demonstrate any changes in the eye as a cause for the disturbance of vision. In some of these cases of disturbance of vision without apparent lesion, the changes are so minute or have such a situation that they are not discoverable by our present methods of examination. In other cases there are no anatomical lesions whatever, and what we have before us is simply the so-called functional affections—i. e., altered conditions of circulation and nutrition resulting in disturbance of function.

The most frequent varieties of disturbance of vision without apparent lesion are:

1. **Congenital Amblyopia.**—We assume this to exist in those cases in which, according to the account given by the patient, the weakness of sight has existed for a long time, and in which all other causes for it can be excluded. We are justified in making this assumption whenever other congenital anomalies are also present in the amblyopic eye, such as an extreme degree of hypermetropia or astigmatism, coloboma of the iris or the deeper membranes, microphthalmus, etc. For experience shows that such eyes almost always display a reduction of the visual power, which can not be brought to the point of normal vision even by the correction of the error of refraction that is present.

Congenital amblyopia is usually unilateral; the affected eye is then very prone to fall into a state of squint. If the amblyopia affects both eyes, nystagmus develops (see § 129).

2. **Amblyopia ex Anopsia.***—Amblyopia from non-use occurs when there has been present since earliest youth an obstacle to vision in the eye, which makes the formation of sharp images upon the retina impossible. In this category belong cases of opacities either of congenital origin or acquired early in life, situated in the cornea, lens, or in the region of the pupil (pupillary membrane). Amblyopia also develops in an eye which has squinted since childhood, because in this case the perception of the retinal images in this eye is suppressed, and the eye is thus purposely excluded from participation in the act of vision. In all these cases, the retina, owing to lack of exercise, fails to attain to that delicacy of function which belongs to normal eyes, or the functional capacity which has been already acquired is lost; but absolute blindness never occurs. The function of the retina never again becomes perfectly normal, even if the cause of the visual disturbance is done away with either through removal of the optical obstacle to sight or through correction of the squint by an operation.

---

* From ἀ, priv., and ὄψ, sight.

When—as in an adult man—the development of the retina has once been completed, an obstacle to vision may last for many years without the retina suffering any harm. Thus cataracts which have formed in adults have been operated upon with perfect success twenty years or more afterward.

Treatment consists in the earliest possible removal of obstacle to vision. This rule holds good particularly for the cataracts of childhood, the performance of an operation upon which was formerly as a matter of choice put off till the age of puberty, although we may operate upon cataract (by discission) in children even at the age of a few months with the best results. Exercising of the amblyopic eye is of service in bringing up the functional power of the retina. This is particularly employed in cases of strabismus, where by bandaging the sound eye we force the eye which squints to see (see § 128).

3. **Hemeralopia** * **(Night-Blindness).**—By this term when used in its widest sense we understand that condition in which one sees well by day, but at night or under feeble illumination from any cause sees poorly or not at all. This condition is not in itself a disease, but simply a symptom which may belong to various diseases. These latter are divided into two groups—opacities in the media and diseases of the light-perceiving apparatus. The former may excite the symptom of hemeralopia when they occupy the periphery and leave the center free, as in the case of peripheral opacities of the cornea and lens. Under brilliant illumination, when the pupil is contracted, these no longer fall within the area of the latter, while, when the illumination is diminished and the pupil is dilated, they project into the pupil and interfere with sight. Again when there are slight diffuse opacities distributed uniformly over the entire cornea, the sight is often better when the pupil is contracted, because the dazzling due to diffused light is then less. The diseases of the light-perceiving apparatus which are associated with hemeralopia are those in which the peripheral portions of the retina are under-sensitive. In such cases we find the field of vision normal in bright daylight but contracted when the illumination is diminished, and hence find that orientation and therefore the power of going about are rendered difficult at night. This symptom appertains most especially to retinitis pigmentosa, but is also sometimes observed in other forms of inflammation of the retina and the chorioid. Idiopathic hemeralopia, which will be discussed more at length further on, also depends upon a lesion of the light-perceiving apparatus, although it is impossible to demonstrate any material changes in the latter.

The symptom opposed to hemeralopia is *nyctalopia* †—i. e., that condition in which the sight is better at night or in diminished illu-

* From ἡμέρα, day, and ὄψ, sight.
† From νύξ, night, and ὄψ, sight.

mination than in bright daylight. This symptom, too, belongs to two groups of diseases which have their seat either in the media or in the light-perceiving apparatus—only, in this case the site of the changes is just the reverse of that found in hemeralopia. The opacities of the media causing nyctalopia are centrally situated (in the cornea, pupil, or lens), so that when the pupil is contracted they occupy its entire area, but, when upon diminution of the illumination the pupil dilates, the peripheral portions which are still transparent can be used for seeing. The affections of the light-perceiving apparatus are those in which the outlying portions of the field of vision are normal, while in the center there is a scotoma. In these cases, to be sure, the visual acuity is ordinarily no better with diminished illumination than it is in full daylight, but the feeling that central vision is blunted is less unpleasant, so that the patient imagines that he sees better in the evening. This symptom is most pronounced in tobacco-amblyopia (see page 440).

Besides the above-mentioned cases in which hemeralopia exists as a symptom of other changes, there are some in which apparently *hemeralopia occurs idiopathically*, i. e., without perceptible changes in the eye. These are denoted by the name of hemeralopia or night-blindness, in the narrower sense of the word. If tests of the vision are made in such a case, it is found that, according to the statements of the patient, the visual acuity is normal when the illumination is good, but sinks with unusual rapidity when the illumination is diminished. If the room is darkened, by letting down the window-curtains to such an extent that the examining physician can still read medium-sized print, the patient will perhaps no longer recognize the large letters, or he will even in walking through the room stumble over the chairs which stand in his way. A more accurate examination can be made by means of Förster's photometer (see page 28), which in these cases shows a considerable reduction of the light-sense. If the retina is set in action by sufficiently strong stimuli—i. e., by brilliant images—it performs its functions normally; but as soon as the stimuli sink below a certain limit it no longer reacts toward them. This condition is called torpor retinæ. In it examination with the ophthalmoscope shows no changes whatever in the interior of the eye. But in most cases a xerosis of the bulbar conjunctiva exists (see page 112); i. e., we find in the latter upon the outer and inner side of the cornea a small rounded or triangular spot, over which the surface of the conjunctiva looks dry and seems as if covered with a fine, whitish foam. Xerosis of the conjunctiva has no other connection with torpor retinæ than that both are symptoms of a reduced state of nutrition of the eyeball.

Hemeralopia originates in a disturbance of nutrition of the retina, the real nature of which has not yet been discovered. Two chief exciting causes for this disturbance of nutrition are known, and heme-

ralopia is usually produced by their combined action. Dazzling by a bright light is the first of these. Hence, the disease is chiefly observed in the spring when the sun begins to shine with greater intensity. Sailors, when they come under the dazzling sun of the tropics, are frequently attacked by the disease. The second, and without doubt more important, cause is a reduction of the general nutrition. The disease accordingly is found in people who in general are insufficiently nourished, as the inmates of workhouses, penal establishments, and orphan asylums, and soldiers and sailors (in the latter occurring simultaneously with scurvy). In Russia, the disease is found especially during and after the long fast at Easter, during which time the people eat no meat; at this time the disease not infrequently appears as an epidemic. Furthermore, hemeralopia is sometimes observed in jaundice, in intermittent fever, in chronic alcoholism, and also in pregnant women.

The *prognosis* of hemeralopia is favorable, as the disease usually gets well of itself after some weeks or months. It, however, leaves behind it a tendency to recurrences which usually make their appearance in the spring or summer of the years next succeeding.

The *treatment* consists in elevating the nutrition by strengthening diet and by corroborative remedies and in protecting the eyes from light. In the lighter cases, we make the patient wear dark glasses, in the severer cases we keep him for several days in a dark room. By this treatment an abbreviation of the disease is secured.

Hemeralopia in conjunction with xerosis of the conjunctiva is also found as a precursor of keratomalacia, which likewise must be regarded as the consequence of a disturbance of the general nutrition (see § 40).

4. **Amblyopia and Amaurosis of Central Origin.**—Disturbance of vision may be set up by disease of the brain without there being any ophthalmoscopically perceptible changes in the eye, such as neuritis or atrophy of the optic nerve. Disturbances of vision of this sort may be transient only, even when they amount to absolute blindness. Uræmic amaurosis (see page 409), which is produced by retention of the urinary constituents, affords a good example of this. But in those cases in which gross lesions of the brain, such as inflammatory processes or new growths, give rise to the disturbance of vision, the latter is permanent, and ophthalmoscopic changes, usually under the form of a descending atrophy of the optic nerve, are often associated with it later. Disturbance of vision dependent upon a central cause makes its appearance not infrequently under the guise of hemiopia (homonymous or temporal).

5. A peculiar form of temporary blindness of central origin is the **scintillating scotoma** (scotoma scintillans, amaurosis partialis fugax, or teichopsia*). The patient who suffers from it notices that a scintillation attended with feel-

* From τεῖχος, wall, and ὄψις, vision, on account of the zigzag lines, resembling fortification-walls, often seen on the edge of the scintillating spots.

ings of vertigo appears before his eyes, and that this rapidly increases until finally he can scarcely see at all. Persons who are more accurate observers of their sensations usually aver that the scintillation takes its origin from a small spot situated not far from the point of fixation, and then gradually spreads over a pretty large portion of the field of vision which becomes more and more contracted as the scintillation extends. The outlines of the scintillating area are often formed by a line which runs in and out in a zigzag fashion. After a quarter or a half of an hour, the attack abates, the visual field beginning to clear up at the point first affected. Scintillating scotoma is usually accompanied by headache and sometimes also by nausea, and frequently a regular attack of migraine is joined with it.

The central origin of scintillating scotoma is apparent not only from the accompanying and following headache, but also from the fact that it always affects both eyes in the same way, and frequently occurs under the form of hemiopia—i. e., it occupies but one half (and that, too, the homonymous half) of the field of vision in each eye. The symptoms, on account of their short duration, can scarcely be referred to anything but circulatory disturbances, the site of which is probably the optical areas of the cortex in the occipital lobes. The circulatory disturbance sets up an irritation of the optical elements—an irritation which according to the laws of projection is referred to the external world, and appears under the form of a colored scintillation, while at the same time the perception of peripheral impressions is abrogated. At the beginning of a fainting attack, too, which in fact is likewise due to circulatory disturbances in the brain, symptoms make their appearance which are perhaps identical with scintillating scotoma; people averring that everything looks green and blue, or scintillates, or grows dark before their eyes.

Scintillating scotoma is an uncommonly wide-spread affection. If it occurs but rarely—at intervals of several years—no significance is attached to it by the patient, as it disappears again rapidly, and without leaving any bad results. It is only when the symptom is repeated frequently—and it may even recur several times a day—that those who are troubled with it come to the physician. Such patients allege as the cause of their scintillating scotoma excessive physical or mental exertion, straining of the eyes, dazzling light, or a great sense of hunger; often, however, no definite cause can be made out. The treatment must be confined to opposing the cause of the scotoma. Such treatment consists in increasing the general strength, excessive exertion being at the same time avoided. A glass of wine drank quickly at the beginning of an attack suffices not infrequently to cut it short (in those cases in which it is caused by anæmia of the brain). Ordinary cases of scintillating scotoma are associated with no evil consequences. It is otherwise with those in which other symptoms of central disturbance, such as weakness or paralysis of an extremity, aphasia, etc., make their appearance at the same time with the scotoma; here the latter is not infrequently the precursor of a serious affection of the brain.

6. The **hysterical disturbances of vision** (disturbances occurring in the same way in *neurasthenia* also) are likewise of central origin. There are hysterical amblyopia and hysterical asthenopia.

Hysterical amblyopia consists in a diminution of the acuity of vision and a concentric contraction of the field of vision; not infrequently too there is an accompanying color-blindness. The peculiar rapidity with which the nervous system becomes exhausted in such patients manifests itself often in their

becoming tired quickly during the act of testing the vision and particularly during the process of taking the visual field. The longer we examine the visual field, the more restricted do we find its limits (Förster). Sometimes the disturbance of vision amounts to complete blindness. Hysterical amblyopia generally exists in both eyes, although for the most part in a different degree.

The *diagnosis* of hysterical amblyopia is principally based upon two points. The first of these is the absence of any demonstrable changes in the eye which might explain the enfeeblement of sight. The second is the lack of that agreement between the individual symptoms constituting the disturbance of vision, which under other circumstances they would exhibit. Thus, the acuity of vision and the extent of the visual field change frequently; the relation of the color-limits within the visual field are not in accordance with the rule (see page 27); persons whose visual field is unusually contracted still move with perfect security and without stumbling in a space which is not well known to them; in fact, even in those who are absolutely blind we sometimes find the same thing occur, if they think that they are not observed. It can be seen from these statements that it is often difficult to draw the line between simulation and a hysterical blindness—i. e., one having an actual existence in the imagination. In the latter case there may be other evidences of hysteria or neurasthenia associated with the symptoms of the hysterical amblyopia, which will render the diagnosis more certain.

Hysterical amblyopia chiefly attacks young people, particularly of the female sex. It affords a good prognosis as ordinarily a complete cure takes place. The disease, however, usually lasts for a long time, often for years. Treatment consists in the management of the causal lesion, re-enforced locally by hypodermic injections of strychnine and the application of the constant current. The brilliant results sometimes obtained by the two last-named remedies is, however, mainly ascribable to their psychic influence upon the patient when the latter has confidence in the treatment and anticipates a cure from it.

Hysterical or nervous *asthenopia** consists in an incapacity of the eye for any continuous exertion, in spite of there being good visual power. Some complain that after reading or working for even a short time everything becomes covered with a cloud, so that the work has to be laid aside. Others, again, allege that after pursuing their occupation for a little while, indeed even after reading a few lines, they have violent pains in the lids, eyeball, or head, which render the continuance of the work impossible (copiopia † hysterica, Förster). When no strain is put upon the eyes, there is no trouble; in other cases, however, the pains never entirely disappear, or a great sensitiveness to light is constantly present.

In making the diagnosis, proof must first of all be forthcoming that there is no error of the refraction or of the muscular equilibrium to cause the trouble. Nervous asthenopia, like hysterical amblyopia, with which it frequently is associated, is often extremely obstinate, and sometimes for years prevents the patient affected by it from engaging in any serious occupation. In it, too, the psychical factor plays a great part in the treatment. I have found electricity (galvanization of the sympathetic) the most efficient means. Very recently cases have been described under the name of *dyslexia* (Berlin) which might easily be confounded with asthenopia. In these cases reading often becomes impossible even after a

---

* From ἀσθενής, weak, and ὤψ, sight.

† From κοπία, exhaustion, and ὤψ, sight.

few words have been read, without there being any blurring of the print or any pain. In several of these cases autopsy has demonstrated the presence of disease in the left cerebral hemisphere, more particularly in the neighborhood of the third frontal convolution.

7. **Color-blindness.**—Color-blindness occurs both as a congenital and an acquired affection. The former is not a disease but an imperfection of vision dependent upon unknown causes; the latter accompanies many diseases of the retina and optic nerve.

Congenital color-blindness is known as daltonism, after the English physicist Dalton, who was himself color-blind, and was the first to describe this defect accurately. It may be *total*, so that no color is recognized, and the external world looks gray all over like an engraving; or it may be partial, only a certain group of colors being deficient. The former variety is extremely rare; the latter, on the other hand, is pretty frequent. Very often it is not complete blindness for any special color that exists, but only a rather less marked ability to distinguish one from the other, so that colors are not recognized with the same certainty and at the same distance as is the case in the normal eye (*weakness of the color-sense*). There are thus all sorts of transition-forms between normal color-sense and total color-blindness.

The distribution of the cases of partial color-blindness into different categories is made in accordance with the theory of color-perception which is considered to lie at their base. In the following considerations we shall first start with the Young-Helmholtz theory. This assumes the existence of three fundamental sensations, corresponding to the fundamental colors red, green, and violet; and supposes the other color-sensations to originate through a varying mixture of the fundamental sensations. Partial color-blindness would then consist in the deficiency of the sensation for one of the primary colors, so that the color-sensations of the affected individual would be compounded only of the other two fundamental colors. According to the fundamental color that is deficient we make the distinction between red-blindness, green-blindness, and violet-blindness.

Now, in what way does a color-blind person—for instance, one affected with red-blindness—comport himself? We are not to suppose that such a one does not perceive red objects at all, or that, if he sees them, they appear perfectly colorless. The fact is simply that the sensation which he has in looking at red objects is the same as that which green objects excite in him, so that he confounds red and green with each other. To understand this, we must for the present adhere to the Young-Helmholtz theory. According to this, there are in the retina three species of fibers corresponding to the three primary colors. Each one of these species of fibers is set into action by all kinds of colored light, but to a different degree of intensity. Some fibers are set into action most strongly by red rays, less so by yellow, still less by green, and least of all by violet. They are hence designated simply as the fibers for the perception of red. The curve represented in Fig. 91, *A*, illustrates the way in which these fibers act. The different colors of the spectrum are laid off upon the abscissa, while the ordinate shows the intensity of the excitation produced by each individual color. In analogous fashion the second set of fibers is set into action most strongly by the green rays (Fig. 91, *B*), the third group of fibers most strongly by the violet rays (Fig. 91, *C*).

Every kind of light affects all three groups of fibers at the same time, and

sets them all into action, but with differing intensity, as is shown by Fig. 91, *D*, in which the curves of the three groups of fibers are erected upon the same abscissa. The red ray, r^1, excites most strongly the fibers for the perception of red, more feebly those for the perception of green, and least of all those for the perception of violet. Under these circumstances we get a sensation of red, because the degree of excitation of the fibers for the perception of red exceeds that of the other fibers. In like fashion, a green ray, gr^1, stimulates the fibers for the perception of green more strongly than it does the other two kinds, and excites the sensation of green. An analogous statement holds good for the sensation of violet (v_1).



FIG. 91.—REPRESENTATION OF COLOR-PERCEPTION, ACCORDING TO THE THEORY OF YOUNG AND HELMHOLTZ.

The abscissa represents the spectrum, the colors of which are—red, *r*, orange, *o*, yellow, *g*, green, *gr*, blue, *bl*, violet, *v*; the curves which rise above the abscissa show graphically the sensitiveness of the three sorts of fibers in the retina toward rays of different wavelengths. The ordinates, r^1, gr^1, and v_1, indicate the intensity of the stimulation of the fibers produced by red, green, and violet rays. *A* gives the curve representing the sensitiveness of the fibers for the perception of red; *B*, that of the fibers for the perception of green; *C*, that of the fibers for the perception of violet. In *D*, all three curves are represented at the same time. *E* shows the curves of sensitiveness of a red-blind eye in which the fibers for the perception of red are assumed to be wanting.

Now, a man afflicted with red-blindness presents a condition differing from this normal one, in that the fibers for the perception of red are absent (Fig. 91, *E*). If he looks at the spectrum it appears to him shortened at its red end, since he sees only blackness at spots where others still perceive red. A red ray, r^1, which falls upon this man's retina sets into action only the fibers for the perception of green and those for the perception of violet—and of these the former more markedly, so that the resultant effect will be a green. If green light falls upon the retina, the fibers for the perception of green are again stimulated more strongly than those for the perception of violet, and again the sensation of green is produced. Where, then, we have two different sorts of sensations, viz., red and green, a person with red-blindness has two that are similar, namely, both green. (The shade of green which appears to most persons with red-blindness to have the same color as red is that hue of bluish green which is complementary to red.) A person with red-blindness, however, can distinguish these

two sensations from each other, for, though similar indeed, they are not quite the same. They are distinguished from each other by their difference in brilliancy. For let us assume that the red and green rays selected as an example are of the same brilliancy to a normal eye. Such an eye can still distinguish them apart, owing to their difference in color. The case is otherwise with a red-blind man; in him the red ray, in spite of its luminous intensity, causes but slight stimulation of the fibers for the perception of green, simply because these fibers are in any case but slightly sensitive to red rays. The sensation produced by the red ray is hence a feeble one, and the color which is seen looks dark. The green ray, on the other hand, is perceived in its full brilliancy, because the fibers for the perception of green are stimulated by it in the normal fashion. In this way it is generally possible for the man with red-blindness to distinguish red from green, not indeed by the difference in color, but by their difference in brilliancy. This difference, however, between the character of his own sensation and that of a man with normal vision usually remains unknown to the color-blind person. When growing up, he learns the expressions red and green from his associates, certain objects being pointed out to him as red and others as green. He is told that the leaves of the cherry-tree are green and the cherries between them red. And, as he too notices a difference between the leaves and the cherries, although it is a difference of brilliancy and not of color, he thinks that he sees just as other people do. On account of the sensitiveness to differences of brilliancy, which color-blind persons usually possess, they can generally tell correctly the color of objects even when they have never seen them before. Thus it happens that, in the case of many color-blind persons, neither do they themselves know anything of their defect nor are their associates aware of it. A physician once came to me who was charged with the task of testing the employés of a railroad for color-blindness. He wished to inform himself under my tuition in regard to the methods of investigating the color-sense. When I came to show him the different tests, it soon turned out that he himself was red-blind. Up to that time he had known nothing of this fact, and indeed was quite offended at the imputation of being color-blind. It even happens that the color-blind carry on occupations which in a peculiar degree demand an excellent sense of color; thus there are color-blind painters.

While with many of the color-blind the defect remains undiscovered during their whole life, in others it is disclosed by their committing some gross mistake in the choice of colors, as, for instance, in the case of the tailor who wanted to mend a black coat with a patch of red cloth. How does a color-blind man commit such mistakes? We have seen above that a man with red-blindness distinguishes red and green of equal brilliancy by the fact that the former looks darker to him than the latter. If now we gradually diminish the brilliancy of the green, we must finally reach a point at which this color looks no lighter to the man with red-blindness than does the red which has not been altered in brilliancy. At this moment he is deprived of the means of discriminating between the two colors, afforded by their difference in brilliancy, and is now unable in any way to distinguish the two colors apart. Colors chosen upon this principle are hence known as confusion-colors. On account of the great sensitiveness of color-blind people to differences in brilliancy, the preparation of these confusion-colors requires great care, and is best performed by painters who are themselves color-blind, and who keep toning down two different colors until they seem to them to be alike. Confusion-colors pre-

pared in this way are very well adapted for the detection of color-blindness (Stilling).

What has been said in regard to those affected with red-blindness is also true of the other two classes of the color-blind, those affected with green-blindness and those affected with violet-blindness. The circumstance that is common to all people affected with partial color-blindness is that one of the three fundamental sensations is deficient. It is not necessary that one of the three species of fibers should be completely absent, as, for the sake of simplicity, has been assumed in the example above adduced. On the contrary, it is probable from various reasons that the excitability of one kind of fibers has simply become altered so that its curve is to be imagined as something different from that which the plan outlined above presents; the curve of the fibers for the perception of red, for example, approximating to that of the fibers for the perception of green.

Many authors place Hering's theory of color-perception at the basis of their division of color-blindness. This theory starts from an analysis of the sensations which we have in looking at a color. Most colors excite in us a mixed sensation. Thus, in orange we see besides yellow a certain amount of red; another sort of yellow, again, has a tinge of green, etc. Still, among all the shades of yellow, there is one in which we can perceive no other color besides yellow; this is the pure or primitive yellow. Of such pure colors which excite in us a simple, unmixed sensation there are besides yellow only three—namely, pure red, pure green, and pure blue. These four primary colors form two pairs, namely, red and green and yellow and blue. The two colors of each pair are called contrary colors, because they have this peculiarity that they never can be perceived at the same time in the same color. We can conceive of a blue which affords simultaneously the impression of some green or some red, but we can not conceive of one which would also excite the sensation of yellow. The contrary colors, therefore, are mutually exclusive, so far as sensation is concerned.

Every color may occur in different degrees of concentration and of brilliancy. This depends upon the fact that every color produces in us besides the sensation of color also that of white. Colors along with their color "valence" have also a white "valence," and upon the mutual relations of these two valences depend the concentration and brilliancy of the color. The primary colors possess along with the white "valence" only one color-valence, but the mixed colors possess two. Thus, there belong to violet a blue, a red, and a white valence. The way in which the action of light upon the terminations of the nerves in our retina takes place is that bodies ("visual substances") are present in the latter which suffer chemical changes due to the light. Such changes may be of two different and indeed opposite sorts, the visual substances being either decomposed ("dissimilated") or regenerated ("assimilated") by the light. The white valence which all colors possess depends upon the disassimilative action which they exert upon the visual substance for the perception of black and white. In the absence of light, assimilation of this substance takes place, so that we have the sensation of blackness. Besides the black and white visual substance there are two others, namely, a red-green and a blue-yellow substance, as we will call them for short. These are not altered by every kind of light, but only by that kind which has the corresponding color-valence. Pure red, for instance, would disassimilate only the red-green substance, pure green would cause its assimilation, while

violet acts both on the red-green and upon the blue-yellow substance. If pure red and pure green light fall at the same time upon the same spot of the retina, it depends upon the proportion between the two whether disassimilation prevails over assimilation or the contrary. The resulting sensation consequently is either red or green, but never both together. If the two contrary colors are so chosen with respect to their quantity that they are in equilibrium in their action upon the visual substance, their color-valences are abrogated; there only remains the action of the two kinds of light upon the black-white substance, so that there is a sensation of white of a certain degree of brilliancy. For these reasons, therefore, the contrary colors mutually exclude each other in sensation, and when mixed in certain proportions afford a sensation of absence of color (i. e., they are complementary colors).

According to Hering's theory of colors, the cause of color-blindness must be conceived to consist in the absence of one or of both of the colored visual substances. In the latter case, in which nothing but the black-white visual substance is left, total color-blindness exists; all colors now act simply by reason of their black-white valence, and hence are perceived as white of different degrees of brilliancy (i. e., gray). Absence of the red-green visual substance causes red-green blindness, absence of the blue-yellow substance, blue-yellow blindness. The former comprises the great majority of cases, namely, those which according to the theory of Helmholtz are called red-blind and green-blind. A man with red-green blindness sees in the spectrum only two colors, yellow and blue. These are separated by a gray space (the "neutral" space) which corresponds to the pure green. Pure red and pure green act upon the eye affected with red-green blindness only with their white valences and hence both appear gray, on which account they are by such an eye confounded with one another. Mixed colors undergo an alteration of their tone, inasmuch as of their two color-valences but one comes into play.

By far the most frequent form of congenital color-blindness is red-blindness (according to Hering, red-green blindness). It occurs, as observations upon a great number of men have shown, in from three to four per cent of the male population. In women color-blindness is much more rare, perhaps because their color-sense undergoes a sort of education through their having such frequent occasion to be busy with colored objects (in making dresses, etc.).

Color-blindness entails no disadvantage upon those who are troubled with it beyond rendering them less fit for the performance of certain callings. Among these are all those occupations which require exact discrimination of colors, e. g., that of the painter, the dyer, etc. Recently particular attention has been called to the fact that the railroad and nautical service also require an accurate sense of color. The signals used on railroads or ships are most frequently red or green, which are just the colors that are confounded by most color-blind persons; in this way accidents might be caused. For this reason the employés upon railroads and sea-going vessels are at present in most countries tested with reference to their color-sense, and their entry into the service is made conditional upon the proof that their color-sense is perfect.

The demonstration of the existence of color-blindness requires accurate and cautious testing. Many of the color-blind who are aware of their defect try to conceal it from the examiner, especially if some material advantage such, as, for instance, a business position depends upon the result of the testing. Accordingly, in the case of such persons we must be on the lookout for all sorts of

artifices, and particularly on the lookout for previous practice in the ordinary methods of testing the color-sense. On the other hand, people with a good color-sense might be considered to be color-blind if from want of imagination or practice they designate the colors that are set before them by incorrect names. We should not, therefore, undertake to test the color-sense by setting colored objects before the person and asking him the name of the color. If we do so, the man who is color-blind will in many cases by using a little attention give the right answer, while, on the other hand, an uneducated man will not infrequently call the colors wrong. The test is better performed by placing before the person under examination those colors which according to experience color-blind persons readily confound with each other, and by then seeing whether mistakes are actually committed. For this purpose a large assortment of colored worsteds are the best adapted (Seebeck, Holmgren). One of the worsteds is set before the person to be tested, and he is asked to place with it all the worsteds that look like it. If, then, samples of different and indeed quite dissimilar colors are placed together—for instance, gray and red with green—these give the special confusion-colors of the person under examination, and make it possible to determine the kind of color-blindness that he has. Some have had embroidery patterns to serve as test objects made out of those worsteds the colors of which are most frequently confounded (Daae, Reuss). Colored papers or powders may also be employed instead of worsteds.

The test most in use besides Holmgren's worsted test is the pseudo-isochromatic diagrams of Stilling. These consist of patterns arranged like a chessboard and composed of squares of different colors, which are disposed so as to form letters or figures. The colors of the squares are selected by the aid of a color-blind painter so as to correspond to the confusion-colors of a man who is color-blind. To the latter, then, all the squares appear of the same color, so that he can not recognize the letters or figures formed by them.

For the scientific examination of the color-blind, the spectroscope is indispensable. By its aid we determine whether the color-blind man sees the spectrum shortened at one of its two ends, and what colors he can distinguish in it. Furthermore, by means of the apparatus we show him isolated portions of the spectrum and make him tell, both by naming the colors and by comparing them with specimens of other colors, how the different parts of the spectrum look to him. For a quantitative determination of the color-sense, the method of Donders, Weber, Wolffberg, and others is adapted. Here small disks of colored paper upon a background of black satin serve as test-objects. When the color-sense is normal, disks of a definite size must be recognized at a definite distance, which to be sure is different for the different colors. The weaker the color-sense of the person under examination, the nearer must he get to be able to tell the color correctly, even supposing that he recognizes it at all. The distance at which the color begins to be recognized gives the intensity of the color-sense for the color in question. Instead of colored paper we may use colored glasses which are lighted from behind. These last tests (lantern-tests) approximate nearest to the conditions which are present in the railroad service.

Many other methods of testing the color-sense have been proposed, all of which are of use, as in doubtful cases we can arrive at definitive results only by means of numerous corroborative experiments. Only one of them need be mentioned here, namely, the tissue-paper test of Meyer. If a border of gray

paper is placed upon red paper it, appears to have the complementary color of its background (that is, green). This is particularly apparent when the whole is covered with a sheet of tissue-paper. A color-blind man, who does not recognize the color of the paper forming the background, will also fail to tell correctly the complementary color of the border.

It is impossible to cure congenital color-blindness.

Acquired color-blindness is a frequent symptom of affections of the light-perceiving apparatus—that is, of the retina, of the optic nerve, and even of the central terminations of the optic tracts. It seems in fact that there is a special center for the color-sense in the occipital cortex, after the destruction of which the perception of colors is lost, while the power of differentiating forms—the space-sense—remains intact. Affections of the optic nerve, particularly its atrophy, are, however, by far the most frequent cause of disturbances of the color-sense. Such disturbances are never absent when once the visual acuity has become considerably reduced as a consequence of the affection of the optic nerve. In these cases the color-blindness does not set in suddenly, nor for all the colors at once; but first and very gradually the perception of green and red is extinguished, then that of yellow, and last of all that of blue. Acquired color-blindness may therefore be utilized for purposes of diagnosis. If the sight is impaired simply by dioptric obstacles (e. g., by opacities in the cornea and in the lens), the perception of color remains intact, even when the general features of objects can no longer be recognized; but as soon as the color-sense proves to be defective, an affection of the light-perceiving apparatus must be assumed to exist. (For the color-sense in the periphery of the visual field, cf. page 27 and Fig. 14.)

CHAPTER XII.

DISEASES OF THE LIDS.

Anatomy and Physiology.

106. The lids (palpebræ*) are, according to embryology, folds of the external skin, which push their way over the eyeball to cover and protect it. The boundaries of the upper lid are formed by the eyebrow (supercilium), but the lower lid passes without any sharp line of division into the cheek. The lids bound the palpebral fissure, at the two extremities of which (the angles of the eye) they unite. The external angle of the eye (canthus externus) runs out to a sharp point; when the lids are drawn apart there is put upon the stretch a delicate reduplication of skin (the external commissure), connecting the upper and lower lids in this situation. The inner angle of the eye, on the contrary, presents a horseshoe-shaped notch, at the bottom of which lies the caruncle (Fig. 24, *C*). The mean width of aperture of the palpebral fissure varies with the individual. On an average, the fissure opens so far that, with the ordinary way of looking, the upper lid covers the uppermost part of the cornea, while the lower lid leaves the lower margin of the cornea free. The shape and width of the palpebral fissure are of the greatest influence upon the expression of the eye. Eyes which have the reputation of being large and beautiful are generally not really large eyeballs, but eyes with a wide-open palpebral fissure. So, too, the expression of the laity that "the eye is smaller" usually has reference not to an actual diminution in the size of the eyeball, but to the slighter degree of opening of the palpebral fissure.

The skin covering the lids is about the thinnest in the human body. As, moreover, it is but very loosely attached to its bed through the medium of a lax and non-fatty connective tissue, it can very readily be made to shift its position. For the same reason it can readily fold up and stretch out again, as the lids open and shut. In old people it is thrown into numerous wrinkles. Because of the ease with which it is displaced, it is readily distorted by cicatrices in its vicinity, so that ectropion cicatriciale is produced. So, too, on account of the laxity of its attachment, it is very prone to be affected by extensive ecchymoses

* From *palpare*, to stroke.

and œdema. It is only in the neighborhood of the free border of the lid that the skin is closely united to the subjacent tarsus by rigid connective tissue. This free border of the lid forms a narrow surface which looks downward in the upper lid, upward in the lower lid (*r*, *r*, Fig. 19). When the lids are closed, these two surfaces are adjusted to each other with perfect accuracy, so that, with the assistance afforded by their lubrication with the secretion of the Meibomian glands, they are able to keep the lachrymal fluid in. When we open the lids forcibly in people affected with lachrymation and blepharospasm, we not infrequently see spurt from the eye a stream of tears which had been kept in by the closed lids—a proof that the closure of the lids is water-tight.

The lines along which the surfaces of the free border of the lids is reflected onto the anterior and the posterior surface, respectively, of the lid are called the anterior and posterior margins of the lids (Fig. 92, *v* and *h*); the narrow surface lying between them is the intermarginal strip. The anterior margin of the lid is rounded off, and has jutting from it the eyelashes (cilia), which are arranged in several rows one behind the other. The cilia upon the upper lid are larger and more numerous than upon the lower. The posterior margin of the lid, where the free border of the lid passes into the conjunctival surface of the latter, is sharp. Directly in front of it lies a single row of small puncta, the orifices of the Meibomian glands (*m*, Figs. 92 and 93). Between these and the cilia runs a fine gray line which divides the intermarginal strip into two parts (*i*, Fig. 93). The description here given of the structure of the lid answers for its whole extent as far inward as the spot where the punctum lacrimale is situated, a spot the position of which corresponds to the inner extremity of the tarsus (*p*, Fig. 93).

On everting the lids we get a view of their posterior surface, which is covered with the conjunctiva. This is intimately adherent to the tarsus, and, particularly in the upper lid, allows the Meibomian glands situated in the tarsus to show through clearly.

The *movements* of the lids are performed in the following way: In *opening the eye* the upper lid is raised by the levator palpebræ superioris, while the lower lid sinks by its own weight, although it does so but very little. Simultaneously with the elevation of the upper lid the skin of the lids, along the line corresponding to the upper border of the tarsus to which the skin is quite intimately adherent, is drawn far in between the eyeball and the upper margin of the orbit. In this way there is formed a furrow, over which the lax skin of the lid hangs down under the form of a fold (covering-fold, *d*, Figs. 19 and 92). In many cases this is so large as to reach down beyond the free border of the lid, and thus cause disfigurement (ptosis adiposa; see § 114). With regard to the *closure* of the lid, we must distinguish between moderate closure, such as takes place during the act of winking and in sleep, and the

process of screwing the lids tightly together. In the former the upper lid sinks by its own weight, while the lower lid is raised, although quite imperceptibly, by the orbicularis muscle. Contact of the free borders of the two lids does not take place throughout their whole extent



FIG. 92.—PERPENDICULAR SECTION THROUGH THE UPPER LID. MAGNIFIED 5×1.

The skin of the lid presents in the upper part, above a sulcus, the covering fold, *d*; below, it covers the anterior edge of the lid, *v*. In the skin are found fine hairs, *e*, *e*, sweat-glands, *a*, cilia, *c*, *c*, *c*, and in the neighborhood of the latter Zeiss's glands, *z*, and the modified sweat-glands, *s*. Beneath the skin lie the transversely divided bundles of fibers of the orbicularis, *o*, *o*, of which those placed most internally, *r*, *r*, form the musculus ciliaris Riolani. The posterior surface of the lid is covered by conjunctiva which at the fold of transition, *b*, shows an adenoid character, but over the tarsus, *t*, shows papillæ, especially where it corresponds to the convex border, *co*, of the tarsus. The Meibomian glands, *g*, have their orifices, *m*, in front of the posterior edge, *h*, of the lid; above them lie Waldeyer's mucous glands, *w*, and still higher Müller's musculus palpebralis superior, *p*, and the levator palpebræ superioris, *l*. From the latter the leash of fibers, *f*, passes to the skin of the lid. *as* is the arcus tarseus superior; *ai*, the arcus tarseus inferior; from the latter the rami perforantes, *rp*, run, at first straight downward, then backward, through the tarsus.

at once, but begins at the external canthus and keeps on taking place progressively toward the internal canthus. Because of this fact, the lachrymal fluid which the lids may be said to remove from the surface

of the eyeball is propelled along in the palpebral fissure, as it closes, toward the inner canthus, and thus arrives at the punctum lacrimale. When the lids become closed in sleep the eyeball also performs a movement, rolling upward. Any one, when he is fighting against sleep and his lids are shutting together, can feel that the eyes are being drawn up as by an invisible force. In persons with thin lids (women and children) we can recognize the convex cornea through the upper lid, and determine that it is directed upward beneath the closed lids. It is still easier to do this in cases of staphyloma of the cornea. This behavior on the part of the eyeball is important, inasmuch as the protection of the cornea by the upper lid is thus provided for, even when the palpebral fissure is not completely closed in sleep. It is not till lagophthalmus reaches quite a high degree that a portion of the cornea remains constantly visible in the palpebral fissure; and this portion is, in fact, always the lowest part of the cornea, which consequently is most exposed to the danger of undergoing desiccation (keratitis e lagophthalmo; see page 161).

The act of screwing up the eyes consists in this, that not only are the lids closed, but also the skin in the vicinity is drawn in toward the palpebral fissure, and is thus thrown into numerous folds.

Winking can be performed voluntarily, but usually results through reflex action, which is excited by the sense of dryness in the eye or by the presence of foreign bodies—dust, smoke, etc. It is produced by means of the trigeminus, which is the sensory nerve of the eye and its vicinity, and is hence rightly called the sentinel of the eye. The effect of winking is threefold: It covers the surface of the eyeball with a uniform layer of lachrymal fluid, and hence prevents its desiccation; it carries the dust away from the eye; and, lastly, it propels the lachrymal fluid toward the inner angles and into the puncta. Hence, interference with winking entails serious disturbance. Epiphora develops, since the tears, instead of entering the puncta, run over the border of the lower lid and down upon the cheek, and the cornea becomes diseased because it is neither properly moistened nor cleansed from the dust which falls upon it.

Dissection of the lids presents the following structural conditions: In the lids are found two voluntary muscles, the orbicularis (sive sphincter palpebrarum) and the levator palpebræ superioris. The *orbicularis* lies directly beneath the skin of the lid to which it belongs; it is nothing but a flat expanded cutaneous muscle which surrounds the palpebral fissure in the form of a circle. We can distinguish it in two portions, an internal and an external. The internal portion lies in the lids themselves, and is thence called the palpebral portion (portio palpebralis). Its fibers (*H*, Fig. 93) originate from the internal palpebral ligament, the *ligamentum canthi internum*. This is a firm, fibrous ligament (*l*) which is attached to the frontal process of the superior

maxilla (*F*), and lies directly beneath the skin of the internal angle of the eye. Hence, it is visible even in the living, especially in lean persons with thin skins, when the eyelids are drawn outward, as a consequence of which the internal palpebral ligament projects and bulges the skin forward. From the internal palpebral ligament the fibers of the palpebral portion run in arches over the anterior surface of the two lids, covering them from the free border of the lids to the margin of the orbit, and finally meeting at the outer side of the palpebral fissure. Here they partly unite with each other and partly are inserted into the external palpebral ligament (the *ligamentum canthi externum; le*, Fig. 93), which is here situated. The external portion of the orbicularis is the orbital portion (portio orbitalis). It lies outside of the palpebral portion, upon and in the vicinity of the margin of the orbit.

The palpebral portion moves only the lids themselves, and is the only part that comes into play in the ordinary act of winking as well as in the moderate closure of the palpebral fissure. The orbital portion contracts the skin in the vicinity of the lids, and thus makes it possible to squeeze or screw the lids firmly together, in which act, therefore, the entire orbicularis participates.

The *levator palpebræ superioris* arises at the bottom of the orbit from the circumference of the optic canal, and from this point runs forward, lying as it does so upon the superior rectus. Spreading out in the form of a fan, it is attached by means of a short tendon to the upper margin and the anterior surface of the tarsus of the upper lid (*l*, Fig. 92). Besides this striated levator muscle of the lid, there is also an organic muscle discovered by Heinrich Müller, and called the *musculus palpebralis superior*. The smooth fibers of this arise from between the striated fibers of the levator, along the under surface of which they too run to the upper margin of the tarsus (*p*, Fig. 92). An analogous bundle of smooth muscular fibers also exists in the lower lid, where it lies to the lower side of the inferior rectus, and is attached to the tarsus of the lower lid (*musculus palpebralis inferior* of Müller).

The orbicularis is innervated by the facial nerve, the levator by the oculo-motor nerve, and the two palpebral muscles of Müller by the sympathetic.

At the free border of the lids there are found, at a spot corresponding to the cilia, hair-follicles and the sebaceous glands (here called Zeiss's glands; *z*, Fig. 92) connected with them. Moreover, close to the margin of the free border of the lids, sweat-glands occur, the structure of which vary somewhat from that of the ordinary sweat-glands, for which reason they are designated under the name of modified sweat-glands or Moll's glands (*s*, Fig. 92). They empty into the glands of the ciliary hair-follicles.

The tarsus (*t*, Fig. 92) forms, so to speak, the skeleton of the lid, giving it rigidity of form and affording it firm support. The tarsus of



FIG. 93.—HORIZONTAL SECTION OF THE ORBIT. SCHEMATIC. MAGNIFIED 2×1.

the upper lid is broader (higher) than that of the lower. In the tarsus are distinguished a free and an attached (convex) border, and also an anterior and a posterior surface. The fibers of the orbicularis (*o*, Fig. 92) lie upon the anterior surface, while the posterior surface is covered by the conjunctiva. The two extremities of the tarsus are continuous with the external and internal palpebral ligaments. To the convex border of the tarsus is attached a fascia which runs from it to the margin of the orbit, and upon either side is connected with the palpebral ligaments (fascia tarso-orbitalis). Hence, when the lids are shut the orbit is closed in all over anteriorly by fibrous structures which together form the orbital septum, namely, the two tarsi in conjunction with the fascia tarso-orbitalis and the two palpebral ligaments.

The tarsus consists of fibro-cartilage, in which are imbedded the *Meibomian glands* (*g*, Fig. 92). These are elongated acinous glands, which, lying parallel with each other, traverse the tarsus from its attached to its free border. They are longest in the middle of the tarsus, where the latter attains its greatest height, and grow progressively shorter toward the edges of the tarsus. In their essential character the Meibomian glands are nothing but large sebaceous glands. Like the latter they secrete sebum, which lubricates the edges of the lids. By this the overflow of tears over the free border of the lids is hindered; the closure of the palpebral fissure is rendered water-tight; and, lastly, the skin of the border of the lid is protected from maceration by the tears. Acinous mucous glands are frequently found near the convex border of the tarsus (Waldeyer, *w*, Fig. 92).

In accordance with its anatomical structure, the lid can be readily divided into two parts. The anterior or cutaneous portion contains the skin, together with the cilia and also the fibers of the orbicularis. The posterior or conjunctival portion consists of the tarsus with the Meibomian glands and of the conjunctiva. The two portions are joined together simply by loose connective tissue, and can therefore be very readily separated from each other. For this purpose we only need to make a puncture in the gray line which runs between the cilia on the one hand and the orifices of the Meibomian glands on the other. The

---

Explanation of Fig. 93.—The nasal wall of the orbit is formed by the lamina papyracea (os planum) of the ethmoid, *L*, the lachrymal bone, *T*, and the frontal process, *F*, of the superior maxilla. The last two bones bound the fossa sacci lacrimalis, in which lies the lachrymal sac, *S*. The bony walls of the orbit are coated by a periorbita (periosteum), *P*, from which the palpebral ligaments take their origin. The internal palpebral ligament, *l*, divides into an anterior limb, *a*, and a posterior limb, *h*, which together inclose the lachrymal sac. From the posterior limb arise the fibers of Horner's muscle. *H*. *le*, external palpebral ligament; *fi* and *fe*, the slips of fascia, likewise originating from the periosteum, going to the internal rectus muscle, *I*, and the external rectus, *E*. The skin, *N*, of the dorsum of the nose passes into the lower lid, at whose free border are seen the cilia and the orifices of the Meibomian glands, *m*; between the two extends a gray line, *i*. At the inner extremity of the lid lies the inferior punctum lacrimale, *p*, and farther along in the conjunctival sac the caruncle, *c*, and the plica semilunaris, *n*. From the eyeball, the lower half of which is exhibited, the lens and along with it the vitreous humor have been taken out, and the pigment-epithelium has been removed by penciling. The anterior chamber, *k*, the iris, *ir*, and the ciliary body, consisting of the corona ciliaris, c_1, and the orbiculus ciliaris, *or*, are visible. Back of the ora serrata, *o*, is the choroid with its veins which are aggregated into vortices, *v*. *f*, fovea centralis retinæ; c_{11}, central vessels of the optic nerve, *O*, entering it at *e*.

division of the lid into its two layers forms an important part of many operations for trichiasis.

The *ligamentum canthi internum* requires a more precise description than that given above. It arises from the frontal process of the superior maxilla (*F*, Fig. 93) and first passes straight outward, skirting the anterior wall of the lachrymal sac (*S*). Then it bends back, winding about the anterior and external walls of the lachrymal sac, and runs backward to the crista lacrimalis posterior of the lachrymal bone (*T*). We accordingly distinguish in the internal palpebral ligament two branches, which meet at the point where it bends backward. The anterior branch (*a*) is situated directly beneath the skin, and hence is visible in the living subject; the posterior branch (*h*), which starts from the point of reflection and extends to the crista lacrimalis, can be brought to view only by dissection. The two branches together with the lachrymal bone (*T*) bound a space, triangular on cross-section, in which lies the lachrymal sac, the walls of the latter being united by loose connective tissue with the inner surface of the ligament. Into the external surface of the ligament are inserted the fibers of the palpebral portion of the orbicularis. One portion of the fibers of the latter springs from the anterior, another portion from the posterior branch of the ligament. The latter fibers, whose insertion is in part continued out beyond the posterior extremity of the ligament upon the inner wall of the orbit, are called *Horner's muscle** (*H*), after their discoverer. The insertion of the fibers of the orbicularis into the internal palpebral ligament is of significance for the conduction of tears. When these fibers contract, they draw up the ligament, and hence also draw up indirectly the wall of the lachrymal sac which the ligament incloses. By means of this the sac is dilated, and is thus enabled to draw the tears toward it by a sort of suction-process. This, then, is a factor which we must take into account in considering the part which the closure of the lids plays in the conduction of the tears.

The *ligamentum canthi externum* (*c*), Fig. 93) is neither as large nor as sharply defined as the ligamentum internum. It is represented simply by a rather pronounced accumulation of connective tissue in the substance of the orbicularis, a sort of inscriptio tendinea of the latter.

The fibers of the orbicularis fuse with the anterior surface of the tarsus. In the neighborhood of the free borders of the lid there are some bundles which lie near the inner margin of the lid, partly in front or partly behind the excretory ducts of the Meibomian glands (*musculus ciliaris Riolani* sive *subtarsalis*; *r*, *r*, Fig. 92).

The *blood-vessels* of the upper lid arise from two arterial arches, the arcus tarseus superior and inferior (*as* and *ai*, Fig. 92), which run along the upper and lower margins of the tarsus. From them fine twigs are given off to all parts of the lid. The most vascular portions are the free border of the lid and the conjunctiva (cf. page 32).

The veins of the lids are still more numerous and of wider caliber than the arteries. They form, beneath the upper and lower folds of transition, a thick plexus, which even in the living subject can be seen in this situation shining through the conjunctiva of the fornix when the lid is everted. The veins of the lids in part empty into the veins of the forehead, in part into the branches supplying the ophthalmic vein. The latter set, in order to reach to

* [The tensor tarsi of many anatomists.—D.]

the veins of the orbit, must pass between the fibers of the orbicularis. Hence, permanent contraction of the orbicularis, such as occurs in blepharospasm, may lead to engorgement of the veins, and consequently to œdema of the lids, a result which, in fact, we very frequently observe, especially in children with conjunctivitis lymphatica and coincident blepharospasm.

The *lymphatic vessels* of the lids are abundant, especially in the conjunctiva. Furthermore, lymph-spaces of larger size (periacinous spaces) are found about the acini of the Meibomian glands. The lymphatic vessels of the lids run to the lymphatic gland situated in front of the ear, which, consequently, is not infrequently found to be swollen in affections of the conjunctiva (particularly in conjunctivitis lymphatica and acute blennorrhœa).

That part of the cornea and of the scleral conjunctiva which ordinarily is not covered by the lids is called the *interpalpebral zone*. Since in this situation the eyeball is deprived of the protection of the lids, it is particularly exposed to many sorts of disorders, and it is therefore important to know its situation. This situation changes according to circumstances, namely, in the following way: 1. In the ordinary way of looking the interpalpebral zone comprises the entire cornea, with the exception of its extreme upper part, and a corresponding large triangular area of the conjunctiva on both sides of the cornea. 2. When the eyes are a little screwed together—e. g., when we are walking in the face of the wind or rain or in the midst of smoke—the interpalpebral zone diminishes in size, and at the same time is depressed so as to occupy the lower half of the cornea. The lower lid is raised a little and covers the extreme lower part of the cornea, and the upper lid drops a good deal, so that its border lies only a little above the center of the cornea. Then the interpalpebral zone forms upon the cornea a zone from four to six millimetres in breadth which occupies the lower half of the cornea, with the exception of its extreme lower part, and with which there is connected on either side a very small triangle of scleral conjunctiva. The interpalpebral zone as thus defined is the part which more than any other is constantly exposed to external injuries. Hence, in many men we find this portion of the scleral conjunctiva somewhat injected all the time, and later on in life we find it occupied by the pinguecula. In this spot are developed pterygium, zonular opacity of the cornea, and xerosis of the conjunctiva and cornea. In inflammations of the conjunctiva this division of the latter is frequently distinguished by being somewhat more swollen than the rest, or it may even protrude into the palpebral fissure under the form of a transversely placed, very œdematous swelling. 3. When the eye is turned upward in sleep the interpalpebral zone is displaced upon it, so as to occupy mainly the scleral conjunctiva beneath the cornea, and at most the extreme lower portion of the latter. Affections within the confines of the interpalpebral zone as thus defined are found when the palpebral fissure is kept open during sleep, and hence mainly in lagophthalmus, in which the conjunctiva beneath the cornea is found injected or œdematous, and in which, when the affection is of greater extent, the lowermost division of the cornea also suffers damage. The same turning upward of the eyeball that occurs in sleep takes place also upon the approach of anything endangering the eye, for which reason injuries by burns and caustic substances affect principally the extreme lower portion of the cornea.

I. Inflammation of the Skin of the Lids.

107. In the skin of the lids we find almost all those diseases which appertain to the skin in general. With regard to them, therefore, reference must be made to the text-books on skin diseases. In this place affections of the skin of the lids will be considered only so far as they are of comparatively frequent occurrence in the lids, or when, in consequence of the peculiar anatomical structure of the latter, they present some special features in their course and their results.

1. Exanthemata.

Among the *acute* exanthemata *erysipelas* must be mentioned first. If this attacks the skin of the face, the lids participate very markedly in the inflammation, so that they are very greatly swollen, and the patient for several days together can not open his eyes. Not infrequently the erysipelatous process penetrates under the guise of a phlegmonous inflammation into the deeper parts, so that abscesses are produced in the lids or even in the orbit itself. In the latter case, implication of the optic nerve may occur, and, by transmission of the suppuration to the cranial cavity, meningitis may take place and lead to a fatal issue.

Herpes zoster is an affection of the skin which consists in the formation of vesicles along the terminal expansions of a nerve. Among the cerebral nerves the trigeminus is the one in whose area of distribution this affection occurs. The efflorescences are then found in the vicinity of the eye, for which reason herpes of the trigeminus is known as herpes zoster ophthalmicus or zona ophthalmica.

Violent neuralgic pains in the course of the trigeminus usually precede for some days the outbreak of herpes. Then the exanthem makes its appearance, with accompanying febrile symptoms—vesicles, which for the most part are arranged in groups, starting up upon the reddened skin. The vesicles most frequently occupy the region of distribution of the first branch of the nerve, so that they are found upon the upper lid, upon the forehead as far as the scalp, and also upon the nose. When the district supplied by the second branch of the trigeminus is affected, the vesicles are situated upon the lower lid, over the superior maxillary region as far down as the upper lip, and over the region of the malar bone. Sometimes the terminal expansions of both branches are affected simultaneously, while it is extremely rare for the region of the third branch to be involved.

At first the vesicles contain a limpid fluid, which soon becomes cloudy and purulent, and finally dries up into a crust. If this is removed, an ulcer is found beneath it, a proof that the suppuration has penetrated into the corium. After the ulcer heals, cicatrices remain which are visible during the whole life, and by their characteristic

arrangement render it possible to diagnosticate the previous existence of a herpes zoster even years afterward. By this formation of cicatrices the vesicles of herpes zoster are distinguished from those of herpes febrilis, in which the epidermis alone is detached by the fluid, so that they heal without leaving any trace of their existence behind (see page 169).

The affection of the skin is very frequently complicated with an analogous affection of the cornea, upon which small vesicles likewise form. By the presence of such a complication the prognosis of herpes zoster is rendered essentially worse; for, while in uncomplicated cases the disease entails no bad consequences further than the small cicatrices upon the skin, it not only lasts much longer when the cornea is implicated, but also often leaves behind permanent corneal opacities.

An inflammatory affection of the trigeminus, which is located either in the trunk of the nerve itself or in the Gasserian or ciliary ganglion, lies at the bottom of herpes zoster ophthalmicus. By what means the inflammation of these structures is produced remains in most cases unknown.

The treatment of herpes zoster is purely symptomatic. We avoid opening the vesicles, as by doing so the raw surface of the skin would be exposed and pain would be excited. To prevent this we sprinkle the affected spots with dusting powder (rice-starch) which causes the vesicles to dry up into crusts, beneath which the ulcers can heal undisturbed. The affection of the cornea is to be treated according to the ordinary rules. For the affection of the nerve itself the internal administration of salicylic acid is said to be of service (Leber).

Among the *chronic* exanthemata affecting the lids, *eczema* is the most frequent. It is found particularly under the form of moist eczema in children, when it is given the name of crusta lactea (milk-crust, tetter). In children it forms the most frequent concomitant of conjunctivitis lymphatica. The connection between the eczema and the conjunctivitis is either that the two owe their origin to the same disease, scrofula, or that the eczema is the result of the conjunctival affection; for, as the latter is associated with profuse lachrymation, the lids are kept constantly moist with the overflowing tears, and thus become eczematous. Moreover, children have the habit of rubbing the eyes with the hands, and by means of this the whole vicinity of the eye is made wet with the lachrymal fluid. A similar eczema due to a permanent wetting of the skin also occurs frequently in adults when they suffer from epiphora in consequence of catarrh, blennorrhœa of the lachrymal sac, or ectropion; the eczema is then localized upon the lower lid.

Eczema requires treatment, both upon its own account and also because of any conjunctivitis lymphatica that may chance to be present. The progress of the latter to a cure is distinctly more rapid if the eczema is at the same time done away with; contrary to the popular belief,

which is prone to assume the opposite. (We often hear the complaint made that "the eruption which the physician has driven from the skin has struck into the eye.") Treatment is usually carried on by means of ointments, of which Hebra's diachylon-ointment, or ointments of oxide of zinc or of white precipitate (one to two per cent), are the ones generally selected. The ointments are spread thickly upon a pledget of linen, which is laid upon the closed lids and retained in place by a bandage. In extensive eczema the entire face may be covered with a linen mask smeared with ointment on the inside. Another efficient method of treatment consists in the application of a five to ten per cent solution of nitrate of silver (see page 91).

At the border of the lids eczema, being modified by the peculiar anatomical structure of this region, appears under a special form, and will receive a separate description later on as blepharitis ciliaris.

2. Phlegmonous Inflammations of the Lids.

Under this head belong: 1. *Abscesses of the lids.* These originate most frequently after injuries. In other cases the affection starts from the bones; periostitis and caries of the margin of the orbit lying at the root of it. This is especially apt to be the case in scrofulous children, in whom, moreover, the carious disease of the margin of the orbit is frequently referable to injury. Lastly, erysipelas not infrequently gives rise to abscesses of the lids if the inflammation penetrates from the skin into the deeper parts. 2. *Furuncles and carbuncles*, which, however, are of comparatively infrequent occurrence in the lids. 3. *Anthrax pustule* (malignant pustule). This arises through a transfer, by a process of inoculation, of the poison of anthrax (the Bacillus anthracis) from animals affected with anthrax to man. It is hence most frequently found in those persons who have to do with animals or the products obtained from them, e. g., in hostlers, shepherds, graziers, butchers, tanners, and furriers. In the Vienna clinics most of these patients come from Hungary. The disease often terminates fatally.

The symptoms of the phlegmonous processes in the lids are marked inflammatory œdema and indurated infiltration in the skin of the lid or beneath it. With this are associated swelling of the lymphatic glands in front of the ear and near the lower jaw, and fever and prostration. In the after-course of the disease disintegration of the infiltrated portions of the skin takes place, or, if we are dealing with an abscess, softening of the infiltrate sets in, with escape of the pus externally by its breaking through the skin. Not infrequently extensive gangrene of the skin of the lids occurs. The result of this is cicatricial shrinking of the lid in the course of healing and its consequent contraction, so that lagophthalmus or ectropion is produced. In both erysipelas and malignant pustule it is not uncommon for both lids to be affected by the destructive process. This latter presents the pecul-

iarity that even when it is of great extent it leaves exempt the free borders of the lids together with the cilia that they bear. This exemption is perhaps to be ascribed to the fact that of all portions of the lids the free border is most abundantly supplied with blood-vessels, and hence less readily falls a prey to necrosis. The preservation of the border of the lid is a very favorable circumstance for those cases in which a plastic operation upon the lids afterward becomes necessary, since the border of the lids can be used to skirt the edge of the implanted flap with.

Treatment follows the general rules of surgery. In abscesses of the lids an incision should be made as early as possible (that is, as soon as we are able to make the diagnosis), in order to prevent the extension of the suppuration into the deeper parts (orbit and meninges). When the skin of the lids is destroyed by inflammation, it is our business to strive to prevent as far as possible the subsequent contraction of the lids due to cicatrization. In large losses of substance in the lids it is best to refresh the edges of the two lids in isolated spots and unite them by sutures. As long as the palpebral fissure is kept closed in this way, lagophthalmus can not develop, and the cicatrix that forms is broader. It is also advisable in such cases to graft bits of skin upon the granulating surface of the injured lids. If in spite of these measures, such a considerable contraction takes place, that lagophthalmus or ectropion is caused by it, the skin which has been destroyed must be replaced by blepharoplasty.

3. Ulcers of the Skin of the Lids.

Ulcers are produced partly as the result of injuries (burns, the action of caustic substances, and contusion), partly spontaneously. Among ulcers of the latter kind are scrofulous, lupous, and syphilitic ulcers. In children scrofulous ulcers are found not infrequently in conjunction with caries of the adjacent bone. Lupus is likewise of frequent occurrence in the lids, usually migrating to them from the neighboring regions (nose or cheek). From the lids it may pass over to the conjunctiva and even to the eyeball; and so, when lupus of the face has lasted for a long time, considerable changes in the lids and eyeballs are often found, which may even produce complete blindness.

After the subsidence of *herpes zoster*, anomalies in the function of the trigeminus often remain; anæsthesia or neuralgia, or both combined, persisting for a long time in the area supplied by the affected branches. The cornea, which even while the inflammation is still present is less sensitive than normal, usually retains this condition of diminished sensibility for a long time. The two following phenomena likewise must be referred to alterations in the nervous influence: The first consists in the abnormally low tension which the eyeball frequently shows when it participates in the inflammation; the second is the striking elevation of temperature of the skin upon the affected side, which

not only occurs while the inflammation is recent, but often lasts for quite a long time afterward.

The cornea may be implicated in various ways in herpes zoster. In the first place, it may be implicated through the breaking out upon it of herpes vesicles, from which quite large ulcers may develop. In other cases deep parenchymatous infiltrates may form which are very slow in disappearing; in other cases again iritis and irido-cyclitis may develop. The cornea may also be affected indirectly, in that a paralysis of the trigeminus remains, and as a consequence of this a keratitis neuro-paralytica is set up. Then I have seen two cases in which herpes was complicated with facial paralysis, and, as a result of the latter, a keratitis e lagophthalmo developed. Paralysis of the oculo-motor nerve also occurs in consequence of herpes zoster.

From what has been said, herpes zoster is to be looked upon as a serious disease, which in some few cases has actually caused death. Refrigeration, the use of arsenic, and poisoning by carbonic-oxide gas, have been observed as causes of herpes zoster, but in most cases all clew to the etiology is wanting.

Eczema of the lids is not infrequently artificial—that is, is caused by the application of irritant ointments, by compresses, or by moist dressings. It hence often arises as an unpleasant complication when there is a necessity of keeping an eye for a long time beneath a bandage. Adhesive plaster, too, such as is employed in bandaging the eyes, excites eczema in many persons.

In adults, eczema squamosum sometimes occurs as a chronic affection of the skin of the lids.

Elephantiasis affects the lids under the form of a monstrous thickening, especially pronounced in the upper lid which hangs down over the lower and upon the cheek, and which, on account of its weight, can not be raised, and thus renders vision with the eye so covered impossible. The treatment consists in excision of the skin to a sufficient extent for the lid to regain approximately its normal dimensions.

Under the name of *chromidrosis* * is denoted that rare affection in which the sweat from the skin of the lids is colored. As a result of it, blue spots come out upon the lids, which can easily be wiped away with a cloth that has been dipped in oil, although in a short time they make their appearance again. This disease is said to occur especially in women. A large number of the known cases must probably be referred to simulation—i. e., to the intentional application of some blue coloring matter to the lids.

Œdema of the Lids.—Œdema of the lids is, of course, not a disease but only a symptom, yet as such it is so frequent and at the same time so conspicuous that it deserves quite a detailed description. Its development is favored in a very great degree by the anatomical structure of the lid (see page 459); hence it is found not only in connection with every violent inflammation of the lids themselves or of the neighboring parts, but also in consequence of simple venous congestion. In the former case we are dealing with *inflammatory œdema* (œdema calidum), in the second case with a *non-inflammatory œdema* (œdema frigidum). As long as the œdema is on the increase, the skin of the lid is found to be smooth and tense; but as soon as the œdema begins to decrease, this is at

* From χρῶμα, color, ἵδρωσις, sweating.

once made manifest by the formation of minute wrinkles in the skin of the lid—a phenomenon which is therefore of value as affording evidence that the process has already passed its acme (as, for instance, in acute blennorrhœa).

Œdema of the lids often causes the patient more alarm than does the lesion which lies at the bottom of it, because he can not open the swollen eye, and hence can not see with it. And for the less experienced physician marked œdema presents difficulties, inasmuch as it hinders the accurate inspection of the eyeball. If, in consequence, the physician gets but a transient view of the eye, or no view at all, he may easily make a false diagnosis, and may cause the patient great anxiety for what is perhaps an insignificant affection. For the benefit of the general practitioner, therefore, those affections which are associated with œdema of the lids will be enumerated in the following lines, and at the same time the symptoms will be given from which the diagnosis can be made. The first thing to be done is to open the lids sufficiently in spite of the œdema, for which purpose we may with advantage use Desmarres's elevator, especially in the presence of marked swelling or violent blepharospasm. If, then, the conjunctiva is found either not reddened at all or but slightly injected, and the eyeball itself is normal, not protruding, and freely movable, we are dealing with a superficial affection; in other cases we recognize from the abnormal character of the conjunctiva or the eyeball that the œdema must be referred to an affection of the deeper parts.

(A) ŒDEMA IN CONSEQUENCE OF A SUPERFICIAL AFFECTION.

It is necessary first to determine whether what we have before us is an inflammatory or a non-inflammatory œdema. The former is distinguished from the latter by the redness, the increased temperature, and not infrequently also by the sensitiveness to touch. Let us assume that we are dealing with an inflammatory œdema. In order to find out what affection lies at the bottom of it, we now try to ascertain whether in palpating the swollen part we do not come upon some one spot which is distinguished by greater induration and special painfulness.

1. If such a spot is found close to the free border of the lid, we are usually dealing with a *hordeolum*. In the very inception of this affection nothing besides the above-mentioned symptoms are noticeable. But, in the days immediately following, a yellowish point of discoloration is discovered either between the cilia, or, if we are dealing with a Meibomian stye, upon the inner surface of the lid.

2. If the indurated and sensitive spot occupies the internal angle of the eye, our first thought must be of an acute inflammation of the lachrymal sac—a *dacryocystitis*. This diagnosis is confirmed if, upon pressure in the region of the lachrymal sac, pus is evacuated from the puncta, or if the patient says that epiphora has for a long time preceded the inflammation. To be sure, a furuncle or a periostitis may also develop in the region of the lachrymal sac, but these cases, in comparison with the frequently occurring dacryocystitis, are extremely rare.

3. In *erysipelas* the redness and swelling of the lid are uniform. The skin itself when grasped between the fingers feels thicker and harder; while, on the other hand, circumscribed infiltration is absent. The swelling, as a rule, occupies both lids and also extends to the neighboring parts; and when we have had the case under observation for some time, we can see that the swelling

migrates. If in the course of the inflammation an induration develops which can be felt to be deeply seated, it is a proof that the process has penetrated into the deeper tissues, and that an abscess of the lid is forming.

Cases of erysipelas sometimes occur which are very slight in intensity and extent, and present correspondingly insignificant inflammatory symptoms. Then only the lids themselves, and perhaps the dorsum of the nose, too, are swollen; these parts are not tense but of doughy consistence, and are scarcely reddened; and fever and pain are absent. The swelling disappears within a few days, and the skin then peels off. In light cases of this sort it is often hardly possible to make the diagnosis of erysipelas with certainty. Many of the puzzling cases of recurrent œdema of the lids probably belong in this category.

4. In œdema of the lids due to a *furuncle* or a *malignant pustule* there is felt, contrary to what takes places in erysipelas, a circumscribed, indurated, and painful nodule of considerable extent in the skin of the lid itself; while, if the infiltration lies deep in the tissues, we are dealing with a commencing *abscess* of the lid. In *periostitis* of the margin of the orbit the latter can be felt through the œdematous lid, and it is then found to be not sharp, but thickened and enlarged, and tender to the touch.

5. Œdema of the lid due to *traumatism* is almost always accompanied by extensive hæmorrhagic suffusion of the lid, and from this fact can readily be recognized. If œdema of the lid develops in consequence of the sting of an insect, it is easy to make the diagnosis when we are able to discover the site of the sting.

Non-inflammatory œdema is met with as one of the symptoms of general œdema, as, for example, in heart-disease, in hydræmia, and in nephritis. Not infrequently the lids are the very first part of the body in which these varieties of œdema show themselves, and thus give warning of the causal disease. In such cases the œdema of the lids sometimes appears under the guise of flying œdema (œdema fugax)—i. e., it comes suddenly and disappears again within a few days or even a few hours, only to return after a short interval of time.

A variety of œdema holding an intermediate position between the inflammatory and the non-inflammatory kinds, is that which is observed in connection with blepharospasm that has lasted a long time (especially in children with conjunctivitis lymphatica). This chiefly affects the upper lid, and is mainly referable to the compression of the palpebral veins by the contracted orbicularis (see page 467).

Finally, œdema of the lids both of inflammatory and non-inflammatory nature occurs, for which no cause whatever can be discovered.

(B) ŒDEMA DUE TO DEEPER AFFECTIONS.

1. Among affections of the *conjunctiva*, those which are associated with œdema of the lids are acute blennorrhœa and diphtheria, less frequently a violent catarrh, or, as above stated, a conjunctivitis lymphatica. The diagnosis is easily made, from the appearance of the conjunctiva and from the character of the secretion.

2. Violent *inflammations in the interior of the eyeball* lead to œdema of the lids; severe irido-cyclitis and acute glaucoma doing so to a less extent, *panophthalmitis* to a more considerable degree. In the latter disease, as in acute blennorrhœa, chemosis is also present. A confusion between the two diseases can, however, be readily avoided; since in panophthalmitis the purulent secretion in

the conjunctiva is wanting, while a purulent exudate is visible in the interior of the eye (in the anterior chamber or in the vitreous). An important differential sign is the protrusion of the eyeball and the consequent diminution in its mobility in panophthalmitis, symptoms which are never present in acute blennorrhœa.

3. *Tenonitis, phlegmon of the orbit,* and *thrombosis of the cavernous sinus,* share with panophthalmitis the symptoms of œdema of the lids, chemosis, and protrusion and immobility of the eyeball. These affections might hence be confounded with each other and with panophthalmitis. From the latter, however, they are at once distinguished by the fact that in all three the eyeball itself, except for the œdema of the conjunctiva, looks normal in its anterior portion, while in panophthalmitis the suppuration in the interior of the eye is visible. The differential diagnosis between the three affections first named is rather more difficult. Serous tenonitis and phlegmon of the orbit are very similar to each other at their commencement, but in the former the chemosis and also the impairment of mobility of the eyeball are very considerable, and the protrusion of the eyeball is comparatively slight; while in the latter, on the contrary, the œdema of the conjunctiva is not very great in comparison with the extreme protrusion of the eyeball, and is not uniform, but is principally developed in the region of the palpebral fissure. In phlegmon of the orbit the fever and pain attain a much greater pitch. Later in the course of the two diseases their differentiation becomes more and more easy. In serous tenonitis all the symptoms soon abate, while in phlegmon of the orbit they constantly increase until the pus breaks through and is evacuated.

Thrombosis of the sinus is distinguished from both affections by the fact that along with the œdema of the lid there is also œdema behind the ear in the mastoid region, and also by the fact that serious cerebral symptoms are present.

A *tumor* developing in the depth of the orbit may also, along with the protrusion of the eyeball, cause œdema of the lid due to congestion. In this case, however, inflammatory concomitants are either slight or are absent altogether.

II. Inflammation of the Border of the Lids.

108. The free border of the lid is simply a part of the skin of the lid, which, however, is distinguished by many anatomical peculiarities, such as its cilia with their hair-follicles and glands, its particularly abundant vascular supply, etc., so that its diseases bear a special stamp. Affections of the borders of the lids are among the most frequent of all diseases.

Hyperæmia of the border of the lid manifests itself by the reddening of it, so that the eyes look as if they had a red fringe. It occurs in many people in consequence of insignificant causes of injury, such as prolonged weeping, great straining of the eyes, the being in vitiated air, a wakeful night, etc. This is especially true of persons with a delicate skin, who at the same time have a light complexion and blonde or reddish hair. In many of these persons the hyperæmia of the lids is present all the time, and sometimes lasts for their whole life. With respect to the troubles that it causes, and also with respect to its

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

treatment, the same statements hold good that will be made in this regard in speaking of blepharitis.

Inflammation of the border of the lids (blepharitis ciliaris or blepharo-adenitis*) appears under the two following principal forms:

1. *Blepharitis squamosa.* In this the skin between the cilia and in their vicinity is covered with small white or gray scales like the dandruff upon the scalp, or, as some have said, the border of the lids looks as though strewn with bran. If the scales are removed by washing, the skin beneath them is found to be hyperæmic but not ulcerated. Upon removing the scales, some cilia usually fall out—a proof that they are less firmly attached than usual; but, as their follicles are not injured, they grow again afterward.

A sub-variety of blepharitis squamosa, which is of less frequent occurrence, appears under the following form: The border of the lids is covered with yellow crusts, which are sometimes rigid, sometimes flexible and fatty (like wax or honey). When they are removed, no ulcers are found beneath them, but simply reddening of the skin of the lid. The yellow crusts are therefore not inspissated pus, but simply the excessively abundant secretion of the sebaceous glands, which has solidified in the air into yellow crusts.

2. *Blepharitis ulcerosa.* In this form also the border of the lid is covered with yellow crusts; but, after washing them off, we find not merely a hyperæmia of the skin but ulcerative processes as well. Thus we see here and there in spots small yellow elevations, from the center of which rises a cilium. These are abscesses, which have originated from suppuration of a hair-follicle and of the sebaceous gland belonging to it. With these we find little excavations—that is, ulcers which have been formed out of small abscesses that have opened. Again, in other spots we notice small cicatrices, the remains of similar ulcers. At the site of the cicatrices the cilia remain deficient, because their hair-follicles have been destroyed by suppuration. Since new hair-follicles are constantly being transformed into abscesses one after another, the row of cilia, when the process has kept up for a long time, becomes more and more thinned out; the cilia that are still present are arranged in separate groups, which for the most part are glued together into tufts by the dried secretion. Blepharitis ulcerosa, accordingly, is distinguished from blepharitis squamosa by its deeper situation and the purulent character of the inflammation. It is hence to be regarded as the more serious of the two forms, the one in which both the inflammatory symptoms are more pronounced, and permanent sequelæ, particularly destruction of the cilia, remain.

The *annoyance* suffered by the patient is slight in the lightest cases of blepharitis, so that many patients visit the physician more on account

* From βλέφαρον, lid, and ἄδην, gland; i. e., inflammation of the glands of the lid.

of the disfigurement due to the reddened border of the lids than on account of any distress they experience. But in most cases the patients are annoyed by the increased sensitiveness of the eyes, which water readily, especially during work and in the evening, are sensitive to light, heat, and dust, and become tired quickly. In the morning the lids are stuck together.

Blepharitis is distinguished by its eminently chronic *course*, which often extends over a series of years. In young patients the disease often disappears of itself when they grow up; in others it continues during the whole life. Proper treatment always produces considerable improvement, or even effects a cure, which latter, however, is in most cases not lasting, as after the discontinuance of the treatment the disease usually returns; a permanent cure is obtained in only a few cases.

After lasting some time blepharitis entails a series of sequelæ, which to a certain extent react in their turn upon the blepharitis and render it worse. These are—

1. *Chronic conjunctival catarrh.* This is the constant concomitant of blepharitis, the annoyance produced by which is in no small part dependent upon it.

2. Blepharitis ulcerosa leads to permanent *destruction of the cilia*, which may go on till nearly all the cilia are lost. In that case there are found upon the border of the lid a few scattered, minute, and abortive hairs. This condition, called *madarosis*, * produces marked disfigurement. As soon as all the cilia are destroyed, the blepharitis ceases of itself, as there are no longer any hair-follicles to undergo suppuration.

3. By the traction produced by cicatrices which remain after suppuration of the hair-follicles, neighboring cilia may be given a false direction, so as to turn backward toward the cornea (*trichiasis*).

4. *Hypertrophy* of the border of the lid may develop in consequence of its being constantly congested and swollen by inflammation. The lid is then found to be thicker and more misshapen at its free border, and drooping in consequence of its weight (*tylosis* †). This change affects mainly the upper lid.

5. The lower lid very often undergoes, as a result of blepharitis, a change of position under the form of *ectropion*. This develops in the following way: Owing to the formation of the cicatrices, the conjunctiva is drawn a little forward over the border of the lid. The border of the lid then looks as if it had a rim of red conjunctiva about it, and the posterior margin of the lid, which before was sharp, is now rounded off, and can no longer be distinctly made out. In consequence of this

* From μαδᾶν, to melt away, to fall off.

† From τύλος, a callous spot.

change of form, the borders of the two lids no longer fit exactly to each other when the latter are shut together. Furthermore, on account of the absence of its sharp posterior margin, the lid is no longer perfectly applied to the eyeball, and a shallow groove remains between the eyeball and the border of the lid (*eversion of the border of the lid*). In common with the border of the lids, the puncta are also turned forward so as no longer to dip into the lacus lacrimalis (*eversion of the puncta*). Owing both to the imperfect closure of the lids in winking and also to the eversion of the puncta, the conduction of tears into the lachrymal sac is interfered with, so that epiphora develops. A portion of the tears runs down over the lower border of the lid upon the skin of the latter, which because of this continual wetting becomes reddened, excoriated, and even eczematous; consequently it loses its pliability and becomes gradually contracted. In this way the lower lid is drawn farther and farther away from the eyeball, so that an ectropion of the entire lid is gradually developed from the eversion of its border. At the same time the lachrymation also constantly increases, and this in turn reacts injuriously upon the blepharitis, the border of the lid being irritated to the point of inflammation by the tears which are constantly flowing over it.

Etiology.—The causes of blepharitis are either of a general or a local nature.

The *general causes* lie partly in the constitution of the patient, partly in external injurious influences. In the first category are to be mentioned anæmia, scrofula, and tuberculosis, which particularly in children and young people furnish a frequent cause of blepharitis. When with increasing age the constitution improves, the blepharitis also disappears. In many families blepharitis is hereditary, being a kind of family disease. Among external injurious influences are to be considered all those which are known to be also causes of chronic conjunctival catarrh (see page 45). Among these belong vitiated air, smoke, dust, heat (for example, in the case of stokers), staying up late at night, etc. Blepharitis produced by general causes is always bilateral.

Among the *local causes* of blepharitis the most frequent are chronic inflammations of the conjunctiva (chronic catarrh, conjunctivitis lymphatica, and trachoma) and lachrymation. The latter excites inflammation of the border of the lid by keeping it continually wet. The lachrymation may be caused either by increased secretion of tears or by interference with their discharge into the nose. The former is the case, for example, in conjunctivitis lymphatica, which is characterized by profuse lachrymation. Since in this case the inflammation of the conjunctiva and the scrofulous diathesis of the patient both act at the same time to favor the development of blepharitis, it is easy to understand why conjunctivitis lymphatica should so exceedingly often be found combined with blepharitis.

Lachrymation may, however, also be produced by interference with the conduction of tears, as a result, for instance, of an affection of the lachrymal sac; in this case the blepharitis is found only in that eye in which the affection of the lachrymal sac exists. Hence the rule is in unilateral blepharitis to examine the lachrymal sac at once, just as, on the contrary, in bilateral blepharitis, we shall first have to look for a general cause for it. Other causes of interference with the conduction of tears, and hence also of blepharitis, are imperfect closure of the lids due to ectropion, to paralysis of the facial nerve, to congenital and acquired contraction of lids, etc.

The *treatment* of blepharitis must take account both of the causal indication and also of the local changes. Regard to the causal indication requires the improvement of the patient's constitution and of the hygienic conditions under which he lives. In most cases, it is true, the object aimed at can not be attained, owing to external circumstances. Local causes of blepharitis, such as lesions of the conjunctiva and the lachrymal sac, lagophthalmus, etc., are to be removed as far as possible. In the treatment of the diseased borders of the lids themselves ointments play the chief part. Their action is to be principally attributed to the fat they contain. This softens the scales and crusts and thus facilitates their removal, and also prevents the occlusion of the orifices of the palpebral glands; it renders the skin more pliable, and protects it from being wet by the overflowing tears. Hence some soft, pliable fat, the unguentum emolliens [cold cream] or vaselin, must be chosen as the basis of the ointment. For the additional ingredient of the ointment, a mercurial precipitate is most frequently selected, the red, yellow, and white precipitates all being employed. Since the ointment ought not to irritate the already inflamed border of the lid, the white precipitate [ammoniated mercury], as being the mildest, is to be preferred to the yellow and the red precipitates [red and yellow oxides]. For the same reason it is advisable to add it in small quantities only (one to two per cent to the fat). The patient applies the precipitate ointment by rubbing it upon the closed eyelids with his fingers before going to bed. On the following morning, after the ointment is wiped off, the crusts and scales adhering to the border of the lids must be removed as carefully as possible by washing with lukewarm water. The physician must insist very particularly upon this point, since the act of cleansing the lids is often painful, and hence, especially in children, is frequently not performed with sufficient care. When by means of this treatment we have finally succeeded in bringing the borders of the lids back to their normal state, we continue the use of the salve for some time longer, as otherwise the blepharitis will very soon recur.

In blepharitis ulcerosa, in addition to the employment of the ointment, the abscesses which form must be opened every day, and the cilia

which project from them must be epilated. For this purpose we make use of the cilium-forceps—that is, of a forceps with broad rounded ends. The healing of the ulcers can be accelerated by touching them lightly with a pointed stick of nitrate of silver.

Since the border of the lids is simply a modified portion of the external skin, it would be proper to consider the affections of it from the *dermatological* standpoint—that is, to compare them with analogous affections of the skin. From this point of view blepharitis squamosa might be regarded as seborrhœa. That form which is associated with furfuraceous scales would correspond to seborrhœa squamosa or seborrhœa sicca of the skin, which we most frequently observe, under the guise of increased formation of scales, upon the scalp. The form of blepharitis squamosa which is characterized by yellow, fatty crusts, is probably identical with the seborrhœa oleosa, which is likewise found upon the scalp, particularly in children, and in this situation is known under the names of scurf or scall. Blepharitis ulcerosa is probably nothing but an eczema which, on account of the hairy character of the border of the lid, is associated with suppuration of the hair-follicles, such as is the case in other hairy portions of the skin (eczema sycomatosum). If the position of blepharitis in the system of skin-diseases, as it is here put down, was really placed beyond a doubt, it would certainly be justifiable to let the old designations and subdivisions of blepharitis drop out altogether and replace them by the dermatological terms. Unfortunately, we have not yet got as far as this. Thus, different authors have been unable as yet to come to an agreement in regard to the significance of blepharitis ulcerosa. Horner considers it as eczema, Stellwag as acne, Michel sometimes as eczema, sometimes as sycosis. Accordingly, I consider it better, as long as a perfectly clear light has not been thrown upon the question, to retain the old designations, whose meaning every one knows.

For the correct diagnosis of blepharitis the crusts covering the border of the lid must be removed, in order to determine the state of the skin beneath them. If the skin beneath the crusts is normal, we are not dealing with blepharitis at all, but with a disease of the conjunctiva, the dried secretion from which forms the yellow crusts. In blepharitis the skin is at least found to be reddened (in blepharitis squamosa), or it is covered with ulcers (in blepharitis ulcerosa). In the vicinity of the ulcers the skin of the palpebral border is not infrequently thickened by hypertrophy of the papillæ, so that warty excrescences are formed, which are painful and bleed readily, and which must be removed.

In the *treatment* of blepharitis the mistake is very frequently committed of prescribing highly irritant ointments, by which the inflammation is simply aggravated. I therefore prefer the one-per-cent ointment of white precipitate, as being the mildest of all. If we select as the basis of the ointment the unguentum emolliens, which I regard as the best for this purpose, we must take care that the ointment is prepared fresh from time to time, as otherwise the fat would become rancid and cause irritation. In severe cases of blepharitis ulcerosa it is advisable to smear the ointment thickly upon a pledget of linen and apply it overnight to the eyes by means of a bandage. In this way the ointment acts in a much more penetrating way than if it were merely smeared upon the borders of the lids. This procedure is particularly indicated when the blepharitis is caused by congenital shortness of the lids, because here the closure of the palpebral fissure during sleep is at the same time insured (see § 113).

In obstinate blepharitis squamosa the employment of tar-ointment has been recommended. For this purpose the oleum fagi (or oleum rusci *), mixed with equal parts of olive-oil, is prescribed, and this mixture is applied upon the borders of the shut lids at night by means of a brush; or, pix liquida and spiritus vini, equal parts, are brushed over the borders of the lids, upon which the solution rapidly dries through evaporation of the alcohol. In either case, the entrance of the fluid into the conjunctival sac must be carefully avoided, as it would greatly irritate it. Many people can not stand the tar-ointments at all, on account of the excessive irritation they produce. A less irritating form of treatment is that with tar-soap, with which the lids should be carefully washed every morning.

In many cases of blepharitis ulcerosa, particularly if tylosis is present at the same time, we will fail to accomplish our object until we have epilated all the cilia. We do this in several sittings, and subsequently also remove the cilia which grow in afterward, keeping on in this way until the border of the lid once more looks perfectly normal. We need not fear that the cilia, even if we have epilated them ever so often, will ultimately fail to grow in again. For the tylosis itself, massage of the lid, with the aid of the white-precipitate ointment, does good service. This acts partly by exciting resorption, partly through the fact that it helps to remove mechanically the contents of the palpebral glands, and thus prevents their occlusion.

Not to be confounded with blepharitis is the condition called *phthiriasis palpebrarum*—i. e., the presence of crab-lice (Phthirius inguinalis or Pediculus pubis) upon the eyelashes. Here the borders of the lids look strikingly dark. Upon more careful inspection we discover as the cause of the discoloration the black nits of the crab-lice sticking fast to the cilia; sometimes, too, a grown specimen is found lodged between the cilia. The disease, which is rare and which is found almost exclusively in children, sometimes itself gives rise to blepharitis. It is easily cured by means of blue-ointment, which, when rubbed into the borders of the lids, kills the parasites.

III. Diseases of the Palpebral Glands.

109. The glands which here come under consideration are the glands of the hair-follicles of the cilia (Zeiss's glands) and the Meibomian glands. The affections of the former have already been treated of in part under the head of blepharitis, a disease which presents a diffuse inflammation extending over the whole border of the lid, and in which the hair-follicles play an important part. To be distinguished from this is the isolated inflammation which is limited to one or a few of these glands, and forms an independent affection. If such an inflammation develops as an acute affection, it is known as hordeolum; if as a chronic affection, it is known as chalazion. From these, again, are to be distinguished the cases of simple occlusion of the glands with inspissation of their contents but without inflammation—cases which form the starting-point of the infarcts in the Meibomian glands.

* [Oleum rusci, empyreumatic oil of birch or birch tar.—D.]

1. *Hordeolum** (*Sty*).

There are a hordeolum externum and a hordeolum internum.

Hordeolum externum [or hordeolum zeissianum] is produced by suppuration of one of Zeiss's glands. There is first noticed an inflammatory œdema of the affected lid, which in violent cases may even extend to the conjunctiva bulbi. Upon careful palpation there is discovered in the swollen lid a spot which is distinguished by greater resistance and by special sensitiveness to touch. It lies near the border of the lid, and corresponds to the inflamed gland. In the next day or two the swelling at this spot increases, and the skin over it grows red, afterward shows a yellowish discoloration, and finally is perforated near the border of the lids with a discharge of pus. After the evacuation of the pus the inflammatory symptoms rapidly abate, the small abscess-cavity soon closes, and the entire process comes to an end. In spite of the fact that the duration of the disease is but a few days, the affection itself is still very burdensome to the patient on account of the pain, which is often considerable, in the tense and greatly swollen lids. Added to this is the fact that many persons have quite a number of repeated attacks.

Hordeolum internum is much rarer than hordeolum externum. It consists in a suppuration of one of the Meibomian glands, and is hence also called hordeolum meibomianum. The course of the disease is, on the whole, the same as that of the hordeolum externum; but as the Meibomian glands are larger than those of Zeiss, and are enveloped in the firm connective tissue of the tarsus, the inflammatory symptoms are more violent, and it takes a longer time for the pus to be evacuated. The pus at first, as long as it is shut in in the affected gland, appears upon eversion of the lid as a yellowish spot shining through the conjunctiva. Afterward it breaks through the conjunctiva or is evacuated through the orifice of the gland. Perforation through the skin occurs only as an exception, in contradistinction to hordeolum externum, in which this is the rule.

Hordeolum externum and internum are essentially the same process—i. e., they are both an acute suppuration of a sebaceous gland, for the Meibomian glands are nothing but modified sebaceous glands. Both, accordingly, present nearly the same clinical picture. They are analogous to acne of the external skin (hence also they are called by Stellwag acne ciliaris). The violent inflammatory symptoms, and particularly the marked œdema which distinguish a hordeolum from ordinary acne-pustules of the skin, are caused by the peculiar anatomical structure of the lids, which especially predisposes the latter to inflammatory swelling.

---

* From *hordeum*, barley.

Hordeolum is found principally in young people, particularly if they are of anæmic or scrofulous constitution and at the same time suffer from blepharitis. The latter, by causing swelling of the border of the lid and the accumulation of scales and crusts upon it, favors the occlusion of the excretory ducts of the glands, which may give rise to their inflammation. Probably, too, the micro-organisms which are always present in great numbers upon the inflamed border of the lid, and which can thence readily penetrate into the orifices of the glands, play a part in the production of this affection.

The *treatment* of hordeolum in the beginning of the disease consists in the use of moist warm compresses, which are applied to the lids in order to convert the hard infiltrate more rapidly into pus. When the yellow color of the pus is visible beneath the skin or the conjunctiva, the abscess may be opened by a small incision, and thus the duration of the inflammation may be shortened by several days. The prime means for avoiding a recurrence of the hordeolum is the treatment of any blepharitis that may be present.

2. *Chalazion.**

Chalazion is a chronic affection of the Meibomian glands. It forms a hard swelling which develops very gradually in the lid. In many cases this occurs without any inflammatory symptoms whatever, so that the swelling is not noticed by the patient until it has become quite large. In other cases, however, there are moderate inflammatory concomitants, which, nevertheless, are insignificant in comparison with those which accompany a hordeolum. The tumor keeps constantly enlarging for months until it reaches the size of a pea or a bean; it then bulges the skin far enough forward to produce a perceptible disfigurement of the lid. Upon palpating the tumor we can make out that it is pretty resistant, and that it is intimately connected with the tarsus, while the skin lying over it can be displaced from side to side. After everting the lid we find the conjunctiva over the tumor reddened, thickened, and somewhat protruding. Later on, the tumor assumes a grayish look as seen through the conjunctiva, and ultimately the latter is perforated; then a viscid, rather turbid fluid flows out, which corresponds to the central softened portions of the tumor. But the main portion of the latter, consisting of spongy granulations, remains behind, for which reason the tumor after it has been opened does not at once disappear completely. On the contrary, it diminishes very gradually in size, and meanwhile it is not uncommon for the granulation-masses to project like a fungoid growth through the perforation in the conjunctiva. It requires months more for the tumor to disappear completely.

Chalazion shares with the hordeolum internum its situation in the

* From χάλαζα, hail.

Meibomian glands, but is distinguished by the character of the process. Hordeolum is an acute inflammation, which goes on to suppuration and is over in a few days. Chalazion is a chronic disease, which does not lead to suppuration but to the formation of granulation tissue, and lasts for months or even years. Chalazion is the analogue of acne rosacea of the skin, in which latter the sebaceous glands play the same part that the Meibomian glands do in chalazion (Horner).

Chalazion affects adults more frequently than children. Not infrequently several chalazia are found at once in the same patient. A chalazion annoys the person who has it by the disfigurement it produces, and also by the condition of irritation which it keeps up in the eye. This condition of irritation is partly the result of the chronic inflammation of the lids, partly the result of the mechanical injury done to the eyeball by the uneven and bulging conjunctiva covering the inner surface of the tumor.

Treatment.—Quite small chalazia are best left alone. Larger chalazia are removed by an operation, in order to do away with the disfigurement and also with the irritation of the eye. The lid is everted, and the conjunctiva and the wall of the chalazion lying beneath it are divided in a vertical direction by an incision with a sharp-pointed scalpel. After the fluid portion of the contents has escaped, the granulation-masses which still remain are removed by scraping (with a small, sharp spoon, or with a Daviel's scoop, or even with a curved sound). Even then the tumor does not disappear completely, because its resistant capsule remains, although this shrinks up after a short time. If the contents of the chalazion are not completely removed, it is apt to form again, so that the operation has to be repeated.

3. Infarcts in the Meibomian Glands.

In elderly people we frequently see, upon everting the lids, small, bright-yellow spots beneath the conjunctiva. These are the inspissated contents of the Meibomian glands, which accumulate in their acini and distend them. These infarcts usually cause no disturbance. But sometimes they are transformed by the deposition of lime salts into hard, stony masses (lithiasis * conjunctivæ). These bulge the conjunctiva forward and even perforate it with their sharp edges, which then cause mechanical injury to the eye. In this case they must be removed from their bed, after an incision has been made in the conjunctiva, and thus be got rid of.

The older physicians considered a chalazion as a hordeolum which had become hardened—i. e., had not gone on to suppuration—a view which is still at present widely diffused among the laity. Others supposed that the chalazion was a simple retention-cyst of the Meibomian glands, and analogous to atheroma

* From λίθος, a stone.

of the sebaceous glands. Neither of these views is correct—a chalazion, in fact, being formed as follows: Some interference with the discharge of the viscid sebum is set up in one of the Meibomian glands. The sebum therefore accumulates in the acini of the gland, and through remaining there a long time becomes inspissated and harder. But at the same time it starts up an irritation of the wall of the acinus, in consequence of which both the epithelium of the acinus proliferates and an inflammatory infiltration is produced in the surrounding tissue of the tarsus. The latter process soon becomes the predominant one, so that both the acini of the gland and the tissue of the tarsus ultimately are overwhelmed in an overgrowth of small cells. This growth of cells forms a soft tissue of the nature of granulation-tissue, and, like the latter, contains also giant cells. In the granulation-tumor are found amorphous flakes representing the remains of the inspissated contents of the acini; and on the outside it is inclosed by a capsule of connective tissue. The development of the latter is owing to the fact that the tissue surrounding the growing tumor is compressed by it and condensed more and more all the time. Finally, the central portions of the granulation-tumor which are very poor in vessels break down by a sort of mucilaginous softening, so that a cavity filled with a turbid liquid is formed in the center of the growth. Horner was the first to call attention to the analogy between chalazion and acne rosacea. Dermatologists, indeed, deny that the sebaceous glands are concerned in the development of acne nodules; but I have been able repeatedly to convince myself, in examining microscopical preparations, that in acne rosacea the process of inflammatory proliferation begins in the sebaceous glands in the same way that it does in the Meibomian glands in the case of chalazion.

In old chalazia, in which perforation has failed to take place, the entire contents sometimes become liquefied. The chalazia are then transformed into a sort of cyst with thick envelope and with turbid, mucilaginous contents. Those chalazia which are developed upon the excretory duct of a Meibomian gland assume a special appearance. They are then situated near the free border of the lid, from which they project like a kind of nipple, while on their posterior side they are flattened out by the counter-pressure of the eyeball. If they do harm to the eye mechanically, they are to be removed by ablation.

It not infrequently happens that persons who have never suffered from chalazia begin all of a sudden to have one after another. New chalazia keep developing at intervals of one or more weeks, manifesting their presence each time by the renewal of the slight inflammatory symptoms. Finally, one or more chalazia are found in each of the four lids. In particularly bad cases an actual degeneration of the lids, especially of the upper, takes place. The lids are thickened, so that it is with difficulty they can be everted. In one of the cases observed by me the lid had become one centimetre thick. The skin of the lids forms nodular projections, but can be displaced upon its bed and is not essentially altered. The conjunctival surface of the lids, on the contrary, appears, uneven, nodular, and reddened, and velvety in some spots, while in others it shows a gray translucency or is perforated by sprouting granulations. In extreme cases of this sort we might at first sight be disposed to suspect the existence of a tarsitis or a neoplasm. In operating upon such cases it can be seen that the entire tarsus has disappeared from view in a spongy and partially softened granulation-tissue.

Instead of merely opening the chalazia, we may extirpate them by dividing

the skin over them and then cutting them out of the tarsus. A fenestra is thus made in the tarsus and in the conjunctiva as well. Such an extirpation of the chalazia is pretty tedious and painful, for which reason we in most cases prefer the simple incision, and are perfectly successful with it too. Extirpation is only indicated when we are dealing with large chalazia, which project far forward and have a particularly thick capsule.

Affections of the Tarsus.—The tarsus is implicated not only in the diseases of the Meibomian glands but also in those of the conjunctiva. This is particularly true of trachoma and of amyloid degeneration of the conjunctiva. In the former we can often feel, when we evert the upper lid, that the tarsus has become thicker and more unshapely. This depends upon its inflammatory infiltration, which subsequently leads to atrophy and distortion through cicatricial contraction, and which must therefore be looked upon as the chief cause of trichiasis. In tarsal cartilages which have undergone this change, the Meibomian glands are also in great part found to be destroyed. In amyloid degeneration of the conjunctiva the tarsus itself falls a victim to the same degeneration, so that it is transformed into a large, unshapely, friable structure (see page 99).

There is a primary affection of the tarsus (*tarsitis syphilitica*) which occurs as a consequence of syphilis. This develops very gradually, and as a rule without any notable pain. When it has reached its acme we find one or both lids of the same eye greatly enlarged and the skin of the lid tense and reddened. Upon palpation we can convince ourselves that the cause of the enlargement lies in the tarsus, which can be felt through the skin as a thick structure of cartilaginous hardness and ungainly form. The swelling of the tarsus is usually so great that the lid can no longer be everted. The enlarged tarsus consists, as is evident when it is cut into, of a lardaceous, bloodless tissue. The cilia upon the affected lid fall out, and the lymphatic gland in front of the ear upon the same side swells up. After the swelling has been for weeks maintained at the same height, it disappears very slowly again until the tarsus has reached its former volume, or has even, in consequence of atrophy, fallen somewhat below it. It takes several months for the disease to run all through its course. Tarsitis makes its appearance in the third stage of syphilis, and is accordingly to be looked upon as a gummatous infiltration of the tarsus.

IV. Anomalies of Position and Connection of the Lids.

1. Trichiasis and Distichiasis.

110. *Trichiasis* * consists in the fact that the cilia, instead of looking forward, are directed more or less backward so as to come into contact with the cornea. This anomaly of position either affects all the cilia, or only those which project most posteriorly; it may also extend over the whole length of the border of the lid, or be present over a part of it only (total and partial trichiasis). The inverted cilia are seldom normal, being for the most part stunted, and consisting of short stumps or of minute, pale, and scarcely visible hairs.

Trichiasis causes a continual irritation of the eyeball, due to the

* From θρίξ, hair.

action of the cilia; there are photophobia, lachrymation, and a constant sense of a foreign body in the eye. The cornea iself suffers more considerable injury. Superficial opacities are produced in it, since the epithelium, in consequence of the constant irritation, undergoes a sort of callous thickening, and may be regarded as protecting thus the cornea against external injuries. In other cases deposits like pannus or ulcers of the cornea are formed. It not infrequently happens that persons are tormented by frequent recurrences of corneal ulcers, until at length the physician discovers one minute cilium which is directed toward the cornea, and which has been the cause of the formation of ulcers.

The most frequent cause of trichiasis is trachoma (page 64). The conjunctiva, which in the regressive stage of trachoma undergoes cicatricial shrinking and contracts, tends to draw the external covering of the lid backward over the free border of the latter, and thus puts the cilia more and more in a false direction. At first the most posterior cilia, afterward the anterior rows, too, are turned backward. The distortion of the tarsus acts to produce the same effect. On account of it, that portion of the tarsus which adjoins the free border of the lid bends off at an angle from the rest of the cartilage and is turned backward (t_1, Fig. 19 *B*), and in so doing it draws with it the covering of the free border of the lid which is firmly attached to it.

Partial trichiasis, in which only some of the cilia are turned backward, develops in consequence of cicatrices which have been left by blepharitis, hordeolum, diphtheria, burns, operations, etc., upon the free border of the lid or in the conjunctiva.

Under the name of *distichiasis** is designated the condition in which, the lids being otherwise normally formed, there are two rows of cilia, one of which looks forward; and the other, which is usually less perfectly developed, is directed backward. This condition occurs as a congenital anomaly, and is sometimes present in all four lids.

Treatment.—When only a few of the cilia have an improper position they can be removed by epilation. Inasmuch as they grow again, epilation must be repeated at intervals of a few weeks—a thing which can very often be attended to by the patient himself. It is still better to employ a method in which, with the performance of epilation, the follicle of the cilium is at the same time destroyed, so that the latter does not grow again. The best procedure for this purpose is electrolysis. The two poles of a constant-current battery are so arranged that the positive pole is formed by a sponge electrode, the negative pole by a fine sewing-needle. The latter is introduced into the hair-follicle of the cilium and the circuit closed by the application of the sponge electrode to the temple. At once a light foam is seen to exude from the root of the cilium. This is formed by the bubbles of hydrogen gas

* From δίς, double, and στίχος, a row.

which are developed at the negative pole and give evidence of the chemical decomposition of the tissue-fluids produced by the electric current. By virtue of this decomposition an adequate destruction of the hair-follicle results without any eschar being produced. The cilium can now be very readily drawn out, or it falls out afterward of itself and it never grows again. The operation is pretty painful. When quite a large number of the cilia or all of them are directed toward the eyeball, epilation is not suitable; in that case those methods are indicated by means of which the cilia are brought to their proper position by a shifting of the place in which the hair-bulbs are implanted (see the section on operations, § 168).

The term *distichiasis* is employed by most authors not only for the condition in which there are congenitally two rows of cilia, but also for the acquired anomaly of position due to trachoma, when simply the posterior rows of cilia are set backward, while the anterior are directed even more forward than usual. But this condition is identical in its nature with trichiasis proper, and differs from it only in degree. At the commencement of the cicatricial contraction the rows of cilia are first drawn apart, and then the posterior and last of all the anterior row are turned backward. Accordingly, distichiasis is developed first and trichiasis afterward, and a sharp line of distinction can not be drawn between the two. I hence prefer to use the expression trichiasis for this condition in all its phases, and to confine the term distichiasis to the congenital cases in which two regular series of cilia are present. Then trichiasis and distichiasis really denote two conditions which differ absolutely in their nature.

2. Entropion.

111. Entropion* is a rolling inward of the lid. The distinction between entropion and trichiasis is one of degree. In the latter the border of the lid, as a whole, is properly situated, but the posterior margin of the lid is rounded off and the cilia are turned backward. In entropion the whole margin of the lid is revolved back so as not to be visible at all when the open eye is seen from in front. Hence, to get a view of the border of the lid we have to roll the lid out again by drawing it up toward the margin of the orbit. The evil consequences of entropion are the same as those of trichiasis. According to their etiology we distinguish two varieties of entropion:

(*a*) *Entropion spasticum* is that form which is produced by the contraction of the orbicularis. The fibers of the palpebral portion of the orbicularis (see page 462) describe arcs having a curvature in two different directions. One sort of curvature is due to the fact that the muscular fibers encircle the palpebral fissure; the concavity of these arcs accordingly looks toward the palpebral fissure and is directed downward in the upper lid, upward in the lower. The second variety of curvature is caused by the fact that the muscular fibers in conjunction with the

* From ἐν, in, and τρέπειν, to turn.

lids are molded to the anterior convex surface of the eyeball; the concavity of these arcs looks backward in both lids. When the fibers of the orbicularis contract, they tend to shorten from the form of an arc to that of its chord. In so doing they exert a double action: by the flattening out of the first set of curves they narrow the palpebral fissure; by the flattening out of the second set they press the lids against the surface of the eyeball. As long as the pressure takes place in the same way over the whole height of the lid the latter is applied uniformly to the eyeball. It is otherwise when from mechanical reasons one part or another of the palpebral portion of the muscle gets the upper hand, so that the lid is pressed backward more strongly at one spot than at another. When the bundle adjoining the border of the lid surpasses the peripheral portions of the muscle in force, the border of the lid is tilted backward and entropion develops. When, on the contrary, the action of those fibers which lie next to the margin of the orbit is stronger than the action of the bundle adjoining the border of the lid, the latter is flapped over to the outside and ectropion ensues. Thus the contraction of the orbicularis may, according to circumstances, produce two opposite conditions, entropion and ectropion, and we now have to investigate those conditions that determine in which of these two senses the mechanical effect of the contraction of the orbicularis makes itself felt.

For an entropion to develop, two conditions are necessary: defective support of the free border of the lid, and an abundant amount of extensible skin upon the lid. Under normal circumstances, when the border of the lid is pressed backward by the muscular bundle adjoining it against the eyeball, it finds in it support and resistance. If the eyeball is taken out, the border of the lid is allowed to flap back. Hence entropion spasticum develops most of all when the eyeball is wanting (entropion organicum of Stellwag). For entropion to develop, however, it is not necessary for the eyeball to be entirely absent; it is sufficient that it should be diminished in size, or should simply be situated more deeply in the orbit, as it is in the old and lean. Again, when the border of the lid is rolled inward, the skin of the lid is drawn after it. If this is prevented an entropion can not develop. If the entropionized lid is put back in place, and then the skin of the lid is drawn a little up toward the margin of the orbit and fixed there by pressure, the rolling in again of the lid is rendered impossible. Entropion spasticum, therefore, does not develop in persons with rigid and elastic skin upon the lids, but requires the presence of a large amount of wrinkly, readily displaceable skin, such as we meet with in old persons.

It is clear that the rolling in of the lids is favored when the fibers of the orbicularis are very forcibly contracted, as in blepharospasm, and also when the pressure with which the muscular bundles of the orbicularis are squeezed against the border of the lid is aggravated by an ex-

ternal pressure—i. e., by a bandage. Similarly, blepharophimosis acts to favor the development of entropion (see page 494).

If we summarize what has just been said, it follows that entropion spasticum develops only in elderly people with flabby lids, and that its production is favored by a deep situation, a diminution in size, or the absence of the eyeball, by the existence of a blepharospasm or a blepharophimosis, or by the wearing of a bandage. For the last-named reason entropion is a frequent and unpleasant complication during the after-treatment of cataract-operations, in which case we are dealing with elderly people whose eyes have to be kept bandaged for quite a long time.

Entropion spasticum is observed almost without exception in the lower lid.

(*b*) *Entropion cicatriceum* is caused by cicatricial contraction of the conjunctiva by means of which the free border of the lid is drawn inward. It may be said to form one step further on the way upon which trichiasis has started. Like the latter, it is observed after trachoma, diphtheria, burns of the conjunctiva, etc.

The *treatment* of entropion is either with or without operation. In entropion spasticum which has formed beneath a bandage, the discontinuance of the latter is often all that is required. If we are compelled by important reasons to continue the bandage, we place upon the lower lid in the neighborhood of the margin of the orbit a roll of adhesive plaster, which is kept pressed against the lid by the bandage. This procedure depends upon the observation that the entropionized lower lid takes a correct position spontaneously when we press back with our fingers that portion of it which lies next to the margin of the orbit. Another method of exerting a constant pressure of this sort has been proposed by Arlt: One end of a narrow strip of linen is fastened with collodion to the inner extremity of the lid beneath the internal angle of the eye; from this point the strip is stretched tightly over the lower part of the lid toward the outer side, and is there again fastened by means of collodion. If entropion occurs in consequence of the absence of the eyeball, we enjoin the wearing of an artificial eye. If we can not attain our object by bloodless measures, we must proceed to the performance of an operation (see section on operations, § 171).

3. Ectropion.

112. Ectropion consists in the revolution of the lid outward, so that its conjunctival surface looks forward. It is, therefore, the opposite of entropion. There are different degrees of ectropion. The lowest degree is that in which the internal margin of the lid stands off a little from the eyeball (*eversion* of the border of the lid). Even this very slight degree, however, bears within itself the conditions for its own increase. With the eversion of the [illegible] of the lid there is also asso-

ciated eversion of the puncta, in consequence of which epiphora develops, and by this a contraction of the skin of the lower lid and hence an increase of the ectropion are produced. Ectropion may present all degrees up to complete eversion of the entire lid. The consequences of ectropion are epiphora and also redness and thickening of the conjunctiva wherever it is exposed to the air. The hypertrophy of the conjunctiva may reach such a high degree, especially if this membrane has already been considerably altered (by acute blennorrhœa or by trachoma), that the conjunctiva looks like exuberant "proud" flesh (wound-granulations), whence the old designations ectropion luxurians or ectropion sarcomatosum. In high degrees of ectropion the cornea is incompletely covered by the lids, so that keratitis e lagophthalmo is set up.

According to differences in their etiology the following kinds of ectropion are distinguished:

(*a*) *Ectropion Spasticum.* It was shown above that the lid is rolled outward whenever those fibers of the palpebral portion of the orbicularis lying near the margin of the orbit get the upper hand over those which are found next to the border of the lid. The mechanical conditions which produce this ascendency are the direct opposite of those which we have found to be the causes of entropion. They consist partly in the displacement forward of the tarsal portion of the lid, and partly in a firm, elastic structure of the skin of the lid, by virtue of which the palpebral border is drawn up toward the margin of the orbit. We often have the opportunity to observe the effect of a traction of this sort when we try to open the palpebral fissure in a child with swollen lids and with blepharospasm. As soon as we draw the lids apart they tilt forward spontaneously, and in such cases if we should not carefully put the lids back in place we might readily set up a permanent spastic ectropion. For, the peripheral bundles of the palpebral portion of the muscle contract behind the everted tarsal portions of the lid and maintain them in their faulty position. Then, just as in the case of paraphimosis, the everted lids swell up from engorgement, a fact which renders their reposition the more difficult the longer the condition lasts. Inasmuch as a certain degree of tension of the skin of the lids is requisite for the development of spastic ectropion, this condition is found principally in children and young persons.

The second condition mentioned above for the development of ectropion is the forcing of the tarsal portion of the lid away from the eyeball, by which the eversion of the lid is favored. It occurs mostly through thickening of the conjunctiva, particularly in consequence of acute blennorrhœa and trachoma. Moreover, the eyeball itself may force the lids so far forward that they become ectropionized, as in enlargement or protrusion of the eyeball (ectropion mechanicum of Stellwag).

The two antecedent determining causes above mentioned will be the more apt to induce eversion of the lid in proportion as there is a coincident blepharospasm by which the peripheral portions of the lid are forced backward.

From what has been said, it follows that ectropion spasticum is particularly prone to occur in young persons who at the same time suffer from inflammation of the conjunctiva with swelling of the latter and coincident blepharospasm. Ectropion spasticum frequently affects the upper and lower lids simultaneously.

(*b*) *Ectropion paralyticum* arises as a result of paralysis of the orbicularis. The lids are then no longer kept pressed against the eyeball by the contraction of the fibers of the orbicularis, and thus the lower lid sinks down of its own weight. For this reason ectropion paralyticum is found only in the lower lid; the upper lid, because of its weight, remaining applied to the eyeball even when there is no action of the muscle. In conjunction with the drooping of the lower lid there is an inability to lift it in the act of closing the lids. Consequently the palpebral fissure can not be perfectly shut (lagophthalmus).

(*c*) *Ectropion senile* also is found only in the lower lid. It arises from the fact that in old people the lower lid is relaxed in all its parts and is pressed with insufficient force against the eyeball by the enfeebled fibers of the orbicularis. Another factor that here comes into play is the chronic catarrh of the conjunctiva (catarrhus senilis), which is so frequent in old people. Ectropion of the lower lid also occurs as a result of enfeeblement of the action of the orbicularis when the lid has been divided in a vertical direction at any spot, or when the external commissure has been destroyed, so that the continuity of the orbicularis is interrupted somewhere.

(*d*) *Ectropion cicatriceum* develops when some part of the skin of the lid has been destroyed and has been replaced by cicatrices so that the lid is contracted. Injuries, particularly burns, ulcers, gangrene, excision of the skin in operations, etc., may give rise to it. Ectropion frequently develops as a sequel to caries of the orbit in scrofulous children. Here, in addition to the contraction of the skin of the lid, its fixation to the osseous cicatrix upon the margin of the orbit is of moment, and with this there is associated marked retraction of the skin. So also ectropion is set up by the contraction of the skin and the loss of its elasticity that results from the eczema which occurs in connection with the continual wetting of the skin of the lid by the tears or from other causes. Ectropion is therefore frequently found along with a blepharitis of long standing and with lesions of the conjunctiva and the lachrymal sac.

Non-operative treatment is successful mainly in ectropion spasticum. It consists in putting the lid back in place and keeping it pressed against the eyeball by a well-fitting bandage. In ectropion paralyticum

we must employ, besides the bandage, the remedies indicated for the cure of the facial paralysis, particularly electricity. Ectropion senile is curable without an operation only as long as it has not reached any very high degree. For quite a long space of time the eye must be bandaged at night, and the patient must be told, when wiping away the tears that flow down over his cheek, to apply his handkerchief from below upward, and not, as is ordinarily done, from above downward, a proceeding by which the lid is drawn down only so much the more. It is furthermore, advisable to slit up the inferior canaliculus in order to diminish the epiphora due to the eversion of the punctum. The higher degrees of ectropion, and particularly ectropion cicatriceum, require treatment by an operation, of which the section on operations (§ 172) contains a description.

4. Ankyloblepharon.

113. Ankyloblepharon * consists in an adhesion of the upper to the lower lid along the palpebral margin. It is either partial or total, and is very often combined with an adhesion between the lid and the eyeball, or symblepharon. It also has a common etiology with the latter; it originates, that is, when, as a result of burns, ulcers, etc., the borders of the two lids are converted into raw surfaces at opposed points and so become adherent.

Through ankyloblepharon the palpebral fissure is diminished in size and the movements of the lids are hindered; in total ankyloblepharon there is complete occlusion of the palpebral fissure. The treatment, when we are dealing with simple ankyloblepharon without coincident symblepharon, consists in separating the adherent lids by an operation. If the adhesion extends as far as the angle of the lid, the latter must be supplied with a lining of conjunctiva, as otherwise the adhesion would form again, starting from the angle. In the cases in which symblepharon is present along with the ankyloblepharon, it depends mainly upon the extent of the former whether an operation is practicable at all or not.

5. Symblepharon (see page 109).

6. Blepharophimosis.

In blepharophimosis † the palpebral fissure appears to be contracted at the external angle of the eye. Upon drawing the lids apart we see that the contraction is produced by a fold of skin which extends in a vertical direction at the external angle of the eye and juts out in front of it like a sliding screen. If we draw the fold of skin outward, we disclose behind it the normally formed external palpebral angle with

* From ἀγκύλη, a stiff limb [or a thong], and βλέφαρον, eyelid.

† From βλεφαρον, lid, and φίμωσις, contraction, from φιμός, a muzzle.

the delicate ligament uniting the borders of the two lids. The distinction between ankyloblepharon and blepharophimosis, two conditions which are commonly confounded, is therefore as follows: In ankyloblepharon the borders of the lids are adherent to each other, but in blepharophimosis they are normal, and the contraction of the palpebral fissure is only apparent, being caused by the drawing of a fold of skin over its outer extremity.

Blepharophimosis is most frequently found in persons who suffer from lachrymation and blepharospasm of long standing—that is, it is especially met with in chronic inflammations of the conjunctiva. It originates in a contraction of the skin of the lids due to their being frequently moistened with the tears or with secretion. If the contraction is particularly marked in a horizontal direction, the skin from the adjacent parts is drawn up so as to project over the palpebral fissure on the temporal side like a sliding screen. We can artificially imitate blepharophimosis by drawing the skin from the temple over the palpebral fissure with our fingers. Blepharophimosis is ordinarily not found at the inner angle of the eye, because the adjoining skin of the bridge of the nose is not so readily displaced, although here too a projecting fold of skin is exceptionally formed.

Blepharophimosis accordingly, like that form of ectropion which occurs in connection with chronic catarrh, lachrymation, etc., owes its origin to a contraction of the skin of the lid. The difference between the two lies in the fact that, in the first case, the contraction makes itself apparent chiefly in the horizontal direction; in the second case, in the vertical direction. Blepharospasm and ectropion, therefore, as originating from the same cause, may be both present at the same time. That this in general is but rarely the case is due to the upward traction which the vertical fold of skin forming the blepharophimosis exerts upon the lower lid and which opposes the eversion of the latter. In fact, therefore, blepharophimosis actually favors the development of an entropion, which in such cases can often be cured simply by the abolition of the blepharophimosis. Another consequence of blepharophimosis is the contraction—to be sure, an apparent one only—of the palpebral fissure, which consequently can not be opened as wide as usual.

If blepharophimosis causes any trouble, it may be removed by widening the palpebral fissure by means of canthoplasty (see the section on operations, § 169).

7. *Lagophthalmus.*

By lagophthalmus * is meant an incomplete closure of the palpebral fissure when the lids are shut together. In the lesser degrees of

* I. e., hare's-eye, from λαγώς, hare, because it was believed that hares sleep with their eyes open.

lagophthalmus complete closure of the palpebral fissure is still possible by squeezing the lids together; but since during sleep there is no such squeezing up of the lids, but only a gentle closure of them, these patients sleep with their eyes open, and from this the disease derives its name. In the higher degrees of lagophthalmus it is no longer possible for the patients, even by squeezing their lids together, to bring them into contact.

The evil consequences of lagophthalmus depend upon the harm which the eyeball suffers from being insufficiently covered. What part of the eyeball is it that remains uncovered by the lids in lagophthalmus? If we tell a patient with lagophthalmus of slight degree to shut his lids lightly together, we see that the borders of the lids remain separated some millimetres from each other, and that between them there lies the part of the sclera that is beneath the cornea, but not the cornea itself. This arises from the fact that at the same time that the lids are shut the eye is turned upward, so that the cornea is concealed beneath the upper lid. The same is the case during sleep. Hence the only part of the conjunctiva scleræ that is constantly exposed to the air is that situated below the cornea. As a result of this exposure it is injected, and the patient suffers from the symptoms of a chronic conjunctival catarrh. In the higher degrees of lagophthalmus the cornea, too, is seen to lie in the slit which remains open when the lids are closed together; and, because the cornea is turned upward, it is the lower part of it that is seen. Lagophthalmus but seldom reaches a degree such that the cornea remains completely uncovered. The cornea may suffer in two ways from being covered insufficiently: either it dries up wherever it is constantly exposed to the air, and the dried portions becoming necrotic, keratitis e lagophthalmo ensues (see page 161); or the cornea protects itself against the exposure by a change in its epithelium which becomes thicker and epidermoid, so that the deeper layers of the cornea are preserved from desiccation (xerosis of the cornea, see page 112). But as opacity both of the epithelium and of the cornea itself is associated with this process, the sight is thereby prejudiced. In any case, therefore, vision is endangered in lagophthalmus if the latter is so considerable that the cornea is no longer sufficiently covered. Another result of lagophthalmus is epiphora, since complete closure of the lids is requisite for the normal conduction of tears into the nose.

The *causes* of lagophthalmus are: 1. Shortening of the lids. This is in most cases caused by the loss of a portion of the skin of the lids in consequence of burns, ulcers (particularly lupus), operations, etc. Less frequent are the cases of congenital shortness of the lids. Such cases are characterized by the fact that the palpebral fissure still remains open a distance of some millimetres when the lids are shut lightly together, and that, nevertheless, no signs whatever of loss of the

skin of the lids under the form of cicatrices are present. There often exists in these cases the symptoms of a chronic blepharitis ulcerosa. 2. Ectropion. 3. Paralysis of the orbicularis. In this case it is the lower lid alone which is accountable for the lagophthalmus, the former not being raised when the lids are closed. 4. The state, occurring in persons who are very ill or who are unconscious, in which the eyes remain open on account of a depression of the sensitiveness of the cornea, so that the reflex acts of winking and of shutting the lids are no longer set up. 5. Enlargement or prominence of the eye, so that the lids, in spite of their normal size and mobility, are unable to cover it completely. In this connection particular mention must be made of Basedow's disease, in which the lagophthalmus is bilateral, so that bilateral blindness sometimes occurs as a result of it.

The *treatment* of lagophthalmus consists first of all in regarding the causal indication—i. e., in the removal of those conditions which prevent the complete closure of the lids. Under this head belong the remedying of contraction of the lids by means of blepharoplasty, the cure of ectropion, the treatment of facial paralysis, etc. Until we have succeeded in doing away with the lagophthalmus itself, for which often quite a long time is required, the eye must be protected from the evil consequences of the disease. This is accomplished by closing the palpebral fissure artificially with a bandage. For this purpose we first bring the borders of the lids into perfect apposition, and keep them thus by strips of sticking-plaster which are attached vertically across the lids; over this is applied an ordinary protective bandage with dry cotton. In the lighter cases it is sufficient to apply this bandage only at night, since then the danger of desiccation of the cornea is the greatest, and during the day the act of winking suffices to keep the cornea moist. But in the higher degrees of lagophthalmus, or in cases in which the cornea is already attacked, the bandage must be worn constantly. In those cases in which the removal of the cause of the lagophthalmus is impossible, or is likely to require a very long time (as, for example, in the cure of a case of Basedow's disease), it would be disagreeable for the patient to have to wear a bandage for so long a time—a year or so. For these cases tarsorrhaphy (see section on operations, § 170) is advisable, by which the palpebral fissure is abbreviated and the borders of the lids are brought nearer each other, so that the closure of the lids is facilitated.

Congenital shortness of the lids does not usually reach any considerable degree. The palpebral fissure, when the lids are closed lightly, gapes a few millimetres, so that a narrow line of sclera (but not the cornea) is visible in it. Another sign of congenital shortness of the lids is that such people sleep with the eyes not perfectly shut. This, to be sure, also occurs in persons with normal lids. I have, in fact, found that the peculiarity of sleeping with the eyes half open is hereditary in many families. But in this case the individual concerned

will, when told to close the lids gently together, do it properly and perfectly, while the man whose lids are too short effects their closure only by screwing them up tight. The measurement of the lids affords more exact information in regard to their relations as to size. This measurement can only be performed in the upper lid, because the lower lid has no sharp boundary-line separating it from the cheek. The measure is taken in the following way: First, the *altitude* of the upper lid—i. e., the vertical distance between its free border and the center of the eyebrow—is measured with the lids gently closed. Then the *vertical extent of the skin of the lid* when its folds are smoothed out is measured. For this purpose we grasp the lid by the cilia and put it moderately upon the stretch, and then again determine the distance between the border of the lid and the eyebrow. The altitude of the lid gives a measure of the area that has to be covered by the upper lid; the extent of the skin of the lid gives a measure of the quantity of skin available for this purpose. Upon the relation between the two, therefore, depends the completeness with which the lid can be shut. I have found by numerous measurements that in adults the vertical extent of the skin of the lid must have an amount at least one half greater than that of the altitude of the lid for a complete closure of the lids to be possible without undue effort. If the extent of the skin of the lid falls below an amount one and a half times as great as that of the altitude of the lid, there is lagophthalmus. The consequences of this are chiefly manifested in epiphora, and as a result of this in blepharitis ulcerosa. Such cases are hence ordinarily regarded as old cases of blepharitis, and the shortness of the lids is either altogether overlooked or is considered to be the result of the blepharitis. Small losses of integument, with consequent cicatrices, do indeed develop in the course of this blepharitis from suppuration of the glands of Zeiss; but they are too inconsiderable to account for the marked shortening of the lids, and this, therefore, if no other cause for it can be found, must be regarded as congenital. This condition is incurable. An amelioration of the troubles suffered is obtained by dressing the eyes overnight with an ointment of white precipitate smeared upon linen; in this way the accompanying blepharitis is kept within bounds. I have seen but few cases in which the congenital shortness of the lids was considerable enough for the cornea to suffer harm from it so that an operative procedure (tarsorrhaphy) was required.

V. Diseases of the Palpebral Muscles.

1. Orbicularis.

114. (*a*) *Spasm of the Orbicularis* (*Blepharospasm* *). This manifests itself by the screwing of the lids tightly together. It is either an accompanying symptom of other eye diseases (symptomatic blepharospasm), or it forms a disease by itself (essential blepharospasm).

Symptomatic blepharospasm accompanies all irritative states of the eye, and is hence found in connection with the presence of foreign bodies in the conjunctival sac, with trichiasis, with the most various forms of inflammation of the eye, etc. The violence of the blepharospasm is by no means in direct proportion to the severity of the dis-

* From *βλέφαρον*, lid, and *σπᾶν*, to draw tight.

ease of the eye, so that no sort of conclusion can be drawn from it with respect to the violence or the duration of the ocular affection which lies at the root of it. It often renders the examination of the eye extremely difficult. Blepharospasm is usually most violent and most obstinate in conjunctivitis lymphatica. It reacts unfavorably upon the eye-trouble; moreover, it often leads to œdema of the lids, to blepharophimosis, and to spastic ectropion and entropion. The treatment of symptomatic blepharospasm consists in the removal of the ocular disease which lies at the root of it (cf. page 94).

Essential blepharospasm is distinguished from the symptomatic variety by the fact that in it the eyes themselves are found to be perfectly normal. In young persons, particularly of the female sex, it manifests itself by the eyes suddenly shutting up and then remaining closed as in sleep. This condition is distinguished from ptosis by the resistance offered through the energetic contraction of the orbicularis to the passive opening of the eye performed by drawing up the upper lid (*blepharospasmus hystericus*). In elderly people blepharospasm appears either under the form of clonic spasms—i. e., continual winking (nictitatio *)—or as a tonic spasm by which the eyes are kept tightly closed all the time (*blepharospasmus senilis*). Essential blepharospasm is extremely tormenting to the patient; indeed, in severe cases it has, as far as he is concerned, almost the same results as a real blindness, since the patient can not make use of his eyes when they are shut. Hysterical blepharospasm in time disappears of itself, while senile blepharospasm resists treatment for a long time, and sometimes, indeed, is absolutely incurable.

(*b*) *Paralysis of the Orbicularis.*—If we are dealing with a recent paralysis, no changes are noticed while the eye is open; but if the patient has cause to shut his eye, it is apparent that the closure is but incompletely performed, because the lower lid can not be lifted properly. This is particularly striking in the inner half of the lid. In consequence of the incomplete closure of the lid there is epiphora, which in light cases often constitutes the only complaint the patient makes. After the paralysis has lasted quite a long time further changes set in. The lower lid falls away from the eyeball and sinks lower and lower down (ectropion paralyticum). The cornea during sleep is exposed to desiccation in its lowermost part, so that keratitis e lagophthalmo develops.

Paralysis of the orbicularis is *caused* by an affection of the facial nerve which innervates it. A lesion of the facial nerve may have either a central or a peripheral situation. In the former case it is located in the course of the nerve-fibers extending from the cortex of the brain to the nucleus of the facial nerve; in the second case it is located in the

* From *nictare*, to wink.

nerve-trunk itself. Central paralyses of the facial nerve chiefly affect its oral branches, while the orbicularis is usually normal. Hence, in a paralysis of this muscle we have ordinarily to do with a peripheral lesion. Most frequently we have to deal with a so-called rheumatic paralysis; but the paralysis may also be caused by injury (particularly by operations in the region of the parotid gland), by an otitis interna, by tumors, and by specific disease. The rheumatic paralyses of the orbicularis give a favorable prognosis, but even in them several months are required before the cure takes place. The *treatment* must first of all endeavor to remove the cause of the paralysis. Symptomatic treatment consists mainly in the application of the electric current, both constant and induced. As long as the closure of the lids is imperfectly performed, the palpebral fissure must be kept closed by a bandage (see lagophthalmus), to prevent the development of ectropion and of keratitis. In the severe cases the bandage must be worn constantly; in the light cases it is sufficient to apply it at night only. If the paralysis proves to be incurable, tarsorrhaphy is indicated in order to facilitate the closure of the lids.

2. *Levator Palpebræ Superioris.*

Paralysis of the levator palpebræ superioris manifests itself by a drooping of the upper lid (*ptosis* *). All degrees of ptosis occur, from a just noticeable depression of the upper lid, to a prolapse of it so complete that it hangs down quite relaxed and devoid of wrinkles, and covers the whole eyeball. The higher degrees of ptosis, in which the lid hangs down in front of the pupil, interfere with vision, unless the patient lifts up the lid with his finger, or unless it is possible for him to draw it up sufficiently by a forced action of the frontalis muscle. By the contraction of the latter the forehead is wrinkled and the skin over it is thus contracted, so that the eyebrows and indirectly the upper lid as well are elevated. But since this elevation is not sufficient, the patient is in addition compelled to throw his head back, because then in looking forward the eyes are directed down, and thus the pupils get to lie in the palpebral fissure even though lowered. The wrinkled forehead and the backward pose of the head are characteristic of persons with bilateral ptosis.

Ptosis is either acquired or congenital in its occurrence. *Acquired* ptosis is the result of a paralysis of that branch of the oculo-motor nerve which supplies the levator palpebræ superioris. It is hence often found in conjunction with paralysis of other muscles supplied by the oculo-motor nerve. The cases of isolated ptosis without any other signs of oculo-motor paralysis, are frequently caused by central disease.

Congenital ptosis does not depend upon paralysis of the nerve, but

* From πίπτειν, to fall.

upon a deficient development or the entire absence of the levator palpebræ superioris, due to some anomaly of formation. In contradistinction to acquired ptosis, which usually affects only one eye, it is generally bilateral. Not infrequently is it transmitted by inheritance through several generations.

As regards the *treatment*, our endeavor should be, in acquired ptosis, to find out the cause of the paralysis and remove it by suitable measures. But if we have to do with a ptosis which has already become inveterate, or if it is congenital, an improvement of the condition can be obtained only by way of an operation (see section on operations, § 173).

Essential Blepharospasm.—In *hysterical* blepharospasm both eyes shut up suddenly and without any known cause. It may take some hours, but it may also take days and even months, before the eyes open again, which they do, and just as suddenly. Such attacks may be repeated quite often, and may also vary greatly in their duration. The spasm almost always affects both eyes; once only have I seen a unilateral hysterical blepharospasm. Other symptoms of hysteria often exist simultaneously with the blepharospasm. In a young girl who suffered with blepharospasm of this sort, and whom I had already treated in vain with different remedies, I was finally successful in relieving the blepharospasm by means of a single instillation of cocaine; but a few minutes after the girl had opened her eyes both legs became paralyzed, and remained so for several days.

In the examination of patients with hysterical blepharospasm it is often possible to find so-called pressure-points—i. e., portions of the body upon which we simply have to press for the eyes to open as if by magic (Von Graefe). In the majority of cases the pressure-points lie in the region of the trigeminus, as at the point of exit of the supra-orbital and infra-orbital nerves at the upper and lower margins of the orbit. But often these points are more difficult to find, being situated, for example, in the cavities of the nose, the mouth (when there are carious teeth), or the throat; sometimes the pressure-points are not found anywhere in the region supplied by the branches of the trigeminus. Thus cases occur in which the blepharospasm can be made to disappear by pressure upon one of the costal cartilages or the vertebræ, or upon some spot of the arm or leg, etc. Often the patient himself calls the physician's attention to the position of the pressure-points, the knowledge of which he has already utilized for his own relief. The most frequent cases are those in which the patient allays the blepharospasm by pressure upon the forehead, a pressure which acts upon the branches of the supra-orbital nerve. Young men wear a hat with a stiff crown which they press down hard upon their face; girls tie a ribbon tight about their head. But as soon as the pressure ceases—e. g., by taking off the hat—the eyes shut together again. In many cases diversion of the attention to other things suffices to temporarily relieve the blepharospasm.

Senile blepharospasm is often only one of the symptoms of a general spasm of the face (tic convulsif). Of the two forms of this spasm the clonic variety is the less disagreeable for the patient, because sight is but little interfered with by the constant winking. In tonic spasm the eyes shut suddenly and remain spasmodically closed for some minutes. If the patient is attacked by

this spasm in a crowd, or while crossing the street, or under other such like conditions, he is helpless and exposed to the likelihood of an accident. In senile blepharospasm, too, there are frequently pressure-points which influence the spasm.

Just as the normal act of winking is set up in a reflex way by irritation of the terminal extremities of the trigeminus upon the surface of the eyeball, so, too, blepharospasm is in most cases of reflex nature. This is beyond doubt the case in symptomatic blepharospasm, in which the irritation of the trigeminus due to a foreign body, to inflammation, etc., is obvious. But besides this, a reflex action starting from the trigeminus must be assumed to exist in the majority of cases of essential blepharospasm also. A proof of this is the fact that pressure upon the branches of the trigeminus so often abrogates the blepharospasm, and that at the same time the pressure-points themselves are frequently sensitive to pressure. Treatment has therefore the greatest prospect of success in those cases in which it is possible to find pressure-points, as then we can attack directly the starting-point of the reflex action. This is done by applying the galvanic current to the pressure-points, or by injecting morphine at these spots. In a girl in whom pressure upon the vertex relieved the blepharospasm the inunction, several times repeated, of an indifferent ointment (veratrine ointment) upon this spot sufficed to do away with the spasm. If no pressure-points are discoverable, we must think of the surface of the eyeball itself as the source of the reflex action. We can try to render this insensitive by cocaine, or we may apply the galvanic current to the closed lids. In addition we employ the remedies that are used against neuroses in general. In one case of senile blepharospasm, in which everything else had proved futile, the repeated application of the moxa behind both ears effected a permanent cure. In the most obstinate cases we may proceed to stretch or resect those branches of the trigeminus from which the reflex starts. Stretching of the trunk of the facial nerve has also been performed quite often, although the results on the whole have not been very satisfactory. It is only in senile blepharospasm that such heroic remedies will be adventured upon, as hysterical blepharospasm always passes off of itself in the course of time.

Children of an age of from eight to fifteen years are frequently brought by their parents to the physician on account of a habit of continual winking. This happens not infrequently during the occurrence of a slight conjunctivitis, and keeps on independently after the latter has been relieved. For the most part, in this case we have to deal with rather anæmic and nervous children. This affection—frequently attributed to badness by the parents—usually passes off of itself after some time.

Repeated fibrillary contractions of single bundles of the orbicularis, which are appreciated by the patients themselves, occur very frequently in perfectly healthy persons with normal eyes. No sort of significance is to be attributed to them.

Ptosis.—Congenital ptosis is frequently found in conjunction with other congenital anomalies. Among the latter are an inability to look up, accounted for by a deficient development or actual absence of the superior rectus (Steinheim), and also epicanthus (§ 117).

There is a sort of ptosis which develops without known cause in women of middle age. It is always bilateral, and develops so gradually, that not till after a series of years, is it pronounced enough to cause any considerable interfer-

ence with vision. In these cases it is not a paralysis of the nerve, but a primary atrophy of muscle itself that is present.

The name of ptosis is incorrectly used for conditions which have nothing to do with an affection of the levator palpebræ superioris—e. g., when the upper lid droops because it has become heavier in consequence of thickening due to trachoma, new growths, etc. So also the *ptosis adiposa* of Sichel, which consists in the fact that the covering fold of the upper lid is of unusual size, so as to hang down over the free border of the lid in the region of the palpebral fissure, does not belong under the head of ptosis proper. It was formerly assumed that this enlargement was caused by an excessive accumulation of fat in the covering fold, for which reason the name of ptosis adiposa was given to it. Its true cause, however, depends upon the fact that the bands of fascia connecting the skin with the tendon of the levator (*f*, Fig. 92) and with the upper margin of the orbit are not rigid enough; consequently the skin is not properly drawn up when the lid is raised, but hangs down in the form of a flabby pouch (Hotz). Except for the disfigurement it causes ptosis adiposa entails no disagreeable symptoms. It can be removed by simple ablation of the excess of skin, but it is better, although also more tedious, to attach the skin to the upper border of the tarsus by Hotz's operation. and thus prevent its drooping (see section on operations, § 168).

Both paralysis and spasm are also observed in the unstriated levator or *musculus palpebralis superior* of Müller. Paralysis of this muscle lies at the bottom of that variety of slight ptosis which belongs to the group of symptoms induced by paralysis of the sympathetic (see page 308). Spasm of the muscle, manifested by drawing up of the upper lid and dilatation of the palpebral fissure, can be excited artificially by the instillation of cocaine. Moreover, according to some, the elevated position of the upper lid in Basedow's disease is caused by a spasm of Müller's muscle.

VI. Injuries of the Lids.

115. Injuries of the lids of all kinds, including simple contusions, incised, lacerated, and contused wounds, burns by heat or caustics, etc., are very frequent. A peculiarity of these injuries that needs to be emphasized is that, because of the great elasticity of the skin of the lids and their loose attachment to the subjacent parts, both ecchymosis and œdema in the injured lids are usually much more considerable than after a similar injury in other parts of the body. Accordingly, we must not allow ourselves to be frightened merely by the great swelling and bluish-black discoloration of the lids, as these appearances are often enough produced by comparatively slight contusions. On the contrary, the diagnosis and prognosis should not be pronounced until after a careful examination. In this, three points are chiefly to be considered: solutions of continuity of the skin of the lids, injury to the subjacent bones, and injury of the eyeball.

Solutions of continuity of the skin of the lids present a varying aspect according to their direction. Those which run horizontal—i. e., parallel to the line of fibers of the orbicularis—gape but little, so that

the lips of the wound often lie in apposition spontaneously. But if the cut or rent runs in a direction perpendicular to the fibers of the orbicularis, the wound gapes widely in consequence of the retraction of the divided bundles of the muscle. Consequently, the cicatrices after horizontal wounds of the skin of the lids are scarcely visible, while those after vertical incisions are conspicuous and disfiguring. Hence, in operations upon the lids the rule is laid down that all incisions should, wherever possible, be made parallel to the course of the fibers of the orbicularis. The worst wounds are those which sever the lid in a vertical direction through its entire thickness. If these do not unite by first intention, there remains an indentation of the border of the lid, or even a deep triangular incision in it (coloboma palpebræ traumaticum). By this the complete closure of the lid is rendered impossible, so that, in addition to the disfigurement, a permanent epiphora results from the injury.

The presence of an *injury of the subjacent bone* is determined by palpating the margin of the orbit with the finger through the swollen lid. A fracture of the orbital margin is manifested by unevenness and special sensitiveness at some spot, symptoms to which in many cases is added distinct crepitation. A certain sign of injury of the bone is *emphysema of the lids.* This consists in a penetration of air into the cellular tissue beneath the skin of the lid. The lids then have a peculiar soft feeling like a feather-bed, and at the same time we get in the palpating finger a sense of crepitation due to the displacement of bubbles of air beneath the pressure of the finger. The air comes from the cavities surrounding the orbit—the nasal fossæ, the ethmoid cavities, the frontal sinuses, the antrum of Highmore. Its presence in the subcutaneous cellular tissue of the lids hence presupposes some abnormal communication between the latter and these cavities, such as can only have originated through a fracture of the bone. The emphysema is increased by blowing the nose, straining, and coughing, since in the performance of these acts the air in the nose and its accessory cavities is put under greater pressure, so that more of it is driven into the subcutaneous cellular tissue.

An added significance is imparted to wounds of the lids from the fact that by their mutilation the *eye itself* may be exposed to danger. Through cicatricial contraction of the lids, or the formation of fissures in them, lagophthalmus and consequently inflammation of the cornea may be set up.

The *treatment* of injuries of the lids is carried on according to general surgical rules. In simple ecchymosis we apply cold compresses with lead-water. In emphysema of the lids the air contained in the tissues usually undergoes resorption without causing any ill results. To accelerate resorption a compressing bandage is indicated; at the same time the patient must avoid straining, blowing the nose, etc., in

order not to drive fresh charges of air into the tissue. Recent wounds, the edges of which are not too greatly contused, are best united at once by sutures. In wounds, the edges of which are destroyed by contusion and the like, we apply an antiseptic dressing and wait for the necrotic portions to be cast off. The same rule holds good for burns and injuries caused by caustic substances. After the elimination of those portions of the skin that have been destroyed, granulating raw surfaces are presented to view which cicatrize over and thus lead to a contraction of the lids. To combat this, we proceed precisely as has been laid down for the treatment of destruction of the skin by inflammation (see page 471).

Ecchymoses are usually pretty sharply limited at a line corresponding to the margin of the orbit, because the skin is attached to this by rigid connective tissue which prevents the further advance of the blood. On the other hand, the blood not infrequently travels beneath the skin of the dorsum of the nose over to the other side. An ecchymosis is then found in the lids of the other eye also. As the skin upon the dorsum of the nose is thick, it frequently does not permit the blood to be seen through it, so that we do not notice the bridge connecting the ecchymosis of one eye with that of another. We might then easily be induced to believe that the injury had affected the other eye also, a thing which, however, can be excluded with certainty in many cases —e. g., when sugillation of the lids of one side sets in after enucleation of the other eye.

A similar migration of extravasated blood is observed in *fractures of the base of the skull.* The blood oozes forward from the site of the fracture and travels along the floor of the orbit. It then makes its appearance some time after the injury under the form of an ecchymosis in the lower part of the conjunctiva of the eyeball, and also on the lower lid close to the margin of the orbit, particularly in the region of the inner angle of the eye. This symptom, although it is not present in all cases, is of great importance for the diagnosis of fractures of the base.

Spontaneous ecchymoses sometimes occur in the lids, in the same way as they do in the conjunctiva, from violent straining, excessive coughing, and the like.

Extravasations of blood into the lids, instead of disappearing by resorption, may go on to *suppuration*, so that an abscess of the lids develops. This is particularly to be apprehended when there is at the same time a solution of continuity of the skin of the lids, through which infectious germs may penetrate into their tissue.

VII. Tumors of the Lids.

116. (*a*) **Benign Tumors.**—*Xanthelasma* * is a flat tumor of a dirty sulphur-yellow color and projecting but little above the skin of the lid. It is found most frequently on the upper and lower lids in the neighborhood of the inner angle of the eye; in this situation the tumors are often located symmetrically on the two sides of the eye, like the yellow

* From ξανθός, yellow, and ἔλασμα, plate. It is also called xanthoma.

spots above the eyes of the dachshund. Xanthelasmata occur in elderly persons, particularly of the female sex. They grow very slowly, and have no bad result besides the disfigurement they cause, which, moreover, affords the only reason for their removal by operation, as is sometimes done.

Molluscum contagiosum is a small, rounded tumor, the surface of which is somewhat flattened and has an umbilicated depression in its center. From this a substance resembling sebum is evacuated upon pressure. This form of molluscum is contagious.

Molluscum simplex (fibroma molluscum) is a tumor of the skin which is attached by a pedicle to the skin of the lids and hangs down like a pouch.

Warts and *cutaneous horns* are also observed on the lids.

Among *cysts*, milia, atheromata, and dermoid cysts occur. The latter, which may attain pretty large dimensions, will receive a more detailed description under the head of affections of the orbit (§ 135). On the borders of the lids small, transparent cysts are frequently met with, which have developed from occluded sweat-glands in the border of the lid (glands of Moll).

The *vascular tumors* (angiomata) are found in the lids under the two forms of telangiectases and of tumores cavernosi. The former are bright-red spots situated in the skin of the lid itself. The latter lie beneath the skin of the lid, which they bulge forward and through which they can be seen shining with a bluish luster. They consist of a convoluted mass of large-sized blood-vessels which can be felt and compressed through the skin; the arteries running to the tumors are dilated. Vascular tumors are usually congenital, but they develop still more extensively after birth, and sometimes attain such a size that they cover a great part of the face, and also pass backward over upon the conjunctiva and the tissues of the orbit. For this reason they should be removed as early as possible. In doing this our principal care must be to destroy the skin of the lids over as small an area as possible, as otherwise we might get shrinking of the skin, with ectropion and lagophthalmus. For this reason the simplest procedure—namely, excision of the tumor—is usually unadvisable, as in doing it we should have to sacrifice too much skin; furthermore, the great bleeding that is associated with the operation is sometimes dangerous in small children, with whom, as a rule, we have to deal. We destroy small teleangiectases by cauterizing them with fuming nitric acid or by heat, applied by means of the thermo-cautery or the galvano-cautery loop. In large teleangiectases it is sufficient to sear the tumor along a number of lines, since, by the cicatrization that follows, the intervening vessels which have not been destroyed are obliterated. In cavernous tumors I have seen the best results from the application of electrolysis. The two poles of a constant-current battery are armed with needles; these are

introduced into the tumor at two different points, and then the current is passed through them. As a consequence of the decomposition of the fluids of the tissues produced by the galvanic current, the blood coagulates in the vessels, which consequently become obliterated. Several sittings are always required for the complete removal of the tumor.

(*b*) **Malignant Tumors.**—*Carcinomata* occurring in the lids are, as a rule, epitheliomata, which start from the skin of the lid, particularly from that of its border. Subsequently they pass over upon the eyeball and even penetrate into the depth of the orbit. *Sarcomata* develop from the connective-tissue portion of the lids, particularly the tarsus, and are often pigmented (melano-sarcomata). With malignant tumors we find an enlargement of the lymphatic glands, occurring first in the gland in front of the ear, afterward in the glands along the lower jaw and in the neck. The extirpation of tumors is conducted according to the well-known rules. If in its performance so much of the lid must be sacrificed that the eyeball as a consequence remains uncovered, a substitute for the palpebral skin which has been destroyed must be procured by a blepharoplasty done immediately after the removal of the new growth. In extensive tumors it is often necessary to remove the eyeball, and even the entire contents of the orbit.

The flat cancers of the skin which not infrequently occur upon the lids require particular mention. In these cases there is found a shallow ulcer with an uneven floor and irregular, rather hard walls. The infiltration of the walls of the ulcer is the only characteristic sign, for there is no tumor in the proper sense of the word, and for this reason inexperienced observers readily mistake the true nature of the lesion, which is nothing else than an epithelial carcinoma. The ulcer advances in one direction while it cicatrizes on the side opposite, for which reason it has been called by the name of *ulcus rodens*. Its progress, however, is extremely slow, so that such tumors often last many years before attaining any great size.

In consideration of the complicated structure of the lids, in which such a manifold variety of tissues take part, it should not surprise us that the most dissimilar kinds of tumors should at times come under observation in them. As rare occurrences there have been observed fibromata, enchondromata, lipomata, cavernous lymphangiomata, plexiform neuro-fibromata, adenomata of the sebaceous glands (including the Meibomian glands and the glands of Krause) of the sweat-glands, and of the glands of Moll, and lastly glandular carcinomata.

VIII. Congenital Anomalies of the Lids.

117. By *coloboma of the lid* is meant a fissure in it, having approximately the shape of a triangle, the base of which corresponds to the border of the lid, while its apex looks toward the margin of the orbit. Coloboma is either congenital (coloboma congenitum) or is acquired, being then produced by injury (coloboma traumaticum). Congenital coloboma is on the whole rare, and is observed oftener in the

upper than in the lower lid. Sometimes it is found in conjunction with a dermoid tumor of the cornea (see page 115).

Under the name of *epicanthus* is denoted a fold of skin which juts out on both sides of the dorsum of the nose and projects over the inner angle of the eye so as partly to cover it. In the Mongolian races a moderate degree of epicanthus is the rule, and produces the characteristic appearance of the palpebral fissure in these men. In the Caucasian race there is not infrequently observed in children a slight degree of epicanthus, which disappears again when, in the process of growth, the dorsum of the nose becomes more prominent. Higher degrees of epicanthus, which persist all through life, must be regarded as a deformity, and are sometimes found in connection with other congenital defects (e. g., ptosis). The fold of skin forming the epicanthus disappears if we pick up the skin upon the dorsum of the nose into a vertical fold and thus shorten it in a horizontal direction. Upon this observation depends the operation for epicanthus recommended by Ammon, which consists in the excision of an elliptical piece of skin upon the dorsum of the nose. We may also excise the projecting fold of skin itself (Arlt).

Among anomalies of the lids which are sometimes of congenital occurrence, the following also must be mentioned: Ptosis, distichiasis, abnormal shortness of the lids, and, as the extreme degree of the latter condition, entire absence of the lids (ablepharia); furthermore, symblepharon, ankyloblepharon, and the condition in which the eye is completely covered by the external skin, which replaces the lids and forms a uniform covering for the aperture of the orbit (cryptophthalmus of Zehender); and, lastly, cysts in the lower lid, in the case of microphthalmus.

CHAPTER XIII.

DISEASES OF THE LACHRYMAL ORGANS.

Anatomy and Physiology.

118. The lachrymal organs consist of the lachrymal gland and the lachrymal passages.

The *lachrymal gland* (glandula lacrimalis) is an acinous gland which consists of two divisions. The larger of these, known as the superior lachrymal gland, lies in the upper external angle of the orbit in a depression in the bony wall of the latter, the fossa glandulæ lacrimalis. The excretory ducts of the superior lachrymal gland pass downward and empty into the external half of the superior fornix conjunctivæ.

The second division of the lachrymal gland—the inferior lachrymal gland—is much smaller, and consists only of one or two lobules, for which reason it is also known as the accessory lachrymal gland. Its lobules lie along the excretory ducts of the superior gland directly beneath the mucous membrane of the fornix. If the upper lid is everted and at the same time the eye is made to look downward, we often see the conjunctiva of the fornix in the vicinity of the outer angle of the lid pushed forward by a soft mass which is in fact the accessory lachrymal gland.

The *lachrymal passages* begin with the puncta lacrimalia. These lie on the free border of the upper and lower lid (upper and lower punctum) and near the inner extremity of the lid at the spot where the tarsus terminates (*p*, Fig. 93). They are situated upon small elevations, the lachrymal papillæ (papillæ lacrimales), and form the orifices of the canaliculi lacrimales. These latter, starting from the puncta, run at first vertically for a short distance—i. e., in the upper lid run upward and in the lower lid downward; then they bend at a right angle and become directed toward the lachrymal sac. In so doing they first pass behind the caruncle, and converging more and more, at length reach the lachrymal sac. Into this they empty, either separately or after having united to form a short common trunk.

The *lachrymal sac* (saccus lacrimalis) lies in the inner angle of the eye in the cleft (fossa sacci lacrimalis) which the lachrymal bone forms for its reception. The lachrymal bone bounds the lachrymal sac (*S*, Fig. 93) on the inside, while to the front and outside it is inclosed by the two branches of the ligamentum palpebrale internum (*a* and *h*,

Fig. 93). This relation of the lachrymal sac to the internal palpebral ligament enables us to determine the position of the former—a matter which is of importance when operations are concerned. If by drawing the lids outward we put them on the stretch and so cause the palpebral ligament to project, the lachrymal sac lies behind the latter, and in such a way as to rise just above it by its summit or fundus.

At the spot where the cleft of the lachrymal bone merges into the bony canal the lachrymal sac passes into the nasal or *lachrymal duct* (ductus lacrimalis). The point where this transition occurs constitutes the narrowest part of the whole lachrymal channel, and is therefore particularly liable to the formation of pathological contractions (strictures). From this point the lachrymal duct passes downward and empties into the nasal fossa below the inferior turbinated body. In its downward course the lachrymal duct deviates a little backward and outward from the vertical. Hence, the two lachrymal channels diverge as they go down, the lachrymal sacs being less far apart than are the lower orifices of the lachrymal ducts. We can represent the course of the lachrymal channel on the living subject by placing a straight sound in such a way as to lie at its upper part upon the middle of the internal palpebral ligament, and below upon the furrow forming the boundary-line between the cheek and the alæ of the nose. This sound gives precisely the direction of the lachrymal duct (Arlt). If we place a sound in this way on each side of the nose, we see how the sounds diverge as they go down, and we can readily convince ourselves that the degree of divergence differs in different individuals. The divergence, in fact, depends upon the breadth of the root of the nose on the one hand, and upon the breadth of the inferior nasal orifice on the other. These facts are of importance with regard to the operation of sounding the lachrymal duct, in the performance of which the sound must be pushed along in the direction of the duct.

The mucous membrane of the lachrymal sac and that of the lachrymal duct forms one continuous whole. There is, therefore, no sharp dividing line between these two structures. They are mainly distinguished by the fact that the lachrymal sac lies against bone (the lachrymal bone) at one side only, and everywhere else is free, while the lachrymal duct is inclosed on all sides by bony walls. It follows from this that, in engorgement of the lachrymal channels with fluid, it is only the lachrymal sac which is distended so as to appear as a visible swelling at the inner angle of the eye. The lachrymal duct can not be distended; on the contrary, it is the favorite seat of constrictions, which again do not occur in the lachrymal sac. The formation of these constrictions is facilitated by the fact that a dense plexus of wide veins, analogous to the venous plexuses beneath the mucous membrane of the inferior turbinated body, is interposed between the mucous membrane of the lachrymal duct and the bony wall. The swelling of these veins

is alone sufficient to contract or to close entirely the lumen of the duct.

The lachrymal passages are always filled with a small quantity of lachrymal fluid. If air is found in them, it is to be regarded as a pathological condition.

The *lachrymal secretion* contains only a few solid constituents, the main part of which is sodium chloride (hence "salty" tears). In the normal state the lachrymal gland secretes scarcely any more liquid than is lost by evaporation from the surface of the eyeball, so that but very small quantities of fluid are discharged into the nose. It is only when the secretion is increased, either in consequence of psychical stimulation or of irritation of the eye, that any considerable quantity of tears is discharged into the nose, where its presence is manifested by repeated blowing of the nose.

The moistening of the eyeball is not due to the lachrymal glands alone. The secretion of the conjunctiva itself, and also of its mucous glands (Krause's and Waldeyer's glands), participates in the performance of this act. Hence it follows that even after removal or degeneration of the lachrymal gland the eye does not become dry. Moreover, the loss of the lachrymal gland often affects only its superior portion, so that the accessory lachrymal gland remains intact.

In the *conduction of tears* into the nose there are two factors to be considered: the entrance of the tears into the lachrymal sac, and their transmission from the latter to the nose.

(*a*) The conveyance of tears through the puncta into the lachrymal sac is effected by the act of winking. This takes place in such a way that the palpebral fissure is closed by a movement beginning at the outer and extending to the inner angle of the eye. In this way the tears are collected from the surface of the eyeball and forced toward the inner angle of the eye, since they can not flow off over the border of the lids owing to the way in which the latter is lubricated with fatty matter. They accumulate in the horseshoe-shaped notch in the inner angle of the eye, and form the lacus lacrimalis into which the puncta dip. If there is a perfect and water-tight closure of the lids, the pressure exerted by the latter at length forces the tears into the puncta. The passage of the tears into the lachrymal sac is facilitated by the passive dilatation of the latter that occurs as the lid is closing; for the fibers of the palpebral portion of the orbicularis arise in part from the internal palpebral ligament (Horner's muscle, *H*, Fig. 93), and hence, in contracting as they do during the closure of the lids, draw the ligament away from the lachrymal bone. The anterior wall of the lachrymal sac which is connected with the palpebral ligament is drawn up at the same time with it, so that the lachrymal sac is dilated and the contents of the canaliculi are, so to speak, sucked into it.

(*b*) The conveyance of the tears from the lachrymal sac into the

nose is due partly to the constant entrance of other charges of tears from the canaliculi and partly to the weight of the fluid; but the chief part in the process is performed by the elasticity of the lachrymal sac. In virtue of this elasticity the sac when distended by the tears tends to contract again and thus expels the tears. Hence, in those pathological cases in which the lachrymal sac has lost its elasticity (atony of the sac) we observe that the conduction of tears downward is arrested, even though the nasal duct is completely pervious.

The mucous membrane of the canaliculi is lined with laminated pavement epithelium, that of the lachrymal sac and nasal duct with a single layer of cylindrical epithelium. Acinous mucous glands are frequently found in the latter. The mucous membrane at different spots projects in the form of folds into the lumen of the lachrymal passages—a phenomenon which has been described as a formation of valves. The largest of these folds is Hasner's valve, at the lower orifice of the nasal duct. This, however, is not a true valve, any more than are the others—that is, not a valve which could close up the lumen of the lachrymal channel. On the contrary, it is simply a fold produced by the great obliquity with which the nasal duct passes through the mucous membrane of the nasal fossa. Like the other folds of mucous membrane in the lachrymal passages, it is not of constant occurrence.

Duplication of the puncta and canaliculi, and also their absence, have been recorded as congenital anomalies.

Different theories have been put forth to account for the transmission of tears into the nose. It is certain that perfect closure of the lids forms an indispensable condition for the conduction of tears. If this closure is interfered with —e. g., by paralysis of the orbicularis, shortening of the lids, notching of the border of the lid, etc.—epiphora at once makes its appearance. The passage of tears into the lachrymal sac takes place even when the rest of the way to the nose is cut off by the obliteration of the nasal duct. Hence it follows that the tears are not sucked into the lachrymal sac through the rarefaction of the air in the nose during inspiration (aspiration theory of E. H. Weber and Hasner).

I. Blennorrhœa of the Lachrymal Sac.

119. Symptoms.—The patient comes with the complaint of the tears running over (epiphora*). On careful inspection we notice that the skin in the region of the lachrymal sac protrudes so as to appear fuller than on the other side. This swelling—tumor lacrimalis—is caused by the lachrymal sac being distended by the excessive accumulation of its contents. When pressure is made upon the tumor the contents are evacuated externally through the puncta, and appear, in recent cases, under the form of a purulent, in older cases as a mucous or even limpid liquid. Sometimes, when pressure is made upon the lachrymal sac, the contents are forced not through the puncta but downward through the nose, in which case we do not get a view of them. Associated with

* From ἐπιφέρεσθαι, to rush upon. We also say *illacrimatio* or *stillicidium* (from *stilla*, drop, and *cadere*, to fall).

these symptoms, which are an evidence of distention and abnormality in the secretion of the lachrymal sac, is a contraction (stricture) of the nasal duct. The proof of this is produced when we attempt to explore the duct with a Bowman's sound, in doing which we come upon a spot where the duct is contracted or even altogether obliterated.

Etiology.—The immediate cause of a blennorrhœa of the lachrymal sac is a stricture of the nasal duct. Such a constriction may be produced, for example, by a swelling of the mucous membrane of the nasal duct. The tears can then no longer be fully discharged into the nose. But as new tears are constantly being forced, by the act of winking, into the lachrymal sac, the latter becomes more and more filled up and distended. The lachrymal fluid that thus accumulates in the sac soon decomposes. The tears, in fact, carry with them from the surface of the eyeball a quantity of germs, which find the best conditions for their development within the lachrymal sac in the fluid which remains stagnant there, and which is kept at the temperature of the body. As a matter of fact, the contents of the lachrymal sac in blennorrhœa of the latter are seen under the microscope to swarm with micro-organisms of all kinds. The decomposed fluid acts as an irritant upon the mucous membrane of the sac, which undergoes inflammation and throws out a pyoid secretion that mixes with the tears that stagnate in the sac. The contents of the sac thus grow constantly more turbid and ultimately resemble pus. Blennorrhœa of the lachrymal sac is, hence, nothing but a catarrhal inflammation of the mucous membrane of the sac. The name blennorrhœa is correct only in so far as it signifies purulent discharges in general; and it would be a mistake to think in this connection of a specific inflammation of the mucous membrane of the lachrymal sac analogous to blennorrhœa of the urethra or of the conjunctiva. This is proved by the fact that we can evacuate the purulent secretion of the lachrymal sac as often as we choose by pressing upon it, without any blennorrhœa of the conjunctiva ever developing in consequence. The secretion of the blennorrhœal lachrymal sac, therefore, possesses no specific poisonous property; it is only virulent in the sense that all purulent or decomposed fluids are—i. e., in containing pus-cocci in great numbers. Hence, in blennorrhœa of the lachrymal sac, infection of ulcers of the cornea readily occurs, so that abscesses of the cornea develop.

The constriction of the nasal duct which, from what has been said, forms the starting-point for blennorrhœa of the lachrymal sac, develops as a rule, in consequence of affections in the nasal cavity. Such affections are: 1. *Inflammation of the nasal mucous membrane.* Under this head belongs coryza in its various forms, whether acute or chronic, and whether a simple catarrhal trouble, or one of scrofulous or syphilitic origin. In these cases a swelling of the mucous membrane of the nose exists, which, owing to the presence of the submucous cavernous tissue,

may very readily reach quite a high degree, so that the nasal cavity is rendered impermeable by it. The swelling extends by continuity to the mucous membrane of the nasal duct, being particularly due to the engorgement of the numerous veins lying beneath the latter, an engorgement which of itself is sufficient to close the lumen of the nasal duct. In the ordinary form of ozæna (rhinitis atrophicans) there is no swelling, but a cicatricial contraction of the nasal mucous membrane, which may be continued from the inferior orifice of the nasal duct into the latter and may thus lead to its constriction. 2. *Ulcers*, such as those which are apt to be associated with the scrofulous and specific inflammations of the nasal mucous membrane, and also lupous ulcers. As the ulcers heal, cicatricial constriction or even obliteration of the nasal duct takes place. This is the more to be apprehended if the subjacent bones are also implicated. 3. *Tumors*. These may conceal the lower orifice of the nasal duct, and thus cause stoppage of the flow of tears. The most frequent tumors of this kind are polypi.

Course.—Blennorrhœa of the lachrymal sac is an eminently chronic disease, the course of which is counted by years. A spontaneous cure may indeed occur, if, as the swelling of the mucous membrane of the nasal duct abates, the lumen of the duct becomes free once more, and at the same time the catarrhal inflammation of the lachrymal sac subsides. This, however, occurs but rarely. The rule is that without artificial aid no cure takes place, but the following course of events ensues: The secretion that at first was purulent becomes after some time mucous and viscid; at length, in consequence of atrophy of the mucous membrane, its secretion ceases altogether. Then the distended lachrymal sac contains simply a clear liquid, namely, the tears which have accumulated in it. But the epiphora nevertheless keeps on, because the constriction of the nasal duct prevents the conduction of the tears into the nose.

As a result of the constant distention of the lachrymal sac by fluid, its walls at length lose their elasticity. When this condition, called *atonia sacci lacrimalis*, has set in, the tears are no longer carried down into the nose, even if the nasal duct again becomes perfectly pervious. The distention of the lachrymal sac may keep on increasing more and more, so that it presents a fluctuating tumor of the size of a walnut and over. This either projects far forward, or often it extends deep into the orbit, so that the eyeball is displaced by it (exophthalmus). It is filled with a clear, watery fluid, hence the name *hydrops sacci lacrimalis*.

Blennorrhœa of the lachrymal sac chiefly causes trouble through the epiphora, which compels the patient to dry his eye frequently. The lachrymation increases in cold weather, and in wind, smoke, etc. If it lasts a long time it leads to chronic catarrh of the conjunctiva and to blepharitis ulcerosa. If these two conditions are found in one eye alone, they must always excite the suspicion of there being a lesion of

the lachrymal sac. In the subsequent course of the disease the moistening of the lower lid by the tears leads to eczema of the lid, contraction of the skin covering it, and ultimately to ectropion. By these conditions, again, the lachrymation itself is increased. In the presence of blennorrhœa of the lachrymal sac, abscesses of the cornea may develop from erosions of the latter, and operation-wounds also may readily become infected.

120. **Treatment.**—This must first of all have regard to the nasal disease which lies at the root of the trouble, and, if this still exists, must apply suitable measures for its relief. As regards the lachrymal sac itself, the patient is to be told to evacuate it very frequently by pressing with the finger upon the inner angle of the eye. In this way the accumulation of the secretion and the consequent decomposition of the latter, together with the dilatation of the lachrymal sac, are combated. In addition it is advisable to cleanse the lachrymal sac by syringing. We select for this purpose disinfectant solutions (1–4,000 sublimate solution, three-per-cent solution of boric acid), which can afterward be replaced by astringent solutions. The liquid is injected through the canaliculus by means of a syringe having a slender cannula with a right-angled bend in it (Anel's syringe).

The main burden of treatment lies in the removal of the stricture of the nasal duct, by gradual dilatation with sounds according to Bowman's method. As a preliminary to the treatment by sounds, *slitting of the inferior canaliculus* is performed. To do this, the inferior canaliculus is first dilated with the conical sound, the pointed extremity of which is introduced into the inferior punctum, and then pushed on in the canaliculus until it strikes against the inner wall of the lachrymal sac (lachrymal bone). After withdrawing the sound we introduce a Weber's knife into the dilated canaliculus, in such a way that the edge of the knife looks up and a little backward. By rapidly raising the knife, the probe-pointed extremity of which rests in the lachrymal sac, the canaliculus is slit open, and is thus converted into an open groove, looking upward and a little backward. The object of slitting the canaliculus, as a preliminary to the operation of sounding, is to facilitate the introduction of the sounds into the lachrymal sac.

For *sounding* the nasal duct we make use of Bowman's sounds, which are kept on hand in different sizes, numbered from one to six. The sound is first introduced through the inferior canaliculus, after this has been slit open, and is passed in until it strikes against the inner wall of the lachrymal sac; the sound taking the direction of the canaliculus—that is, extending from the outer side and below in a direction upward and inward. Then we tilt the sound—that is, we direct it more to be about perpendicular by lifting its free extremity until its point, which is in the lachrymal sac, points to the furrow between the nose and the cheek, this giving the position of the inferior

orifice of the nasal duct. The sound, being thus placed in an upright position, is now slowly and cautiously pushed downward until it rests upon the floor of the nasal fossa. In so doing we necessarily pass the contracted spot, the favorite seat of which is either the point where the lachrymal sac enters the nasal duct, or the inferior extremity of the latter—the former spot, because it is normally the narrowest point in the lachrymal passages; the latter, because it is affected sooner than is the rest of the lachrymal tract by diseases of the nasal mucous membrane. We begin with the slenderest sounds. If we can not pass the contracted spot with one of these, we must not push the sound forcibly forward, but must keep trying again and again on succeeding days to introduce the sound, until at length we succeed in carrying it down into the nose. The sound after its introduction is allowed to remain for about a quarter of an hour. We repeat the sounding every day, or every other day, gradually passing to larger and larger sounds, until at length the nasal duct is readily pervious and the epiphora has ceased. Even then the sounding should not be at once discontinued, as in that case the spots which had been dilated would soon close up again, owing to renewed contraction of the cicatrices. The sounding must therefore be repeated again and again at longer intervals (of a week to a month).

The duration and the success of the treatment with sounds depend upon the nature of the contraction. The most favorable cases are those in which the contraction is caused by simple inflammatory swelling of the mucous membrane; those in which cicatricial strictures are present are less favorable, and the least favorable are those in which the nasal duct is completely obliterated at some spot. Cases of the latter kind do not, for the most part, admit of a permanent cure. Even in the most favorable cases the duration of the treatment amounts to from four to six weeks, and it usually requires several months. If strictures due to cicatrices are present, recurrences may set in, owing to renewed contraction of the cicatricial tissue; and, in fact, this unfortunately occurs so often that permanent cures form the exception.

Those cases which can not be cured by treatment with sounds require, if they give rise to considerable annoyance, the *destruction of the lachrymal sac.* This can be accomplished either by extirpation or by obliteration. In either case the operation is begun by *opening the lachrymal sac* through an incision from in front. This is performed according to Petit's method, for the performance of which Arlt has given the following guides. By drawing the lids to the outer side the internal palpebral ligament is put on the stretch, so that it is seen through the skin of the inner angle of the eye as a prominent projection. The point of a sharp scalpel is introduced exactly beneath, the center of the ligament. The back of the knife looks upward and the knife itself is held so that its handle passes through the middle point of an imaginary line drawn from the apex of the nose to the outer

margin of the orbit. The knife held in this direction is thrust vertically in, thus penetrating through the skin and the anterior wall of the lachrymal sac. As soon as we feel the point of the knife striking against the posterior wall of the lachrymal sac (lachrymal bone) we no longer push it forward, but depress its point by raising the handle as high as the forehead. If now the knife is pushed forward, its point enters the upper part of the nasal duct, the wound in the anterior wall of the lachrymal sac being at the same time enlarged. After withdrawing the knife we enlarge the wound upward and downward, so as to have a view of the mucous membrane of the lachrymal sac throughout its whole extent.

After we have completed the opening of the lachrymal sac we proceed to destroy it. If we intend to perform this by *extirpation*, the mucous membrane of the sac, which now lies exposed, is dissected out through its entire extent. If we should not succeed in doing this completely on account of the great friability of the mucous membrane, we can scrape out the remainder with a sharp spoon. After this we sew up the external wound, and secure the apposition of the walls of the cavity by means of a pressure-bandage. If we wish to perform *obliteration* of the lachrymal sac, we either introduce a caustic (the best one being the Vienna paste, which is molded into a little ball with the aid of some flour and water) into the cavity of the lachrymal sac after it has been laid open, or we destroy the mucous membrane with the actual cautery. The external wound in that case should not be closed up, as the escharotic mucous membrane has to be cast off, after which the cavity gradually closes by the formation of granulations.

Both extirpation and obliteration of the lachrymal sac lead to the same result. The former is more difficult of performance, but gives a shorter period of treatment; if healing takes place by first intention, the cure is completed in a few days. After the operation for obliteration of the lachrymal sac it takes several weeks for the wound-cavity to become completely closed. In both methods it is absolutely necessary that all the mucous membrane be either removed or destroyed, for, if a residue of the mucous membrane has been left, the secretion continues and a fistulous opening remains.

Destruction of the lachrymal sac is suitable in those cases in which the treatment by sounds is likely to be without result. This is the case where there are very extensive cicatricial contractions or complete obliteration of the nasal duct. It is still more advantageous if there are at the same time demonstrable changes in the bone, shown either by our coming upon bared and roughened bone in the act of sounding, or by there being an externally visible implication of the bone manifested by a sinking in of the nose (in consequence of syphilis). Furthermore, cases of atony and dropsy of the lachrymal sac, and also those cases in which external circumstances render a protracted

treatment by sounds impracticable for the patient, are suitable ones in which to perform destruction of the sac.

While the treatment by sounds in favorable cases restores the normal conduction of the tears, the possibility of this restoration is forever prevented by the operation for destruction of the lachrymal sac. Hence a condition of epiphora always remains, which, however, reaches a troublesome degree only when, in consequence of irritation of the conjunctiva, there is an excessive secretion of tears. As a compensating circumstance the patients are relieved of the presence of a constantly suppurating cavity which continually exposes them to the danger of getting an abscess of the cornea, and which also usually gives rise from time to time to acute phlegmons (dacryocystitis).

II. Dacryocystitis.

122. **Symptoms.**—In an individual who suffers from blennorrhœa of the lachrymal sac, a violent inflammation may suddenly develop in the region of the sac. The skin in its vicinity is reddened and greatly swollen; the swelling also extends to the lids, and even to the conjunctiva, in which there is chemosis. The inflammation is accompanied by fever and violent pain, so that the patient is deprived of sleep for several nights. After some days the skin at the apex of the swelling takes on a yellowish discoloration, and finally becomes perforated, when quite a large quantity of pus is evacuated. Upon this the pain abates and soon ceases altogether, and the swelling also rapidly goes down. Later on there is discharged from the perforation a fluid which at first is purulent, afterward mucous, and at length perfectly clear like water. Ultimately nothing but the tears which are forced into the lachrymal sac run out again through the perforation, which latter is hence called a *lachrymal fistula*.

As long as the lachrymal fistula remains open the patient is safe from any new attack of inflammation. But if the fistula closes up and the tears again accumulate in the lachrymal sac, a recurrence of the dacryocystitis may ensue.

Dacryocystitis consists in a purulent inflammation of the connective tissue surrounding the lachrymal sac. This inflammation leads to purulent disintegration of the submucous tissue with the formation of an abscess which ruptures externally. Dacryocystitis is accordingly a phlegmon. Blennorrhœa of the lachrymal sac, on the contrary, is a catarrhal inflammation of the mucous membrane itself, in which the purulent secretion of the latter is deposited upon the surface only. The connection between the two diseases consists in the fact that blennorrhœa of the sac precedes the development of the phlegmon and gives rise to it; for the blennorrhœal sac is filled with decomposed secretion, and it only requires the presence of a small defect in the epi-

thelial covering of the mucous membrane of the sac to enable the micro-organisms of the secretion to penetrate into the submucous tissue, where they excite suppuration and cause dacryocystitis.

Treatment.—If we are dealing with a dacryocystitis in its very inception, we may try to prevent the development of an abscess. With this end in view, we sedulously express the fluid from the lachrymal sac, inject it with antiseptic solutions, and in the intervals apply a pressure-bandage, which constringes it.

If the inflammation has passed the initial stage, it is idle to endeavor to prevent the formation of an abscess; besides, the methods of syringing, expression, and compression, given above, could not be employed, on account of the swelling and painfulness of the parts. The only thing to do now is to hasten the formation of the abscess, an object which is best attained by the use of moist and warm compresses. As soon as fluctuation makes itself apparent, we incise the anterior wall of the lachrymal sac, or that portion of the skin beneath which the presence of pus can be made out. A lachrymal fistula is thus artificially produced, through which the contents of the abscess and of the lachrymal sac itself are discharged externally. This is kept open by the introduction of a strip of iodoform gauze every day, until all inflammatory symptoms have disappeared and the secretion that exudes has lost its purulent character. But even then we ought not to allow the fistula to close at once, for we must recollect that a blennorrhœa of the lachrymal sac has preceded the dacryocystitis, and that consequently there is a stricture present in the nasal duct. If the fistula should close without the stricture being relieved, we should have to apprehend another attack of dacryocystitis. Hence, the permeability of the nasal duct must first be restored by treatment with sounds. When we have succeeded in doing this the fistula usually closes of itself. If this should not be the case, we can effect a closure of the fistula by either refreshing and uniting the edges of the wound or by their cauterization. If the conditions are such that a permanent state of perviousness of the lachrymal channels is unattainable, we proceed to the operation of destroying the lachrymal sac.

It is extremely rare for the *lachrymal gland* to be the seat of disease. Among such diseases belong: 1. Inflammation [dacryo-adenitis]. This may go on to resolution; in other cases, suppuration of the gland with discharge of the pus externally has been observed, a fistula of the lachrymal gland remaining afterward. There have even been described cases of bilateral dacryo-adenitis which ran either an acute or more frequently a chronic course; some of these cases were complicated with simultaneous swelling of the parotid glands. 2. New formations, including carcinomata, adenomata, cylindromata, lymphadenomata, chloromata, and sarcomata. 3. Cystoid dilatation of one of the ducts of the gland—a condition which is designated under the name of dacryops. 4. Atrophy of the lachrymal gland in xerosis (Arlt ; see page 113).

In the *puncta* there can be frequently made out a change of position of such a character that the lower punctum is turned outward (forward) instead of looking upward (*eversion of the punctum*). This represents the very first stage of an ectropion—a stage which bears within itself the germ for its own development (see page 490). In simple eversion of the punctum, without ectropion proper, the epiphora can be relieved by slitting the canaliculus. The tube is thus converted into an open groove, which looks backward and hence dips into the lacus lacrimalis and takes up the tears. Bowman has the credit of showing that the conduction of tears is not injuriously affected by the slitting of the canaliculus. If this operation is performed with Weber's knife in the way described above, it affects only the external two thirds of the canaliculus; the inner third of the latter lies beneath (behind) the caruncle, and remains unopened. Slitting of this most internal part would be possible only if the caruncle were divided at the same time; and if this were done, the cut surfaces that were made would be pretty broad, and it would be quite hard to prevent their reunion. Even in the ordinary method of performing the operation of slitting, the divided canaliculus is usually found to have closed up again on the following day, so that we have to introduce the conical sound and thus tear apart the slightly agglutinated edges of the wound. If in this way readhesion is prevented the first time, the cut surfaces become clothed with epithelium, so that afterward adhesion is no longer to be apprehended.

In both the *puncta* and *canaliculi* contraction and even obliteration are sometimes observed, the consequence of which is also epiphora. The most frequent cause giving rise to these conditions is injury of the mucous membrane of these structures due to sounding. To remove them, we must endeavor to enter the canaliculus with a conical sound and thus dilate it, or, if necessary, we must slit it up. Occlusion of the canaliculi may also be produced by foreign bodies or by concretions. The latter are of a gray or grayish-green color and of friable or hard consistence, and prove to be conglomerated masses consisting of a fungus, the Streptothrix Fœrsteri. In some cases cystoid dilatation of the canaliculi has been found. This arises from an obliteration of the canaliculus at both extremities and the accumulation of fluid in its cavity, so that the tube is gradually distended till it forms a cyst.

Blennorrhœa.—For the two most important diseases of the lachrymal tract—namely, blennorrhœa of the lachrymal sac and dacryocystitis—the expression dacryocystitis catarrhalis and dacryocystitis phlegmonosa have been proposed. Although they correspond to the actual state of things better than do the old designations, I do not employ them, not wishing to give rise to confusion. Some observers have also distinguished another form called *dacryocystitis blennorrhœica*. Under this name are designated those cases in which a blennorrhœa of the lachrymal sac exists in conjunction with trachoma of the conjunctiva. This is a pretty frequent occurrence, which has been interpreted as meaning that the secretion of the trachomatous conjunctiva enters the lachrymal sac and infects its mucous membrane. In that case we should have to do with a true blennorrhœa of the lachrymal sac—i. e., with a specific inflammation of its mucous membrane. This variety is supposed to differ from the ordinary catarrhal blennorrhœa of the lachrymal sac, in that the secretion in the former is purulent, in the latter mucous. But the nature of the secretion does not depend upon the variety of blennorrhœa existing in the lachrymal sac, but upon the stage in which the latter is at the time: it is purulent in recent cases,

mucous or watery in those which are more advanced. That blennorrhœa of the lachrymal sac occurring in trachoma may arise from a specific infection of the sac, is doubtless possible and indeed probable, but is by no means certainly proved. It is an exceedingly frequent thing to find ozæna in trachomatous patients, in which case the blennorrhœa of the lachrymal sac is much more likely to be referable to this than to the trachoma. And infection of the mucous membrane of the lachrymal sac through the blennorrhœal virus does not take place in acute blennorrhœa of the conjunctiva, although the latter is much more infectious than trachoma.

Blennorrhœa of the lachrymal sac affects the female more frequently than the male sex, perhaps on account of the zealous use that the former makes of the lachrymal apparatus. Persons having the bridge of the nose flattened (flat noses and "saddle-noses," particularly when due to hereditary disease) also are predisposed to this affection.

Tuberculosis of the lachrymal sac occurs as a secondary affection in tuberculosis of the conjunctiva or in tuberculosis (lupus) of the nasal mucous membrane. The lachrymal sac feels very much thickened, and upon opening it we find its inner surface lined with discolored granulations (cf. pages 102, 103).

Injections into the lachrymal sac are not only of service for cleansing it and for the treatment of its mucous membrane, but also for determining whether the lachrymal channels are permeable. If this is the case, the injected fluid enters the nose, and, if the patient bends his head forward during the injection, runs out by the nasal orifice. If the injection is performed incautiously, it may happen that the mucous membrane is injured by the point of the cannula, and the fluid is injected into the subcutaneous cellular tissue of the lids. A marked inflammatory œdema is thus set up, which, however, usually abates in a few days without producing any bad results.

The operation of *sounding* can be performed through either the upper or lower canaliculus. The former is narrower, but, as an offset to this, we have to turn the sound but little after its introduction in order to place it upright. In sounding through the lower canaliculus, the sound must be tilted so as to be turned through more than a right angle, but the canaliculus is wider. Accordingly, the lower canaliculus is usually selected because the mucous membrane of the narrow canal would be lacerated in passing sounds of a higher number. The consequence of this would be contraction or obliteration of the canal, which would set in as soon as the sounding is stopped. The sound can also be introduced and carried into the nose through a canaliculus which has not been slit up, but this is unadvisable, because of the likelihood of producing injuries to the mucous membrane such as have just been mentioned. I usually do it only for diagnostic purposes (for demonstrating the presence of a stricture), and then only employ the sounds of the lowest number, which can be readily introduced even through a canaliculus that has not been slit open. Preliminary slitting of the canaliculus is always indicated when the treatment by sounds is to be kept up for any length of time.

The act of sounding itself requires a deft hand and much experience, for which reason it ought first to be practiced very industriously upon the cadaver. It is often very painful, so that the patients sometimes become faint during its performance. Hence, the indication is to make the mucous membrane of the lachrymal tract insensitive, by the preliminary injection of a few drops of a solution of cocaine into the lachrymal sac. Beginners in sounding frequently

make the mistake of tilting the sound before its point has got into the lachrymal sac. We then feel an obstacle opposing the downward progress of the sound, and if we should try to overcome this obstacle by force we would make a false passage. That the sound has been tilted up too soon, is recognized from the fact that, when it is set vertical, the skin beneath the canaliculus is drawn along with it and is thrown into wrinkles. We shall not commit this mistake if we avoid tilting the sound until we distinctly feel through its point the firm resistance offered by the inner osseous wall of the lachrymal sac (the lachrymal bone). The obstacles opposing the passage of the sound in the nasal duct may be actual constrictions of the duct, but are often nothing but projecting folds in which the sound catches. We accordingly try to push our way forward by sliding the point of the sound sometimes along one, sometimes the other, wall of the lachrymal sac in order to smooth out the folds. Sometimes we can pass a rather thicker sound (No. 3) more readily than we can the thinnest ones; the latter, moreover, are more apt to injure the mucous membrane, so that we get beneath it and make a false passage. Bleeding from the nose after sounding points to an injury of the mucous membrane, as does also the striking of the apex of the sound upon bare bone. The latter, however, can also happen without the mucous membrane being injured, if, for example, the bone has been already denuded by ulcerative disintegration of the mucous membrane of the nasal duct. In cases of this kind a cure can not usually be obtained by treatment with sounds.

When finally the sound has been passed all the way through, it is felt to rest upon the floor of the nasal cavity. In most persons the central lamina of the sound then lies upon the inner end of the eyebrow. To ascertain the position of the sound more precisely, we may place on the outside a second sound of the same length in the direction of the lachrymal tract and in such a way that the laminæ of the two sounds are superimposed; the exterior sound then shows at what height the lower extremity of the sound that we have introduced stands.

Treatment by sounds must be kept up until at least No. 4 of Bowman's sounds passes with ease. Then the patient may be instructed how to pass the sound upon himself with the aid of a looking-glass, so that the sounding may be performed from time to time subsequently in order to prevent a recurrence of the contraction.

The long duration of the treatment by sounds has excited a desire to accomplish the dilatation of the strictures rapidly instead of gradually, and thus shorten the treatment. This can be done either by Weber's method of introducing very thick sounds, or by Stilling's method of incising the strictures with a knife designed for the purpose, or by a combination of both methods. By these methods of treatment, however, solutions of continuity are made in the mucous membrane, which lead to the formation of fresh cicatrices, and which hence, after a period of apparent cure, entail recurrences that are all the more rapid in their development. Most ophthalmologists therefore prefer the gradual dilatation of the strictures.

Dacryocystitis almost always originates from a blennorrhœa of the lachrymal sac; consequently the patients declare that epiphora has existed for quite a long time before the acute inflammation which they often designate under the name of erysipelas. It is only in very rare cases that a caries of the lachrymal bone gives rise to dacryocystitis. Children sometimes come into the world with a recent dacryocystitis, or they acquire one a few days after birth. The

mucous or watery in thos… the situation of the abscess, lachrymal sac occurring … sac. To be sure, a furuncle sac, is doubtless possibl… ght produce similar symptoms, proved. It is an exce… We shall therefore scarcely patients, in which … likely to be referable … dacryocystitis in the case of an cous membrane of … sac. The spot where the pus take place in acute bl… spond with the position of the more infectious than … a distance below and to the out-

Blennorrhœa of … that the pus beneath the skin sinks the male sex, perha… side along the inferior margin the lachrymal app… is attached to the bone by rigid con-noses and "saddl… whom it makes its way through the predisposed to … that remains. That an opening in

Tuberculosis … side may still be a lachrymal fis-losis of the … push a sound through from the brane. The … should not succeed in this, we inject a find its inner … the sac; we then see it flow out again

Injections … for the treat… contract and sometimes become lachrymal … but a fine bristle. The external the nose, … called, is then scarcely visible with out by the … of clear lachrymal fluid appearing pen that … the lachrymal sac; it is only upon fluid is in… capillary opening. flammato… without p…

The … lower … lachrymal apparatus find expression turn the … sence of the tears. *Epiphora* is an ex-sounding … various conditions, and is either based turned … hindrance to the discharge of the tears. cordin… weeping, and also in the presence of all brane… expansion of the trigeminus and its numb… air rendered foul by smoke, etc., canal… inflammations of the eye and its adnexa, also … the first and second branches of the not l… collection of tears into the nose may have injur… the lid or in anomalies of the lachrymal do … the former condition are to be men-and … ening or ectropion of the lids, notching intr… eversion of the lower punctum; to allo… lachrymal channels which have been lo… quently happens that persons complain … cold weather, without our being able … cases there is probably an excessive … nose which excites increased secre-… pungent odors, such as the vapor of am-… terminal extremities of the trigemi-… being the tears to our eyes; and lach-… severe coryza. A like connection also

exists in the contrary sense, in that a bright light striking upon the eye excites an impulse to sneeze, as is observed especially in children with photophobia, when the attempt is made to open their eyes for purposes of examination. Hence, in cases of epiphora for which no other cause can be found, it is requisite to examine the nose carefully and treat it according to the indications.

The opposite condition, namely, *abolition* of the lachrymal secretion, is extremely rare. It is found in paralysis of the trigeminus, in consequence of interference with the innervation of the lachrymal gland; and in xerophthalmus, in consequence of atrophy of the gland. A purely nervous disturbance lies at the bottom of those cases in which persons declare that formerly they wept a good deal, but that for a long time past they have not been able to weep, even when very much distressed.

CHAPTER XIV.

DISTURBANCES OF MOTILITY OF THE EYE.

Anatomy and Physiology of the Ocular Muscles.

122. The ocular muscles are distinguished into extrinsic and intrinsic. The later, also called the interior muscles of the eye, are the sphincter pupillæ and the ciliary muscle. Of these we shall have something to say later; at present we shall concern ourselves only with the extrinsic muscles. These are six in number, four straight and two oblique.

The four straight muscles are the rectus internus, externus, superior, and inferior. All four take their origin from the apex of the orbit along the bony circumference of the foramen opticum (*F*, Fig. 94), and from this point run forward, diverging as they go. They thus bound a funnel-shaped space, the muscular funnel (*t*, *t*), the apex of which lies at the foramen opticum, while the eyeball forms its base and the optic nerve (*o*) runs along its axis. The external and internal recti muscles (*i* and *e*) are inserted into the sclera to the outer and inner side of the cornea; the superior rectus (*su*) has its insertion above (s_1), the inferior rectus below, the cornea. The attachment is effected by means of short tendons which spread out in the form of a fan and become fused with the sclera, which in this way is thickened in its most anterior portion.

The two oblique ocular muscles are the obliquus superior and inferior. Their course is more complicated than that of the straight muscles. The *superior oblique* (*os*, Fig. 94) also arises from the margin of the optic foramen and runs forward upon the upper and inner wall of the orbit as far as the trochlea, before reaching which it passes into its tendon. The trochlea itself (*T*, Figs. 94 and 95) lies a little behind the upper and inner margin of the orbit. It consists of a firm fibrous loop through which the tendon of the muscle is carried in such a way as to be able to glide up and down in it. After traversing the trochlea, the tendon bends backward at an acute angle, and passes beneath the superior rectus to the eyeball. Here it spreads out in the form of a fan, and is inserted in the upper half of the eyeball about in the vertical meridian and behind the equator (*os*, Fig. 94).

The *inferior oblique* arises from the lower margin of the orbit near its inner extremity (*oi*, Fig. 95). From here it runs upward and outward and arrives at the outer side of the eyeball, into which it is in-

serted about in the horizontal meridian and also behind the equator (*oi*, Fig. 94).

The tendons of the ocular muscles before reaching the sclera must pass through the fascia of Tenon which surrounds the eyeball. In the spot where the tendon of the muscle perforates the fascia, the latter does not present a simple aperture, but is reflected backward upon the tendon (*e* and e_1, Fig. 53). It ensheaths the tendon and farther back is continuous with the fascia which envelops the muscle itself. By these "lateral invaginations," therefore, the tendons are connected with Tenon's capsule—a fact which is of importance with regard to the operation for squint.

The *innervation* of the ocular muscles is accomplished by three nerves. The oculo-motor nerve supplies the internal, superior, and inferior recti, and also the inferior oblique; and, in addition, the levator palpebræ superioris and the internal muscles of the eye, namely, the sphincter pupillæ and the ciliary muscle, are innervated by it. The abducens nerve is reserved for the external rectus, the trochlear nerve for the superior oblique. The nuclei for the three nerves supplying the eye-muscles lie upon the floor of the fourth ventricle.



FIG. 94.—HORIZONTAL SECTION THROUGH THE ORBIT (SCHEMATIC). NATURAL SIZE.

The apex of the orbit is formed by the foramen opticum. The external wall of the orbit does not reach as far forward as the internal, so that its anterior margin, *A*, lies in the same plane as the equator of the eyeball. At the anterior extremity of the internal wall of the orbit is shown the trochlea, *T*, which in reality lies in the upper and inner angle of the orbit, and hence would not be met with in the cross-section of the orbit that is here represented. The external rectus, *e*, and the internal rectus, *i*, bound the muscular funnel, *t*, *t*. A portion of the superior rectus (*su*) is cut away to show the optic nerve, *o*. s_1 is the insertion of the superior rectus upon the eyeball, lying obliquely to the margin of the cornea. os_1 is the fan-shaped insertion of the tendon of the superior oblique, *os*; *oi*, the line of insertion of the inferior oblique. *f*, *f* is the frontal, *s*, *s*, the sagittal axis of the eyeball.

The movements of the eyeball take place freely in all directions as in a ball-and-socket joint (arthrodia). The eyeball may be said to represent the articular head; Tenon's capsule, the socket. The movements take place in such a way that the eyeball, as a whole, undergoes no change of place; it simply rotates about a center of movement which corresponds approximately to the center of the eye.

We can imagine all movements of the eyeball resolved into components which correspond to three *primary axes*. These are perpendicular to each other and cross at the center of movement. One of these is vertical; the movements which take place about it are the lateral movements of the eye—that is, the movement to right and left, or to the out-

side (abduction) and inside (adduction). The frontal axis runs from right to left (*f*, *f*, Fig. 94), and corresponds to the movements of elevation and depression of the eyeball. The sagittal axis (*s*, *s*, Fig. 94) runs from before backward, and coincides with the line of vision. The movements which take place about it are known under the name of rotation of the eyeball; by virtue of them the upper extremity of the vertical meridian of the eyeball is inclined outward or inward.

The muscles may be grouped into pairs according as they rotate the eye predominantly about one or the other of these axes. The muscles belonging to any one pair are called antagonists, because they tend



FIG. 95.—ANTERIOR ORIFICE OF THE ORBIT WITH THE EYEBALL. NATURAL SIZE.

The tendons of the four recti muscles are cut off near their insertion upon the eyeball, but the inferior oblique, *oi*, and the tendon, *os*, of the superior oblique are left entire. The latter comes out from the loop of the trochlea, *T*. To the temporal side of the trochlea lies the supra-orbital notch, *i*, and somewhat to the outside of this there is a foramen, i_1, which is not regularly present, for a branch of the supra-orbital nerve. In this case the infra-orbital foramen, *fi*, is also abnormally divided into two distinct foramina. *x* is the orifice of the zygomatico-facial canal, *fl* the lachrymal fossa.

to move the eye about the same axis, but in a contrary direction. In this sense the six ocular muscles are divided into the following pairs:

First pair: internal and external recti, which turn the eye about the vertical axis.

Second pair: superior and inferior recti, which turn the eyeball about the frontal axis.

Third pair: the superior and inferior obliques, which turn the eyeball about the sagittal axis.

A simple action in the sense of rotating the eyeball about only one of the three primary axes belongs to the first pair alone, the only effect of which is to turn the eye inward and outward. The action of the other four ocular muscles is a complicated one, and if we seek to deter-

mine the axes about which they actually rotate the eyeball, we find that these do not coincide with any one of the three primary axes.

The *superior rectus* runs from the apex of the orbit not only forward, but also a little outward, in order to reach the eyeball. Its direction, therefore, does not coincide exactly with the sagittal axis of the eyeball, but forms with it an angle, the branches of which diverge posteriorly (Figs. 94 and 103 *A*). Hence, as its insertion falls somewhat in front of the center of rotation of the eye, it will not only elevate the latter, but also adduct it at the same time. For the same reason it also rotates the eye in such a way that the upper extremity of its vertical meridian is inclined inward.

The *inferior rectus* likewise deviates somewhat to the outside in its course forward. Hence, besides lowering the eye, it has an adducting action imparted to it. Furthermore, it rotates the eye in such a way that the upper extremity of the vertical meridian is depressed to the outside.

To learn the action of the *superior oblique* we have merely to consider that section of it which lies between the trochlea and the eyeball; the trochlea being, so to speak, the physiological origin of the muscle. Its chief action consists in its rotating the eye, so that the upper extremity of the vertical meridian is inclined inward. Since, furthermore, it is inserted into the posterior half of the eyeball and this insertion lies below the trochlea (*os*, Fig. 95), the posterior half of the eyeball will be raised when it contracts, and consequently the cornea will be depressed. The superior oblique, in addition, produces an abduction of the eyeball, since it is inserted behind the center of rotation of the eye, and in its contraction draws the posterior half of the eyeball inward, so that the cornea goes outward. The action of the superior oblique is accordingly to rotate, depress, and abduct the eyeball.

The *inferior oblique* accomplishes, first of all, a rotation of the eye in the opposite direction to that effected by the superior oblique—i. e., a rotation in which the upper extremity of the vertical meridian is inclined outward. Since its origin in the margin of the orbit lies below its insertion upon the posterior half of the eyeball (*oi*, Fig. 95), it draws this half downward and thus elevates the cornea. Furthermore, since it draws the posterior half of the eyeball inward, it abducts the eye. The action of the inferior oblique is accordingly to rotate, elevate, and abduct the eyeball.

The internal and external recti are the only muscles which are perfect *antagonists* in every respect. The superior and inferior recti are antagonists with respect to the elevation and depression, and also with respect to the rotation of the eyeball; but, as adducting muscles, they both act in the same sense. The superior and inferior obliques are likewise antagonists with regard to vertical deviation and rotation, but

they have one action, that of abduction, which takes place in the same direction.

Let us make a brief summary, showing which of the muscles act in concert in the movements of the eye about the three primary axes. Adduction is performed by the internal, superior, and inferior recti; abduction by the external rectus and the superior and inferior obliques. The superior rectus and inferior oblique are concerned in elevating the eye, the inferior rectus and superior oblique in depressing it. Rotation of the eyeball, in such a way that the upper extremity of the vertical meridian is inclined inward, is effected by the superior oblique and superior rectus, while rotation in the opposite sense is effected by the inferior oblique and inferior rectus.

Hence, in every movement of the eyeball there are always several muscles set into action at once. But, besides, this the muscles of one eye act in conjunction with those of the other in such a way that the two eyes always move in the same sense (*association* of the ocular movements). These associated movements are regulated by the centers of association, which are centers of a higher order than the nerve nuclei. According to the necessities of the case, they innervate certain muscles or groups of muscles of one eye simultaneously with those of the other. The internal rectus of the right eye, for example, may be set into action at the same time with the internal rectus of the left eye, so that a movement of convergence takes place; but, on the other hand, it may also act in concert with the external rectus of the left eye, so that both eyes are turned to the left.

123. Orientation.—Orientation in space—i. e., the ascription of objects seen to the place where they actually belong—is effected in the following way: The objects of the external world form images upon the retina. To find the situation of the retinal image of any object whatever, we only need draw a line from the object to the retina through the nodal point of the eye (*k*, Fig. 96). Thus the image of the object of fixation, *o* (Fig. 96), lies at *f c* (the fovea centralis). Objects, such as o_1, situated beneath the point of fixation, throw their image above the fovea centralis, at b_1; and, on the other hand, the object o_{11} lying above the point of fixation has its image at b_{11} beneath the fovea. We ourselves judge of the place in which an object is by following out a re-



FIG. 96.—PROJECTION OF RETINAL IMAGES EXTERNALLY.

verse process. We refer the object to the extremity of a line which we imagine drawn from the retinal image and through the nodal point to the outside. This process for determining the place of external objects, which is learned by experience, is called *projection* (of the retinal images to the outside). By virtue of it we see the objects in the outer world arranged side by side just as their images are upon our retina, only in reverse order; whatever forms an image to the right of the point of fixation, is seen upon the left of the latter, etc. We are thus informed with certainty in regard to the relative position of objects to each other (*objective orientation*). But for perfect orientation it is further requisite that we should assign to its correct situation in space the whole mosaic of images which we project from our retina to the outside, and which is already properly constructed as far as the relations of its own parts to each other is concerned. Not till we do this can we have any conception, corresponding to the real state of things; a conception, that is, of the position of objects not only with reference to each other but also with reference to our own body (*subjective orientation*). Such subjective orientation depends upon our having a knowledge of the position of our own body in space, and of the position which the eyes occupy in our body. The former is accomplished by virtue of the sense of equilibrium, the latter by the muscular sensations which originate in the ocular muscles, and which inform us how our eyes are directed with relation to our body. By means of subjective and objective orientation together, we are able to recognize correctly the absolute position in space of any object that we see.

FIG. 97.—BINOCULAR SINGLE VISION.

As a rule, we see with both eyes at once, these being so placed by means of their associated movements that their visual lines cross in the object looked at—i. e., we "fix" the object with both. The object *o* (Fig. 97) then forms an image in the fovea centralis (*f* and f_1) in both eyes. An object, o_1, situated to the left of the point of fixation, would cast an image at *b* and b_1, to the right of the fovea in both eyes, and in both eyes, moreover, equally far to the right of it. These images, as well as all others which are situated on symmetrically disposed spots of the two retinæ, are, according to the law of projection, located by both eyes at the same point of the outer world (*o*, o_1, etc.), and hence are seen single (*binocular single vision*).

Interference with binocular single vision is manifested by *binocular*

diplopia, which always makes its appearance when the visual axis of one eye deviates from the object of fixation. For example, the right eye, *R* (Fig. 98), fixes the point, *o*, while the visual axis, *g*, of the left eye, *L*, deviates inward because the eye has a convergent squint. The point, *o*, then forms an image at the fovea, *f*, in the right eye, but in the left it forms an image at b_1 to the right of the fovea, f_1. With the right eye the object is seen in its right place, *o*. With the left eye, too, the object would be seen at a point opposite the retinal image, *b*, that is, in its proper situation, *o*, and hence would be seen single with binocular vision, if the person possessing such an eye would proceed simply according to the law of projection. But this he does not do, because he is in error with regard to the way in which the left eye is directed. He knows nothing of the deviation of this eye inward, but has the idea that, like the right, it has its visual axis adjusted for the object. He therefore expects the image of the object to be at the fovea in the left eye as well as in the right. But as this is not the case, and the image, *b*, lies to the right of the fovea, he thence concludes that the object, *o*, has become displaced toward the left—that is, to o_1—since he knows from former experience that all objects situated to the left of the point of fixation throw their images to the right of the fovea. In this case, accordingly, the subjective orientation is not correct; the entire mosaic of retinal images in the left eye is located in space too far to the left, because the person who has such an eye has an erroneous impression in regard to the way in which it is placed in his head (Nagel, Alfred Graefe).



Fig. 98.—Homonymous Double Images.

The double images that have been here selected as an example are known as *homonymous*, because the image, *o*, seen upon the right side belongs to the right eye; the one, o_1, seen on the left belongs to the left eye. In practice this fact is determined by temporarily covering, first one eye and then the other, and asking the patient which of the two images in each case disappears. We can also place a colored glass before one eye and have the patient tell which of the two images is colored, and which appears of its natural hue. Homonymous double images depend, as the preceding demonstration shows, upon excessive convergence of the eyes.

Heteronymous or *crossed* double images are produced when there is

a relative divergence of the eyes. In Fig. 99 the left eye, L, deviates outward. The image of the point, o, therefore, falls to the left of the fovea, f_1, at b, for which reason the object itself is erroneously seen at o_1, to the right of the point of fixation, o. In this case the left image corresponds to the right eye, the right image to the left eye.



Fig. 99.—Crossed Double Images.

A *difference in the level* of the double images occurs when the eyes themselves stand on different levels. In Fig. 100 the eyes are represented as behind each other instead of side by side. The right, R, fixes correctly, but the left eye, L, is deviated upward. Hence, the image, b, of the point, o, falls above the fovea, f_1, in the left eye, and the person who has such an eye, because he believes that it is correctly placed, imagines that he sees the point, o, at o_1, below its true situation, since when the eyes are correctly placed all objects situated below the visual plane cast their images upon the



Fig. 100.—Double Images, with Difference in Level.

upper half of the retina. The image which stands lower, therefore, always belongs to the eye which stands higher, and vice versa.

Double images can also be *inclined* in such a way that their upper or lower extremities are approximated. This is the case when one of the two eyes has undergone a rotation about its sagittal axis and the

other has not. In Fig. 101 *A*, *R* and *L* represent the posterior halves of the two eyes seen from behind and imagined to be transparent, so that the inverted image of an arrow is seen as it is situated upon the retina. In the right eye the vertical meridian of the retina, *v v*, really does stand vertical, but in the left eye (v_1 v_1) it is supposed to be inclined. The image of a vertically directed arrow is also vertical in the two retinæ; hence, in the right eye it coincides with the vertical meridian, but in the left eye it forms an angle with the vertical meridian,

FIG. 101.—DOUBLE IMAGES WITH OBLIQUITY.

because this is inclined. Since, now, the left eye has been previously accustomed to consider as vertical only those objects the images of which coincide with the vertical meridian, it will consider the arrow as having an oblique position. Hence, two images of the arrow are seen (Fig. 101 *B*, *w* and *s*), of which that belonging to the left eye stands obliquely.

When there is binocular double vision, the two images do not look alike; one is more distinct than the other, and is hence known as the *true image*, in contradistinction to the *apparent image*. The true image is the one that corresponds to the eye which fixes the object. It is therefore, seen in its right place, and, moreover, is seen clearly, because it is perceived by the fovea. The apparent image belongs to the deviating eye. It is less distinct than the image of the other, eye because it is perceived by a peripheral spot of the retina; moreover, it is seen in the wrong place, so that the patient, if he tries to reach out to it, reaches to one side of it—hence apparent or false image.

A condition to be strongly differentiated from binocular diplopia is *monocular diplopia*. The former depends upon the fact that though

there is but one image of the object cast upon each one of the two retinæ, it is not thrown upon symmetrically situated spots; but the latter is due to the formation of two images of the same object upon *one* retina. Binocular diplopia, therefore, disappears at once when one eye is shut, while monocular diplopia persists, although but one eye—that is, the one which sees double—is open. In this fact lies the most certain differential sign between the two kinds of diplopia. The cause of monocular diplopia is either an anomalous refraction of the rays of light or the presence of a double pupillary opening. The former represents one form of irregular astigmatism (see §149), and has its seat either in the cornea or in the lens (particularly in the case of subluxation of the lens). In incipient cataract also monocular diplopia may develop as a result of the unequal refracting power of the different sectors of the lens, although in this case monocular polyopia (see page 365) is of much more frequent occurrence. A double pupillary opening produces diplopia when the eye is not adjusted for the distance at which the object of fixation is placed. It is most frequently found as a consequence of iridodialysis.

The lines of insertion of the four recti muscles are situated at unequal distances from the margin of the cornea, and usually, too, are not quite concentric with it. Moreover, they are not perfectly symmetrical in their relation to the horizontal and vertical meridians. The mean variations in regard to the position of the lines of insertion are shown as accurately as possible in Fig. 102, which represents the anterior half of the eyeball projected upon a plane. In it are marked the distances of the lines of insertion from the cornea in millimetres, as I have found them from the mean of a great number of measurements.

FIG. 102.—LINES OF INSERTION OF THE FOUR RECTI MUSCLES PROJECTED UPON A PLANE. NATURAL SIZE.

The muscles are surrounded by *fasciæ* which are continuous anteriorly with Tenon's capsule at the spot where the latter is reflected upon the tendons of the muscles. Lateral prolongations of the fasciæ unite the muscles together, and also pass from them to the bony wall of the orbit. By means of this system of fasciæ pervading the orbit, the contents of the latter are fixed in place. It is owing to them that the eye does not leave its place when performing its movements, but turns about a fixed center. The continuations of the fasciæ,

vation would then have become reduced to nothing. In like fashion, the action of the individual components can be deduced from the position of the eye for every other ocular muscle as soon as the course which it takes is accurately known. This fact is of importance for the diagnosis of paralyses of the ocular muscles, the failure of the paralyzed muscle being particularly marked in the direction of one or the other of the components of its action, according to the different way in which the eye is directed.

FIG. 104.—LINEAR MEASUREMENT OF THE LATERAL EXCURSIONS OF THE EYE. (AFTER ALFRED GRAEFE.)

The *measurement* of the excursions of the eyeball is an important matter not only for physiologists, but also for the ophthalmic practitioner, particularly for the determination of the degree of a paralysis, the progress of its improvement, the prognosis of a squint operation, etc. The simple process of linear mensuration, according to the method of Alfred Graefe, is applicable only to movements in a horizontal direction (abduction and adduction). The patient is first made to look straight forward at an object which has been placed at quite a distance from the eye in the middle line of the face. With the eyes in this middle position, the distance between the outer margin of the cornea and the outer angle of the eye (*cm*, Fig. 104) is measured with the circle. This distance is also measured when the eyes are turned as far inward and as far outward as possible (*ci* and *ca*). The difference between these values and the value for the middle position gives the magnitude of abduction and adduction of the eyeball. Suppose we have found *cm* to be 8 mm., *ci* 18 mm., and *ca* 1 mm.

FIG. 105.—NORMAL FIELD OF FIXATION. (AFTER LANDOLT.)

Then the adduction = *ci*—*cm* = 10 mm., and the abduction = *cm*—*ca* = 7 mm. The adduction and abduction together constitute the total range of lateral movement which, in the example selected, would amount to 17 mm.

This method of mensuration is attended with many inaccuracies, but, owing to its simplicity and the rapidity with which it can be performed, it is a very suitable one, particularly for cases of squint. An accurate measurement of the excursions can be made by means of the perimeter. The person examined supports his head on the chin-rest of the instrument in such a way that the eye to be tested (the other meanwhile must be kept closed) is placed at the center of the perimetric arc. Objects are then moved along the latter (large test-types being the best for this purpose) from the periphery toward the center, until the patient in looking at the object recognizes it distinctly (e. g., can name the letters, thus proving that he is really employing central fixation). Of course, in so doing, the movements should be made with the eye alone and not with the head. The limits thus found for the excursions of the eyes are set down upon an ordinary perimetric diagram. The region which is bounded by these limits, and which the eye has under its direct control through its excursions, is called the *field of fixation*. Fig. 105 shows the field of fixation of a normal eye according to Landolt. Paralyses of the ocular muscles manifest themselves by a corresponding limitation of the field of fixation.

Nerves of the Ocular Muscles.—Paralyses of the ocular muscles are a frequent symptom of cerebral affections. He who knows accurately the origin of the muscular nerves of the eye in the brain, and their course down to the orbit, will often be able to determine, from the kind of the paralyses and the way in which they are combined, the site of the lesion, and hence be able to give a more precise diagnosis of the brain-disease with respect to its nature and situation than would be otherwise possible. For this reason the most important points relating to the origin and course of the nerves of the ocular muscles will here be briefly given.

The movements of the ocular muscles are regulated by nervous centers of different rank. The lowest centers are the nuclei on the floor of the rhomboidal fossa [fourth ventricle] from which the trunks of the nerves themselves arise. Presiding over these are centers of higher rank, the association centers, for co-ordinating the actions of the individual ocular muscles. The centers of the highest rank are situated in the cortex of the brain; they are the cortical centers for the voluntary movements of the eye. These probably lie, not sharply separated from each other, in the motor sphere of the cerebral cortex.

The centers which are most accurately known are those of the first rank—i. e., the nuclei of origin of the nerves of the ocular muscles. These lie beneath the aqueduct of Sylvius and upon the floor of the fourth ventricle on both sides of the rhaphe. The most anterior of them is the nucleus of the *oculomotor nerve* (*III*, Fig. 106), which begins as far forward as the most posterior portion of the third ventricle, and extends beneath the aqueduct of Sylvius as far as the posterior pair of tubercles of the corpus quadrigeminum. It may be supposed to consist of a number of partial nuclei—i. e., of separate segments, each one of which corresponds to one of the muscles innervated by the oculomotor nerve. In what order the individual partial nuclei follow each other is not yet absolutely known. It appears, however, to be established that the most anterior

partial nuclei are set apart for the accommodation and for the pupil, and that next to them come those for the internal recti (convergence); succeeding these are the partial nuclei for the rest of the muscles supplied by the oculomotor nerve (Hensen and Völckers, Kahler, and Pick). Accordingly, the nuclei for those bundles of nerve-fibers which are always set into action simultaneously, especially the nerves for the contraction of the pupil (sphincter pupillæ), for accommodation, and for convergence, adjoin each other; these particular partial nuclei, in fact, occupying the most anterior part of the whole oculomotor nucleus.

The fibers coming from the nucleus of the oculomotor nerve pass through the crus cerebri downward to the base of the brain, where, uniting into a com-



FIG. 106.—NUCLEI OF ORIGIN OF THE NERVES OF THE OCULAR MUSCLES. SCHEMATIC SAGITTAL SECTION THROUGH THE CAUDEX CEREBRI. NATURAL SIZE.

The oculomotor nucleus, *III*, lies beneath the anterior pair of tubercles of the corpus quadrigeminum, *Q*. The fibers coming from this nucleus run, converging downward, and emerge as a united nerve-trunk, *O*, at the anterior border of the pons, *Po*. Directly behind the oculomotor nucleus lies the nucleus, *IV*, of the trochlear nerve, from which the trunk of the nerve passes upward. The two points (drawn of light color in the figure) directly above it, and at the posterior margin of the corpus quadrigeminum, represent the cross-sections of the trunks of the trochlear nerves as they decussate in the velum medullare anticum. The nucleus of the abducens, *VI*, lies upon the floor of the fourth ventricle, *4*, directly beneath the nucleus of the facial nerve, *VII*. The dotted band running from the nucleus of the abducens to the nucleus of the trochlear nerve represents the posterior longitudinal fasciculus connecting the nerve nuclei. The trunk of the abducens, *A*, emerges at the posterior border of the pons. *a*, shows the site of a lesion which, through destruction of the oculomotor nerve, *O*, and the pyramidal tract, *P*, *P*, would result in crossed paralysis of this nerve and of the extremities. In like fashion a lesion at *b* would produce crossed paralysis of the abducens and of the extremities. P_1, P_1, pyramidal tract of the other side; *Th*, optic thalamus.

mon trunk, they become visible upon the anterior border of the pons (*O*, Fig. 106). From this point the nerve-trunk runs through the cavernous sinus, and the superior orbital fissure into the orbit.

The nucleus of the *trochlear nerve* (*IV*, Fig. 106) follows almost directly upon the posterior extremity of the oculomotor nucleus, so that it might almost be regarded as the last partial nucleus of the latter. It lies beneath the anterior tubercles of the corpus quadrigeminum. But the fibers which arise from it do not join with the trunk of the oculomotor nerve, which runs downward, but pass in the opposite directions upward and toward the spinal column, into the velum medullare anticum. In this they pass over to the other side and

thus decussate with the fibers of the opposite nerve, and then come out upon the base of the brain, winding about the outer side of the crus cerebri.

The nucleus of the *abducens* (*VI*, Fig. 106) lies pretty far behind the nuclei of the other two nerves, and in the immediate vicinity of the facial nucleus (*VII*, Fig. 106), a little in front of the striæ medullares. The nerve-fibers arising from the nucleus pass downward between the bundles of the pyramidal tracts and become visible at the posterior border of the pons (*A*, Fig. 106). Both the trochlear and the abducens nerves, as soon as they have reached the base of the brain, run forward like the oculomotor nerve and pass through the cavernous sinus and the superior orbital fissure into the orbit.

Numerous fibrous connections exist between the nuclei of the nerves of the ocular muscles. These connections are made by means of the posterior longitudinal fasciculus—i. e., by those fibers which, on both sides of the rhaphe, run from before (above) backward (downward), and connect the nerve nuclei lying at different levels. Transverse connections also exist through the passage of fibers from the nuclei of one side to those of the side opposite. These connect not only the homonymous nuclei of the two sides (e. g., the two oculomotor nuclei), but also by the aid of the posterior longitudinal bundle connect nuclei which lie at different levels. Thus it is assumed that the fibers arising from the abducens nucleus (*a*, Fig. 107), while in part passing directly to the trunk of the abducens nerve of the same side (*e*), also in part cross the median line and become associated with the fibers arising from the nucleus of the oculomotor nerve of the other side (o_1) (Huguenin, Duval, Graux). Hence, the nerve-twig (i_1) which enters the internal rectus would bear fibers of twofold origin, those from the oculomotor nucleus of the same side (o_1) and those from the abducens nucleus of the other side (*a*). This arrangement probably serves the purpose of giving the internal rectus a double innervation according as it is going to act in the way of convergence or of associated lateral movement. The connection subserving convergence would be effected by the fibers arising from the oculomotor nucleus, which are set into action at the same time with the homonymous fibers of the opposite side, and thus produce a synergic contraction of the two interni. The contraction for lateral movement would start from the abducens nucleus, which stimulates simultaneously the external rectus of the same side and the internal rectus of the opposite side. Lesion of one abducens nucleus would abolish the movement of the eyes toward the same side, but would not abolish convergence, which could only be abrogated by a destruction of the oculomotor nucleus. In this way many cases of conjugate paralysis of the ocular muscles would be accounted for, in which the internus is no longer able to move the eye laterally in conjunction with the other eye, but is still able to produce a strong movement of convergence.



FIG. 107.—CONNECTION BETWEEN THE NUCLEI OF THE OCULOMOTOR AND THE ABDUCENS NERVES. SCHEMATIC.

Binocular Vision.—The fact of a person's seeing single with two eyes may be accomplished in two ways. Either he fixes correctly with both eyes and refers to the same spot the impressions produced in both (binocular single vision) or one of the two eyes fails to see, either because it is blind or because it suppresses the impression that it receives (monocular vision). How can we know which of these two conditions is present in any given case? We make the patient fix his gaze upon an object—e. g., a lighted candle at the distance of some metres. If, then, we see that one of the two eyes is evidently deviated, binocular single vision can not exist. If, nevertheless, there is single vision, this can only be explained upon the assumption that the image formed in the deviating eye is either not perceived or is suppressed. If manifest deviation of one eye can not be made out, we test in the following way to see if there is correct binocular fixation: While the person under examination fixes his gaze upon the lighted candle, we cover first one eye, then the other. If the two eyes are rightly placed, each will remain fixed in its position after the other is covered. But let us assume that the right eye deviates a little outward when the left is fixed upon the object. If, now, the former is covered, the left will continue in the act of fixation; but if the left is covered, the right has to be brought into the position of fixation by a movement of adduction. Hence, in covering the eye which is performing fixation, we notice a movement of adjustment in the non-fixing eye, the direction of which movement is precisely opposite to that of the previous deflection. This movement of adjustment is still distinctly visible when the deflection itself is too slight to be recognized with certainty. Another method of testing whether single vision depends upon the fusion of the two images or upon the suppression of one of them is as follows: A prism with its base down is held before one of the eyes (Fig. 112). If there was binocular vision before, two images would now necessarily be seen standing one above the other (o and o_1). But if there is still single vision, this can only occur because the image formed in one of the eyes is either not perceived or is neglected.

It is only a person who has binocular single vision that has also solid or *stereoscopic* vision. Hence, we may also test binocular vision with stereoscopic pictures, special samples of which have been made for this purpose. A particularly delicate test of stereoscopic vision—i. e., of the perception of degrees of depth—is by means of Hering's *experiment with falling bodies*. The person under examination looks with both eyes through a long tube at a slender thread stretched in a vertical direction. Little balls (glass beads or peas) are dropped along the thread, sometimes in front of it, sometimes behind. A man having proper binocular vision will tell every time, without delay and without mistake, whether the balls have fallen in front or behind the thread; but one having only monocular vision can at best guess at what takes place, and hence often makes a mistake.

Binocular single vision is converted into *binocular double vision* when one of the two eyes leaves the correct position of fixation. This takes place most frequently in consequence of disturbances in the muscular apparatus of the eyes, such as paralyses or contractures of the ocular muscles. But the eye can also be forced mechanically into an incorrect position—e. g., by tumors in the orbit, etc. Binocular double vision can readily be produced experimentally by pushing one eye a little to one side by pressure with the finger. Finally, double vision ensues whenever the excursions of one eye are limited, as compared with

those of the other by mechanical obstacles, as for example by symblepharon or by pterygium.

The position of the double images has been already considered above. The distance between the double images measured in degrees of arc corresponds precisely to the deflection of the deviating eye from the correct position, and can therefore serve as a measure for the degree of deviation. The linear distance between the double images, on the contrary, depends not only upon the degree of deviation, but also upon the distance to which the double images are projected. The greater this distance is, the farther apart the double images appear to be. When the double images stand very close to each other they overlap in part, so that only their outlines appear double. In this case the patient is often not aware that he sees double, but only complains of seeing indistinctly or complains that every object has a shadow.

Double images interfere with vision and cause confusion, so that every one tries to avoid them as far as he can. He does this by attempting to bring the eyes by suitable muscular effort into a proper position, so that the double images coalesce. This attempt at union or fusion of the double images is called the *tendency to fusion*. Frequently by virtue of it considerable obstacles opposing single vision are overcome. The following experiment shows this: We make the patient fix an object, *o*, and then hold before one of the eyes, for instance, the right one, a prism, *P*, whose base is directed toward the temporal side (Fig. 108). The rays coming from *o* are deflected toward the base of the prism, and would strike the retina of the eye at a point to the outer side of the fovea; but in that case, as the object forms an image at the fovea, f_1, in the left eye, crossed double images would be produced. To prevent this, the right eye is turned inward until the fovea, *f*, has moved outward sufficiently far to be impinged upon by the rays which have been deflected by the prism. Hence, to avoid seeing double, an increased effort of convergence is made, so that the visual lines cross at *h* instead of at *o*. By this convergence the prism is "overcome." By placing constantly stronger and stronger prisms before the eye, we find the strongest prism which can be still overcome by convergence; the maximum of convergence thus determined is known as the *adduction*. If the prism is placed before the eye with the base inward, the rays passing through it are deviated in, and the image of the object is thrown to the inner side of the fovea. The eye must then be turned outward in order to bring the fovea to the place of the image. In this case, accordingly, to produce single vision the prism is overcome by a diminution of the convergence, or, in other words, by a divergence of the eyes. The strongest prism which can be overcome in this way gives the measure of the *abduction*. The tendency to fusion also makes itself apparent



FIG. 108.—THE OVERCOMING OF A PRISM BY CONVERGENCE.

if a prism is placed before the eyes with its base up or down (Fig. 112). In this case there are formed double images with a difference of level, which have to be united by a deviation of one eye upward or downward. Quite strong prisms can be overcome by adduction, weaker ones by abduction; and only very feeble prisms (of 1° or 2°) can be overcome by vertical deviation of the eyes.

Monocular diplopia with double pupillary aperture (iridodialysis, perforation of the iris, division of the pupil into two parts by an opaque strand, etc.) takes



FIG. 109.—SCHEINER'S EXPERIMENT. (The eye is adjusted for the point *o*.)

place only when the eye is not properly focused; otherwise, there is single vision, even with a double pupil. This fact is accounted for by the well-known experiment of Scheiner. Two holes are made in a piece of card-board with a needle, the distance between them being somewhat less than the diameter of the pupil, so that, when looked through, both lie at the same time in front of the pupil.



FIG. 110.—SCHEINER'S EXPERIMENT. (The eye is not adjusted for the point *o*.)

Through this apparatus we look at an object—e. g., at a tightly stretched thread, *o*, at a distance of twenty-five centimetres. If the eye is focused for this distance, all the rays emanating from the object, *o*, are united upon the retina at the point, o_1 (Fig. 109). If, now, out of the whole cone of rays only

those are transmitted which pass through the two holes, these rays still unite to form an image at o_1; the only change which this image undergoes by having the diaphragm placed before it is an enfeeblement of its luminosity due to the cutting off of many rays. But if the eye is not focused for the distance of the object (Fig. 110), the apex of the cone of rays does not fall upon the retina, but (in this case) behind it at o_1. The cone of rays is cut off in front of its apex by the retina, so that the image of the point, o, is a disk (diffusion-circle), a, and the point looks completely blurred. But if now only two bundles of rays out of the entire cone are admitted to the eye through the diaphragm, each one casts its own smaller diffusion-circle (b and b_1); the point, o, is now seen more distinctly, it is true, but is seen double.

In myopia, especially of high degree, the complaint is sometimes made of monocular diplopia. This makes itself particularly apparent when rectilinear outlines, such as telegraph wires, the outlines of picture-frames, etc., become objects of fixation, they then appearing double. Here we are probably dealing with the effect of an irregular astigmatism.

I. Insufficiency of the Ocular Muscles.

124. In the normal state the eyes are in perfect *muscular equilibrium* in every natural—i. e., not forced—position. What the expression muscular equilibrium signifies is rendered clear by the following experiment: We cause the patient to fix an object at a distance of thirty centimetres with both eyes. Then we push a sheet of paper before one eye and watch behind the paper the eye thus covered. We shall find that the eye remains correctly adjusted for the object, although it no longer sees it. It remains steadily in the position of fixation because this is the position of equilibrium for the eye. This position is the resultant of the varying amounts of innervation which are supplied to the individual muscles and which are distributed among them in proper proportions.

Disturbances of muscular equilibrium are recognized by the same experiment. For, suppose that both eyes are properly adjusted for the object held before them. A screen is now held before one eye. This deviates behind the screen in some way—say outward. When then the screen is withdrawn, the visual axis of this eye is no longer directed at the object, but the eye has an outward squint. It hence has to be brought back to the position of fixation by a movement inward (movement of adduction). Hence, on withdrawing the screen we observe a movement of the eye in a direction precisely opposite to that of its deviation behind the screen (*movement of readjustment* or *redress*). This latter movement is generally easier to make out than the deviation of the eye behind the screen, and hence is currently employed as a means of recognizing the latter. If, on the withdrawal of the screen, the eye makes a movement of redress inward, it has been deviating out behind the screen, and vice versa. The phenomena that present themselves in this experiment are accounted for as follows: In the example

selected, in which the eye deviates out behind the screen, the two eyes during the act of fixation were not in muscular equilibrium, but the external ocular muscles preponderated over the internal muscles. Yet, so long as vision was performed with both eyes, there was correct fixation, because otherwise there would have been double vision. Now, there is a great antipathy toward double images and a correspondingly strong effort to secure single vision (tendency to fusion; see page 540). Hence, an amount of innervation in excess of the normal is conveyed to the interni, in order to oppose the preponderance of the external ocular muscles. But as soon as one eye is covered, diplopia can no longer take place; there is now no object in maintaining an excessive exertion on the part of the interni, and the eye in obedience to the preponderating force of the externi rolls outward. The position of equilibrium for this eye is therefore a pathological one—namely, a position of divergence to a certain amount. As soon as the screen is withdrawn again, double images make their appearance, which, however, are speedily united by the return of the deviating eye to its normal position once more.

The disturbance of equilibrium of the ocular muscles that has just been described is known as *insufficiency*. When the externi predominate, we speak of insufficiency of the interni; * in the opposite case, of insufficiency of the externi. †

Strabismus and paralysis of the ocular muscles are also disturbances of equilibrium. Insufficiency is distinguished from them by the fact that under ordinary circumstances it is not apparent, since it is compensated for by a correspondingly greater exertion of the feebler muscle. It is hence called latent or dynamic squint (Von Graefe).

The *causes* of insufficiency, giving one pair of muscles the preponderance over the other, are partly organic, partly functional.

(*a*) The *organic* causes depend upon anatomical conditions, such as the size of the muscle, the way in which it is inserted, etc. Matters that also come in for consideration are the size of the eyeball—since large eyes (in excessive myopia) are more difficult to move than small ones—the distance of the two eyes from each other, etc.

(*b*) As *functional* causes of insufficiency may be adduced general muscular weakness, after exhausting diseases or due to affections of the nervous system. But much greater significance attaches to those causes which spring from a disturbance in the relations between accommodation and convergence. These two functions in an emmetropic eye go hand in hand, so that with each definite degree of accommodation there

* [Also called *exophoria*, from ἔξω, outward, and φορεῖν, to tend (G. T. Stevens).—D.]

† [Also called *esophoria*, from ἔσω, inward, and φορεῖν, to tend. Similarly, insufficiency producing difference in level of the eyes—vertical insufficiency—is called *hyperphoria*, from ὑπέρ, above (G. T. Stevens).—D.]

is associated the quantum of convergence that belongs to it, and vice versa (see § 141). When such eyes accommodate for an object situated at a distance of thirty centimetres, for example, they also converge for the same distance, and hence are still in a state of muscular equilibrium. If an eye has an abnormal condition of the refraction, either myopia or hypermetropia, the quantum of accommodation required for any given distance changes accordingly. The myope requires less, the hypermetrope more accommodation than the emmetropic person. The convergence may adapt itself to these altered conditions, so that the harmony between the accommodation and the convergence is preserved. But very often this is not the case. A myope, for example, whose far point lies at thirty centimetres needs no accommodation at all to see an object at this distance distinctly. Hence, the necessary impulse for the requisite degree of convergence is wanting, because with the accommodation at rest the eyes tend to arrange themselves parallel to each other, and in this case an insufficiency of the interni will exist.

The reverse is true of hypermetropes who have to employ an excessive degree of accommodation for the distance of thirty centimetres. Consequently, there is a tendency to converge too strongly—a fact which gives the preponderance to the interni and produces the symptoms of insufficiency of the externi. The disturbances of equilibrium arising from the conjoined action of accommodation and convergence are of great importance, because they lie at the bottom of most cases of strabismus.

The *consequences* of an insufficiency vary according to its degree.

1. Slight degrees of insufficiency are overcome without difficulty by a correspondingly strong innervation of the weaker pair of muscles, and cause no trouble whatever.

2. Mean and extreme degrees of insufficiency impede the convergence which is required for every kind of close work, like reading, writing, and all the more delicate varieties of handicraft. Hence, the eyes get tired when the work is carried on too long; the object looked at grows indistinct and often looks double; and subsequently headache and even nausea set in. This condition is known as *asthenopia muscularis* (to distinguish it from accommodative and nervous asthenopia). It is a characteristic mark of it that the asthenopic difficulties disappear at once if the patient closes one eye and uses but one for fixation, since then no convergence is required.

3. The insufficiency of the interni which is so frequent in myopic eyes favors the progress of the myopia, because it makes convergence difficult and laborious.

4. High degrees of insufficiency often pass into strabismus, and, in fact, into divergent or convergent strabismus according as the external or internal recti predominate. The impulse for the transformation of insufficiency (or latent strabismus) into manifest strabismus is often

furnished by the fact that one of the eyes has its visual power reduced, so that binocular vision becomes of less utility or is actually abolished. Then the condition of affairs becomes the same as that which the experiment for testing insufficiency produces artificially, when one eye is covered and thus excluded from the act of vision. For this reason blind eyes are very frequently found to deviate out or in.

Treatment.—Only those cases of insufficiency which cause trouble or threaten to pass into strabismus call for assistance. The condition which mainly requires consideration in this point of view is insufficiency of the interni, which renders convergence difficult, and thus makes continuous work impossible. The defective convergence may be assisted by prisms. These are placed before both eyes in such a way that their base is directed inward (P and P_1, Fig. 111). The rays coming from the fixed point, o, are deflected by each prism toward its base.



FIG. 111.—EMPLOYMENT OF PRISMS IN INSUFFICIENCY OF THE INTERNAL RECTI FOR THE PURPOSE OF FACILITATING CONVERGENCE.

The eyes, therefore, need only converge, as though they were fixing the more remotely situated point, o_1. Both on account of the weight of the stronger prisms and of the chromatic dispersion that they cause, only those of 4°, or at most of 6°, for each eye can be used. They may be combined with spherical glasses. For higher degrees of insufficiency tenotomy is indicated. This is performed upon the muscles which have the preponderance—e. g., upon the externi in insufficiency of the interni.

We can test the capacity of convergence by bringing an object—e. g., the extended finger, held in the middle line—closer and closer to the person under examination. When the capacity for convergence is normal, the eyes can converge to the tip of the nose. If one of the eyes deviates out before this point is reached, this proves an insufficiency of the interni. But the converse conclusion, that there is muscular equilibrium if no deviation occurs, can not be

drawn. It is, in fact, quite possible that, when the tendency to fusion is great and a strong effort of the will is made, the extreme amount of convergence can be produced for a moment, while even moderate degrees of convergence can not be borne if they have to be steadily maintained. So, too, a weak man, by calling forth his whole energy, can make a single great exhibition of strength, while he is, nevertheless, unable to do hard work for an entire day. Hence, the surest method for discovering an insufficiency is still that which consists in alternately placing a screen before the eyes and withdrawing it again, when, if there is any insufficiency present, there is always a movement of redress upon the withdrawal of the screen.

For the numerical determination of the degree of insufficiency Von Graefe has proposed his *equilibrium test*. This starts from the fact that a disturbance of equilibrium becomes manifest as soon as binocular single vision is rendered impossible. To accomplish this, we place before one eye a prism with its base down or up and of such strength that it can not be overcome by an effort of the eyes acting to place them on different levels (see page 541). For example, we



Fig. 112.—Von Graefe's Equilibrium Test.

place the prism, *P* (Fig. 112 *A*), whose refracting angle amounts to 10°, with its base down before the left eye, and tell the person under examination to fix his gaze upon an object, *o* (e. g., a black dot upon white paper or when the object is to be at a greater distance, at a candle flame). The left eye now sees the object, *o*, not at its proper place, but at o_1; and hence with both eyes together there are seen double images on different levels. If there is muscular equilibrium, so that the eyes converge properly at *o*, the two images stand vertically over one another (*L* and *R*, Fig. 112 *B*). But if there is a disturbance of equilibrium, and consequently an excessive or a deficient convergence, a lateral separation of the images is superadded to the difference of level. In fact, the effort to compensate for the insufficiency by increased innervation of the feebler muscles now disappears, since the double images could not be seen as one in any

case on account of the difference of level. Now suppose, for instance, that the externi predominate. Then the left eye deviates out behind the prism. The point *o* consequently casts an image to the outer side (left) of the fovea, and is therefore seen too far to the right (crossed double images, Fig. 99). Hence, the upper point which belongs to the left eye no longer stands vertically above the lower, but to the right of it (Fig. 112 *C*). If now a second prism, the base of which looks inward, is placed before the prism which has its base down, the rays coming from the point are deflected by it inward toward the fovea, and the upper image moves to a point more nearly above the other. By trying stronger and stronger prisms we can at length find one which brings the two images exactly over each other in a vertical line. This corrects the lateral deviation of the eyes, and hence gives the numerical expression for the insufficiency. We usually determine the insufficiency in this way for two distances—namely, for infinite distance (i. e., 6 metres), and for the ordinary reading distance.

II. Paralysis of the Ocular Muscles.

125. Symptoms. 1. *Limitation of Movement.*—In paralysis of an ocular muscle the excursion of the eye toward the side corresponding to the action of the muscle that is paralyzed is diminished or entirely abrogated. If, for example, the external rectus of the right eye were completely paralyzed, the right eye could be brought only to the middle line and not beyond it to the right. When the paralysis is of slighter degree, the deficiency in motility is, of course, less considerable, and often can only be made out by comparison with the other, or sound eye. In very slight paralyses the defective motility is not marked enough to be recognized at all with certainty. This is particularly true of those muscles which have a complicated action, and, above all, of the two obliques. In these cases we must rely for our diagnosis upon the double images produced.

The result of the limitation of mobility is a lagging behind of the eye when an associated movement is initiated within the sphere of action of the paralyzed muscle. Thus, if in paralysis of the right externus a point, *o* (Fig. 113), situated upon the right should be the object of fixation, the left eye will be adjusted for it properly; but the right eye will not be turned sufficiently far to the right, and consequently its visual axis, *g*, will shoot off to the left of the object. The eye "squints" inward (*strabismus paralyticus*, or *luscitas* *). This squinting takes place only when the eye is turned in the direction of the sphere of action of the paralyzed muscle, and becomes more pronounced the farther the eye is moved toward this side; but in all directions of the gaze in which the paralyzed muscle does not have to participate, the eyes stand in their proper position. By this fact paralytic squint is distinguished from ordinary or concomitant squint, which is present

* *Strabismus*, from στρέφειν, to turn. The term *luscitas* comes from *luscus*, squinting, and is at present used exclusively for paralytic strabismus. From luscus is derived the French *louche*.

in all directions in which the eye is turned, and always in the same amount.

The measure of the deflection is determined by the angle *s* (Fig. 113), that the visual axis, *g*, makes with the line of direction, *r*, which passes from the object to the retina through the nodal point of the eye, and which gives the place of the retinal image, *b*. This deflection of the squinting eye is known as the *primary deviation*.

FIG. 113.—PRIMARY STRABISMIC DEVIATION IN PARALYSIS OF THE RIGHT EXTERNAL RECTUS.

While the patient keeps on looking at the object, *o*, a screen, *s*, is placed before the left eye (Fig. 114). Now the right eye takes up the task of fixation, it being presupposed that it can be really brought far enough to the right for this purpose. If now we look at the left eye behind the screen we shall find it turned strongly inward—much more so, in fact, than the right eye had been previously. The deflection of the sound eye when covered, which is measured by the angle s_1 (Fig. 114), is called the *secondary deviation*, which therefore exceeds the primary deviation in magnitude. It is accounted for as follows: When with both eyes uncovered the gaze was directed toward the right, the left internus and the right externus received the ordinary impulse for a movement to the right; but the right eye lagged behind the other in proportion as the right externus, owing to its impaired innervation, failed to answer to the impulse. If now the left eye is covered, the patient is compelled to make fixation with the right. He can accomplish this, supposing that the object does not lie too far to the right, by sending into the right externus a very strong impulse of innervation, although in so doing he still obtains only a very slight effect. He can not, however, innervate thus strongly the right externus alone, but can simply send out a very energetic impulse for a lateral movement to the right to both eyes—an impulse, therefore, which also affects the left internus. But in the latter the impulse has its full effect, so that the left eye is drawn very strongly to the right (inward). Thus, while in primary deviation it is a mere question of lagging behind of the eye, secondary deviation is produced by a powerful muscular traction; therefore, the secondary deviation is greater than the primary. This point, too, is of

importance in distinguishing between paralytic and concomitant squint, since in the latter the primary and secondary deviation are equal. To measure the magnitude of the primary and secondary deviation the best way of proceeding is to mark the position of the external margin of the cornea each time by an ink-dot upon the lower lid, as will be set forth more precisely in the section on strabismus (§ 127).

2. *False Orientation.*—With the paralyzed eye the patient does not see objects in their true place; for suppose that, when the right external rectus is paralyzed, he shuts the left eye and looks with the right alone at an object situated a little to the right hand—i. e., within the sphere of action of the paralyzed muscle—and then is told to point quickly at the object with his extended index-finger: as he does so, the finger will always be carried to the right of the object, whence it follows that the latter is seen too far to the right (*Von Graefe's groping-test*). The same phenomenon comes to light when the patient tries to walk straight toward a given point with the help of his paralyzed eye, the other being closed. He takes a wavering and zigzag course, first bending his steps too far to the right, then recognizing his mistake and correcting it; then deviating anew to the right, and so on.

The explanation of this occurrence is similar to that which has been given for binocular diplopia (page 530). The object is falsely localized, because the patient is in error in regard to the position which his eye occupies. When (Fig. 115) the patient with his paralyzed right eye so fixes the object, *o*, which is placed somewhat to the right of him, that it forms an image upon the fovea centralis, *f*, he can accomplish this only by the strongest possible innervation of his paralyzed externus. Now, the ideas which we have with respect to the position of our eyes depend upon our sensations with regard to the innervation of the individual muscles. The patient, therefore, is compelled to believe that the right



FIG. 114.—SECONDARY STRABISMIC DEVIATION IN PARALYSIS OF THE RIGHT EXTERNUS.

treme cases not until the gaze was directed quite laterally (as when, for example, the patient looks behind him to the right). From the direction of the eyes in which double images and strabismus make their appearance, from the position of these double images with respect to each other, and from the way in which their distance apart increases or diminishes according to the different directions in which the eyes are looking, we diagnosticate which of the ocular muscles is paralyzed, and whether we are dealing with a complete or an incomplete paralysis.

4. *Vertigo.*—This is the result both of the false orientation and of the diplopia. It often makes its appearance even in walking upon a level floor, but does so still more in going up and down steps, in performing complicated manipulations, in doing work, etc., and makes the patients unsteady and timid, and even excites a tendency to vomit. This kind of vertigo is known as visual vertigo, and is distinguished from other kinds by the fact that it disappears at once when the paralyzed eye is covered. Most patients hit upon this fact themselves, and in walking keep the paralyzed eye closed, either by shutting it or by covering it with a bandage. Another way of preserving themselves from visual vertigo lies in the—

5. *Maintenance of an Oblique Position of the Head.*—A patient in whom, for example, the right externus is paralyzed, keeps the head turned to the right. If he looks forward with his head in this position, both eyes are turned somewhat to the left, in which position the right externus does not come into play, and in which, therefore, paralysis of it does not make itself evident. And so for every variety of paralysis of the ocular muscles there is a definite position of the head, which diminishes the visual vertigo, and which is so characteristic of the paralysis that the skilled observer is able from it alone to suspect the nature of the latter.

Old Paralyses.—The characteristic symptoms of a paralysis are more unmixed and more pronounced the more recent it is. If the paralysis gets well after the lapse of not too long a time, the symptoms that have been produced by it disappear, and normal binocular vision is restored; if, on the other hand, the cure of the paralysis takes place only after a long time has elapsed, or does not take place at all, the symptomatic picture changes as follows: 1. The mistakes in orientation, particularly as they make their appearance in Von Graefe's groping-test, gradually cease; the patient learns by experience that the impulses of innervation for his paralyzed eye correspond to much slighter actions than those for the sound eye, and by taking account of this fact he once more forms a correct judgment of the situation of objects. 2. The diplopia disappears because the sensory perceptions of the paralyzed eye are suppressed (exclusion). 3. Contracture of the antagonists of the paralyzed muscle gradually sets in. Thus, in paralysis of the right externus, it is the right internus that becomes short-

ened; and so, while in a recent paralysis of the externus, the eye, when the gaze is directed straight forward, stands in the middle line, it afterward becomes drawn in more and more, and can no longer be brought up to the median position. The result of this is an increase in the paralytic strabismus, this reaching a higher degree and becoming manifested over a more extensive area than before, since it exists not only upon the side of the paralyzed muscle but also over the entire field of fixation. Owing to this fact, paralytic strabismus acquires a constantly greater and greater resemblance to concomitant squint, so that sometimes the distinction between the two becomes very difficult. The contracture of the antagonists may even persist when the paralysis itself is cured, and may thus prevent the restoration of binocular vision.

126. Mode of Occurrence.—Paralysis may affect simply one muscle, or it may affect several muscles in different combinations.

1. Paralysis of *one single muscle* most usually affects either the external rectus or the superior oblique, because each one of these muscles is supplied by an independent nerve (abducens and trochlearis). All the other ocular muscles are innervated by the oculomotor nerve, for which reason paralysis of any single one of them is of less frequent occurrence.

2. For the reason just mentioned, *simultaneous paralysis of several muscles* is found most frequently in those supplied by the oculomotor nerve, and of these muscles some or all may be affected at once. *Complete oculomotor paralysis* presents a characteristic picture. The upper lid hangs loosely down (ptosis), and has to be drawn up with the finger to give a view of the eyeball, which is deflected strongly to the outside and somewhat down, because the two muscles not paralyzed—the external rectus and the superior oblique—draw it in this direction. The pupil is dilated and immobile (paralysis of the sphincter pupillæ), and the eye is focused for the far-point and can not accommodate for near by (paralysis of the ciliary muscle). A slight degree of exophthalmus exists because three of the recti, which normally draw the eyeball backward into the orbit, have lost their tone.

Other muscles besides those innervated by the oculo-motor nerve may be affected, and the paralyses may affect not simply one but both eyes. In this way many manifold combinations are formed, of which the following are the most frequent: (*a*) All the eye-muscles in one or both eyes are paralyzed, so that the lids hang loosely down, the eyes are directed immovably forward, and there is dilatation of the pupil, with abolition of the accommodation (*ophthalmoplegia totalis*). (*b*) The paralysis affects only the external eye-muscles, while the internal muscles of the eye (sphincter pupillæ and ciliary muscle) are intact (*ophthalmoplegia externa*). This is more frequent than total ophthalmoplegia, and finds its explanation in the arrangement of the nerve nuclei below the aqueduct of Sylvius. This arrangement is such that the

nuclei for the sphincter pupillæ and the ciliary muscle lie farthest forward (see page 537), and hence frequently remain exempt from processes which destroy the more posteriorly situated nuclei of the other ocular muscles. For this reason ophthalmoplegia externa can only be of central (nuclear) origin. (*c*) *Ophthalmoplegia interna* forms the converse to ophthalmoplegia externa, as in it only the interior muscles of the eye are paralyzed. It can be produced artificially by means of atropine.

3. There are combined paralyses which do not affect the individual muscles, but affect associated movements. Thus the ability to look to the right or left, or to look up or down, etc., may be lost. These are known as *conjugate paralyses* (Prevost). The most characteristic cases of this sort are those of paralysis of the lateral rotators. There may, for example, be a paralysis of the associated movements to the right. If the patient then fixes his gaze upon an object which is carried in front of him from left to right, the eyes follow it until it has got to the middle line; then both eyes stand still without being able to move farther to the right. One might suppose that he was dealing with a paralysis of the right externus combined with one of the left internus. But this idea can be readily disproved by approximating an object to the patient along the middle line. The patient converges upon the object until it is very close to him, and hence can use his left internus perfectly for purposes of convergence, while the same muscle is paralyzed in its capacity of rotator to the right. The cause of conjugate paralyses are lesions in the association centers of the nerves for the ocular muscles.

Etiology.—Paralyses of the ocular muscles are the result of a lesion which may be situated anywhere in the course of the nerve-tract, from its very beginning in the cerebral cortex to its termination in the muscle itself. According to the site of the lesion, paralyses are distinguished into intracranial and orbital.

In *intracranial* paralyses the focus of disease lies within the cranial cavity. It may affect the centers of highest rank which lie in the cortex of the brain (cortical paralysis), or the association centers, or, lastly, the centers of lowest rank—i. e., the nerve nuclei upon the floor of the fourth ventricle (nuclear paralysis). The bands of fibers, likewise, which connect these centers and those fibers which run from the nuclei to the surface of the brain and unite there to form the nerve-trunks, may be injured (fascicular paralysis); and the nerve-trunks themselves may be affected in their course along the base of the skull (basal paralysis).

Orbital paralyses are those in which the lesion is seated in the nerve-trunk and its branches, commencing from the entrance of the nerve into the orbit through the superior orbital fissure, and extending to its termination in the muscle.

To diagnosticate the site of the lesion we must take account of the character of the paralysis, and particularly of those accompanying symptoms which point to an intracranial or to an orbital lesion.

As regards its *nature*, the lesion may develop as a primary affection in the nerves or in their areas of origin, these being attacked by inflammation or by simple degeneration. Much more frequently, however, these structures suffer indirectly as a result of disease in their vicinity, such as exudates (especially in the meninges), thickenings of the periosteum, neoplasms, hæmorrhages, injuries, etc., by which the nerves or their nuclei are thrown into a condition of inflammation, are compressed, or are in some other way subjected to injury. Among the vascular changes which are to be enumerated as causes producing lesions of the nerves supplying the ocular muscles are atheroma, aneurism, and occlusion of the vessels.

The *cause* of the lesion is frequently to be sought for in some general disease. Among these syphilis is the most usual cause of paralyses of the ocular muscles. Other diseases that result in these paralyses are tuberculosis, tabes, diabetes, toxic affections, disseminated sclerosis, hysteria, in fact, the most various diseases of the brain, including particularly those of focal character and those situated at the base of the skull. Among acute infectious diseases, diphtheria is the most frequent cause of paralyses of the ocular muscles. Injuries may affect the nerves of the ocular muscles in the orbit, or, in the case of fracture of the skull, in their intracranial course. Rheumatic paralyses are very frequent. By this term we understand those paralyses in which, judging from the accompanying symptoms, the lesion is situated without the cranial cavity, and for which no cause can be found except possibly the action of cold. It is for this latter reason that they have been called rheumatic paralyses.

Course and Treatment.—The paralyses either set in suddenly or develop in an insidious manner. Sometimes relapses occur. The course of the paralyses is always chronic. Even in the most favorable cases six weeks and more are required for a cure, and many paralyses are absolutely incurable. Whether this is so or not depends mainly upon the cause which lies at the bottom of the paralysis, and which, therefore, must first of all be taken into consideration in making the prognosis. Another means for determining the latter is afforded by the duration of the paralysis, since old paralyses, on account of the secondary changes which set in (atrophy of the paralyzed muscle and contracture of its antagonist), no longer hold out any prospect of a cure.

Treatment has first of all to take account of the causal indication. In this respect syphilitic and rheumatic paralyses afford the best prognosis. In the former an energetic antisyphilitic treatment with iodine and mercury is indicated. In the latter we give sodium salicylate, and employ diaphoresis (also by means of sodium salicylate or by

means of pilocarpine). The symptomatic treatment consists mainly in the local application of electricity, administered principally under the form of the constant current, rarely under that of the induced current. Exercise of the paralyzed muscle with the aid of prisms is also sometimes employed with advantage.

Besides the treatment of the paralysis itself, it seems also requisite, until the cure has been accomplished, to relieve the patient from the annoyance which the diplopia and the vertigo bring with them. When we are dealing with very slight paralyses we can unite the double images by means of prisms set in a suitable position; in this case the patient is made to wear the prisms under the form of glasses. In more marked paralyses prisms do not suffice to compensate for the incorrect position of the eyes. Then there is no other way of relieving the diplopia than to bandage the paralyzed eye, or, better still, to apply glasses which have an opaque plate for the paralyzed eye.

In old paralyses in which contracture of the antagonists has set in, we can get a result only by operative treatment. This consists in section of the contracted muscle with simultaneous advancement of the muscle that is paralyzed (see § 165). The latter is thus put under more favorable mechanical conditions for working—conditions, to be sure, of which it can avail itself only if it still possesses a certain degree of contractility. Complete paralyses, therefore, with marked failure of motility are incurable even by operation.

To make the *diagnosis* of paralyses of the ocular muscles, it is not sufficient to know the signs of the paralysis of each individual muscle and then see to which of them any case that may be before us fits. In this way, to be sure, we would quickly make the diagnosis in the typical and uncomplicated cases, but in the numerous cases of combined paralysis we would be helpless. A much more proper way of going to work is to determine exactly all the symptoms in any given case, and from them find out in what directions the motility of the eye is incomplete; then, with the aid of a precise knowledge of the method of action of each ocular muscle, we can make out which one or which two or three of the muscles are paralyzed. This method of examination may be illustrated by the following concrete example:

A patient comes complaining of diplopia. We first determine that we are dealing with binocular (not monocular) diplopia, from the fact that, as soon as one of the eyes is covered, there is single vision. Then we make the patient fix his gaze upon a pencil held in front of him, and while moving this in different directions we notice whether both eyes follow it uniformly. We observe that this is the case in all directions of the gaze except when the eyes are cast down. When the attempt is made to look down, the left eye does not sink as low as the right, and at the same time converges rather too much. We are, therefore, dealing with a paralysis of one of those muscles which depress the left eye—that is, of the left inferior rectus or the left superior oblique. To distinguish between these two we examine the double images.

We again carry the pencil in different directions in front of the patient's eyes, and determine that the pencil is seen double chiefly in the lower half of

left. This corresponds to the upper extremity of the retinal image (*p*, Fig. 101 *A*), which then must lie to the right of the vertical meridian of the retina, $v_1 v_1$, since its projection externally lies to the left of the vertical. The retinal image, however, really lies vertically in the retina, since the object stands vertically in space. Hence, the above statement is better expressed thus: The upper half of the vertical meridian of the retina lies to the left of the upper extremity of the vertically placed retinal image. Hence, it follows that the vertical meridian has its upper half inclined to the left, or outside, and its lower half inclined to the right, or inside.

What paralysis corresponds to this position of the vertical meridian? The superior oblique (*s*, Fig. 101 *A*) rotates the eye in such a way that the vertical meridian has its upper extremity inclined inward; the inferior oblique (*i*, Fig. 101 *A*) tends to incline the upper extremity of the vertical meridian outward. In a state of health these two muscular actions are in equilibrium in the primary position of the eyes, so that the vertical meridian really does stand vertical. But if the action of the superior oblique is abrogated in consequence of paralysis of the muscle, the inferior oblique gets the upper hand and draws the meridian toward its own side, so that the upper extremity of the meridian is inclined outward. Since this is the position of the meridian which we conclude to exist in our case from the obliquity of the double images, our diagnosis of a paralysis of the superior oblique is thus confirmed.

If the inferior rectus had been paralyzed the apparent image would have been inclined in the contrary direction. The inferior rectus inclines the upper extremity of the vertical meridian outward, and when, owing to paralysis of the muscle, its action ceases, the vertical meridian assumes the opposite inclination — i. e., with its upper extremity inward. This position would be just the opposite of that present in our case, and hence, too, the obliquity of the apparent image would be in a direction contrary to that actually observed.

For a complete examination of the case it would also be requisite to test the position of the double images in the different directions in which the eye is turned. The action of the superior oblique is made up of three components, the magnitude of which varies according to the position which the eyeball occupies at the moment when they come into play. Consequently, the horizontal separation, the difference in height, and the obliquity of the double images undergo characteristic changes according as the direction of the gaze is varied. Moreover, we may perhaps be informed by the patient that the apparent image seems to stand closer to him than does the real image. This is a peculiar condition, which is also quite frequently observed in paralysis of the inferior rectus. We must further try to discover whether the double images can be united by a prism, and what the strength and the position of this prism would have to be. Finally, the way in which the patient holds his head must be considered. In paralysis of the superior oblique this attitude is such that the head is bent forward, and at the same time is rotated toward the sound side.

To facilitate the diagnosis of paralyses of the ocular muscles for the beginner, there is placed on the following page a schedule showing the position of the double images and their relation to each other in the different directions in which the eye is turned. The position of the images is shown in the figures appended, in which the dotted outline represents the false image, and hence corresponds to the paralyzed eye.

Relation of the Double Images in Paralyses of the Ocular Muscles.

(The apparent image has a dotted outline.)

Left-sided Paralysis.

Right-sided Paralysis.

External Rectus.

Fig. 117.

Diplopia appears in looking toward the paralyzed side.

The lateral separation of the images increases as the paralyzed eye is abducted.

Fig. 118.

Internal Rectus.

Fig. 119.

Diplopia on looking toward the sound side.

The lateral separation of the images increases in adduction.

Fig. 120.

Superior Rectus.

Fig. 121.

Diplopia on looking up.

The vertical distance between the images increases as the eye is elevated and abducted.

The obliquity increases in adduction.

The lateral separation of the images diminishes when the eyes are turned laterally in either direction.

Fig. 122.

Inferior Rectus.

Fig. 123.

Diplopia on looking down.

The vertical distance between the images increases as the eye is depressed and abducted.

The obliquity increases in adduction.

The lateral separation of the images diminishes when the eyes are turned laterally in either direction.

Fig. 124.

Superior Oblique.

Fig. 125.

Diplopia on looking down.

The vertical distance between the images increases as the eye is depressed and adducted.

The obliquity increases with the abduction.

The lateral distance between the images diminishes when the eyes are turned laterally in either direction.

Fig. 126.

Inferior Oblique.



Fig. 127.

Diplopia on looking up.

The vertical distance between the images increases as the eye is elevated and adducted.

The obliquity increases with the abduction.

The lateral distance between the images increases as the eye is elevated and abducted.



Fig. 128.

The diagnosis as to which muscle is paralyzed often presents considerable difficulties even to the adept, if the case is complicated. This occurs—

1. When several paralyses are combined, particularly in both eyes, and the paralyses are partly complete, partly incomplete.

2. When a disturbance of muscular equilibrium under the form of an insufficiency was previously present. Such a disturbance is converted from a latent into a manifest one when the paralysis sets in, as binocular vision becomes impossible on account of the latter in spite of the tendency toward fusion.

3. When the two eyes have an unequal visual power, and the paralysis affects the better eye. The latter then is used to fix with, and the non-paralyzed eye is in a condition of secondary deviation. In such a case it is easy for the sound eye to be regarded as the paralyzed one.

4. When, in old paralyses, a contracture of the antagonists has taken place.

The difficulties of diagnosis are often increased by lack of intelligence or by insufficient attention on the part of the patient, in consequence of which it is impossible to determine with precision the position of the double images. It is also impossible to do the latter when, as in old paralyses, there is a tendency toward the suppression of the double images. In this case we must try to prevent the suppression of the false image by making it as well marked as possible—e. g., by selecting an object, such as a candle-flame, which catches the attention of the eye, or by placing a colored glass before the eye so as to give the image a distinguishing tint.

Measurement of the Paralysis.—A precise determination of the degree of paralysis is particularly desirable in order to be able, in the course of treatment, to calculate whether the paralysis is really undergoing recession or not. The measurement is made with the help of the double images; the region which these occupy being displaced farther and farther toward the periphery of the field of fixation, and the distance between them becoming smaller and smaller as the paralysis decreases.

1. The simplest way of estimating the position and the degree of separation of the double images consists in placing the patient at a distance of two or three metres from a wall upon which a point lying directly opposite one of his eyes has been marked as a point of departure. Starting from this point we carry an object which the patient is to follow with his eyes in different directions. We mark on the wall the points where the object begins to appear double, and also the degree of separation of the double images projected upon the wall in the different directions in which the eye is turned. By repeating this test in the same way at certain intervals of time we determine the alterations in the diplopia. Inasmuch as we know the distance of the patient from the wall and the linear distance from each other of the double images projected upon the wall, we can readily calculate the angle by which the paralyzed eye falls short of the line of fixation—that is, the angle of primary strabismic deviation (Landolt).

2. If we have a perimeter at our disposal, we can project the double images upon a hollow sphere instead of upon a plane, in which case we shall find the angle of the strabismus directly, and not have to get at it by calculation. We make the patient sit in front of the perimeter as in the process of determining the field of vision; then, by carrying the mark used as an object of vision along the perimetric arc, we ascertain the point where it begins to appear double.

3. We can also by means of the perimeter determine the field of fixation, and, from the way in which it is limited, judge of the degree of the paralysis.

4. We try to find the prism which in any given direction of the eyes corrects the strabismic deviation, so that the double images are fused into one. The angle of strabismus then amounts to one half of the refracting angle of the prism, since for weak prisms the law holds good that they deflect the rays through one half the angle which the refracting edge incloses. So, if double images are united by a prism of 20°, the strabismic deviation amounts to 10°.

An indispensable condition for the precision of all these methods of mensuration is that, while they are being performed, the patient should move his eyes alone, and not his head.

Site of the Lesion.—Paralyses of the ocular muscles constitute for the clinician engaged in the study of internal diseases one of the most important means of determining the site of a cerebral affection. Hence, we shall now enter more particularly into the consideration of the diagnostic points from which we can determine in what part of the nervous tracts the lesion occurs.

1. Lesions of the *centers of higher rank*, situated above the nerve nuclei (that is, the cerebral cortex, the association centers, and the fibers connecting these parts with one another and with the nuclei—regions which are all comprised under the name of intra-cerebral tracts), never cause paralyses of individual ocular muscles. If, therefore, isolated paralyses are present, lesions of as high a situation as this can be excluded. The only exception is ptosis, as this sometimes is met with as an isolated phenomenon in cortical affections.

2. Lesions of the *association centers* cause conjugate paralyses. The eyes are unable to turn in some special direction, and then are not infrequently found to be drawn toward the opposite side by a spasmodic contraction of the antagonists. Thus, for example, in paralysis of the lateral rotators to the right, not only is it impossible to turn the eyes to the right, but it may be that both eyes are turned continuously and strongly to the left (*conjugate deviation*). Conjugate paralyses, with or without deviation of the eyes to the opposite side, occur in disease of the crura cerebelli ad pontem, of the pons, of the corpora quadrigemina, and of the great ganglia of the brain, particularly of the thalamus opticus.

3. Lesions of the *nuclei* on the floor of the fourth ventricle (nuclear paralyses) produce for the most part paralyses of several ocular muscles. The paralysis generally attacks one muscle first and then gradually extends to the others. In this way there is developed what is known as *central ophthalmoplegia*, which is usually chronic, rarely acute, in its onset. It may be unilateral or bilateral. In most cases the interior muscles of the eye (those of the pupil and accommodation) remain exempt from the paralysis, because the nuclei for them lie farthest forward, and belong to a different vascular district from the nerve-nuclei that lie farther back, so that they are not involved with them in the disease. In these cases of ophthalmoplegia externa the diagnosis of nuclear paralysis can be made with perfect certainty; for it is not conceivable that a lesion affecting the nerve-trunk itself should destroy all the rest of its fibers, and leave intact only those which are designed for the interior muscles of the eye. But if there is an ophthalmoplegia totalis—that is, one in which all the muscles are paralyzed without exception—the site of the lesion may vary. We may be dealing with a nuclear paralysis, in which the disease has passed on to the most anterior nerve-nuclei as well; but cases of ophthalmoplegia totalis may also originate in a

lesion of the trunk of the nerve at the base of the brain, or even within the superior orbital fissure. In this case, therefore, the diagnosis of the site can be made only from the accompanying symptoms.

A primary affection of the gray substance of the nuclei of the nerves of the ocular muscles lies at the bottom of most cases of ophthalmoplegia (Wernicke's polioencephalitis superior). In its nature this affection is analogous to that which in bulbar paralysis attacks the motor nuclei situated farther down the facial, glosso-pharyngeal, hypoglossal, and vago-accessorial nuclei); and as a matter of fact several cases have been observed in which, by an extension of the process downward, an ophthalmoplegia has had associated with it the symptoms of bulbar paralysis. The most frequent cause of the disease of the nerve-nuclei is syphilis; but cases of central ophthalmoplegia due to diphtheria, influenza, tabes, disseminated sclerosis, traumatism, and poisoning (by alcohol, lead, carbon-monoxide gas, and nicotine), and also cases of congenital ophthalmoplegia, are known.

Paralyses of individual muscles also may arise as a result of lesion of the nerve-nuclei. In this category belong, first of all, the paralyses which appear in the beginning of tabes dorsalis, and, although somewhat less frequently, in disseminated sclerosis, and which in all probability are of nuclear origin. Tabetic paralyses, on the whole, give a favorable prognosis, as after some time they usually disappear spontaneously, in spite of the progress of the causal disease. Still, there are cases in which the paralyses either do not retrogress at all, or else recur after retrogression. By a nuclear lesion the abducens can be paralyzed at the same time as the facial, since the nuclei of these two nerves lie close together.

4. *Fascicular paralysis* due to lesion of the fibers between their point of departure from the nerve-nuclei and their emergence at the base of the brain, may be diagnosticated if there is paralysis of the oculomotor nerve of one side with simultaneous paralysis of the extremities of the opposite side (alternate paralysis). In this case, then, a focus of disease must be assumed to exist in the lower part of the pedunculus cerebri (*a*, Fig. 106). Such a focus of disease causes injury both to the fibers of the oculomotor nerve as they pass through the peduncle, so that the oculomotor nerve of the same side is paralyzed, and to the pyramidal tract; but as the latter crosses over to the other side below this point, the extremities are paralyzed on the side opposite to the lesion. Such a paralysis, however, might also be produced by a focus of disease at the base of the brain, if the disease were situated so near the peduncle as to cause injury to it. An intrapeduncular site of the lesion in alternate paralysis of the oculomotor nerve and the extremities can not with certainty be assumed to exist, except when the fibers destined for the interior muscles of the eye have escaped paralysis, inasmuch as within the peduncle the fibers of the nerve still lie so far apart that the most anterior of them may remain unaffected by the lesion. In analogous fashion an alternate paralysis of the extremities and of the abducens (and also of the facial) argues the existence of a focus of disease in the posterior part of the pons, or in the portions of the base of the brain adjoining it (*b*, Fig. 106).

5. Lesions at the *base of the brain* may likewise affect one nerve or several, and not infrequently affect both sides at once. The facts which with more or less probability lead us to infer the existence of a basal paralysis are: (*a*) When a whole series of cerebral nerves upon one side, such as the oculomotor, the

facial, the trigeminal, the optic, and the olfactory nerves, are paralyzed one after another. (*b*) When the affection of the trigeminus begins under the guise of a neuralgia; the latter not being observed in central paralyses. (*c*) When one eye is perfectly blind while the other still sees, and the ophthalmoscope does not afford evidence of any changes sufficient to account for this state of things. From such a condition, in fact, the conclusion may be drawn that the lesion involves the intracranial segment of one optic nerve. Interruptions of the optic conducting paths higher up can not affect one eye alone; on the contrary, they always lead to visual disturbance of both eyes under the form of hemiopia. Hemiopia, to be sure, can also be caused by a basal lesion—which, however, must in every case be situated behind the chiasm, so as to implicate one of the two optic tracts; but hemiopia may also, and quite as readily, originate in a lesion situated higher up, even as far as the cerebral cortex. Hemiopia, therefore, is neither an argument for nor against a basal lesion; that is, this is the case in homonymous hemiopia; temporal hemiopia, is of course, a certain sign of a lesion at the base, affecting the chiasm at the anterior or posterior angle, or in the middle line (see page 429). (*d*) Paralysis of the olfactory nerve argues the existence of a basal affection in the anterior fossa of the skull.

A basal paralysis can with certainty be excluded when there is an oculomotor paralysis in which the interior muscles of the eye do not share. Such a paralysis can only be of nuclear origin.

Of probably basal origin are the cases of frequently recurring oculomotor paralysis, of which some twenty are now known. These are usually observed after injuries, although some cases were of hysterical origin. Leber has described a bilateral paralysis of the abducens which was caused by the pressure of the carotid upon the nerves that directly adjoined it.

6. The diagnosis of an *orbital* paralysis must be made from the accompanying symptoms, when these are indicative of an affection within the orbit. Among such symptoms are pain in the orbit, either spontaneous or excited by pressure upon the eyeball or upon the margin of the orbit, a deeply situated tumor discoverable by palpation, protrusion of the eyeball, unilateral optic neuritis due to pressure on the optic nerve, and finally the history of an antecedent trauma which has affected the orbit.

Paralyses of the ocular muscles may be of *congenital* occurrence. Mention has already been made of congenital ophthalmoplegia. The most frequent congenital paralyses are those of the abducens. It is a remarkable fact that in these, contrary to what takes place in the acquired paralyses, contracture of the antagonists does not set in; both eyes have a perfectly proper position as long as the gaze is not directed toward the side of the paralyzed muscle. An inability to turn the eye upward has been observed occurring coincidently with congenital ptosis. Autopsies have shown that in this case the superior rectus was absent. Perhaps similar defects lie at the bottom of many other congenital paralyses.

III. Squint.

127. Symptoms.—Squint consists in a deviation of the visual axis of one of the eyes from the correct position of fixation upon an object, the deviation occurring in every direction in which the eyes are turned, and always through the same angle. Squint is thus distinguished from

paralysis, in which on the one hand the deflection is present only in the sphere of action of the paralyzed muscle, and, on the other hand, when once within the limits of this sphere, it becomes greater and greater the farther the eye is carried into the latter, because then the paralyzed eye lags more and more behind the sound one. A squinting eye, on the contrary, does not lag behind the other in any direction in which the eyes may look, but accompanies it in all its movements, and always deviates to the same degree from the correct position, for which reason squinting is known as *strabismus concomitans.*

The simplest way of going to work to measure the strabismic deviation is as follows: We cause the patient to fix his gaze upon an object which we have placed in the median line between the two eyes, and at



FIG. 129.—MEASUREMENT OF STRABISMIC DEVIATION.
A, primary position; *B*, secondary position.

a distance from them of some metres. Suppose that the left eye (*L*, Fig. 129 *A*) fixes correctly, while the right eye, *R*, squints inward. We then mark by an ink-dot upon the border of the lower lid the position of the external margin of the cornea in both eyes (m_1 and s). We next cover the left eye, which is doing the fixation, with a screen, *S* (Fig. 129 *B*), at the same time telling the patient to try to find the object again. He does so by now using the right eye for fixation, and for this purpose brings it into the correct position by a distinctly visible movement of redress. We now once more mark the position of the outer margin of the cornea of this eye by a dot, *m*, upon the lower lid; the distance, *m s*, then gives the linear measure for the deviation of the squinting eye—that is, gives the *primary strabismic deviation.*

As the right eye is being brought into the position of fixation, the left eye moves inward behind the screen (*L*, Fig. 129 *B*); it is now in a position of *secondary deviation.* We may note the position of the outer margin of the cornea behind the screen by means of the point s_1, and thus find the magnitude of the secondary deviation, $s_1 m$. It is

equal to the primary deviation—a fact which constitutes a further point of difference between concomitant and paralytic squint, since in the latter the secondary deviation is always larger than the primary (page 548).

As a result of one of the eyes being in an incorrect position, a man with squint should see double. But this is really the case only at the commencement of strabismus. The diplopia soon disappears, and afterward can be evoked only by the use of all sorts of artifices, or can not be evoked at all. This, too, is a feature distinguishing strabismus from paralysis, in which the diplopia is such an annoying symptom. A man with strabismus fails to see double, because he learns to withdraw his attention from the impression conveyed by the squinting eye; he "excludes" the image with this eye. The act of *exclusion* is a psychical act; the squinting eye really does see, but the visual perceptions set up by it do not excite attention—just as many men are able, in looking through a microscope or telescope with one eye, to leave the other open and yet not see with it. As a result of this act of exclusion, a man with squint has mere monocular vision; he does not, therefore, have stereoscopic sight in the proper sense of the word.

The *visual acuity* of the squinting eye is diminished as compared with the other or sound eye. Without doubt a certain degree of enfeeblement of sight exists even before the inception of the strabismus, and, in fact, constitutes one of the reasons for the development of the latter. The enfeeblement of sight, however, becomes greater and greater the longer the strabismus lasts, since an amblyopia ex anopsia develops on account of the exclusion of the eye from the act of vision (see page 446). This amblyopia finally reaches such a pitch that reading becomes impossible, and the sight may even be reduced to the ability to count fingers at a short distance. Such an eye has unlearned its ability to perform fixation; when the sound eye is covered the squinting eye remains rigidly fixed in its false position.

We distinguish between inward and outward squint (*strabismus convergens* and *divergens*). Either the same eye squints all the time (*strabismus monolateralis*), or the two eyes squint alternately (*strabismus alternans*). In the latter event it is usually the case that one eye fixes for looking at the distance and the other for looking at near points. One eye or the other, however, always fixes; it never happens that both eyes squint at once, as the laity often believe. Squinting may occur only at intervals, or may be present all the time (*periodic* and *constant strabismus*).

Etiology.—Strabismus develops from insufficiency. If, when there is disturbance of the muscular equilibrium, the eyes are no longer retained in their proper position by a special effort, but pass into the position corresponding to the muscular conditions and remain there, strabismus is produced. If we call insufficiency latent squint, we may

with even better right denominate squint as an insufficiency which has become manifest. In insufficiency the disturbance in the equilibrium of the muscles remains latent, because the correct position of the eyes is maintained for the sake of binocular vision, as otherwise diplopia would ensue. Hence, the fact of an insufficiency's becoming manifest, or its transformation into a strabismus, is effected by such circumstances as reduce the usefulness of binocular vision—that is, such as render diplopia less unpleasant. This is accomplished, in the experiment which is made for demonstrating the presence of insufficiency, by covering one eye (see page 542); but in the natural development of strabismus it is accomplished by a reduction of the visual acuity of one eye. In this way the retinal image of the latter becomes less distinct, and hence diplopia becomes less troublesome. Thus, we see a man who has hitherto had simply an insufficiency become the subject of a manifest strabismus when corneal opacities are left as the result of a keratitis in one eye. The most frequent causes leading to strabismus through reduction of the visual acuity are: 1. Errors of refraction which are present in one eye alone, or to a higher degree in it than in the other. In conjunction with such an error of refraction there frequently exists a congenital amblyopia. 2. Opacities in the refracting media, particularly in the cornea and in the lens. 3. Intraocular diseases.

Perfectly blind eyes are very apt to become subject to strabismus.

Strabismus is, therefore, the result of the combined action of two factors — diminution of the visual power of one of the eyes, and a pre-existing disturbance of the muscular equilibrium. According as the latter factor consists in a preponderance in the internal or in the external ocular muscles, a convergent or a divergent squint is produced.

128. (*a*) *Strabismus Convergens.*—This occurs especially in hypermetropes, hypermetropia being found in about three fourths of all cases of convergent squint. Donders was the first to determine this fact, and he explains it in the following way: Hypermetropes have to make an unusually strong effort of accommodation to see distinctly; but as this effort, on account of the connection between accommodation and convergence, is possible only when conjoined with a strong impulse toward convergence, the interni acquire a functional preponderance. Moreover, in hypermetropes the interni are apt to be intrinsically powerful (organic preponderance of the interni, see page 543). This preponderance of the internal muscles of the eye develops into strabismus if one of the eyes from the time of birth has a more feeble vision than the other (e. g., on account of a higher degree of hypermetropia or hypermetropic astigmatism), or if through subsequent disease it suffers an impairment of its visual power. Among the affections which particularly tend to produce the latter effect is conjunctivitis

lymphatica, which leads to strabismus through the opacities of the cornea that it leaves behind it.

Convergent strabismus develops, as a rule, in those years of life when the attempt at accurate and long-maintained fixation begins to demand a greater effort of accommodation than formerly; it develops, that is, between the age of two and six. Usually the strabismus is first noticed only when near objects are looked at (periodic squint). This may remain the case during the whole life, but generally a constant strabismus develops from the periodic one, a squint soon making its appearance when the gaze is fixed on distant objects as well. Moreover, the squint at first is usually greater in the act of fixation of near objects, in accordance with the greater accommodative effort required for this purpose; but later on the strabismic deviation becomes constant.

In exceptional cases it happens that children with strabismus gradually cease squinting as they grow up, and lose their strabismus about the age of puberty. They "outgrow" their squint. But the eye that was previously deviated is left with its sight permanently weakened, and accurate binocular vision is never restored.

(*b*) *Strabismus Divergens.*—In this, myopia plays the same part that hypermetropia does in convergent strabismus. About two thirds of all persons with divergent squint are myopic. The cause is as follows: The myope, to see objects near by, needs to use, according to the degree of his myopia, either little or no accommodation; consequently the impulse for convergence is too weak—there is functional insufficiency of the interni. To this are added organic causes which diminish the functional capacity of the interni, such as the increased dimensions of the myopic eye, which offer a mechanical impediment to convergence. For these reasons myopes are particularly liable to divergent strabismus, especially if one of the eyes has less visual power than the other. Since small children are not myopic, divergent strabismus, unlike convergent strabismus, does not form during childhood, but later on, during youth, when myopia itself develops. As the myopia increases, the strain upon the accommodation and consequently the impulse for convergence steadily decrease, while the demands made upon the convergence increase in proportion, owing to the approximation of the near point. This state of things must ultimately lead to a point where the convergence is no longer able to answer the demands made upon it. The convergence first becomes incompetent in the act of fixation of near objects, for which a stronger effort is required, and thus one of the eyes deviates out. Many myopes remain for their whole life in this condition of periodic strabismus; in others a constant strabismus develops from this condition, since later on one eye gets to deviate out in looking at distant points as well.

A spontaneous cure, such as is sometimes observed in inward squint,

never occurs in divergent strabismus; on the contrary, it tends to increase with age.

In the highest degrees of myopia the development of a periodic strabismus divergens is inevitable. In these cases the far point is approximated to a distance of ten centimetres or less; and reading, writing, etc., must be carried on at this short range. Now, even the strongest interni are unable to maintain continuously such a convergence as this; hence, in accurate inspection of objects near by, one eye always deviates out, even though the eyes have a correct position for great or medium distances.

Treatment.—*Non-operative treatment* accomplishes good results only in convergent strabismus, and then only in particularly favorable cases. Such treatment depends upon the fact that with the removal of the excessive effort of accommodation, which is the main cause of the inward squint, the latter itself disappears, provided that it is not already too deeply implanted for eradication. We begin accordingly by paralyzing the accommodation completely by the repeated instillation of atropine, and then determine the precise degree of hypermetropia (the total hypermetropia, § 146). Upon the basis of this determination we order convex glasses which shall completely correct the hypermetropia, and which the patient is to wear continuously from that time on. The instillation of atropine is still kept up for several weeks after the wearing of glasses has been begun with, and then is quite gradually discontinued. This treatment is re-enforced by the use of a bandage several times a day, for from a quarter to half an hour at a time, over the eye which has previously been employed for fixation. In this way we compel the other or squinting eye to do the fixing. Non-operative treatment is only applicable in those children who are old enough to wear glasses without hurting themselves with them. It holds out a prospect of success only when we have cases to deal with that are not too far advanced. The most suitable cases for its application are those in which the strabismus is still periodic, and diplopia recurs spontaneously —i. e., without the employment of any artificial means for its production—thus proving that the squinting eye has not yet been finally excluded from participation in the act of binocular vision. If this treatment is to lead to any result, it must be pursued energetically, and for a long time (for months or years), and even after the strabismus has been relieved the convex glasses must be used either from time to time or continuously, in order that the patient may not again become a victim of squint.

In most cases of strabismus, and particularly in all cases of external strabismus, a cure can be expected only from *operative treatment*. This consists in a tenotomy which in inward strabismus is to be performed upon the internal rectus, in outward strabismus upon the external rectus. In the higher degrees of strabismus the tenotomy must be made

upon both eyes or must be combined with advancement of the antagonist. The technique of these operations, and the way in which they act, will be described in the section upon operations; at present, simply the indications for their performance will be briefly given.

In *convergent strabismus* tenotomy is indicated in all cases in which non-operative treatment has remained unsuccessful, or in which it is apparent beforehand that such treatment offers no prospect of success. In this latter category belong all cases in which the strabismus has lasted a long time, or in which it has attained a high degree. As strabismus in some cases, although rarely, disappears of itself as the children become older, it is advisable to delay the performance of the operation until the child has passed the age of ten; for, if we should perform early tenotomy in a case which has a tendency to become well spontaneously, a divergent strabismus would subsequently set in. Meanwhile, in order not to let the time pass unemployed until the children are old enough for the operation, we may keep the deflected eye in constant practice by frequently bandaging the other, and may thus prevent a failure of visual power due to disuse. In addition, we forbid their playing with small toys, so as to avoid any unnecessary exertion of the accommodation; and, when possible, we order them to wear the proper convex glasses.

Divergent strabismus can be cured in no other way than by an operation. Recent cases in which the strabismus is still periodic hold out the best chance of success; in such cases a simple tenotomy usually suffices. When there is a constant external squint, an advancement of the internal rectus is generally required in addition; but in old cases, and in those of extreme degree, even this gives only imperfect results.

The *result* obtained by the operation is, as a rule, simply cosmetic. The visual power of the squinting eye is not influenced by the operation, and even the restoration of binocular vision is accomplished in only a few instances. Nevertheless, the results that we secure by the operation are not to be undervalued. A man with squint scarcely ever complains of the bad sight in his squinting eye, or of the absence of binocular vision; he is ordinarily unaware of the existence of either. He only desires relief from his disfigurement, and is very grateful if this is accorded him.

The laity are accustomed to attribute strabismus to an improper placing of the cradle with relation to the light, or to the fact that objects upon one side of the child excite his attention and cause him to look to one side, or to other like causes. But none of these have anything to do with the origin of strabismus. The strabismus which is so frequently observed in quite small children (those below the age of two) is founded upon the fact that such children have not yet learned perfectly the complicated associated movements required for correct binocular vision. This variety of strabismus disappears of itself with advancing years. Permanent strabismus convergens develops somewhat later,

after the age of two, and its true cause is that discovered by Donders. It depends, as has been set forth more in detail above, upon the connection between accommodation and convergence. In what way this leads to strabismus is very beautifully demonstrated by the following experiment likewise propounded by Donders: We cause a man who has perfect muscular equilibrium in his eyes to fix his gaze upon an object near by. If, now, we cover one of the eyes, it remains fixed in the correct position behind the screen. But if we now place a concave glass before the uncovered eye, so that the person under examination is compelled to accommodate quite strongly in order to see the object distinctly the covered eye at once turns inward—that is, an artificial inward strabismus is thus produced, owing to the increased effort of accommodation. A disturbance of the relation between accommodation and convergence is accordingly the most important, but it is by no means the only, cause of strabismus. If this were the case, all hypermetropes would necessarily squint inward, all myopes squint outward, while, as a matter of fact, only a small fraction of them become the subjects of strabismus. In fact, for strabismus to be produced, there must be other causes as well acting in conjunction with this one. Of these causes one of the most important is the congenital state of the muscular equilibrium. A hypermetrope who from the start has feeble interni (insufficiency of the interni) will not be apt to acquire an inward squint; on the contrary, the strong accommodation which he has to call forth in order to see clearly actually helps him by enabling him to put his too weak interni sufficiently upon the stretch. But if, simultaneously with the hypermetropia and independently of it, there is a preponderance of the interni, as is the case in many hypermetropes, an additional reason is afforded for the development of inward squint; and the latter will in all probability develop if a still further favoring factor is present in the shape of a diminution of the visual acuity in one eye. The hypermetrope, in fact, is placed in the following dilemma: If he wishes to see distinctly, he has to make too strong an effort of accommodation; but he can do this only with the aid of an excessive convergence, so that he sees double. But if he converges only as much as is necessary, he can not bring the proper amount of accommodation into play, and hence sees indistinctly. He is, therefore, given the choice of either seeing distinctly and double, or of seeing single and indistinctly. He prefers the former alternative whenever, from the fact that the image in one of the eyes has grown indistinct, diplopia is made less disagreeable to him.

In *strabismus alternans* both eyes often have good visual acuity, but unequal refraction. If, for instance, one eye is far-sighted and the other near-sighted, the former sees clearly at a distance, the other near by, but both eyes can never see distinctly at the same time. In this case the far-sighted eye would perform fixation in looking at a distance, the near-sighted eye when looking near by, and in either event the eye not used would squint; the image in this eye not being distinct, its suppression is readily accomplished. Alternate strabismus is usually divergent.

With many persons it happens that during fixation the eyes are properly placed, but, when they are looking about without thinking of anything in particular, one of the eyes squints a little outward. In such a case we are generally dealing with myopes with some insufficiency of the interni. In most this condition remains the same all through life, while in some few a constant outward squint develops from it.

Contrary to the rule that short-sighted persons squint outward, strabismus convergens is sometimes found conjoined with myopia of a high degree. This is distinguished from ordinary strabismus convergens by the fact that it does not develop in childhood, but in the later years of life, and is generally associated with an extremely unpleasant diplopia. It is dependent upon the constant decrease in the power of movement of the eye, due to its enlargement.

Intermittent should not be confounded with periodic strabismus. While the latter takes place only upon the supervention of certain definite causes, such as the act of fixation for near objects, the former makes its appearance without known cause. It develops quite suddenly, and after some time disappears as suddenly again and returns at regular intervals (e. g., every other day). Intermittent strabismus is ordinarily directed inward and is almost exclusively observed in children; it is probably referable to purely nervous disturbances.

Deviation of the eyes upward or downward, although rare, also occurs. Such cases are for the most part those of strabismus convergens in which along with the horizontal deviation there is also one in the vertical direction. The vertical deviation usually disappears when the strabismus is relieved by tenotomy of the internus. We must hence conclude that this vertical deviation is not to be referred to the superior or inferior rectus, but to an abnormal insertion of the internal recti, such that in contraction of the latter a deflection in the vertical direction is produced at the same time. Pure vertical deviations, not referable to paralysis of the superior or inferior rectus—i. e., a genuine *strabismus sursumvergens* or *deorsumvergens*—are extremely rare.

In the commencement of convergent strabismus there is simply an abnormally strong innervation of the internus. Hence, the squint disappears during sleep and also under narcosis (Stellwag); but afterward the muscle, owing to its continual contraction, becomes drawn up permanently, and remains thereafter always too short.

The *diagnosis* of strabismus can ordinarily be made at a glance. In cases where the deflection is doubtful, the test given on page 542 serves to make the diagnosis. Strabismus is present according to this test if, upon covering one eye, the other makes a perceptible movement of redress in order to fix the object held before it.

Just as a slight strabismus may remain unnoticed, so also it can happen that we may believe that we are dealing with a strabismus when none exists. An *apparent strabismus* of this sort is most frequently simulated in the following way: The visual axis which joins the object of fixation to the fovea centralis does not in most eyes pass through the apex of the cornea, but the latter lies somewhat to the outside or inside of the axis.* If, then, the visual axes are parallel for distant vision, the corneal apices in the first case are divergent, in the second case convergent. If this deviation attains a pretty high degree, it becomes noticeable and simulates strabismus. Here, again, the test above mentioned leads to the correct diagnosis; for when each eye is covered alternately it is apparent that the eye which is not covered remains steadfast in its position, and hence performs fixation properly.

* [The angle determining the amount of this divergence—i. e., the angle between the visual axis and the optical axis, or the antero-posterior line passing through the apex of the cornea, is called the *angle α*. This is usually positive (i. e., the visual axis passes to the inside of the optical axis) in hypermetropes; and is negative (i. e., the visual axis passes to the outside of the optical axis) in myopes.—D.]

Vision of Patients with Strabismus.—There is no doubt but that in the beginning of strabismus there is diplopia quite as much as there is in paralysis of an ocular muscle. But since in convergent strabismus the development of squint takes place in childhood, we hear nothing about diplopia, and, by the time that the children have become old enough to give a trustworthy account, they have already learned to perform exclusion. Then diplopia can for the most part be produced only by artificial means—e. g., by putting colored glasses before the eye or by the use of prisms through which the image in the squinting eye is brought nearer to the fovea centralis. But when the squint does not develop until later in life, as is only exceptionally the case in convergent strabismus, but regularly the case in divergent strabismus, diplopia is then one of the regular symptoms. Sometimes it is so disagreeable that it furnishes the main reason for the patient's visit to the physician.

While ordinarily no diplopia exists in old cases of strabismus, it is just in these cases that it is very apt to make its appearance after tenotomy. This is accounted for as follows: As long as the eye was squinting inward, the image of the object of fixation fell upon the portions of the retina situated to the inner side of the fovea (Fig. 98). This region of the retina had accordingly accustomed itself to abstract its attention from the impressions received (regional exclusion). If, now, after tenotomy the eye stands in the proper position, the image of the object of fixation falls upon the fovea or its vicinity—that is, upon portions of the retina which have not been exercised in the act of exclusion. Hence, the patient complains of diplopia. This as a general thing soon disappears; but in rare cases it obstinately persists and becomes extremely unpleasant to the patient.

The *visual acuity* of the squinting eye is almost always reduced. As to the cause of the amblyopia, opinions differ. Some think that such amblyopia as is found in the squinting eye already existed before the squint; the latter having had little or no effect in changing it. Others admit that a certain degree of amblyopia existed before the development of the squint, and that, in fact, one of the main causes of the latter consisted in this amblyopia, but allege that the amblyopia increases afterward, and, often to a considerable degree, owing to the disuse of the eye. The latter view, in which I also share, is based upon the fact that the older the squint is, the worse the visual power is found to be. The visual power is finally reduced to the point where there is simply the ability to count fingers, and the power of fixation is lost. Then when the sound eye is covered, the deviated eye no longer adjusts itself for fixation, but remains fixed in its squinting position, or even squints still more strongly inward than before. Schmidt-Rimpler mentions the following instructive case which shows the gradual diminution of visual acuity in the deviated eye: He operated on a seven-year-old boy for strong inward squint. At the time of the operation there was still perfect vision in the squinting eye. By the operation the squint was diminished, but not perfectly done away with. Ten years afterward the vision of the squinting eye had sunk so low, without the latter having been diseased in any way, that it could only count fingers at four metres, and was no longer able to perform central fixation.

A further proof that the vision of the squinting eye is at least in part not congenital, but acquired because of the squint, is afforded by the fact that it can be improved by suitable exercise. There are a few cases known in which eyes that were no longer able to perform fixation, were brought up to such a

the size of the strabismic angle, since—the size of the eyeball being assumed to be about normal—one millimetre of linear deviation corresponds approximately to an angle of 5°.

By means of a linear measurement we can also, following the method proposed by Alfred Graefe (see page 535), measure the *lateral excursions* of the squinting eye. The following is the result thus obtained in convergent strabismus: The adduction of the eyeball is increased; the cornea can be carried so far inward that its margin is in contact with the caruncle—in fact, it not infrequently is completely concealed behind the caruncle. On the other hand, abduction is diminished, but, in case the squint has not already lasted too long, not more than the increase in adduction amounts to. The total capacity for lateral excursion has therefore remained the same, but the latter has suffered a general displacement inward. In old and extreme cases of inward squint this relation changes, the abduction being reduced still lower without being compensated for by a corresponding increase in the adduction, so that the total excursion-range is diminished. The increase in the power of making inward movement always exists in both eyes, although it attains a higher degree in the eye that squints. This fact is explained as follows: Owing to the increased demands made upon the accommodation, an excessive impulse is set free for the production of convergence. As convergence is an associated movement of both interni, this impulse affects both at once, so that, owing to their excessive contraction, the visual axes would cross in front of the object; but as the patient then would fail to have direct vision of the object with either eye, he turns his head a little to one side. He thus gets the object into the line of vision, g, of one (and that the better) eye (L, Fig. 130), while the line of vision, g_1, of the other eye shoots off so much the farther from the object. Thus the patient secures fixation with one eye at all events, although both interni are still strongly contracted. It is owing to the last-named fact that the increase in the power of adduction develops in the course of time in both eyes. By this fact, too, is explained the *oblique position* of the head in those affected with convergent strabismus—such persons carrying the head turned toward the side of the healthy eye (Arlt).



FIG. 130.—OBLIQUE POSITION OF THE HEAD IN THOSE AFFECTED WITH CONVERGENT STRABISMUS.

In divergent strabismus the region of lateral excursion-movements of the eye is displaced outward. The power of moving outward has increased, that of moving inward has diminished. Since the latter diminution is much greater than the former increase, the total capacity of the eye for making excursion-movements is always considerably decreased.

A knowledge of the power possessed by the squinting eye for making lateral excursion-movements is indispensable as a guide in selecting the method of operation and in predicting the result that may be expected. In convergent strabismus section of the interni has the greater effect, in proportion to the power with which the externus can draw the eye over to its own side after the operation. But the measure for the working capacity of the externus is the degree to which the eye can be abducted. If the abduction is greatly diminished, simple tenotomy of the internus will afford very little result, and we shall be obliged to proceed to advancement of the externus. In divergent strabismus advancement of the internus is almost always required, owing to the very great diminution in the power of adduction.

IV. Nystagmus.

129. By nystagmus or tremulousness of the eyes are meant short, jerking movements of the eye which are very rapidly repeated and always occur in the same direction. The movements of the eye, as a whole, are not affected by it. Different kinds of nystagmus are distinguished according to the direction in which the movements occur. *Nystagmus oscillatorius* is present when the eyes are in a state of vibratory movement which may take place in either a horizontal or a vertical direction (nystagmus oscillatorius horizontalis et verticalis). In *nystagmus rotatorius* rolling movements of the eye about the sagittal axis take place. Frequently the vibratory are found combined with the rotatory movements (*nystagmus mixtus*).

Nystagmus is usually more pronounced in some directions of the gaze, less pronounced in others; often it is quite inconstant and does not appear at all, except in certain directions of the gaze. The nystagmus ordinarily grows more marked if the patient knows that he is observed, or if he is told to keep his eyes still.

Nystagmus usually affects both eyes. It sometimes happens, though, that it is less pronounced in one eye than in the other, and it may actually be limited to one eye. Not infrequently nystagmus is associated with squint.

The most frequent *causes* of nystagmus are—

(*a*) Amblyopia, when this has existed since birth or very early youth. Blennorrhœa neonatorum is extremely apt to give rise to it, if this disease leaves corneal opacities or anterior polar cataract behind it. In other cases there are very great errors of refraction, congenital opacities, or other congenital anomalies (especially albinism), retinitis pigmentosa, etc. If, therefore, we have a patient with nystagmus to examine for refraction and vision, we must be prepared beforehand for a failure to secure perfect vision by a glass of any kind.

In what way does amblyopia produce nystagmus? Fixation is not a faculty inborn in man, but has to be learned by practice. Very small children do not perform fixation, but move their eyes about aimlessly.

Now, if the retina does not receive well-defined images, the child does not learn to place the eye accurately in the direction required and keep it still. Hence, nystagmus fails to develop if the amblyopia does not set in till later in life, at a time when the eyes have already learned how to perform fixation.

(*b*) Nystagmus is a symptom of many cerebral affections, particularly of disseminated sclerosis.

(*c*) Nystagmus develops in laborers in coal-mines, owing to the way in which they work in the drifts.

Nystagmus is associated with no special harm for the patient, for the defective vision of such cases is not to be attributed to the nystagmus, but, on the contrary, is the cause of it. There is no cure for nystagmus.

To these statements miners' nystagmus forms the only exception. It causes the patients very considerable annoyance, owing to the fact that it makes all objects appear in motion, which is not the case in the other kinds of nystagmus. Everything seems to dance before the eyes, so that vertigo is produced and further work becomes impossible. Moreover, this form of nystagmus is curable, although, to be sure, only on condition that work in the coal-mines is given up entirely. When this is done, the nystagmus after some time disappears of itself.

Persons suffering from nystagmus are not aware of it themselves; they learn of the tremor of their eyes only through information given by others. Many patients make the same vibratory movements with their heads as with their eyes, only in an opposite direction. There are also men who can produce nystagmus voluntarily.

A certain degree of visual power must be present for nystagmus to exist; persons who are born blind, or who become totally blind very early, do not acquire nystagmus. In such persons the eyes move slowly and aimlessly about, making large excursions and often going quite contrary to the laws of association.

Miners' nystagmus occurs exclusively in those who work in the coal-drifts. It affects hardly any except the class of workers known as pick-men. After these men have worked several years in the drifts, they notice that, when they leave the drift in the evening, everything dances before their eyes. This phenomenon disappears again in a short time, but if the work is kept up reappears, occurring earlier each time and lasting longer, until the patient is compelled to give up his work. In the examination of such patients at the commencement of their disease, it can be made out that nystagmus takes place only when the gaze is directed straight up, or up and to one side. This fact furnishes the explanation for the occurrence of nystagmus. The pick-men in many coal-mines work in a recumbent position with their eyes turned a good deal upward and in an oblique direction. This way of looking, which causes a good deal of strain, leads, when long maintained, to exhaustion and clonic spasms of the eye-muscles. The apparent movement of objects that results from nystagmus is readily accounted for. As the eyes vibrate to and fro, the images of all objects upon the retina move, too, but in an opposite direction. But as the patient is

not aware of the movement of his eyes, he necessarily attributes the displacement of the retinal images to movements of the objects themselves. But why, then, do not those who have acquired nystagmus because of amblyopia, see objects affected with a like dancing motion? Because they have suffered from nystagmus from childhood, and hence, at the same time that they have learned to see, have also learned in projecting their retinal images to take the nystagmic movements of the eyes into account.

Tonic spasms of the ocular muscles are extremely rare. Many cases of intermittent strabismus (page 570) belong under this head. They are furthermore observed in cerebral affections, particularly under the form of conjugate deviation (Prévost). This arises from a deflection of both eyes toward the same side, which is due to spasm of the appropriate muscles, resulting from disease of one of the centers for the association of ocular movements. These cases, therefore, are comparable with those of conjugate paralysis (pages 553 and 560), except that the case is one of spasm instead of paralysis. Tonic spasms of the ocular muscles may also occur as a result of hysteria. I have observed two perfectly analogous cases in women. At every attempt to perform fixation of an object, either far or near, both eyes at once assumed a position of extreme convergence, the pupils at the same time being very greatly contracted and the accommodation thrown into a state of spasm. Here, therefore, the three associated muscles —i. e., the interni, the sphincter pupillæ, and the ciliary muscle, were simultaneously thrown into a condition of spasmodic contraction. By a rather protracted treatment with the constant current, one case was entirely cured, the other essentially improved.

CHAPTER XV.

DISEASES OF THE ORBIT.

ANATOMY.

130. THE bony orbit forms a quadrilateral pyramid, whose base corresponds to the anterior aperture of the orbit, and whose apex to the optic foramen. The nasal walls of the two orbits are about parallel to each other; but the temporal walls diverge from each other a good deal from behind forward. The nasal wall is the thinnest, as it is formed by the lachrymal bone which is as thin as paper, and by the delicate lamina papyracea of the ethmoid (Fig. 93, *T* and *L*). At its anterior extremity it bears the fossa lacrimalis for the reception of the lachrymal sac (Fig. 95, *fl*). In the posterior portions of the orbit are found three apertures which connect the orbit with the parts adjacent. These are: 1. The optic foramen which passes between the two roots of the lesser wing of the sphenoid into the middle fossa of the skull. Through it the optic nerve and beneath the latter the ophthalmic artery pass into the orbit (Fig. 24, *F*). 2. The superior orbital fissure lies at the junction of the upper and outer wall, and is bounded by the lesser and greater wing of the sphenoid. It also opens into the middle fossa of the skull, and transmits the nerves for the ocular muscles and the first branch of the trigeminus. 3. The inferior orbital fissure is longer than the superior orbital fissure, and lies at the junction of the outer and the lower wall of the orbit, between the great wing of the sphenoid and the superior maxilla. It connects the orbit with the temporal fossa (fossa sphenomaxillaris). Through it the twigs of the second branch of the trigeminus, the largest of which is the infra-orbital nerve, pass into the orbit.

The walls of the orbit at their anterior margin become thickened into a strong bony ring, the *margin* of the orbit. This constitutes the most important defense of the eye against external force, especially above and below where it juts farthest out. On the inner side there is no sharply defined margin to the orbit, but here the eye is protected by the bridge of the nose. On the outer side the orbital margin recedes the farthest (Fig. 94, *A*), so that here the eye is most exposed to injuries. At the upper margin of the orbit is found the supra-orbital notch designed for the artery and nerve of the same name (Fig. 95, *i*).

At the lower margin of the orbit there is a canal (the infra-orbital canal) for the infra-orbital artery and nerve, and this opens upon the cheek—by means of the infra-orbital foramen (*fi*, Fig. 95)—about four millimetres beneath the orbital margin. This point and the supra-orbital notch are of practical importance, as constituting the points of exit of the aforesaid nerves. Sensitiveness to pressure at these spots is a frequent symptom in neuralgiæ of the trigeminus and also in essential blepharospasm.

The orbit is surrounded by several other cavities in disease of which it can itself be implicated. These cavities are the nasal fossæ and the cavities accessory to them—namely, the ethmoidal and sphenoidal sinuses, the frontal sinus, and the antrum of Highmore.

The *contents* of the orbit consist of the eyeball with the optic nerve and the muscles, the lachrymal gland, the vessels, and the nerves. The interstices between these structures are filled with orbital fat, and the whole is maintained in a state of firm connection by a system of *fasciæ*. The latter display a greater strength and a more intimate union with one another in three places, viz.: 1. Along the walls of the orbit. They cover the latter under the form of a periosteum (here called periorbita), and likewise may be regarded as making an anterior wall for the orbit. This anterior wall is formed by the fascia which starts from the margin of the orbit and is attached to both tarsi and also to the ligamentum canthi internum and externum (fascia tarso-orbitalis). These structures combined represent the septum orbitale, which, when the lids are closed, shuts off the orbit anteriorly and keeps its contents in. 2. The ocular muscles are surrounded by fasciæ which send out processes connecting the muscles with each other, with the lids, and with the margins of the orbit (see page 533). 3. Surrounding the eyeball the fasciæ are condensed into a fibrous capsule, *Tenon's* (also called *Bonnet's*) *capsule.* This extends forward as far as the conjunctiva of the eyeball and backward nearly to the optic nerve. It is thus open in front and behind, and may be said to represent a broad ring placed about the eyeball. It forms the articular socket for the eyeball, which can move in it freely in all directions. The contiguous surfaces of Tenon's capsule and of the eyeball are smooth, and are provided with an endothelial covering (Schwalbe). The intervening space, Tenon's space (*t*, Fig. 53), must be regarded as a lymph-space which is continuous posteriorly with the lymph-space (supra-vaginal space; *s*, Fig. 53) surrounding the external sheath of the optic nerve. At the points where the tendons of the ocular muscles pierce Tenon's capsule, the latter is reflected upon the muscles and becomes continuous with the fasciæ covering them (lateral invaginations of the muscles, *e* and e_1, Fig. 53).

The *blood-vessels* of the orbit arise from the ophthalmic artery which springs from the internal carotid and enters the orbit through the optic foramen. The venous blood leaves the orbit through the superior and

inferior ophthalmic veins, both of which make their way through the superior orbital fissure to the cavernous sinus into which they empty. The above-mentioned veins form numerous anastomoses with the veins of the forehead.

Lymph-vessels and lymphatic glands are wanting in the orbit.

The *nerves* of the orbit are either motor—these being the nerves destined for the ocular muscles—or sensory; the latter belonging to the first and second branch of the trigeminus. To the outer side of the trunk of the optic nerve lies the ciliary ganglion. This contains motor fibers derived from the oculomotor nerve (short root), sensory fibers from the trigeminus (long root), and sympathetic fibers from the plexus which envelops the carotid. The short ciliary nerves pass from the ciliary ganglion to the eye, through the posterior division of which they enter the interior of the organ. The long ciliary nerves, which likewise enter the eyeball, do not arise from the ciliary ganglion, but come directly from the trigeminus (from the branch of it called the naso-ciliary nerve).

Position of the Eyeball in the Orbit.—This on an average is such that a straight-edge applied in a vertical direction to the upper and the lower margin of the orbit and pressed against them just comes into contact through the closed lids with the apex of the cornea, but does not sensibly compress the eye. Variations from this mean position very frequently occur: partly in consequence of individual differences in the formation of the face; partly, too, on account of changes in the quantity of orbital fat. When corpulence is on the increase, the eyes project farther from the orbit (goggle-eyes); but when there is emaciation, they sink back into their sockets.

Pathological changes from the normal position occur chiefly in the way of a protrusion of the eyeball from the orbit—*exophthalmus*. On account of the great individual variations in the position of the eyeball, small degrees of exophthalmus can be diagnosticated with certainty only when they are limited to one eye, so that, by making the comparison with the other eye, a guide to the diagnosis is secured. Higher degrees of exophthalmus attract our notice at once. The protrusion of the eyeball may advance so far that the lids are no longer able to keep the eye back in the orbit, and thus it prolapses in front of the lids—*luxatio bulbi*. The protrusion of the eyeball is either directed straight forward, or there is at the same time with this forward projection a lateral displacement of the globe of the eye.

Exophthalmus is caused either by an increase in the volume of the orbital tissue or by a diminution in the capacity of the orbit. The former is much the more frequent. But exophthalmus can also be produced by a relaxation of the tone of the recti muscles, which draw the eye backward. This is the case in paralysis or in division (tenotomy) of them.

The *consequences* of exophthalmus when it is of high degree are extremely disastrous to the eye: 1. The farther the eye comes forward, the more it pushes the lids apart. The palpebral fissure is, therefore, more widely open and more of the eyeball is visible in it than usual. In slight cases of exophthalmus the dilatation of the palpebral fissure is often more conspicuous than the actual protrusion of the eyeball. The fact of the eyeball being more exposed results in symptoms of irritation upon the part of the conjunctiva, such as redness of the ocular conjunctiva and epiphora. As the protrusion of the eyeball grows greater, the closure of the lids becomes imperfect (lagophthalmus) and then the cornea begins to suffer, because keratitis e lagophthalmo develops. This is the most dreaded sequel of exophthalmus, and one to which regard has primarily to be paid in the treatment (see page 496). 2. The pressure which the eyeball exerts upon the lids from behind leads to their eversion; ectropion of the lower lid develops. 3. The mobility of the eyeball diminishes in proportion as the protrusion increases, owing to the tightening of the recti muscles and of the optic nerve. 4. Vision is affected in various ways. In the cases in which, together with the protrusion of the eye, a lateral displacement of the organ exists, diplopia makes its appearance. Later on the vision of the protruding eye may be abolished altogether by keratitis or by disease of the optic nerve. The latter, as long as the protrusion of the eye is but slight, is subject to no undue tension, its normal S-shaped curve (see page 423) being simply straightened out; it is not until the eye is caused to protrude pretty far that the optic nerve is put on the stretch. If this stretching takes place gradually, the nerve-fibers often accommodate themselves to it in a wonderful fashion, so that they preserve their conductivity, and vision is maintained intact; but if the exophthalmus increases rapidly, the optic nerve reacts to the traction by undergoing inflammation, with subsequent atrophy.

In the growth of the body the orbit expands in proportion as the eyeball enlarges. If the eyeball is backward in its growth, and more especially if it is entirely destroyed in childhood, the dimensions of the orbit also remain smaller. If, therefore, in such cases it is desired later on in life to wear an artificial eye, the orbit is usually found to be too small for this purpose.

The inferior orbital fissure is closed by a fascia with which numerous smooth muscular fibers are interwoven (musculus orbitalis of Müller). These are innervated by the sympathetic, and it is therefore supposed that the slight recession of the eyeball in paralysis of the sympathetic depends upon relaxation of these fibers.

The situation of the eyeball in the orbit not only varies in different men, but may also be unlike on the two sides in the same individual. This is combined with an asymmetrical formation of the face, which is frequently associated with a difference in the refraction of the eyes. In this case the difference in position may be only apparent, since the myopic eye is longer, and hence is more prominent, so that an exophthalmus is simulated.

For measuring the degree of exophthalmus, instruments have been constructed, which are called exophthalmometers or statometers (Cohn, Hasner, Zehender, Snellen).

The opposite condition to exophthalmus, namely, the recession of the eyeball into the orbit—*enophthalmus*—occurs: 1. In decrease of the orbital fat consequent upon extreme emaciation. In Asiatic cholera this condition develops within a few hours, owing to the enormous loss of water from the tissue (Von Graefe). 2. In paralysis of the sympathetic (see above). 3. After injuries (enophthalmus traumaticus). In most cases of this kind the traumatism does not affect the eyeball itself, but the upper margin of the orbit. Nieden looks upon the enophthalmus that follows in these cases as due to the cicatricial contraction of the orbital tissue caused by the injury. Lang, on the contrary, believes that the case is one of indirect fracture of the lower wall of the orbit which is thus driven in to the antrum of Highmore. As a result of this the space occupied by the orbit would be enlarged, so that the eyeball is pushed back by the pressure of the external air. In favor of this view are one or two cases in which the eyeball has been actually luxated into the antrum of Highmore by a blow from a cow's horn. 4. After the spontaneous subsidence of a pulsating exophthalmus (Bronner). 5. In neurotic atrophy of the face.

I. Inflammations.

(*a*) *Inflammations of the Bony Wall and of the Periosteum of the Orbit.*

131. *Periostitis* of the bones of the orbit is not rare, particularly at the orbital margin. Here, too, it is easiest to diagnosticate. A hard swelling is felt immovably attached to the bone and causing the margin of the orbit to appear thicker and misshapen—a fact which is particularly striking when comparison is made with the sharp margin of the orbit on the other side. In view of the great tendency toward œdematous swelling possessed by the lids and the conjunctiva, it is quite conceivable that such a swelling may exist to a greater extent upon one side than upon the other; still, it is usually easy to feel the tumefaction of the periosteum through the soft swelling of the lids. Moreover, the diseased spot is distinguished by its greater sensitiveness to pressure.

If the periostitis is situated, not at the margin, but in the depth of the orbit, the diagnosis is much more difficult. We have at first simply the signs of a painful inflammation in the deeper parts of the orbit. That this inflammation starts from the periosteum is frequently not apparent until the periostitis leads to the formation of an abscess, and this breaks through to the outside, in which case we then come down upon the diseased bone with the sound.

The *course* of periostitis leads in favorable cases to complete resorption of the periosteal exudate or to the formation of a permanent de-

posit of bone (especially in syphilitic periostitis); it is more unfavorable when the periostitis goes on to suppuration which is followed by caries and necrosis of the bone.

When a periosteal abscess develops at the margin of the orbit, the skin over the affected spot first becomes reddened, then becomes thinned by the pus, and finally is perforated. A fistula is thus produced through which the sound passes down to bare bone. Afterward there develops at the site of the fistula the funnel-shaped depression which is characteristic of bone-disease. The discharge of pus from the fistula keeps up until all the diseased bone that has died has been eliminated, a process for which not infrequently several years are required. Then the fistula heals and leaves a depressed, funnel-shaped cicatrix attached to the margin of the orbit. Through this can be felt the defect in the margin of the orbit left by the necrosis. Other consequences which frequently remain are ectropion of the affected lid and even lagophthalmus. These two conditions are caused partly by the fact that the lid is attached to the margin of the orbit and drawn well back toward it, partly by the fact that a portion of the skin of the lid has been destroyed in consequence of the prolonged suppuration.

When the periostitis which has gone on to the formation of an abscess is situated in the depth of the orbit, the disease runs its course with the symptoms of retrobulbar phlegmon, which will be described later on. The process is then much more severe and of longer duration, since it takes a good while for the pus to make its way from the depth of the orbit to the surface. These deep suppurations, moreover, may be dangerous to life, if they are transmitted to the cranial cavity and give rise to meningitis or abscess of the brain. In this respect the periostitides of the roof of the orbit are particularly to be dreaded, because at this spot the cranial cavity is separated from the focus of pus in the orbit only by a very thin lamella of bone.

The *causes* of periostitis are: 1. Injuries. This traumatic periostitis is found most frequently at the margin of the orbit, because this is the part most exposed to injuries. 2. Dyscrasiæ, particularly scrofula (tuberculosis) and syphilis. These periostitides are likewise localized more frequently at the margin than in the depth of the orbit, because in this case, too, injuries play a part as exciting causes. Injuries of a comparatively trifling nature, such as bumps or falls upon the orbital margin, which in healthy persons would remain without further ill result, may in people affected with dyscrasiæ start up protracted specific inflammation. Scrofulous (tuberculous) periostitis occurs chiefly in children and principally affects the superior external and inferior external margins of the orbit, which are the parts most exposed to knocks; it leads, as a rule, to caries. Syphilitic periostitis, on the contrary, is ordinarily met with in adults and only exceptionally in children (those with hereditary syphilis). It belongs to the third (gum-

matous) stage of syphilis, and for the most part appears as a chronic affection under the form of periosteal thickening, more rarely as an acute affection with suppuration following it.

Treatment must, more than anything else, have regard to the etiological factor. In this respect the best results are obtained in syphilitic periostitis, which usually subsides rapidly under a promptly initiated treatment with mercury and iodide of potassium. As local treatment moist warm compresses are applied, which in the beginning favor resolution, but in the later stages accelerate the softening of the abscess that is in process of development. As soon as there are signs that suppuration has taken place, there should be no delay about making the incision, in order that the pus which has accumulated beneath the periosteum may not detach the latter still more extensively from the bone. Particularly in the case of deep-seated periosteal abscesses is early incision indicated, even though no fluctuation is yet perceptible, in order to prevent the transfer of the suppuration to the brain. After the abscess has been opened, a drainage-tube or a strip of iodoform gauze is placed in the wound, so as to keep it open for the exit of the pus. If caries or necrosis succeeds periostitis, they are to be treated according to the general rules of surgery. Ectropion or lagophthalmus, which may develop subsequently, likewise calls for relief by operation. This relief must be given without delay when the cornea is in danger from being insufficiently covered; otherwise it is better to put off operative interference until the process in the bone has entirely healed, as otherwise the success of the operation upon the lids might be again jeopardized by the renewed formation of abscesses and fistulæ.

(*b*) *Inflammation of the Cellular Tissue of the Orbit.*

132. Inflammation of the cellular tissue of the orbit, terminating in suppuration, is called phlegmon of the orbit or retrobulbar phlegmon (or abscess). It makes itself apparent by marked œdema of the lids and the conjunctiva (chemosis). The eyeball is protruded, and hence suffers impairment of its mobility; vision is reduced or even quite abolished. At the same time there are violent pain, fever, and not infrequently cerebral symptoms such as headache, vomiting, mental hebetude, retardation of the pulse, etc. When the symptoms have reached their acme, the skin of the lids at a certain spot grows red, then shows a yellow discoloration, and finally is perforated by a discharge of pus. After the evacuation of the pus, which is present in large quantity, the inflammatory symptoms in most cases rapidly abate and the opening soon heals again. The sight may suffer permanent diminution or be altogether annihilated, if the optic nerve is implicated; for inflammation of the optic nerve or thrombosis of its vessels may develop, succeeded by atrophy of the nerve. Detachment of the

retina and even suppuration of the eyeball (panophthalmitis) also occasionally occur in retrobulbar phlegmon. If the suppuration is carried over from the orbit to the cranial cavity, it leads to a fatal issue through purulent meningitis or abscess of the brain.

Retrobulbar phlegmon may originate from the following *causes:* 1. Injuries, when the body causing the traumatism enters the orbit and carries infectious germs into its tissues. Those injuries in which a foreign body is left in the orbit are particularly dangerous. Operations, too, such as enucleation, may give rise to suppuration in the orbit if not performed aseptically. 2. Transfer of inflammation from the wall of the orbit or parts in the vicinity of the latter to the cellular tissue. This is the case in periostitis of the wall or of the adjacent bones, in empyema of the adjoining cavities when this ruptures in the direction of the orbit, and finally in purulent thrombosis of the cavernous sinus, when the thrombotic process is carried from the latter over into the orbital veins. 3. Erysipelas; the inflammation being transmitted from the skin to the deeper parts. 4. Metastases in pyæmia, typhus, scarlet fever, small-pox, purulent meningitis, etc. 5. In a number of cases for which no other cause for its development has been discoverable, a cold has been accused of being the cause of retrobulbar phlegmon. In many of these cases there has probably been a preceding attack of erysipelas which has been very slight, and therefore has been overlooked (Leber).

A retrobulbar abscess requires to be opened as early as possible in order to prevent the suppuration from spreading to the brain. We introduce a sharp-pointed scalpel at the spot where we suppose the abscess to be, and do not hesitate to plunge it deep in. The situation of the abscess is inferred from the way in which the eyeball is displaced. If, for instance, the latter is pushed forward and downward, the abscess is to be sought for in the upper part of the orbit. Even when we do not succeed in getting out any pus by our incision, because no abscess-cavity of any size has yet formed, yet the relief of tension in the tissues produced by the incision and the profuse bleeding exert a favorable effect.

Chronic periostitis, particularly when of syphilitic origin, may set up a gradually increasing thickening of the bones of the orbit, by which the cavity of the latter is rendered progressively smaller. The consequence of this is exophthalmus and also compression of the nerves which enter the orbit, so that neuralgiæ and paralyses are produced. This complex of symptoms is similar to that which is observed in *leontiasis ossea*. This consists in a gradually increasing thickening of the bones of the whole face, a process in which the bones of the orbit participate, so that in this case, too, the symptoms of contraction of the orbit with simultaneous thickening of its walls are produced.

Symptoms similar to those which present themselves in the beginning of a retrobulbar phlegmon accompany *thrombosis of the cavernous sinus*. The lids and the conjunctiva swell up with œdema, and the eyeball is protruded and be-

comes hard to move. The veins of the retina are seen, upon ophthalmoscopic examination, to be distended enormously with blood. At the same time there is a doughy œdema in the mastoid region. These symptoms are referable to the fact that the veins of the orbit discharge the greater part of their blood through the ophthalmic veins into the cavernous sinus; if the latter is occluded, an extreme degree of venous stasis in the orbit necessarily takes place and leads to protrusion of the eyeball and also to venous hyperæmia of the retina. The œdema of the mastoid region depends upon the fact that in this region an emissary vein of Santorini (the emissarium mastoideum) empties into the transverse sinus and thus indirectly into the cavernous sinus, so that when there is occlusion of the latter this region also shares in the venous stasis. When this œdema is present (which, to be sure, is not always the case), it forms an important diagnostic sign between thrombosis of the sinus and retrobulbar phlegmon, in which latter it is absent. A further point of difference lies in the fact that thrombosis of the sinus frequently passes over to the other side, so that the same complex of symptoms develops there also, while, on the contrary, a bilateral orbital phlegmon would be one of the greatest rarities. Finally, thrombosis of the sinus is associated with very severe cerebral symptoms, interrupted at last by the onset of the fatal issue.

In occlusion of the sinus what we are dealing with is either a simple thrombosis produced by marasmus or a thrombosis due to infection. The latter usually originates from a focus of pus situated in the vicinity—e. g., from a phlegmon of the orbit, which gives rise to a thrombotic process in the superior or inferior ophthalmic vein which is then carried over into the cavernous sinus. Thrombosis of the sinus most frequently originates in a caries of the petrous bone, the thrombosis extending from the sinus of the latter [the petrosal sinus] to the cavernous sinus. Suppurative processes starting from the teeth also may lead to thrombosis of the sinus. Finally, thrombosis of the sinus may be set up metastatically in infectious diseases, such as erysipelas, scarlet fever, etc.

Tenonitis.—Tenon's capsule may be implicated in inflammations of the eyeball, so that an exudate accumulates in Tenon's lymph-space and the eyeball is thus pushed forward. Hence a slight degree of exophthalmus is sometimes found in severe cases of irido-cyclitis (particularly after injuries). This is quite regularly the case and to a much higher degree in panophthalmitis, in which exophthalmus is one of the most constant and striking symptoms. If we enucleate the eyeball at this stage of the disease, we can convince ourselves that the exudate is fibrinous and but very rarely purulent. Afterward the exudate becomes organized and leads to extensive adhesions between Tenon's capsule and the eyeball—a fact of which we can likewise convince ourselves if an enucleation is performed in this later stage. Exudation into Tenon's space also occurs after it has been laid open by injuries, and particularly after squint operations, when infection of the wound has taken place from dirty instruments.

There is also a primary *serous tenonitis*. The symptoms of this rare disease can be best gathered from the description of the following case which I myself observed: It concerned a woman of fifty-eight years of age, otherwise healthy, in whom the disease had begun, without known cause, six days before she came under my observation. I found the skin in the vicinity of the lids, and still

more the lids themselves, very swollen and œdematous, so that the eyes could be opened to only a very small extent indeed by spontaneous effort. When I drew the lids apart I found the eyes prominent and almost immovable. The conjunctiva of the lids was but moderately, that of the eyeball, on the other hand, quite markedly, injected, and the latter was so greatly swollen as to form a thick protuberance projecting from all sides over the cornea. The secretion was not increased. The cornea and also the deep portion of the eye were healthy, and vision was normal, except that there was diplopia due to the impaired mobility of the eyes. The disease was associated with moderate pain, and particularly with a sense of pressure and tension of the eyes. The treatment consisted in the administration of an infusion of jaborandi, in order to produce rapid absorption of the exudate by means of profuse diaphoresis. Under this treatment the œdema and the protrusion of the eyes gradually went down, so that when the patient four weeks later was discharged from the clinic, the condition of the eyes had become once more perfectly normal.

The disease described, as far as its nature is concerned, consists in all probability in a serous exudation into Tenon's space. Its causes are obscure; in some cases it has been supposed that a cold could be made accountable for it. Some cases (among them one case of primary purulent tenonitis) were observed in the last epidemic of influenza. The disease tends to relapse, but leaves no permanent bad results behind.

II. Injuries.

133. Injuries of the orbit affect either the soft parts alone or the bones as well. Injuries of the *soft parts* originate, as a rule, from the penetration of a foreign body into the orbit, the lids and the eyeball being, of course, very frequently implicated at the same time. The direct consequence of the injury is an extravasation of blood into the tissue of the orbit. If this is considerable it causes exophthalmus, and also, since the blood oozes slowly forward, it comes into view beneath the conjunctiva and the lids under the form of an ecchymosis. Paralysis of the ocular muscles, too, may be produced by the injury, and so also may lesions of the optic nerve, the latter entailing as their direct result partial or complete blindness. It also happens sometimes that the eyeball is driven out of the orbit by the foreign body which has penetrated into the latter, and is thus found lying in front of the lids (*luxatio bulbi traumatica*). This is most of all possible when the body that causes the injury enters from the outer side, since here the wall of the orbit recedes the farthest—about as far back, in fact, as the plane of the equator of the eyeball. There are parts of the world where such injuries are purposely inflicted in brawls, the eye being pried out of its socket by the thumb, which is thrust into the orbit from the outer side. Insane patients have sometimes enucleated one or both of their own eyes in this way. Ordinarily the luxated eyeball is lost, but cases are known in which after reposition the eye healed again in its place and retained its visual power.

Injuries of the *bone* are most frequently produced by the action of

a contusing force (e. g., by a blow or a fall) upon the margin of the orbit. They are easy to diagnosticate when they affect the margin of the orbit itself. The site of a fracture in this locality is recognized by the unevenness, the sensitiveness to pressure, and in extreme cases by the crepitation. When in consequence of the fracture the orbit is made to communicate with the neighboring cavities, emphysema may develop both in the lids (see page 503) and in the orbit itself. Emphysema of the latter kind, like extravasations of blood into the orbit, manifests its presence by exophthalmus. But there is this point of distinction from extravasation, that in emphysema the protruded eye can be pushed back into the orbit again with the finger, since the air is displaced by the pressure. On the other hand, the exophthalmus is increased by straining during the act of coughing, blowing the nose, etc., owing to the fact that fresh supplies of air are forced into the orbit.

The injury may, if no important organs have been destroyed, heal after the resorption of the extravasated blood and leave the parts as well as before. In other cases disturbances of motility of the eyeball remain, owing to its adhesion to the neighboring structures, or as a result of paralysis of the ocular muscles. Moreover, if the optic nerve has been injured, permanent blindness of the eye may ensue. Still worse are the cases in which the injury results in a phlegmon of the orbit, in which case it may even end fatally.

Treatment in the case of a recent injury consists, in the first place, in careful cleansing and disinfection of the wound. If we suspect the existence of a foreign body in the orbit we endeavor to extract it; but foreign bodies, such as grains of powder, etc., which are known to have the power of becoming incorporated in the tissues, may be left in the orbit. After taking care that any secretions that form in the wound shall have free exit (by the introduction of a drainage-tube or of a strip of iodoform gauze), we apply an antiseptic dressing. If there is an excessive degree of exophthalmus, a pressure-bandage contributes to the rapid absorption of the blood or (in the case of emphysema) of the air. As soon as the symptoms of deep suppuration have set in, we must proceed as in the case of a retrobulbar phlegmon.

Deep fractures of the orbit without fracture in the margin may be produced by deeply penetrating foreign bodies, but may also be caused apart from these and indirectly (by contrecoup). This is the case, for example, after a fall upon the head, the dropping of a heavy weight upon it, etc. Such fractures when deeply situated can only be suspected from the fact that they are accompanied by orbital hæmorrhage, which manifests itself by a suddenly developing exophthalmus and the appearance later on of ecchymosis of the conjunctiva and the lids. A further diagnostic point would be supplied if directly after the injury partial or total blindness were determined to exist along with a normal appearance of the eyeball. This condition would necessarily be referred to an injury of the optic nerve in the canalis opticus, into the wall of which the fracture extends (Hölder and Berlin; see page 444). Similar symptoms also at times ac-

company fractures of the base of the skull, except that in this case the exophthalmus is wanting and the ecchymosis of the conjunctiva and lids sets in still later, since the blood takes a longer time to push its way so far forward.

Spontaneous hæmorrhages into the orbit are of extremely rare occurrence, taking place as a consequence of whooping-cough or in persons who in general are prone to have hæmorrhages.

Contusion of the Eye.—It may be of service to the general practitioner to give a brief, comprehensive presentation of all the consequences which contusion of the eye or of the adjoining parts may entail. The physician before whom a case of this kind comes will deduce from this summary the changes that may possibly be present. He will then look for these changes, and thus perhaps will arrive at the discovery of lesions of this sort which otherwise might have escaped him because they are not very conspicuous. The changes produced by contusion are:

In the *lids*, ecchymoses, emphysema, solutions of continuity.

In the *margin of the orbit*, fractures with or without dislocation of the fragments.

In the *location of the eyeball*, exophthalmus which may be caused by the effusion of blood or air (emphysema) into the retrobulbar tissue or by the formation of an arterio-venous aneurism due to rupture of the carotid into the cavernous sinus (page 594).

The *tension* of the eyeball is greatly reduced when a perforation of the tunics of the eye has taken place. But the tension may be found to be temporarily diminished even apart from any gross material lesion, this alteration being then due to a decrease in the fluids of the eye and particularly of the vitreous (Leplat), which again must be regarded as a consequence of a disturbance of nutrition dependent upon nervous influence.

In the *conjunctiva*, ecchymoses, lacerations (with or without coincident scleral rupture).

In the *cornea*, epithelial desquamation, and, later on, the varieties of parenchymatous inflammation; rarely purulent processes or rupture of the cornea.

In the *aqueous chamber* and the *vitreous*, effusion of blood (hyphæma, hæmophthalmus).

In the *iris*, iridodialysis partial or complete (aniridia traumatica), radial lacerations, recession of the iris, likewise paralysis of the iris (mydriasis) with or without paralysis of accommodation.

In the *lens*, astigmatism, subluxation, and luxation due to partial or complete laceration of the zonula, likewise the formation of cataract.

In the *sclera*, rupture in the anterior division, attended in well-marked cases with prolapse of the uvea, the lens, or the vitreous.

In the *chorioid* and *retina*, extravasations of blood, detachment, rupture; in the retina alone, cloudiness (commotio retinæ).

In the *optic nerve*, compression by effusion of blood, and contusion or rupture by fracture taking place in the optic canal.

III. Basedow's Disease.

134. Basedow's disease belongs to the domain of internal medicine, and hence can only be considered here in so far as *exophthalmus* belongs among its most important symptoms. This exophthalmus is bilateral; the eyes are pushed straight forward, sometimes but little, sometimes to such a great extent that they can not any longer be perfectly covered by the lids. Even when the exophthalmus is great, there is little or no limitation of mobility of the eye. It is obvious that when the exophthalmus is considerable, it becomes noticeable at the first glance; but even when the protrusion is slight the peculiar appearance of the eyes strikes one at once. This appearance is caused by the fact that the upper lids are raised unusually high. The eyes look as if forced wide open, and give the patient an expression of astonishment or of fear. When the eyes are depressed, the upper lids do not descend in proportion with the eyeball, but remain elevated, so that a broad portion of the sclera is visible above the cornea (Von Graefe's symptom). Winking takes place less frequently, and hence desiccation of the deficiently covered cornea is favored (Stellwag's symptom). The eyeball itself, as long as the cornea has not yet suffered harm, is normal and the visual power is good.

The two other main symptoms of Basedow's disease are the *swelling of the thyroid gland* and the acceleration of the heart's action (*tachycardia*). The former is distinguished from ordinary goître by the fact that when the hand is placed upon the thyroid gland it feels the strong movement of pulsation in the arterial vessels, which is communicated to the entire gland. So also the carotids are found to be dilated and strongly pulsating. The intensity of the heart-beat is increased, the frequency of the pulse is regularly over a hundred. The slightest bodily exertion or mental excitement at once increases the frequency of the pulse very considerably. The physical examination of the heart, apart from the enlargement of the left heart, gives a normal result. The general state of the patients is disordered to this extent that they are for the most part very excitable, and suffer from the symptoms of anæmia or chlorosis. Not infrequently rapid emaciation is present, even when the appetite remains good.

The disease principally attacks women, beginning at the time of puberty and extending up to the appearance of the menopause. Men suffer from it more rarely. The most frequent cause of the disease is (in women) seated in affections of the genital organs. In addition, mental excitement, great fright, anxiety, etc., give rise to an outbreak of the disease.

Basedow's disease generally develops quite gradually. Palpitation usually sets in first, and with this is afterward associated the thyroid dilatation, and, last of all, the exophthalmus. As a general thing it

takes months or even years before all the symptoms of the disease are distinctly marked. Then it usually remains at the same point for years, after which it subsides again very gradually and not without leaving a tendency to subsequent recurrences. In many cases, however, the disease does not get well, but remains until the patient's death, nay, more, it may even—by the exhaustion or the complications which it produces—be itself the cause of death. As a general thing the disease runs a severer course in men and in elderly people than in women and in younger persons. Basedow's disease is a source of danger to the eyes from the fact that when the exophthalmus is of a pretty high degree closure of the lids is imperfectly performed and keratitis e lagophthalmo develops. In this way blindness of one or even of both eyes may be produced.

Treatment, unfortunately, has little power over Basedow's disease. The anæmia is counteracted by means of strengthening diet and also by means of iron, quinine, or arsenic. We attack the tachycardia with digitalis, while for the general nervous symptoms potassium bromide and the cold-water treatment have been pressed into service. What usually does the most good is the long-continued employment of the constant current applied to the cervical sympathetic. The exophthalmus per se requires treatment only when it leads to imperfect closure of the lids and thus endangers the cornea. In this case we must, by bandaging the eyes at night-time, provide for their being covered during sleep. If the bandage turns out to be insufficient, we must undertake tarsorrhaphy, by which the palpebral fissure is permanently closed in its outer portion. We may also, when the tension of the protruded lids is very considerable, close the inner part of the palpebral fissure by sutures applied temporarily—i. e., without refreshing the borders of the lids.

Basedow's disease was first described as a special form of disease by English physicians, and particularly by Parry and afterward by Graves, and hence it is even now called Graves's disease by the English. These authors, however, had not recognized the exophthalmus as being one of the essential symptoms of the disease; this was first done by Basedow, who in 1840 did the pioneer work in demonstrating the whole triad of symptoms of the disease.

In marked cases no disease is easier to diagnosticate than this; even from a distance we can tell what the patient's trouble is. But, on the other hand, there are numerous cases in which some of the symptoms are less pronounced or are even wanting altogether, so that the diagnosis becomes difficult. If in this connection we take only the exophthalmus into account, we find that it may be slight, absent altogether, or confined to one eye. When exophthalmus is absent, Von Graefe's symptom is still sometimes present, so that this is not to be regarded simply as the consequence of the exophthalmus; but this symptom is not constant either, and in the same case may be sometimes present, sometimes wanting.

Precisely as the separate symptoms of Basedow's disease may show great

variations with regard to the degree of their development, so also may the character which the course of the disease assumes vary exceedingly. Although as a general thing the course is very chronic, yet cases are known in which the disease has been very acute in its onset. Trousseau gives an account of a woman in whom the symptoms of the disease had developed in the course of a single night, which she had spent in tears, lamenting the death of her father. The subsequent progress of the disease, too, may be so speedy that within a few weeks it leads to recovery or to death.

The essential nature of Basedow's disease is at present obscure, since most autopsies give negative results. In consideration of the symptoms of the disease, and especially in consideration of the absence of demonstrable anatomical lesions, it must be assumed that a disturbance of innervation lies at the root of the disease. As far as the eye is concerned, the sympathetic is the part whose function appears to be disturbed. In consequence of this we find a dilatation of the vessels in the district supplied by the carotids—a dilatation which is manifest even to external observation in the pulsation of the carotids. It is on account of this distention of the arterial vessels in the thyroid gland and the orbit that the thyroid dilatation and the exophthalmus develop, and both conditions therefore disappear at death. Von Graefe's symptom, too, must be referred to a disturbance of innervation on the part of the sympathetic, which supplies the organic levator of the lid (musculus palpebralis superior); and, as a matter of fact, changes have been found in the cervical portion of the sympathetic in some autopsies, but in other autopsies they have not been found. In the latter class of cases the focus of disease must be conjectured to be in the central nervous system itself—that is, in the medulla oblongata or in the cervical part of the cord.

IV. Tumors of the Orbit.

135. Tumors of the orbit—in the widest sense of the word—have in common one very important symptom, namely, exophthalmus. To determine the site of the tumor, attention must be paid to the nature of the protrusion: whether the latter is directed straight forward, or whether there is at the same time a lateral displacement of the eyeball. With the same object in view we test the mobility of the eye in all directions. Then we try to palpate the tumor itself, so as to be able to give an account of its size, form, consistency, mobility, etc. If the tumor lies deep in the orbit, we endeavor to penetrate with the little finger as deeply as possible between the margin of the orbit and the eyeball (under narcosis, if necessary), so as to get at the tumor. Finally the examination should be completed by the determination of the visual acuity and of the results afforded by ophthalmoscopic examination, by which we ascertain whether and in what way the optic nerve has suffered injury from the tumor.

(*a*) *Cysts.*—The most frequent of these are the dermoid cysts, which are congenital, but which often develop to a more considerable size after birth. They lie in the anterior part of the orbit, and there usually in its upper and outer or its upper and inner angle. On account of

their superficial situation they do not displace the eyeball, but push forward the skin of the lids, through which they can readily be felt as round movable tumors of the size of a bean or walnut. Upon extirpating them one can convince himself that they are, as a general thing, unilocular cysts with pultaceous or sebiform contents; sometimes processes from them extend pretty deep into the orbit, and thus render their complete removal difficult. The only harm that the dermoid cysts produce is the disfigurement caused by them, and this, moreover, is the only reason for the rather frequent attempts that are made to extirpate them. In doing this, we must go to work very carefully to dissect out the cysts, as far as may be, unopened. If the wall of the cyst, which often is thin, breaks prematurely, a part of it may easily be left behind and give rise to recurrences.

(*b*) *Vascular Tumors.*—Belonging to vascular tumors, in the widest sense of the word, are vascular dilatations (aneurisms) and new growths consisting of vessels (angiomata). Both the one and the other occur, although rarely, in the orbit. Among the angiomata we here meet with are the two forms that also occur in the lids (the teleangiectasis and the cavernous tumor, see page 505). The former is congenital, and is originally seated in the lids, from which it may gradually extend into the orbit. The diagnosis therefore is easy, since upon the lids the tumor is exposed to view. Its treatment when in the orbit is the same as when upon the lids. Cavernous tumors, in contradistinction to those just named, usually develop first within the orbit and grow slowly, pushing the eyeball farther and farther before them. As long as they are situated wholly within the depth of the orbit, their correct diagnosis can be made only from the variable volume which these tumors possess. We can diminish their size by pressing the eyeball back into the orbit, and, on the other hand, they become more swollen in the acts of crying, straining, etc. When the vascular tumors become larger and extend farther forward they gleam with a bluish luster through the skin of the lids, and dilated blood-vessels are seen to make their appearance in the latter; in this case the diagnosis is, of course, easy. When we see that these tumors are putting the eye in danger through the progressive protrusion to which they give rise, we must remove them. Extirpation with the knife is principally adapted to those cases in which the tumor is sharply limited and is inclosed in a fibrous capsule; for the case of a more diffuse vascular tumor electrolytic treatment is indicated.

(*c*) *Malignant Tumors.*—Both sarcomata and carcinomata occur in the orbit. The former are far more frequent, and may take their starting-point from bone, from periosteum, from the muscles or connective tissue of the orbit, from the lachrymal gland, and even from the optic nerve and its sheaths. Not to be confounded with them are the sarcomata which develop primarily in the eyeball, and, after breaking through

the posterior wall of the latter, grow out into the orbit, at the same time pushing the eyeball forward. Orbital sarcomata are usually rounded, pretty soft, and sharply defined, because they are inclosed in an envelope of connective tissue.

Primary carcinomata of the orbit are very rare; they start from the lachrymal gland. On the other hand, it frequently happens that carcinomata the original seat of which is in the lids or the conjunctiva, grow inward into the orbit.

If malignant tumors are not removed early, they push the eye more and more out of the orbit, afterward destroy it, and finally fill the entire orbit, from whose anterior opening they project as large, ulcerated, readily bleeding masses. Still later they pass over to structures adjacent to the orbit, and especially to the brain; the neighboring lymphatic glands swell up, and metastases form in the internal organs. The patient succumbs from exhaustion or from a transmission of the growth to vital organs. To this course a stop can be put only by as early and as radical a removal of the growth as possible. Small encapsulated sarcomata can be cleanly enucleated with preservation of the rest of the contents of the orbit. Large tumors, particularly if they are not sharply circumscribed, demand the removal of the entire contents of the orbit (exenteratio orbitæ, see § 168), in doing which the eye, even when it still retains its ability to see, must be sacrificed.

Histological examination of *dermoid cysts* shows that their wall possesses essentially the structure of the external skin—it consists, that is, of a substratum of connective tissue, the papillary body, which supports an epithelial lining like that of the external skin, and which not infrequently contains hair-follicles and glands (sebaceous and sweat glands). The contents of the cyst is mostly like porridge or sebum, and is formed of the exfoliated epithelial cells, and the secretion of the glands contained in its walls; in many cases hair, and even teeth, have been found in it. Sometimes the contents of the cyst are converted into an oily or honey-like liquid (oil-cysts and honey-cysts or meliceris); or they may even become like serum. The anatomical structure of these cysts ranges them in the series of dermoid cysts—i. e., of those which are imagined to have developed through an invagination of the external germinal layer, which then develops afterward into a cyst (Remak). Many of the cysts with serous contents may perhaps have originated from an analogous invagination of the nasal mucous membrane (Panas). In structure and mode of development dermoid cysts are allied to the dermoids of the corneal margin, which likewise are to be regarded as aberrant islands of skin (see page 111). The two varieties of tumors are distinguished clinically by the fact that the first are deeply placed cavities; the second, superficially situated, flat, expanded, wartlike structures.

Another form of tumor with which the dermoid cysts might occasionally be confounded are the *herniæ cerebri*. These consist of a herniaform extrusion of the dura mater into the orbit. A sac is formed by them which is either filled with cerebro-spinal fluid (meningocele) or which also contains brain-substance (encephalocele). Herniæ cerebri develop at those regions of the skull at which

the bones come into apposition by sutures. In the orbit they are most frequently situated above and to the inner side, where they utilize for their avenue of escape from the cranial cavity the suture between the ethmoid and frontal bones. Meningocele of the orbit, therefore, is ordinarily represented by a tumor which is situated in the upper and inner angle of the orbit, is covered by normal skin, is distinctly fluctuant, and has existed since birth. Since dermoid cysts also are congenital and frequently occupy the same spot, an error in diagnosis might be readily made. Such an error might possibly lead to the worst consequences, if extirpation of the meningocele, which may be followed by meningitis, should be thereupon performed. It is hence important to know how such a mistake can be avoided. The signs which principally distinguish a meningocele from the dermoid cysts are as follows: 1. A meningocele is immovably attached to the bone. Not infrequently we are able to feel with our finger the opening in the bone through which the meningocele communicates with the cranial cavity (hernial orifice). 2. A meningocele shows the pulsatory and respiratory oscillations which are communicated to it from the brain. 3. A meningocele can be diminished in size by pressure with the fingers, since their fluid contents are in part pushed back into the cranial cavity. At the same time symptoms of increased cerebral pressure, like vertigo, nausea, deviation of the eyes, convulsions, etc., may make their appearance. 4. In order to be perfectly certain, we make an exploratory puncture of the cyst. In doing this we must proceed under rigid antiseptic precautions, so as not to excite inflammation of the cyst and consequent meningitis. The diagnosis becomes more difficult, or is even impossible, when the communication between the meningocele and the cranial cavity (the subdural space) is obliterated; but then in this case removal of the tumor is not associated with danger of any sort. In all other cases the indication is to leave meningoceles—which anyway are very rare—undisturbed.

Besides those already given, the only *cysts* of the orbit requiring mention are those formed by entozoa (cysticercus and echinococcus), and also the congenital cysts of the lower lid in microthalmus (page 330).

Pulsating Exophthalmus.—Under this term is denoted the following complex of symptoms: The eye is protruded; the blood-vessels of the conjunctiva and the lids, and often of the surrounding parts, too, are dilated. If the hand is placed upon the tumor, distinct pulsation of the eyeball itself and of the surrounding parts is felt; and if the ear is applied to it, blowing murmurs and a continuous whirring and rumbling sound are heard. The patient also hears the same sounds; he has a constant rumbling in his head, as if he were standing near a waterfall, and he is often more disturbed by this than by anything else. The eye can be pushed back into the orbit with the hand. A special feature distinguishing the disease is the fact that compression of the carotid of the same side as the exophthalmus diminishes both the pulsation and the sounds or causes them to disappear altogether. The visual power of the eye is in many cases abolished, and that, as the ophthalmoscope shows, by neuritis of the optic nerve; a conspicuous feature that is brought to light at the same time being the enormous dilatation of the retinal vessels. At times there are violent pains in the orbit, and impairment of the hearing.

It has been proved by a number of autopsies that the most frequent cause of this complex of symptoms is an arterio-venous aneurism resulting from rupture of the carotid into the cavernous sinus. Through the spot where this rupture has taken place the blood of the carotid is discharged under a high

pressure into the cavernous sinus and the veins of the orbit, which empty into it and which are thus very greatly dilated and set pulsating. The rupture of the carotid is most frequently caused by traumatism, and particularly by severe injuries of the skull with fracture of the base; rarely a spontaneous rupture occurs as a result of degeneration of the vessel-wall.

In rare cases the aneurism subsides spontaneously; otherwise it persists, and may produce death with cerebral symptoms or by hæmorrhage from the dilated vessels. The treatment is self-evident, from the fact that the symptoms disappear as soon as the carotid is compressed upon the affected side. Hence we try first the employment of compression by digital or instrumental pressure upon the carotid every day for as long a time as can be borne. If this procedure, after being continued for some time, is unsuccessful, there is nothing left but to tie the carotid—an operation by which most cases are cured.

Besides the tumors enumerated above there have also been observed in the orbit, as rare occurrences, the following: Angioma lipomatodes, lymphangioma, neuroma plexiforme, leukæmic tumors and lymphosarcomata (simultaneously in both orbits), cylindromata, endotheliomata, psammomata, and osteomata. The *osteomata* start from the bony wall of the orbit, and most frequently from the frontal bone. They may, however, also develop in one of the cavities adjoining the orbit, particularly in the frontal sinus, and penetrate into the orbit itself afterward through ulceration of the orbital wall. They are usually sessile, being attached to the bone by a broad base. In rare instances they are pediculated, in which case it occasionally happens that they undergo necrosis spontaneously and are then eliminated. Most osteomata are as hard as ivory, so that chisel and saw can make scarcely any impression upon them (exostosis eburnea); but there are also osteomata having a spongy or partly cartilaginous structure. They grow very slowly, and after a time displace the eyeball from the orbit and destroy the sight by compression of the optic nerve. For this reason they call for removal by operation, which on account of the great hardness of the growth is often very difficult, and, moreover, is not devoid of danger, since in its performance the cranial cavity may be opened. Hence we often abstain from taking the growth out radically, and satisfy ourselves with removing only so much of it as projects into the orbit. When the eye has been pushed out of the orbit by a large osteoma and has been already rendered blind, it is sometimes better to relieve the patient of his troubles by enucleating the eye which has become useless, rather than to expose him to the dangers of an extirpation of the growth.

Dilatation of the Cavities adjoining the Orbit.—This disease commonly affects the frontal sinus or the maxillary antrum. Diseases of the other accessory cavities of the nose, namely, the ethmoidal and the sphenoidal sinuses, are among the greatest of rarities, and, besides, are for the most part not possible to diagnosticate in the living. The dilatation of these cavities takes place through a bulging out of their walls. Hence even on external inspection there is visible a protrusion at the corresponding spot, namely, on the forehead in enlargement of the frontal sinus, and upon the cheek in enlargement of the antrum of Highmore. Moreover, the wall of these cavities which looks toward the orbit is bulged outward, so that exophthalmus takes place with a coincident lateral displacement of the eyeball toward the side opposite to that of the ectasis. The most frequent cause of ectasis of these cavities is the accumula-

tion of secretion in them. They are accessory cavities of the nose, and are lined by processes of the nasal mucous membrane. Catarrhal inflammation of the nasal mucous membrane is frequently communicated to them, and if the passage, narrow as it frequently is, between the accessory cavities and the nares is blocked by swelling of the mucous membrane, secretion accumulates in the former. As the mucous membrane of the accessory cavities does not stop secreting, the cavities gradually become filled and finally distended with secretion. The secretion has either a purulent or a watery character, so that we distinguish between empyema and dropsy of these cavities. In rare cases the distention of the cavities is produced by tumors, such as polypi, osteomata, or malignant new growths.

If the distention of the cavities is caused by fluid, the treatment consists in opening the cavities according to the rules of surgery, and in securing a permanent drainage of the secretion. If tumors are the cause of the distention, they must be extirpated wherever possible.

PART III.

ANOMALIES OF REFRACTION AND ACCOMMODATION.

THE eye is constructed upon the principle of a camera obscura. This consists of a box blackened on the inside, the anterior wall of which is formed by a strong convex lens, which throws upon the posterior wall an inverted image of the objects that may chance to be in front of the camera. In the human eye we find instead of the convex lens quite a number of refracting surfaces constituted by the surfaces bounding the refracting media of the eye, namely, the cornea, aqueous humor, lens, and vitreous; and in place of the posterior wall is found the retina, which not only receives the image, but also at the same time perceives it. Hence a diminution of visual power may be produced by two different causes: either the dioptric apparatus of the eye is defective, so that a sharp image is not thrown upon the retina, or it is the retina that is at fault in that it is not sensitive enough.

In order to throw a sharp image upon the retina the dioptric apparatus of the eye must fulfill two conditions. In the first place, the refracting media must be perfectly transparent. Hence opacities of the cornea, lens, etc., make distinct vision impossible. The second condition is, that the refractive power of the media should be such that they project an image of external objects which is both perfectly distinct and also lies precisely upon the retina. The variations from this rule we designate as errors of optical adjustment or as errors of refraction and accommodation. The theory of these errors, as we see it presented to us to-day, forming a harmonious, well-compacted whole, is chiefly Donders's work. It is the exactest portion of ophthalmology, and, in fact, of all medicine, for it is based directly upon the application of physical and mathematical laws to the eye. These laws, therefore, as far as they will require consideration here, must be supposed to be known in advance.

---

and, in fact, there is no image formed at any spot whatever. This apparent image is called virtual (formed at the virtual focus), and lies

FIG. 132.—DISPERSION OF PARALLEL RAYS BY A CONCAVE LENS.

upon the same side as that from which the rays come to the lens. Here, precisely as in the case of convex lenses, the law holds good that the path of the rays is the same when the direction is reversed. If rays impinge upon the lens from its posterior aspect (a) with a convergence such that they are directed toward F, they will be parallel upon their emergence from the lens at its anterior aspect.

The distance between the principal focus, F, and the optical center, h, is called the principal focal distance. In convex lenses this lies upon the opposite side to that upon which the rays impinge; it is known as positive focal distance, and convex lenses are hence given the sign +. The converse is true of concave lenses, whose negative focal distance is denoted by the sign —. The refraction of rays by a lens is greater, cæteris paribus, the more curved its surface is—that is, the shorter its radius of curvature is.

The *numeration* of lenses, the object of which is to show their refractive power, is based upon their principal focal distance; for, the more strongly the rays are refracted, the closer their point of union comes to the lens, and the shorter, therefore, is their principal focal distance. The latter accordingly is in inverse proportion to the refracting power of the lens, and can hence be utilized as a measure for it. A principal focal distance of 1 metre is assumed as unity, and the lens which has this principal focal distance is called a metre-lens or dioptre (D). If 2 metre-lenses are placed in apposition, twice the refractive power is obtained, namely, 2 dioptres (2 D). The principal focal distance is now one half that of the former lens—i. e., $\frac{1}{2}$ metre = 50 centimetres. Instead of placing 2 metre-lenses in apposition, we may grind a lens whose curvature is twice as large (or whose radius of curvature is half as large) as that of the single metre-lens. We thus get a lens of a 2-dioptre refracting power and a principal focal distance of

50 centimetres. In analogous fashion a lens of 4 *D* would have one fourth the focal distance of the metre-lens—i. e., 100 cm. ÷ 4 = 25 cm. A lens of ½ *D* refractive power has, on the other hand, a focal distance of 100 cm. ÷ ½ = 200 cm. The focal distance of a lens of *n D* is thus 100 cm. ÷ *n*. The trial-cases ordinarily employed for examining the eye contain lenses from 0·25 *D* up to 20 *D*.

137. The lenses so far considered have been biconvex and biconcave. For weak glasses plano-convex (Fig. 133, *A*) and plano-concave (Fig. 133, *B*) lenses are also employed, the refracting power of which



FIG. 133.—*A*, plano-convex lens; *B*, plano-concave lens; *C*, positive meniscus; *D*, negative meniscus; *E*, convex cylindrical lens; *F*, concave cylindrical lens.

is one half of that which the doubly curved lenses possess, the curvature of the surface being the same. There are also lenses one surface of which is convex, the other concave. If the radius of curvature of the two surfaces is the same, so that they are parallel with each other, the glass acts like a plane glass. This is the case in the coquille or protective glasses. Such lenses have refracting power only when the curvature of one surface surpasses that of the other (meniscus). If the convex bulges more than the concave surface, the lens acts as a convex lens (positive meniscus, Fig. 133, *C*). If, on the contrary, the concave is more strongly curved than the convex side, the combination acts as a concave lens (negative meniscus, Fig. 133, *D*). Menisci have the advantage over ordinary lenses that we see as distinctly when looking through the marginal portion of the glasses as when looking through their center, while ordinary lenses give distorted images when we look through their marginal portion. Hence, menisci are also called periscopic * glasses. They are, however, only suited for weak glasses, since the higher numbers of menisci are too heavy.

Besides the lenses just given, which are called collectively *spherical* lenses, there are also *cylindrical* lenses. If we image a segment cut out of a cylinder (Fig. 134), this segment forms a convex cylindrical

* From περί, about, and σκοπεῖν, to see.

lens (Fig. 133, *E*). This has the property of allowing rays which impinge along its axis, *a a* (Fig. 134), to pass without deflecting them. Rays which impinge perpendicularly to the axis, along a line corresponding to *b b b*, undergo the maximum refraction—i. e., that corresponding to the curvature of the cylindrical calotte. Rays which pass through the lens in meridians lying between the two main directions undergo a deflection which has a value somewhere between zero and the maximum, varying according to the angle that the meridian in which the rays impinge upon the lens forms with the axis. The same thing is true of concave cylindrical lenses (Fig. 133, *F*), which may be regarded as representing the mold of the positive cylinder.

Since cylindrical lenses refract unequally the rays impinging upon them in different meridians, they are calculated to compensate for a difference in refrangibility existing in the different meridians of the eye; they serve, accordingly, to correct regular astigmatism.

Prisms are employed for glasses either alone or combined with lenses. The number engraved upon prisms indicates their refracting angle; the deflection which the rays undergo amounts in the case of weak prisms to one half this angle. Prisms find their chief application in insufficiency and paralysis of the ocular muscles.

Protective glasses for shielding the eye against light are made of various shades of blue or gray glass (London smoke). The coquille-shaped, curved glasses are the best, since they also moderate a part of the light that comes in from the side. Workmen's glasses for shielding the eye against foreign bodies consist of glass, or, when the intention is to make them unbreakable, of mica or of fine wire gauze.

FIG. 134.—THE CONVEX CYLINDRICAL LENS CONSIDERED AS A SEGMENT OF A CYLINDER.

Stenopæic glasses* consist of a blackened disk of metal, in which is placed a small round hole or a narrow slit. The stenopæic slit is principally used for examining astigmatic eyes. The round stenopæic hole is sometimes employed with advantage in cases of corneal opacities. It is adapted for those cases in which a part of the pupillary area of the cornea is clear, while another part is occupied by a semi-transparent spot of cloudiness, which cause disturbance of vision through diffusion of light. If the disk is held before the eye in such a way that

* From στενός, narrow, and ὀπή, peep-hole.

is, therefore, about a dioptre. A No. 10 glass ($\frac{1}{10}$)—i. e., of 10 inches focal distance—has one fourth the focal distance of a No. 40 glass, and is therefore four times as strong as the latter; it is accordingly 4 dioptres. Hence, we get at the value of the old number in dioptres if we divide 40 by the old number. The conversion of the new numbers into the old is done in a similar way: e. g., 5 *D* have one fifth the focal distance of 1 *D*. The latter is about 40 inches; 5 *D*, therefore, have a focal distance of $40 \div 5 = 8$ inches. Hence, the old number is converted into the new, or the new into the old, by dividing 40 by the given number, when the number of the other system is then at once obtained.

The problem very often confronts the physician of determining the strength of a glass which the patient brings along with him. If, as is generally the case, no great precision is required, we may employ the following methods for *determining the strength of a lens:*

1. Direct measurement of the focal distance. We station ourselves with the glass—supposing it to be a strong convex glass—close to the wall of a room which is situated opposite the window, and throw with the glass an image of the window upon the wall. Then we measure that distance of the glass from the wall at which the image is the sharpest. This distance gives the principal focal distance of the glass directly. Suppose, for instance, the distance to be 20 centimetres; then the number of the glass would be $100 \div 20 = 5$ *D*. In doing this the not quite proper assumption is made that the window is at an infinite distance from the glass, since the principal focus is the point of union of rays that are parallel—i. e., come from an infinite distance and impinge from the lens. But this error is negligible when the window is distant not less than 6 metres from the wall. At smaller distances this procedure, however, is not applicable. Moreover, it can not be used for weak convex glasses, which do not afford a sufficiently distinct image; nor for concave glasses, which do not produce a real image at all. For these two cases we must add to the glass to be tested a strong convex lens of known focal distance and determine the focal distance of the two together. Then from the number of dioptres corresponding to the combined focal distance must be subtracted the number of dioptres added. Suppose, for example, that we have found that a certain glass combined with a lens of + 10 *D* throws a distinct image upon the wall at a distance of 14 centimetres. 7 *D* correspond to a focal distance of 14 centimetres, for $100 \div 14 = 7$. Since the auxiliary glass was one of 10 *D*, the glass which is being determined must be $7 - 10\ D = -3\ D$. It is, therefore, a concave glass having a refracting power of 3 *D*.

2. If we have a case of glasses at our disposal, we determine the refractive power of a lens most speedily by placing lenses of the contrary sign before it until we have found a lens which completely neutralizes the first one. So if we had to search for the number of a concave lens we would keep adding to it stronger and stronger convex lenses until the combined action of both lenses is the same as that of a plane glass. This is the case when vision through the combination is the same as with the naked eye. A still more certain way of deciding this question is by parallactic displacement. If we look at a distant object through a concave glass and then move the glass to and fro before the eye, the object executes an apparent movement in the same sense; but if we look through a convex glass, the apparent movement of the object takes place in the contrary direction. Hence, as long as one of the two superimposed glasses is in excess of the other, we get a parallactic displacement in one direction or the other—a

displacement which disappears the moment we combine two perfectly similar glasses of different sign.

The general practitioner who does not care to buy a complete trial-case can get along with one having a smaller number of glasses (10 to 12 convex and as many concave), as by their combination he can produce the other numbers.

The effect of the glasses depends not only upon their refractive power, but also upon their distance from the eye. The effect of concave glasses is weakened and of convex glasses is strengthened the farther they are held from the eye. We hence see old people whose convex glasses have already become too weak for reading frequently push their glasses far down on the nose so as to carry them away from the eye. The stronger the glass the greater is the influence which its distance from the eye exerts. For this reason the intervals between the separate numbers are not required to be so numerous in the case of the stronger glasses as in the weaker ones, since the effect of the former can be readily increased or weakened by slight alterations in its distance. This is mainly of advantage to those that have been operated upon for cataract, who possess no power of accommodation, and hence with their strong convex glasses can never have their sight adjusted except for one definite distance. By slightly displacing the glass they so far help matters that with the same glass they can see sometimes a little closer to them, sometimes a little farther off.

In the act of displacing the glasses attention should be paid to having the centers of the glasses separated from each other as far as are the pupils of the person wearing the glasses, otherwise he would be looking through the edges of the latter. In this case the images are less distinct, and, moreover, the glasses then act like weak prisms.

It is frequently the case that a person needs glasses for vision both at a distance and near by, but that these are of a different strength. If the gaze has to be directed alternately and in rapid succession at far and near objects, as, for example, in the case of a painter who looks first at the landscape then at his canvas, the continual changing of glasses would be very troublesome. For such cases glasses are employed composed of two bisected lenses which meet along a horizontal plane. The upper half is designed for distant, the lower for near vision, since in looking near by the visual plane is somewhat depressed. From their inventor,* who also was the first to use them, such glasses are called Franklin glasses. Instead of joining two separate glasses together we may also order the same glass ground, so as to have a different curvature in its upper half from that which it has in its lower (bifocal lenses).

The only advantage that glasses made of rock-crystal, which are much dearer than those ground from glass, have over the latter is that on account of their superior hardness they are less readily scratched—an advantage, however, which is of consequence only in convex lenses.

---

* [Benjamin Franklin.—D.]

CHAPTER II.

OPTICAL PROPERTIES OF THE NORMAL EYE.

(*a*) *Refraction.*

138. By the refraction of the eye we mean the state of its refraction in the state of rest—i. e., in the absence of any accommodative effort. The refraction of the normal eye is so constituted that parallel rays impinging upon the cornea are united so as to form a sharp image upon the retina. The retina, therefore, is situated at the principal focal distance of the dioptric apparatus of the eye, and thus constitutes its focal plane. Such a refractive condition is called *emmetropia*,* *E* (Donders).

In order to follow the passage of the rays through the refracting media of the eye we must know precisely the curvature of the refracting surfaces, their distance from each other, and the index of refraction of the individual refracting media. On the basis of these data we can by a complicated calculation find the path of the rays from one refracting surface to the other. To facilitate this calculation for practical purposes, Donders has devised a simplified schematic model, the *reduced* or *schematic eye* (Fig. 135). This has an axial length of 20 millimetres (*h b*) and consists of a single refracting substance, which has an index of refraction of $\frac{4}{3}$, and the anterior surface of which (representing the anterior surface of the cornea) has a radius of curvature of 5 millimetres. Hence, the center of curvature which coincides with the nodal point (*k*, Fig. 135) lies 5 millimetres behind the refracting surface and 15 millimetres in front of the retina, which lies at the principal focal distance of the eye (20 millimetres). This schematic eye varies very essentially from the normal human eye, the principal focal distance of which (axial length) amounts to about 24 millimetres; but calculations in regard to the size of retinal images, of diffusion-circles, etc., which are made upon the basis of the schematic eye, give results which approximate very closely to those found for the real eye. Hence, for practical purposes the schematic eye can without hesitation be made the basis of calculation.

The calculation which the ophthalmic practitioner has most frequently to make concerns the size of the retinal image of a given object. To do this the size of the object and its distance from the eye

* From ἔμμετρος, in due measure, and ὤψ, eye.

must be known. The retinal image of the object $o\,o_1$ is $b\,b_1$ (Fig. 135). The triangles $o\,o_1\,k$ and $b\,b_1\,k$ are similar; hence, $b\,b_1 : o\,o_1 = b\,k : o\,k$ and $b\,b_1 = \frac{o\,o_1 \times b\,k}{o\,k}$. If we call the size of the image ($b\,b_1$) B, that of the object ($o\,o_1$) O, and the distance of the latter ($o\,k$) from the eye E, then $B = \frac{O \times 15 \text{ mm.}}{E}$. The size of the retinal image is therefore directly proportional to the size of the object and inversely proportional to the distance of the object from the eye. E. g., a rod 1 metre high



FIG. 135.—REDUCED (SCHEMATIC) EYE OF DONDERS.

placed at a distance of 15 metres from the eye would give a retinal image whose altitude $B = \frac{1{,}000 \text{ mm.} \times 15 \text{ mm.}}{15{,}000 \text{ mm.}} = 1$ mm. This rod, if approximated to one third of the distance—i. e., 5 metres—would give a retinal image of $\frac{1{,}000 \text{ mm.} \times 15 \text{ mm.}}{5{,}000 \text{ mm.}} = 3$ mm., or three times as great as before. This sort of calculation is often applied in order to discover the size of a diseased area of the retina, corresponding to which is a scotoma in the visual field, whose size can be determined by examination. The scotoma is then regarded as the object for which the size of the retinal image is calculated.

(*b*) *Visual Acuity.*

139. The smaller the objects that an eye can distinguish or the greater the distance at which it can distinguish an object of given size, the greater is the acuity of vision that it possesses. Suppose, for instance, that the eye is able just to distinguish the object $a\,b$ (Fig. 136) at the distance $a\,k$. Another, better eye still distinguishes the object when it is carried twice as far off, to the distance $a_1\,k$. The size of the retinal image $\alpha\,\beta_1$ is in this case reduced to half of that in the former ($\alpha\,\beta$)—that is, the visual acuity of the second eye is twice as great as

that of the first. Instead of carrying the object $a\,b$ twice as far off, we may leave it at the same spot but make it half as small ($a\,b_{II}$). In this case, too, the size of the retinal image would be reduced one half. In both cases, therefore, a retinal image of the same size is obtained, and that, moreover, because the angle v remains the same. This angle is subtended by the rays which pass from the terminal points of the object through the nodal point of the eye to the retina. It is called the visual angle (angulus visorius), and is the true measure of the visual acuity. For estimating the visual acuity—i. e., the least visual angle—there are from the above example two ways open to us, both of which are made use of. We may take an object of given size and carry it off with us from the eye until the farthest point at which it can be recognized is reached. This, for instance, is done when we try to find at what distance an eye is able to count the fingers when extended. The second way consists in conducting the test at a constant distance, objects of different size being presented to the eye and the attempt being



FIG. 136.—RELATION OF THE VISUAL ANGLE WHEN OBJECTS VARY IN SIZE AND DISTANCE.

made to find the minimum size which the object can have and still be recognized. This method is employed when we test the visual acuity with test-types.

What objects are best adapted for *testing the visual acuity?* A single dot, the distance of which from the eye is altered, is unsuitable because the visibility of a dot depends less upon the visual angle which it subtends than upon its luminosity. The fixed stars, radiant as they are, are nothing but mathematical points even when seen with the most powerful telescopes; they have, therefore, a visual angle equal to zero, and yet they are seen very clearly. Every one can recall having seen a cross upon the top of a church-spire, when sparkling in the luster of the setting sun, at distances at which the church-spire itself was scarcely distinguishable. For this reason we select for the test not one but two points (or two parallel lines) and then determine the greatest distance at which they can still be perceived as separate objects. From this can be readily calculated the minimum visual angle, which for a normal eye amounts to about 1′ (Volkmann). On the basis of this determination

Snellen has constructed his test-types. These consist of letters of varying size arranged in rows. Each row contains letters of the same size, and has a number inscribed over it. This number gives the distance in metres at which the separate letters of the row ought to be distinguished by a normal eye. For example, the letter *F* (Fig. 137) has been taken from the row with the superscription 12, and ought, therefore, to be read at a distance of 12 metres. Like all the other letters of the test-card, it is inscribed within a square, whose sides are divided by partition lines into 5 parts each. The dimensions are so chosen that the whole square appears under an angle of 5′ at the given distance (12 metres in the example selected). Each partial square is hence seen under an angle of 1′, which is the minimum visual angle for the normal eye. But the details of the letter, upon the recognition of which the ability to decipher the whole letter depends, correspond to the size of the partial squares. A normal eye will, therefore, distinguish Snellen's test-types at the distances given above the separate rows. It will see the letter *F* (Fig. 137) at 12 metres and its visual acuity $S^* = \frac{1}{1}\frac{2}{2} = 1$. As a general thing, however, we make the person under examination stand always at the same distance from the card—namely, 6 metres. If at this distance he distinguishes the lowermost row which has 6 written over it, he has $S = \frac{6}{6} = 1$; but if, for instance, he distinguishes only the uppermost letters, No. 60, $S = \frac{6}{6\,0} = \frac{1}{1\,0}$. Hence, S always $= \frac{d}{D}$, in which d is the distance at which the reading is done, and D the number of the row read.

Fig. 137.—A Letter from Snellen's Test-card.

The testing of vision near by is made with small print, namely, with the low numbers of Jäger's or Snellen's test-types. In doing this, we try to determine two distinct things—namely, what is the smallest-sized print that can be read, and what is the least and the greatest distance at which it is legible. It is evident from Fig. 136 that, the nearer the object approaches the eye, the larger do its retinal images become. If the object, $a_1\ b_1$ is brought down to one half the distance —i. e., to $a\ b$—its retinal image is made twice as large. Hence, the smaller the objects are, the nearer we hold them to the eye. Very myopic eyes often have defective visual acuity, and yet pass among the laity as being excellent, because they can distinguish extremely minute objects. But the only reason for this is that they are able to hold objects extremely close. Persons with diminished visual acuity like to bring objects up extremely close, so as to get quite large retinal images from them, and in this way make up for what the images lack in dis-

* [S = Sehschärfe, visual acuity. In this country V (= vision, or the Latin visus) is usually employed.—D.]

tinctness or the retina lacks in sensitiveness. Such persons are often wrongly regarded as very myopic.

When the visual acuity has become so reduced that the largest letters of Snellen's test-card can no longer be recognized at 6 metres, the patient must go up nearer to it, or we select, instead of the letters, objects that are easier to distinguish—e. g., the outspread fingers, and try to find at what distance they can be counted. When the visual acuity is still worse, nothing can be distinguished but the movements of the hand before the eye. When even this is no longer the case, so that the eye simply distinguishes light from darkness, we say that qualitative vision is lost and that only quantitative vision—i. e., mere perception of light * is present.

Arlt, in 1844, was the first to introduce letters of different size (measured in lines) as a standard for determining the visual acuity. Ten years later Jäger published his scale of types, which soon acquired general acceptance, and which even at the present time is frequently employed. Practically these are very useful, since they present a great number of successive grades in the size of the letters; but they are not arranged upon any scientific principle. This defect Snellen has supplied by his test-types, which at present are the ones most extensively employed. Snellen has based them upon the assumption that the minimum visual angle for a sound eye amounts to 1′, so that No. 6 of the test-types, the details of which appear under an angle of 1′, can still just be read at this distance. He has, therefore, assumed $S = \frac{6}{6}$ as the normal visual acuity. But we are not to suppose that this is absolutely the greatest visual acuity that there is. Most eyes in young persons see No. 6 at a greater distance, as far as 12 metres or even farther, so that they may possibly have $S = \frac{12}{6} = 2$, or more. $S = \frac{6}{6}$ is accordingly to be looked upon simply as the minimum to be required of a normal eye; if the visual acuity sinks below this minimum, the eye is no longer to be considered as perfectly normal. The eyes of very aged persons are an exception, as such people even without any disease often show a visual acuity less than $\frac{6}{6}$. The cause of this lies mainly in the lessened transparency of the refracting media at an advanced age, and more particularly in the very dark-colored nucleus of the lens.

In order that persons who have a vision $S > \frac{6}{6}$ may not have to go beyond a distance of 6 metres, Snellen's cards are provided with still smaller letters—namely, with the numbers from 5 to 2. These, moreover, can be used for those cases in which the physician does not have a room 6 metres in length, but has at his command one of, say, only 5 or 4 metres. For persons who can not read, there are cards with curved and angular figures.

The illumination must be considered in making the tests for vision. Artificial illumination is the best one for the letter-card, because this can always be made of the same strength, while the illumination produced by daylight varies according to the weather and the hour of the day. On a dark day we must make our own visual power the basis of estimation in determining the results obtained with the patient. If a physician, who with good illumination has $S = \frac{6}{6}$, sees on a cloudy day only $\frac{6}{9}$ ($\frac{9}{9}$), the visual acuity of the patient found upon the same day must also be increased by one third.

* For the method of testing this, see § 156.

The visual acuity as determined by Snellen's card is usually given without reducing the fractions: thus we write $S = \frac{6}{6}$ or $S = \frac{12}{12}$, not $S = \frac{1}{1}$ or $\frac{1}{2}$. This is done with the object of showing by the fraction in what way the visual acuity has been obtained—i. e., what number was read and at what distance this was done.

To know the *absolute visual acuity* of an eye we must test it in a condition of emmetropic refraction and with the accommodation completely relaxed. For the latter purpose the eye should be made to look at infinite distance. Since this can not be carried out in practice, we satisfy ourselves with hanging Snellen's card at a distance of 6 metres from the patient whom we are examining. The rays impinging upon the eye from this distance subtend such a small angle that for practical purposes they may be regarded as parallel—i. e., as coming from infinite distance. If the eye under examination is not emmetropic but has an error of refraction, it must first be corrected by glasses up to the point of emmetropia (E). The visual acuity, which an ametropic eye shows without glasses is its *relative visual acuity*, and furnishes no measure whatever of the general usefulness of the eye for vision.

(*c*) *Accommodation.*

140. Suppose that we hold an open book at a distance of about 40 centimetres from one eye and the point of a pencil at about half this distance between the book and the eye, the other eye in the mean time being kept closed. We can soon convince ourselves that the print of the book and the point of the pencil are never seen clearly at the same time. All that we can do is to see either the print or the point distinctly, and it takes some time to "focus" from one object to the other, and in doing this a change is felt to take place in the eye. This



FIG. 138.
The eye being focused for a certain distance, B, rays emanating from a nearer point, S, form a diffusion-circle upon the retina.

change is the accommodation, which is alternately thrown into a state of tension and relaxation, by which means the optical adjustment of the eye is altered.

Why is it that, when we have our gaze fixed upon the print, we do not see the point of the pencil before us distinctly? Because we see it in *diffusion-circles*. What does this mean? If the eye (Fig. 138) is

focused for the rays emanating from the book, B, they are united upon the retina at b. The rays coming from the point of the pencil (S), which is nearer, have a greater divergence, and hence if the condition of the refracting media remains the same, are rendered somewhat less convergent by the latter; they would therefore unite at s—that is, behind the retina. As a matter of fact, the cone which they form has its apex truncated by the retina. The section thus made, which represents the image upon the retina of the point s, is circular because the base of the cone—namely, the pupil—is circular; hence, we say that the point S appears upon the retina under the guise of a diffusion-circle. That vision should be rendered indistinct by the diffusion-circles is easy to understand. Suppose that there are two points so far distant from each other and from the eye that when the latter is accurately focused they appear as two separate punctate images upon the retina (Fig. 139 A); the points are then readily recognized as two. But if, in consequence of the eye's being incorrectly focused for the position of either point, a diffusion-circle is formed upon the retina, the two circles, provided they are but a short distance from each other, partly overlap (Fig. 139 B), and the eye imagines that it has before it only one elongated point. A line (Fig. 139 C), when seen in diffusion-circles, does not look distinct, but appears broadened and hazy; for we may conceive a line to be composed of an infinite number of points placed side by side, and if each one of these is seen as a diffusion-circle, and the circles to a great extent overlap (D), the narrow line is converted into a broad band (E).



FIG. 139.—DIFFUSION-CIRCLES.

Vision, then, is always in diffusion-circles when the eye is not properly focused for the object of fixation. This may occur not only through improper accommodation, as in the example selected, but also on account of faulty refraction, such as myopia or hypermetropia. All indistinct vision which is caused by an anomaly of refraction or accommodation is produced by diffusion-circles. The larger the diffusion-circles are, the more indistinct is the vision. We must, therefore, inquire upon what the *size of the diffusion-circles* depends:

1. The diffusion-circles are larger in proportion to the remoteness from the retina of the focus of the rays emanating from the object. Suppose (in the instance above adduced) that the eye is focused for the book, so that the point of the pencil (S, Fig. 140) appears in diffusion-circles.

believe that they become less near-sighted with increasing years because they see better at a distance; but this is often simply due to the circumstance that their pupils diminish in size with age. Far-sighted persons who are compelled to read close to them without convex glasses try to get as brilliant an illumination as possible, so that their pupils may become very greatly contracted and thus diminish the size of the diffusion-circles. The same object is secured to a still greater extent by placing a fine stenopæic aperture before the eye. This allows only a very narrow beam of rays to pass, and reduces the diffusion-circles so greatly that they no longer exert a disturbing effect. If we repeat the experiment made above of attempting to look simultaneously at the book and the pencil-point, and while we are doing it hold a minute aperture before the eye, we see the print and the pencil-point distinctly at the same time. By means of a stenopæic aperture myopic persons can see distinctly at a distance even without concave glasses.

The pupil, being the base of the cone of light, determines not only the size but also the shape of the diffusion-circle, which accurately mirrors the shape of the pupil. In this way it happens that persons with irregular pupils (owing, for example, to posterior synechiæ) are very well able themselves to perceive these irregularities.

In making the above experiment with the pencil and book, we feel that the eye is called upon to make an active effort when it is directed by a process of adjustment from the more distant book to the less distant pencil. In the same way, although not quite so distinctly, we feel a relaxation of this effort when adjustment is made for the book again. It may be concluded from this that the change of adjustment from a more distant to a less distant point is an active process—i. e., a muscular effort. On the other hand, the relaxation of the accommodation by which the eye is again adjusted for a greater distance consists in a relaxation of the contracted muscle. When in a state of perfect rest, the emmetropic eye is adjusted for infinite distance. This condition of adjustment we find existing when the ciliary muscle is completely relaxed either, naturally from paralysis of the oculomotor nerve, or artificially from the use of atropine.

The *mechanism of accommodation* was determined, once for all, by the investigations of Helmholtz. It depends upon the elasticity of the lens, owing to which the latter always tends to approximate to the shape of a sphere. In the living eye the lens is inclosed in a capsule which is attached to the ciliary body by the fibers of the zonula of Zinn. These fibers are tightly stretched, and hence exert a uniform traction from all sides upon the capsule, so that the latter and the lens as well are flattened. The elasticity of the latter can only make itself apparent when the tension of the fibers of the zonula, and hence, too, of the capsule of the lens, is relaxed. This takes place most completely after division of the fibers of the zonula. When we remove the lens

from the eye of a young person, we see it assume a spherical shape immediately upon the division of its connections. The same thing is observed in traumatic luxation of the lens into the anterior chamber. In the act of accommodation, the relaxation of the zonula is effected by the contraction of the ciliary muscle. It is the annular layer of fibers of the latter (Müller's portion; see *Mu*, Fig. 47) that is mainly of account in accomplishing this. When this fiber-layer contracts, it lessens the size of the circle formed by the ciliary processes by approximating their apices to the border of the lens (shown by the black line in Fig. 142). In this way the space between the ciliary body and lens, which is bridged over by the fibers of the zonula, is contracted and the zonular fibers themselves are relaxed. It is the task of longitudinal

FIG. 142.—SCHEMATIC REPRESENTATION OF THE PROCESS OF ACCOMMODATION.

The relation of the parts when the accommodation is at rest is designated by the shaded portions, and the relation when there is an effort of accommodation by the black line. The latter shows the ciliary processes and also the equator of the lens pushed toward the axis of the eye. Both surfaces of the lens are more curved and the anterior surface is pushed forward. The iris is broader, and at its pupillary border is displaced forward; at its ciliary border backward.

fibers of the ciliary muscle (Brücke's portion; *M*, Fig. 47) to reinforce the action of the circular fibers. The former have their anterior, fixed insertion in the corneo-scleral margin, while their posterior extremity loses itself in the movable chorioid. By the contraction of these fibers the flat portion of the ciliary body and the most anterior portion of the chorioid are drawn forward, and thus the relaxation of the fibers of the zonula which lie upon the surface of these structures is facilitated; but the main part of the work of accommodation always falls upon the annular fibers of the ciliary muscle, for which reason we find these fibers particularly well developed in eyes which have to accommodate a good deal—e. g., those of hypermetropes (see Fig. 153).

By the relaxation of the zonula the tension of the lens-capsule is diminished, so that the lens is enabled in conformity with its elasticity to assume a more curved shape. At the same time there is necessarily produced a corresponding decrease in the equatorial diameter of the lens. The equator of the lens, accordingly, recedes inward toward the axis of the eye, and is thus kept from coming into contact with the ciliary processes as they advance.

The increase in curvature affects both the anterior and the posterior surfaces of the lens, but the former to a much higher degree (Fig. 142). The posterior surface of the lens does not change its place in the fossa patelliformis of the vitreous, the increase in thickness of the lens being effected simply by the advancement of its anterior surface. Hence, the anterior chamber becomes correspondingly shallower; at the periphery alone is there a deepening of the chamber, inasmuch as here the iris recedes a little. The sphincter pupillæ and, if vision is performed with both eyes, the two internal recti also, contract in conjunction with the ciliary muscle. The act of accommodation, accordingly, is regularly accompanied by a contraction of the pupils and a movement of convergence.

141. Measurement of the Accommodation.—In order to measure the magnitude of accommodation we must determine two points. One of these is the remotest point which the eye can see with distinctness—i. e., the point for which the eye is focused when the accommodation is completely relaxed (*far-point*, or punctum remotum; *R*). The second is the nearest point which the eye can see with distinctness when exerting its entire accommodation (*near-point*, or punctum proximum; *P*).

In the emmetropic eye, with which alone we shall for the present concern ourselves, *R* lies at an infinite distance, since the emmetropic eye when in the state of rest is focused for parallel rays. Such an eye, accordingly, can see the letters of Snellen's card distinctly when the latter is hung up at a distance of 6 metres, which in practice is regarded as infinitely great.

While the position of *R* is the same for all emmetropic eyes, that of *P* varies greatly. It is determined by bringing fine print closer and closer to the eye until the limit of legibility has been reached. Suppose, for example, this occurs at 10 centimetres ($P = 10$ centimetres). The space lying between *R* and *P*—i. e., in the example selected the space between ∞ and 10 centimetres—is called the *region of accommodation*. But the extent of this region affords no measure for the amount of work done by accommodation; this, in fact, being measured by the increase of refractive power which the eye undergoes in passing from the state in which the accommodation is at rest (*R*) to the state in which the utmost effort of accommodation is made (*P*). The amount of increase of refractive power is called *amplitude of accommodation*

(A), and is accordingly the difference between the refractive power of the eye when the accommodation is exerted to its utmost and when it is at rest—i. e., $A = P - R$. For R and P in this equation should be substituted, not their linear values, but the number of dioptres; these being, in fact, our measure of the refracting power.

The method of determining the amplitude of accommodation requires some explanation which is best given by concrete examples. Let us assume the three following cases represented graphically in Fig. 143: 1. An emmetrope twenty years of age, whose far-point lies at an infinite distance and near-point at 10 centimetres from the eye; 2. An emmetrope thirty-seven years of age, whose $R = \infty$ and $P = 20$ centimetres; and lastly, 3. A myope twenty years of age, whose $R = 10$ centimetres and $P = 5$ centimetres. The region of accommoda-



FIG. 143.—REGION OF ACCOMMODATION.

1. In an emmetrope of twenty years; 2. an emmetrope of thirty-seven years; 3. a myope of twenty years.

tion—i. e., the space lying between R and P—is of a very different extent in these three cases. In cases one and two it is infinitely large, since it extends to an infinite distance, while in case three it amounts to only 5 centimetres. If, therefore, we were to reckon the work done in accommodation by the extent of the region of accommodation, we would arrive at the erroneous view that, with regard to the former as well as the latter, there is an enormous difference between the first two cases on the one hand and the third case upon the other.

But, as a matter of fact, the case is quite different, as can be gathered from the experimental test of the accommodation adduced above. Suppose that while we close one eye we hold before the other a book at a distance of 20 centimetres, and a pencil-point midway between the book and the eye—i. e., at a distance of 10 centimetres from the latter. We then first look out into space over the book, so that the accommodation is completely relaxed, and then fix our gaze upon the print of the book. In so doing, we have a sense of accom-

modative effort in the eye. We now turn our glance from the book to the pencil-point, and endeavor to see the latter distinctly. If this is possible at all, it costs us a very considerable effort which will tax the energies of most persons more than does the effort required to adjust the eye from infinite distance to the book. Hence, the act of changing the accommodation from 20 centimetres to 10 centimetres costs us at least as much effort as the change from infinity to 20 centimetres. From this it is clear that we are not justified in taking the linear distance between the points of fixation as a measure of the accommodative effort, and that, therefore, the region of accommodation can not serve as an expression of the work done in accommodation.

We get a correct idea of the amount of accommodation that is called into play if we take into consideration the increase produced in the refractivity of the eye by the accommodation. This increase of refractivity is effected by an increase in the curvature of the lens, a thing which we can also conceive of as accomplished by the addition to the unchanged lens of a second, weaker convex lens. This "supplementary" crystalline lens (z, Fig. 144), represents the increase in refractivity, and would form the best measure of the accommodation. Now, of course, we can not determine the refractive power of this supplementtary lens directly, but we can determine what glass placed before the cornea of



FIG. 144.—ACCOMMODATION REPRESENTED SCHEMATICALLY BY A "SUPPLEMENTAL" CRYSTALLINE LENS, z.

the eye would produce the same increase of refractive power as would such a supplementary lens, conceived to exist in the eye. What proceeding to adopt in doing this may be shown by case one of those assumed above (Fig. 143). In this, when the accommodation is making its utmost effort, the refractivity of the eye is increased by the supplementary lens to such an extent that rays emanating from P—that is, from a distance of 10 centimetres from the eye—are united upon the retina (Fig. 144). We now paralyze the accommodation in this eye with atropine, so that the eye remains steadily focused for infinite distance, and try to find the convex glass with which the eye is enabled to see the point, P, distinctly. We find that for this purpose a glass, L, of a focal distance of 10 centimetres = one of 10 D is necessary (Fig. 145.) If this glass is placed in front of the eye—i. e., 10 centimetres behind the point P—the latter will lie just in the principal focus of the glass.* The rays (pp, Fig. 145) ema-

* Properly, if we take into account the distance of the lens from the eye, we should have to choose a lens of shorter focal distance—e. g., when the distance be-

nating from P are hence made parallel by the glass, and being so, are united by the non-accommodating eye upon its retina. The lens L, therefore, does the same work as the natural accommodation (represented by the supplementary crystalline lens, z), and can accordingly be taken as the measure of the latter. Accommodation measured in this way we call *amplitude* [or *range*] of accommodation. This, therefore, would be in the first case $A = 10\,D$. In the second case (Fig. 143, 2) as may be shown in the same way, $A = 5\,D$. Hence, in the emmetropic eye, A is expressed by the lens whose focal distance equals the distance of the near-point from the eye; or, $A = P$, when P is expressed in dioptres.

What relation does A bear in the third case (Fig. 143, 3)? Here P is situated at 5 centimetres, and hence $P = 20\,D$. But this value can not be regarded as the expression of the work done in accommodation, since the eye in question being short-sighted, is, even when the accommodation is at rest, adjusted for a distance less than infinity—i. e., for 10 centimetres. This eye, when its accommodation is at rest, acts like a non-accommodating emmetropic eye before which has been placed a lens of $10\,D$ (Fig. 145); for this eye, therefore, we can say



FIG. 145.—THE ACCOMMODATION REPLACED BY A LENS OF GLASS, L, SET BEFORE THE EYE.

$R = 10\,D$. But, when making its utmost accommodative effort, this eye acts like a non-accommodative emmetropic eye before which has been placed a glass of $20\,D$. Obviously, in order to determine the work done in accommodation—i. e., the increase in refractivity in passing from R to P—we must subtract from the value corresponding to P the value of R, or $A = 20\,D - 10\,D = 10\,D$. Hence, we may enunciate the following formula as representing the general law:

$$A = P - R,$$

in which P and R are expressed in dioptres. This formula holds good for all conditions of the refraction. For the emmetropic eye it is simplified by the fact that the latter, when the accommodation is at rest, is adjusted for infinite distance, so that $R = 0\,D$, and consequently $A = P$, as we found above.

Let us take another survey of the three cases, and compare the region of accommodation with the range of accommodation. We find that the former is infinitely large in the first two cases, and only 5 centimetres in the third case. Now, A in the first case is $10\,D$, in the second only half as great—i. e., $5\,D$—and in the third case again is as great as in the first. Accordingly, from the

tween the lens and the nodal point of the eye amounts to 1 centimetre, one of 9 millimetres.

range of accommodation we get an entirely different and in fact a more correct conception of the work done in the accommodative act than we do from the region of accommodation. This is owing to the fact that different portions of the region of accommodation represent entirely different values. It takes as much accommodative effort to bring the accommodation from 10 centimetres to 5 centimetres (case three) as to accommodate from infinity to 10 centimetres (case one); the value in both cases being 10 *D*. This fact is in harmony with the sensations that we experience in our eyes when, in the experiment previously adduced, we look successively at infinite distance, at the book, and finally at the pencil-point. Displacement of the accommodation through 1 centimetre of the region of accommodation is significant of an effort which is the greater, the nearer this centimetre is situated to the eye.

The region of accommodation, however, gives us a good idea of the *availability of accommodation*. In case one the region of accommodation is so situated that the eye sees clearly at all distances which can be considered to exist in practical life. But in case three the region of accommodation lies so close to the eye that practically it has no value whatever; this eye would be no worse off without accommodation. (This, of course, holds good only upon the supposition that correcting glasses are not worn, as by these the location of the region of accommodation is shifted.)

Practical Determination of *R* and *P*.—Since the refraction of the eye as commonly determined, is its refractivity when the accommodation is at rest—i. e., when the eye is focused for the far-point—the determination of the refraction and of the far-point are synonymous; if the latter has been got at, the refraction is determined as well. Emmetropia is present when *R* lies at infinity. How do we ascertain whether this is the case or not? Primarily by the fact that such an eye can read No. 6 of Snellen's test-types at 6 metres (a distance which is regarded as equivalent to infinity). In this case the condition in which *R* is nearer than infinity (myopia) is excluded by the test, because then No. 6 could not be seen distinctly enough to be read. On the other hand, hypermetropia is not excluded, since this can be so far corrected by an effort of accommodation that the eye is focused for infinite distance (see § 147). But in this case No. 6 would also be seen distinctly with convex glasses—a thing which would not be possible for an emmetropic eye. Hence we must say: Emmetropia is present—i. e., $R = \infty$—when Snellen's No. 6 is read at a distance of 6 metres with the naked eye, but not with the weakest convex glass.

P is determined by the lowest numbers of the reading tests, but the rod-optometer may also be employed. This latter consists of fine threads which are stretched in a metal frame, and which are brought closer and closer to the eye until they cease to appear perfectly distinct.

When *P* has receded to such a distance from the eye that small objects like fine print or the threads of the rod-optometer appear under too minute an angle, and hence can not be seen distinctly at all, the following expedient is adopted: We place before the eye a convex glass—e. g., one of 6 *D*, by which near vision is rendered distinct—and then determine the near-point. This is found to be, say, 16 centimetres. The refraction corresponding to this distance is 6·5 *D*, from which, in order to learn the actual near-point, we must subtract the 6 *D* supplied by the lens. Thus $P = 6{\cdot}5\ D - 6\ D = 0{\cdot}5\ D = 50$ centimetres.

Relative Accommodation.—In the course of our considerations in regard to the accommodation hitherto, we have started from the assumption that vision

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

is performed with only one eye. When the two eyes are employed simultaneously the convergence as well as the accommodation must be taken into account. These two functions go hand in hand. When our gaze is fixed upon the distance, $A = \infty$, and the visual axes are parallel—i. e., the convergence, too, is in a state of rest. When we look at a near-point—e. g., one situated at a distance of 20 centimetres—we are compelled both to accommodate and to converge for this distance. Hence, through constant practice an intimate connection is effected between accommodation and convergence, so that with any given accommodation the corresponding effort of convergence is always made, and vice versa.



Fig. 146.—Schematic Representation of Relative Accommodation.

This connection, however, is not one that is rigid and insusceptible of change. On the contrary, we have the ability of emancipating ourselves from it within certain limits—that is, while in the act of converging for a certain distance, of making a little more or a little less accommodation than corresponds to this distance. A man is made to fix his gaze upon fine print at a distance of 33 centimetres. Now, suppose that the subject is emmetropic and thus has his far-point (R) at infinity while P is situated at 10 centimetres, which corresponds to a range of accommodation (A) of 10 D (Fig. 146). Of this range of accommodation 3 D will be employed in making convergence at 33 centimetres ($100 \div 33 = 3$). Now, a concave glass of 1 D is placed before each eye. The subject will for the first moment have obscuration of vision, but will soon see distinctly. He has compensated for the diminution of the refractive power of his eye, caused by the -1 D glass, by exerting 1 D more of his accommodation. But the convergence meanwhile remains unchanged—

i. e., it is still adjusted for 33 centimetres. The same phenomenon occurs when, instead of $-1\ D$, a glass of $+1\ D$ is placed before the eye. The refractive power of the eye is made too great by the convex glass, and this is neutralized by the eye's relaxing its accommodation through $1\ D$. In this way we can bring stronger and stronger glasses successively before the eye until finally we come to those with which distinct vision is no longer possible. We thus find the limits (*relative accommodation*) within which the accommodation may be augmented or relaxed, the convergence remaining the same.

In the example selected, suppose that the subject is able to see distinctly at a distance of 33 centimetres with a convex glass of $2\ D$. This corresponds to a relaxation of his accommodation from $3\ D$ to $1\ D$—that is, his relative far-point, R_1, lies at a distance equivalent to $1\ D$, or 1 metre, from the eye. Suppose that, on the other hand, the subject with the same degree of convergence overcomes concave glasses of $3\ D$, a thing which is effected by an augmentation of the accommodation from 3 to $6\ D$, his relative near-point, P_1, then is at a distance equivalent to $6\ D = 17$ centimetres. The relative range of accommodation $A_1 = P_1 - R_1 = 6\ D - 1\ D = 5\ D$. This is the relative range of accommodation for a convergence of 33 centimetres; for a different convergence the relative near-point, far-point, and range would be different still. On the other hand, there is only one absolute far-point, near-point, and range of accommodation.

The region of relative accommodation is divided by the point upon which convergence is made into two segments. One lies upon the proximal side of the point of fixation, and thus in the example selected extends from 3 to $6\ D$. It represents the amount of accommodation which, if necessary, one can still press into service while keeping the convergence the same—i. e., it represents the amount of accommodation which one may be said to have in reserve. It is hence denoted as the positive portion (+, Fig. 146) of the relative range of accommodation. The other segment lies on the distal side of the point of fixation, and in our case extends from 3 to $1\ D$. It is that part of the relative accommodation which has already been employed in maintaining the given degree of convergence—i. e., it is its negative portion (−, Fig. 146). Hence, with a convergence of 33 centimetres the positive portion of the relative accommodation amounts to $3\ D$, the negative portion only to $2\ D$. Upon the relation of the two segments to one another depends the ability of the eye to work continuously and without exhaustion while keeping up the necessary convergence and accommodation. A man is able to make frequent successive repetitions of a bodily effort only when this effort does not lie near the limits of his working capacity. If, for example, one has to set in motion the wheel of some machine which moves with such difficulty that he is able to make it revolve only by the exertion of his whole strength, he will possibly be able to do this two or three times in succession, but then will become exhausted. If a laborer is to keep the wheel in motion for an hour, each revolution of it must not take more than a moderate portion of his entire strength, so that another portion of his strength shall remain in reserve. This fact also holds good for the eyes. It is impossible to use them continuously except for a distance at which the positive portion of the accommodation is at least as great as the negative portion, otherwise exhaustion rapidly supervenes.

When the gaze is fixed upon infinite distance, the negative portion of A_1 is equal to zero, since then the accommodation is completely relaxed. All the

relative accommodation therefore is positive, and accordingly exhaustion of the eyes is impossible. Thus, no one will complain that his eyes get tired from walking. For a convergence of 33 centimetres, it has been shown above that the positive portion of the relative accommodation (A_1) is half as large again as the negative portion, for which reason work can be carried on continuously at this distance without exhaustion. When fixation is made upon an object situated at the absolute near-point of the eye, the entire relative accommodation (A_1) is negative. A positive or reserve portion of accommodation does not exist in this case, since the whole absolute accommodation (A) has been already used up. Hence we can have distinct vision at our near-point for only a moment or two at a time. From what has been said, it follows that work is more exhausting for the eyes the nearer it has to be brought to them.

Changes of the Accommodation with Age.

142. 2. The accommodation diminishes with age, and this diminution is manifested by a continuous recession of the near-point. The diminution in the accommodation can not be referred to the decrease in the power of the muscles in general and the ciliary muscle in particular occurring in old age, for it begins in youth, and probably even in childhood—that is, at the time when the muscles are still gaining in strength. In fact, the cause of the diminution of the accommodation lies in the gradual decrease of the elasticity of the lens. This, again, stands in causal connection with the condensation of the lens due to loss of water and leading to a process of sclerosis that begins in the center of the lens (formation of a nucleus). The harder the lens becomes in virtue of this process the more its elasticity is impaired, so that even after relaxation of the zonula it becomes less and less able to change its shape.

The state of the accommodation at different ages is shown in the accompanying figure (147) taken from Donders. The line $r\ r$ shows the position of the far-point, the line $p\ p$ that of the near-point, for all ages from ten to eighty; the distance between the two lines gives the range of accommodation in dioptres at the different ages. The far-point remains pretty nearly constant during the whole life—i. e., at infinite distance; but the near-point continually recedes, so that the line $p\ p$ forms a curve which constantly approaches the line for the far-point, until finally it coincides with it. When this occurs the range of accommodation is equal to zero, and the lens no longer changes its shape.

The diminution in the range of accommodation does not begin to be troublesome until the near-point has receded so far from the eye that the finer kinds of work become difficult or impossible to do. This condition is known as *presbyopia*.* Since the diminution in the accommodation takes place with perfect uniformity from youth to age,

* From πρέσβυς, old man, and ὤψ, sight.

and not by sudden advances, the point of time when presbyopia sets in must be established arbitrarily. Donders has assumed this time to be that at which the near-point recedes beyond 22 centimetres ($A = 4{\cdot}5$ D), an event which usually happens about the fortieth year of life. After this time it is hard work to read fine print, and hence glasses are desired.

Presbyopia is not a disease, but a physiological process which every eye undergoes. Persons who are presbyopic push the book farther



FIG. 147.—RANGE OF ACCOMMODATION AT DIFFERENT AGES. (AFTER DONDERS.)

away from them, like to avoid fine print, and overlook the foot-notes. Reading at night gives them special trouble, because the pupils dilate owing to the enfeebled illumination, and hence the diffusion-circles are larger. They then try the expedient of bringing the light between the book and their eyes, so as to make their pupils contract by having a large amount of light fall upon them. In the subsequent progress of presbyopia reading or fine work at last becomes absolutely impossible without glasses. Pain, however, or exhaustion does not occur, as it does in hypermetropes. When an eye is not emmetropic, but has an error of refraction, this error shifts the range of accommodation, and hence also the time when presbyopia begins. Reference in regard to this point must be made to the chapters upon myopia and hypermetropia.

Presbyopia requires the use of convex glasses for near work. The glass must be strong enough to make the near-point come into the

place which appears demanded by the work in question. The situation of this depends primarily upon the nature of the work; the finer this is, the closer must the near-point be approximated. But in addition to this the visual acuity must be taken into account. If the latter is defective, objects must be brought nearer, so as to make up in size what the retinal image lacks in distinctness.

From the reasons set forth above it follows that it will not do simply to prescribe for each separate age the convex glass that ought to be ordered. On the contrary, we must proceed according to the individual requirements of each case by itself, and determine the glass for it specially. Suppose, for instance, that the subject is sixty years old, and that his near-point is one metre from the eye ($A = 1\ D$). The man is a cabinet-maker, and in doing his work, which he carries on at arm's-length—i. e., at about 50 centimetres—no longer sees distinctly. His near-point, therefore, must be brought up to 50 centimetres ($= 2\ D$). As he himself can furnish 1 D, it suffices to give him a $1 + D$ glass (or, better still, 1·5 D, so that he may not have to work at his near-point, but may have some accommodation in reserve). Perhaps the same man also wishes a glass to read with in the evening when his work is done. For this purpose we must bring his near-point up to at least 30 centimetres (3·5 D), so that he can read ordinary print with ease, and we would therefore recommend him a glass of $+ 2{\cdot}5\ D$ or $+ 3\ D$.

Many erroneous views, which we must oppose, are prevalent among the laity with respect to the wearing of glasses in advanced life. Some consider it advantageous to begin wearing glasses as late as possible, and this from the fear that when once they begin they will have to keep on using stronger and stronger ones. But as far as this is concerned they gain nothing, whether they begin using glasses at the proper time, or for years struggle along laboriously without them until they can do so no longer. Every presbyope has to increase the strength of his glasses as long as his range of accommodation keeps diminishing. It is only when the range of accommodation has become equal to zero that he can stick to the same glass. It is just as erroneous to believe that by wearing glasses early one can "save" his eyes. Presbyopia goes on its appointed way unaffected by the wearing of glasses or by the nature of those that are worn, and independent of the fact whether the eyes are strained a good deal or not at all by fine work.

In examining Fig. 147 we are struck with the fact that the line $r\,r$, representing the far-point, does not run straight, as we should expect, but makes a curve. The far-point of the emmetropic eye, which lies at infinity, recedes beyond infinity at the age of fifty—that is, the refraction of the eye changes and it becomes hypermetropic. This fact has nothing to do with the diminution of accommodation. It depends upon a decrease in the refractive power of the eye, due to a senile change in the lens—a change which is effected by an increase taking place in the density, and hence in the refractive power, of the layers of the latter from within outward. Every ray of light passing through the lens undergoes a new deflection in each layer, so that the entire refraction is much greater than if the whole lens had even the high refractive power of its innermost layers but was at the same time homogeneous. Now, in old age, the process of condensation extends farther and farther from the center to the periphery, and the lens becomes constantly more homogeneous, so that as a whole it

suffers impairment of its refractive power. The emmetropic eye thus gets to be somewhat hypermetropic, while the myopic eye becomes less near-sighted, and, in fact, slight degrees of myopia may disappear altogether in old age.

Optical variations of the eye from the normal may relate either to its refraction or to its accommodation. The anomalies of refraction are to be strongly differentiated from those of accommodation, with which they are frequently confounded. An eye whose refraction varies from the normal or emmetropic we call ametropic.* There are three varieties of ametropia: myopia, hypermetropia, and astigmatism. When the refraction of the two eyes is different, we speak of anisometropia.†

* [From ἀ, privative, μέτρον, a limit, and ὄψ, sight.]

† [From ἄνισος, unequal, μέτρον, limit, and ὄψ, sight.]

CHAPTER III.

MYOPIA.

143. SHORT-SIGHTEDNESS (*myopia*, *M*) is that refractive condition of the eye in which rays that are parallel to each other when they fall upon the eye come to a focus *in front* of the retina. Hence, when the rays strike the retina, they have become divergent once more, and therefore form a diffusion-circle upon the latter ($a\,a_1$, Fig. 148). A distinct image is formed upon the retina only when the rays have a certain degree of divergence as they arrive at the eye, which is the case when



FIG. 148.—PATH OF THE RAYS IN A MYOPIC EYE.

they emanate from a point *R* situated close by (Fig. 148). This point is the far-point of the myopic eye. The greater the myopia, the farther in front of the retina is the point of intersection of parallel rays, and hence the greater is the divergence that rays must have in order to unite upon the retina, and hence, too, the nearer to the eye must the far-point (*R*) lie. Consequently the degree of myopia is determined by the distance of *R*.

Determination of Myopia.—The distance of *R* from the eye can be measured directly by placing fine print before the eye and gradually withdrawing it until it becomes too indistinct to be read. This method, however, has various defects, so that we prefer to determine the position of *R* by means of concave glasses. Let us assume that the eye has such a degree of myopia that its far-point is 50 centimetres in front of the eye (Fig. 149, *F*); the rays, then, that emanate from this point come to a focus upon the retina (at *f*). How can we manage to have this

eye see parallel rays distinctly—i. e., have them focused upon the retina? Evidently by giving them the same direction as if they emanated from the far-point. This is effected by placing before the eye a concave glass of 50 centimetres, focal distance—i. e., of $-2\,D$. By this glass parallel rays are rendered as divergent as if they emanated from its focus (see page 598). This lies 50 centimetres in front of the glass—that is, at the same spot at which the far-point of the eye is



FIG. 149.—CORRECTION OF MYOPIA BY A CONCAVE GLASS.

situated (at f). Accordingly, parallel rays acquire the same direction as if they emanated from the far-point of the myopic eye, and are hence focused upon the retina of the latter so as to form a distinct image. (In this discussion the distance of the glass from the eye is neglected.)

The deduction made in the foregoing example holds good for all degrees of myopia. The following rule may therefore be enunciated: A myopic eye sees distinctly at infinite distance with that concave glass whose focal length is equal to the distance of the far-point from the eye. And conversely: The focal length of that concave glass with which the myopic eye sees remote objects distinctly gives the distance of the far-point from the eye—i. e., the degree of myopia. If a man sees remote objects distinctly with $-5\,D$, his far-point is 20 centimetres ($100 \div 5 = 20$). But in designating the degree of myopia we do not usually give the position of the far-point, but give directly the refractive power of the correcting glass—writing, therefore, $M = 5\,D$.

If a glass of $-6\,D$ is placed before an eye whose $M = 5\,D$, such an eye would still see clearly at a distance; the extra strength of $1\,D$ being neutralized by a corresponding effort of the accommodation. Since in myopia there is often a tendency to accommodate, it is by no means rare to find myopes who are wearing glasses that over-correct. In order not to fall into the same mistake in determining myopia, and thus make the latter greater than it really is, we must regard as the correcting glass the *weakest* concave glass with which the myope sees distinctly at a distance. Hence, in determining myopia we proceed as follows: *We*

place the myope at a distance of 6 metres from Snellen's test-card, and keep putting concave glasses before his eyes, beginning with the weaker ones and gradually advancing to those which are stronger, until the best vision is obtained which can possibly be secured in this special case. The weakest concave glass with which this vision is obtained gives the degree of myopia.

This method of determining myopia, which was instituted by Donders, is the one generally employed. It is pretty tedious, since we are obliged to go gradually from weaker to stronger glasses, and frequently, therefore, have to place quite a large number of glasses before the eye before we get to the one that corrects. Hence, some have conceived the idea of determining not only myopia but also the refraction generally in a more expeditious way, namely, by the use of various apparatus which are called *optometers*. These are constructed upon various principles. Most consist of a test-object at which the eye looks through a single lens or through two lenses combined. The rays which enter the eye can be given a parallel, convergent, or divergent direction, and so adjusted to suit the different refractive errors that may exist, either by altering the place of the test-object or by shifting the lenses. The refraction is then simply read off from a scale which is attached to the instrument. In spite of the advantage accruing from the almost instantaneous determination of the refraction which these instruments afford, they have not become popular, because the refraction as found by them is regularly too high; for the person who is looking into the instrument exerts, without being aware of it, some effort of accommodation. Hence, if we desire to find the true refraction—i. e., the refractive state of the eye when the accommodation is relaxed—we are obliged first to paralyze the accommodation with atropine, a procedure which causes the patient considerable discomfort and annoyance.

The determination of myopia by glasses or optometers is called the *subjective* method, because it is dependent upon the statements of the patient. For this reason its results are not always exact. It often happens that, by the patient's straining his accommodation, a higher degree of myopia is simulated than really exists. Moreover, we are dependent upon the patient's good-will and the intelligence. Frequently we are dealing with malingerers, who purposely try to make their myopia appear too high, in order to escape military service. Again, in small children this method is not applicable. For such cases the *objective* method, which consists in the determination of the refraction by means of the ophthalmoscope, and which is therefore independent of the statements of the patient (see 16), is suitable. And even when the degree of myopia has been already determined by the subjective test, the result should in every instance be verified by the objective test for the refraction.

Causes of Myopia.—The fact of parallel rays coming to a focus in

front of the retina, which constitutes the essence of myopia, may in general arise in two ways:

1. The *refractive power of the eye is abnormally great*, so that parallel rays are made too convergent, the retina in this case being in its normal situation. The cause of the increased refractive power may lie in the cornea or in the lens. In the *cornea* it is increased curvature that leads to myopia. This, therefore, is found in ectases of the cornea of the most diverse sort, but to the greatest degree and most obviously in keratoconus, because in this condition the cornea at the same time retains its transparency. Myopia caused by increased curvature of the cornea is always associated with a considerable degree of astigmatism.

The *lens* can cause abnormal elevation of the refractivity of the eye either through increased curvature or through augmentation of density. The following cases are to be regarded as belonging in this category: (*a*) In luxation the lens takes on an increased curvature because the tension exerted by the zonula is removed. If the case is one of luxation into the anterior chamber, the forward displacement of the lens contributes to the increase in refractive power, since with the lens the nodal point of the whole dioptric system is shifted forward. (*b*) Accommodation, which increases the curvature of the lens, may be kept permanently in action, and as long as this spasm of accommodation continues myopia will be present. The latter disappears when the accommodation is paralyzed by atropine. (*c*) Myopia due to increase in density of the lens not infrequently sets in at the beginning of senile cataract (see page 366).

2. The refractive power of the eye may be normal, so that parallel rays come to a focus at the customary spot, but the retina may lie too far back. The cause of this is an elongation of the axis of the eye, for which reason this sort of myopia is called *axial myopia*. The distention of the sclera, to which the elongation of the eye is due, may affect either its anterior or its posterior division. We find the former condition after scleritis, in which the zone of sclera which adjoins the cornea is softened by inflammation, and then distended by the intraocular pressure (see page 214). But by far the most frequent site of the distention is in the posterior division of the sclera, which is bulged out posteriorly, forming the staphyloma posticum of Scarpa. This is the ordinary typical form of myopia, which therefore deserves special mention.

Typical Myopia.

144. Myopes see indistinctly *at a distance*, because of the presence of diffusion-circles. To make these smaller, and thus see better, they screw the lids together, and in this way produce a stenopæic slit. In fact, it is from this habit of blinking that the name myopia* takes its origin.

* From μύειν, to shut, to blink, and ὤψ, sight.

Myopes see well *near by*, and, moreover, have the advantage that they need use little or no accommodation for this purpose. The range of accommodation has the same relation in the myopic eye (if the high degrees of myopia are excepted) as in the emmetropic eye. Only, since the far-point lies at a finite distance, the whole region of accommodation is placed closer to the eye, as can be seen from Fig. 143 (No. 3), in which the region of accommodation lies between 10 and 5 centimetres in front of the eye. In working at close range, therefore, the myope needs to use less accommodation than the emmetrope, or even no accommodation at all. Suppose, for instance, that work has to be done at a distance of 33 centimetres. In this case the emmetrope requires an accommodation of 3 *D* (100 ÷ 33 = 3). A myope whose myopia equals 1 *D* needs only 2 *D* of accommodation, and one having a myopia of 3 *D* needs none at all, since his far-point lies at the working distance. As soon, therefore, as myopia has reached a certain degree, the accommodation ceases to be used (it being presupposed that no glasses are worn). Hence, in myopia of high degree the range of accommodation is, as a rule, not normal, but diminished.

For the same reason, in myopes *presbyopia* sets in later than in emmetropes, or does not set in at all. To be sure, the diminution in elasticity of the lens is produced in a myopic eye just the same as in any other, but practically it does not make itself so perceptible. If a man has a myopia of 4·5 *D*, his far-point lies at 22 centimetres, and will always remain there though he be ever so old. During his whole life, therefore, there will be distinct vision at this distance, the only difference from what existed previously being that the patient, when at an advanced age he has lost his power of accommodation, will no longer be able to see closer than 22 centimetres—a thing, however, which there is no necessity of his doing in any case. Such a myope, therefore, does not become presbyopic at all. Those having myopia of less degree do become presbyopic, but do so later than emmetropes. The point of time when presbyopia sets in—i. e., when the near-point recedes beyond 22 centimetres—can easily be calculated for each individual case if we know the degree of myopia and the amount of the range of accommodation at different ages.

The *troubles* that myopes complain of vary according to the degree of myopia. In the lower grades of myopia distant vision is indistinct, and yet often suffices for ordinary purposes, so that many myopes of this sort do not use glasses. For near work moderately near-sighted eyes are generally regarded as serviceable, because they do their work with less accommodation, and, moreover, either become presbyopic late, or do not become so at all.

It is otherwise with the high degrees of myopia. In this case not only is the complaint made of indistinct vision at a distance, but also of inability to keep on with work near by for any length of time; for,

owing to the short distance at which the far-point lies, a considerable effort of convergence is required—an effort which, moreover, is often rendered difficult by insufficiency of the internal ocular muscles—so that troubles symptomatic of muscular asthenopia develop. From the insufficiency may develop a strabismus divergens, a condition, therefore, which is most frequently met with as a result of marked myopia.

In myopia of high degree it is often the case that satisfactory distant vision is not attained even by glasses, because morbid changes exist in the fundus. For the same reason, vision close by is frequently defective in spite of the great approximation of the object. Moreover, complaint is made of rapid exhaustion of the eyes, of great sensitiveness to light, and of muscæ volitantes. The last-named phenomenon is also, to be sure, found in healthy eyes (see page 397); but the myopic eye is more prone to see muscæ volitantes, and sees them in greater number. This arises from the fact that myopic eyes without glasses see everything indistinctly; and upon a hazy background, such as is produced by this indistinct vision, opacities are better projected; moreover, in the higher degrees of myopia pathological opacities of the vitreous are apt to be present. Muscæ volitantes are not infrequently a source of constant annoyance and worry to myopic patients.



FIG. 150.—CROSS-SECTION OF A MYOPIC EYE HAVING AN AXIAL LENGTH OF 28 CENTIMETRES. MAGNIFIED 2×1.

The ectasia (staphyloma posticum) which occupies the posterior segment of the eye extends from e to e_1. Over the area occupied by the staphyloma the sclera is very much thinned, and at the spot where it is continuous with the sheath of the optic nerve its layers have separated from each other, so that the intervaginal space is dilated at its extremity, and more so at the temporal side, t, than at the nasal side, n. The optic nerve, s, shows within the foramen scleræ an outward bend. Over the area occupied by the posterior staphyloma there is a posterior detachment of the vitreous, h; and in this eye there is also present an anterior detachment of the vitreous, v.

Objective examination of a near-sighted eye shows that it is longer than normal (Arlt). The elongation is produced, as dissection of such eyes shows, by the distention of the sclera at the posterior pole (Fig. 150). In marked myopia the enlargement of the eyeball is recognizable even in the living eye. The eye projects far forward (pop-eye); and when it is turned well in toward the nose the equatorial region appears in the outer portion of the palpebral fissure, and then does not, as in the case of the normal eye, make a sharp curve in turning backward, but runs back without much curving—

almost straight, in fact. Very myopic eyes are also usually characterized by a deep anterior chamber and a dilated pupil.

The most important changes in myopia are those which are situated in the fundus and can be recognized by ophthalmoscopic examination. These, as a general thing, are the more extensive the higher the degree of the myopia. They affect first of all the chorioid and retina, which become atrophic, both in the vicinity of the papilla and in the region of the macula lutea (see page 316). The latter spot, moreover, is the favorite seat of retinal hæmorrhages. Numerous floating opacities are formed in the vitreous, the latter at the same time becoming liquefied. The consequences of the degeneration of the vitreous make themselves apparent both in the lens and in the retina. In the former there develop opacities, and, as a result of the atrophy of the zonula of Zinn, tremulousness and even luxation; in the retina, detachment occurs.

Most cases of myopia are those of low degree, which develop during youth and come to a stop after the completion of the body-growth (*stationary myopia*). In other cases, however, the myopia attains a considerable height even in youth, and then does not remain stationary, but increases steadily during the whole life, so that finally it reaches the greatest possible degree (*progressive myopia*). It is mainly these cases which lead to destructive changes in the interior of the eye, and which cause myopia to appear in the light of a disease of the eye, and that, too, of a severe disease, which in advanced age often gives rise to amblyopia or even blindness.

145. Causes of Myopia.—Myopia is only exceptionally congenital, elongation of the eye in that case existing at the time of birth. The rule is that myopia develops in youth at the time when, as the whole body is growing rapidly, considerable demands are at the same time made upon the eyes by school life or by work. It has been established by many observations that acquired near-sightedness is found almost exclusively in those persons who are compelled to strain their eyes with near work. Such are, on the one hand, the members of the cultivated classes who apply themselves to study; and, on the other hand, working people, like tailors, seamstresses, compositors, lithographers, etc., who have fine work to do. There is thus no doubt but that the cause of myopia is furnished by near work. Here two factors come in for consideration, namely, the accommodation and the convergence, by the combined action of which the distention of the posterior pole of the eye is effected. But, although straining of the eyes in near work is the cause of myopia, not all but only a fraction of those who are subjected to this strain actually become near-sighted. In this fraction, therefore, special additional factors must be present which favor the development of the myopia due to near work. The following are the factors of this sort that we know of: 1. A *predisposition* to myopia, which doubtless has its seat in definite anatomical conditions, such as too slight resistance of

the sclera, peculiarities in the relations of the ocular muscles or of the optic nerve, etc. Since anatomical peculiarities are prone to be inherited, the hereditary character of myopia is also readily explainable. The children of near-sighted parents are not, to be sure, born near-sighted; but if they are exposed to those conditions which favor the development of near-sightedness, they show a greater tendency to become myopic than do the children whose parents have normal sight. 2. Those circumstances which compel *too great approximation of the work*, and thus require an abnormally great accommodation and convergence. This is the case when particularly fine work has to be done, or when work is carried on with insufficient illumination, and also when the visual acuity is diminished (by maculæ of the cornea, opacities of the lens, astigmatism, etc.), so that it becomes necessary to bring the objects closer than usual (see page 608). 3. *Insufficiency of the internal ocular muscles.* The greater the myopia, and hence the nearer the point at which objects have to be held, the greater the effect which this factor exerts. It impedes the act of convergence, which consequently can be accomplished satisfactorily only by an excessive effort of the interni, and in this way it accelerates the progress of the myopia. 4. *Spasm of the accommodation* at first simulates myopia and afterward generally passes into actual near-sight. It arises from the fact that the accommodation is kept strained upon close work for many hours every day; then, finally, it happens in young persons suffering from this accommodative spasm that they are no longer able to relax their accommodation completely, so they still accommodate when they are looking at the distance, and hence appear to be near-sighted, although they are really emmetropic, or even hypermetropic; and if they are actually near-sighted, a still higher degree of myopia is simulated because of the spasm. The existence of a spasm of accommodation is discovered by our finding the myopia to be higher when we make the subjective test with glasses than when we determine it objectively with the ophthalmoscope, for the accommodation is usually completely relaxed during the examination with the ophthalmoscope, so that the eye manifests its true refraction. The test of the correctness of our determination is the instillation of atropine, which paralyzes the accommodation and thus removes the spasm, so that when the examination with glasses is made the true refraction is found.

Treatment.—It is impossible to cure myopia, or even, in fact, to diminish it to any great extent. We must confine ourselves to making provision by means of suitable glasses for distinct vision, and to procedures that will enable close work to be carried on as far as may be without exhaustion. Moreover, the progress of the near-sight must be checked as far as possible, and any complications present be attacked.

The following principles hold good with reference to the wearing of glasses by myopes: In the low degrees of near-sight (up to about 2 *D*)

it is sufficient to order glasses for distance, provided that any desire for them is expressed. For near work glasses are unnecessary, since vision can be carried on without them at a sufficient distance—that is, up to or beyond 50 centimetres. In the medium degrees of near-sight—i. e., from 2 to about 7 *D*—glasses are necessary for distance, and they are often desirable for near work as well; for otherwise the work would have to be held too close, and would thus require great convergence, which might give rise both to exhaustion of the eyes and to progressive increase of the near-sight. If the eye is otherwise healthy, and the range of accommodation is large enough, a glass is prescribed which can be worn constantly for both distant and near points. This glass ought not quite to correct the myopia—e. g., in a myopia of 5 *D* a glass of, say, − 4 *D* would be given. If the range of accommodation is small, either on account of advanced age or from other reasons, the glass which nearly corrects the myopia will not be borne for near work. Near-sighted persons who have worn the same glass constantly for many years find that, as they become older, reading with this glass becomes more and more difficult. In such cases two sets of glasses must be ordered: a stronger one, which almost corrects the myopia, for far-points; and a weak one, for near work, which removes the working distance to the point desired. The same rule holds good for the high degrees of myopia, in which, likewise, different glasses must be prescribed for far and near. When, owing to complications, the visual acuity is greatly diminished, glasses are in any case of little or no use.

Prescribing glasses for near-sighted persons requires much experience and a careful consideration of all the attendant conditions. In no case should the choice of glasses be left to the optician.

In addition to the selection of glasses, the *regulation of the patient's habits*, both as regards his general condition and his eyes, must be attended to. This is the more important the greater the myopia is, and the more reasen there is to apprehend its progressive advancement and the development of complications. And, first of all, near work must be restricted as much as possible. Such work as has to be done under any circumstances should be performed at the greatest possible distance from the eyes. To effect this we must see to it that the print of the books is good, that the illumination is sufficient, that the correct position is maintained in reading and writing, etc. Work in the evening by artificial light must be restricted as far as possible. It is very advantageous to interrupt the work at frequent intervals and rest the eyes by looking at a distance. If it is apparent that the near-sight is making rapid progress and threatens to reach a still higher degree, it is advisable to drop all studies for quite a long time. If spasm of the accommodation exists, intervals of this sort can be utilized for treatment with atropine. Young people with markedly progressive myopia should be warned to take the condition of their eyes into account in

choosing a profession. An occupation, like that of civil-service clerk or one of the learned professions, which requires constant reading and writing, is not suitable for people of this sort.

The anatomical demonstration of the enlargement of the myopic eyeball was first made by Arlt, and thus the nature of myopia was established (1854). Scarpa, to be sure, had already at an earlier date (1807) observed the ectasia of the posterior pole of the eye peculiar to myopia, but did not recognize it as the cause of the latter. The size of this ectasia is in direct ratio to the degree of the myopia. In near-sight of moderate amount the ectasia is limited simply to the posterior pole of the eye; but in the higher degrees of myopia the ectasia (ee_1, Fig. 150) extends until the optic nerve is implicated, and gets to lie upon

Fig. 151.—Ciliary Body of an Emmetropic Eye.

Fig. 152.—Ciliary Body of a Myopic Eye.

Fig. 153.—Ciliary Body of a Hypermetropic Eye.

the side of the protrusion. The elongation of the eyeball due to the ectasia may be very considerable; there are eyeballs which have an axial length of upward of 35 millimetres, while the normal eye is only 24 millimetres long.

Microscopic examination of a very myopic eye proves that its anterior segment as far back as the ciliary muscle is normal (Iwanoff). This latter has a smaller transverse diameter than in the emmetropic eye, since the circular fibers are less developed, and are sometimes, indeed, almost entirely wanting (Fig. 152). These circular fibers, in fact, are mainly the ones whose function it is

to provide for accommodation; and as accommodation is but little employed in a myopic eye, they are not properly developed there. But as the ciliary processes, too, in the myopic eye are not as large as usual, the whole ciliary body appears abnormally flat. In hypermetropic eyes the opposite condition exists. In these, Müller's portion of the ciliary muscle is hypertrophied by constant accommodative effort, and thus the whole muscle is increased in size; and as the ciliary processes, too, are more fully developed, the entire ciliary body projects farther toward the interior of the eye (Fig. 153). A comparison of Figs. 152 and 153 with each other and with Fig. 151, which represents the ciliary body of an emmetropic eye, shows how the shape of the sinus of the anterior chamber is determined by the form of the ciliary body. In a myopic eye the sinus is deeper, in a hypermetropic eye shallower, than in the emmetropic eye. This relation, which can also be observed macroscopically in the living eye, is held to be of importance in the genesis of glaucoma. We know that in the latter condition the iris is pushed against the cornea, and the sinus of the anterior chamber is obliterated, owing to swelling of the ciliary processes (see page 351). Obviously the larger the ciliary processes and the narrower the sinus of the anterior chamber the more readily will this result take place. In this fact is probably contained, at least in part, the reason why hypermetropic eyes are very frequently, and myopic eyes, on the contrary, are very rarely indeed, attacked by inflammatory glaucoma.

The pathological changes in the posterior segment of the eye are much more manifold than those in the anterior segment. The head of the optic nerve looks as if it had been displaced, with reference to the foramen sclerae through which it passes (Weiss; see Fig. 150, *s*). As a result of this, we find its fibers curved or bent and its sheaths distorted. This latter effect is most apparent at the temporal side, where the external sheath becomes removed a considerable distance from the inner, so that a marked dilatation of the intervaginal space is thus produced (Jäger; see *t*, Fig. 150). This same displacement is recognizable in the chorioid, from the fact that the latter is drawn away from the optic disk on the temporal side, so that the atrophic crescent is produced there, while at the nasal border the chorioid is not infrequently drawn up over the optic disk. All these phenomena lead us to infer that the sclera tends to draw the optic nerve toward the temporal side, and, as this can not be done, it shifts its own place and with it that of the chorioid in the same direction against the traction exerted by the optic nerve. The sclera, wherever it happens to lie within the ectasia, becomes attenuated, so that often it is only as thin as paper. The superjacent chorioid and retina present in the main the appearances of atrophy together with slight inflammatory changes; in the later stages both membranes are reduced to a thin pellicle almost destitute of pigment. The vitreous in its posterior division is detached from the retina, and the space thus formed is filled with liquid (posterior detachment of the vitreous; *h*, Fig. 150).

The ophthalmoscopic and anatomical changes which make their appearance in the higher grades of myopia, render it evident why the visual acuity is almost never found to be normal in very marked near-sight. Among the laity there is a belief that near-sight diminishes in age; but this is true only for the lowest degrees of myopia. In advanced age the emmetropic eye, owing to diminution in the refractive power of the lens, becomes hypermetropic (see page 624); consequently, in a myopic eye the myopia must diminish. Myopes, however, often

believe that they are becoming less near-sighted because they see better at a distance without glasses than they used to do, and yet testing with glasses shows no diminution in the myopia. This improvement in vision depends upon the fact that in old age the pupils become more contracted, and hence, when looking with the naked eye, the diffusion-circles are smaller. But all persons who have a great degree of near-sight see worse and worse as their age increases, because not only is the myopia augmented, but the complications of myopia tend to develop more and more.

Near-sight of any high degree incapacitates the subject for *military service.* In Austria, according to the military regulations of 1889, capacity for every branch of the service is held to exist when the myopia of the more near-sighted eye is not more than that represented by an approximation of the far-point equal to 25 centimetres ($M = 4\ D$). For the one-year volunteers this limit for the far-point is reduced to 20 centimetres ($M = 5\ D$), and for physicians, apothecaries, and veterinary surgeons, to 15 centimetres ($M = 6{\cdot}5\ D$). Moreover, recruits are admitted, although only to the reserve corps, whose far-point varies between 25 and 20 centimetres ($M = 4 - 5\ D$), while any higher degree of near-sight excludes them altogether from actual military service. The visual acuity is also taken into account. Those only are regarded as available for all purposes who have at least vision $= \frac{6}{12}$ in both eyes (after correction of any existing ametropia). Any one whose vision in the better eye is only $\frac{6}{12}$, and in the worse eye at least $\frac{6}{24}$, may be admitted to the reserve corps, while diminution of the visual acuity below this standard incapacitates the patient for military service.

In Germany a myopia in which the far-point in the better eye is distant 15 centimetres or less ($M = 6{\cdot}5\ D$ or more) is regarded as permanently incapacitating the patient from military service, even supposing that the visual acuity is normal. A less degree of near-sight than that above given renders a man conditionally fit for service, if the visual acuity amounts to more than half of the normal (German army orders of September 28, 1875).

Near-sightedness is so wide-spread and important a disease that it has received an amount of investigation which, for extent and for thoroughness along all lines of research, few other diseases can equal. The main thing that these numerous investigations have proved is that near-sight is an attribute of culture. In the country, for example, we encounter fewer people with glasses than we do in the city. In the latter, again, it is the schools which are the main hotbeds for the propagation of near-sightedness. Cohn by his extensive researches was the first to direct general attention to this fact. Since then statistical researches in regard to myopia have been published in almost all countries—researches which extend to all classes of every condition and every age, even including new-born children. It has been proved that among new-born children myopia practically never occurs; in fact, they are almost without exception hypermetropic. Near-sightedness is acquired later in life through straining the eyes, and hence fails to occur when this strain is absent. In savage nations near-sightedness no more occurs than it does among children. Again, in the lowest order of schools—the common schools—there are extremely few near-sighted persons, and the same is true of the rural population, whose education does not, as a rule, get much beyond the common school. The school most dangerous for the eyes is the high school. It is in this that myopia first develops and then increases, both as regards its intensity and as regards the number of myopes in proportion as we ascend the classes. In Germany about

twenty per cent are myopic in the lowest classes of the high schools and sixty per cent in the highest classes. In going into the higher classes the scholar who is already near-sighted becomes more and more so; and, furthermore, new scholars are constantly being attacked with myopia. In the university the conditions are still more unfavorable. Near-sight acquired as a result of study thus rightly bears the name of "school myopia."

Continuous employment of the eyes upon fine work exerts the same influence as do schools. Among lithographers Cohn found forty-five per cent and among compositors fifty-one per cent to be myopic.

The male and female sex are equally predisposed to myopia. It is true that fewer near-sighted women are seen than near-sighted men. This is partly due to the fact that the course of study among women is shorter; but in part the difference between the sexes which makes it seem as though there were but few near-sighted women is apparent only, since women are unwilling to take the step involved in wearing glasses, because it is contrary to the fashion. But, while the two sexes are nearly equal in this regard, it is assumed that certain races, and chief among them the Germans, are more predisposed to myopia than others are.

The great prevalence of near-sight, particularly among the young who are engaged in studies, has justly excited wide-spread anxiety and led to endeavors to put a stop to the extension of the evil. First of all, the excess of work which many scholars have at present to struggle with should be reduced to the proper standard. The way in which scholars are overtasked, both in school and at home, is admitted by most, and is prejudicial not only to the eyes, but also to the boy's whole mental and physical development. Instruction ought not to be begun too early (if possible, not before the completion of the sixth year), and more time should be allotted to bodily exercise, especially in the open air, than has hitherto been the case. The hours set apart for this latter purpose should alternate suitably with the hours devoted to sedentary occupations, so as to serve as a rest from both mind-work and eye-work. That amount of work which absolutely has to be done should be done under the most favorable conditions. To accomplish this, special attention must be paid to the schools, since the work done at home is beyond our control. The requisites which in many modern schools are already carried out are: 1. Good illumination—i. e., illumination of sufficient strength and falling upon the work in the proper direction; the light should come mainly from the scholar's left side. 2. Well-constructed seats and tables, which, furthermore, should be adapted to the varying size of the scholars, so that they may not be forced to adopt a bad attitude of the body. If, however, the scholars do bend forward too much, especially in writing, the use of some straightening appliance (that of Kallmann, in Breslau, is the best) is indicated. 3. A proper method of instruction in writing which will enable the pupil to keep the head and body straight while writing (upright script). 4. Good print. Books having too fine print, and also too fine fancy-work for girls, should be banished from schools.

While no one doubts that near work produces near-sight, observers have not been able to agree as to how it does it. As regards this point different theories have been propounded, each one of which probably contains one or more points that are correct, although none is perfectly satisfactory. Those who accuse the accommodation of being the cause of myopia, declare that during accommodation the intra-ocular pressure is somewhat elevated. If this pro-

cess is frequently repeated, it may lead to distention of the posterior portion of the sclera where it is most yielding. According to Von Graefe, inflammatory processes in the chorioid and sclera (sclerotico-chorioiditis posterior), by which the sclera is rendered softer, are also to be considered in this connection. Others believe that it is not so much the accommodation as the convergence that should be made accountable for the development of myopia, inasmuch as in convergence a pressure is exerted upon the eyeball by the external ocular muscles, which leads to its distention. It has been supposed that either the internal and external recti which in the act of convergence are stretched more tightly over the eyeball, or the two obliques which surround the eyeball, like a sort of noose, may produce this effect. The muscles last named are, furthermore, so situated that they press upon the points of exit of some of the venæ vorticosæ from the eyeball, and may thus produce venous congestion in the latter. Convergence might, however, produce distention of the posterior pole of the eye in another way—namely, by the fact that the latter is displaced outward, and consequently is pulled upon by the optic nerve. This action would be particularly looked for when the optic nerve is, relatively speaking, too short (Hasner, Weiss). This view gains in weight from the result of anatomical investigations which show changes in the head of the optic nerve, that must be referred to tension exerted in the direction mentioned.

CHAPTER IV.

HYPERMETROPIA.

146. FAR-SIGHT, hypermetropia* (*H*), is that refractive condition of the eye in which parallel rays falling upon the eye come to a focus *behind* the retina (at *f*, Fig. 154). Properly speaking, the rays do not come to a focus at all, since the conical beam of rays has its apex truncated by the retina, and a diffusion-circle is formed there. Hypermetropia is the opposite of myopia; in the former the apex of the cone of rays lies behind the retina, in the latter in front of it.

What sort of rays, then, can come to a focus, so as to form a distinct image upon the retina? When we try the experiment of bringing an



FIG. 154.—PATH OF THE RAYS IN A HYPERMETROPIC EYE.

object from infinite distance closer to the eye, we find that it becomes more and more indistinct; for, the more divergent the rays are when they reach the eye, the farther behind the retina will they be when they come to a focus (thus in Fig. 154 the rays coming from *O* come to a focus at f_1), and hence the larger will be the diffusion-circles. Accordingly, the hypermetropic eye can not, without the exercise of accommodation, see either distant or near objects distinctly. For rays to come to a focus upon the retina of a hypermetropic eye, they must have a certain degree of convergence as they fall upon the eye (*c c*, Fig. 155). From what point would rays of this sort start? To ascertain this we must prolong the rays until they meet. This would occur at a point (*R*, Fig. 155) situated behind the retina. This point is, accordingly, the

* [From ὑπέρ, in excess of, μέτρον, measure, and ὤψ, sight.] Also called hyperopia [from ὑπέρ and ὤψ].

far-point of the hypermetropic eye, since we understand by the far-point that point from which the rays must emanate, in order to be brought to a focus by the eye when it is exerting no accommodation. In the present case, to be sure, the far-point is simply an imaginary point, since rays emanating from a point behind the eye could never



FIG. 155.—CORRECTION OF HYPERMETROPIA BY A CONVEX LENS.

really get into the latter. We say, therefore, that the hypermetropic eye has only a virtual far-point, and we designate it by the negative sign: $-R$.

Determination of Hypermetropia.—The greater the hypermetropia, the greater must be the convergence of the rays that come to the eye for them to unite upon its retina, and the nearer, therefore, to the posterior pole of the eye must be the point of union of these rays—i. e., the far-point. The degree of hypermetropia is determined, therefore, just like the degree of myopia, by the distance of the far-point from the eye; in both cases the error of refraction is the greater the nearer the far-point is to the eye. The only difference is that in myopia the far-point lies in front of the eye, and in hypermetropia behind it. For this reason the distance of the far-point can not in hypermetropia be measured directly as it can in myopia. We are forced to determine it indirectly by means of the test with glasses. In doing this we start as in correcting myopia with the attempt to cause such a refraction of parallel rays by means of the lens that they shall come to a focus upon the retina. Obviously a convex lens is required for this purpose, since this alone is able to render parallel rays convergent. If the far-point of the hypermetropic eye lies at — 50 centimetres (R, Fig. 155), we would have to take a lens of 50 centimetres' focal length ($= 2\,D$). Parallel rays ($\infty\,\infty$, Fig. 155) falling upon the lens will be so refracted by the latter as to converge toward its focus, which lies 50 centimetres behind the eye—i. e., at the same spot as the far-point. These rays will therefore be brought to a focus upon the retina. In this discussion, for the sake of simplicity, the distance of the glass from the eye has been neglected.

As the same thing can be proved for hypermetropia of any other degree, the following statement may be enunciated as a general law: To see distinctly at infinite distance the hypermetropic eye requires that convex glass whose focal length is equal to the distance of the far-point from the eye. Accordingly, the glass that corrects the hypermetropia gives through its focal length at once the position of the far-point and the degree of the hypermetropia. We express the latter by the number of dioptres which the correcting glass represents; and hence say a hypermetropia of 2 *D*, not a hypermetropia with far-point at 50 centimetres.

While it was said above that hypermetropes can see neither distant nor near objects distinctly, this statement only holds good when no accommodation is made; for by means of his accommodation the hypermetrope is able to increase the refractive power of his eye precisely as if a convex glass had been placed in front of it: he can correct his hypermetropia by accommodation. This fact renders the exact determination of hypermetropia difficult. If we examine the same individual at different times for hypermetropia, we find that it is not always of the same degree. For example, it may happen that in a young hypermetrope the hypermetropia to-day is found to be 1·5 *D*, a little while after 1 *D*, and to-morrow perhaps 2 *D*. Which of these findings is the correct one? If we instill atropine several times and again make the examination, we now find the hypermetropia to be constantly the same but considerably higher than before—e. g., 4 *D*.

The only possible reason for the fact that the hypermetropia as determined by us before atropinization was too low is that a part of this hypermetropia is concealed all the time by the accommodation. The hypermetrope is so accustomed to accommodate that he is unable to relax his accommodation completely even when convex glasses are placed in front of the eye, which render his accommodation superfluous, or even a disadvantage. Thus, with a glass which completely corrects his hypermetropia, the hypermetrope sees at a distance no less badly, and as a general thing much worse than with his naked eye. If we begin by placing very weak convex glasses before his eyes and then gradually use stronger and stronger ones, he will indeed keep on relaxing his accommodation, but only up to a certain point; he always retains a reserve of accommodation which he is unable to give up. With the glass thus found, combined with this residuum of accommodation, he corrects his hypermetropia and sees distinctly. If still stronger glasses are placed before the eye, these combined with his residuum of accommodation produce an over-correction of his hypermetropia, and vision will once more become indistinct. When, then, we determine the glass with which the hypermetrope sees most distinctly, this does not give us the entire hypermetropia, but only that portion of it which has been unmasked by the relaxation of the accommodation. This is called the

manifest hypermetropia (Hm). The remaining portion which is concealed all the time by the accommodation is the *latent* hypermetropia (Hl). Both together constitute the *total* hypermetropia (Ht)—i. e., $Ht = Hm + Hl$. In the example adduced above, $Hm = 1 - 2\,D$, $Ht = 4\,D$, and hence $Hl = 2 - 3\,D$.

The ratio of Hm to Ht depends upon the range of accommodation, and hence chiefly upon the age. In youth, when the range is large, upward of half of the total hypermetropia is latent. The older a man grows the more the manifest hypermetropia increases at the expense of that which is latent, until in old age $Hm = Ht$. Hence, when we test an old man with convex glasses, we find the whole hypermetropia at once; but in persons who still possess the power of accommodation, a determination of the total hypermetropia is possible only after paralyzing the accommodation with atropine.

In practice we generally abstain from determining the total hypermetropia, because atropinization is accompanied by effects which are disagreeable to the patient and which last several days. We ascertain simply the manifest hypermetropia from which, when we know the age of the subject, a conclusion can be drawn as to the total hypermetropia. However, that we may come as near as possible to the true value of the hypermetropia, we try to get the patient to relax his accommodation all that he can. For this purpose we proceed as follows:

We place before the eyes of the patient, who is stationed at a distance of 6 metres from Snellen's test-card, convex glasses, passing very gradually from weaker to stronger ones, until the best possible vision has been obtained. The strongest convex glass with which this occurs gives the manifest hypermetropia.

It very often happens that a hypermetrope has perfect vision with the naked eye, because he corrects his entire hypermetropia by means of the accommodation. In this case it is obviously impossible to improve his visual acuity with convex glasses. For a case of this sort the statement made above may be expressed as follows: The degree of manifest hypermetropia is determined by the *strongest convex glass with which the patient is still able to see as well as with the naked eye.* The fact that any one sees as well at a distance with a convex glass as with the naked eye is of itself enough to prove the existence of hypermetropia, since the emmetrope and still more the myope see worse with even weak convex glasses; for, while concave glasses can be overcome by a suitable effort of accommodation, there is no way of combating the effect of a convex glass, since the crystalline lens can not be made flatter than it is already when in the state of accommodative repose.

In the case of hypermetropia, even more than in that of myopia, it is necessary to confirm the results of the subjective method by an objective determination. It is only exceptionally the case that we get at the true amount of hypermetropia by the former method; but with

the objective test the total hypermetropia is usually found, the accommodation being entirely relaxed during the examination with the ophthalmoscope.

Causes of Hypermetropia.—The condition, characteristic of hypermetropia, in which parallel incident rays are brought to a focus behind the retina, may in general be produced by two different causes:

1. The *refractive power* of the media is altered so that parallel rays are not rendered sufficiently convergent to come to a focus upon the retina, although the latter is in the same position as in the normal eye. The *cornea* may be the part accountable for this state of things—e. g., when it is flattened by cicatrices. In this case there is always a considerable degree of astigmatism as well. The *lens* gives rise to hypermetropia when its refractive power abates, as is the case in advanced age; old people, therefore, if they were formerly emmetropic, become then slightly hypermetropic (see page 624). A high degree of hypermetropia is produced when the lens disappears from the pupillary area, either from being luxated or because it has been removed from the eye altogether (aphakia). In this case the eye is not only hypermetropic, but also loses its power of accommodation.

2. Hypermetropia also develops when the refractive power of the eye is normal, but the retina lies too far forward (*axial hypermetropia*). This may be produced by a protrusion of the retina due to exudations or tumors. But the most ordinary cause of axial hypermetropia is a congenital shortness of the entire eye, so that typical hypermetropia constitutes the opposite to typical myopia, which is produced by abnormally great length of the eyeball.

Typical Hypermetropia.

147. Symptoms.—Hypermetropes would have indistinct vision both for distance and near-points if they possessed no accommodation. In hypermetropes, therefore, this latter plays a particularly important part. The range of accommodation is the same in hypermetropia as in emmetropia. In the former, to be sure, we find that the near-point lies at a greater distance from the eye. But this is due to the fact that a part of the range of accommodation is employed in correcting the hypermetropia, and only the residue is available for making the accommodation for shorter distances. The hypermetrope, in fact, must accommodate even *when looking at a distance.* When the power of accommodation is good and the hypermetropia is not too large, the total hypermetropia may be corrected by the accommodation, so that there is distinct vision at a distance (*facultative hypermetropia*). In the higher degrees of hypermetropia the effort involved in concealing the latter completely by means of the accommodation begins to cause trouble. To effect this concealment, a very great effort of accommodation must be made,

which, owing to the connection between the accommodation and convergence, is only possible provided that a strong impulse for the performance of convergence is at the same time set into action. In this case, therefore, distinct distant vision is possible only when excessive convergence is made at the same time—i. e., when there is an inward squint. This is *relative hypermetropia*. In this fact is contained the reason why strabismus convergens most frequently occurs in consequence of hypermetropia. In the high degrees of hypermetropia it becomes absolutely impossible to correct the hypermetropia completely by accommodation, so that there is indistinct vision even for distance (*absolute hypermetropia*, Donders).

The extent to which hypermetropia can be concealed by accommodation depends not only upon the degree of the hypermetropia, but also upon the strength of the accommodation. But this latter changes with age, diminishing steadily with advancing years, and in old age becoming equal to zero. Every variety of hypermetropia, therefore, even the slightest, becomes absolute in an advanced age.

While the hypermetrope needs accommodation even for distant vision, this is much more the case for *seeing near by*. Let us assume that work has to be done at a distance of 33 centimetres. For this purpose the emmetrope must use an accommodation of 3 *D*. A hypermetrope with $H = 2\,D$ also uses the same amount of accommodation; but he must employ $2\,D$ more to conceal his hypermetropia, so that altogether he must make an accommodative effort of $5\,D$. Now, as his range of accommodation is no greater than that of an emmetrope, this great amount of accommodation causes him more trouble in proportion. He may be said to be always dragging about with him a deficit in his accommodation (namely, the quota of the latter necessary for the correction of the hypermetropia)—a deficit which causes him to become exhausted quickly when doing near work (asthenopia). At first, vision near by is distinct and the work goes on well; but after a little while the object, print, near work, etc., begin to grow indistinct and are blurred as though enveloped in a slight haze. This is owing to the fact that the overstrained accommodation gives way, and the eye then ceases to be properly focused. A short period of rest, during which the eyes look at distant objects or are kept closed, enables them to continue the work. But the same obscuration soon sets in again and compels another pause. These periods of enforced rest are the more frequently repeated and are of greater duration the longer the work is kept up. With them are associated pains in the eyes, and more especially pains in the forehead and headaches. The symptoms just described at first make their appearance only after quite prolonged work—i. e., toward evening. But afterward they keep coming on earlier and earlier all the time, so that the work has to be set aside after even a short period of exertion. After quite a prolonged rest—for example, after the repose

of Sunday or upon laying work aside for several weeks—the symptoms probably disappear for a number of days in succession, but only to appear again in the old way and in an even more aggravated fashion. They are dependent upon an exhaustion of the ciliary muscle, and are hence comprised under the name of *asthenopia accommodativa* to distinguish them from asthenopia muscularis (see page 544), and asthenopia nervosa (see page 451).

The injurious effect of hypermetropia upon vision at near-points furthermore finds expression in the fact that *presbyopia* sets in earlier than in emmetropic eyes. At the same age—i. e., with the same range of accommodation—the near-point of the hypermetrope is situated farther from the eye than is that of the emmetrope. In an emmetrope of thirty-three years with a range of accommodation of $6\,D$, P lies at 17 centimetres ($100 \div 6 = 17$). A hypermetrope having a hypermetropia of $2\,D$ would at the same age and with the same range of accommodation have his near-point at 25 centimetres (corresponding to $4\,D$), since he has to use $2\,D$ of his range of accommodation for correcting his hypermetropia. Such a hypermetrope, therefore, would be already on the threshold of presbyopia at the age of thirty-three.

The shortness of the eyeball, which is the cause of hypermetropia, is congenital. Almost all new-born children are hypermetropic, their eyes being originally constructed too short in proportion to the refractive power of the media. As the child grows the eyeballs elongate in proportion, so that they acquire their requisite axial length and become emmetropic—indeed, the elongation may even shoot beyond the mark and pass into myopia. On the other hand, the elongation of the eye may fail to take place to a sufficient degree, so that a certain amount of hypermetropia remains during the whole life. This is the typical hypermetropia of which we are speaking. Higher degrees of it can be recognized by external examination of the eye, which shows that the eyeball is distinctly diminished in size, and that the anterior chamber is shallower and the pupil more contracted than usual. If the eye is turned strongly inward, we see that the equatorial region of the ball, which comes into view in the outer part of the palpebral fissure, presents a particularly sharp curve as it turns backward, and thus gives evidence of the shortness of the axis of the eyeball. The ophthalmoscope shows that the interior of the eye is sound. The hypermetropic eye, accordingly, is an optically defective but otherwise healthy eye, as opposed to the myopic eye, which is diseased, and is hence threatened by dangers of various kinds.

In the extreme degrees of hypermetropia, however, the eye is no longer normal as a whole. It is abnormally small even from the time of birth (slight degree of microphthalmus), and many of these eyes show other signs of disturbed development, such as a strikingly small

cornea, marked astigmatism, deficient visual acuity due to incomplete formation of the retina, and other congenital anomalies.

Hypermetropia does not change in its amount in the later years of life; it remains stationary. It is true that to the laity it appears as if it increased with years, because vision at near-points becomes steadily worse; but this is not due to an increase in the error of refraction, but to a diminution in the power of accommodation, the result of which is that less and less of the hypermetropia is concealed all the time.

Treatment.—There is no way of curing hypermetropia—i. e., of transforming it into emmetropia. All that we can do is to make vision distinct by means of properly selected glasses, and enable it to be performed without exhaustion.

When the hypermetropia is not great and the range of accommodation is good, glasses for distant vision are not as a general thing required. In the contrary event, convex glasses are given which correct the manifest hypermetropia. Full correction of the total hypermetropia is indicated only in those cases in which we have to combat a strabismus convergens which is beginning to develop in consequence of the hypermetropia.

Of more importance than the glasses for distance are those for near-points or for working. A priori it would seem best to have the hypermetrope start at once by wearing that glass which corrects the total hypermetropia and so converts him into an emmetrope; but in that case he would soon quite forget altogether how to correct his hypermetropia by his accommodation in case of necessity. Should he then be accidentally deprived of his glasses he would be thrown into a very embarrassing position, for he could no longer see clearly with his naked eye. We therefore confine ourselves to correcting the hypermetropia by glasses only as far as is required to relieve the asthenopia. For this purpose it is generally sufficient to give a glass which is somewhat stronger than the manifest hypermetropia. Inasmuch as the latter increases with the age, the hypermetrope must keep on getting stronger and stronger glasses. It is only when he has reached an age at which his range of accommodation $= 0$, and hence his whole hypermetropia has become manifest, that he can keep on using the same glasses.

Formerly presbyopia and hypermetropia were confounded with each other. People saw a hypermetropic boy, whose eyes soon grew tired in studying, finally take up his grandfather's glasses and then read well with them and without becoming tired. This boy, they reasoned, must have the same sort of weakness in his eyes that his grandfather has, only that with him it has already set in in youth, and therefore is very serious. This "hebetudo visus" was attributed to a weakness of the retina, and it was believed that it might possibly go on to blindness. The only thing which might have ameliorated the sufferings of the hypermetrope—namely, the use of glasses—was held to be particularly dangerous.

Donders deserves the great credit of having discovered the true nature of

these conditions. The weak sight of the old man is presbyopia and has reference to the *accommodation*. It is, however, not an anomaly of accommodation, but a physiological state. The boy's bad sight depends upon hypermetropia, which has nothing to do with the accommodation, but is an error of refraction that exists in the eye even when destitute of accommodation. The similarity of the two conditions lies in their having one symptom in common—namely, impairment of vision for near-points; and yet even in this regard there is an essential difference between the two. In presbyopia, distinct vision inside of a certain distance is simply impossible. In hypermetropia, distinct vision at near-points is generally still possible, but is associated with straining and exhaustion of the eyes.

Donders also has shown that the asthenopia of hypermetropes is not the symptom of a serious lesion of the eye, but is an evidence of fatigue consequent upon unfavorable optical conditions. As this can be corrected by simple optical devices, a countless number of men have since his discovery been rendered once more capable of work and have been freed from the dread of growing blind.

Myopia is a state which is the direct opposite of hypermetropia, and yet there are cases in which these two conditions might be confounded with each other. When the hypermetropia has attained a very high degree, even the strongest effort of accommodation proves insufficient for rendering the vision at near-points distinct. Then the hypermetrope gives up altogether the attempt to focus his eye for near-points and holds the object as close as possible so as to get large retinal images, just as amblyopic patients do (see page 608). In this way very small print is often read well at a distance of a few centimetres, and, as at the same time distant vision is pretty bad, such a condition may easily be regarded as myopia. Examination with glasses and with the ophthalmoscope, however, will at once rectify the diagnosis.

The difference in the capacity of the emmetropic, the myopic, and the hypermetropic eye for close work is explained by the difference in the position of their region of accommodation. In emmetropia it has its normal position, in myopia it is carried inward (3, Fig. 143), and in hypermetropia it is displaced outward. For example, suppose that an emmetrope twenty years old has a range of accommodation of 10 *D*. His region of accommodation then extends from ∞ to a point 10 centimetres from the eye where his near-point is situated (1, Fig. 143). Let us compare with this an eye having the same range of accommodation but with a total hypermetropia of 4 *D*. In this case *R* lies 25 centimetres ($100 \div 4 = 25$) behind the eye. In the graphic representation of the region of accommodation annexed (Fig. 156), *R* is denoted, for purposes of more ready demonstration, as being situated on the farther side of ∞. [This assumption is justified by the following consideration.] Rays coming to the eye from a finite distance are divergent. The farther the starting-point of the rays is situated from the eye the more does the divergence of the former decrease, finally disappearing altogether and being replaced by parallelism when infinite distance has been reached. If now we could go beyond infinite distance, the parallelism of the rays would be transformed into convergence. As now in hypermetropia the far-point is the place from which rays that are convergent emanate, the custom is to denote them as being situated beyond infinity, and in the example selected at a distance of 25 centimetres (corresponding to 4 *D*) from it. To change its adjustment from this far-point to infinity, the eye must em-

ploy 4 *D* of its accommodation. Hence, out of its whole range of accommodation of 10 *D* the eye has only 6 *D* left, and by means of this it is enabled to approach to within 17 centimetres of the object. This distance, therefore, is the near-point (*P*) of the eye. Hence, the region of accommodation of the latter is displaced in comparison with that of an emmetropic eye having the same range, and in such a way that the near-point is made to recede 7 centimetres farther away, while at its extremity the region of accommodation extends somewhat beyond infinity. But as this latter portion can not be utilized, and, on the

FIG. 156.—REGION OF ACCOMMODATION OF A HYPERMETROPIC EYE.

other hand, the recession of the near-point hinders the vision of objects close by, the displacement of the region of accommodation is unfavorable to the availability of the eye for working purposes.

The calculation of the range of accommodation in hypermetropia is made according to the same rules as in emmetropia. *P* can be found directly, *R* is determined by the convex glass which corrects the error. $A = P - R$; hence, in the example selected, $A = 6\ D - (-4\ D) = 10\ D$. *R* must be taken as a negative because it lies on the farther side of ∞.

The approximate position of *R*, and consequently the *H t*, can be estimated from the position of *P*, it being presupposed that we know the age and hence the range of accommodation of the subject. Since $A = P - R$, $R = P - A$. If in the above example *P* had been found to be 6 *D*, and for the age of twenty *A* is assumed to be 10 *D*, we would have $R = 6\ D - 10\ D = -4\ D$. Hence, $H\,t = 4\ D$.

CHAPTER V.

ASTIGMATISM.

148. By astigmatism* (*As*) we understand that refractive condition of the eye in which parallel rays falling upon the eye are *not at any spot* brought to a common focus. This is the case when the curvature of the refracting media is irregular. We distinguish two kinds of astigmatism: regular and irregular.

(*a*) *Regular Astigmatism.*

This is present when the curvature of the refracting media is regular in each meridian considered by itself, but the separate meridians are distinguished from each other by differences in curvature. The place in which regular astigmatism is ordinarily situated is the cornea. In Fig. 157, let $v\,h\,v_1\,h_1$ represent the circumference of the cornea, and $v\,v_1$ its vertical meridian, which has a curvature such that the rays passing through it come to a focus at f. In the meridian immediately adjoining the curvature becomes a little greater, and in the succeeding meridians it increases still more, so that it reaches its maximum value in the horizontal meridian, $h\,h_1$. The rays passing through the latter may be supposed to intersect at a point as near as f_1. In this case we would have one meridian (the horizontal one) which refracts rays most strongly, and one perpendicular to it (the vertical meridian) which refracts most feebly; and corresponding to these are the most anterior and posterior foci, f_1 and f. These two meridians thus distinguished from the others are called principal meridians; those meridians lying between them represent all intermediate stages of curvature and refractive power, and the rays passing through them cut the optical axis in the portion lying between f and f_1. We see that when the refracting surface is of this character there is no point at all at which all the rays passing through the surface will unite. The image of a point cast by such a surface is therefore not a point, but a diffusion-circle. In reality, however, the image does not always have a circular shape. On the contrary, its shape depends upon the spot where the retina is situated and cuts the conical beam of rays. Let us assume that the retina is at the point marked *1*. Here the rays passing through the horizontal

---

* From ἀ, privative, and στίγμα, point.

meridian are already brought closer together than those incident upon the vertical meridian; hence the section of the cone of rays is an erect ellipse. At *2*, where the rays of the horizontal meridian come exactly to a focus, the image of the point is a vertical line. In the same way the shape of the cross-section of the beam—i. e., the shape of the diffusion-image of the point—can be ascertained for the more posteriorly situated points from *3* to *7*. This cross-section is sometimes an erect or horizontal ellipse, sometimes a vertical or horizontal line, according as it is more or less distant from the refracting surface. It



FIG. 157.—REFRACTION OF THE RAYS IN REGULAR ASTIGMATISM.

is only at *4* that there is really a diffusion-circle, because here the rays passing through the horizontal meridian diverge to the same extent that those of the vertical meridian converge.

The *vision* of an astigmatic person is not simply indistinct, like that of one who is near-sighted or far-sighted, but presents special peculiarities on account of the elongated form of the diffusion-images. Circular surfaces—e. g., the full moon—appear elliptical. Straight lines sometimes look distinct, sometimes indistinct, according to the direction that they take. Let us assume that we have before us an astigmatic who sees the diffusion-image of a point under the form of a vertical line (*2*, Fig. 157). If this man looks at two lines standing perpen-

dicular to each other (*A*, Fig. 158), the horizontal line appears broadened and indistinct but the vertical line seems sharply defined. For, we may imagine these two lines to be composed of an infinite number of points. Each one of these points appears upon the retina of the astig-

FIG. 158.—RETINAL IMAGES IN REGULAR ASTIGMATISM.
A, two lines placed perpendicular to each other; *B*, their image upon the retina of an astigmatic person.

matic patient under the form of a short vertical stroke, and the horizontal line therefore appears under the form of a series of such vertical strokes, which coalesce and constitute a band of a certain degree of breadth (*B*, Fig. 158). In the vertical line the vertical strokes are superimposed and cover each other, so that the line appears sharply defined. Only the uppermost and lowermost diffusion-lines extend beyond the terminal points of the vertical line and make it seem somewhat longer than it is. Thus, for every astigmatic person there is one direction in which straight lines appear most distinct, and one, perpendicular to it, in which they appear most confused. Most people looking attentively at Fig. 159 will find that, of the radii of the star, two situated opposite to each other are distinguished by being particularly black, while the radii which are placed perpendicular to them are the ones that look most pale and hazy. If one is unable to perceive this phenomenon with the naked eye, he can readily do so if he makes himself artificially astigmatic by placing a cylindrical glass before his eye.*

The principal meridians usually intersect at a right angle, and the cross formed by them is generally vertical, more rarely oblique. The rule is, that the vertical meridian has a greater curvature than the horizontal; but the reverse condition (selected for Fig. 157 because of being more readily represented) also occurs, and is then known as "astigmatism against the rule." The degree of astigmatism is expressed by the difference between the meridians of greatest and of least refraction. As long as this difference remains below 1 *D* the astigmatism may be regarded as physiological, since most eyes are affected with a slight error of curvature of this sort; but as soon as the astigmatism

* In default of this, an ordinary convex or concave glass may be used, which is held obliquely before the eye.

amounts to 1 *D* or over it must be regarded as pathological. It then affects the visual acuity, and in many cases causes asthenopic troubles, since the patients endeavor to compensate for the astigmatism by making an unequal effort of their accommodation.

The *determination* of astigmatism must be undertaken, whenever in making our tests, perfect vision can not be attained with spherical glasses. It is performed as follows: We first try to find the direction of the two principal meridians by making the astigmatic subject look at lines drawn in different directions—as, for instance, those in Fig. 159. That line which looks most distinct (blackest) gives the direction of one principal meridian; the direction of the other principal meridian is perpendicular to this. We now begin by placing a stenopæic slit before the eye in the direction of one meridian in order to determine the refraction in the ordinary way with glasses in this meridian alone to the exclusion of all the others. The same thing is then done for the meridian perpendicular to it. The difference between the refraction of the two principal meridians gives the degree of astigmatism.

Various kinds of astigmatism are distinguished, according to the character of the refraction of the principal meridians. If one meridian is emmetropic and the other hypermetropic, the condition is called simple hypermetropic astigmatism; but if both meridians are hypermetropic, it is compound hypermetropic astigmatism. In analogous fashion we speak of simple and compound myopic astigmatism. If one meridian is hypermetropic and the other myopic, the condition is known as mixed astigmatism.

The *cause* of regular astigmatism in the great majority of cases is a *congenital* irregularity of the curvature of the cornea—a condition which is apt to be transmitted by heredity. High degrees of congenital astigmatism are associated not infrequently with other defects in the development of the eye, in which case it is impossible, even with perfect correction of the astigmatism, to bring the visual acuity up to the normal pitch. Congenital astigmatism is often present in both eyes, although not always in the same degree, and the direction of the principal meridians is apt to be symmetrical in the two eyes. *Acquired* astigmatism may have its cause in the cornea or in the lens. The former variety occurs when the curvature of the cornea has been altered, either because of diseases affecting it, or

FIG. 159.—TEST-OBJECT FOR DETERMINING THE POSITION OF THE PRINCIPAL MERIDIANS IN REGULAR ASTIGMATISM.

still more frequently because of operations. After every cataract operation, and in fact even after an iridectomy, a certain degree of corneal astigmatism develops, which indeed diminishes with the consolidation of the cicatrix, but seldom disappears entirely. The lens gives rise to regular astigmatism when it is obliquely placed, as, for example, in case of subluxation. This state of things can readily be imitated experimentally if, as was said above, we look through a spherical lens obliquely. The print then looks as if in a state of astigmatic distortion, and the separate radii of Fig. 159 seem to differ in distinctness. Accordingly, an obliquely placed spherical lens acts also as a cylindrical one. Many astigmatic patients who wear spherical glasses hit upon this fact themselves; to see better, they place their spherical glasses in such a way as to look obliquely through them.

The *treatment* of astigmatism consists in correcting it as precisely as possible by means of cylindrical glasses. In this way distinct vision can be secured, and at the same time the asthenopia is relieved.

(*b*) *Irregular Astigmatism.*

149. Irregular astigmatism occurs when the curvature in any one single meridian is not everywhere alike, so that the rays passing through the same meridian are never united into one point. A certain degree of irregular astigmatism must be regarded as physiological, as it exists in every eye, its location being the lens. The individual sectors composing the latter do not all have the same refracting power, this being probably due to unequal curvature of their surfaces. Accordingly, the images of a point which these sectors cast do not all fall upon the same spot in the retina, although they come so close together that for the most part they overlap. For this reason even a normal eye does not see a star, which is really nothing but a mathematical point, as such, but under a stellate form—i. e., provided with radiating projections. The rays of the star are simply the images produced by the separate sectors of the lens, the central ends of these images meeting in the center of the star.

Under pathological conditions—e. g., in beginning opacity of the lens—this lenticular astigmatism is so much increased as to give noticeable trouble. As the refractive power of the separate sectors of the lens becomes more and more different, the images produced by them recede farther and farther apart, so that ultimately they appear entirely distinct from each other. It is in this way that monocular polyopia develops in incipient cataract (see page 365). A very high degree of irregular astigmatism occurs in subluxation of the lens when the lenticular displacement is so considerable that part of the pupil still has the lens in it and part is aphakic.

Pathological irregular astigmatism originates from the cornea even more frequently than it does from the lens. It is found in this situa-

tion as an accompaniment of marked regular astigmatism, and still more often in consequence of pathological processes—e. g., in faceting of the cornea after ulceration, or in flattening or ectasis of the entire cornea.

Irregular astigmatism makes objects appear irregularly distorted, and sometimes also look multiple, and in this way diminishes the visual acuity. It is impossible to correct it by glasses. In many cases of irregular corneal astigmatism a stenopæic slit is of service for making out minute objects (see page 601).

The sort of regular astigmatism which is present, whether hypermetropic, myopic, or mixed, does not depend upon the curvature of the cornea, but upon the situation of the retina. If the latter is situated at point *2* (Fig. 157), where the rays passing through the horizontal meridian come to a focus, this meridian has an emmetropic refraction. But the vertical meridian is hypermetropic, since the rays passing through it would meet behind the retina. In this case, then, there would be simple hypermetropic astigmatism. If the position of the retina were farther forward—e. g., at *1*—both meridians would be hypermetropic; that is, compound hypermetropic astigmatism would be present. If the retina were situated at any point between *2* and *6*, the rays passing through the horizontal meridian would have their focus in front of the retina, those passing through the vertical meridian behind it, and mixed astigmatism would exist. If the retina is situated at *6*, simple hypermetropic astigmatism is present, because there is emmetropia for the vertical meridian and myopia for the horizontal meridian. Finally, if the retina should be situated still farther back—that is, behind the foci of both meridians—myopia would be present in both the latter, or there would be compound myopic astigmatism. Hypermetropic astigmatism is of the most frequent occurrence; mixed astigmatism is the rarest.

The *vision* in regular astigmatism is distinguished from the vision in other errors of refraction by the fact that objects are distorted, and that not all their parts are seen with the same indistinctness. If the principal meridians are respectively vertical and horizontal, the horizontal strokes of the letter *E* will appear distinct, the vertical ones indistinct, or vice versa. The astigmatic subject then tries from the parts which he does see to guess the rest. If we test the visual acuity of a myope at a distance of 6 metres, he will read Snellen's test-types well down to a certain line, and then stops because he does not see any farther down. The astigmatic patient, on the contrary, often reads the whole card down to the bottom, but tells almost every letter wrong. In fact, he takes refuge in guessing—an attempt, however, which gives rise to a peculiar and very unpleasant form of asthenopia. Another cause of asthenopia lies in the endeavor of the astigmatic patient to correct his astigmatism by means of his accommodation. For this to be effected, it is necessary that the act of accommodation shall take place with a varying degree of force in the separate meridians of the lens. That this can be done, is proved by the fact that after atropinization the astigmatism is not infrequently found to be considerably higher than before (Dobrowolski).

How astigmatism is determined and corrected may be illustrated by the following example: We first make the astigmatic patient look at Fig. 159, or some similar one, and thus determine that the horizontal radii of the star appear blackest. From this we conclude that vertical lines are seen distinctly,

because the horizontal radii are composed of vertical lines. If vertical lines appear distinct, the diffusion-lines or diffusion-ellipses must be vertical (Fig. 158)—i. e., the adjustment for the horizontal meridian must be correct, or at least be better than the adjustment for the vertical meridian. We now place the stenopæic slit before the eye, in the horizontal meridian first, and determine the refraction of the latter by means of spherical glasses. Suppose that this refraction is $M = 1\ D$. In the succeeding test of the refraction which is made with the slit in the vertical position a myopia of $3\ D$ is found. Accordingly, myopic astigmatism ($A\ m$) is present, and one, namely, of $2\ D$, since the degree of astigmatism is given by the difference in refraction of the two meridians. The correction of this astigmatism would have to be made by two concave cylindrical glasses, the axes of which run vertical and horizontal. The cylindrical glass refracts most strongly in the direction perpendicular to its axis (see page 601). Hence, to correct the horizontal meridian, we must place a cylindrical glass of $-1\ D$ with the axis vertical, and for the vertical meridian a glass of $-3\ D$ with the axis horizontal. This is written as follows:

$$-1\ D \text{ cyl. vert.} \frown -3\ D \text{ cyl. horiz.}*$$

In cases where the sign of both cylinders is the same, a simplification of the combination is obtained in the following way: If, in the example chosen, we give a spherical glass of $-1\ D$, this will correct the horizontal meridian to the point of emmetropia, and the vertical meridian to $2\ D$. To get the complete correction, therefore, we only need to add to the spherical glass a $-2\ D$ cyl. horiz. We would therefore prescribe

$$-1\ D \text{ sph.} \frown -2\ D \text{ cyl. horiz.}$$

As can be seen from the example above given cylindrical glasses may be combined with cylinders and also with spherical glasses, and they may likewise be combined with prisms. Cylinders should not be used under the form of eye-glasses, but only under that of spectacles—i. e., in a frame which insures the axes of the glasses being in proper position.

---

* [According to the notation prevailing in this country, this would be written: —1·00 cyl. axis 90° ⌒ — 3·00 cyl. axis 180°. So also the equivalent formula, mentioned just afterward, would be written: — 1·00 sph. ⌒ — 2·00 cyl. axis 180°. In this notation the direction of the axis is indicated by the angle which it makes with the horizontal, the angles being numbered continuously from 0°, which is situated at the left side of either eye (nasal side of the right eye, temporal side of the left eye), round to 180° at the right side of the eye. This is shown in the following diagram:



Copyrighted, 1888, by E. B. Meyrowitz.

FIG. 159A.

Another system is in vogue in the Ophthalmic and Aural Institute in this city. According to this notation the vertical meridian is indicated by 0° or V, and from this point the angles are numbered on either side to 90° (or H), which is the hori-

The result which we obtain by the methodical method of determining the astigmatism above described we can get at more quickly in the following way: If we suspect astigmatism, we put on a weak cylindrical glass and rotate it before the eye. If there is no astigmatism worth mentioning, the patient sees worse through the cylindrical glass, no matter what direction it occupies in front of the eye. But if astigmatism is present, the sight will become better when the glass is in a certain position, worse when it is in another. In this way we find the direction of the principal meridians. Then, convex or concave cylinders of varying strength, and either alone or combined with spherical glasses, are successively placed before the eye in a direction corresponding to the principal meridians, until the best combination has been found.

It is unnecessary to correct every case of astigmatism; this is done only when the astigmatic patient wishes to see more distinctly, or when he has asthenopic troubles from his astigmatism.

The *objective determination* of astigmatism can be made in different ways. Astigmatism manifests itself to the ophthalmoscope by the alteration in the shape of the papilla, which in regular astigmatism appears elongated either lengthwise or laterally; in irregular astigmatism it appears irregularly distorted. In the erect image, in cases of regular astigmatism, the horizontal and vertical vessels are not seen distinctly at the same time, as, owing to the difference in their refraction, they require different correcting glasses. It is on account of this fact that it is possible to determine the astigmatism with the erect image by finding for each of the two principal meridians the correcting glass with which the vessels of this meridian are seen most distinctly. Astigmatism can also be made out and measured by means of keratoscopy, and by following Schmidt-Rimpler's method.

Regular corneal astigmatism can be determined by measuring directly the radii of curvature of the individual corneal meridians. This is effected by the ophthalmometer, of which the principal varieties in use are that of Helmholtz and the more recent one of Javal and Schiötz. The former is chiefly of service for precise, scientific examinations; the latter is more adapted for practical pur-

---

zontal, those angles on the temporal side being indicated by *t*, those on the nasal side by *n*. This system is shown in the following diagram:



FIG. 159B.

In each eye the position of the axis of the cylinder is denoted by the angular deviation of its upper end from the vertical meridian (v or 0°) either on the nasal or on the temporal side, and is written $5n = 5°$ nasal, $5t = 5°$ temporal, etc., down to $h = 90°$ (horizontal).

Both systems are also employed for indicating the direction of the axis of a prism—e. g., prism 1°, apex at 75°, indicates a prism of 1° refracting angle with its apex turned to the left 15° from the vertical.—D.]

poses on account of the rapidity with which the measurements can be made. A very useful instrument for determining whether there is actually any great amount of astigmatism present is Placido's keratoscope. This consists of a disk of cardboard, one surface of which bears a number of black concentric rings upon a white ground. An aperture in the center of the disk, and corresponding to the center of the rings, allows the observer to look through the disk. The disk is held so that the side with the rings upon it is turned toward the eye that is being examined, and so that the plane of the disk is parallel to the base of the cornea. If now we look through the central aperture at the eye, we see the rings mirrored upon its cornea. If the cornea has the normal curvature, these rings appear perfectly circular; if not, the rings are transformed into ellipses, or show irregular bulgings, according as regular or irregular astigmatism is present.

150. Anisometropia.*—By anisometropia is meant a difference in the refraction of the two eyes. One eye may be emmetropic and the other myopic, hypermetropic, or astigmatic, or both eyes may be ametropic, but in a different way. In this regard all possible combinations occur.

Anisometropia not infrequently is congenital, and then, at least in the higher degrees of it, often manifests itself even upon external inspection by an asymmetrical formation of the face and of the skull. Acquired anisometropia most frequently originates from the circumstance that the change taking place in the refraction during life, such as the decrease in a hypermetropia or the development of a myopia, does not advance at the same pace in both eyes. Very high degrees of anisometropia develop when one eye is normal, but the other, in consequence of a cataract operation, has become very hypermetropic.

A correction of anisometropia without the aid of glasses would be conceivable only as the result of an effort of the accommodation differing in the two eyes; but this the eyes are incapable of doing, at least to any noteworthy extent. Accordingly, the anisometrope never sees distinctly with both eyes at once. This, however, gives him so little inconvenience that many persons do not become aware of the fact that they are not seeing equally well with both eyes until the tests of vision which the physician institutes are made. Moreover, if the difference in the refraction is not too great, binocular vision is not disturbed by it. Both images, even though they are of unequal distinctness, are superimposed and made to coalesce. In the high degrees of anisometropia, however, strabismus very frequently sets in. This may be either divergent or convergent, and under these circumstances is very frequently alternating, particularly when one eye is hypermetropic, the other myopic (see page 569).

The obvious course to pursue would seem to be to correct the anisometropia by ordering different glasses for the two eyes. Nevertheless,

* From ἀ, privative, ἴσος, equal, and μέτρον, measure.

this measure in most cases proves impracticable. If the difference between the two glasses is somewhat great, the patients complain of an unpleasant sensation in the eyes, of vertigo, headache, etc., and lay the glasses aside. This fact is explained in the following way: Glasses alter not only the distinctness but also the size of objects. This is enlarged by convex and diminished by concave glasses, and the more so the stronger the glass is. With different glasses the retinal image of the same object is altered in size, more in one eye and less in the other; the images then no longer match one another, and can not be perfectly superimposed. We therefore prefer in anisometropia either to give the same glasses for both eyes, or to correct only one eye and place a plane glass before the other. In doing this we always have regard to the better eye, namely, the one which appears more efficient for the purpose in view (distant or near vision).

CHAPTER VI.

ANOMALIES OF ACCOMMODATION.

151. Paralysis of Accommodation.—Paralysis of accommodation is diagnosticated from the diminution of the range of accommodation (*A*). To make this diagnosis it is necessary that we determine the far-point and near-point, and from them calculate the range. The range found is compared with that which the patient ought from his age to have in accordance with the values set forth by Donders (Fig. 147), and from this a conclusion is drawn as to whether the range falls below the normal, and, if so, how far.

The disturbance which paralysis of the accommodation causes varies greatly according to the refractive condition of the eyes. If an emmetrope is affected with paralysis of the accommodation, reading and writing become perfectly impossible, or at least, in case of incomplete paralysis (paresis of accommodation), very difficult, and possible for only a few moments at a time. Distant vision, for which the emmetrope does not require to use the accommodation, is not affected. In the hypermetrope paralysis of accommodation makes itself still more noticeable, since without accommodation he sees poorly even at the distance. The reverse is true of the myope, to whom the abolition of accommodation causes little or no inconvenience; and in the higher degrees of myopia a paralysis of accommodation is often discovered only accidentally at the time when a careful examination is being made.

Paralysis of the accommodation arises from a paralysis of the ciliary muscle or of the oculomotor nerve which supplies this muscle. It may be simply one of the symptoms of a complete oculomotor paralysis, in which case its etiology agrees with that of oculomotor paralysis in general (see page 554). But in many cases the paralysis of accommodation exists alone, or is at most associated with a coincident paralysis of the sphincter pupillæ. These two intrinsic muscles, which under physiological conditions act in conjunction, are also commonly paralyzed together, so that the paralysis of accommodation is combined with mydriasis paralytica (ophthalmoplegia interna). The *causes* of paralysis of accommodation (with or without paralysis of the pupil) with which we are acquainted are as follows:

1. *Diphtheria.*—Paralysis of accommodation belongs among the post-diphtheritic paralyses—i. e., those which usually develop in the

stage of convalescence. The most common of these, besides the paralysis of accommodation, is paralysis of the soft palate, which manifests itself in the nasal character of the speech and also by frequent attacks of choking during eating and drinking. Paralyses of the sphincter pupillæ or of the other eye-muscles, of the muscles of the extremities, or of the trunk itself, occur less often. Diphtheritic paralysis of the accommodation affects both eyes, and is usually not associated with paralysis of the sphincter pupillæ. It generally passes away of itself in one or two months as the patient gains in strength, and hence affords a good prognosis. Cases of paralysis of accommodation consequent upon influenza, which were analogous in their behavior to post-diphtheritic paralyses, occurred pretty frequently during the last epidemic.

2. *Poisoning.*—The most complete paralysis of accommodation, combined with paralysis of the pupil, is produced by atropine and the other mydriatics. These act not only when administered internally, but also locally when introduced into the conjunctival sac. The cases in which paralysis of the accommodation, together with symptoms of general poisoning, have been observed after eating spoiled meat, sausages, fish, etc., likewise probably depend upon poisoning by alkaloids, which in this case are the alkaloids of putrefaction (ptomaines).

3. *Syphilis* and *diabetes.*

4. *Severe affections of the central nervous system* (e. g., tabes).

5. *Contusions of the eyeball.*

The *treatment* of paralysis of the accommodation must first of all be regulated according to the lesion which lies at the bottom of it, and seek to effect the cure of this latter by appropriate means. In post-diphtheritic paralysis we institute corroborative measures, giving hearty nourishment, wine, iron, quinine, etc., and ordering a warm bath daily or every other day. For local treatment, the miotics, pilocarpine and eserine, are employed. These, besides contracting the pupil, also produce a spasm of the accommodation by contracting the ciliary muscle. This, however, is not of long duration, any more than the miosis is; after some hours the muscle relaxes again and the paralysis returns. Nevertheless, the contraction of the muscle produced by the miotic appears sometimes to exert a favorable influence upon the paralysis itself, perhaps acting in the same way as faradization does when it produces a good effect in paralyses. In addition, the constant current is employed. As long as the paralysis is still recent the eyes should not be strained in any way, but in older paralyses work may be facilitated by means of the appropriate convex glasses.

In paralysis of the accommodation, whether produced by disease or artificially by a mydriatic, the statement is frequently made that objects appear smaller than usual (*micropsia*).* This phenomenon is explained in the following way:

* [From μικρός, small, and ὄψις, appearance.—D.]

We estimate the size of an object from the size of its image upon the retina taken in connection with the distance at which we judge the object to be situated. An object of certain size seen at a certain distance gives us a retinal image of certain size. If the object is approximated to one half the distance, its retinal image becomes twice as great. If this were not the case, and the retinal image remained of the same size when the object was approximated, we would infer that the object itself had been reduced to one half its former size. It is this mistake that we fall into in case of paralysis of the accommodation. Since in this condition the act of accommodation for any given distance of the object costs us a greater effort than under other circumstances, we estimate the accommodation at too high a figure, and hence believe the object to be nearer than it really is; but as the retinal image is no larger, we think that the object itself has diminished in size. The same phenomenon manifests itself when an emmetrope looks through concave glasses; these make objects look smaller to him; for, to overcome the concave glasses, he must strain his accommodation. Now, without being distinctly aware of this strain, he yet infers from it that objects are nearer than they are, and thus the latter, since their retinal images are not any larger, seem smaller to him. The converse phenomenon, by virtue of which objects appear larger than normal—*macropsia**—is observed in spasm of the accommodation. This, too, originates in a delusion as to distances, resulting from the disturbance of the accommodation.

To show how a paralysis of accommodation is diagnosticated, I will adduce here the following case: In May, 1887, a boy ten years of age was brought to me by his mother because for some weeks he had been unable to read and write. At the same time the unusual width of his pupils had attracted his mother's attention. I found before me a delicate, pale lad, whose pupils at the time he was brought to me showed once more their normal size and mobility. The boy could read with his naked eye all the lines on Snellen's test-card hung up at a distance of 6 metres, hence he had normal vision. From this fact alone it was possible to draw the inference that it could not be a case of opacities of the media, disease of the chorioid or retina, or the like, as by these the visual acuity would necessarily be diminished for all distances. It could only be an anomaly of refraction or accommodation that was in question. He was not near-sighted, since otherwise he would have been unable to read the smallest letters of Snellen's test-card at a distance of 6 metres, but he might perhaps have been hypermetropic. Accordingly, I put a very weak convex glass before his eye; as with these his distant vision at once became indistinct, hypermetropia too was excluded. Hence there was emmetropia, and his incapacity to read could only depend upon a disturbance of accommodation. This was at once confirmed by the fact that the boy with $+ 3\,D$ read the finest print fluently. The print then could be brought to within 13 centimetres of the eye; his near-point, therefore, lay at this distance. Expressed in dioptres, $P = 8\,D$ $(100 : 13 = 8)$ and $A = P - R = 8\,D$, since the boy was emmetropic, and hence $R = \infty = 0\,D$. But the range of accommodation of $8\,D$ had been determined with the aid of the $+ 3\,D$ glass which had been placed before the eye, and which, therefore, had to be subtracted in order to ascertain the true range; this accordingly was only $5\,D$. At the age of ten the image should have been $14\,D$; the boy's range, therefore, was upward of $9\,D$ too small. There was paresis of accommodation.

* [From μακρός, long, and ὄψις, appearance.—D.]

To my question as to an antecedent diphtheria, the mother professed to have no knowledge of any such occurrence. It was only after further questioning that she remembered that the boy had had, the Christmas before, an inflammation of the throat, which, however, had not been at all severe, and which the physician had said was not diphtheria. After this attack of inflammation in the throat the boy had been feeble for a remarkably long time, so that since that date he had not been able to go to school; the glands in the neck had become greatly swollen, so as to be visible externally. Later still the boy had become hoarse; he had got a nasal voice, and could not pronounce certain letters and syllables (paralysis of the soft palate). This symptom, like the dilatation of the pupils, had already disappeared when I first saw him.

The boy was given generous nourishment and a tonic (ten drops of a mixture of equal parts of Fowler's solution, and the tinctura ferri pomata, twice a day in a glass of wine); in addition, every second day a warm bath, and finally every morning and evening a drop of a one-per-cent solution of pilocarpine in each eye. The effect of the pilocarpine during the first few days continued only eight to ten hours after the instillation, but afterward became more and more lasting all the time. After ten days, at which time the boy had had for two days no pilocarpine in his eyes, he could read the finest print with his naked eye up to 13 centimetres—i. e., he had a range of 8 *D.* The accommodation, therefore, was not yet normal, but he could already do his work without trouble, and later still doubtless regained his full power of accommodation. This case is instructive, for it shows that diphtheria need not run a severe course in order to have paralysis of the accommodation follow it—a fact which also holds good for the other post-diphtheritic paralyses. In this instance the diphtheria could not be recognized as such while it was still recent; but that it was a case of true diphtheria was apparent from the long-continued disturbance of the health, the marked swelling of the glands, and the paralysis of the soft palate, of the pupil, and of the accommodation.

After severe diseases there is a weakness of the accommodation which often lasts for quite a long time, but which is no more to be regarded as a paresis than is the muscular weakness of convalescents in general. The range of accommodation in these cases is normal, but its lasting power is defective, so that exhaustion and asthenopic troubles speedily set in. This weakness of accommodation disappears of itself in proportion as the strength of the patient comes back.

A reduction of the accommodation is furthermore found in the prodromal stage of glaucoma and in sympathetic ophthalmia.

It is evident that the accommodation is completely abolished when the lens is luxated, or is removed altogether from the eye, but such cases are not properly designated by the name of paralysis of the accommodation.

Spasm of the Accommodation.—The instillation of atropine, besides causing paralysis of the accommodation, usually results also in a slight change of the refraction, which in fact becomes somewhat lessened. If, for example, there was emmetropia before, the eye after atropinization is slightly hypermetropic. The slight reduction of the refraction produced by atropine corresponds to the tonic contraction (tone) of the ciliary muscle which is constantly present, and which

disappears only when the muscle is paralyzed. But if upon the use of atropine the refraction is diminished to a greater extent—i. e., to 1 *D* or more—the condition then can not be regarded as representing the tone of the ciliary muscle, but must be looked upon as a spasm of the latter. This spasm develops in consequence of continual near-work, as the accommodation, when it is strained all the time, at length gets to be in such a state that it can no longer be relaxed. It is found only in young persons, and most frequently in myopic eyes, which then appear more myopic than they really are. But spasm of the accommodation also occurs not infrequently in emmetropic and hypermetropic eyes, making the former appear myopic; the latter appear less hypermetropic than they are, or even emmetropic or myopic. Spasm of the accommodation disappears spontaneously when, as age advances, the range of accommodation diminishes. But before this occurs it may have given rise to true myopia. It is combated by the instillation of atropine, which must be kept up for quite a long time (four weeks and more). Unfortunately, in most cases when the atropine has been discontinued, the spasm returns after a shorter or longer interval.

An artificial spasm of accommodation of high degree combined with contraction of the pupil develops after the instillation of a miotic.

PART IV.

OPERATIONS.

CHAPTER I.

GENERAL REMARKS.

152. The *antiseptic method*, which represents the greatest progress made in surgery during recent times, has also produced an essential improvement and greater certainty as to results in the special domain of operations upon the eye. It is therefore the first duty of every operator upon the eye to proceed in a perfectly aseptic and antiseptic manner. In operations upon the eye we have less to do with antisepsis than with asepsis; we do not have to disinfect a contaminated wound, but to make a wound that is clean and keep it from contamination.

Contamination of the wound may either be effected by means of the operator and his instruments or it may take its origin from the adnexa of the eyeball. To avoid the former, the hands of the operator must be well cleansed and then disinfected with a four-per-cent solution of carbolic acid or a solution of corrosive sublimate (1 : 2,000). The delicate instruments which are used for operating upon the eyeball itself are best disinfected by boiling in distilled water, and the larger instruments by means of a solution of carbolic acid. To prevent infection of the wound by the conjunctival sac, the latter must be thoroughly washed out with a sublimate solution (1 : 4,000) directly before the operation; but the conjunctival sac affords special danger of infection only when decomposed secretion is present in it as a result of a lesion of the conjunctiva or lachrymal sac. In this case infection of the wound can not always be avoided even by the most careful disinfection, for it is impossible to kill with certainty all the germs present in the conjunctival sac, since strong antiseptic solutions, such as are in use for other parts of the body, can not be borne by the eye. Moreover, we can not prevent the conjunctiva from continuing to secrete after the operation has been performed, and no more can we shut off completely the communication that the conjunctiva has with the lachrymal sac and through the latter with the nose. For these reasons, before

proceeding to perform an operation, we ought to try first to relieve by appropriate treatment any lesion of the conjunctiva or lachrymal sac that may be present. In respect to the special case of blennorrhœa of the lachrymal sac, its perfect cure, unfortunately, requires a very long time. Hence, in order to accomplish my purpose more quickly, I often either extirpate the lachrymal sac some days before the operation, or I split its anterior wall, and, after suitable cleansing, fill it with iodoform powder.

After the operation an aseptic dressing is applied. If the operation was upon the eyeball itself, directly after it has been completed we close the lids and place upon them first a pledget of sterilized gauze (iodoform gauze, sublimate gauze), and upon this lay a dressing of cotton, which is held in place by a bandage. Operation-wounds upon the conjunctiva or the lids are disinfected anew before the application of the dressing by flushing with sublimate solution, and are then sprinkled with iodoform powder, and over this the dressing is applied.

Anæsthesia for operations upon the eyeball is effected by cocaine, a five-per-cent solution of which is instilled several times into the conjunctival sac at intervals of a few minutes. The solution should be freshly prepared and filtered. After instilling it we must take care that the patient keeps the eye shut, because, as a result of the cocaine anæsthesia, winking takes place with less frequency, and hence the cornea, if uncovered, is apt to become dry upon its surface. Cocaine anæsthesia lasts about ten minutes. It affects only the superficial parts, like the cornea and conjunctiva, while the iris remains sensitive. In iridectomy, for example, the grasping of the eyeball and the incision are not felt, but the excision of the iris is painful.* In operations upon the lids, several drops of the cocaine solution may be injected beneath the skin of the lids. Narcosis, with chloroform or ether, is required only for the major operations, such as enucleation,† etc., and in children.

153. In regard to *operations upon the eyeball itself* the following principles hold good:

The separation of the lids is effected by means of lid-specula (blepharostats, elevators, or écarteurs). There are some which hold both lids open at once, keeping them apart by the elastic force of a spring (spring-specula), and others which are designed for one lid only and must be held with the hand (Desmarre's lid-retractor). The eyeball

* [If, however, the performance of the operation is delayed long enough (ten or fifteen minutes) after the first instillation of cocaine for the drug to pass through the cornea, the iris also may be completely anæsthetized, and iridectomy is then performed absolutely without pain.—D.]

† [Even enucleation has been done under cocaine, the latter being injected into the deeper tissues of the orbit by means of a specially devised syringe with curved tip, which reaches behind the eyeball (syringe of J. A. White, of Richmond, Va.).—D.]

itself is fixed by grasping a fold of conjunctiva close to the corneal margin with a toothed forceps (Waldau's fixation forceps) and holding it in place.

In cases where it is important to exert no pressure upon the eyeball (as, for example, when it is desired to avoid escape of vitreous) we have the lids held apart by the finger of an assistant, and, wherever possible, abstain from grasping the eyeball with the fixation forceps.

The *incision* which lays the eyeball open is made, as a rule, within the limits of the anterior chamber. As this latter is bounded by the cornea and at its periphery by the most anterior portion of the sclera, the section may lie either in the cornea or in the sclera. We therefore distinguish sections with respect to—

(*a*) Their *position*, into corneal and scleral. These differ from each other mainly in the following points: 1. In scleral incisions there is more tendency to prolapse of the iris than in those of the cornea (see the remark at the close of the following paragraph). Hence arises the necessity of excising the iris in scleral sections in order to prevent inclusion of the iris in the wound. For this reason such an operation as Von Graefe's peripheric cataract-extraction is always combined with iridectomy. If, on the other hand, we wish to save the iris (as, for instance, in paracentesis of the cornea and in simple cataract-extraction), we will place our section not in the sclera, but in the cornea, and as far as possible from the edge of the sclera. 2. The sclera is covered by conjunctiva, and a wound in the sclera can therefore be provided with a conjunctival flap—a thing which is not possible in corneal sections. 3. Scleral wounds are less apt to become infected than those in the cornea, because of the slighter tendency that the sclera exhibits toward purulent inflammation. Hence, before the introduction of antiseptic methods, scleral incisions gave better results than did those in the cornea. At present, when infection is avoided in every possible way, this distinction is no longer of so very much weight.

Fig. 160.—Different Forms of Sections in the Cornea.

(*b*) In *shape*, incisions may be linear or curved. The former lie in a great circle of a sphere, and hence form upon the surface of the eyeball a line which is the shortest that can be made to connect the terminal points of the section (*e a f*, Fig. 160). The curved or flap incisions correspond to a small circle of a sphere. Between the largest curved section (*e d f*, Fig. 160) and the linear section an infinite number of sections (*e c f*, *e b f*) may be conceived to exist, constituting the transition-forms between the two. These are curved sections of varying altitude; the linear section forms their infe-

rior limit, and may therefore be regarded as a curved section whose altitude = 0. Most of the sections in general use are curved ones, with an arch of greater or less altitude. An example of a pure linear section would be the one devised by Saemisch for laying open an abscess of the cornea, in which the latter is divided with a Graefe knife from behind forward (§ 155). A flap-incision, having the ends of its section at the same distance apart as a linear incision, will have a longer wound-tract than the latter, and is apt to gape more widely, owing to the likelihood of a lifting up of the flap.

In *making* the section, care must be taken that the knife is withdrawn from the wound slowly, so that the aqueous may escape as gradually as possible. In this way we avoid the evil results which too rapid escape of the aqueous often entails, such as extensive prolapse of the iris, subluxation of the lens, prolapse of the vitreous, and intraocular hæmorrhage. The slow escape of the aqueous is particularly important if an operation is done when there is increase of tension.

In completing the operation the greatest attention must be paid to having *the iris in proper position*. Under no circumstances should the

FIG. 161.—NORMAL POSITION OF THE IRIS (AFTER A SCLERAL FLAP-EXTRACTION). MAGNIFIED 2×1.

The angles of the sphincter, a and a_1, are both low down.

FIG. 162.—INCARCERATION OF THE IRIS IN THE WOUND (AFTER A CORNEAL FLAP-EXTRACTION). MAGNIFIED 2×1.

The iris is visible as a dark nodule, i, in the wound, and the angle, a_1, of the sphincter on the same side appears drawn up in comparison with that of the other side, which is in its proper position.



FIG. 163.—INCARCERATION OF THE IRIS (AFTER SIMPLE LINEAR EXTRACTION WITHOUT IRIDECTOMY). MAGNIFIED 2×1.

The pupil is drawn toward the cicatrix, N; s, s_1, section in sclerotomy after De Wecker's method.

iris be left incarcerated in the wound. Prolapse of the iris is manifested by different signs, according to the extent to which the iris is protruded. If the iris has pushed its way through the wound to the outside, it becomes visible as a dark swelling or nodule either in the middle of the section, or, if some of the iris has been excised, at one or both ends of it (i, Fig. 162). The condition when the iris does not protrude from the wound, but is merely jammed in between the internal lips of the latter (Fig. 164), is recognized by the displacement of the pupil. For, after operations of this sort, in which the iris has been excised, the boundary between the pupil and the coloboma is marked by two projecting angles, forming what are called the angles of the sphincter

(Fig. 161, *a* and a_1). These correspond to the spot where the margin of the pupil passes into the lateral limits ("pillars") of the coloboma. When the iris is free, the angles of the sphincter are directly opposite one another, and, moreover, lie in the circular line which the margin of the pupil would form if still uninjured ("the angles of the sphincter are low down," Fig. 161). But if the iris is incarcerated in the wound, the corresponding pillar of the coloboma is thereby shortened, and the angle of the sphincter looks as if drawn up ("the angle of the sphincter is higher," Fig. 162, a_1). The angle of the sphincter may be pushed up so far that it is not visible at all.

After operations in which no part of the iris has been excised, there are, of course, no angles in the sphincter; the inclusion of the iris in the wound then manifests itself only by the displacement of the pupil toward the wound, precisely as is seen after perforating ulcers of the cornea with incarceration of the iris (Fig. 163).

Inclusion of the iris in the wound is accompanied by evil consequences of many kinds. The healing of the wound is interfered with by inflammatory irritation, and is protracted. The cicatrix is less solid and regular in its formation, and even when it is formed the inclusion of the iris may afterward give rise to increase of tension, to inflammation, and even to sympathetic disease of the other eye. To avert these results every attempt must be made, after completing the operation, to release the iris from its condition of incarceration, and to put it in the proper position. This is done by entering the wound with a spatula, and with this stroking the iris so as to bring it back again into the anterior chamber. Should this attempt be unsuccessful, or should the iris after replacement again prolapse into the wound, the incarcerated portion of the iris must be drawn out and excised.

Hæmorrhage into the anterior chamber occurs in those operations which cause injury to vascular tissues like the sclera and iris. If the iris is healthy, it hardly bleeds at all upon being cut through, since its vessels close very rapidly from contraction of their walls. But in those cases in which an operation is done upon a diseased iris (as in iritis, glaucoma, and atrophy of the iris), copious bleeding often takes place from the iris, so that the whole anterior chamber fills with blood. The bleeding is disagreeable, because it prevents the operator from inspecting the interior of the eye; but in otherwise healthy eyes it generally produces no other disadvantage, as the blood is absorbed again within a few days. But in eyes where the iris is diseased not only is the hæmorrhage more extensive, but in addition the blood takes a longer time—sometimes in fact months—to disappear by resorption; and, moreover, it is precisely in such cases that the whole metabolism of the eye is seriously affected.

Hæmorrhage from divided vessels should not be confounded with those intraocular hæmorrhages which are caused by the sudden and

upon the eye, coughing, sneezing, and the like. This "bursting of the wound" is ordinarily followed by extravasation of blood into the anterior chamber. The iris also may be swept into the wound and incarcerated there, or inflammation (irido-cyclitis) may set in. Another way in which the healing of the wound may be interfered with consists in the fact that the edges of the wound do not adhere to one another directly, but are united by an interposed cicatricial mass of recent formation. This is most frequently the case when direct contact of the edges of the wound is prevented by the presence of an incarcerated iris or lens-capsule, but it may also occur when there is an increase of tension by means of which the wound is made to gape and is thus kept open. In these cases the cicatrix that is formed is less firm, and in fact a small portion of it may remain entirely open, so that the aqueous keeps trickling through it beneath the conjunctiva and makes the latter œdematous (*cystoid cicatrization*, Fig. 164). Cicatrices which are not sufficiently firm often become ectatic. This has as its immediate consequence an irregular bulging of the adjoining parts of the cornea, so that the results of the operation, as far as vision is concerned, are impaired by the presence of irregular astigmatism. Later on cystoid or ectatic cicatrices may give rise to elevation of tension or to inflammation.



FIG. 164.—INCLUSION OF THE IRIS WITH CYSTOID CICATRIZATION AFTER THE EXTRACTION OF A SENILE CATARACT BY GRAEFE'S PERIPHERIC LINEAR SECTION. ENLARGEMENT 13×1.

The iris *I* extends from its origin in the ciliary body *C* to the inner orifice of the wound, so that here the anterior chamber is contracted into a narrow slit. The iris within the tract of the wound is folded upon itself, the point of flexion corresponding to the exterior surface of the sclera. The pupillary portion *P* of the iris extends from the site of the constriction into the anterior chamber, where it lies free. On its anterior surface may be seen the entrance of a crypt, near its posterior surface, the cross-section of the sphincter pupillæ. Besides the iris, the capsule *k* of the lens is also drawn up to the cicatrix, and has become adherent to it. The section by which the extraction was made cuts in two the line of junction between the sclera *S* and the cornea *H*, so that by its anterior half it lies in the sclera, by its posterior half in the cornea. On account of the interposition of the iris, the lips of the wound have not united; in fact, the tract of the wound extends as an open cavity *h* even into the tissue of the conjunctiva of the limbus *L*, so that the wound is closed only by a very thin layer of tissue.

2. *Suppuration of the Wound.* This is manifested by the yellowish discoloration which the wound assumes at some point, while at the same time violent inflammatory symptoms (often, however, unassociated with pain) set in. From the wound the suppuration extends either to the uvea alone, so that purulent irido-cyclitis develops, or to

the cornea as well, which becomes infiltrated with pus and then breaks down. The outcome is atrophy, or, if panophthalmitis is superadded, phthisis of the eyeball. Suppuration of the wound is most apt to set in after cataract-extractions, and formerly was the most frequent cause for the development of blindness in an eye which had been operated upon for cataract. We now know that suppuration of the wound is the consequence of infection of the wound; and by the application of antiseptic methods the number of cases in which suppuration takes place can now be reduced to a minimum.

3. *Inflammation of the Uvea.* Iritis and irido-cyclitis occur very frequently after operations in which the eyeball has been opened. In most cases there is simply a slight iritis, which does no harm beyond that induced by a few posterior synechiæ which remain. But in the severe cases the inflammation leads to occlusion of the pupil, and either necessitates a secondary operation, or actually terminates in incurable blindness due to atrophy of the eyeball. In cases of the latter sort there is also a danger of sympathetic disease of the other eye. Slight inflammations of the iris are generally to be regarded as a purely traumatic affection caused by the way in which the iris has been grasped and pulled upon. In other cases it is possible that either portions of the lens which are left behind, or similar substances, produce mechanical or chemical irritation of the iris. Severe inflammations depend either upon infection or upon a lighting up of old inflammation, as when an operation is done in an eye which was formerly the seat of an irido-cyclitis.

In former times much more importance was attached than now to the shape and position of the section, especially in cataract-operations, the hope of a happy result being based solely upon the proper performance of the section. Starting with this view, observers devised a great number of different methods of operating which have already, in part at least, fallen into oblivion. At the present time we know that the rigorous carrying out of antisepsis in the operation and after-treatment is of much greater significance than the choice of a method of operating. Any section which is of the necessary size and is suitable in position gives good results, if in other respects we proceed with the most scrupulous cleanliness. In eye-operations this is doubly important, since the result that we seek is attained only if healing by first intention is secured. When an amputation-wound does not heal by first intention, but by suppuration, this accident usually does the patient no harm beyond prolonging his stay in bed; but if suppuration ensues instead of primary union after an iridectomy or cataract-operation, the eye is lost, which for an operator upon the eye is the same thing as the death of the patient would be for the surgeon.

In judging of the size and position of any particular form of section, not only the *outer and visible wound* but also the *internal* one must be taken into consideration. That the latter is of a different size, shape, and position from the external wound arises from the fact that in most methods of performing the section the knife divides the tunics of the eye obliquely (Fig. 166, *I* and *P*). This is particularly the case with the wounds made by the lance-shaped

knife. Even if at first we plunge the lance-knife in perpendicularly, we must still, as soon as its point has entered the anterior chamber, change its position so that it shall be pushed along parallel with the iris, as otherwise we should get into the iris and lens. The inner orifice of the section (Fig. 165, *i i*) therefore lies nearer the center of the cornea than does its outer orifice (Fig. 165, *a a*).



FIG. 165.—SECTIONS FOR IRIDECTOMY AND CATARACT-EXTRACTION. SCHEMATIC. MAGNIFIED 2×1.

D, peripheric section for iridectomy in case of increase of tension: *a*, *a*, external orifice of the wound situated in the sclera; *i*, *i*, internal orifice situated at the sclero-corneal junction. In order to represent these relations a correctly performed iridectomy was made upon the eye of a cadaver, and the exact position of the orifices of the wound, properly magnified, was transferred to the drawing. *O*, section for an iridectomy done for making an optical coloboma. The section lies entirely in the cornea; the coloboma is slender, and does not extend up to the ciliary margin. *L*, section for a simple linear extraction.

For this reason sections whose outer orifice lies in the sclera, and which hence are usually regarded as scleral sections, nevertheless by their inner segment belong to the cornea (*I*, Fig. 166). A further fact contributing to this relation between the external and internal sections is that the sclera overlaps the cornea externally, and the latter therefore in its inner layers extends farther toward the periphery than can be seen from the outside. Hence, even sections situated pretty high up, like Von Graefe's peripheric linear section for cataract-extraction (Fig. 164), are in great part located in corneal tissue. This fact that the internal wound is less peripherally situated than the external must be taken into account in making the section. If, for example, we desire to excise the iris up to a certain spot, we must not perforate the cornea at a point directly opposite the latter, but must place the corneal section farther toward the periphery, so that the internal wound may lie at the spot at which the iris is to be cut off.

The internal wound is also of less length than the external (Fig. 165, *a a* and *i i*). This fact also must be taken into consideration, particularly in cataract-operations, in which care must be taken that not only the external but also the internal wound shall be large enough to allow the cataract to pass through.

The *oblique course* of the wound through the tunics of the eye, furthermore, affects the tendency of the wound to gape. It was said above that flap-wounds gape more than linear wounds; but the tendency toward gaping depends still more upon whether the wound traverses the tunics of the eye perpendicularly or obliquely. The former is more particularly the case in sections made with Graefe's knife, in which the knife passes through the cornea or sclera from within outward; the latter is the case in sections made with the lance-knife. Sections of the former sort gape, owing to the elastic retraction of the edges of the wound. Wounds, on the other hand, which are made with the lance-knife, and pass obliquely through the tunics of the eye, do not gape, because the lips of the wound close upon one another like a valve. The closure is effected by the intraocular pressure. This latter is exerted to the same extent on every point of the internal surface of the eyeball. It presses as strongly upon the posterior lip

of the wound (*a*, Fig. 166) as upon the anterior (*b*), and hence pushes the former against the latter. To this valve-like closure of the wound is to be attributed the fact that the aqueous does not escape after paracentesis of the cornea if the lance-knife is withdrawn cautiously, and without pressure or rotation, from the wound. The wound must be made to gape before the aqueous (or, in simple linear extraction, the soft masses of lens-matter) can be evacuated. It would be a mistake to try to effect this by pressure either upon the center of the cornea or upon the sclera, as in so doing we should only increase the intraocular pressure by that which is exerted from outside, and thus push the posterior lip of the wound still more strongly against the anterior. Only upon very strong pressure, by which the lips of the wound would be shoved past one another, would the wound gape open. The proper procedure, rather, is to depress the peripheral lip of the wound (*c*, Fig. 166) with a Daviel's scoop, and thus open the valve.

The firm closure of the wounds made with a lance-knife diminishes the danger of prolapse of the iris. How, then, does *prolapse of the iris* occur at all? When the cornea has been perforated at any spot, the aqueous flows from every direction toward this point, because here the ocular tension has sunk to nothing (i. e., has become equal to that of the external air). The fluid of the anterior chamber can flow toward the opening without obstruction; but the fluid of the posterior chamber, to get at the opening, must first pass through the pupil. Let us assume that the opening lies at the inner margin of the cornea (*I*, Fig. 166). In this case the liquid from the outer (more centrally situated) portion of the posterior chamber would flow toward the opening directly through the pupil, because this is its shortest way. The case is otherwise with the inner portion of the chamber, which lies immediately opposite the opening. Here going through the pupil means taking a roundabout way, which is the more circuitous the farther the opening lies toward the periphery. The aqueous will therefore tend to take the shortest way and rush straight forward toward the opening, pushing the iris before it. In the language of physics, the posterior surface of the iris is subjected to the pressure of that portion of the aqueous which has not yet been evacuated (*d*, Fig. 166). On the other hand, the pressure upon the anterior surface of the iris has become zero, and the iris consequently is pushed against and into the opening. This is the way in which a prolapse of the iris originates, the prolapse being nothing but a sac consisting of iris and filled with the liquid of the posterior chamber.



FIG. 166.—OBLIQUE COURSE OF THE SECTION THROUGH THE TUNICS OF THE EYE. SCHEMATIC.

I, section for iridectomy, lying externally in the sclera, internally in the cornea. *P*, section for paracentesis; *a*, peripheral; *b*, central lip of the wound.

The *danger of a prolapse of the iris* occurring is greater—1. The greater the rapidity with which the aqueous is evacuated, because then proportionately less time is allowed the liquid of the posterior chamber to make the circuit by way of the pupil. Hence the rule that in making the section the aqueous should be allowed to flow off as slowly as possible. 2. In proportion as the ocular tension rises, because then the difference between the pressure in the anterior chamber which has been emptied and the posterior chamber which is full becomes so much the greater. When an iridectomy is made in glaucoma, a considerable

extent of the iris usually at once protrudes from the wound. 3. In proportion as the wound lies nearer the periphery, for then the route which the aqueous has to take through the pupil is just so much the more circuitous, and both a greater depth of posterior chamber and a greater quantity of aqueous to propel the iris forward are present at the spot corresponding to the section. Hence, operations with a peripheral section must be combined with iridectomy, which, when the situation of the section is more toward the center (simple cataract-extraction, paracentesis of the cornea) is not required. 4. According to the size and shape of the aperture, since these conditions likewise have an effect in producing prolapse of the iris. It is evident that the opening must be of a certain size for the iris to enter it at all. Again, if the aperture is circular—as is the case, for example, after perforation of an ulcer of the cornea has taken place—prolapse of the iris will assuredly not fail to develop. On the other hand, wounds with a valvular closure, such as those made with the lance-knife, display a comparatively slight tendency to inclusion of the iris. We therefore try to anticipate the occurrence of perforation of an ulcer by making paracentesis with the lance-knife, in order to avoid prolapse of the iris and the anterior synechia that results from it.

Prolapse of the iris may occur not only during the operation but afterward also. We may, for example, have succeeded in avoiding the development of prolapse during the operation, or have removed it if it has developed; and yet on the next day, when we change the dressing, we may find the iris prolapsed into the wound. This occurrence is due to the fact that the recently agglutinated wound has reopened, and at the moment when this took place the same conditions favoring prolapse of the iris were supplied as at the instant of the operation itself.

Prolapse of the iris and its incarceration in the operation-wound must be avoided at any cost. If we are dealing with wounds in which there is but little tendency to prolapse, it is sufficient to carefully replace any iris that may have prolapsed during the operation. But if the section is of such a character that the iris is apt to be pushed into it (as is the section of the peripheric cataract-extractions), the reposition of the iris affords no security against prolapse; this may, and very often will, take place subsequently. In these cases the only resource is excision of the iris. How does this avert prolapse? Is it perhaps because all the iris is removed that could possibly prolapse into the wound? If that were the case, the iris would have to be excised through the entire extent of the wound—that is, often for a considerable width. But this is not always by any means necessary. As a matter of fact, iridectomy prevents prolapse of the iris because it puts the posterior into direct communication with the anterior chamber at the site of the wound, so that the fluid which reaccumulates in the posterior chamber can flow directly toward the opening of the wound without forcing the iris before it. For this purpose a small opening is all that is necessary. Accordingly, my invariable practice is to combine a peripheric cataract-extraction with simply a narrow iridectomy, and I find that in this way I am able to avoid incarceration of the iris with no less or even with more security than by making a broad coloboma.

An escape of aqueous after the cornea has been opened presupposes a proportionate contraction upon the part of the capsule of the eyeball. If the walls of the eyeball were perfectly rigid, like a metallic capsule, for instance, not a drop of liquid would escape from the orifice which had been made; a

counter-opening would have to be made in another spot before it could do so. In addition to the elastic contraction of the tunics of the eye, the pressure of the external ocular muscles, and also the pressure of the lids upon the eye, contribute to reduce the volume of the capsule of the eyeball. Another factor contributing to the same result is added where the diaphragm formed by the lens and zonula is yielding enough to push forward after the escape of the aqueous. In old persons, the capsule of whose eyeball is rigid and whose eyes lie deep in the socket, so that the lids and muscles have but little power over them, the cornea after the escape of the aqueous (especially if the lens is removed at the same time) is often pushed in by the external atmospheric pressure (*collapsus corneæ*). This occurrence is favored by the diminished thickness of the cornea in old age, and also by the use during, the operation, of cocaine, which reduces the ocular tension. Collapse of the cornea was formerly looked upon as an evil event, because it prevents the precise apposition of the lips of the wound, and it was supposed that suppuration of the wound was thus produced. We now know that the process of healing is in no respect affected by a collapse of the cornea. The collapse disappears as soon as the aqueous reaccumulates, which is generally the case as early as a few minutes after the operation. When the cornea on account of its elasticity tends to resume its shape after collapse has taken place, a negative pressure develops in the anterior chamber precisely as when the rubber ball of a syringe, after being compressed with the hand, is allowed to expand again. Air may be sucked in by means of this negative pressure, so that an air-bubble enters the anterior chamber. This does no sort of harm to the eye. A more unpleasant effect of this aspirating action occurs when the blood is sucked out by it from the divided vessels of the iris, so that the chamber is filled with blood. This is particularly apt to take place when the cavity of the chambers is separated from the cavity of the vitreous by a more solid diaphragm than usual (exudation membranes), which is not able to advance properly after the escape of the aqueous. Particularly profuse hæmorrhage is thus encountered in those iridectomies and iridotomies which are made in eyes with an old irido-cyclitis. The blood in this case is unpleasant for two reasons: first, because it is very slow in being absorbed; and, second, because it may in part become organized and close the new-made pupil up again. To prevent this hæmorrhage ex vacuo, I apply in such cases a pressure-bandage to the eye as soon as possible after the pupil has been formed. This bandage by external pressure diminishes the volume of the capsule of the eyeball, and presses the vitreous against the cornea.

If we except the cases mentioned above, the *dressing* applied after an operation should be a protective, not a pressure bandage. Its function consists merely in keeping the eye closed. In fact, a bandage that is too tightly applied may become the cause of secondary rupture of the wound. Accordingly, in recent years my practice has been to fasten the cotton which is laid upon the lids in place simply by a single strip of linen, whose two extremities being coated with adhesive plaster are attached to the forehead and cheek respectively. In this way no pressure at all can possibly be exerted upon the eye. To prevent the eye from being touched by the patient, I fasten over the dressing just described a very light, somewhat convex wire frame. There is no necessity of darkening the room in which the patient operated upon lies; it is sufficient to protect him by means of some contrivance like a screen from any light that may fall upon him directly. In order to prevent breaking open of the wound, all kinds of physical

exertion must be avoided. Under this head belong even such acts as violent mastication, coughing, sneezing, etc. Sneezing can be restrained if the patient, when he feels a tendency to sneeze, presses his finger against the hard palate at the site of the incisive foramen.

In old people, especially if they are drinkers, delirium not infrequently occurs, particularly when both eyes are bandaged. In this case the eye that has not been operated upon must be opened at once. Old people suffering from marasmus are apt, if they lie quiet upon their backs for several days after an operation, to get hypostases in the lungs, which may cause the patient's death. Hence, persons that are weak from old age ought to be taken out of bed very soon—if necessary, as early as the day after the operation. There are other accidents, too, by which the course of the healing may be interfered with. As these can not usually be foreseen, it is advisable never to operate upon both eyes at one sitting; for from the operation and after-treatment in the case of one eye, we learn what we are to expect when operating upon the second.

In small children quietude of behavior after the operation is not to be expected, and hence the larger sections, such as those made for iridectomy or cataract-extraction, have their healing interfered with. Accordingly, for small children we ought to choose only those methods of operating, such as discission, which produce very small wounds.

(For keratitis traumatica after operations, see page 184.)

CHAPTER II.

OPERATIONS UPON THE EYEBALL.

I. Paracentesis of the Cornea.

155. Paracentesis, or puncture of the cornea, may be made either with the lance-knife or with Von Graefe's linear knife.

In making *paracentesis with the lance-knife* the latter is plunged in perpendicularly close to the outer and lower margin of the cornea. As soon as its point has entered the anterior chamber the handle of the knife is depressed until the blade is parallel with the plane of the iris; then the lance-knife is pushed a little farther forward, so that the wound gets to be 2 or 3 millimetres long, when the knife is withdrawn very slowly from the wound. Then, to make the aqueous flow off, we need only depress the peripheral edge of the wound (*c*, Fig. 166) gently with a Daviel's scoop. The evacuation of the aqueous should be gradual, and preferably intermittent.

Paracentesis with the lance-knife is made—1. In progressive ulcers of the cornea whose advance either along the surface or into the depth of the tissues can not be arrested by medicinal treatment. In the case of corneal ulcers which threaten rupture we anticipate the occurrence of the latter by performing paracentesis. We thus avoid having the perforation take place too suddenly, and also avoid the occurrence of a prolapse of the iris. When the floor of the ulcer is greatly thinned and is bulging, we select this as the site of our puncture. 2. In ectasiæ of the cornea of various kinds, and also in markedly bulging prolapses of the iris, or in the staphylomata that develop from the latter. 3. In obstinate inflammations of the cornea or uvea, and also in opacities of the vitreous, in order to exert a favorable effect upon the nutrition of the eyeball by altering the conditions of tissue-metamorphosis. 4. In elevation of tension when this is likely to be transient, as, for example, in irido-cyclitis or in swelling of the lens. 5. After discission when the process of resorption is arrested in spite of the swelling up of the lens, since, as experience as shown, resorption then takes a fresh start owing to the removal of the aqueous. 6. In hypopyon, for removing it when it extends high up.

In all these cases it is not infrequently necessary to repeat the paracentesis one or more times.

Paracentesis with Von Graefe's linear knife is made according to

the method proposed by Saemisch in abscess of the cornea (see page 158). The Graefe knife, whose cutting edge is directed straight forward, is entered to the outside of the external border of the abscess, in the healthy portion of the cornea; then it is pushed in the anterior chamber toward the nasal side until its point is brought out again through the cornea to the inside of the inner margin of the abscess. We then may be said to have the abscess lying upon the edge of the knife, which latter, therefore, has only to be pushed farther to the front in order to split the abscess from behind forward. The section should have both its terminal points lying in sound tissue, and, if possible, should be so made that the most intensely yellow, progressive portion of the abscess wall is bisected by it. After the section has been completed the hypopyon is removed. The section must be reopened daily (with a Weber's knife or with a Daviel's scoop), until the abscess begins to grow clean.

Paracentesis of the Sclera (*Sclerotomy*).—This may be performed in the most anterior portion of the sclera, belonging to the anterior chamber, or in the posterior and larger division of it (sclerotomia anterior and posterior).

Sclerotomia anterior by De Wecker's method is made as follows: The Graefe knife is entered one millimetre outside of the external margin of the cornea, and brought out again at an equal distance to the inside of the internal margin of the cornea. The points of entrance and emergence are therefore symmetrically situated, and are selected as though the intention was to form a flap two millimetres high out of the upper part of the cornea. And, in fact, after the counterpuncture has been made, the incision is carried upward by sawing cuts just as if this flap was to be separated, but the knife is withdrawn before the section is completed. Thus, at the upper margin of the cornea there remains a bridge formed of sclera, which connects the flap with the parts below it and prevents the gaping of the wound. Hence, by this operation two sections at once are made in the scleral margin separated from each other by a narrow bridge (s and s_1, Fig. 163).

Sclerotomy, on account of the peripheral position of the wound, is very prone to be attended with prolapse of the iris. It should therefore be undertaken only in those cases in which it is possible to produce a marked degree of miosis by eserine; the spasmodically contracted sphincter then keeps the iris in the anterior chamber. Should the iris in spite of this become wedged in the wound, and should it be impossible to replace it satisfactorily, it would have to be drawn out and cut off.

Sclerotomy is performed in glaucoma, but its results are not as certain, and, more particularly, not as lasting as those of iridectomy. Sclerotomy, accordingly, has either been given up altogether by most operators, or is performed only in exceptional cases. Under the latter belong the following: 1. Glaucoma simplex, with a deep anterior chamber and without distinct elevation of tension. 2. Inflammatory glaucoma, when the iris through atrophy has become so narrow that one can not hope to perform excision of the iris that would be according to rule. 3. Hæmorrhagic glaucoma. 4. Hydrophthalmus. *5. Instead of a second iridectomy in those cases of glaucoma in which the increase of tension returns in spite of an iridectomy performed according to rule.

In *sclerotomia posterior* the opening of the sclera is made in the posterior division of the latter. The section should be meridional—i. e., run from behind forward, since this is the direction of most of the scleral fibers, and hence such sections gape the least. The position of the section must be chosen, so that neither an ocular muscle nor the ciliary body is injured. For the latter reason the section should not extend farther forward than at most to a point six millimetres from the margin of the cornea. The indications for sclerotomia *posterior* are:

1. Detachment of the retina. A broad Graefe knife is thrust into that spot of the sclera which corresponds to the most prominent part of the detachment. As soon as the knife has penetrated the sclera it is turned a little, so that the wound is thus made to gape. We then observe that the conjunctiva is lifted up by the subretinal fluid which escapes from the wound, so as to form a yellowish vesicle. As soon as the fluid ceases to be discharged the knife is withdrawn again.

2. Glaucoma, when the anterior chamber is obliterated, and hence iridectomy has become technically impossible (cases of glaucoma malignum and glaucoma absolutum). The operation is performed in the same way as in detachment of the retina, except that instead of subretinal fluid some vitreous is evacuated. Owing to the greater consistence of the vitreous it is usually necessary to make the section somewhat longer. After sclerotomy the anterior chamber is usually restored, so that an iridectomy can be performed later on.

3. A meridional section of pretty great extent is made when extraction of a foreign body, or of a cysticercus from the vitreous, is in question.

II. Iridectomy.

156. Iridectomy by Beer's method is performed as follows: The incision is made with the lance-knife in the vicinity of the margin of the cornea, being sometimes a little to the outside, sometimes a little to the inside of the latter, according as the point at which it is desired to excise the iris is more or less close to the ciliary margin. The lance-knife is entered perpendicularly until its point is in the anterior chamber; then the handle is depressed until the blade lies parallel with the plane of the iris. The lance-knife is next pushed forward until the wound is of the desired length (four to eight millimetres, according to the breadth of the portion of the iris that it is proposed to cut out); in doing this the lance-knife must be so held that the section is concentric with the margin of the cornea. The withdrawal of the lance is performed slowly, and with the instrument pressed against the posterior surface of the cornea, so as not to injure the iris or lens, which push forward as the aqueous flows off. After completing the section, the iris-forceps with its branches closed is introduced into the anterior chamber and pushed on up to the border of the pupil. At this point the branches are allowed to separate and a fold of the iris is grasped, gentle pressure being at the same time made upon the latter. The iris is now drawn from the wound, and at the moment when it is most upon the stretch it is cut off close to the wound with the curved scissors or with

the scissors-forceps (pinces-ciseaux of De Wecker). The operation then is done, and it only remains by introducing a spatula into the wound to put back into the anterior chamber any iris that may have been wedged into the wound, so that at the completion of the operation the pupil and the coloboma have their proper shape.

The *indications* for iridectomy are:

1. *The presence of optical obstructions.* These consist in opacities of the refractive media, occupying the area of the pupil. Among these belong: (*a*) opacities of the cornea; (*b*) a membrane in the pupil (occlusio pupillæ); (*c*) opacities of the lens, such as lamellar cataract, nuclear cataract, or an anterior polar cataract of particularly large diameter, and lastly shrunken cataracts which do not extend far toward the periphery; (*d*) subluxation of the lens when the attempt is made to place the pupil in front of the part that contains no lens.

For any good to be gained from the performance of an iridectomy for optical purposes, the following *conditions* must be present:

(*a*) The opacity must be so *dense* that it prevents the formation of distinct images upon the retina, and does not simply interfere with vision by giving rise to dazzling. In the latter event the dazzling would actually be increased by the iridectomy. A mistake that we frequently meet with is that of making an iridectomy when there are comparatively slight opacities of the cornea; by such an operation the sight is made worse instead of better. To avoid this mistake we first make an accurate determination of the visual acuity, then dilate the pupil with atropine, and once more test the sight. If the latter then proves to be considerably better than before the pupil was dilated, iridectomy is indicated; otherwise not.

(*b*) The opacity must be *stationary*. In the case of opacities of the cornea the inflammatory process should have already run its course in opacities of the lens; it must be stationary forms of cataract that are in question. Otherwise we run the risk of having the very spot become opaque which we have selected for making the artificial pupil in.

(*c*) The *parts concerned with the perception of light*—the retina and optic nerve—must be capable of performing their functions. This fact is determined by testing the vision. The latter must correspond approximately to the amount of dioptric obstruction that is visible. When the opacity is so dense that only quantitative vision is present, the latter is to be tested with a candle-flame. We darken the room and station ourselves with a lighted candle opposite the patient. Now, by alternately holding the hand in front of the light and then withdrawing it, we test whether the patient can tell aright the change from light to darkness. We first make this test near by, and then withdraw farther and farther from the patient, so as to find the greatest distance at which he is still able to distinguish between the alternation of light and darkness. The degree of direct perception of light is thus determined. In

order to test the extent of the visual field, the candle is gradually carried from one side of the patient to a position in front of the eye, which all the time must be looking straight forward; at the same time we ask when the light is perceived and upon what side it is situated. In this way the limits of the visual field in every direction can be determined.

The quantitative perception of light in the center and at the periphery is not abrogated by even the densest opacity. If the retina and optic nerve are sound, the glimmer of the candle must be recognized in a darkened room at a distance of at least six metres, and it should also be seen by the patient on all sides of him and its place be correctly given. If this is not the case, the percipient portions of the eye are not normal. Upon the degree to which the perception of light is retained will depend the question whether an iridectomy for optical purposes is undertaken at all or not. These remarks regarding the perception of light hold good, moreover, not only for iridectomy, but also for all operations undertaken for the restoration of sight, and particularly for the operation of cataract.

The following conditions must be regarded as *contra-indications* to iridectomy for optical purposes: 1. Deficiency or total absence of the perception of light. 2. Strabismus of the eye which is affected with the opacity. In this case, even if the operation was technically a perfect success, not much gain in sight would be got, owing to the amblyopia ex anopsia which exists in such eyes. 3. Flattening of the cornea. For, where applanatio corneæ has developed, it is always a sign that there has been in conjunction with the keratitis an irido-cyclitis, which has left thick membranous exudates behind the iris. Hence, even if we actually succeed in excising the iris, a free aperture is not produced, and we have before us a hull of exudation which it is impossible to penetrate. 4. Incarceration of the iris in a cicatrix of the cornea, the iris being atrophied and pushed up against the posterior surface of the cornea. In this case iridectomy fails because the friable iris is too firmly agglutinated to the cornea.

A *coloboma* which is made for optical purposes must be so fashioned as to cause as little disturbance from dazzling as possible. This result is secured when the coloboma is narrow and does not reach to the margin of the cornea (*O*, Fig. 165). An excision extending up to the root of the iris would expose the margin of the lens and also the interspace between it and the ciliary processes, and thus admit a great quantity of irregularly refracted rays into the eye. In order to make the coloboma narrow and not too peripheral, the incision must be short, and lie at or even inside of the limbus. Those cases constitute an exception to this rule, in which only the most exterior marginal portion of the cornea has remained transparent, so that the iridectomy must, for obvious reasons, be quite peripheral.

That spot is chosen as the *site* of the coloboma at which the media

are the most transparent. Wherever possible, we avoid making the coloboma above, as in that case it would be partly covered by the lid. If the media are everywhere equally transparent (as when there is a cicatrix situated exactly in the center of the cornea, a pupillary membrane, or a perinuclear cataract), the iridectomy is performed downward and inward (Fig. 165), because in most eyes the visual axis cuts the cornea a little to the inner side of the apex.

157. [Other indications for iridectomy are:] 2. *Increase of tension.* Iridectomy is hence indicated in primary glaucoma, and also in secondary glaucoma resulting from ectasiæ of the cornea or sclera, from seclusio pupillæ, from irido-chorioiditis, etc. In hæmorrhagic glaucoma iridectomy is often a failure. In general, the success of the operation is better the earlier it is performed. Nevertheless, an operation is sometimes done in cases of increased tension even when the perception of light has been already abolished, in which case there can be no idea of restoring sight. Then it is simply a case of relieving pain or of avoiding further degeneration (and especially further ectasis) of the eyeball.

When iridectomy is made for increase of tension, the coloboma, in contradistinction to an iridectomy made for optical purposes, must be broad and must extend to the ciliary margin of the iris. Hence the section must be situated as far back as possible in the sclera and must be made quite long (*D*, Fig. 165). If there are not at the same time any optical conditions, to which regard must be paid in making the iridectomy, the latter must be directed upward so that the coloboma may be partially covered by the upper lid, and thus the confusion due to dazzling be lessened.

3. *Ectatic cicatrices of the cornea* (partial staphylomata), in order to cause their flattening. This is the more apt to succeed, the more recent and the thinner walled the staphyloma is—that is, the closer akin it is to a prolapse of the iris.

4. *Recurrent iritis*, in which case the iridectomy is designed to prevent the recurrences—an object, however, which is not always attained. The operation is to be done during an interval in which there is no inflammation.

5. *Fistula of the cornea.* Iridectomy here serves the purpose of securing the formation of a firm cicatrix. We must wait to perform the operation until at least some trace of the anterior chamber has been restored, as otherwise the operation is impracticable on technical grounds.

6. *Foreign bodies* imbedded in the iris, which sometimes can only be removed by excising the portion of iris in which they occur. The like is true of cysts and small tumors of the iris.

7. *As a preliminary to the operation for cataract.* Iridectomy is done under these circumstances: (*a*) When we are dealing with complicated cataracts (e. g., those complicated with posterior synechiæ, in-

crease of tension, etc.). Many operators also perform this sort of "preparatory" iridectomy before operating upon uncomplicated cataracts, since they believe that the cataract-operation itself is made less disturbing in its effects, and consequently less dangerous. (*b*) In unripe cataracts in order to mature them. This procedure, devised by Förster, consists in rubbing the cornea in a circular direction with a blunt instrument (Daviel's scoop or a squint-hook) after excising the iris. Since the cornea is so thin that it dimples upon being rubbed, this procedure acts upon the lens also, the anterior cortical layers of which are thus compressed and partly crushed. It is a necessary requisite for the accomplishment of this that there should be a hard nucleus present, against which the soft cortex can be pressed. The result of this massage of the lens is that the latter becomes completely opaque in the course of a few weeks or even a few days. The extraction of the lens should follow the iridectomy at an interval of not less than four weeks.

In cases where iridectomy is made as a preliminary to a cataract-extraction the excision of the iris must be made upward, so that the coloboma may also be utilized for the extraction of the cataract, which as a general thing is made upward.

The *success* of an iridectomy for optical purposes, as far as the amount of vision obtained is concerned, very often falls behind the expectations which both physician and patient have entertained in regard to it. This is especially the case with iridectomy in cicatrices of the cornea. In this case there are various reasons for the vision being often so defective, even when the operation itself has been a complete success. The chief one is that usually a considerable degree of astigmatism is present in that part of the cornea which has been used for the iridectomy. This astigmatism is caused partly by the adjoining cicatrix, partly by the operation itself. To this is added the astigmatic refraction of those rays which in the peripheral portion of the coloboma pass through the margin of the lens. This astigmatism, which is for the most part irregular, has a greater effect than usual, inasmuch as the new pupil is large and is almost or quite immovable, and hence can not lessen the size of the diffusion-circles (see page 612). Moreover, the cornea over the coloboma is often less transparent than was supposed before the iridectomy, for slight opacities are scarcely visible when a light-colored iris is behind them, while they at once become obvious when after iridectomy a black coloboma forms the background. Still greater is the disappointment in store for the operator when after a successful iridectomy he finds the coloboma white instead of black, because the lens has already become opaque in that very spot.

It is obvious that the degree of sight that is regained depends also upon the condition of the percipient parts—a condition which should be ascertained before the operation by testing the perception of light. With regard to this point special stress must be laid upon the fact that in *testing the periphery of the visual field* we should ask not only if the light is seen when held to one side, but also where it is. If necessary, we make the patient point to it or grasp at it. It not infrequently happens that the patient recognizes the glimmer of the light as soon as the candle-flame appears in the periphery of the visual field, but that

he tells its place wrong. He says every time, for instance, that it is on the right hand, even when it is held in some quite different spot. This circumstance is accounted for as follows: When an eye with transparent media is tested with a candle-flame in a dark room, there is formed upon the retina, at a point opposite to the flame, an image of the latter, while the rest of the retina is not illuminated and has a sensation of darkness. If that part of the retina which is situated directly opposite the light were insensitive, no light would be seen at all. The case is different with an eye whose media are cloudy. In this the rays emanating from the light are so dispersed by the cloudy media that the whole retina is illuminated no matter where the light is placed. To be sure, the illumination of the retina is not perfectly uniform. There are always more rays falling upon that part of the retina which lies opposite the light than upon the other regions of the retina, and thus the patient is able to tell where the light is; but he would also see the light if the portion of the retina lying opposite



Fig. 167.—Path of Rays in the Case of an Excentrically Situated Pupil.

the latter were insensitive, since the rest of the retina likewise receives light upon it. Let us assume that the whole retina has become insensitive with the exception of a region situated on the temporal side. This latter region, no matter where the light may be, will receive diffused light and will perceive it, too. The patient will locate the source of this sensation in the portion of the external world lying opposite to this region of the retina, and will therefore believe always that what he sees is on his nasal side. Hence the mere statement that a light is seen is not sufficient proof of the possession of functional capacity by all parts of the retina. For this it is requisite that the situation of the light be told correctly every time.

How must a man adjust his eye in order to see with an excentrically situated pupil? Let us assume that the eye is affected with a central cicatrix of the cornea (*n*, Fig. 167), so that it can see only with the assistance of a coloboma which has been made upward. Must this eye, in order to fix an object, *o*, be turned downward so that the coloboma may lie opposite the object? By no means. The refraction of the rays in such an eye takes place in precisely the

same way as in a sound one. The only difference is, that the portions of the beam emanating from *o* which enter the eye are not those situated in the center, but those situated above and corresponding to the coloboma. These latter throw the image upon the fovea, *f*, provided the object lies in the line of vision. An object, o_1, which is situated opposite the coloboma would form its image at i_1 below the fovea, and would therefore not be seen by central vision. Hence an eye with an excentrically placed pupil performs fixation in the same way as does a normal eye. It is not superfluous to lay particular stress upon this point, inasmuch as many erroneous ideas prevail with respect to it. In a very learned treatise on retinitis pigmentosa, one can read how in this disease an iridectomy does no good if central opacities of lens are present, because in that case the images of objects would fall upon the peripheral portions of the retina which are insensitive! As a matter of fact, this would only be so if the objects themselves were situated in the periphery of the visual field.

The considerations just adduced also furnish an answer to the question whether a man would see double who has colobomata in both eyes which extend in different directions—e. g., upward in the right eye and inward in the left. In this case there will be binocular single vision, since the object of fixation forms its image at the same spot in both eyes—namely, the fovea—no matter where the coloboma is situated.

It is difficult *to perform iridectomy* when the anterior chamber is shallow. This happens in gibbous protrusion of the iris, in incarceration of the iris by the cornea, in glaucoma, in fistula of the cornea, etc. In these cases the lance-knife can be pushed forward but a little distance, as otherwise we should get into the iris or the lens. We must then widen the section to the proper length by making a lateral cut with the lance while withdrawing it from the wound. In such cases we may also use a Graefe knife for making the section, but only when we have one to do that is at the upper or lower margin of the cornea. We can not make vertical sections with a Graefe knife, because we are then prevented by the margin of the orbit from carrying the knife where it should go.

The *mishaps* which may occur in the course of an iridectomy are: 1. Injury of the iris or lens with the lance, either through the clumsiness of the operator or through the restlessness of the patient. Injury done to the lens-capsule entails a traumatic cataract, which not only produces a new obstacle to vision but also endangers the eye by giving rise to inflammation or increase of tension. 2. Iridodialysis. By this the excision of the iris is rendered difficult, great bleeding is set up, and often, too, a double pupil is produced (see page 301). 3. The last-named result may also occur from the fact that the sphincter pupillæ at the site of the iridectomy is left behind, so that it separates the pupil from the coloboma like a bridge. This accident occurs either because the margin of the pupil is firmly adherent to the lens-capsule, so that it does not follow the rest of the iris when the latter is drawn out, or because the iris is excised before it has been drawn far enough out of the wound. We shall not have to complain of this disagreeable occurrence if we observe the two following rules: The first is, not to grasp the iris with the forceps until we have pushed the instrument forward as far as the margin of the pupil, so as to get this latter between its branches. The second rule is, to cut off the iris only when it has been drawn out far enough for its black posterior surface to be visible. If, however, the sphincter should remain behind, we enter the anterior chamber again with a blunt hook and draw up the bridge of sphincter in order to cut

it off. 4. When we operate in a case of total posterior synechia it often happens that the retinal pigment of the iris within the area of the coloboma remains upon the lens-capsule, with which it is intimately united by exudation. In that case, immediately after the iridectomy is completed, we may suppose that we have made a fine black coloboma, and it is only upon lateral illumination that we become convinced that the coloboma is not black, but dark brown—i. e., is filled with pigment. The optical result of the operation is then nil. It happens not less frequently in total posterior synechia that it is absolutely impossible to bring the iris out of the wound for the purpose of cutting it off. The iris, on the one hand, is so rotten, and, on the other hand, is so firmly attached to the lens, that the forceps, instead of drawing the iris out, only tears small fragments out of it. Both in this case and in the one in which the pigment-layer remains behind, there is nothing left to do but to remove the lens also; hence we follow our iridectomy by an extraction of the lens by Wenzel's method (§ 162). 5. Prolapse of the vitreous is particularly apt to occur in iridectomy when the zonula is diseased, as, for example, in subluxation of the lens or in hydrophthalmus.

III. Iridotomy.

158. Iridotomy consists in simply dividing the iris without excising a piece of it, and in this respect differs from iridectomy. It serves the purpose of making a new aperture in the iris when the pupil is closed and of thus producing a new pupil. As the incision in the iris would also affect the lens which lies behind it and would thus produce traumatic cataract, this operation is only adapted to those cases in which no lens is present. In most cases the operation has to do with eyes which have been operated upon for cataract but which have lost their sight again through a subsequent irido-cyclitis. In these cases the iris is united with the exudation membrane and with the secondary cataract to form a firm diaphragm, which separates the cavity of the chambers and the cavity of the vitreous. To restore sight the diaphragm must be perforated. This can be accomplished by a simple incision, if this is so directed as to divide the diaphragm along a line perpendicular to that of greatest tension; then the incision gapes from retraction of the edges of the wound and leaves a slit-like pupil (cat's-eye pupil).

The operation may be performed with—

(*a*) The *Graefe knife.* This is plunged through the cornea and the diaphragm, and the latter is divided in a direction perpendicular to that of greatest tension. This method is only applicable when the diaphragm is not too thick. If the latter was the case, the diaphragm would offer great resistance to the knife, and in the endeavor to divide it the ciliary body would be pulled upon, and this might start up a new attack of irido-cyclitis.

(*b*) The *scissors-forceps* (pinces-ciseaux) by De Wecker's method. With the lance-knife an incision is made along the margin of the cornea, and through this the scissors-forceps is introduced closed into the chamber. Here the instrument is opened, and its posterior sharp

branch is plunged through the diaphragm while the anterior branch remains in the anterior chamber; then, by closing the scissors-forceps, the diaphragm is divided perpendicularly to the direction of greatest tension. This is a severer operation than the former, and is also usually associated with loss of vitreous. On the other hand, it does not cause any pulling, as in it the diaphragm is divided just as a sheet of paper is cut in two by a pair of scissors.

Iridotomy often fails of accomplishment owing to the too great firmness of the diaphragm, which may actually be ossified; but even an excellent immediate result may be nullified because the old iridocyclitis is lighted up again by the operation, and the pupil which has been made is closed again by a renewal of the exudation. Hence we put off the performance of iridotomy as long as possible until all inflammatory symptoms have disappeared, unless we are compelled to operate speedily by special circumstances, such as protrusion of the iris, increase of tension, or beginning atrophy of the eyeball.

IV. Discissio Cataractæ.

(*a*) *Discission of Soft Cataracts.*

159. Discission * of soft cataracts has for its object the opening of the anterior capsule of the lens in order to effect the resorption of the latter. Discission is performed with the discission-needle, which is passed in through the cornea (keratonyxis †). The site of the puncture is the center of the lower and outer quadrant of the cornea, at which spot the needle is passed through the cornea and perpendicular to the latter, and is then pushed forward in the anterior chamber as far as the anterior capsule of the lens. The latter is then laid open by one or more incisions in the area of the pupil (which has previously been dilated with atropine). The needle must be handled very lightly, no pressure being made with it, but simply sweeping movements; moreover, the incisions should not penetrate deep into the lens. The needle is then withdrawn from the eyeball, this being done quickly so that the aqueous may not escape.

After the operation the aqueous enters the lens through the wound in the capsule, and the lens swells up and is gradually absorbed in the manner described at length under the head of traumatic cataract (see page 382). In fact, discission is nothing but an imitation of the kind of injury of the capsule that accident so frequently produces.

Discission is adapted for all soft cataracts—i. e., for those which are capable of complete resorption because they have as yet no hard nucleus. This is the case in children and young persons. After the age

* From *discindere*, to split (*sc.*, the lens-capsule).

† From κέρας, horn, and νύττειν, to prick.

of twenty-five, when there is already a hard nucleus present, discission is no longer indicated. Discission may also be made in unripe cataracts —i. e., in those which still contain transparent portions of lens-substance—since these become opaque under the influence of the aqueous. Perinuclear cataract affords the most frequent indication for discission.

The main advantage of discission consists in the freedom from danger of the operation itself and in the simplicity of the after-treatment. Since the small puncture in the cornea closes again directly, the patient is able to leave his bed as early as a few hours after the operation and to go about without a bandage. If the course is favorable, no further treatment is required than to keep the pupil dilated with atropine until the resorption of the lens is complete. Discission, therefore, is the only cataract-operation which can be employed with very small children who do not keep quiet after the operation.

The time required for complete resorption of the lens amounts to at most a few months. In the course of this time various accidents may occur necessitating interference on the part of the physician. These are sometimes produced by the fact that the process of swelling takes place with too great violence; sometimes, on the contrary, by the fact that the swelling and absorption of the lens are brought to a standstill.

The *violent swelling* of the lens may be caused by too extensive a splitting of the capsule, owing to which the lens is exposed to the action of the aqueous over an excessively large area. In other cases, again, there exists in the lens a peculiar tendency to swell, which makes itself apparent even with small incisions of the capsule. As one can not form in advance a judgment of the tendency that the lens has for becoming tumefied, it is advisable at the first discission to make only a short and shallow section. The results of a rapid swelling of the lens may be either increase of tension or irido-cyclitis. The former manifests itself by the dull appearance of the cornea, by an increase of tension perceptible to palpation, and by the contraction of the field of vision; and these symptoms, if they were allowed to persist, would lead to amaurosis due to excavation of the optic nerve. The iritis is caused either by the mechanical injury (pressure) or the chemical irritation which the swelling masses of lens-substance produce in the iris. Both increase of tension and iritis are particularly to be apprehended in elderly persons, because these bear swelling of the lens worse than others do. To avoid these accidents the pupil must be kept well dilated with atropine, so that the swelling masses of lens-substance may come into contact with the iris as little as possible. Excessive swelling is most effectually combated by iced compresses, which, moreover, have an antiphlogistic action. If in spite of this treatment increase of tension sets in, paracentesis must be made, and, if necessary, be repeated several times. We may also make a pretty large incision in the cornea,

as is done for simple linear extraction (§ 161), and, as far as may be, evacuate the swelling masses of lens-substance through it.

In opposition to the cases just mentioned, there are others in which from the outset the processes of swelling and resorption of the lens *take place to an insufficient degree.* In this event we are often dealing with the kind of lenses which are especially apt to occur in aged persons, and which are capable of swelling but little. In other cases everything goes well at first, but after a part of the lens has been absorbed the swelling and resorption come to a standstill. The cause of this commonly lies in a union of the capsular wound, which takes place to such an extent that the aqueous no longer comes into contact with the lens-fibers. In either case the indication is to repeat the incision, in doing which one may proceed more boldly than in the first discission and make an extensive opening in the capsule. It sometimes happens that the whole chamber is full of swollen fragments of lens, the resorption of which shows no disposition to advance. We may then, following Werneck's method, evacuate the aqueous through a puncture in the cornea, so that the aqueous is renewed; whereupon absorption again goes on. It frequently happens that to obtain a complete cure of a cataract by means of discission two or three operations are required.

Discission is *contra-indicated*—1. In elderly persons whose lenses already have a nucleus, and whose eyes, moreover, do not bear well the swelling of the lens. 2. In subluxation of the lens, a condition which is recognized by the tremulousness of the latter. In this case discission is impracticable on technical grounds, since the lens being insufficiently fixed in its place would recede before the discission-needle. 3. When there is considerable thickening of the capsule of the lens, as in this case the discission-needle would cause luxation of the lens before it could tear through the capsule. 4. In the presence of posterior synechiæ, which render the dilatation of the pupil by atropine impossible. In such a case an iridectomy would have to precede the discission.

(*b*) *Discission of Membranous Cataracts* (*Dilaceration*).

160. The discission of membranous cataracts is not made with the view of effecting their resorption, since shrunken cataracts no longer contain much or any matter capable of being absorbed. On the contrary, their object is to make a free opening in the cataractous membrane by tearing it apart, and for this reason it had better be called dilaceratio cataractæ.* The operation may be performed either through the cornea or through the sclera.

* [This name, however, is scarcely applicable to the operation as performed in several places in this country, and notably at the New York Ophthalmic and Aural Institute. In this the cataractous membrane is not torn but cut, the discission-needle being replaced by a knife-needle, or a needle with a short, and very fine and sharp cutting edge at its extremity.—D.]

In the operation *through the cornea* (keratonyxis) the puncture is made in the center of the outer and lower quadrant of the cornea, as in the discission of a soft cataract. The needle is then pushed forward and plunged through the cataract, and then the attempt is made by means of sweeping movements to tear the cataract in all directions, so that as large a gap as possible may be formed in it.

In the *operation through the sclera* (scleronyxis*) the needle is plunged in perpendicularly through the sclera, six millimetres behind the external margin of the cornea, and somewhat below the horizontal meridian, and is then pushed forward so that its point passes through the cataractous membrane into the anterior chamber close to the external margin of the pupil. Then the attempt is made to tear the cataract to the greatest possible extent by means of sweeping movements in which the point of the needle travels from before backward. The difference between discission through the cornea and that through the sclera consists in the possibility of exerting in the latter method a greater force upon the cataract with the needle—a thing which is especially desirable when the cataractous membranes are rather thick.

Discission is adapted for all membranous cataracts, provided they are not too thick, and that there are no extensive adhesions of the cataract to the iris. Discission is frequently done as a secondary operation after the extraction of cataract to remove a secondary cataract.

The discission of soft cataract is a sure but slow procedure for its removal. If we desire to get at the same result quickly, we may pursue the following course: We perform a very extensive discission through the cornea, so that within a few days the whole lens is swollen up and disintegrated. Then we remove the broken-up masses of lens-substance by means of a simple linear extraction. We may also introduce the cannula of a syringe into the anterior chamber through an incision in the cornea, and by drawing up the piston suck out the fragments of the lens. This procedure, which is especially employed in England, is called *suction of cataract.*

In soft, non-shrunken cataracts, which it is designed to subject to the processes of swelling and resorption, one should not make discission through the sclera, for in that case, in order to split the anterior capsule, we would have to pass the needle through the entire lens and break the latter all to pieces—a procedure which, apart from the fact that we might easily luxate the whole lens in doing it, would give rise to excessive and violent swelling. Hence, scleronyxis is adapted only to those cases in which there are but few, if any, portions of the lens left which are able to swell up.

Dilaceration of a membranous cataract is an operation productive of but little disturbance as long as there are no adhesions between the cataract and the iris. In the latter case there is danger of undue traction being made upon the iris, with consequent irido-cyclitis. Simple discission should be made only when the cataractous membrane is thin enough to be torn apart without being pulled upon. In the case of rather thicker membranes the operation can be done according to

* [From *sclera*, and νύττειν, to puncture.]

duced through the section, and with these instruments the cataractous membrane is grasped and drawn out through the wound.

The advantages of simple linear extraction consist in the fact that the section is short and passes through the cornea obliquely, for which reason it closes readily, does not necessitate an iridectomy, and does not require any very strict after-treatment. But owing to this very fact that the section is so short, this method is adapted only to membranous or to soft cataracts—i. e., to those that have no hard nucleus, since the latter could only be removed through such a wound with difficulty, or could not be removed at all.

(*b*) *Flap-extraction.*

162. This operation has a curved section of an extent requisite for the removal of large, hard cataracts. The section may be made either in the sclera or in the cornea.

1. *Scleral Flap-extraction.*—This consists of four steps:

First step: Performance of the section. This is done with the Graefe linear knife, which is entered near the upper and outer border, and is brought out again near the upper and inner border of the cornea (Fig. 168). The points of entry and exit are situated in the sclera, at

FIG. 168.—SCLERAL FLAP-EXTRACTION, DRAWN FROM A CASE UPON WHICH THE OPERATION HAD BEEN PERFORMED. MAGNIFIED 2 × 1.

S, S_1, scleral incision situated throughout at a distance of half a millimetre from the border of the cornea; *a*, a_1, the angles of the sphincter in their proper position. From them the pillars of the coloboma run upward, converging somewhat as they go.

a distance of about half a millimetre from the margin of the cornea, and should lie so that a straight line connecting them corresponds to the dividing line between the upper fourth and the lower three fourths of the cornea. The knife is introduced at the point of entry, *S*, in such a way that the cutting edge looks upward, and the point is directed toward the center of the cornea. As soon as the point has passed this latter, it is raised by depressing the handle until it arrives at the site of the counter-puncture S_1, behind the upper and inner margin of the cornea. The counter-puncture should lie exactly opposite the site of the puncture. After the transfixion has been made, the section is completed by sawing cuts, so that through its whole extent it divides the sclera just behind the limbus. As soon as the knife has cut through the sclera, and lies beneath the conjunctiva, it is carried rapidly upward so as to

cut through the conjunctiva somewhat farther back. In this way a conjunctival flap is formed about two millimetres broad.

Second step: Iridectomy. After the conjunctival flap has been turned down upon the cornea, so that the wound may be exposed to view, the latter is entered with the iris-forceps, the iris is grasped close to the pupillary margin, drawn out, and cut off with a single sweep of the scissors.

Third step: Opening of the capsule. This is performed with the capsule-forceps, the delicate teeth of which are directed backward (Förster, Schweigger). The forceps, closed, is introduced and passed on in the anterior chamber until the center of the pupil has been reached. Here the forceps are allowed to open, and by the exertion of light pressure the capsule is grasped over as large an extent as possible, and is drawn out of the wound.

Fourth step: Expulsion of the lens. The Daviel's scoop is placed parallel to the wound against the lowermost part of the cornea, and light pressure is exerted with it upon the latter upward and backward. The pressure must be intermitted the instant the greatest diameter of the lens has passed through the wound.

After the operation is finished, the "toilet" of the eye is next in order. The portions of the cataract which are still left in the eye, and also any extravasated blood, are removed by stroking with the lower lid,* the iris is replaced from the wound into the anterior chamber by the introduction of the spatula, until the pillars of the coloboma have the proper position (see page 669), then the conjunctival flap is stroked out smooth, and the eye is bandaged.

2. *Corneal Flap-extraction* (De Wecker, Stellwag).—The way of using the linear knife is the same in this method as in the preceding, the difference between the two consisting merely in the length of the section. This is situated throughout in the limbus, the points of entry and of exit ($S\ S_1$, Fig. 169) being both made in it. The height of the puncture and counter-puncture must be so selected that the section detaches exactly the upper third of the cornea from the sclera. Hence, a conjunctival flap is either not formed at all or is formed only in an incomplete way. The other steps of the operation are performed as in scleral flap-extraction, with the exception of the iridectomy. This last may either be performed in the manner described above or it may be omitted. In the latter case the iris must be carefully replaced after the operation is finished, and then eserine must be instilled in order to prevent by the contraction of the pupil any subsequent prolapse of the iris.

The *indication* for the performance of flap-extraction is furnished by all cataracts which have a hard nucleus, and hence are not adapted

* [Or with a spatula.—D.]

either for discission or for simple linear extraction. The section is made upward, so that the coloboma, too, may be situated above and be covered by the upper lid. The section performed as above described is long enough for the largest-sized cataracts. If we have a cataract to operate upon whose nucleus is probably small, we may make a section of correspondingly smaller size.

The difference between the two methods depends upon the following fact: In *scleral extraction* the section ultimately lies beneath the conjunctiva, out of which therefore a flap can be formed. After the operation this flap becomes agglutinated very speedily to the raw sur-

FIG. 169.—CORNEAL FLAP-EXTRACTION. MAGNIFIED 2 × 1.

S, S_1, corneal section, which everywhere lies in the limbus. The operation has been performed without iridectomy, and the pupil is greatly contracted by means of eserine. As a consequence of this marked miosis, the pupil is not perfectly circular, but somewhat irregular, and the fringe of pigment lining it has become broader.

face upon the sclera, and closes the wound externally even when the edges of the incision in the sclera have not yet united. It thus protects the wound from subsequent infection, for which reason the scleral method affords the best conditions for healing.

The *corneal section* is destitute of the advantage of a conjunctival flap, but retains the possibility of *performing the operation without iridectomy*, for, as this section is less peripherally situated than that in the sclera, it is less apt to be complicated with prolapse of the iris. The omission of iridectomy has the advantage of keeping the patient's pupil round and mobile, but it also entails many disadvantages, which limit the number of cases in which extraction without iridectomy is indicated. Thus: 1. The delivery of the lens is more difficult without iridectomy, because the lens has to be expelled through the narrow pupil, and to accomplish this pretty strong pressure is required. Hence, this method is not adapted to those cases in which a very easy delivery of the lens is desirable, as, for instance, in cases of tremulousness of the lens in which any kind of strong pressure would produce rupture of the zonula and hyaloid membrane, and consequently prolapse of the iris. 2. Extraction without iridectomy is not adapted to cases in which there is a complicated cataract connected with the iris by synechiæ. 3. In spite of the use of eserine, prolapse of the iris may take place in the days following the operation. In this case we are obliged to make a secondary excision of the prolapsed iris. Accordingly, extraction without iridectomy is not adapted to cases which show a great tendency toward

prolapse of the iris, nor to those in which we can not count upon the patient's remaining quiet after the operation. We may therefore say: The corneal flap-extraction without iridectomy gives under favorable circumstances the most perfect result, but is neither adapted to all cases nor does it secure the same almost absolute certainty of success as the scleral flap-extraction with iridectomy.

Under special circumstances flap-extraction requires to be modified in special ways, two of which need to be particularly emphasized:

1. *Extraction of the Lens in the Closed Capsule* (Pagenstecher).—Instead of opening the capsule and expelling the lens from it, we may extract the lens along with the capsule and without opening the latter. For this purpose, after completing the section and excising the iris, we pass a special form of scoop behind the lens, and, at the same time maintaining pressure upon the cornea, lift the lens out of the eye. This operation is successful only when the capsule is thickened, since a capsule of normal thickness, when the attempt was made to remove it in toto with the lens, would rupture every time. Hence, this method is adapted only to cases of hypermature and complicated cataracts in which there are obvious signs of thickening of the capsule. It has the advantage that the entire lens is certain to be removed, and consequently that no material for an after-cataract can be left behind; but it is very frequently associated with loss of vitreous, since the scoop which is introduced behind the lens ruptures the hyaloid membrane in the fossa patellaris.

2. *Extraction by Wenzel's Method.*—This is designed for those cases in which there is adhesion of the surface of the iris to the lens (total posterior synechia). A curved incision directed downward is made either in the limbus or in the transparent cornea. This is so managed that, directly after the puncture is made in the cornea, the knife is passed through the iris and carried on behind the latter—that is, through the lens—to the opposite side, where the counter-puncture is made. If, then, the section is completed, there is formed at the same time with the incision in the cornea a flap composed of the iris and the anterior capsule of the lens. This flap we try to excise over as great an area as possible, in order to secure a large aperture in the iris and the lens-capsule. Then the lens is delivered. This operation is indicated when, owing to the presence of total posterior synechia, iridectomy can no longer be performed. There is then, in fact, no way of making an open pupil except to remove the lens along with the iris, even though the former is still transparent.

Accidents occurring in the Operation for Cataract.—The extraction may be made difficult or fail altogether, owing to accidents of various nature. Many of these are the fault of the operator. If the section proves to be too short, or if the capsule is insufficiently opened, the delivery of the lens is difficult or impossible. In this case the section

must be enlarged, or the capsule must be again ruptured, and this time more thoroughly. If the operator exerts too strong a pressure with his instruments upon the eyeball as a whole, or upon the iris or lens, the zonula ruptures and the vitreous gushes out. The greater the operator's skill grows with practice, the less frequently do these unlucky accidents happen to him. But there are other accidents which are caused by the abnormal condition of the eye that is operated upon, and in that case it generally does not lie in the power of the operator to prevent them. The most frequent of these accidents is *prolapse of the vitreous*. This takes place when the zonula ruptures. Such rupture not infrequently happens, because the patient screws his lids tightly together and thus presses upon the eyeball. It also occurs when the zonula was defective before the operation, and hence especially in hypermature and in complicated cataract. The significance of prolapse of the vitreous for the subsequent course of the operation varies according as it takes place before or after the delivery of the lens. In the former case the lens can not be evacuated in the usual manner by pressure exerted upon the eye; for then the larger part of the vitreous would escape before the lens itself came away. Hence, the lens must be drawn out of the eye with instruments—i. e., extracted in the true sense of the word. For this purpose the proper instruments are Weber's loop or Reisinger's double hook, which are introduced behind the lens and lift it out by force of traction.

Prolapse of the vitreous is much less to be dreaded when it takes place after delivery of the lens. The most serious harm that prolapse then does is that it hinders the accurate replacement of the iris, and also that the prolapsed vitreous lies between the lips of the wound and prevents their accurate coaptation. The vitreous may also give rise to suppuration of the wound, since it is very prone to become infected.

A rare but unpleasant accident is that in which the lens, before being delivered, becomes *luxated*, and disappears into the vitreous from which ordinarily it can not be extracted.

163. Result of the Cataract-extraction.—An eye whose lens has been removed is *aphakic*. It presents the following appearance when the operation and the healing of the wound have pursued a normal course: The cicatrix left by the operation, if situated in the cornea, appears as a narrow gray line; if the section has been made in the limbus or in the sclera, the resulting cicatrix becomes later on almost unrecognizable. The anterior chamber is abnormally deep, the iris is tremulous and, when the operation has been done with iridectomy, presents a coloboma above. The pupil is of a pure black, but on lateral illumination presents to view a membrane of silky luster, which not infrequently is thrown into folds. This is the lens-capsule which was left in the eye when the lens was removed. The capsule is left, partly because it would be impossible to remove a normal, non-thickened capsule intact from

the eye; partly because the capsule along with the zonula forms a diaphragm which, being stretched between the ciliary processes, keeps the vitreous in the eye, so that, in removing the capsule, we would always run the risk of having prolapse of the vitreous. It is, however, only the posterior capsule of the lens (*h*, Fig. 170) which is intact throughout. The anterior capsule (v, v_1), where it occupies the area of the pupil, is lacerated and in part deficient; the remains of it are applied directly to the posterior capsule. Since both capsules are transparent, the pupil appears round and black. Behind the iris the anterior capsule, where it was protected from the instrument used for making the opening, is preserved intact, and in conjunction with the posterior capsule incloses remains of the lens, which correspond to what was once the equator of the latter (Fig. 170, *k*). As the anterior and posterior capsules become agglutinated together in the pupillary area, these remains of the lens are shut off from the aqueous, and can not therefore be absorbed; in fact, they usually increase in amount, owing to proliferation of the cells of the capsule. They then form an annular swelling lying behind the iris (Soemmering's crystalline swelling). The lumen of the ring, which corresponds to the pupil, is closed by a thin, transparent membrane consisting of the two apposed layers of the capsule. As the opaque and swollen mass is concealed completely behind the iris, it in no way interferes with vision. If the operation has been made with an iridectomy, the mass is wanting in the course of the coloboma, because the anterior capsule was opened there likewise.



FIG. 170.—CROSS-SECTION THROUGH THE ANTERIOR SEGMENT OF AN EYE, UPON WHICH AN EXTRACTION HAS BEEN PERFORMED BY MEANS OF A SCLERAL SECTION. MAGNIFIED 4 × 1.

The section *s* which was made upward lies by its inner portion in the cornea, by its outer portion in the sclera; the latter is covered by the conjunctival flap, *b*. At a point corresponding to the section the iris is wanting, except for a short stump. The anterior capsule presents a large aperture, the edges of which (v, v_1) are curled over, while the posterior capsule, *h*, although slightly folded, is unruptured. In the lower part of the eye behind the iris the remains of the lens which are inclosed in the folds of the capsule form Soemmering's crystalline swelling, *k*, which is wanting in the parts above that correspond to the coloboma.

Without glasses the *sight* of persons who have been operated upon for cataract is just sufficient to allow them to go about alone or to do very coarse work. Distinct vision is possible only with the aid of convex glasses, since by the removal of the lens the refractive power of the eye has become too small, and hence there is a high degree of hypermetropia. If the eye was emmetropic before the operation, the hypermetropia afterward amounts on an average to from 10 to 12 *D*. It is

otherwise in cases in which an error of refraction already existed beforehand. If a hypermetropia was present previously, it is added to that which is acquired by the operation, and makes it greater by just its own amount. If, on the other hand, the eye was myopic before the operation, the subsequent hypermetropia is so much the less; extremely myopic eyes may actually become emmetropic after a cataract operation or even remain a little myopic. The aphakic eye, moreover, is destitute of accommodation. The eye is incapable of altering its refractive state. Hence it follows that by any single glass the latter is corrected for a single distance only. Accordingly, an eye operated upon for cataract needs at least two glasses—one for distance, the other for near.

It often happens, even in cases in which the operation has been well performed, that the result of the operation is impaired by the *retention of portions of the cataract.* This happens particularly when the operation is done on immature cataracts, but by no means fails to occur also in those that are mature and hypermature. If the anterior capsule is thoroughly opened, the portions of lens left behind (if they were not already opaque previously) grow opaque, swell up, and become absorbed. In this case, therefore, a pure black pupil is ultimately obtained. But if the layers of the capsule become agglutinated early and shut off the remains of lens-substance from the aqueous, these remains are not absorbed but persist as a white membranous opacity. This is called after-cataract (*cataracta secundaria*). If this is present in only one part of the pupil while another part of it is quite clear, the sight may be perfect. But if the whole pupil is filled by the secondary cataract, the sight is diminished in proportion to the density of the opacity. It may also happen that the after-cataract does not develop until later on; the epithelium of the anterior capsule which has been left behind proliferating and inducing a secondary thickening and opacity in the latter.

After-cataract, when it interferes with sight, requires a secondary operation—namely, discission or simple linear extraction. The secondary operation should be performed not sooner than four weeks at earliest after the cataract-extraction.

The result of a cataract-operation may furthermore be impaired by *inflammation* (see pages 671, 672). If suppuration of the wound sets in, the eye is almost always lost. If irido-cyclitis develops, the secondary cataract is united by the exudate which is formed to the iris and even to the ciliary processes (cataracta secundaria accreta). It depends upon the condition of the light-perception whether the sight in such a case can be restored or not by a secondary operation (iridectomy or iridotomy).

Historical.—In the preceding lines it has been shown that there are various ways open to us for removing cataract. We may either subject it to resorption by means of discission, we may tear a hole in it by dilaceration, or we may remove it altogether from the eye. But not even by this list are all the

The cases in which the lens became prolapsed into the anterior chamber after the operation of depression occasioned the first performance of *extraction* of cataract. This method of operating if we are to believe some authors, was perhaps practiced now and then even in ancient times, but at any rate it had in the middle ages fallen completely into oblivion. The first information that we have in regard to it we get from the seventeenth century, when there are several instances in which the lens was removed from the anterior chamber into which it had got after the operation of depression. The Frenchman Daviel had already done this in several cases, when in the year 1745 he first dared to undertake this operation upon a cataract which was situated in its normal position. In so doing Daviel inaugurated a new era in the history of cataract-operations, since from that time the extraction of cataract began more and more to take the place of depression.

The original method of Daviel was naturally very much in need of improvement. Of the many modifications which it underwent, the last and best was that of Beer. The latter made the section with a knife invented by himself, which broadens out from point to handle so as to have a wedge shape. With Beer's cataract-knife it is possible to complete the section by simply pushing the knife forward after it has been entered, and owing to this fact the section acquires a high degree of regularity. The section ran somewhat inside of the limbus, and separated exactly the lower half of the cornea from the sclera. Then, after opening the capsule, the lens was delivered, but no part of the iris was excised.

Beer's procedure was soon generally adopted, and was for a long time the prevailing method. In successful cases it gave ideal results. The pupil was black, round, and perfectly movable, and it was only upon close examination of the eye that it could be discovered that an operation for cataract had been performed at all. Unfortunately, it always happened that a considerable number of eyes were lost after this operation, especially by suppuration of the cornea. As at that time it was not known that this was caused by infection of the wound, the method of operating, and particularly the way in which the section was made, were regarded as accountable for it. Hence, other better methods were sought after, and this time Von Graefe was the one to take the most important step forward and create a revolution in the methods of performing extraction by the invention of his process.

Von Graefe considered that the cause of the suppuration of the cornea in Beer's method lay in the shape of the section which was made with a flap. This gives rise to great gaping of the incision, in consequence of which the lips of the wounds are not properly applied to one another, and this fact was supposed to furnish the cause of the suppuration. Von Graefe accordingly believed that the linear incisions were preferable, as he had become convinced of the promptness with which they healed in the case of simple linear extraction, an operation which had already been practiced by him. Accordingly he, as well as others, attempted to apply the linear section which was made with the lance-knife, and which originally was employed only for soft or shrunken cataracts, to large cataracts with a hard nucleus. With this object in view these experimenters tried to make the linear incision as large as possible by placing it in the upper part of the cornea, and by combining it with iridectomy. Others tried to diminish the size of the lens first by crushing it so as to be able to extract it through the section. But these attempts were all unsuccessful.

traction" (in contradistinction to the simple linear extraction). Later on one made a virtue of necessity, and laid special stress upon the advantages of the iridectomy that was combined with the extraction. It prevented, they said, the incarceration of the iris, made it possible to open the capsule more thoroughly, facilitated the removal of the remains of the cataract, and afforded a protection from subsequent inflammation of the iris. Hence, people soon got to regard the excision of the iris as one of the additional advantages of the new method.

The results of Von Graefe's linear section were, in fact, much better than those which the earlier methods had given. Suppuration of the wound, in particular, had become less frequent. But yet the method had its dark side, too. Its performance required more operative skill, and the delivery of the lens was made more difficult, owing to the slight tendency to gape that the wound possessed. Other disadvantages arose from the peripheral situation of the section, which brought the latter, especially at its extremities, close to the zonula and the ciliary body. Prolapse of the vitreous was frequently met with, and also inclusion of the pillars of the coloboma in the wound. While suppuration of the wound proved to be less frequent, iritis and irido-cyclitis became proportionately more common, and in consequence sympathetic disease of the other eye was observed more frequently than before. These facts induced operators to depart more and more from this section, which was felt to be too peripheral in its situation, and in particular led them to place the extremities of the latter near the cornea. If Von Graefe's original section, as Von Graefe himself gave it, was itself not a pure linear incision, this is still more the case with the section as it was subsequently performed. It had become a curved section, forming an arc of small altitude. Under this somewhat modified form, scleral extraction soon became the method that was generally employed. I myself make this section as it is shown in Fig. 168, and as it is described on page 693, under the name of scleral flap-extraction. This form of section has, it is true, developed gradually out of the linear section of Von Graefe, but it is no longer entitled to the same name.

Since with the introduction of the antiseptic method the danger of suppuration of the wound has been reduced to a minimum, operators no longer hesitate to make the section in the limbus or in the transparent cornea itself—as, for example, is done in the corneal flap-extraction above described. Other improvements that have been made have had regard to the *excision of the iris.* Operators had already learned by careful reposition of the iris to avoid the dangers arising from its incarceration. When this is done there is no need of making a large coloboma such as Von Graefe had described. I myself take pains to make the excision of the iris as slight as possible (Fig. 168). With this object in view, I draw the iris from the wound only far enough for its pupillary margin to become visible, and then, holding the scissors-forceps perpendicular to the direction of the wound, snip off simply the apex of the tag of iris. A small coloboma averts prolapse of the iris as certainly as does a large one (see page 675), and causes less confusion from dazzling.

When at length surgeons again adopted the section in the cornea, they took the last step and operated entirely *without iridectomy*, as Daviel and Beer had done in former times.

The *opening of the capsule* was made by Von Graefe with a cystitome—i. e., with a triangular-cutting lancet, and by others was made with the discission-

needle or with a sharp hook. An important improver
duction of the capsule-forceps for opening the capsule.
capsule is not only split, but also has a piece taken out
lar wound is prevented from closing quickly again, and
fering with the resorption of the fragments of the lens
employment of the capsule-forceps, secondary cataract
frequent, although at present unripe cataracts are ope
often than formerly.

In recent times many operators have followed the ex
of the anterior chamber with weak antiseptic solutions,
out the fragments of lens which remain behind, and p
terior of the eye (MacKeown, Wicherkiewicz). I ha
pretty often, but without seeing any essential advantag

Besides the methods of extraction which have beer
innumerable number of others, distinguished by diffe
position of the section, in the way of excising the iris,
ing the capsule, etc. Many operators placed the incisi
(Lebrun, Liebreich)—in fact, even in its center (Kûchl
the section with hollow-ground knives—e. g., Weber
Eduard Jäger with a concave knife. It would carry
these methods in detail. We know now that the s
depends far less upon the way in which the section
cleanliness of the operator.

In many persons who have been operated upon f
of *erythropsia* (= red-sight, from ἐρυθρός, red) is obse
shows itself after the patients have been discharged a
go home. These patients say that suddenly everythin
color. This phenomenon lasts for a period varying
some hours, and is apt to recur quite frequently. It is
by dazzling of the eye, and sometimes also by heating
nature of this phenomenon, which does the patient no fu
In rare cases it has also been observed after other oper
has even been observed in eyes that have not been oper

CHAPTER III.

OPERATIONS UPON THE ADNEXA BULBI.

I. Squint-operations.

(*a*) *Relaxation of an Ocular Muscle* (*Tenotomy*).

164. Tenotomy is performed upon the internal or external rectus; very rarely, indeed, upon the other ocular muscles.

Tenotomy of the internal rectus by Arlt's method is performed as follows: The conjunctiva on the inner side of the cornea is lifted up with a fixation-forceps so as to form a horizontal fold in which a vertical cut, situated about four millimetres from the margin of the cornea, is made with a single snip of the scissors. The incision is then enlarged upward and downward, and the conjunctiva to the nasal side of it is undermined. Starting from the wound, the fixation-forceps is passed inward till it reaches the tendon, which is grasped, drawn somewhat away from the eyeball, and divided close to its insertion in the sclera. For this purpose a small pair of curved scissors is used, the branches of which should have blunt points, so as not to stick into the sclera. After dividing the tendon the next thing to do is to see whether there are not some strands of tendon still remaining at its upper or lower border. A squint-hook is accordingly passed in beneath the tendon and is carried upward and downward so as to explore all parts, the intention being to catch up upon the hook any fibers that may chance to be intact and then to divide them.

After the division of the tendon has been completed, a test must be made of *effect* of the operation, which should be neither excessive nor insufficient. We first (1) make the eye that has been operated upon turn toward the side of the divided muscle. If the tendon has been cut through completely, there must be a considerable diminution of the motility inward. If the eye can be turned inward as well as it could before the operation, this proves that some strands of the tendon have remained undivided. As in this case the result of the operation would be nil, these fibers must be sought out with the hook and divided. (2) We make the patient fix his gaze upon the finger held in front of him, and then keep bringing the latter nearer and nearer to his eyes. After a properly performed tenotomy of the internus, a convergence to at least twelve centimetres should be still possible. If the eye that has been

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

operated upon halts in its movement of convergence before it reaches this point, this argues an excessive effect of the operation. The working capacity of the internus is then so greatly weakened that we should have to fear the subsequent development of a divergent strabismus. In this case the effect of the operation would have to be restricted once more. The extent to which the strabismic deflection is corrected by the operation is to be regarded as of only secondary importance. In fact, when the deflection is great, the correction can not possibly be secured by a single tenotomy.*

When, by testing in the manner given, the effect of the operation is discovered to be satisfactory, the operation is finished by uniting the conjunctival wound with a suture.

The operation can be rendered painless by means of cocaine; but for this purpose it is requisite that cocaine should be instilled not only before but also repeatedly during the operation.

Tenotomy of the external rectus is performed in an analogous fashion. We must simply keep in mind the fact that the insertion of the external rectus lies farther from the cornea than does that of the internus.

Tenotomy *acts* by displacing the insertion of the divided muscle to a spot situated farther back. Let us assume that the case is one of an operation upon a convergent strabismus, in which the internus is shortened by a certain amount. The externus is elongated to the same degree by being stretched just as it is whenever the eye rolls inward. The muscle thus put upon the stretch attempts to return to its normal length, but can not accomplish this, owing to the resistance of the shortened internus; but, as soon as this resistance is removed by the division of the internus, the externus contracts and draws the eye outward, so that the position due to the squint is corrected. As this takes place, the divided tendon of the externus glides upon the sclera to a point situated proportionately far back, and there becomes attached anew to the sclera. Owing to the fact that the insertion of the internus now lies farther back, the latter suffers permanent impairment in the effect that it exerts upon the eyeball. The immediate result of the operation is greater than it is found to be afterward. The more solid is the union which the divided tendon forms again with the sclera,

* [A third and more delicate way of testing the effect of the operation is by the prismatic tests, which are frequently employed, especially in the graduated or "partial" tenotomies done for the correction of insufficiencies. In the latter class of cases the amount of insufficiency is accurately measured by the prismatic tests before the operation, a certain amount of correction is made by tenotomy (or advancement), the test repeated, and the operation continued according to the indications furnished by this second test. It not infrequently happens that three or four such successive tests are made during the performance of the operation, the effect of which can thus be gauged with such nicety that in hyperphoria, for example, a deflection of only a fraction of 1° is corrected with almost absolute accuracy.—D.]

the stronger is the action which it can exert, and thus the effect of the operation diminishes in the succeeding four or six weeks.

(*b*) *Advancement of an Ocular Muscle.*

Advancement consists in a displacement of the insertion forward, and consequently is an operation that is the opposite of tenotomy. It is performed upon the antagonists of the shortened muscle, and always in conjunction with tenotomy of the latter. Suppose, for example, that the case is one of strabismus divergens. In this case the internus would be advanced in the following way: A tenotomy of the externus is first performed in the regular way; then the conjunctiva over the tendon of the internus is divided just as for tenotomy of this muscle. The exposed tendon is caught up upon a squint-hook that is pushed beneath it, and then two threads are passed through the tendon some millimetres behind the line of insertion. These are passed through from behind forward, one near the upper, the other near the lower border of the tendon, Tenon's capsule and the conjunctiva being included at the same time. The tendon, which now being held fast by the threads, can not slip back into the orbit, is next divided close to the sclera.* The upper of the two threads is now carried forward from the conjunctival wound along beneath the conjunctiva as far as the upper margin of the cornea, where it is brought out again. In like manner the lower thread is carried beneath the conjunctiva to the lower margin of the cornea; then the upper and lower threads are tied separately. The tighter the threads are drawn, the farther is the tendon carried forward. In this way the effect of the operation can be regulated.

By advancement the insertion of the muscle is brought nearer the cornea, and thus there is given to it more power over the eye. The farther forward the extremity of the tendon is attached, the greater is the effect of the operation. Later on, however, the effect diminishes, for which reason the operation is regulated in such a way that at first an over-correction is obtained.

156. Indications for the Squint-operations.—1. *Concomitant strabismus* is the most important and most frequent indication for performing the squint-operations. In *convergent strabismus* the operation is indicated in all cases which can not be cured by non-surgical means. A simple tenotomy corrects a squint of about three or four millimetres. If the strabismic deflection is considerably greater than this amount, a second tenotomy must be performed in addition upon the other eye. This should be done not sooner than fourteen days, and later if possible, after the first tenotomy, in order that we may judge of the final

* [Sometimes also the portion of the tendon to the corneal side of the suture is exsected.—D.]

result of the first operation and gauge the second accordingly. The effect of the squint-operation depends mainly upon the state of the antagonist of the contracted muscle, whose task it is to bring the eye back into its proper position after the tenotomy. When, after a squint has lasted a long time, the antagonist has lost a great part of its strength, the effect of a simple tenotomy is very slight. For such cases advancement of the antagonists is indicated to increase this strength.

In convergent strabismus it sometimes happens that divergence of the eyes sets in quite a long time after a successful operation. To avert this danger, the strabismic deflection should never be completely corrected, but the tenotomy should rather be so gauged that a slight degree of inward squint, such as shall not be perceptible to the laity, remains. After the operation that convex glass is prescribed which is demanded by the hypermetropia that is usually present. If the eye which has formerly squinted is not too amblyopic, we also institute exercises in the practice of binocular vision, partly to prevent the return of the squint, partly to remove the slight degree of convergence which has been left.

In *divergent strabismus* the effect of tenotomy is much slighter. The correction here amounts to not more than two millimetres on an average, and, moreover, is afterward considerably reduced. Hence, in order to obtain the desired result, the attempt must be made to produce a considerable over-correction of the squint. A single tenotomy is hardly ever sufficient for this purpose; we must at least perform a tenotomy in both eyes, and generally an advancement in addition. As it never happens that a divergent strabismus is spontaneously transformed into a convergent strabismus, one need have no fear of making a thorough operation.

That form of strabismus divergens which develops from strabismus convergens, after too extensive a tenotomy, is associated with considerable enfeeblement of the divided internus, and hence always requires the advancement of the latter.

2. *Insufficiency.* Ordinarily it is only insufficiency of the interni that furnishes the occasion for tenotomy, which is then performed upon one or both of the externi. It is done—(*a*) When the insufficiency causes the symptoms of a muscular asthenopia. (*b*) When the insufficiency threatens to pass into strabismus. (*c*) When the insufficiency exerts harmful influence upon myopia by favoring the progress of the latter. The performance of tenotomy, however, should not be resolved upon until all non-operative measures have proved to be fruitless. Furthermore, the insufficiency must be so considerable that it will not possibly be transformed into its opposite, or an insufficiency of the externi, by tenotomy; we should then have to deplore the development of a convergent strabismus with a tormenting diplopia as a result of

the operation. On the whole, the performance of tenotomy for insufficiency is comparatively rare at the present time.*

3. *Paralytic strabismus.* In this the squint-operation is indicated only when we are dealing with an old paralysis, the spontaneous cure of which is no longer to be counted upon. If the paralysis is complete, so that the paralyzed muscle is no longer able to exert any effect whatever upon the eyeball, the operation is fruitless. The operation is only of service when the muscle, although enfeebled, is still capable of performing its functions, and the strabismic deflection is caused mainly by the contracture of the antagonist. It is only in the slightest cases that we can attain our object by making a tenotomy of the contracted muscle; as a rule, we must combine this with advancement of the paralyzed muscle. In many cases we operate not upon the paralyzed but upon the sound eye. Suppose, for example, that the inferior rectus of the right eye has been left permanently enfeebled by a paralysis, so that troublesome double images are formed upon looking downward. In this case we may, by tenotomy of the inferior rectus of the left eye, also limit its capacity for making excursions downward, and thus remove the troublesome symptom—namely, the diplopia.†

*[In this country, however, tenotomy and advancement are pretty frequently performed for the relief of insufficiency. Moreover, these operations are done not only for insufficiency of the interni (exophoria), but also, and perhaps more frequently, for insufficiency of the externi (esophoria); and tenotomy or advancement of the inferior or superior rectus for vertical insufficiency (hyperphoria) is also quite common. Indeed, as far as the relief of muscular asthenopia is concerned, the results of the operation in vertical insufficiency are both more satisfactory in their immediate effects, and also more permanent than is the case with tenotomy of the lateral recti. As hyperphoria is a much more frequent condition than formerly supposed (being, for example, found by the translator in one third of the cases which he has examined), it seems likely that some of the previous failures in the treatment of muscular asthenopia by operation have been due to the failure to appreciate this important condition, the operator confining himself simply to a correction of the lateral insufficiency.—D.]

† [This operation—namely, tenotomy of the homonymous muscle of the other eye—was the one recommended by the elder Von Graefe in cases of paresis of the superior and inferior rectus. Alfred von Graefe, however, prefers in such cases advancement of the paretic muscle itself, a procedure which he calls the "substitution operation." In the case of the other muscles the same authority has demonstrated that the most serviceable operation is tenotomy of the associated antagonist—i. e., of that muscle of the other eye which turns the latter in the same direction as the muscle affected would, when in the normal state, turn the eye to which it belongs. Thus, in case of paresis of the right internal rectus, external rectus, superior oblique, and inferior oblique, their respective associated antagonists—namely, the left external rectus, internal rectus, inferior rectus, and superior rectus—would be divided. The reason for this operation, which Von Graefe calls the "compensating operation," is obvious when we consider that by division of the associated antagonist we limit the movement of the sound eye in precisely the same way that the movement of the affected eye is limited by the paresis. Thus, paresis of the right inferior oblique restricts the movement of the right eye upward and outward (to the right).

Tenotomy of an ocular muscle was first tried by Stromeyer upon the cadaver and some years later (1839) was also performed by Dieffenbach upon the living subject. Dieffenbach did not divide the tendon, but the belly of the muscle. Hence, it not infrequently happened that the posterior half of the muscle retracted so far that it could never again become attached to the eyeball. The divided muscle was then completely paralyzed, and when the operation had been performed upon a convergent strabismus, the latter was transformed into a marked divergent squint. Owing to such bad results, the operation gradually fell into such disrepute that surgeons were on the point of giving it up again. Then Böhm proposed a new and improved method, namely—the division of the tendon as we practice it now. Von Graefe added to this the method of regulating the operation with precision, showing how its result could be increased or diminished. Von Graefe performed the operation, and most other operators still perform it, somewhat differently from the way described above. He did not grasp the tendon with the forceps, but with a hook, upon which he made his cut dividing the tendon, and then used a second smaller hook for the purpose of exploring after undivided strands of tendon.

Advancement was first performed by Guérin and soon after by Von Graefe. The latter proposed the procedure known as the *thread operation*. This is distinguished from the method above described only in the following particular: The contracted muscle is not divided directly at its insertion, but somewhat behind it, so that a short portion of the tendon remains upon the sclera. Through this portion a thread is passed by means of which the eyeball can be drawn as far as desired toward the opposite side. After the operation has been finished, the ends of the thread are fastened in the vicinity of the eye by means of adhesive plaster, so as to keep the eyeball in the position desired. In this way both the effect of the operation is increased and the tension upon the muscle that had been advanced is lessened.

How does tenotomy of a muscle weaken the latter? Let us assume that a tenotomy has been performed upon the right internus for right convergent strabismus. After the division of the tendon, the externus draws the eye outward. For this reason, and also on account of the elastic contraction which every divided muscle shows, the tendon of the internus becomes attached farther back upon the sclera. The insertion of the muscle is thus approximated to its point of origin at the optic foramen, and the muscle is shortened. Before being divided, the muscle in its relaxed state had a certain length, from which by its contractile force it was able to shorten down to a certain minimum. After the division this minimum remains the same, but the length of the muscle in the state of relaxation is less; hence, the difference between the state of rest and of maximum contraction is diminished. But this difference corresponds to the power of adduction of the eye, which, accordingly, is permanently reduced

---

and also restricts the rotation of its vertical meridian outward (to the right); and tenotomy of the associated antagonist (left superior rectus) restricts the movement of the left eye upward and inward (to the right), and also restricts the rotation of its vertical meridian inward (to the right). In paresis of the superior and inferior obliques the compensating operation alone is sufficient; in paresis of the external and internal recti, the compensating operation (tenotomy of the internal or external rectus of the other eye) usually needs to be supplemented by tenotomy of the internal or external rectus of the same eye ("equilibrating operation"), and often also by advancement of the paralyzed muscle itself.—D.]

after the tenotomy. We can readily convince ourselves that after an operation, the eye can not be brought inward as far as it could before; indeed, it is from this fact that we determine whether the operation has been successful.

It is hence clear that the correction of the faulty position due to the squint is purchased at the expense of the adduction. In fact, the loss in the motility inward is always greater than the gain in the position of the eye. The former loss, however, is ordinarily of no importance, since in convergent strabismus the adductive power is abnormally great. Hence, even if it is reduced by the operation to a point somewhat below its mean value, this reduction would still fail to become noticeable except when the eyes were in the extreme lateral position. But the case is different when the attempt is made to correct a marked strabismic deflection by a very thoroughgoing tenotomy of the internus, with which there would necessarily be associated a considerable diminution of the power of adduction. We would then, it is true, have the eyes in a correct position while the gaze is directed straight forward; but as soon as the patient wishes to look toward the side upon which the tenotomy has been performed (e. g., in the case of right convergent strabismus, to the left), the eye that has been operated upon would not be able to follow the movement properly. When the eyes are cast in this direction, divergent strabismus would appear just as in the case of a paralysis of the internus. Hence, we ought not to try to compensate for a marked strabismic deflection by a unilateral operation, but must distribute the operation between the two eyes. A tenotomy is first made upon the squinting eye, and some weeks later upon the sound eye. Thus, by adding the effects of the two operations we obtain the desired effect, while at the same time we get only an inconsiderable reduction of the adducting power in each eye. The performance of a tenotomy upon the sound eye is the more justified in that this eye also shows a pathological increase of adducting power, because patients with inward squint always innervate both interni too strongly (see page 573).

We can form beforehand an approximate estimate of the effect of a simple tenotomy. This effect depends essentially upon the condition of the antagonist of the contracted muscle. The more powerful this is the greater will be its ability to bring the eye into the correct position after the division of the contracted muscle. But for the force of the muscles we have a sure gauge in the amount of the lateral excursion (abduction and adduction) which we can determine (see page 535). This measurement, therefore, should be performed before every squint-operation; then, when the desired effect has been secured by the operation, this effect can be still further increased or be diminished by appropriate means (regulation of the effect).

The methods of *increasing the effect* of the operation are:

1. *Relaxation of the lateral invagination* of the tendon. By this latter term is meant the connection which, at the spot where the tendon passes through Tenon's capsule, exists between these two structures. This connection still persists after tenotomy, since the tendon is divided inside of Tenon's capsule. In this way is explained the fact that the muscle, although separated from the eyeball, has not yet lost all action upon the latter, since it still moves Tenon's capsule, and thus indirectly the eye as well. By the lateral invagination, too, the tendon is kept after its division in the vicinity of the sclera, so that it can become reattached to it. The more this connection is interfered with, the more will the tendon retract and the farther back will be the point at which it becomes reattached to the eyeball. Accordingly, we can heighten the effect of the

operation by dividing the connective tissue on both sides of the tendon and setting the tendon itself free. We should not, however, proceed so far as to separate the tendon completely from Tenon's capsule, since in that case it would retract altogether into the orbit and would not again form an adhesion with the eyeball. We might then, as in the case of Dieffenbach's operation, have to deplore an excessive result.

2. Insertion of a *suture* which reinforces the action of the antagonist (Von Graefe, Knapp). In tenotomy of the internus the suture is applied to the outer side of the eyeball. The thread is introduced close to the external margin of the cornea and parallel with it. One end of the thread is afterward passed from within outward through the external commissure, and is then tied to the other end. The tighter the thread is drawn while being tied the more will the eye be rolled outward. In tenotomy of the externus the suture must be inserted on the inner side of the eyeball.

3. *Advancement of Tenon's capsule* (De Wecker). This is performed over the antagonist whose action it is desired to strengthen—i. e., in convergent strabismus over the externus. We proceed as in advancement of the tendon, exposing it and passing threads through it and the conjunctiva, which draw the tendon forward and Tenon's capsule along with it. From advancement this method is mainly distinguished by the fact that the tendon itself is not divided.

To *diminish the effect* of the operation the following means are at our command:

1. When the suture is applied which is designed to close the wound in the conjunctiva, a wide and deep grasp is taken upon the conjunctiva, so that the needle is passed through Tenon's capsule as well. Then, when the knot is drawn tight, the tendon is drawn forward a little along with the conjunctiva.

2. If it is apparent that the divided muscle has suffered too great impairment of its action, its end must be grasped and attached again farther forward by means of threads. This event occurs when the connection of the muscle with Tenon's capsule has been loosened to too great an extent, or when the operation has been done for a very slight strabismic deviation. It is, in fact, better to leave very slight cases of squint unoperated upon. It is true that the attempt has been made to modify the tenotomy, so that its action shall be very slight, the aim being to effect this by leaving some fibers of the tendon undivided (Von Graefe and Abadie*). Such a partial tenotomy has, however, had no permanent result whatever. We can convince ourselves of this fact in those cases in which some fibers of the tendon are unintentionally left. In such cases the effect of the operation disappears completely after some length of time. The fibers which remain in place prevent the tendon from retracting, so that it becomes reattached to the sclera at the same spot as before.

As regards the *final* result, cases behave differently. The most frequent outcome is that the effect of the operation increases somewhat in the first few days, then diminishing again, and ultimately becoming less than at first. Sometimes the diminution proceeds so far that the effect of the operation almost completely disappears and the operation has to be repeated. This is particularly apt to be the case in divergent strabismus. In convergent strabismus, on the contrary, it sometimes happens that the effect slowly but steadily increases until finally divergent strabismus supervenes. This may take place even years after-

* [And in this country, G. T. Stevens, of New York.]

ward. Unfortunately, it is impossible, either before or directly after the operation, to foresee with certainty which of these occurrences is going to ensue, so that we can not at once take measures to combat them.

Among the unpleasant results which sometimes accompany tenotomy is *sinking in of the caruncle*, which looks as if it had been drawn far back. This condition develops only after tenotomy of the internus, and is due to the fact that the muscle as it retracts draws the conjunctiva of the inner half of the eyeball after it. This can be prevented if the conjunctival wound is closed with a suture and the conjunctiva thus kept in its proper place. Impairment of the cosmetic result may also be produced by *exophthalmus*. This originates from the fact that after division of one of the recti the eye is not retracted into the orbit with as much force as formerly. For the same reason a slight degree of exophthalmus is observed not infrequently in paralyses of the recti. The exophthalmus can not be removed, but when it has a disfiguring effect it can be concealed, for in exophthalmus of such a slight degree as is here the case the conspicuous thing is not so much the protrusion of the eyeball as the increase in size of the palpebral fissure which is caused by the protrusion, and this latter defect can be corrected by shortening the palpebral fissure at the outer angle of the eye (tarsorrhaphy). During the after-treatment of a squint-operation there is not infrequently formed a *nodule of granulation*, growing out of the sclera at the site of the conjunctival wound. Subsequently this becomes constricted at its base and ultimately falls off. It may also be snipped off with the scissors.

Serious accidents, such as suppuration of the wound, exudation into Tenon's space, with protrusion of the eyeball, and actual panophthalmitis, can only occur when the wound has been infected during the operation. At the present time these accidents are among the greatest of rarities. If we should perform the operation with a sharp pair of scissors, and at the same time are dealing with an unruly patient, it may happen to us to perforate the sclera. If the operation has been performed aseptically, this accident will, as a rule, pass over without producing any bad results. In general, tenotomy, if carefully performed, may be said to be perfectly free from danger; and it is one of the operations for which patients (especially those of the female sex) are most grateful.

An indication for tenotomy, although, to be sure, a rare one, is found in those cases in which we are compelled to make a *coloboma upward for optical purposes*. Such a coloboma, when the palpebral fissure is open only to the ordinary extent, is covered by the upper lid. Most patients soon learn to expose the coloboma by raising the lid strongly; but, if they should be unable to do this, a tenotomy would have to be performed upon the superior rectus, so that the inferior rectus may depress the eye and bring the coloboma into the palpebral fissure. Obviously this should only be done when the other eye is blind, as otherwise diplopia would develop just as in case of paralysis.

II. Enucleation of the Eyeball.

166. Enucleation consists in shelling the eyeball out of Tenon's capsule, the conjunctiva and all the tissues adjoining the eyeball being left behind. Bonnet has the credit of having been the first to introduce this operation, which he did upon the basis of his studies upon Tenon's

capsule (which hence is also called Bonnet's capsule). Before this, operators were in the habit of cutting the eyeball, together with the neighboring soft parts, out with a knife in a way not very different from that in which a butcher is accustomed to do it. This much more radical operation, which is called *extirpatio bulbi*, is at the present time performed only in those cases in which malignant neoplasms have grown out from the eyeball into the tissues of the orbit so that a simple enucleation of the eyeball is no longer practicable. By *exenteration of the orbit* (exenteratio orbitæ) is meant a scooping out of the contents of the entire orbit, so that nothing but the bony walls of the latter are left. This operation, too, is performed only for malignant new growths.

Enucleation, as done by Arlt, is performed as follows: The patient is anæsthetized, and the lids are separated by Desmarre's retractors. For the operation itself a fixation-forceps and a pair of straight scissors, which should have one branch blunt and the other sharp-pointed, are employed. If the operation is performed on the left eye, the conjunctiva close to the external margin of the cornea is first picked up and incised. From this wound as a starting-point the conjunctiva is divided all round the cornea, and then it is loosened from its connections still farther back. Then the external rectus is grasped with the forceps and divided behind the latter, so that a stump of tendon remains attached to the sclera. This serves to hold the eye with, during the subsequent course of the operation, which consists in the division of the rest of the ocular muscles and of the optic nerve. The blunt-pointed branch of the scissors is passed beneath the tendon of the superior rectus, and the latter is taken up upon the scissors and is divided close to the sclera by a single snip. The same is done with the inferior rectus. Then the scissors, closed, are passed from the outer side in behind the eyeball to feel for the optic nerve, which when the eyeball is drawn forward is put upon the stretch so as to form a hard cord. When the optic nerve is felt, the scissors are opened and the nerve is cut off as close as possible to the eyeball. As soon as this is done the eye can be pulled out of the orbit (luxated) in front of the lids. Then the remaining structures attached to the eyeball (the internal rectus and the two oblique muscles) are divided as close as can be to the eyeball. With this act the enucleation of the eyeball is complete. A wound cavity is now presented, which is bounded behind by Tenon's capsule, in front by the detached conjunctiva of the eyeball. Through the margin of the latter, which corresponds to the limbus of the conjunctiva, a thread is passed alternately in and out, so that a suture is formed like the string of a tobacco-bag, and when this is drawn tight the conjunctiva is completely closed. Then by the use of a pressure-bandage we take care that the conjunctiva shall be pressed against Tenon's capsule, so that it may become united with it.

In the right eye the operation is performed in the same way, except that the detachment of the conjunctiva is begun at the inside of the cornea, and the internal rectus is the first thing to be divided. This slight difference between the operation upon the right eye and that upon the left is explained by the act that we try always to cut from right to left with the scissors, as this is the more handy way of doing.

Healing takes place after enucleation without suppuration and by primary union. The cavity which remains after the removal of the eyeball is lined by Tenon's capsule, the raw, inner surface of which is presented to our view. Upon it can be recognized the divided ends of the ocular muscles, and at its most posterior part the cross-section of the optic nerve surrounded by some orbital fat. This raw surface is covered by the bulbar conjunctiva, which after being detached from the eyeball hangs down so as to form the anterior wall of the wound-cavity, and is then carried into the latter, so that its posterior, raw surface gets to lie against the anterior, raw surface of Tenon's capsule. The aperture which the conjunctiva has in its center corresponding to the cornea has been already closed by the tobacco-bag suture. Hence, there is no raw spot remaining uncovered.

Enucleation, if performed in an aseptic manner, is an operation perfectly devoid of danger. The hæmorrhage ordinarily is slight, so as to require no other measures for its arrest than the application of a pressure-bandage upon the closed lids. In case the bleeding is more profuse, a tampon of iodoform gauze must be introduced into the orbit itself. Under normal conditions the operation-wound heals within less than a week. Purulent inflammation (phlegmon) of the orbital tissue occurs after enucleation only when the wound has been infected. When enucleation is performed upon an eye in which panophthalmitis is present, purulent meningitis with a fatal issue sometimes sets in after the operation. Panophthalmitis, therefore, is a contra-indication against enucleation (see page 322).

The *prothesis* (*artificial eye*) should not be inserted sooner than fourteen days at earliest after the operation. It consists of a shell of glass, which is made in imitation of the anterior division of the eyeball, and which is retained in place behind the lids. After an enucleation which has healed in the normal way there is found a cavity clothed with conjunctiva, which, behind the upper and lower lid, is converted into a deep furrow corresponding to the fornix conjunctivæ. It is into this furrow that the upper and lower rims of the artificial eye are inserted. The deeper the furrow is the better will it keep the artificial eye in place. For this reason we take care in operating to preserve the bulbar conjunctiva as much as possible. In cases in which we are compelled to remove part of the conjunctiva, the portion which remains may be drawn into the cavity by cicatrization, so that the fornix is made proportionately shallower. In this way it may become impossible for an

artificial eye to be worn. The artificial eye moves conjointly with the other eye, although its excursions are smaller; for the ocular muscles, although detached from the eyeball, still retain their connection with Tenon's capsule. They move the latter in the same direction that the other eye is moving in, and with Tenon's capsule they move both the conjunctiva which lines it and the artificial eye which rests upon the conjunctiva.

167. The *indications* for enucleation are:

1. *Malignant tumors* upon or in the eyeball, provided they can not be removed by a less radical operation with retention of the eyeball. In tumors which develop in the posterior section of the eyeball (gliomata of the optic nerve and sarcomata of the chorioid) there is a possibility that the new growth is in process of transmission backward along the optic nerve. In such cases, therefore, the optic nerve is not divided close to the eye, but as far back as possible. After the enucleation has been performed, the cross-section of the piece of nerve attached to the eyeball is examined. If it should prove to be attacked by the new growth, the portion of the optic nerve which has been left in the orbit must also be sought for and exsected.

2. *Injuries.* Enucleation is performed at once (primary enucleation), when such a considerable injury is present that the eye is lost beyond peradventure. This is the case in extensive laceration of the anterior portion of the eyeball, with evacuation of a part of the contents of the globe. By enucleation in such a case we spare the patient the panophthalmitis that otherwise awaits him, or the tedious and painful process of shrinking of the eye.

If the injury is of such a character that the preservation of the eye, at least as far as its form is concerned, is not altogether out of the question, we try first to save the eye by initiating that form of treatment which is indicated by the nature of the injury. If, nevertheless, inflammation develops, and the vision of the eye is absolutely abolished, the indication then is to perform enucleation (secondary enucleation) in order to prevent sympathetic inflammation of the other eye. Enucleation should also be performed upon those eyes which have been blinded by inflammation in consequence of an unsuccessful cataract-operation.

3. *Irido-cyclitis*, *atrophy of the eyeball*, and *phthisis bulbi* furnish an indication for enucleation whenever sympathetic ophthalmia threatens to occur, or has already broken out. And even a condition of painfulness in the eye which can not be relieved in any other way demands the performance of enucleation. This is upon the supposition that all hope for retaining or restoring a serviceable degree of vision has disappeared.

4. *Glaucoma absolutum*, when it is associated with continual pain, and when other less radical operations have either been already performed without success or are impracticable.

5. *Ectasia of the eyeball.* When the eyeball is very much increased in size either by large staphylomata of the cornea or sclera, or by hydrophthalmus, it torments the patient by giving rise to continual attacks of irritation, by preventing the closure of the lids, and by producing disfigurement. Enucleation is then indicated provided the eyeball can not be diminished in size in any other way (e. g., by a staphyloma-operation).

6. *Hæmorrhage* which comes from an eye that has been operated upon or that has been ruptured, and which can be arrested in no other way.

7. *Cosmetic considerations* sometimes furnish the indication for the removal of a blinded and very disfiguring eye, so as to allow an artificial eye to be worn in its stead.

Many operators use the squint-hook for performing enucleation. The tendons that are to be detached are grasped with this, drawn out, and divided upon the hook. This method is easier, but also more elaborate and more tedious, than the method which Arlt devised of picking up and dividing the tendons with the scissors directly.

It sometimes happens that we have to enucleate an eyeball which itself is not diseased—e. g., in the removal of large tumors from the orbit when the eyeball is so much in the way as to prevent the radical extirpation of the new growth. Again, the eye is sometimes deprived of all its supporting structures by extensive operations in its vicinity, and would thus be left quite denuded. In this case, too, it is better to remove it at the same time that we do the operation, rather than to allow it to be destroyed by panophthalmitis.

The *artificial eye* should be taken from the orbit every night and be well cleaned. In time it loses its luster, and must then be replaced by a new one. It not infrequently happens that the conjunctiva is thrown into a state of catarrhal inflammation by the mechanical irritation which the artificial eye sets up. Then the wearing of the latter must be restricted to a few hours each day, or given up altogether for a while, and the conjunctival catarrh must receive appropriate treatment. But the opposite of this state of things also occurs—namely, that, through wearing an artificial eye, troubles that were formerly present are made to disappear. This is the case when, after an enucleation, the lids sink back and an entropion develops, in consequence of which the cilia, which are directed inward, irritate the conjunctiva. By the insertion of an artificial eye the lids receive support; the entropion disappears, and with it vanishes the condition of irritation in the conjunctiva.

The artificial eye may be worn not only in an empty orbit but also over the eyeball. The only prerequisite is that the eyeball shall be diminished in size, either as a whole through atrophy or phthisis, or at least in its anterior division through applanatio corneæ, or as a consequence of ablation of a staphyloma of the cornea. An artificial eye when resting upon the natural eyeball has a particularly deceptive and natural appearance, and also moves quite perfectly with the eye which lies beneath it; while an artificial eye which rests in an empty orbit always appears a little too small and too deeply seated, and, moreover, does not move as well. Hence, for cosmetic reasons, enucleation should be performed only when it is absolutely required, and in other cases methods of operat-

ing—such as staphyloma-operations—should be preferred which preserve the eyeball, although in a diminished form. Unfortunately, the stump of an eye does not always bear an artificial eye over it. It may become irritated by the latter so as to get inflamed and painful; and, indeed, cases of sympathetic inflammation of the other eye have been actually known to result from the irritation of the stump produced by the artificial eye. In such cases either the artificial eye must be laid aside, or the too painful stump must be enucleated.

Inasmuch as the artificial eye acquires such a cosmetic advantage from being placed upon the shrunken eyeball, the attempt has been made to replace enucleation by an operation which does leave a stump in the orbit. This operation is *exenteratio bulbi*. According to Alfred von Graefe's method, it is performed in the following way: In the first place, the cornea together with an adjacent zone of the sclera is removed by first incising the sclera near the limbus with a knife, and then detaching it by a circular cut with the scissors. Then the contents of the eyeball which has thus been opened are scooped cleanly out with a sharp spoon, so that the inner surface of the sclera lies exposed. Lastly, the opening is closed again by means of sutures passing through the conjunctiva and the cut edges of the sclera.*

In the endeavor to be as conservative as possible, observers have also tried to replace enucleation by the division of the nerves going to the eye. This operation is *optico-ciliary neurotomy* (Boucheron, Schöler). First the conjunctiva over the internal rectus and then the muscle itself are divided. From the wound thus made the scissors are passed backward to the optic nerve, which is divided as far back as possible. It is then possible to rotate the eyeball so far outward that its posterior segment together with the stump of the optic nerve shall appear in the wound. The portion of the optic nerve still attached to the sclera is then removed close to the latter, so that, supposing the nerve was divided well back the first time, a long piece of it is resected. Next, the posterior section of the eyeball as far forward as the equator is freed from all tissues attached to it, in doing which most of the ciliary nerves are divided. Then the eyeball is returned to its place in Tenon's capsule, and fixed there by uniting the divided ends of the internal rectus and the divided conjunctiva with sutures. After the operation is completed a pressure-bandage is applied.

Obviously neither exenteration of the eyeball nor neurotomy can replace enucleation when there are malignant neoplasms present in the eye. On the other hand, they might be substituted for this operation when we are dealing with eyes which are to be removed because of being painful, or on account of a threatening sympathetic inflammation. Neither method of operation, however, has proved to be perfectly reliable. The pain not infrequently returns, and sympathetic ophthalmia, too, has been observed after both methods of operation. Added to this is the fact that these operations are more difficult to perform than enucleation, and require a considerably longer time for healing. They will therefore probably never displace enucleation, although they may sometimes be indicated in special cases.

Exenteration of the orbit is performed as follows: After the patient is anes-

---

* [In what is called *Mule's operation*, a glass bead is inserted into the eyeball after the exenteration of the latter, and then the opening in the sclera is closed by sutures. The bead (or "artificial vitreous") thus remains permanently inclosed in the stump.—D.]

thetized, the external commissure of the lids is split to a point over the external margin of the orbit. By this procedure the lids are made freely movable, and can be turned back, the one up the other down, so as to admit as free access as possible to the orbit. Then the soft parts behind the everted lids are divided with the scalpel down to the bony margin of the orbit. From this as a starting-point the periosteum is detached from the bone all round down to the apex of the orbit. The entire contents of the orbit now form a wedge which lies free in the latter, and is attached only at the optic foramen by means of the optic nerve and the ophthalmic artery. This pedicle is best divided by some blunt instrument, so as to avoid hæmorrhage from the artery. Should the latter bleed in spite of this, it must be cauterized with Pacquelin's thermo-cautery or with the galvano-cautery, since ligation of this artery is impossible for technical reasons. Next, all shreds of tissue still attached to the bone are removed, so that the latter is completely denuded. Then the orbit, after suitable irrigation with a disinfecting fluid, is packed with tampons of iodoform gauze, and a light pressure-bandage is applied over it.

III. Operations for Trichiasis.

168. The number of operative methods proposed for the relief of trichiasis (and distichiasis) is extremely large. Many of the procedures advocated are, however, distinguished only by trifling details from each other, so that it is sufficient to describe at length only some few of the methods which may be regarded as constituting the main types of operation.

Of any good trichiasis operation it must be demanded that it relieve the faulty position of the cilia and prevent a return to this position (a relapse). Circumstances being the same, preference will be given to that method which attains this result with the least amount of disfigurement. The obvious procedure for surgeons first to hit upon consisted in simply removing that part of the lid which bears the cilia (ablation of the zone of hair-follicles). But since the results of this method of operating leave much to be desired, it was so modified that the zone of hair-follicles was not removed, but simply displaced in such a way that the cilia took on the direction desired (transplantation of the zone of hair-follicles). By these methods the trouble is removed, but without its cause—namely, the distortion of the tarsus—being done away with. Hence, still others conceived the idea of curing trichiasis by giving the distorted tarsus its normal shape again (straightening of the tarsus). Upon some one of these principles depend most of the known operations for trichiasis.

1. *Ablation of the Zone of Hair-follicles by Flarer's Method.* During the operation some firm support upon which the cutting can be done must be placed beneath the lid. For this purpose a lamina of horn is employed, which is pushed beneath the lid, the lamina being either in the simple form of Jäger's horn-plate or in the complicated form of Knapp's blepharostat [lid-clamp], in which the lid is kept

pressed against a horn-plate by means of a metal ring.* After inserting the horn-plate an incision is made with the lance-knife (or with a scalpel) in the intermarginal space, and in fact in that gray line which separates the orifices of the Meibomian glands from the roots of the cilia (*i*, Fig. 93). When we make the incision here we get into the loose connective tissue which lies between the tarsus and the muscular fibers of the orbicularis, and which is readily divided. We thus split the lid into two laminæ, the anterior of which contains the skin with the cilia, and the posterior the tarsus with the conjunctiva. This process of cleavage must run along the whole length of the edge of the lid and be carried inward to a point over the roots of the cilia—i. e., to a distance of about three millimetres from the free edge of the lid. When the zone of hair-follicles is thus detached from the tissues beneath it, we now need only separate it from its connection with the skin of the lid. This is done by an incision carried through the skin parallel with the edge of the lid and situated at the limits of the zone of hair-follicles. This latter is then connected with the skin of the lid only at its two extremities. This connection being now divided with the scissors, the zone of hair-follicles (the portion *a*, bounded by the dotted line in Fig. 172 *A*) is detached. A raw surface now remains along the border of the lids, the floor of which is formed by the anterior surface of the denuded tarsus. This wound heals by granulation within a few days.

Ablation of the region of hair-follicles has the advantage of simplicity, and, moreover, when nothing has been left, makes all relapses impossible; but it produces a permanent disfigurement, due to the removal of the cilia, and deprives the eye of the protection which the cilia afford. This is of particular importance in the upper lid, where the cilia are more numerous and are larger. Moreover, the hard cicatrix which is formed at the site of the ablated zone of hair-follicles is often a cause of renewed irritation of the eye. Hence, ablation of the zone of hair-follicles is at present but rarely performed. It is employed upon the lower lid, where the cilia in any case are small and scanty, and particularly in cases of partial trichiasis in which the ablation need be done only over a short extent of surface.

2. *Displacement (Transplantation) of the Zone of Hair-follicles by Jaesche-Arlt's Method.* In the upper lid the operation is performed by beginning with an incision in the intermarginal space, which divides the lid into two laminæ as far as the upper limit of the zone of hair-follicles, just as in the operation for ablation of the latter. In this way the zone of hair-follicles is detached from the underlying tissue and is made movable. In order now to draw this zone up and attach it at a higher point, the skin of the lid is shortened in the vertical direction

* [This has the advantage of preventing bleeding during the operation. The clamp is also used in any operation upon the lids, such as the removal of small tumors, in which deep incisions and much pressure are employed.—D.]

by the excision of a fold. The fold to be exsected is bounded by two incisions. One runs three or four millimetres above the free border of the lid and parallel with it; the other is carried above the first along a curved line, so that at its center it is farthest (six to eight millimetres) from the first incision, but at its extremities coincides with it. In this way an elliptical piece of skin is circumscribed, which then is dissected from the underlying tissues with a pair of scissors, care being taken to preserve the subjacent muscular fibers. If, then, the two lips of the wound are united by a number of sutures, which are applied in a vertical direction (*s*, Fig. 172 *B*), the lower lip of the wound, together with the zone of hair-follicles, is drawn well up, and the cilia are in this way directed straight. At the same time the incision in the intermar-



FIG. 172.—METHODS OF OPERATING FOR TRICHIASIS. REPRESENTED SCHEMATICALLY IN A SERIES OF PERPENDICULAR SECTIONS MADE THROUGH THE UPPER LID. MAGNIFIED 2×1.

A, ablation of the zone of hair-follicles by Flarer's method. *B*, transplantation of the zone of hair-follicles by Jaesche-Arlt's method. *C*, elevation of the zone of hair-follicles by Hotz's method. *D*, straightening of the tarsus by Snellen's method. *E*, transplantation of the zone of hair-follicles by Oettingen's method.

ginal space gapes open and displays at its bottom the raw anterior surface of the tarsus. In order that the zone of hair-follicles may not be drawn down again by the cicatrization of this wound, the piece that has been excised from the skin of the lid is inserted into the wound so as to be implanted there. This piece must be trimmed down so as to fit well into the wound (*h*, Fig. 172 *B*). If care is taken by proper bandaging of the eye to keep the transplanted strip of skin pressed against the raw surface forming the bed of the wound, it almost always becomes well attached to the latter in healing.

In performing this operation the mistake is frequently made of excising too broad a piece of skin from the cutaneous surface of the lid, which thus becomes so much shortened that ectropion or lagophthalmus develops. We should therefore, before the operation, determine the size of the piece to be exsected, by pinching up a fold of skin with the

finger and seeing how large this must be in order to effect its object without shortening too greatly the skin of the lids.

In the lower lid the operation is performed in the same way, except that here, in order not to get ectropion, the piece of skin to be exsected must be made still narrower.

3. *Hotz's Operation.* When this operation is made upon the upper lid, an incision is first carried through the skin of the latter, passing along the upper border of the tarsus from one end of it to the other. Then the lips of the wound are separated, and the bundles of fibers of the orbicularis which are visible at its bottom are exsected. The wound is next closed by stitching its lower lip to the upper border of the tarsus. For this purpose the needle is passed first through the upper lip of the cutaneous wound, then through the upper border of the tarsus, and lastly from within outward through the lower lip of the cutaneous wound (*s*, Fig. 172 *C*). As many of these sutures are applied as necessary. The idea underlying this operation is to raise the zone of hair-follicles, not by shortening the skin of the lids, as in Jaesche-Arlt's method, but by attaching the skin to a fixed point—namely, the upper border of the tarsus. The exsection of the fibers of the orbicularis is done with the intention of diminishing the power of this muscle which tends to force the lid backward. This operation dispenses with the step of detaching the zone of hair-follicles by an incision in the intermarginal space; but it may, if necessary, be combined with such an incision.

In the lower lid the method of operating is the same, but the cutaneous incision, in accordance with the smaller height of the tarsus, runs closer to the free border of the lid.

4. *Straightening of the Tarsus by Snellen's Method.* This object is sought to be obtained by the excision of a prismatic piece from the tarsus. The skin is incised about two millimetres above the border of the lid, and in a direction parallel to the latter along the entire length of the lid (*i*, Fig. 172 *D*). Then the lowermost bundles of fibers of the orbicularis which lie exposed in the wound are excised, so that the tarsus is presented to view. A prismatic piece is now exsected from this latter along its entire length, by making sawing cuts with a knife which is applied obliquely. The next thing to do is to bring the two cut surfaces of the tarsus (*e*, Fig. 172 *D*) into contact. This is accomplished by sutures applied under the form of loops by means of threads armed with needles at both ends. One needle is first passed through the upper border of the tarsus (*a*), and is then carried down in front of the m... in the cartilage and between the tarsus and the skin as far as high... border of the lid, above which it is brought out again. A

* [T... manœuvre is performed with the other needle. The loop then clamp is a... the upper end of the tarsus, while the two extremities of the tumors, in wh... in view above the border of the lid. These ends are then

tied upon a bead (*p*), and are afterward carried up to the forehead, where they are attached with plaster above the eyebrow. In this way the lid is kept drawn up, and coaptation of the cutaneous wound is rendered superfluous, as this then closes of itself.*

Ablation of the zone of hair-follicles is among the oldest of the methods for operating upon trichiasis. At the present time it has been almost entirely displaced by the methods for transplantation of the zone of hair-follicles. Stellwag has attempted to bring it once more into currency, under an improved form which he calls inversion of the zone of hair-follicles. This consists in reattaching to the raw surface of the tarsus the ablated zone of hair-follicles upside down—i. e., in such a way that the border which bears the cilia looks upward, and that which has the raw surface looks downward. The reattachment of the strip of skin, which it is designed to effect, usually takes place, but the cilia fall out of themselves; a result, however, which is really desirable, as otherwise the upward-pointing, transplanted cilia would have a very repulsive appearance. This method therefore amounts to the same thing as the ablation of the zone of hair-follicles, but, as the wound is covered with skin, it produces a smaller cicatrix in the free border of the lid.

The most important step in the way of improving the operations for trichiasis was made by Arlt, who devised the plan of detaching the zone of hair-follicles from the tarsus. In this way one was enabled to do an extensive transplantation without having to fear a necrosis of the zone of hair-follicles, as in the original method of Jaesche, who released the zone of hair-follicles, along with the subjacent tarsus, from end to end, and separated both completely from the underlying tissues. Even Arlt's method, however, is not free from disadvantages. One of these consists in the difficulty of gauging accurately the size of the piece to be exsected; another, in the possibility of a relapse. As regards the first point, no fixed breadth can be assigned for the strip of skin to be removed, because this breadth varies according to the character (i. e., the elasticity or laxity) of the skin of the lids. If too little is exsected, the zone of hair-follicles is not drawn up sufficiently and the trichiasis returns; if too much skin has been removed, we get ectropion or lagophthalmus, which could only be got rid of by subsequent operations. For this reason methods have been devised which are intended to effect the elevation of the zone of hair-follicles without excising any skin. Hotz's operation belongs in this category. A somewhat different method is that of Oettingen. He carries the incision in the intermarginal space to a point above the upper border of the tarsus, so that all the skin which covers the tarsus can be displaced upward. This portion of skin is then, by means of sutures, attached near its free border, which carries the cilia, to the upper border of the tarsus (Fig. 172 *E*). Below the free border of the lid, which has been thus elevated, there remains quite a large wound, formed by the anterior surface of the tarsus. Upon the same principle depend the methods of Kostomyris, De Wecker, and Warlomont.

The relapses which are of frequent occurrence after Arlt's operation, as well as after many other methods, have the following causes: 1. If the trachomatous process has not completely run its course, the shrinking of the conjunctiva and

* The account here given of the method of operating, which differs from the ordinary descriptions of it, I owe to a communication conveyed by letter from Prof. Snellen himself.

of the tarsus continues to progress after the operation, and once more throws the cilia into a faulty position. 2. The shortening of the skin produced by the excision of a strip of it often fails to be permanent, because the skin, especially in old persons, gradually stretches out again. 3. The wound in the intermarginal space, which remains uncovered, heals by granulation and the formation of cicatrices. By the gradual contraction of the cicatricial tissue the free border of the lid may be drawn down again and the position of the cilia be made worse. The first point has its basis in the nature of trachoma, and can not be charged to the account of the method of operating; but the second and third points constitute defects in the operation, which it has been sought to remedy. In order to make the contraction of the skin permanent, the latter has been attached to a fixed point—namely, the convex border of the tarsus (Hotz). The main cause of relapses—i. e., the depression of the zone of the hair-follicles due to the cicatrization of the wound—it has been attempted to get rid of by covering the wound with skin. In Arlt's method this object is attained, as has been described above, by transplanting the excised portion of skin upon the wound (Waldhauer). Van Millingen prefers to cover the wound with mucous membrane which he takes from the lips of the patient, or from the conjunctiva of a rabbit. Since flaps of skin or mucous membrane, when destitute of a pedicle, are exposed to the danger of mortification, and in any case shrink very greatly, others have chosen pediculate skin-flaps for covering the wound. In Spencer Watson's method this flap is formed in the following way: An incision is made in the intermarginal space, and a second one is made parallel to the border of the lids and above the row of cilia, as is done for their ablation (Fig. 173, in the outer half of the upper lid). Then, instead of detaching the strip of skin, thus marked out, at both ends, as in the operation of ablation, it is separated at one extremity only. The zone of hair-follicles is thus transformed into a long, slender flap which is free at one extremity, but at the other is connected with the skin of the lids (*a*, Fig. 173). Then a second flap of skin similar in shape is fashioned by making a second incision about three millimetres above the first and parallel to it, and thus marking out a narrow strip of skin, which is likewise left in connection with the skin of the lid by one extremity only (Fig. 173, *b*). The base of this flap must lie at the outer end of the lid, provided the base of the lower flap, which bears the cilia, is situated at the inner end, and vice versa. Then the two flaps are interchanged, so that the one which carries the cilia gets to lie above, and the one that was above gets to lie below, along the free border of the lid (Fig. 173, a_1 and b_1). The flaps are kept in their place by sutures. Other methods which likewise employ flaps with a pedicle are those of Gayet, Jacobson, and Dianoux. Spencer Watson's operation has the disadvantage that, if performed along the whole length of the lid, the flaps have a very great length in proportion to their slender base, and are hence apt to die. Accordingly, I ordinarily employ this operation only in those cases in which the trichiasis is present simply at one or the other extremity of the row of cilia, and in which, therefore, a short flap is sufficient.



FIG. 173.—SPENCER WATSON'S OPERATION FOR TRICHIASIS.

This is represented as being performed in such a way that the flaps do not extend over the entire length of the lid, but only over one half of it. The outer half of the upper lid shows the flaps in their natural position; the inner half shows the position of the flaps after they have been interchanged.

Each of the methods named has certain advantages and disadvantages. The experienced operator will not employ any one of them exclusively, but will select the method to suit the case in hand, and when necessary will even combine two different methods. Thus Hotz's method may be combined with the excision of a strip of skin, with the detachment of the zone of hair-follicles by an intermarginal incision, or, if the distortion of the tarsus is a very conspicuous feature, by the excision of a wedge from the latter. In cases in which the trichiasis is greatest in the center, Arlt's method is very suitable, since in this method the exsected piece of skin is broadest in the center, and hence it is in this place that the greatest displacement is produced in the zone of hair-follicles. The methods of Hotz and Snellen also exert their greatest effect in the center of the lid. Again, for trichiasis at one end of the row of cilia implantation of a skin-flap with a pedicle—e. g., by Spencer Watson's method—is the most suitable procedure.

IV. Canthoplasty.

169. Canthoplasty (Von Ammon) has for its object the dilatation of the palpebral fissure by the division of the external angle of the eye. The two lids are separated widely with the fingers, so that the external commissure is put upon the stretch, and the blunt-pointed blade of a straight pair of scissors is introduced behind it as far as possible; then, with one snip the skin lying between the blades of the scissors is divided in a horizontal direction; then, upon drawing the lids apart, a rhomboidal wound is exposed to view. The two outer sides of this wound lie in the skin, the two inner sides in the conjunctiva. The inner sides are next stitched to the outer by grasping the conjunctiva at the spot where the two borders of the wound come together, and attaching this point to the external angle of the wound by a suture. Then an additional suture is passed through the upper and the lower portions of the wound respectively.

If the wound in the external angle of the eye were not covered with the conjunctiva thus stitched to it, it would reunite within a short time. Hence, if all that we need is a temporary dilatation of the palpebral fissure, we satisfy ourselves with splitting the external commissure without applying any subsequent suture—provisional canthoplasty. A modification of this latter operation has been devised by Von Stellwag. The incision with the scissors is not made in the prolongation of the palpebral fissure, but from the external angle of the lid obliquely outward and downward. Owing to the retraction of the divided fibers of the orbicularis the wound gapes and forms a triangular slit. This should not be lined with mucous membrane by means of sutures, but, on the contrary, should be allowed to reunite. If reunion does not take place, a notch is left in the border of the lid (artificial coloboma of the lid). This causes disfigurement and epiphora, and may also occasion ectropion, and would therefore have to be removed by means of a new operation (paring the edges and stitching them together).

Stellwag's operation is called oblique blepharotomy or sphincterotomy.

The *indications* for canthoplasty are:

1. *Blepharophimosis* and *ankyloblepharon*. In this case a permanent effect is derived from the operation, and this is therefore made with a conjunctival suture.

2. *Blepharospasm*, especially if it gives rise to spastic entropion. Here provisional canthoplasty is sufficient. The success of the operation in these cases is attributable not only to the lengthening of the palpebral fissure, but also and mainly to the division of the fibers of the orbicularis, in consequence of which the latter suffer a considerable impairment of strength. For this reason Stellwag's oblique blepharotomy is still more effective in relieving blepharospasm, but entails the danger of a coloboma of the lid. If, as is so frequently the case, the spastic entropion is combined with blepharophimosis, the canthoplasty must be combined with a suture.

3. *Acute blennorrhœa*, when the lids are extremely swollen and exert a considerable pressure upon the eye. In this case provisional canthoplasty is sufficient. The same thing is true when the enlargement of the palpebral fissure serves as—

4. A *preliminary step* to enable us to remove through the palpebral fissure an eyeball which is very much increased in size, or an orbital tumor.

V. Tarsorrhaphy.

170. Tarsorrhaphy consists in shortening the palpebral fissure by uniting the edges of the lids; it is accordingly the direct opposite of canthoplasty. The union of the edges of the palpebral fissure may be effected either at the outer or at the inner angle of the eye (tarsorrhaphia lateralis and medialis).

1. *Lateral tarsorrhaphy*. In Von Walther's method this is performed by paring the upper and lower borders of the lids by ablation of the zone of hair-follicles over the space adjoining the external angle of the eye, and then stitching the borders of the lids to each other along the denuded area. As in this way it is only a very narrow raw surface—i. e., the raw edges of the lids—over which union is effected, the wound is apt to tear apart under any considerable amount of strain. Hence I perform the operation in a different way. First, the extent to which it is desired to join the lids together is marked out; then the lower lid is split into its two laminæ by an intermarginal incision of a length equal to that thus indicated. From the inner extremity of the section a short incision is carried downward through the skin, thus converting the anterior lamina of the bisected portion of the lid into a flap (*a*, Fig. 174). The upper and inner borders of this flap are free, while the lower and outer borders are connected with the skin of the lid. Then the upper lid is rendered raw by first making the intermar-

ginal section in the same way as upon the lower lid and then ablating the zone of hair-follicles thus detached, as in Flarer's operation. There is thus produced a raw surface (*b*, Fig. 174), to which it is intended that the skin-flap of the lower lid shall adhere by its raw surface. In order that adhesion of the raw surfaces themselves, and not simply of their edges, shall take place, the suture is applied as follows: Both ends of a thread armed with a needle at each end are carried through the upper lid near its free border, the needles being passed from behind forward. In this way the loop of the thread gets to lie upon the conjunctival side of the lid, while the free extremities come out upon the raw anterior surface. These extremities are then passed through the base of the skin-flap below and are tied upon its anterior aspect over a glass bead. By this suture the base of the flap is kept pressed against the raw surface of the tarsus of the upper lid; then, as an additional precaution, the edges of the skin-flap are accurately united to the edge of the wound in the upper lid by means of a few fine sutures. The adhesion of the lids obtained by this method is firm enough to withstand even a powerful strain.



FIG. 174.—TARSORRHAPHY.
A lateral tarsorrhaphy is represented at the external angle of the eye; a median tarsorrhaphy at the internal angle. On the lower lid is shown the position of the loop of thread in Gaillard's suture.

2. *Median tarsorrhaphy*, as devised by Arlt, is performed by excising with the forceps and scissors a narrow strip of skin from both the lower and the upper lid close to their inner angles. The long and slender wounds thus produced should meet in an acute angle at a point on the inside of the inner commissure (*m*, Fig. 174). They are then united to each other through their entire extent by means of interrupted sutures. If a firmer adhesion is desired, this operation, too, like external tarsorrhaphy, may be made with the formation of a small skin-flap.

Tarsorrhaphy is indicated—

1. In *ectropion*. In this the lower lid is raised by attaching it to the upper. Tarsorrhaphy is most effective in senile and paralytic ectropion, and also in slight cases of cicatricial ectropion. Tarsorrhaphy is very often performed, in conjunction with blepharoplasty, in order to insure the lids remaining in the proper position.

2. In *lagophthalmus*, because the closure of the palpebral fissure is facilitated by shortening the latter. It is more particularly that form of lagophthalmus which develops in Basedow's disease in consequence

of the exophthalmus that furnishes the occasion for the performance of tarsorrhaphy, inasmuch as we have no other means of relieving this condition.

As a rule, lateral tarsorrhaphy is the operation which is done. Median tarsorrhaphy is scarcely ever employed except in paralytic ectropion, and is done then only because in this condition the lower lid generally droops more in its inner than in its outer half.

When the lower lid has been in a condition of ectropion for a pretty long time, it is ordinarily found to have become elongated by the stretching it has undergone. In order to make the lid short again, a procedure by which it is at the same time put upon the stretch and pressed against the eyeball, the lower lid, in the performance of tarsorrhaphy, is pared to a greater extent than is the upper. When the elongation is particularly marked, the lid is shortened by excising a triangular piece at its lateral extremity. The apex of the triangle is directed downward, and its base corresponds to the free border of the lid. The two sides of the triangular notch are united by means of sutures.

The operation of uniting the lids by means of tarsorrhaphy is sometimes done under great tension—e. g., when the attempt is made to bring closer together lids that have become shortened, or when the operation is done in a case of exophthalmus. In the latter event it is the enlarged eyeball that tends to push the lids apart. To diminish the tension, that portion of the palpebral fissure which is to remain open may also be closed by means of sutures, this being done without paring the edges of the lids, so that the union shall be only a provisional one. The sutures are left in until they cut their way through, or until the healing of the wound made by the tarsorrhaphy has become sufficiently firm.

VI. Operations for Entropion.

171. *Spastic entropion* develops only when the skin of the lids is abundant and relaxed (see page 489). If then the skin is put upon the stretch by pinching up a horizontal fold of it in the fingers, the entropion disappears. Upon this observation depend those methods of operating for entropion which produce contraction of the skin of the lid in a vertical direction. Other methods, on the contrary, attempt to cure the entropion by relieving the blepharospasm which causes it. The methods of operating which are most in use are:

1. *Gaillard's Suture.* This operation as modified by Arlt is performed as follows: One needle of a thread which is armed with needles at both ends is entered at the junction of the middle and inner thirds of the lower lid. The point of entry lies close to the border of the lid (*c*, Fig. 175 *A*), the point of exit at a distance below it upon the cheek equal to about the breadth of the thumb (*d*). The second needle is passed in a similar fashion and near the first, so that the loop-end of the thread lies upon the skin near the border of the lid (*c*, Fig. 174), and the two threads run downward beneath the skin of the lids in a parallel direction. A similar loop of thread is applied at the junction of the middle and outer thirds of the lid. If the two ends of each thread are

tied over a small roll of adhesive plaster and drawn tight, a horizontal fold of skin is pinched up upon the lower lid (*a*, Fig. 175 *B*), and thus the entropion is made to disappear. The threads should be left in until the tracks formed by them begin to suppurate, so that after the removal of the threads cicatricial bands may be formed which shall produce the same effect that the threads did. In spite of this, the entropion is apt to set in again subsequently. This operation, accordingly, is only adapted to those cases in which we are dealing with an entropion of presumably short duration, as, for example, that form which develops beneath a bandage.

2. *Excision of a Horizontal Strip of Skin.* A horizontal fold of skin is pinched up between two fingers, its size being so gauged that the entropion shall be relieved by it without, however, an ectropion or a lagophthalmus being produced; then this fold is snipped off with one stroke of the scissors, and the two edges of the wound are next



FIG. 175.—METHODS OF OPERATING UPON ENTROPION. MAGNIFIED 2 × 1.
A, suture in Gaillard-Arlt's method; mode of applying the loop of thread. *B*, the same after the loop has been drawn tight. *C*, suture in Snellen's method.

united by means of some sutures. If the operation is to be effectual, the upper edge of the wound must lie pretty close to the free border of the lid. The result of this operation is ordinarily permanent, although here, too, recurrences of the ectropion sometimes take place through subsequent stretching of the skin. Hence the much more complicated Hotz's operation (see page 722), which fastens the skin of the lids to a fixed point, the attached border of the tarsus, is also employed in entropion.

3. *Canthoplasty*, and also the oblique blepharotomy of Stellwag, since they relieve blepharospasm, may also be employed for the abrogation of spastic entropion. In those cases in which blepharophimosis is present with the entropion, the former condition must be removed permanently by the canthoplasty.

In *cicatricial entropion*, due to shrinking of the conjunctiva and the tarsus, those methods of operating are indicated which are employed for trichiasis, since cicatricial entropion may, as far as its origin is con-

cerned, be regarded as nothing but a trichiasis that has become far advanced.

Instead of Gaillard's suture we may also employ one of Snellen's (not to be confounded with Snellen's suture for ectropion). This was modified by Stellwag in the following way: "One or two stout threads armed with curved needles at both ends are passed through the entire thickness of the lid, starting from the deepest portion of the fold of transition of the conjunctiva (*a*, Fig. 175 *C*), so that they form at the fundus of the conjunctival sac one or two loops four to five millimetres in length and placed parallel to the free border of the lid. The separate needles are next carried back through their points of exit in the external covering of the lid (*b*), then are passed vertically between the latter and the fibro-cartilage to a point just at the external lip of the lid, there (*c*) are brought out again, and the two ends of each thread are drawn as tight as necessary over a roll of adhesive plaster and tied."

VII. Operations for Ectropion.

172. In *spastic ectropion*, which does not yield to reposition and the application of a bandage, *Snellen's suture* gives the best service. Like Gaillard's suture in entropion, it consists of two loops of thread, one of which is situated at the junction of the external and middle thirds, the other at the junction of the middle and inner thirds, and which are passed downward (or in the upper lid upward) beneath the skin of the lid. The point of entry, however, is different. In Snellen's suture this lies at the summit of the ectropionized conjunctiva—that is, under ordinary circumstances close to the posterior margin of the tarsus (*a*, Fig. 176 *A*). From this point the needle is passed down beneath the skin of the lid to a point about at the summit of the lower margin of the orbit, and there is brought out again (*b*). The second needle with the other end of the thread is carried down close to the first and parallel with it. The two extremities of the thread which thus come to view upon the cheek are tied over a roll of adhesive plaster or iodoform gauze and drawn tight until a slight degree of entropion (Fig. 176 *B*) is produced. The same thing is done with the second loop. The mode of action of the operation depends upon the fact that the protruding portion of the conjunctiva, which is caught in the loop, is drawn downward and forward in the direction of the skin. This suture can also be employed in senile ectropion, although in this case it usually has no permanent effect.

Fig. 176.—Snellen's Suture for Ectropion.
A before tightening the loop. *B* after tightening the loop.

Paralytic ectropion indicates the performance of *tarsorrhaphy*. The latter is also frequently performed in senile ectropion, although in the latter Kuhnt's operation gives much better results. This is nothing but a modification of the old method of Antyllus. It depends upon the fact that the lid when ectropionized is elongated, and that, when it has been made stiffer by being shortened, it becomes applied to the eyeball. The shortening is accomplished by cutting out a triangular piece, the base of which must lie at the border of the lid, since here the elongation is most considerable. In order that a coloboma of the lid may not be produced, the excision should not affect the entire thickness of the lid, but only its inner layers—namely, the conjunctiva and tarsus. The piece to be exsected is first marked out by two incisions, which begin at the free border of the lid and are carried backward in a convergent direction through the conjunctiva and tarsus until they intersect at the lower border of the tarsus. The segment inclosed between them is removed by entering the instrument from the intermarginal space and passing it in between the skin and the tarsus, thus detaching completely the wedge-shaped piece of tarsus that has been already circumscribed by the incisions; then the wound upon the inner side of the lid is closed by a suture which is passed along the base of the triangular notch—i. e., close to the free border of the lid—through the conjunctiva and tarsus.

With respect to *cicatricial ectropion*, the least serious cases are those in which not much skin has been lost and the contraction of the lid is caused simply by a few cicatricial bands, especially if these draw the lid in against the bone and attach it to the latter—a condition which so frequently remains after caries of the margin of the orbit. In such cases the cicatricial bands may either be divided subcutaneously or be cut out altogether, according to their situation, and the cutaneous wound be closed again by sutures. The effect of such an operation is made more thorough and also more lasting by a tarsorrhaphy performed at the same time. If, however, much of the skin of the lid has been lost, we will have no success with this simple operation, but must proceed to the performance of *blepharoplasty*, the object of which is to replace the skin that has been lost. In this operation the cicatricial portion of the lid is first divided by an incision parallel to the free border of the lid, and then the more deeply situated cicatricial bands are also cut through until the lid is freely movable and can be brought into its normal position without any strain being put upon it. Those portions of the cicatricial skin which appear to have but little vitality are excised, in doing which, however, the free border of the lid, wherever it has been preserved, is spared as far as possible; then the lid is brought into the proper position and retained there by being united to the other lid. The union of the two lids should be made a permanent one for about the outer third of the palpebral fissure—i. e., should be

combined with paring of the borders of the lids as in the method of tarsorrhaphy—but the inner two thirds of the palpebral fissure are united simply by means of a temporary suture. After the lid has been thus put in place, the incision which was made for the purpose of releasing it gapes widely so as to form quite a large raw surface. As the ectropion would recur when this surface cicatrized, the latter must be covered with skin either by means of pediculate skin-flaps taken from the vicinity of the wound, or by means of pieces of skin which have no pedicle.

For the formation of *flaps with a pedicle* a great number of methods have been proposed, according to the size and shape of the loss of substance. The methods most employed are those of Fricke and Dieffenbach.

Fricke's method is especially adapted for elongated losses of substance, whether upon the upper or the lower lid. To cover these losses of substance a tongue-shaped flap (*L*, Fig. 177) is fashioned, the base of which adjoins one end of the loss of substance. The flap is most commonly taken from the skin of the temple and the cheek, and in size and shape must be made to fit the loss of substance. In doing this it must be borne in mind that the flap shrinks not only immediately after it has been detached, but also subsequently. It must therefore be made about one third larger in all its dimensions than the loss of substance. In order that its nourishment may be satisfactory, its base must be made broad enough, and, moreover, should not be twisted too much in the act of transplanting the flap into the wound. For the same reason the skin should not be dissected off clean, but the subcutaneous fat, together with the vessels running in it, should be taken with the flap. The flap thus dissected off is placed upon the loss of substance, and is attached by sutures to its edges, which have previously been rendered movable by undermining. The raw surface which remains at the spot where the flap has been dissected off can usually be diminished considerably in size by means of sutures; the remaining surface is allowed to heal by granulation. At the base of the flap there is formed by the torsion to which it has been subjected a swelling which is larger in proportion to the amount of twisting that the flap has undergone. This swelling flattens out afterward so as to become

FIG. 177.—BLEPHAROPLASTY.
The method of Fricke is represented on the upper lid; that of Dieffenbach on the lower.

less perceptible; should it, however, cause disfigurement, it may be excised later on.

Dieffenbach's method becomes applicable whenever the loss of substance either has the form of a triangle (the base of which looks toward the border of the lid), or can be readily brought into the triangular form (*s*, Fig. 177). It is better adapted to the lower than to the upper lid. The flap (*l*) is ordinarily taken from the temporal side of the loss of substance—i. e., from the cheek. An incision is made toward the temporal side along the prolongation of the base of the triangle. It should be somewhat longer than the latter, in consideration of the shrinking which the flap will undergo. From the outer extremity of this section (*a*) a second incision is made downward parallel to the outer side of the triangle. In this way a quadrangular flap is circumscribed, the base of which is situated below. This flap is now detached by dissection, and is turned slightly toward the nasal side so as finally to lie upon the loss of substance, to which it is then attached by sutures. The loss of substance which remains at the spot from which the flap was taken is made as small as possible by means of sutures, and the remainder of it is allowed to heal by granulation.

The raw surface which is presented to view after the ectropionized lid has been put into place may also be covered by portions of skin destitute of pedicles—an operation which is called *skin-grafting*. This was first introduced into surgery as a well-established procedure by Reverdin, although isolated experiments had been made with it before. Two different methods are distinguished, according to the thickness of the piece of skin that is grafted. In one method very thin pieces are taken which contain only the most superficial layers of the skin—namely, the epidermis, the rete Malpighii, and the apices of the papillæ (epidermic graft). In the other method portions of skin are used which include the entire thickness of the cutis, and which are transferred to the loss of substance either cut up into small pieces, or under the form of flaps of some size (dermic graft). In dissecting off the skin that is to be transplanted, all subcutaneous fat must be carefully removed from it; and, furthermore, it should be taken from those parts of the body which have a thin skin, such as the lids have. For this purpose the inner side of the upper arm is commonly selected. The skin may also be taken from other persons or from amputated limbs with sound skin. With these pieces of skin, which are trimmed to fit the freshly made raw surface, the latter is carefully covered over in such a way that they are everywhere in intimate contact with the subjacent parts, against which they are then kept applied by means of a light pressure-bandage.

The method of grafting has the advantage over the formation of skin-flaps with a pedicle, that the face is not disfigured by any additional cicatrices. On the other, hand it affords less certainty of success,

since the pieces of skin often become gangrenous. But even when they do become attached they afterward shrink very much, so that the success of the operation is diminished, or is even entirely nullified. The operation of grafting, therefore, is especially adapted to those cases in which we are dealing with only small losses of substance and the operation is performed mainly for cosmetic purposes. It is further indicated in these cases in which the skin surrounding the lids can not be employed for making flaps with pedicles, owing, for example, to its cicatricial character. In the other cases, in which large losses of substance are to be covered, and especially where the object is to relieve a lagophthalmus, the method of pediculate flaps is to be preferred, because, although causing more disturbance of the parts, it nevertheless gives more certainty of success.

VIII. Operations for Ptosis.

173. An operation is indicated both in congenital ptosis and in old cases of acquired ptosis which can not be cured in any other way. A whole series of methods of operating for ptosis has been proposed, a circumstance which proves that no one of them gives perfectly satisfactory results. This can be readily understood, since, in fact, the physiological action of a muscle can not be perfectly replaced by any surgical operation whatever. In the following paragraphs only some of the most approved methods, which may be regarded as constituting type-forms, will be described:

1. *Von Graefe's method* proposes to effect the excision of the fibers of the orbicularis. An incision is made in the skin five millimetres above the border of the lid and parallel to it from one extremity of the lid to the other; then the lips of the wound are separated, and the fibers of the orbicularis which are visible at the bottom of it are quite extensively exsected. If there is much skin present, a strip of this also is excised; then the wound is closed again, and in such a way that the sutures include not only the lips of the cutaneous wound, but those of the wound in the muscle as well, being passed through the bundles of muscular fibers that have been left above and below the wound. The effect of the operation is supposed to be twofold: namely, in the first place, a weakening of the orbicularis, which is the antagonist of the levator; and, in the second place, subcutaneous contraction of the lid due to the excision of a strip of the muscle. On the whole, the effect of the operation is usually slight, for which reason it is adapted for only very light cases of ptosis.

The more recent methods start from the fact that persons with ptosis are able to lift the lid a little by wrinkling the forehead, for by this means the eyebrow is elevated, and thus indirectly the lid is elevated too. It was thought that the elevation of the lid might be rendered greater if the lid was connected directly with the fibers of the

frontalis muscle, a connection which is intended to be secured by the two following methods:

2. *Pagenstecher's suture.* One needle of a thread armed with needles at both ends is entered above the arch of the eyebrows and is carried down below it and beneath the skin of the lid to the free border of the lid, above which it is brought out again. The second needle is passed alongside the first. There is thus a loop of thread lying within the lid, the middle of the loop being situated above the eyebrow and its two ends emerging above the border of the lid. These latter are tied over a roll of adhesive plaster and drawn tight. The threads are not removed until suppuration makes its appearance in the tracks made by the sutures. It is thought that in this way cicatricial bands are formed beneath the skin, which extend from the lid to the surface of the frontalis muscle and connect these two structures together (give the muscle what may be called a tendon for the upper lid).

3. *The operation of Panas* tries to secure the connection between the lid and the frontalis muscle by the formation of a pedicle from the skin of the former, which pedicle is attached to the skin of the forehead and to the surface of the muscle. The appended figure (Fig. 178) shows how the pedicle is cut out of the skin of the lid. The pedicle *s*, which is defined by incisions made about it, is dissected from its bed until it is freely movable; then a horizontal incision *a* is made through the skin directly above the eyebrow. Starting both from this incision and from the wound already made below, the skin of the eyebrow is undermined to such an extent that a bridge of tissue is formed, beneath which the pedicle *s* is slipped so that its upper margin is in contact with the upper lip of the incision, *a*. Its attachment to the latter is effected by means of a loop of thread, the center of which lies on the cutaneous side of the pedicle, while its extremities *b b* are passed through the upper lip of the wound. By drawing the loop tight the pedicle is lifted up and is attached to the upper border of the wound. If necessary, a second loop may be applied, and also some interrupted sutures, to secure exact adaptation of the edges.

FIG. 178.—PANAS'S OPERATION FOR PTOSIS.

Panas's operation has given me the best results of any. Its description as here given varies in some unimportant details from that which Panas himself gives. It may happen that upon drawing up the pedicle ectropion is produced.

In this case an additional loop of thread must be applied on either side, which passes above through the upper margin of the wound, as the other loops do, but below does not take in the skin of the flap but only the deeper parts (fascia tarso-orbitalis). When these additional loops are drawn up, ectropion will not occur. In this operation there is no skin lost. Hence, if it should be apparent that the lid has been shortened too much, all that we need to do is to draw the pedicle less high up—i. e., attach it farther down.

For those cases in which the action of the levator muscle is simply weakened and not entirely destroyed, Eversbusch has proposed a method of operating which consists in an advancement of the tendon of the levator so as to put this muscle under more favorable conditions for working. A cutaneous incision is made about midway between the border of the lid and the eyebrow, and passing in a horizontal direction from one end of the lid to the other. Starting from this incision, the skin and the fibers of the orbicularis are loosened from their attachments, so that they can be pushed to one side, and the upper border of the tarsus together with the levator can be exposed to view. A loop of thread is then passed through the tendon, the two ends of the loop being carried down between the tarsus and the skin of the lids and brought out in the intermarginal space. If these ends are tied there and drawn taut, the tendon of the levator is drawn down by means of the loop which has been passed through it. Three such loops should be applied—one in the middle and one on either side.

APPENDIX.



FIG. 179.—INSTRUMENTS FOR OPENING THE EYE AND KEEPING IT IN PLACE.

a, *b*, *c*, *d*, *e*, various forms of spring specula for holding the eye open in operations (page 666).

f, Desmarre's elevator or lid retractor, for holding the lids apart in examinations of the eye and in operations. (See pages 2, 666.)

g, fixation forceps, for holding the eyeball steady in operations (page 667).

h, Sédillot's double hook for fixing the eyeball, especially in strabismus operations.



FIG. 180.—INSTRUMENTS FOR OPERATIONS UPON THE LIDS.

a, Jäger's horn-plate lid-holder; *b*, Knapp's blepharostat (entropion-forceps, lid-clamp); *c*, Desmarre's entropion-forceps. *a*, *b*, *c* are inserted beneath the lid, thus affording a resisting surface upon which to cut in all operations upon the lids (operations for entropion, ectropion, trichiasis, ptosis, chalazion, etc.). (See pages 484, 719, 720, 728, 730, 734.) *b* and *c*, which have a ring that can be screwed down upon the lid, also act as clamps, holding the lid firmly in place and preventing hæmorrhage during the operation. *d*, epilating forceps (cilium-forceps). (See pages 480, 487.) Other instruments used in lid-operations are ordinary scalpels, bistouries, and dressing-forceps.



FIG. 181.—INSTRUMENTS FOR STRABISMUS AND ENUCLEATION.

a, *b*, *c*, squint-hooks for picking up the tendon and putting it upon the stretch. *b* is Stevens's slender tenotomy-hook, used especially in performing partial tenotomies. *d*, strabismus-forceps, which may be used for the same purpose, and is also employed for taking up the conjunctiva before the incision is made in the latter. *e*, Stevens's tenotomy-scissors, with cutting edges near the end for doing partial tenotomies. For the ordinary strabismus operation, and also for enucleation, any curved, blunt-pointed scissors may be used. Other instruments used are a spring speculum or Desmarre's retractor, for holding the lids open, and a fixation forceps or Sédillot's hooks. (See Fig. 179.) A needle-holder and curved needles are also required for stitching the conjunctiva, and, in the case of advancement, for suturing the tendon. (See pages 710, 712, 714, 717.)



FIG. 182.—INSTRUMENTS FOR LACHRYMAL STRICTURE.

a, Bowman's sounds (page 514). *b*, Bowman's director.
c, Anel's probe. *d*, Theobald's probe.
e, Weber's thick sound for graduated dilatation (page 521).
f, Weber's curved canaliculus-knife for slitting the canaliculus (page 514).
g, Stilling's knife, for division of lachrymal strictures (page 521).
h, Anel's syringe (page 514).



FIG. 183.—INSTRUMENTS FOR REMOVING FOREIGN BODIES.

a, foreign-body needle and spud (page 186).
b, Knapp's foreign-body hook.
c, Bradford's electro-magnet. (See pages 221, 227.)

FIG. 184.—TATTOOING-NEEDLES FOR CORNEAL OPACITIES.

a, single, grooved tattooing-needle; *b*, bundle of tattooing-needles (page 194).



FIG. 185.—INSTRUMENTS FOR IRIDECTOMY AND IRIDOTOMY.



FIG. 186.—INSTRUMENTS FOR PARACENTESIS AND DISCISSION.

a, broad needle for paracentesis. *b*, Bowman's stop-needle.
c, Beer's cataract-needle. *d*, couching-needle. (See page 700).
e, Knapp's knife-needle, for discission of membranous cataract. (See page 690).


a
b
c
d
e
f
g
h
i

j

k

FIG. 188.—OPHTHALMOSCOPES.

a, *b*, and *c* show the back view of three varieties of the ordinary form of ophthalmoscope. This latter consists essentially of two parts, an anterior and upper part, the mirror, and posterior to this a revolving disk bearing the lenses. The mirror may be circular and fixed, as in the examples here presented (see *d*, which shows the mirror of *c*), or quadrangular and slightly movable about a vertical axis (tilting mirror). In either case it contains a central aperture through which the observer looks from behind the mirror, and before which each of the lenses in the rotating disk passes as the latter revolves. The disk is revolved by the pressure of the finger on its milled edge. It consists either of a single piece bearing convex and concave glasses (distinguished by the signs + and —), as in *b*; or of two superimposed disks, as in *c*; or of a disk with a superimposed quadrant (*a*). In the compound instruments (*a* and *c*) any glass in the superimposed disk or quadrant may be brought before the central aperture simultaneously with any glass in the anterior disk, and consequently a great variety of combinations can be made. The disks are usually covered, as shown in *b* and *c*, by a removable metal cap having a perforation corresponding to the aperture in the mirror.


MEYROWITZ BROS
NEW YORK
209
MEYROWITZ BROS
NEW YORK
125
G. TIEMANN-CO
a
b
c
d

FIG. 189.—THE JAVAL-SCHIÖTZ OPHTHALMOMETER.

This represents the latest model of the Javal-Schiötz ophthalmometer, by the aid of which the corneal astigmatism is measured directly. (See page 657.)



FIG. 190.—A PERIMETER.

The perimeter consists essentially of a graduated arc along which the test-object is carried. (See page 22.) This arc is capable of rotation through all meridians, the meridian which it occupies and the position of the test-object on the arc being marked upon the diagram, which, as shown on the left side of the cut, is attached to the instrument. The patient sits with his chin in the chin-rest sliding in the upright, shown on the right-hand side of the cut.

INDEX.

Abducens, course of, 538; nucleus, 538; paralysis of, 552, 558; paralysis of, congenital, 562.

Abduction, 540; how effected, 528; measurement of, 535.

Ablatio retinæ, 413.

Ablation of staphyloma, 202; of zone of hair-follicles, 719.

Ablepharia, 507.

Abrasio corneæ, 193.

Abscess of cornea, see CORNEA, ABSCESS OF; of lids, 470, 504; retrobulbar, 583.

Absolute far-point, 620; hypermetropia, 645; near-point, 620; scotoma, 26; visual acuity, 610.

Accessory lachrymal gland, 508.

Accidents after tenotomy, 713; in cataract-extraction, 696; in discission of soft cataract, 689; in iridectomy, 686; to eye, frequency of, 227.

Accommodation, 610; abrogated by cataract-extraction, 699; amount of, not proportionate to the extent of the region of accommodation, 618; amplitude of, 615, 616, 618; anomalies of, 660; availability of, measured by the region of accommodation, 619; changes of, in age, 622; concealment of hypermetropia by, 642; contraction of pupil associated with, 257; disturbance of its relations with convergence causing insufficiency, 543; little employed by myopes, 630; measurement of, 615, 619; mechanism of, 613; paralysis of, 660; range of, 615, 616, 618; reduced in glaucoma and sympathetic ophthalmia, 663; region of, 615, 616, 619; relation of, to convergence, 543, 620; relative, 619; spasm of, 663; spasm of, macropsia in, 662; spasm of, simulating and producing myopia, 633; tested with reference to central vision, 20; weakness of, after severe diseases, 663.

Accommodation theory of the production of myopia, 638.

Acetate of lead in conjunctivitis, 43; in follicular conjunctivitis, 47.

Acetic acid in vernal catarrh, 97.

Acne, blepharitis ulcerosa regarded as, 480.

Acne rosacea, analogy of chalazion to, 484, 485; conjunctivitis of, 97.

Acquired astigmatism, 653.

Action of ocular muscles, 525; how varying with position of the eye, 534.

Acuity, visual, 606; absolute, 610; relative, 610.

Adaptation of the retina, 28.

Adduction, 540; how effected, 528; how measured, 535; how reduced by tenotomy of the internus, 710.

Adenoma of chorioid, 327; of glands of the lids, 506; of lachrymal gland, 518.

Adhesions between iris and cornea, see SYNECHIA, ANTERIOR; between iris and lens, see SYNECHIA, POSTERIOR; between lids and eyeball, see SYMBLEPHARON.

Adnexa bulbi, operations upon, 705.

Advancement, 707; capsular, 712; of levator palpebræ superioris, 736; of Tenon's capsule, 712.

After-cataract, 699.

After-treatment of eye operations, 670.

Age, changes of accommodation in, 622; changes of myopia in, 636; changes of refraction in, 624.

Air, change of, in conjunctivitis lymphatica, 90; in anterior chamber, 676;

vitiated, effect of, in producing conjunctival catarrh, 45.
Albinism, 330.
Albinos, luminosity of pupils in, 10.
Albuminuric amaurosis, 409; œdema of lids, 115, 474; optic neuritis, 436; retinitis, 404, 409.
Alcoholism producing hemeralopia, 449; producing nuclear paralysis of ocular muscles, 561; producing retrobulbar neuritis, 441.
Alternating strabismus, 564, 569.
Aluminated copper, 46.
Amaurosis, 445; albuminuric, 409; how causing mydriasis, 307; of central origin, 449; partialis fugax, 449; produced by quinine, 408; uræmic, 409.
Amaurotic cat's-eye, 322, 416; luminosity of pupil in, 10.
Amblyopia, 445; alcoholic, 441; congenital, 446; ex anopsia (from disuse), 446, 571; how producing nystagmus, 574; hysterical, 450; nicotinica, 440; of central origin, 449; tobacco-, 440.
Ametropia, 625.
Ammon's scleral protuberance, 228, 230, 231.
Amotio retinæ, 413.
Amplitude of accommodation, 615, 616, 618.
Amyloid degeneration of conjunctiva, 99.
Anæmia causing arterial pulsation in retina, 15; from loss of blood producing optic neuritis, 436; of retina, 408; pernicious, producing retinal hæmorrhages, 406.
Anæsthesia in operations, 666; produced by cocaine, 260, 666.
Anatomy of the chorioid, 245; of the ciliary body, 241, 242; of the conjunctiva, 31; of the cornea, 122; of the iris, 234; of the lachrymal organs, 508; of the lens, 361; of the lids, 459; of the ocular muscles, 524; of the optic nerve, 420; of the orbit, 577; of the retina, 400; of the sclera, 211; of the uvea, 234; of the vitreous, 395.
Anel's probe, 740; syringe, 514, 740.
Aneurisms of the orbit, 592.
Angioma of the conjunctiva, 119; of the lids, 505; of the orbit, 592.
Angioma lipomatodes of the orbit, 595.
Angle a. 57
244; of th
visual, m
Angulus vi
Aniridia, 31
Anisocoria,
Anisometro
Ankyloblep
726.
Annular ab
terior syn
toma, 25;
Anomalies
cornea,
Anomali
modation
Anophthalr
Antagonist
709.
Antagonist
Anterior ch
examinat
669, 676
operation
390, 393;
tive act,
337–340;
dectomy
Anterior c
vessels, 3
detachme
cataract,
228, 230
142.
Anthrax pu
Antisepsis
cessity o
Antiseptics
blennorr
junctivit
of the c
upon the
cornea, 1
Antrum of
Antyllus-K
pion, 731
Aortic insu
in retina
Aphakia a
698.
Apparent i
hyperme
of the ac

Appearance of eye with the ophthalmoscope, 15.
Applanatio corneæ, 143, 190.
Application of the ophthalmoscope, 7.
Aquacapsulitis, 278.
Aqueous humor, 252; character of, in glaucoma, 351.
Arachnoid sheath of optic nerve, 424.
Arch, inferior tarsal, 32; superior tarsal, 32.
Arcus senilis (corneæ), 122, 190, 195; senilis lentis, 379; tarseus inferior, 32; tarseus superior, 32.
Area, optical, 426.
Argyll-Robertson phenomenon, 261, 308, 442.
Argyria, 42.
Argyrosis, 42.
Arlt's method of median tarsorrhaphy, 727; method of performing enucleation, 714; method of performing tenotomy, 707; modification of Gaillard's suture for entropion, 728; ointment, 94; operation for trichiasis, 720, 723; test-types, 609.
Arrangement of vessels of optic nerve, 14.
Arsenic in conjunctivitis lymphatica, 91.
Arteria centralis corporis vitrei, 267.
Arteria hyaloidea, 267.
Arterial pulse in vessels of optic nerve, 15.
Arteries, ciliary, 248; retinal, how distinguished from veins, 8.
Arterio-venous aneurism causing exophthalmus, 594.
Artery, central, 425; central, laceration and compression of, 408; central, of the vitreous, 267; hyaloid, 267, 305, 397.
Artificial coloboma of lid after canthoplasty, 725; eye, 715, 717; leech, 295; pupil, situation of, in cataract-extraction, 684; pupil, situation of, in iridectomy for increase of tension, 683; pupil, situation of, in iridectomy for optical purposes, 682; pupil, vision with, 685; vitreous, 718.
Asepsis in eye-operations, 665; importance of, 672.
Aspergillus glaucus causing abscess and ulcer of cornea, 158.
Aspiration-theory of Weber and Hasner, 511.
Assimilation of visual substances in retina, 455.
Associated antagonist, tenotomy of, 709; movements, 538; reaction of the pupil, 257.
Association centers, 528, 536; of ocular movements, 528.
Asthenic ulcer of cornea, 139.
Asthenopia, accommodative, 646; hysterical, 451; in astigmatism, 655; muscular, 544; nervous, 451.
Astigmatism, 650; acquired, 653; against the rule, 652; asthenopia in, 655; cause of, 653, 654; compound hypermetropic, 653, 655; compound myopic, 653, 655; congenital, 653; corneal, 653, 654, 657; determination of, 653, 655; determination of, by direct method, 18, 657; hypermetropic, 653, 655; irregular, 654; lenticular, 654; mixed, 653, 655; myopic, 653, 655; objective determination of, 18, 657; physiological, 652, 654; produced by dislocation of the lens, 391, 394, 654; regular, 650; simple hypermetropic, 653, 655; simple myopic, 653, 655; treatment of, 654, 656; vision in, 651, 655.
Astringents in conjunctivitis catarrhalis chronica, 46.
Atheroma of lids, 505.
Atheromatous ulcers of the cornea, 153.
Atonia sacci lacrimalis, 513.
Atrophia bulbi, 323.
Atrophic crescent, 316; excavation, 335.
Atrophy of eyeball, 281, 284, 323; enucleation for, 716.
Atrophy of optic nerve, 442; descending, 439, 442; genuine, 442; inflammatory, 443; neuritic, 443; non-inflammatory, 442; primary, 442; retinitic, 443; scotoma in, 25; simple, 442; simple, anatomy of, 445.
Atrophy of retina, 410.
Atropine applied in substance, 258, 294; diminution of mydriatic effect produced by irritation of iris and inflammation of the cornea, 180; employed in anterior synechiæ, 153, 297; employed in convergent strabismus due to hypermetropia, 567; employed in

Blindness, after blepharospasm, 93; blue-yellow, 456; color, 452; day-, see NYCTALOPIA; green, 452, 453; how causing mydriasis, 307; night-, see HEMERALOPIA; red, 452; red-green, 456; snow-, 102; violet, 452.
Blind-spot, Mariotte's, 25.
Bloodletting in diseases of the eye, 318; in iritis, 295; in optic neuritis, 437; in retinitis, 405; in superficial sclerítis, 213.
Blood-vessels, ciliary system of, 248; conjunctival system of, 34; new formation of, in cornea, 132; of chorioid, 245, 248; of conjunctiva, 34; of embryonic eye, 267; of eye, three systems of, 248; of iris, 235, 248; of lids, 32, 466; of optic nerve, 14, 425; of orbit, 578; of retina, 402; of sclera, 212; of uvea, 248.
Blue-stone, Blue-stick. See COPPER SULPHATE.
Blue-yellow blindness, 456.
Blue-yellow visual substance, 455.
Böhm's method of performing tenotomy, 710.
Bonnet's capsule, 578, 714; discovery of the principle of performing enucleation, 714.
Bowman's membrane, 123; method of performing discission, 692; sounds, 514, 740; stop-needle, 743.
Brain-disease as a cause of optic neuritis, 435.
Brawny trachoma, 74.
Bridge-coloboma, 311; coloboma, artificial, 686.
Bridge, herpetic, 87.
Brisseau's discovery of the true seat of cataract, 389.
Buphthalmus, 229, 344.
Burns of the conjunctiva, 100, 102; of the cornea, 188.

Calcareous cataract, 377.
Calomel in cicatrized ulcers of the cornea, 150; in conjunctivitis lymphatica, 90, 93; in parenchymatous keratitis, 177.
Canal, central, of the vitreous, 250, 267, 395; hyaloid, 250, 267, 395; of Cloquet, 250, 267, 395; of Petit, 263; optic, 425; Schlemm's, 244.
Canaliculus, 508; cystoid dilatation of, 519; occlusion of, by streptothrix, 519; slitting of, 514, 519; stricture of, 519.
Canaliculus-knife, 514, 740.
Canalis Cloqueti, 267, 395; hyaloideus, 395; opticus, 425.
Canthal ligaments, 462, 463, 466.
Canthoplasty, 725; for acute blennorrhœa, 53, 726; for blepharospasm, 94, 726; for entropion, 726, 729; provisional, 725.
Canthus externus, 459; internus, 459.
Capillary fistulæ, 522.
Capsular advancement, 712; cataract, pathological anatomy of, 368.
Capsule, anterior of lens, 362; Bonnet's, 578, 714; of lens, 362; of lens, changes in, after removal of lens, 697; of lens, opening of, in cataract-extraction, 692, 694, 703; of Tenon, 525, 578.
Capsule-forceps, 704.
Capsulo-lenticular cataract, 364, 377.
Capsulotome. See CYSTITOME.
Carbolic acid in eye-operations, 665.
Carbon disulphide producing retrobulbar neuritis, 441.
Carcinoma of chorioid, 327; of lachrymal gland, 518; of lids, 506; of orbit, 593.
Carnivora, luminosity of the pupils in, 10.
Carotid, compression and ligation of, for pulsating exophthalmus, 595.
Caruncle, 34; diseases of, 120; sinking in of, after tenotomy, 713.
Cataract, 364; after-, 699; anterior cortical, 372, 374; anterior polar, 368, 372; astigmatism after operation for, 654; Beer's operation for, 701, 744; black, 378, 445; Brisseau's discovery of seat of, 389; calcareous, 377; capsular, pathological anatomy of, 368; capsulo-lenticular, 364, 377; complicated, 383; complicating chorioiditis, 383, 384; complicating corneal suppuration, 383; complicating detachment of the retina, 383; complicating diabetes, 382, 385; complicating general diseases, 382; complicating glaucoma, 343, 383; complicating irido-cyclitis, 282, 383; complicating myopia, 383; complicating retinitis pigmentosa, 383, 384; complicating rickets, 382; congenital, 381, 384; cortical, 372, 374; couching of,

Cataract-prickers, 700.
Cataract-pricking, 700.
Catarrh, atropine-, 263; conjunctival, see CONJUNCTIVITIS CATARRHALIS; follicular, see CONJUNCTIVITIS FOLLICULARIS; of conjunctiva, see CONJUNCTIVITIS CATARRHALIS; of conjunctiva, pustular form, 41; of conjunctiva, vesicular form, 41; vernal, 94.
Catarrhal conjunctivitis, see CONJUNCTIVITIS CATARRHALIS; ulcers of the cornea, 38, 151.
Catarrhus siccus, 44.
Cat's-eye, amaurotic, 322, 416.
Cat's-eye pupil, 687.
Caustics, injuries of the conjunctiva by, 102; injuries of the cornea by, 188.
Cauterization in abscess of the cornea, 157; in fistula of the cornea, 150; in keratectasiæ, 208; in keratoconus, 209; in ulcer of the cornea, 148, 153.
Cavernous sinus, thrombosis of, 470, 584.
Cavernous tumor of the orbit, 592.
Cellulitis of the orbit, 583.
Centering of glasses, importance of, 604.
Centers, cortical, for ocular movements, 536; for associated movements of the eye, 528, 536; for movements of the ocular muscles, 536; visual, 426.
Central artery (of the optic nerve), 425; artery, embolism of, 407; artery, laceration and compression of, 408; artery of the vitreous, 267, 369; canal of the vitreous, 250, 267; chorioiditis, 315; non-irritative ulcer of the cornea, 151; ophthalmoplegia, 560; parenchymatous inflammation of the cornea, 182; scotoma, 25; vein of the optic nerve, 425; vein, thrombosis of, 408; vision, 20.
Chalazion, 483.
Chamber, anterior, 243, 244; anterior, air in, 676; anterior, examination of, 3; anterior, hæmorrhage into, 669, 676; anterior, irrigation of, 704; anterior, luxation of lens into, 390, 393; anterior, shallowness of, in accommodation. 615; anterior, shallowness of, in glaucoma, 337–340; anterior, shallowness of, rendering iridectomy difficult, 686; anterior, sinus of, 244; posterior, 243, 244.
Change of accommodation with age, 622; of air in conjunctivitis lymphatica, 90; of refraction with age, 636.
Chemosis, 50.
Chiasm, 425, 426.
Children, comparative infrequency of corneal ulcers in, 150; operations in, 677, 689; watered-silk reflex in, 15.
Chloral producing retrobulbar neuritis, 441.
Chloroform in eye-operations, 666.
Chloromata of lachrymal gland, 518.
Chlorosis causing arterial pulsation in retina, 15.
Choked disk, 436, 437.
Cholesterin in degenerated lenses, 377, 381; in vitreous, 398.
Chorio-capillaris, 245.
Chorioid, 245; adenoma of, 327; carcinoma of, 327; changes of, in myopia, 316; coloboma of, 328; detachment of, 323; diseases of, 312; functions of, 264; inflammation of, 312; layers of, 245; leuco-sarcoma of, 326; melano-sarcoma of, 324; rupture of, 323; sarcoma of, 324; tuberculosis of, 327; tumors of, 324; vessels of, 16, 245, 248; vessels of, how distinguished from those of retina, 16.
Chorioidal ring, 13.
Chorioiditis, 312; anterior, 316; causing cataract, 383; causing glaucoma, 359; centralis, 315; diffuse, 316; disseminata, 315; disseminata, scotomata in, 25; exudativa, 313; metastatic, 320, 321; non-suppurativa, 313; suppurativa, 319; suppurativa, diagnosis of, 322.
Chorio-retinitis, 316, 409.
Chromidrosis, 472.
Chronic conjunctivitis, etc. See CONJUNCTIVITIS, CHRONIC, etc.
Cicatricial ectropion, 492; ectropion, operations for, 731; entropion, 490; entropion, operations for, 729; pterygium, 108.
Cicatrix, ectatic, of cornea, 140, 143; of operation-wounds, rupture of, 671.
Cicatrization, cystoid, 218, 671.
Cilia, blanching of, in irido-cyclitis, 277.
Ciliary arteries, 248; body, 241; body, changes of, in glaucoma, 352; body, diseases of, 268; body, function of, 264; body, tumors of, 302; injection,

alies of the retina, 411; anomalies of the sclera, 228; anomalies of the superior rectus, 501; anomalies of the vitreous, 397; astigmatism, 653; cataract, 369, 370, 381, 384; dislocation of the lens, 392; opacities of the cornea, 196; ptosis, 499; shortness of the lids, 496; tumors, 116, 591.

Conglobated tuberculosis of the chorioid, 327.

Conjugate deviation, 560, 576; paralysis, 553, 560.

Conjunctiva, 31; amyloid degeneration of, 99: anatomy of, 31; angioma of, 119; blood-vessels of, 34; bulbi, 33; burns of, 102; cicatrices of, following burns and cauterization, 101, 108; cicatrices of, following diphtheritic conjunctivitis, 81; cicatrices of, in trachoma; congenital anomalies of, 116; corneæ, 33; cyst of, 117; dermoid tumor of, 116; diphtheria of, see CONJUNCTIVITIS DIPHTHERITICA; diseases of, 31; divisions of, 31; epithelioma of, 116, 119; examination of, 2; fibroma of, 120; follicles in, 46; fornicis, 31; fornix of, 31; granulations of, in diphtheritic conjunctivitis, 84; granulation tumor of, 118; hyperæmia of, 43; inflammation of, see CONJUNCTIVITIS; injuries of, 100, 101, 103; lepra nodules of, 99; limbus of, 33; lipoma of, 117; lupus of, 98; lymphangioma of, 120; myxoma of, 120; of the eyeball, 33; of the fornix, 31, 33; of the lids, 31; of the region of transition, 31, 33; of the sclera, 33; osteoma of, 120; palpebral, 31; papillary condition of, 36, 73; papillary hypertrophy, 73; papilloma of, 118; pemphigus of, 98; polypi of, 118; producing infection in eye-operations, 665; sarcoma of, 117, 119: scarification of, in acute blennorrhœa, 56; scleræ, 33; syphilitic inflammation of, 98; syphilitic ulcers of, 104; tarsi, 31; tuberculosis of, 103; tumors of, benign, 115, 117–120; tumors of, malignant, 116, 117, 119, 120; ulcers of, 102, 104; xerosis of, 111.

Conjunctival catarrh, see CONJUNCTIVITIS CATARRHALIS; division of the cornea, 125, 126; flap, 667, 694, 695; injection, 34, 133; system of vessels, 36.

Conjunctivitis blennorrhoica acuta, 49; catarrhalis acuta, 37; catarrhalis acuta, diagnosis of, from iritis, 275; catarrhalis chronica, 43; caused by acne rosacea, 97; caused by atropine, 79, 263; caused by bacteria, 41, 49, 82–91; caused by dazzling, 102; caused by diphtheria, 80; caused by eye-strain, 45; caused by foreign bodies, 45; caused by gonorrhœa, 49, 54; caused by hay-fever, 41; caused by herpes iris, 98; caused by infection during birth, 56; caused by inverted cilia, 45; caused by irritant liquids and vapors, 102; caused by lachrymal diseases, 45; caused by lepra, 98; caused by measles, 97; caused by pityriasis, 98; caused by psoriasis, 98; caused by scrofula, 85, 89; caused by syphilis, 98; caused by variola, 97; caused by vitiated air, 45; chronic, 43; crouposa, 47; crouposa, not a diphtheritic process, 83, 84: diphtheritica, 80; diphtheritica, ulcers of cornea in, 151; eczematosa, 91; ex acne rosacea, 97, 151; exanthematica, 91, 97; follicularis, 46; follicularis, produced by atropine, 79, 263; follicularis, relation of, to trachoma, 78; gonorrhoica, 49; granulosa, 73; lymphatica, bacteria in, 91; lymphatica, course and prognosis, 88; lymphatica, diagnosis of, 92; lymphatica, etiology of, 89, 91; lymphatica, identity of, with keratitis phlyctænulosa, 91; lymphatica, pannus in, 87, 92; lymphatica, symptoms of, 85, 93; lymphatica, synonyms of, 91; lymphatica, treatment of, 90, 93, 94; lymphatica, ulcers of cornea in, 151; membranacea, 47; metastatic gonorrhœal, 54; phlyctænulosa, 85, 91; pustulosa, 91; scrofulosa, 85; simplex, 40; trachomatosa, 58; variolous, 97.

Consensual reaction of the pupils, 261.

Constant strabismus, 564.

Contagion, how effected in acute blennorrhœa, 54; contagiosity of acute blennorrhœa, 52, 54; of acute catarrhal conjunctivitis, 41; of trachoma, 67, 71, 73.

Contraction, concentric, of visual field,

24; of pupil, governed by oculomotor nerve, 256.
Contraction-furrows of iris, 238.
Contracture of antagonists in paralysis of the ocular muscles, 551.
Contusion of the eye, 223, 588; producing paralysis of accommodation, 661.
Conus, 316.
Convergence, capacity for, how tested, 545; contraction of pupil associated with, 257.
Convergence-theory of the production of myopia, 639.
Convergent squint, 564, 565, 707.
Conversion of old numbers of glasses into new, 602.
Convex cylindrical lens, 600; lenses for the correction of hypermetropia, 17; lenses, properties of, 598.
Copiopia hysterica, 451.
Copper aluminated in conjunctival catarrh, 46; sulphate in chronic blennorrhœa, 53; sulphate in trachoma, 68; sulphate in vernal catarrh, 97.
Coquille glasses, 600, 601.
Corectopia, 310.
Corelysis, 298.
Cornea, 122; abscess of, characters of, 130, 154, 159; abscess of, etiology, 156; abscess of, glaucomatous, 156; abscess of, paracentesis for, 679; abscess of, prognosis, 156; abscess of, symptoms and course, 154, 155; abscess of, treatment, 157, 160, 679; affections of, in acute blennorrhœa, 51; affections of, in acute catarrhal conjunctivitis, 38; affections of, in chronic catarrhal conjunctivitis, 45; affections of, in conjunctivitis lymphatica, 86, 87; affections of, in glaucoma, 153, 347, 351; affections of, in irido-cyclitis, 283; affections of, in trachoma, 61, 69, 157; anatomy of, 122; annular abscess of, 51; anterior epithelium of, 123; asthenic ulcer of, 139; atheromatous ulcer of, 153; blennorrhœal ulcer of, 151; burns of, 188; catarrhal ulcers of, 38, 151; central non-irritative ulcer of, 151; central parenchymatous infiltration of, 182; changes in, producing hypermetropia, 644; changes in, producing myopia, 629; cleansed ulcer of, 136, 139; cloudiness of, in glaucoma, 347, 351; coated ulcer of, 135, 138; collapse of, 127, 676; congenital anomalies of, 196, 210; conjunctiva of, 33; conjunctival portion of, 125, 126; curvature of, how tested, 126; deposits upon, in cyclitis, 272, 276; diffusion through, 126; diseases of, 122; disturbance of nutrition of, producing ulcers, 145; divisions of, 125, 126; ectasiæ of, 197; ectasiæ of, causing glaucoma, 359; endothelium of, 125; epithelium of, 123, 125; erosions of, 187; erosion of, recurrent, 171, 187; evenness of, how tested, 127; examination of, 2, 126; facet of, 139, 190; fistula of, 144, 149; fistula of, causing glaucoma, 359; fistula of, iridectomy for, 683, 686; fistula of, treatment, 149, 683, 686; flattening of, 143; foreign bodies in, 185; foul ulcer of, 126, 138; glaucomatous œdema of, 347, 351; glaucomatous ulcer of, 153; herpetic ulcer of, 152; infiltrated ulcer of, 126, 138; infiltration of, in conjunctivitis lymphatica, 87; inflammation of, see Keratitis; injuries of, 185; injuries of, by burns and caustics, 188; injuries of, slight, producing abscess, 156; layers of, 123; lymph-system of, 124; marginal ulcer of, 152; method of infection in acute blennorrhœa, 55; nerves of, 125; nutrition of, how effected, 126, 257; œdema of, in glaucoma, 347, 351; opacities of, 189; opacities of, band-shaped, 191; opacities of, cause of disturbance of vision in, 191; opacities of, congenital, 196; opacities of, glasses for, 194; opacities of, inflammatory, 189; opacities of, iridectomy for, 194; opacities of, metamorphoses in, 195; opacities of, non-inflammatory, 190; opacities of, pressure-, 191; opacities of, stenopæic slit for, 194; opacities of, trachomatous, 66; opacities of, treatment, 193; opacities of, varieties, 194, 195; opacities of, zonular, 190, 195; pannous ulcer of, 157; paracentesis of, 678; paracentesis of, how favoring tissue-metamorphosis in the eye, 255; paracentesis of, indications for, 148, 407, 679, 689; perforation of, 140, 148; polish of surface, examination of, 127; posterior epithe-

lium, 125; progressive ulcer of, 126, 138; regressive ulcer of, 126, 139; rodent ulcer of, 152; rupture of, 223; scleral portion of, 125, 126; scraping of, for opacities, 193; scrofulous infiltrates of, 185; sensitiveness of, how tested, 3, 128; serpiginous ulcer of, 138; shape of, 122, 126; size and form of, 122, 126; solutions of continuity in, 186; staphyloma of, 197; staphyloma of, ablation, 202, 203; staphyloma of, consequences, 199; staphyloma of, enucleation for, 203, 717; staphyloma of, excision, 202, 203; staphyloma of, incision, 201, 203; staphyloma of, increase of tension in, 200, 205; staphyloma of, iridectomy for, 203, 683; staphyloma of, morbid anatomy, 204; staphyloma of, treatment, 201, 683, 717; stroma of, 123; structure of, 122; tattooing of, 194; torpid ulcer of, 139; trachomatous ulcer of, 151; transparency of, 128; transplantation of, 193; traumatic ulcer of, 151, 159; traumatism of, see CORNEA, INJURIES OF; tumors of, 210; ulcer of, 138; ulcer of, cicatrization of, 139; ulcer of, clinical signs, 130; ulcer of, course, 138, 139; ulcer of, etiology, 145, 151; ulcer of, nature, 129, 130; ulcer of, perforation in, 140; ulcer of, prognosis, 150; ulcer of, regeneration, 134, 139, 142; ulcer of, sequelæ, 139–141, 143–145; ulcer of, stages, 138, 139; ulcer of, symptoms, 138, 139; ulcer of, treatment, 146, 150, 153, 154; ulcer of, varieties, 45, 61, 86, 126, 138, 139, 151–153, 157, 159; uveal portion of, 125, 126; vascularization of, 132; vesicles of, see KERATITIS WITH THE FORMATION OF VESICLES.

Corneal astigmatism, 653, 654, 657; flap-extraction, 694; incisions, 667; reflex, examination of, 3.

Corneitis, (see KERATITIS); scrofulosa, 180.

Corona ciliaris, 241.

Corpus vitreum, 395.

Corpuscles of the cornea, 124.

Correction of astigmatism, 654, 656; of hypermetropia by a convex lens, 17; of insufficiency, 544, 708; of myopia by a concave lens, 17; of paralytic strabismus, 555, 709; of presbyopia, 623; of squint, 567, 707.

Corrosive sublimate in diseases of the eye, 48, 53, 58; in eye-operations, 665.

Cortex of lens, 361.

Cortical cataract, 372, 374; centers for the ocular movements, 536; paralyses of the ocular muscles, 553, 560.

Coryza producing blennorrhœa of the lachrymal sac, 512.

Cosmetic enucleation, 717.

Couching, 700.

Couching-needle, 743.

Counter-puncture and puncture, situation of, in cataract-extraction, 693, 694, 702.

Crab's eyes inserted into the eye, 101.

Credé's method of prophylaxis of blennorrhœa neonatorum, 57.

Crescent, atrophic, 316; below the papilla, 318.

Crossed diplopia, 530.

Croupous conjunctivitis, 47.

Crusta lactea, 469.

Cryptophthalmus, 507.

Crypts of the iris, 235, 237.

Crystalline body, crystalline lens. See LENS, CRYSTALLINE.

Crystalline swelling of Soemering, 698.

Curvature of the cornea, how tested, 126.

Curved incisions, 667; incisions in cataract-operations, 703.

Cutaneous diseases accompanied by conjunctivitis, 97, 98; diseases, classification of blepharitis as, 480; diseases of lids, 468, 471, 472; horns on lids, 505.

Cyclitic shell, 281.

Cyclitis, 272 (see also IRITIS and IRIDOCYCLITIS); diagnosis from iritis, 274; simple, 275; symptoms of, 272.

Cycloplegia. See CILIARY MUSCLE, PARALYSIS OF.

Cylindrical lens, 600.

Cylindromata of lachrymal gland, 518; of orbit, 595.

Cysts, dermoid, of conjunctiva, 117; of iris, 302, 303; of lids, 505; of orbit, 591, 593.

Cystic cataract, 380.

Cysticercus in anterior chamber, 304; in conjunctiva, 118; in vitreous, 397, 399; operations for, 415, 680.

Cystitome, 703, 744.
Cystoid cicatrization, 218, 671.

Dacryoadenitis, 518.
Dacryocystitis, 517, 521; blennorrhoica, 519; catarrhalis, 519; phlegmonosa, 519.
Dacryops, 518.
Daltonism, 452.
Darkening of room not necessary after operations, 676.
Daviel's discovery of the method of cataract-extraction, 701; scoop, 484, 674, 684, 692, 694, 744.
Dazzling, cause of, in opacities of the cornea, 196; producing conjunctivitis, 102; producing retinitis, 410.
Decussation of the optic nerve, 426, 429.
Deep forms of keratitis, 172; keratitis in irido-cyclitis, 184; scrofulous infiltrates of the cornea, 185.
Degeneration, glaucomatous, 340, 342; of cataractous lenses, 377; of corneal opacities, 195; pigmentary, of retina, 410.
Delirium after eye-operations, 677.
Deposits on cornea, 272, 276, 277.
Depressio cataractæ, 700.
Depression of cataract, 700; of eye, how effected, 528.
Dermic graft for ectropion, 733.
Dermoid cysts of lids, 505; tumors of conjunctiva and cornea, 116, 210.
Descemetitis, 278.
Descemetocele, 140.
Descemet's membrane, 125.
Descending atrophy of the optic nerve, 439, 442; neuritis, 436, 437.
Desmarre's elevators (or lid-retractors), 2, 666, 737; entropion-forceps, 738.
Detachment of the chorioid, 323; of the retina, 413; of the retina, sclerotomy in, 680; of the retina, scotoma in, 25.
Determination of astigmatism, 18, 655; of field of vision, 21; of hypermetropia, 641; of insufficiency, 546; of myopia, 626; of presbyopia, 624; of refraction, 16, 626, 641, 655.
Development of the eye, 264.
Deviation, conjugate, 560, 576; of eye behind a screen, 542; of squinting eye, measurement of, 563, 572; primary and secondary, in concomitant squint, 563; primary and secondary, in paralytic squint, 548.
De Wecker's capsular advancement, 712; method of cataract-extraction, 694; method of performing iridotomy, 687; scissors-forceps, 687, 742.
Diabetic cataract, 382, 385; iritis, 287; paralysis of the accommodation, 664; retinitis, 404; retrobulbar neuritis, 441.
Diachylon-ointment in eczema of the lids, 470.
Diagnostic table of the paralyses of the ocular muscles, 555.
Diaphoretics in detachment of the retina, 414; in iritis, 295; in opacities of the vitreous, 396; in optic neuritis, 437; in retinitis, 405, 412; in superficial scleritis, 213.
Diaphragm, action of iris as a, 256.
Diathesis, scrofulous, agency in the production of conjunctivitis lymphatica, 89.
Dieffenbach's blepharoplasty, 732; method of tenotomy, 710.
Differentiation, minimum of, 28.
Diffuse chorioiditis, 316; trachoma, 74.
Diffusion circles, 610.
Dilaceratio cataractæ, 690.
Dilaceration, 690.
Dilatation of cavities adjoining orbit, 595; of pupil, governed by sympathetic, 256; of lachrymal strictures, 514, 520.
Dilator pupillæ, 237, 239.
Dioptre, 599, 602.
Diphtheria, confluent, 81; *en plaques*, 81; of the conjunctiva, 80; partial, 81.
Diphtheritic paralysis of the accommodation, 660, 663; paralysis of the ocular muscles, 554.
Diplopia, binocular, 530; character of, in paralytic squint, 550, 558; crossed, 530; developing after tenotomy, 571; heteronymous, 530; homonymous, 530; in strabismus, 564; monocular, 532, 541; tabular view of, in paralysis, 558; vertical, 531; with difference of level, 531; with obliquity, 531.
Direct method of examination with the ophthalmoscope, 6; vision, 20.

Disassimilation of visual substances in retina, 455.
Discissio cataractæ, 688.
Discission, Bowman's method of, 692; of membranous cataract, 690; of soft cataract, 688, 691.
Discission-needle, 688, 743; employed for capsulotomy, 703; employed in simple linear extraction, 692.
Disease, Basedow's, 589, 590; Graves's, 590.
Diseases of the chorioid, 312; of the ciliary body, 268; of the conjunctiva, 31; of the cornea, 122; of the iris, 268; of the lachrymal passages, 508; of the lens, 361; of the lids, 459; of the ocular muscles, 497, 524; of the optic nerve, 420; of the orbit, 577; of the retina, 400; of the sclera, 211; of the uvea, 234; of the vitreous, 395.
Dislocation of the eyeball, 579, 586; of the lens, 389; of the lens in cataract-extraction, 697.
Dispersing lens, 598.
Displacement of cataract, 700; of the zone of hair-follicles, 720; parallactic, 11.
Disseminated chorioiditis, 315; sclerosis producing optic-nerve atrophy, 442; tuberculosis of the chorioid, 327.
Dissemination of trachoma, 72.
Distichiasis, 487, 488; operations for, 719.
Disturbances of motility of the eye, 524.
Divergent squint, 564, 566; squint, operation for, 708.
Division of strictures of the nasal duct, 521.
Donders's schematic eye, 606; theory of glaucoma, 350; work in refraction, 597.
Double images, in ocular paralysis, table of, 558; pupil, produced in iridectomy, 686; pupil, vision with, 541.
Dressing in eye-operations, 666, 676.
Dropsy of lachrymal sac, 513; of maxillary and frontal sinuses, 596.
Duboisine, 263.
Duct, lachrymal, 509: nasal, 509.
Ductus lacrimalis, 509.
Dural sheath of optic nerve, 423.
Dynamic squint, 543.
Dyslexia, 451.
Écarteurs, 666.
Ecchymoma subconjunctivale, 114.
Ecchymoses of conjunctiva, 114; of lids, 502, 504.
Ectasiæ, lymphatic, 115; of cornea, 197; of sclera, 227.
Ectatic cicatrix of cornea, 140, 143.
Ectogenous infection in abscess of cornea, 150; in suppurative chorioiditis, 320.
Ectopia lentis, 392; pupillæ, 310.
Ectropion, 490; cicatriceum, 492; cicatricial, 492, 731; how developed in trachoma, 65; in conjunctivitis catarrhalis chronica, 44; luxurians, 491; operations for, 730; paralytic, 492, 731; paralyticum, 492; sarcomatosum, 75, 491; senile, 492, 730, 731; spastic, 491; tarsorrhaphy for, 727.
Effect of squint-operation, how gauged, 705; of tenotomy, how diminished, 712; of tenotomy, how increased, 711.
Efflorescences of conjunctivitis lymphatica, 85, 86.
Egyptian ophthalmia, 67, 71.
Electric light producing conjunctivitis, 102; producing retinitis, 410.
Electricity in essential blepharospasm, 501; in optic-nerve atrophy, 443; in paralysis of the ocular muscles, 555; in paralysis of the orbicularis, 492; in retinitis pigmentosa, 412.
Electrolysis in trichiasis, 487; in tumors of the orbit, 529; in ulcers of the cornea, 154.
Electromagnet for removing foreign bodies, 221, 227, 741.
Elephantiasis of lids, 472.
Elevation of eye, how effected, 528.
Elevators, 666; Desmarre's, 2, 666, 737.
Embolism of central artery, 406.
Embryology of eye, 234, 264.
Emmetropia, 605; character of ciliary muscle in, 636.
Emphysema of lids in fracture, 503; of orbital tissues, 587; subconjunctival, 115.
Empyema of the frontal and maxillary sinuses, 596.
Encanthis benigna, 121; maligna, 121.
Encephalocele of orbit, 593.
Enchondroma of lids, 506.
Endogenous infection in abscess of cor-

nea, 157; in suppurative chorioiditis, 320.
Endothelioma of orbit, 595.
Endothelium of cornea, 125; of lymph-passages of the eye, 252.
Engorgement neuritis, 437.
Enophthalmus, 581; traumaticus, 581.
Entropion, 488; canthoplasty for, 726, 729; cicatriceum, 490; cicatricial, 490, 729; how developed in trachoma, 65; operations for, 726, 728, 729; organicum, 489; spastic, 488, 728; spasticum, 488.
Entropion-forceps, 738.
Enucleation, 713, 716; anæsthesia in, 666; dangerous in panophthalmitis, 322; indications for, 171, 221, 222, 296, 303, 321, 323, 326, 328, 356, 360, 393, 417, 595, 716; instruments for, 739; method of performing in case of malignant growths, 716; not an absolute preventive of sympathetic ophthalmia, 298; primary, 716; secondary, 716.
Epicanthus, 507.
Epidermic graft for ectropion, 733.
Epilating-forceps, 480, 738.
Epilation in blepharitis ulcerosa, 480, 481; in trichiasis, 487.
Epiphora, 511, 522.
Episcleral tissue, 33, 212.
Episcleritis, 212.
Epithelioma of conjunctiva, 116, 119; of lids, 506.
Epithelium, anterior, of cornea, 123; pigment-, 247; posterior of cornea, 125.
Equator of lens, 361.
Equatorial staphyloma of sclera, 228, 230.
Equilibrating operation, 710.
Equilibrium of ocular muscles, 542; test for insufficiency, 546.
Erect image, examination with, 6.
Erosions of cornea, 171, 187.
Errors of refraction and accommodation, 597.
Erysipelas of lids, 468, 473.
Erythropsia, 704.
Eserine, action of, 259 (see also Miotics); in anterior synechiæ, 297; in fistula of cornea, 149; in glaucoma, 342, 356; in paralysis of accommodation, 661; in ulcer of cornea, 153.
Esophoria, 543, 709.
Essential blepharospasm, 498, 500; phthisis, 360.
Ether in eye-operations, 666.
Eversbusch's operation for ptosis, 736.
Eversion of border of lid, 478, 490; of lids, necessity of, in examining eye, 2; of puncta, 478, 519.
Evisceration of eye, 322, 718.
Exacerbation, evening, in conjunctivitis catarrhalis, 38; morning, in conjunctivitis lymphatica, 88.
Examination, general, of patient, 1; objective, of eyes, 1; of anterior chamber, 3; of conjunctiva, 2; of cornea, 2, 126; of corneal reflex, 2; of eyeball, 1; of field of vision, 21; of iris, 3; of lens, 3, 375; of lids, 1; of malingerers, 29; of refracting media, 11; of refraction, 16, 626, 641, 655; of sensitiveness of eye, 3; of tension, 4, 254; with erect image, 6, 16; with inverted image, 7, 19; with ophthalmoscope, 4.
Exanthematous conjunctivitis, 97.
Excavation, 13; atrophic, 335; glaucomatous, 332, 334; partial, 335; physiological, 13, 334; total, 13, 335.
Excision of prolapsed iris, 149, 669; of staphyloma of cornea, 202, 203.
Excursion-range of eye in squint, 573.
Excursions of eyeball, how measured, 535.
Exenteratio bulbi, 718; orbitæ, 714, 718.
Exenteration of eyeball, 322, 718; of orbit, 714, 718.
Exertion avoided after operations, 676, 676.
Exophoria, 543, 709.
Exophthalmometer, 581.
Exophthalmus, 579; after tenotomy, 713; character of, in tumors of optic nerve, 444; due to dilatation of frontal and maxillary sinuses, 595; due to emphysema, 587; due to oculomotor paralysis, 552; pulsating, 594.
Exostosis eburnea, 595.
Experiment, Hering's, 539; Scheiner's, 541.
Exposure to air, effect of, in producing conjunctivitis, 45.
Extent of field of vision, 23.
External canthal ligament, 463, 466; canthus, 459; commissure, 459; operation-wound, 672; rectus, see Recti, External.

Externi, insufficiency of, 543.
Extirpatio bulbi, 714.
Extirpation of eyeball, 714; of lachrymal sac, 516.
Extractio cataractæ, 692.
Extraction of cataract, see CATARACT-EXTRACTION; of dislocated lens, 393.
Extravasation of blood into orbit, 586; of blood, subconjunctival, 113.
Extrinsic muscles of eye, 524.
Exudate, chorioidal, distinguished from atrophic spots, 315; gelatinous, in anterior chamber, 276; into vitreous, in cyclitis, 274; lenticular, in anterior chamber, 276; spongy, in anterior chamber, 276.
Eye, appearance of, after cataract-extraction, 697; artificial, 715, 717; development of, 264; healthy, enucleation of, when required, 717; hygiene of, in conjunctivitis, 40; hygiene of, in iritis, 295; hygiene of, in myopia, 634, 638; injuries of, summarized, 588; lymph-passages of, 250; nutrition of, 252; objective examination of, 1; optical properties of, 605; position of, in orbit, 579; reduced, 605; refraction of, 605; schematic, 605.
Eyeball, atrophy of, 281, 284, 716; axes of, 526; conjunctiva of, 33; contusions of, 223, 588; dislocation of, 579, 586; ectasia of, see SCLERA, STAPHYLOMA OF, and CORNEA, STAPHYLOMA OF; elongation of, in myopia, 631, 635; enucleation of, 713; evisceration of, 322, 718; examination of, 1; exenteration of, 322, 718; extirpation of, 714; foreign bodies in, 219, 225–227; general rules for operation upon, 666; hæmorrhage from, 670, 717; injuries of, 216, 223, 588, 716; luxation of, 579, 586; moistening of, effected by various agencies, 510; operations upon, 678; phthisis of, 320, 323; rupture of, 223; shape of, in hypermetropia, 646; shape of, in myopia, 631; tumors of, causing glaucoma, 359; tumors of, necessitating enucleation, 716.
Eye-stones, inserted into the eye, 101.
Eye-water. See COLLYRIUM.

Facet of cornea, 139, 190.
Facultative hypermetropia, 644.
Falling bodies. Hering's test with, 539.
False image, 532; orientation, in paralytic squint, 549.
Far-point, 615; determination of, 619; in hypermetropia, 641, 648; recession of, in old age, 624; virtual, in hypermetropia, 641.
Far-sight, 640.
Fascia of ocular muscles, 533; of orbit, 578; of Tenon, 525; tarso-orbitalis, 578.
Fascicular keratitis, 86, 87; paralyses of the ocular muscles, 553, 561.
Fasciculus, vascular, 86.
Fibroma of the conjunctiva, 120; of lids, 506.
Fibroma molluscum of lids, 505.
Field of fixation, 536; of vision, determination of, 21, 682, 684; of vision, extent of, 23, 27; of vision for colors, 27; of vision in detachment of the retina, 413; of vision in glaucoma, 25, 334; of vision in retinitis pigmentosa, 410; of vision, necessity of determining in opacities of refracting media, 682, 684; of vision, pathological alterations of, 24 (see also SCOTOMA and HEMIOPIA); of vision, projection of, 22.
Filamentous keratitis, 171.
Filaria oculi humani, 399.
Filtration-œdema, 115.
Fingers as a test for vision, 609.
Fissure, fœtal ocular, 266.
Fistula, capillary, 522; lachrymal, 517, 522; of cornea, 144, 149, 583, 586.
Fixation, field of, 536.
Fixation-forceps, 667, 737.
Fixed corpuscles of the cornea, 124; scotomata, 26.
Flap, conjunctival, 667, 694, 695.
Flap-extraction of cataract, 693.
Flap-incisions, 667.
Flap-operation for cicatricial ectropion, 732; for trichiasis, 724.
Flarer's operation for trichiasis, 719.
Fluid cataract, 376.
Focal distance, principal, 599, 603; illumination, 2.
Focus, principal, 599; virtual, 599.
Fœtal ocular fissure, 266.
Fold, semilunar, 34. See PLICA SEMILUNARIS.
Follicles in the conjunctiva, 46.

Follicular catarrh, 46.
Forceps, fixation, 667.
Foreign bodies in the cornea, 185; in the eye, 219, 225–227; in the vitreous, 397; sclerotomy for, 680.
Foreign-body hook, 741; needle, 186, 741.
Fornix conjunctivæ, 31.
Förster's operation for ripening cataract, 684; perimeter, 22; photometer, 28.
Fossa patellaris, 395; sacci lacrimalis, 508.
Foul ulcer of cornea, 130.
Fourth nerve, course and nucleus of, 537; paralysis of, 552, 558.
Fovea centralis, 15, 400–403.
Fracture of base of skull, ecchymosis of lids in, 504; of bones of orbit, 587.
Franklin glasses, 604.
Fricke's blepharoplasty, 732.
Frontal axis of eye, 526; sinus, dilatation of, 595.
Fuchs's method of tarsorrhaphy, 726.
Fulminating glaucoma, 340.
Functional causes of insufficiency, 543; testing, 20.
Fundus oculi, appearance of, with ophthalmoscope, 8, 12, 15; changes of, in myopia, 632, 636; measurement of depressions and projections of, 18; tessellated, 16, 315.
Fungi, various species causing abscess and ulcer of cornea, 158.
Funnel, muscular, 524; vascular, 8.
Fusion of double images, 540.

Gaillard's suture for entropion, 728.
Galvano-cautery in conjunctivitis lymphatica, 90; in corneal ulcers, 148, 153; in exenteration of orbit, 719; in vascular tumors of lids, 505.
Gaultheria oil in rheumatic iritis, 296.
Gelatinous exudate into anterior chamber, 276.
Gelsemine, 263.
Genuine atrophy of optic nerve, 442.
Germans predisposed to myopia, 638.
Gerontoxon (corneæ), 122; lentis, 379.
Glands, Henle's, 36; Krause's, 31; lachrymal, 508; Meibomian, 465; mucous, of Waldeyer, 31, 465, 510; of Moll, 463; of Zeiss, 43.
Glandula lacrimalis, 508.
Glasses, 298 (see also Lens); bifocal, 604; centering of, important, 604; cylindrical, 600; for astigmatism, 601, 655; for correction of vision in dislocation of lens, 394; for hypermetropia, how prescribed, 647; for myopes, rules governing their prescription, 633; for opacities of the cornea, 194; for strabismus, 567; Franklin, 604; hyperbolic, in keratoconus, 210; periscopic, 600; prescriptions for, how written, 656; prismatic, 601; protective, 54, 600, 601; spherical, 600; stenopæic, 601; strength of, how determined, 603; strength of, how varying with distance from eye, 604; theory of, 598.
Glaucoma, 332; absolutum, 340; absolutum, enucleation for, 716; acute, 337; anatomy of, 351; attack of, 338; atropine in, baneful action of, 264, 341; cataract in, 343, 383; cause of increase of tension in, 349; changes of ciliary body in, 352; changes of cornea in, 153, 347, 351; changes of iris in, 347, 351; changes of lens in, 343, 352, 383; changes of optic nerve in, 332, 334, 352; changes of uvea in, 351; character of aqueous in, 351; ciliary body in, 352; cornea, cloudiness of, in, 347, 351; cornea, ulcer and abscess of, in, 153; cause of, 339; diagnosis of, 334, 335; eserine in, 264, 341, 342, 356; etiology of, 338, 349; evolutum, 338; excavation of optic nerve in, 332, 334; field of vision in, 25, 334; frequency of, 334; fulminans, 340; general considerations, 332; hæmorrhage after iridectomy in, 357; hæmorrhagic, 359, 679; hæmorrhagicum, 359; history of our knowledge concerning, 334; importance of diagnosis of, 334; increase of tension in, cause of, 349; inflammatorium, 337; inflammatorium acutum, 337; inflammatorium chronicum, 340; inflammatory, 337, 340; inflammatory, its relations to glaucoma simplex, 345; iridectomy in, 353, 355, 358, 683; iridectomy in, difficulties of, 353, 357, 686; iris changes of, in, 347, 351; lens in, 352; malignum, 355; medicinal treatment of, 356; miotics in, 264, 341, 342, 356; mydriatics in, 264, 341, 357; œdema of cornea and iris in, 347; oph-

thalmoscopic appearances in, 335, 343; pain in, 342, 347; pilocarpine in, 264, 356; pathological anatomy of, 351; posterior sclerotomy in, 680; primary, 337; prodromal stage of, 337; pulsation of retinal vessels in, 15; relations of, to hypermetropia and myopia, 636; sclerotomy in, 356, 679; scotoma in, 25; secondary, 358; simplex, 343; simplex, efficacy of iridectomy in, 355, 358; simplex, its relations to inflammatory glaucoma, 345; simplex, sclerotomy in, 679; stages of, 337; symptoms of, 337, 341, 344; theories of, 346; treatment of, 353, 356; visual acuity in, 333.
Glaucomatous attack, 338; cataract, 343; degeneration, 340, 342; excavation, 332, 335.
Glioma retinæ, 416.
Gonococci producing acute blennorrhœa, 49.
Gonorrhœal conjunctivitis, see BLENNORRHŒA ACUTA ADULTORUM; iritis, 287; ophthalmia, see BLENNORRHŒA ACUTA ADULTORUM.
Graft, dermic, for ectropion, 733; epidermic, for ectropion, 733.
Granular conjunctivitis, see TRACHOMA; form of trachoma, 60, 73; lids, see TRACHOMA.
Granulations of conjunctiva after diphtheritic conjunctivitis, 84; of conjunctiva occurring in various diseases, 79; of conjunctiva, ordinary (= papillary form of trachoma), 73; trachomatous, 73.
Granulation-tumor of conjunctiva, 118.
Granuloma of iris, 305, 306.
Graves's disease, 590.
Green-blindness, 452.
Green cataract, 339.
Groping test, 549.

Hæmophthalmus, 217, 222.
Hæmorrhage into anterior chamber, 222, 669, 676; into orbit, 586, 588; into retina, 405, 406; into vitreous, 222, 398; intra-ocular, enucleation for, 717; intra-ocular, from perforation of cornea, 144; intra-ocular in glaucoma, 357.
Hæmorrhagic glaucoma, 259, 679; retinitis, 405.
Hand used for testing field of vision, 21.
Hard cataract, 377.
Hasner's valve, 511.
Hay-fever, 41.
Head, oblique position of, in concomitant squint, 573; oblique position of, in paralytic squint, 551; of optic nerve, 14, 422.
Healing after operations, 670; irregular, 670.
Helmholtz's discovery of the cause of the darkness of the pupil, 10; discovery of oblique illumination, 2; discovery of the ophthalmoscope, 4; ophthalmometer, 657; theory of color-perception, 452.
Hemeralopia, 447; in cataract, 365; in retinitis pigmentosa, 410.
Hemianopia, 428.
Hemiopia, 428, 431.
Hemiopic pupillary reaction, 433.
Henle's glands, 36.
Hering's experiment with falling bodies, 539; theory of color-perception, 455.
Hernia cerebri, 593; of iris, see IRIS, PROLAPSE OF.
Herpes conjunctivæ, 73, 91; corneæ, 171; corneæ febrilis, 152, 169, 171; corneæ of Stellwag, 171; corneæ zoster, 152, 169; febrilis corneæ, 152, 169, 171; zoster corneæ, 152, 169; zoster of lids, 468, 471; zoster ophthalmicus, 169, 468.
Herpetic bridge, 87.
Heteronymous diplopia, 530.
Heurteloup's artificial leech, 205.
Himly's operation for symblepharon, 111.
Hippus, 308.
Histology. See MICROSCOPIC ANATOMY.
History of cataract-operations, 699; of our knowledge about cataract, 388; of our knowledge about glaucoma, 334; of our knowledge about trachoma, 71.
Holmgren's worsted test for color-blindness, 457.
Homatropine, 263; producing glaucoma, 342.
Homonymous diplopia, 530; hemiopia, 428; muscle, tenotomy of, 709.
Honey-cysts of orbit, 593.
Hook, foreign-body, 741; Reisinger's, 697; Sédillot's, 737; sharp, for cap-

Indirect method of ophthalmoscopy, 6; vision, 20.
Infarcts of Meibomian glands, 484.
Infection, ectogenous, 156, 320; endogenous, 157, 320.
Infectious character of trachoma, 67, 71, 72.
Inferior lachrymal gland, 508; oblique, see OBLIQUE, INFERIOR; rectus, see RECTI, INFERIOR; tarsal arch, 32.
Infiltrated ulcer of cornea, 130.
Infiltration in keratitis, 128.
Inflammation of chorioid, see CHORIOIDITIS; of ciliary body, see CYCLITIS; of conjunctiva, see CONJUNCTIVITIS; of cornea, see KERATITIS, CORNEA, ABSCESS OF, and CORNEA, ULCER OF; of iris, see IRITIS and IRIDO-CYCLITIS; of lids, see BLEPHARITIS; of optic nerve, see NEURITIS, OPTIC; of orbit, see ORBIT, CELLULITIS OF; of retina, see RETINITIS; of sclera, see SCLERITIS; of uvea, see IRITIS, IRIDO-CYCLITIS, CYCLITIS, and CHORIOIDITIS; pathology of, illustrated by the morbid anatomy of keratitis, 134.
Inflammatory atrophy of optic nerve, 443; glaucoma, 337; œdema, 114, 472, 473.
Influenza producing retrobulbar neuritis, 439.
Injection, ciliary, 36, 133; circumcorneal, 36; conjunctival, 34, 133; pericorneal, 36.
Injuries of conjunctiva, 100; of cornea, 185; of eye, 216 *et seq.*, 223, 588, 716; of eye, enucleation for, 716; of eye, frequency of, 227; of eye, summary of, 588; of iris, 299; of lids, 502; of orbit, 580; of retina, 419.
Insertion of recti muscles, 533.
Instruments, disinfection of, 665; for cataract-extraction, 744; for discission, 743; for ectropion-operations, 738; for entropion-operations, 738; for enucleation, 739; for extraction of foreign bodies, 741; for iridectomy and iridotomy, 742; for keeping eye open and in place, 737; for lachrymal stricture, 740; for operations upon lachrymal apparatus, 740; for operations upon lens, 743, 744; for operations upon lids, 738; for operations upon muscles, 739; for paracentesis, 743; for ptosis-operations, 738; for squint-operations, 739; for tattooing cornea, 741; for tenotomy, 739; for trichiosis-operations, 738.
Insufficiency of externi, 543; of interni, 543; of interni, producing myopia, 633; of ocular muscles, 542; operation for, 708; vertical, 543.
Intercalary staphyloma, 231.
Intermittent strabismus, 570, 576.
Internal canthal ligament, 462, 466; canthus, 459; operation-wound, 672; rectus, see RECTI, INTERNAL.
Interni, insufficiency of, 543, 633.
Interpalpebral spot, 34; zone, 467.
Intervaginal space, 250, 423.
Intracranial paralyses of ocular muscles, 553, 560; section of optic nerve, 425.
Intra-ocular division of optic nerve, 420; pressure, 253.
Intrapeduncular paralysis, 561.
Intrascleral division of optic nerve, 420.
Intrinsic muscles of eye, 524.
Introversion of iris, 300, 302.
Invaginations, lateral, of ocular muscles, 525, 578.
Inversion of zone of hair-follicles, 723.
Inverted image, determination of refraction with, 19; image, examination with, 6; image, parallactic displacement with, 18.
Iodides and iodine in chorioiditis exudativa, 315; in conjunctivitis lymphatica, 91; in deep scleritis, 215; in detachment of retina, 414; in iritis, 296; in opacities of vitreous, 396; in optic-nerve atrophy, 443; in optic neuritis, 437; in parenchymatous keratitis, 177; in retinitis, 405, 412; in scleritis, 213, 215; in syphilitic paralyses of ocular muscles, 554; in syphilitic periostitis of orbit, 583; in tobacco-amblyopia, 440.
Iodoform in abscess of cornea, 157; in tuberculous conjunctivitis, 103; in ulcers of cornea, 147, 153; in wounds of cornea, 188.
Iodoform-gauze in enucleation, 715; in operation for orbital periostitis, 583.
Iridectomy, 680; accidents in, 686; astigmatism after, 654; contra-indications for, 682; difficulties in performance of, 353, 357, 686; for corneal ope-

681; for dislocation of lens, 393, 394; for ectatic prolapse of iris, 149; for fistula of cornea, 149; for glaucoma, 353, 683; for hydrophthalmus, 358; for increase of tension, 353, 358, 683; for irido-chorioiditis, 298; for iritis, 295; for keratectasia, 208; for keratitis vesiculosa, 170; for lamellar cataract, 371; for occlusio pupillæ, 297; for optical purposes, 681, 684; for scleritis, 215; for seclusio pupillæ, 297, 298; for staphyloma of cornea, 203; for total posterior synechia, 297; hæmorrhage after, in glaucoma, 357; how preventing prolapse of iris in operations, 675; in cataract-extraction, 683, 694, 702, 703; indications for, 149, 170, 194, 203, 208, 215, 295, 297, 298, 353, 358, 371, 393, 394, 681, 683, 694, 702, 703; injury of iris and lens in, 686; in scleral-flap extraction of cataract, 694, 702, 703; iridodialysis in, 686; prolapse of vitreous in, 687.

Iridectomy-forceps, 742.

Iridectomy-scissors, 742.

Irideremia, 310; traumatica, 300.

Irido-chorioiditis, 312; chronica, 287; chronica, iridectomy in, 298; plastica, 319; serosa, 318; suppurativa, 319.

Irido-cyclitis, 268 (see also Iritis); after cataract-extraction, 699, 703; after depression of cataract, 700; after discission, 689; after keratitis, 145; after operations upon eye, 672; causing glaucoma, 359; course and termination, 279; enucleation for, 716; etiology of, 285; morbid anatomy of, 277, 283; plastic, 278; purulent, 145, 278; secondary, 291; serous, 278; sympathica, 289, 292; symptoms, 268 *et seq.*

Iridodialysis, 299, 306; in iridectomy, 686; spontaneous, 233.

Iridodonesis, 234, 238.

Iridotomy, 687.

Iridotomy-scissors, 687, 742.

Iris, 234; action of, as a diaphragm, 256; anatomy of, 234; atrophy of, in iritis, 280, 283; coloboma of, 330; color of, 238, 239; congenital anomalies of, 309; contraction-furrows of, 238; crypts of, 235, 237; cysts of, 302; diseases of, 268; disorders of motility of, 306; examination of, 3; foreign bodies of, 304, 683; formation of gaps in, 283; great circle of, 235; hernia of, see Iris, Prolapse of; hyperæmia of, 268; incarceration of, in corneal cicatrices, 190; incarceration of, in operation-wounds, 668, 669; inflammatory œdema of, in glaucoma, 347; injuries of, 288, 299; introversion of, 300, 303; laceration of, 300; lepra of, 306; lesser circle of, 235; limiting membrane of, 237; melanoma of, 306; morbid changes of, in glaucoma, 351, 352; nodulation of, in leucocythæmia and pseudo-leucocythæmia, 305; non-tubercular nodules of, 305; pearl-cysts of, 303; pigment layer of, 237, 239; prolapse of, 141, 668; prolapse of, evil consequences of, 669; prolapse of, how averted by iridectomy, 675; prolapse of, how diagnosticated, 668; prolapse of, how occurring, 674; prolapse of, treatment, 148, 675; protrusion of, in iritis, 283; radiating lacerations of, 300; reposition of, in operations, necessity of, 668; retinal pigment-layer of, 237, 239; sarcoma of, 303, 306; sphincter of, 235; stroma of, 235; tuberculosis of, 302, 304, 305; tumors of, 302; tumors of, differential diagnosis, 306; tumors of, iridectomy for, 683.

Iritis, 268 (see also Irido-cyclitis); after operations upon eye, 288, 672; atrophy of iris in, 280, 283; condylomatosa, 292; diabetica, 287; diagnosis of, from conjunctivitis, 275; diagnosis of, from cyclitis, 274; diagnosis of from glaucoma, 275; etiology of, 285; gonorrhoica, 287; gummosa, 286, 292; idiopathica, 287; in acute conjunctivitis, 38; in acute infectious diseases, 287; in keratitis, 133; papulosa, 286, 292; primary, 285; recurrent, iridectomy in, 683; recurrent, not dependent upon presence of synechiæ, 279; rheumatica, 286; scrofulosa, 286; secondary, 291; serosa, 287; serous, 275, 279, 287 (see Cyclitis); symptoms of, 266; syphilitic, 285, 292; traumatica, 288; treatment, 294; tuberculosa, 286.

Iron in conjunctivitis lymphatica, 91; in scleritis, 215.

Irregular astigmatism, 654; healing, 670.

Irrigation of anterior chamber, 704.
Irritants for clearing opacities of cornea, 193; for clearing up ulcers of cornea, 150; for keratitis profunda, 182; for parenchymatous keratitis, 177.
Irritation, sympathetic, 289, 292.

Jacobson's method of cataract-extraction, 702.
Jaesche's operation for trichiasis, 720, 723.
Jäger's horn-plate, 719, 738; test-types, 608, 609.
Jäger, Eduard, his method of cataract-extraction, 704.
Javal and Schiötz's ophthalmometer, 657, 748.
Jequirity ophthalmia, 70; treatment of pannus, 1, 69, 80.
Jews, especially prone to suffer from trachoma, 66; predisposed to glaucoma, 341.

Keratectasia, 207; e panno, 66, 207; ex ulcere, 140, 143, 207.
Keratitis, 128; bullosa, 170; centralis annularis, 179; clinical diagnosis of, 131, 135; complications of, 133; deep, 172, 182, 184; dendritica, 152, 169; diagnosis of, 131, 135; diffusa, 172; e lagophthalmo, 161, 165, 167, 168; fascicularis, 86, 151; filamentous, 171; fœtal, 196; general features of, 128; hypopyon-, 159; implication of neighboring organs in, 133; interstitialis, 172; marginalis, 185; neuroparalytica, 164–168; non-suppurative, 129; parenchymatosa, 172; parenchymatosa circumscripta, 182; parenchymatous, 172; parenchymatous, complications of, 175; parenchymatous, etiology of, 175, 180, 181; parenchymatous, morbid anatomy of, 178; parenchymatous, prognosis of, 175; parenchymatous, symptoms of, 178; parenchymatous, treatment of, 177; phlyctenular, see Conjunctivitis lymphatica; profunda, 172, 179, 182; punctata, 277; punctata profunda, 179; punctata superficialis, 171; punctata syphilitica, 179; rheumatica, 182; sclerosing, 182; scrofulosa, 181; springing from posterior surface of cornea, 183; stages of, 128; subdivisions of, 137; subjective symptoms of, 134; suppurative, 129; symptoms, 134 (see also the varieties); syphilitica, 181; traumatic striped, 184; vascularization of cornea in, 132, 137; vesiculosa, 170; with formation of vesicles, 168; xerotica, 166, 168.
Keratocele, 140, 149, 207.
Keratoconus, 208, 210.
Keratoglobus, 209.
Keratomalacia, 162, 165, 167, 168.
Keratonyxis, 688, 691.
Keratoscope, Placido's, 658.
Keratoscopy, 19, 657.
Knapp's blepharostat, 719, 738; cystitome, 744; foreign-body hook, 741; knife-needle, 690, 743; operation for symblepharon, 111; thread-operation, 712.
Knies and Weber's theory of glaucoma, 350.
Knife, Beer's, 701, 744; lance-, 678, 680, 692, 742; lance-, concave, of Weber, 704, 744; linear, of Von Graefe, 702, 744; Stilling's, 521, 740.
Knife-needle, Knapp's, 690, 743.
Krause's glands, 31, 510.
Küchler's method of cataract-extraction, 704.
Kuhnt's operation for ectropion, 731; operation for symblepharon, 111.

Lachrymal duct, 509; duct, sounding of, 514, 520; duct, stricture of, 512; fistula, 517, 522; gland, anatomy of, 508; gland, atrophy of, 518; gland, cystoid dilatation of, 518; gland, inflammation of, 518; gland, tumors of, 518; organs, anatomy of, 508; organs, diseases of, 508; papillæ, 508; passages, 508; sac, 508; sac, a source of infection in eye-operations, 665; sac, blennorhœa of, 511, 519; sac, destruction of, for blennorrhœa, 515; sac, extirpation of, 516, 666; sac, obliteration of, 516; sac, tuberculosis of, 520; secretion, 510; sounds, 514.
Lachrymation, absence of, 523; excessive, 522; marked, in conjunctivitis lymphatica, 88.
Lagophthalmus, 494; tarsorrhaphy for, 496, 727.
Lamellar cataract, 370, 373; paracentesis for, 371, 688.

Lamina cribrosa, 420, 422; vitrea, 247.
Laminar cataract, 370.
Lance-knife, 742; concave, of Weber, 704, 744; for iridectomy, 680; for paracentesis of cornea, 678; for simple linear extraction, 692.
Lantern-tests for color-sense, 457.
Lapides cancrorum, 101.
Lapis divinus, 46.
Latent hypermetropia, 643; squint, 543.
Lateral hemiopia, 428; illumination, 2; invaginations of ocular muscles, 525, 578, 711; tarsorrhaphy, 726.
Layers of chorioid, 245; of cornea, 123; of retina, 400; of secondary ophthalmic vesicle, 265.
Lead acetate in catarrhal conjunctivitis, 43; acetate in follicular conjunctivitis, 47; incrustation, 43; poisoning, producing retro-bulbar neuritis, 439, 441.
Lebrun's method of cataract-extraction, 704.
Leech, artificial, 295.
Leeches in acute blennorrhœa, 53; see also BLOODLETTING.
Lens, see also GLASSES; bifocal, 604; collecting, 598; concave cylindrical, 601; concave, for correction of myopia, 16; concave, properties of, 598; concavo-convex, 600; convex cylindrical, 600; convex, for correction of hypermetropia, 17; convexo-concave, 600; convex, properties of, 598; crystallina, 361; crystalline, anatomy of, 361; crystalline, capsule of, 362; crystalline, changes in capsule after cataract-extraction, 697; crystalline, changes in, producing hypermetropia, 644; crystalline, changes in, producing myopia, 629; crystalline, changes of position in, 389; crystalline, changes of shape in accommodation, 615; crystalline, cortex of, 361; crystalline, dislocation of, 389; crystalline, examination of, 3; crystalline, excessive swelling of, after discission, 689; crystalline, expulsion of, in cataract-extraction, 694; crystalline, histology of, 362; crystalline, inflammation of, not existing, 368; crystalline, in glaucoma, 352; crystalline, injuries of, 382, 386; crystalline, injury and swelling of, causing glaucoma, 359, 689; crystalline, luxation of, 144, 359, 390, 697; crystalline, nuclear zone of, 363; crystalline, nucleus of, 361, 378; crystalline, nutrition of, how effected, 253, 255; crystalline, opacity of, see CATARACT; crystalline, subluxation of, 389, 654; crystalline, swelling of, in traumatic cataract and discission, 382, 688; cylindrical, 600; dispersing, 598; focal distance of, 599; numbering of, 599, 602; periscopic, 600; plano-concave, 600; plano-convex, 600; spherical, 600; strength of, how determined, 603; strength of, varying with distance from eye, 604.
Lens-capsule, 362; after cataract-extraction, 697; discission of, in after-cataracts, 691, 699; extraction of, with lens, 696; opening of, in cataract-extraction, 692, 694, 703; simple linear extraction of, in after-cataracts, 692, 699.
Lens-star, 362.
Lenticonus, 394.
Lenticular astigmatism, 654; exudate in anterior chamber, 276; reflex, 4.
Leontiasis ossea, 584.
Lepra of conjunctiva, 98; of iris, 306.
Leptothrix buccalis causing abscess of cornea, 158.
Leucocythæmic retinitis, 404; tumors of orbit, 595.
Leucoma adhærens, 142.
Leucosarcoma of chorioid, 326.
Levator palpebræ superioris, 463; paralysis of, 499, 501.
Lice causing conjunctivitis lymphatica, 94; in eyebrows, 481.
Lids, abscess of, 470, 504; adenoma of, 506; anatomy of, 459; angioma of, 505; anomalies of position and connection, 486; atheroma of, 505; carbuncle of, 470; carcinoma of, 506; coloboma of, 506; congenital shortness of, 496; conjunctival portion of, 465; cutaneous horns in, 505; cutaneous portion of, 465; cysts of, 505; dermoid cysts of, 505; diseases of, 459; diseases of muscles of, 497; distortion of, in trachoma, 64; ecchymoses of, 502, 504; eczema of, 469, 472; elephantiasis of, 472; emphysema of, in fracture, 506; enchondroma of, 506; epithelium of, 506; erysipelas of, 468, 473; examina-

tion of, 1; exanthemata of, 468; fibroma of, 506; fibroma molluscum of, 505; furuncle of, 470, 474; glands of, 31, 36, 463, 465; glands of, diseases of, 481; granular, 73; herpes zoster of, 468, 471; hyperæmia of border of, 475; inflammation of borders of, 475, 476; inflammation of skin of, 468; injuries of, 502; lipoma of, 506; lousiness of, 481; lupus of, 471; lymphangioma of, 506; malignant pustule of, 470, 474; milium of, 505; molluscum contagiosum of, 505; molluscum simplex of, 505; movements of, 460; muscles of, 462; neuro-fibroma of, 506; œdema of, 472; phlegmonous inflammation of, 470; sarcoma of, 506; spasm of, see BLEPHAROSPASM; telangiectasis of, 505; tumor cavernosus of, 505; tumors of, 504; ulcers of, 471; warts of, 505; xanthelasma of, 504; xanthoma of, 504.
Lid-clamp, 719, 738.
Lid-retractors, 666, 737.
Lid-specula, 666, 737.
Liebreich's method of cataract-extraction, 704.
Ligamentum canthi externum, 463, 466; canthi internum, 462, 466; pectinatum, 242, 244; suspensorium lentis, 361.
Ligation of carotid for pulsating exophthalmus, 595; of pterygium, 108.
Light-perception, how tested, 681, 684.
Light, reaction of pupil to, 256.
Light-sense, 20, 27.
Limbus conjunctivæ, 33.
Limitation of motility after squint-operations, 771; of motility in paralysis of ocular muscles, 547.
Limiting membrane of iris, 237.
Linear extraction, 692; incision in cataract-extraction, 701–703; incisions, 667; knife, Graefe's, 678–680, 686, 687, 693, 702, 744; measurement of lateral excursions of eye, 535.
Lipoma of lids, 506; subconjunctivale, 117.
Liquefaction of vitreous, 396.
Liquor Morgagni, 367.
Lithiasis conjunctivæ, 484.
Lithographers, prevalence of myopia among, 638.
Löffler's bacillus, 84.
Loop, Weber's, 697.
Lousiness of lids, 481.
Luminosity of pupil, 9.
Lungs, hypostatic congestion of, after eye-operations, 671.
Lupus conjunctivæ, 98, 103; of lids, 471.
Luscitas, 547.
Luxatio bulbi, 579; bulbi traumatica, 586.
Luxation of eyeball, 579, 586; of lens, 390; of lens, in cataract-extraction, 697.
Lymphadenoma of lachrymal gland, 518.
Lymphangioma of conjunctiva, 120; of lids, 506; of orbit, 595.
Lymphatic conjunctivitis, see CONJUNCTIVITIS LYMPHATICA; ectasiæ, 115.
Lymph-channels of eye, 250.
Lymphosarcoma of orbit, 595.
Lymph-passages of cornea, 124; of eye, 250.
Lymph-spaces of cornea, 123; of eye, 250.

Macropsia in miosis, 260; in spasm of accommodation, 662.
Maculæ corneæ, 189.
Macula lutea, 15, 400; lutea, changes in, in myopia, 318; lutea, coloboma of, 329, 330.
Madarosis, 477.
Malingerers, examination of, 29.
Manifest hypermetropia, 643.
Manometer for determining intra-ocular tension, 254.
Marginal keratitis, 185; network of the cornea, 34; ulcers of cornea, 152.
Massage in superficial keratitis, 213; of cornea for cicatrized ulcers, 150; of eye for embolism of retina, 402; of lids for tylosis, 481.
Mature cataract, 375, 377.
Measles, conjunctivitis in, 97, 98.
Measurement of depressions and projections in fundus, 18; of excursions of eyeball, 535; of insufficiency, 546.
Mechanism of accommodation, 613.
Median tarsorrhaphy, 726, 727.
Medullated fibers in fiber-layer of retina, 405.
Megalocornea, 229.
Meibomian glands, 465; glands, adenoma of, 506; glands, infarcts of, 484; sty, 482.

bralis superior, 463, 502; subtarsalis, 466.
Mydriasis, 257, 307; in amaurosis, cause of, 307; in glaucoma, cause of, 347; paralytic, 307, 308; spastic, 307; traumatic, 300, 307.
Mydriatics, 258, 259, 263; see also Atropine; harmful in glaucoma, 341, 357.
Myodesopsia, 366, 396.
Myoma of ciliary muscle, 306.
Myopia, 626; apparent, produced by spasm of accommodation, 662; apparent, simulated by hypermetropia, 648; axial, 629; bad results and complications of, 630, 631; cause of, 628, 632, 637; causing cataract, 383; causing divergent squint, 566; causing glaucoma, 359; changes of chorioid in, 316; changes of, in age, 636; ciliary muscle in, 635; correction of, by a concave lens, 16, 633; determination of, 627; developing in conjunction with senile cataract, 366; developing in lamellar cataract, 374; elongation of eye in, 631, 635; hereditary tendency to, 633; hygienic regulations for, 634; incapacitating for military service, 637; in schools, 637; monocular diplopia in, 542; morbid anatomy of, 631, 635; muscæ volitantes in, 631; objective determination of, 16, 628; origin of term, 629; predisposition to, 632, 638; prevalence among certain professions and races, 638; progressive, 632; prophylaxis of, 638; relation of, to glaucoma, 636; rules for prescribing glasses in, 633; staphyloma posticum in, 635, 636; stationary, 632; subjective determination of, 628; theories of its production, 638; treatment of, 633; typical, 629.
Myopic astigmatism, 653, 655.
Myo-sarcoma of ciliary muscle, 306.
Myxoma of conjunctiva, 120.

Naphthalinic cataract, 385.
Nasal duct, 509.
Near-point, 615; determination of, 619; recession of, 622.
Near-work, excessive, producing myopia, 632, 637.
Needle, cataract-, 743; couching, 743; discission-, 688, 743; foreign-body, 186, 741; knife-, 690, 743; paracentesis-, 743; tattooing-, 194, 741.
Negative meniscus, 600; portion of relative accommodation, 621; scotoma, 26.
Nerve, optic, 420. See Optic Nerve.
Nerves of cornea, 125; of ocular muscles, 525, 536; of orbit, 579.
Nerve-stretching in senile blepharospasm, 501.
Nervous asthenopia, 451.
Nervus opticus, 420.
Network, marginal, of cornea, 34.
Neurasthenia, disturbances of vision in, 451.
Neuritic atrophy of optic nerve, 443; swelling, 445.
Neuritis descendens, 436; intra-ocularis, 433; optica, 433 (see also Optic Neuritis); optic, morbid anatomy of, 444; retro-bulbar, 439; retro-bulbar, scotoma in, 26.
Neuro-fibroma of lids, 506.
Neuroma plexiforme of orbit, 595.
Neuro-retinitis, 409, 437.
Neurotomy, optico-ciliary, 718.
Night-blindness, 447.
Nitrate of silver. See Silver Nitrate.
Non-inflammatory atrophy of optic nerve, 442; œdema, 114, 115, 472.
Non-irritative central ulcer of cornea, 151.
Non-suppurative keratitis, 129.
Nourishment of eye, 252.
Nubeculæ corneæ, 189.
Nuclear cataract, 381; paralyses of ocular muscles, 553, 560; zone of lens, 363.
Nuclei of nerves of the ocular muscles, 536.
Nucleus for the accommodation and the pupil, 537; for the internal recti (convergence), 537; of abducens, 538; of cataract, 367; of cataract, size, how determined, 378; of lens, 361; of oculomotor nerve, 536; of trochlear nerve, 537.
Nyctalopia, 447; in cataract, 365; in tobacco-amblyopia, 440.
Nystagmus, 574; miner's, 575; mixtus, 574; oscillatorius, 574; rotatorius, 474.

Objective determination of astigmatism, 657; determination of hypermetropia,

643; determination of myopia, 628; examination of the eyes, 1; orientation, 529.
Oblique blepharotomy, 726.
Oblique, inferior, action of, 527; paralysis of, 558.
Oblique muscles, anatomy of, 524.
Oblique position of head in paralytic squint, 551; in strabismus, 573.
Oblique, superior, action of, 527; paralysis of, 552, 558.
Obliteration of lachrymal sac, 516.
Occlusio pupillæ, 269, 276, 281.
Ocular fissure, fœtal, 266; muscles, 463, 524; vesicle, primitive, 264; vesicle, secondary, 265.
Oculomotor nerve, 537; paralysis, 552.
Œdema calidum, 114, 472; filtration-, 115; frigidum, 114, 472; inflammatory, 114, 472; non-inflammatory, 114, 115, 472; of lids, 472; of mastoid process in thrombosis of cavernous sinus, 585; subconjunctival, 113.
Oettingen's operation for trichiasis, 723.
Oil-cysts of orbit, 593.
Ointment, ammoniated-mercury, see Ointment, White-Precipitate; Arlt's, 94; Pagenstecher's, see Ointment, Yellow-Oxide; white-precipitate, 91, 470; yellow-oxide, yellow-precipitate, 90, 150, 177, 213.
Old paralyses of ocular muscles, 557; system of numbering lenses, 602.
Oleum fagi and oleum rusci in blepharitis, 481.
Onyx, 136.
Opacitates corporis vitrei, 395.
Opacities in the refractive media, how recognized by means of the ophthalmoscope, 8; of the cornea, 189; of the cornea, congenital, 196; of the cornea, how recognized, 128; of the lens, see Cataract; of the vitreous, 395, 397.
Opening of eyes, how effected, 460.
Operations (or operation), 665; after-treatment of, 670; antisepsis in, 665; Antyllus-Kuhnt's, for ectropion, 731; Arlt's, for tarsorrhaphy, 727; Arlt's modification of Gaillard's, for entropion, 728; avoided in diphtheritic conjunctivitis, 83; Beer's, for staphyloma, 202; compensating, 709; delirium after, 676; Dieffenbach's, for blepharoplasty, 732; dressing after, 666, 676; equilibrating, 710; Eversbusch's, for ptosis, 736; flap-, for cicatricial ectropion, 732; for cataract, see Discission, Cataract-Extraction, Depression, and Reclination; for cicatricial ectropion, 731; for cicatricial entropion, 729; for ectropion, 730; for entropion, 728; for insufficiency, 545, 708, 709; for paralytic ectropion, 731; for paralytic squint, 555, 709; for ptosis, 734; for senile ectropion, 730, 731; for spastic ectropion, 730; for spastic entropion, 728; for squint, 705; for staphyloma, 201; for symblepharon, 110, 111; for trichiasis, 719; Fricke's, for blepharoplasty, 732; Fuchs's, for tarsorrhaphy, 726; Gaillard-Arlt's, for entropion, 728; general rules for, 665; healing of wound after, 670; Hotz's, 722, 723, 725, 729; inflammation after, 671, 672; Kuhnt's, for ectropion, 731; Kuhnt's, for symblepharon, 111; Mule's, 718; Oettingen's for trichiasis, 723; Pagenstecher's, for ptosis, 735; Panas's, for ptosis, 735; sliding flap-, for ectropion, 732; Snellen's, for ectropion, 730; Spencer Watson's, for trichiasis, 724, 725; Stellwag's, for canthoplasty, 736; Stellwag's, for trichiasis, 723; substitution-, 709; thread-, 710, 712; upon the adnexa bulbi, 705; upon the eyeball, 678; Van Millingen's, for trichiasis, 724; Von Graefe's, for ptosis, 734; Von Graefe's, for strabismus, 710; Von Walther's, for tarsorrhaphy, 726.
Ophthalmia ægyptiaca, 67, 71; catarrhalis, 37; Egyptian, 67, 71; gonorrhœal, 49; jequirity, 70; metastatic, 321; neonatorum, see Blennorrhœa Neonatorum; purulenta chronica, 73; sympathetic, 289, 292.
Ophthalmomalacia, 360.
Ophthalmometer of Helmholtz, 657; of Javal and Schiötz, 657, 748.
Ophthalmoplegia, central, 560; externa, 552, 560; interna, 553, 660; totalis, 552, 560.
Ophthalmoscope, 4, 746; application of, 7; determination of refraction by, 16, 657; examination with, 4; invention of, 4; principle of, 4, 5; visibility of

opacities in the refractive media by means of, 8.
Ophthalmoscopic examination with the erect image, 6; with the inverted image, 7.
Ophthalmoscopy, 4.
Optic disk, 9, 13, 14, 400, 422; coloboma of, 329.
Optic nerve, anatomy of, 420; arachnoid sheath of, 424; atrophy of, 442; atrophy of, morbid anatomy, 445; atrophy of, scotoma in, 25; descending atrophy of, 439, 442; diseases of, 420; dural sheath of, 423; excavation of, 8, 13, 332, 334; head of, 14, 400, 422; inflammation of, 433; injuries of, 443; intracranial section of, 425; intra-ocular division of, 420; intra-scleral portion of, 420; non-inflammatory atrophy of, 442; orbital division of, 423; pial sheath of, 423; primary atrophy of, 442; sheaths of, 423; simple atrophy of, 442; trunk of, 423; tumors of, 444.
Optic neuritis, 433; neuritis, morbid anatomy of, 444; papilla, 8, 9, 13, 14, 400, 422; tracts, 425.
Optical area, 426; memory pictures, 426.
Optico-ciliary neurotomy, 718.
Optometer, 628; rod-, 619.
Ora serrata, 400.
Orbicularis palpebrarum, 462, 466; paralysis of, 498; spasm of, 497.
Orbiculus ciliaris, 241, 247.
Orbit, anatomy of, 577; aneurism of, 592; angioma of, 492; angioma lipomatodes of, 595; blood-vessels of, 578; carcinoma of, 593; cavernous tumor of, 592; cellulitis of, 583; cylindroma of, 595; cysts of, 591, 593; dermoid cyst of, 591, 593; diseases of, 577; emphysema of, 587; encephalocele of, 593; endothelioma of, 595; exenteration of, 714, 718; extravasation of blood into, 586; fasciæ of, 578; fractures of bony walls of, 587; hæmorrhage into, 586, 588; inflammation of bones and periosteum of, 581, 584; injuries of, 586; leucocythæmic tumors of, 595; lymphangioma of, 595; lymphosarcoma of, 595; meningocele of, 593; muscle of, 580; nerves of, 579; neuroma plexiforma of, 595; osteoma of, 595; phlegmon of, 475, 583; position of eye in, 579; psammoma of, 595; sarcoma of, 592; septum of, 578; telangiectasis of, 592; tumors of, 591; tumors of, enucleation for, 716.
Orbital cellulitis, 583; division of optic nerve, 423; muscle of Müller, 580; paralysis of ocular muscles, 553, 562; periostitis, 581, 584; phlegmon, 475, 583; portion of orbicularis, 463; septum, 578.
Organic causes of insufficiency, 543; entropion, 489.
Orientation, 528; false (in paralytic squint), 549; how facilitated by peripheral vision, 21; objective, 529; subjective, 529.
Osteoma of conjunctiva, 120; of orbit, 595.
Outer operation-wound, 672.
Ozæna producing blennorrhœa of lachrymal sac, 513.

Pagenstecher's method of cataract-extraction, 696; ointment, see OINTMENT, YELLOW-OXIDE; operation for ptosis, 735.
Pain in glaucoma, 342, 347.
Pairs of ocular muscles, 526.
Palpebra tertia, 34.
Palpebral conjunctiva, 31; glands, 31, 36, 463, 465; glands, diseases of, 481; muscles, 462; muscles, diseases of, 497; muscles of Müller, 463; portion of orbicularis, 462, 466.
Panas's operation for ptosis, 735.
Pannus, 168; carnosus, 75; causes of, in trachoma, 75; crassus, 75; in conjunctivitis lymphatica, 87; inoculation of blennorrhœal virus for cure of, 56, 80; jequirity-treatment of, 69, 80; sarcomatosus, 75; scrofulosus, 87, 92; siccus, 75; simulating pterygium, 109; tenuis, 75; trachomatous, 60; trachomatous, anatomical character of, 74; trachomatous, treatment of, 69, 80; trachomatous, ulcer of cornea in, 151; treatment of, 69, 80; vasculosus, 75.
Panophthalmitis, 319, 321; diagnosis of, 145, 474, 475.
Papilla nervi optici, 8, 9, 13, 14, 400, 422.
Papillæ lacrimales, 508.
Papillary condition of conjunctiva, 36;

form of trachoma, 59, 72; hypertrophy of conjunctiva occurring in many eye-diseases, 79.
Papilloma, 433.
Papilloma of conjunctiva, 118.
Papillomatous bundle, 432; region, 432.
Papilloretinitis, 277.
Paracentesis of cornea, 678; after cataract-operation, 678, 689; for abscess of cornea, 678, 679; for embolism of central artery, 677; for increase of tension, 678; for removal of hypopyon, 678; for staphyloma, 393, 398, 678; for iritis, 393, 678; for ulcers of cornea, 148, 678.
Paracentesis of sclera, 679.
Paracentesis scleræ, 743.
Paralysis of Displacement, 11, 18.
Paralysis, basal, 533, 561; changes of ocular muscles in old cases of, 551; conjugate, 561, 562; conjugate, 553, 560; crossed, 553, 560; diagnosis of, 560, 561; ascular, 553, 561; intra-ocular, 553, 560; measurement of, 559; ocular, 553, 560; oculomotor, 552; ophthalmoplegia, 552, 558; of accommodation, 660; of ciliary muscle, 660; of external rectus, 552, 558; of fourth nerve, 552, 558; of individual ocular muscles, 552, 558; of inferior oblique, of inferior rectus, 557, 558; of internal rectus, 558; of levator palpebræ superioris, 499, 501; of musculus orbitalis superior, 502; of ocular muscles, of oculomotor nerve, 499; of several muscles, 553; of sixth nerve, of ophthalmoplegia interna, 556, 558; of ophthalmoplegia, 558; of sympathetic, 552; of trochlear nerve, 553, 562; post-diphtheritic, cases of double vision, pathology of, how diagnosed, 562; supranuclear, 552, 558.
Paralysis, 562, 581; miosis, 308; mydriasis, 308; 547, 709.
Paralysis of the fifth nerve, 172; xerosis, 172.
Paralysis of the third nerve, accidental iridis, 547; mydriasis, 308.
Partial tenotomy, 718.
Path of rays when eye is focused for source of light, 10.
Pathological alterations of visual field, 24; excavation, 13.
Pearl-cysts of iris, 303.
Pemphigus conjunctivæ, 98.
Perception of colors, 452, 455; of colors, rapid diminution of, a sign of optic-nerve disease, 27; of light, always retained in uncomplicated cataract, 367; of light, how tested in opacity of the refractive media, 681, 684.
Perforation of cornea, 140; of cornea, treatment, 148; of eye, symptoms of, 216.
Perichorioidal space, 250.
Pericorneal injection, 36.
Perimeter, 22, 749; for measuring degree of paralysis, 559, 560; for measuring excursions of eye, 536.
Perinuclear cataract, 370, 373; discission in, 689.
Periodic strabismus, 564, 566.
Pericdical erosion of cornea, 171; formation of vesicles on cornea, 171.
Periorbita, 578.
Periosteal abscess, 581.
Periostitis of orbit, 581, 584.
Peripheral vision, 20.
Periscopic glasses, 600.
Peritomy, 80.
Persistent hyaloid artery, 397; pupillary membrane, 309, 310.
Petit's canal, 263; method of opening the lachrymal sac, 515.
Phlegmon of orbit, 583; diagnosis of, 475; retrobulbar, 583.
Phlyctæna pallida, 95.
Phlyctænular conjunctivitis and keratitis. See Conjunctivitis lymphatica.
Photometer of Förster, 28.
Photophobia in conjunctivitis lymphatica, 88; not to be too much regarded, 90; treatment, 90, 93.
Photopsia in chorioiditis, 313; in detachment of retina, 416.
Phthiriasis palpebrarum, 481.
Phthisis bulbi, 320, 323; bulbi, enucleation for, 716; corneæ, 143; essential, 360.
Phakitis, 368.
Physiological astigmatism, 652, 654; excavation, 13, 334.
Physostigmine. See Eserine.
Pial sheath of optic nerve, 423.

Pigment, retinal, 247; stroma, 247.
Pigmentary degeneration of retina, 410.
Pigment-epithelium, 247, 401.
Pigment-layer of iris, 237, 239.
Pilocarpine, 259, 263; as an absorbent in inflammation, 264; in chorioiditis, 315; in detachment of retina, 414; in fistula of cornea, 149; in glaucoma, 263, 264, 356; in iritis, 295; in mydriasis, 263, 264; in opacities of vitreous, 396; in paralysis of accommodation, 661; in rheumatic paralyses of ocular muscles, 555; in tobacco-amblyopia, 441.
Pince-ciseaux, 687, 742.
Pinguecula, 34, 36, 37.
Placido's keratoscope, 658.
Plano-concave lens, 600.
Plano-convex lens, 600.
Plica semilunaris, 34; diseases of, 120.
Point, far-, 615; near-, 615; pressure-, 500.
Points, visibility of, dependent upon their brilliancy, 607.
Poisons producing paralysis of accommodation, 661.
Polioencephalitis superior, causing ophthalmoplegia, 561.
Polyopia monocularis in cataract, 365.
Polypi of conjunctiva, 118.
Portio orbitalis, 463; palpebralis, 462, 466.
Position of eye in orbit, 579.
Positive meniscus, 600; portion of relative accommodation, 621; scotoma, 26.
Post-diphtheritic paralysis of accommodation, 660.
Posterior chamber, 243, 244; conjunctival vessels, 34; cortical cataract, 372, 374; detachment of vitreous, 396; lenticular reflex, 4; longitudinal fasciculus, 538; polar cataract, 369; scleral protuberance of Ammon, 228, 230, 231; sclerotomy, 680; synechia, 269, 280.
Precipitates on cornea in cyclitis, 272, 276, 277.
Presbyopia, 622: formerly confounded with hypermetropia, 647; occurring early in hypermetropia, 646; occurring late in myopia, 630.
Prescriptions for glasses, how written, 656.
Pressure, intra-ocular, 253.
Pressure-bandage, 147; in detachment of retina, 414; in enucleation, 714; in exophthalmus due to extravasation or emphysema, 587; in operations upon eyes affected with increase of tension, 676; in prolapse of iris, 149.
Pressure-opacity of cornea, 191.
Pressure-points in hysterical blepharospasm, 500.
Priestley Smith's lamp, 3.
Primary atrophy of optic nerve, 442; deviation in concomitant squint, 563; deviation in paralytic squint, 548; enucleation, 716; glaucoma, 337.
Primitive ocular vesicle, 264.
Principal focal distance, 599.
Prisms, 601; for measuring insufficiency, 546; for measuring paralysis, 560; for treatment of insufficiency, 545; for treatment of paralysis, 555.
Prism-tests, 546, 560.
Probes, lachrymal, 740.
Prodromal stage of glaucoma, 337; of sympathetic irido-cyclitis, 289.
Progressive atrophy of optic nerve, 442; cataract, 368, 374; myopia, 632; paralysis producing optic-nerve atrophy, 442; pterygium, 105; ulcer of cornea, 130.
Projection of field of vision on a hollow sphere, 22; of field of vision on a plane, 22; of retinal images externally, 529.
Prolapse of iris, 141; circumstances determining it, 674; diagnosis of, 668; evil consequences of, 669; how averted by iridectomy, 675; mode of occurrence in operations, 674; treatment, 148, 675.
Prolapse of vitreous in cataract-extraction, 697, 703; in iridectomy, 687; in iridotomy, 688.
Prophylaxis in acute blennorrhœa, 52; in blennorrhœa neonatorum, 57; in diphtheritic conjunctivitis, 83; in sympathetic ophthalmia, 296; of trachoma, 70.
Protection of sound eye in acute blennorrhœa, 52, 54.
Protective bandage, 147; in diphtheritic conjunctivitis, 83.
Protective glasses, 600, 601; for

Reflex, 15; corneal, 2, 3; images of Purkinje-Sanson, 3; lenticular, 4; reaction of pupil, 256; streak, 15; watered-silk, 15.
Refracting media, examination of, 7, 11.
Refraction of eye, 8, 605; anomalies of, 597; determination of, by erect image, 16; determination of, by inverted image, 17; determination of, by keratoscopy, 19; determination of, by objective methods, 16, 17, 19; determination of, by ophthalmometer, 657; determination of, by ophthalmoscope, 16; determination of, by optometer, 628; determination of, by subjective methods, 626, 641, 655; tested with reference to central vision, 20.
Refractive power of eye, diminishing in old age, 624; greatly decreased by cataract extraction, 698; slightly reduced by atropine, 663.
Regimen of eyes. See HYGIENIC TREATMENT.
Region of accommodation, 615, 616, 619; of transition, 31, 33.
Regressive ulcer of cornea, 130.
Regular astigmatism, 650.
Reisinger's double hook, 697.
Relative far-point, 620; hypermetropia, 645; near-point, 620; range of accommodation, 619; scotoma, 26; visual acuity, 610.
Relaxation of lateral invaginations, 711.
Resorption in keratitis, 129; of lens, after injury, 382, 688; of hypopyon, 136.
Retina, 400; adaptation of, 28; anæmia of, 408; anatomy of, 400; arteries of, how distinguished from veins, 18; atrophy of, 410; atrophy of, scotoma in, 25; concussion of, 419; detachment of, 413; detachment of, sclerotomy in, 680; detachment of, scotoma in, 25; diseases of, 400; function of, 402; hæmorrhages into, 406; hæmorrhages into, causing glaucoma, 359; hyperæmia of, 405; inflammation of, see RETINITIS; injuries of, 419; nutrition of, how effected, 253, 255; physiological opacity of, from presence of medullated nerve-fibers, 405; physiology of, 402; position of, influencing character of astigmatism, 655; position of, influencing size and shape of diffusion-circles, 611, 650; rupture of, 416, 419; sensitiveness of, in cataract, etc., how determined, 681, 684; vessels of, 8; vessels of, how distinguished from those of chorioid, 16.
Retinal images, size of, how calculated, 605; pigment-layer of iris, 239; system of vessels, 35, 248.
Retinitic atrophy of optic nerve, 443.
Retinitis, 403; albuminurica, 404, 409; diabetica, 404; from dazzling, 410; hæmorrhagica, 405; idiopathica, 405; leucæmica, 404; metastatic (suppurative), 407; morbid anatomy of, 412; nyctalopica, 440; pigmentosa, 410; pigmentosa, loss of peripheral vision in, 21, 411; pigmentosa, scotoma in, 25; proliferans, 410; pyæmic, 407; suppurative (metastatic), 407; syphilitica, 404.
Retino-chorioiditis, 313, 316, 409.
Retinoscopy, 19.
Retrobulbar abscess, 583; neuritis, 439; phlegmon, 583.
Rheumatic iritis, 286, 296; paralyses of ocular muscles, 554.
Rhytidosis corneæ, 127.
Rickets causing lamellar cataract, 371, 373.
Riders, 370.
Ring, chorioidal, 13; scleral, 13.
Ripening of cataract, 374, 379; by iridectomy, 684.
Rock-crystal glasses, 604.
Rods and cones of retina, 400, 401.
Rodent ulcer of cornea, 152; of lids, 506.
Rodeur, the slave-ship, trachoma on, 72.
Rod-optometer, 619.
Romershausen's collyrium, 46.
Rotation of eye, how effected, 528.
Ruete's (indirect) method of ophthalmoscopy, 6.
Ruptura retinæ, 416.
Rupture of chorioid, 323; of cicatrix in eye-operations, 670; of cornea, 223; of retina, 416, 419; of sclera, 223.

Saccus lacrimalis, 508.
Saemisch's method of paracentesis for corneal abscess, 158, 689.
Sagittal axis of eye, 526.

Salicylates and salicylic acid in chorioiditis, 315; in detachment of retina, 414; in herpes zoster, 469; in iritis, 295, 296; in opacities of the vitreous, 396; in rheumatic paralyses of the ocular muscles, 554; in superficial scleritis, 213.
Salines in opacities of the vitreous, 396; in retinitis, 405.
Sarcoma of chorioid, 324; of ciliary body, 303; of conjunctiva, 117, 119; of iris, 303, 306; of lachrymal gland, 518; of lids, 506; of orbit, 592; of sclera, 233.
Scarification of conjunctiva in acute blennorrhœa, 56; of superficial scleritis, 213.
Scheiner's experiment, 541.
Schematic eye, 605.
Schizomycetes causing abscess and ulcer of cornea, 158.
Schlemm's canal, 244.
Schmidt-Rimpler's method of determining refraction by the inverted image, 19.
Schools, myopia in, 637.
Scintillating scotoma, 449.
Scissors, iridotomy-, 742; strabismus-, 739.
Scissors-forceps, 687, 742.
Sclera, 211; anatomy of, 211; diseases of, 211; ectasiæ of, 227; ectasiæ of, causing glaucoma, 359; fibroma of, 233; inflammation of, see SCLERITIS; injuries of, 216; osteoma of, 233; paracentesis of, 679; rupture of, 217, 223; sarcoma of, 233; staphyloma of, 227; staphyloma of, anterior, 228, 230; staphyloma of, causing glaucoma, 239; staphyloma of, ciliary, 231; staphyloma of, enucleation for, 717; staphyloma of, equatorial, 228, 230; staphyloma of, intercalary, 237; staphyloma of, morbid anatomy, 231; staphyloma of, posterior, 228, 230; tumors of, 233; ulcers of, 233.
Scleral circle of vessels of Zinn, 252; conjunctiva, 33; division of cornea, 125, 126; discission, 691; flap-extraction, 693; incisions, 667; paracentesis, 679; protuberance of Ammon, 329; ring, 13.
Scleritis, deep, 213; superficial, 212.
Scleronyxis, 691.
Sclerosing keratitis, 182.
Sclerotomia anterior, 679; posterior, 680.
Sclerotomy, 356, 679.
Scotoma, 25; absolute, 26; annular, 25; central, 25, 440; color-, 27; fixed, 26; in chorioiditis, 313; in detachment of retina, 413; in embolism of the central artery, 407; in optic-nerve atrophy, 443; in retinitis, 404; in retinitis pigmentosa, 35, 411; in retrobulbar neuritis, 439; in tobacco-amblyopia, 440; motile, 26; negative, 26; positive, 26; relative, 26; scintillans, 449.
Screen-test for muscular insufficiency, 542.
Scrofula producing blennorrhœa of lachrymal sac, 513.
Scrofulous conjunctivitis, 85; diathesis, signs of, 89; iritis, 286; pannus, 87, 92.
Sea-baths in conjunctivitis lymphatica, 91.
Seclusio pupillæ, 271, 276, 280; causing glaucoma, 359; treatment of, 297, 298.
Secondary cataract, 699; deviation in concomitant squint, 563; deviation in paralytic squint, 548; enucleation, 716; glaucoma, 359; ocular vesicle, 265.
Secretion of conjunctiva increased and altered in inflammation of conjunctiva, 37.
Sections, 667; corneal, 667; curved, 667; linear, 667; oblique, 673; scleral, 667; valve-like, 673.
Sédillot's double hook, 737.
Semi-decussation, 426, 429 *et seq.*
Semilunar fold. See PLICA SEMILUNARIS.
Senile blepharospasm, 498, 500; cataract, 374, 381, 384; ectropion, 492; ectropion, operations for, 730, 731.
Sensitiveness of cornea, how tested, 3, 128.
Sensory stimuli, reaction of pupil to, 257.
Septum orbitale, 578.
Serous irido-cyclitis, 278; iritis, 275, 279, 287; tenonitis, 585.
Serpiginous ulcers of cornea, 86, 138, 153.
Shadow-test, see KERATOSCOPY; of cataract, 375, 380.
Short-sightedness, 626.
Sight. See VISION.
Silver nitrate, discoloration produced by, 42; excessive use of, producing croupous and diphtheritic conjunctivitis, 84;

in acute blennorrhœa, 53; in acute catarrhal conjunctivitis, 39; in blennorrhœa neonatorum, 57; in blepharitis ulcerosa, 480; in conjunctivitis catarrhalis chronica, 46; in diphtheritic conjunctivitis, 82; in eczema of lids, 470; in keratitis vesiculosa, 170; in trachoma, 67; method of application of, 39, 40; rationale of action in conjunctival disease, 42; rules for application of, 42.
Simple atrophy of optic nerve, 442; glaucoma, 343; linear extraction, 692.
Simulation of blindness, 28.
Sinus of anterior chamber, 244.
Site of opacity, how diagnosticated, 12.
Sixth nerve, course of, 538; nucleus of, 538; paralysis of, 552, 558, 562.
Skiascopy, 19.
Skin-grafting for ectropion, 733.
Skull, fractures of base, ecchymosis of lids in, 504.
Sliding-flap operation for ectropion, 732.
Slitting of canaliculus, 514, 519.
Small-pox, conjunctivitis in, 97.
Snellen's operation for symblepharon, 111; operation for trichiasis, 722; suture for ectropion, 730; suture for entropion, 730; test-types, 608, 609; test-types for determination of simulated blindness, 30.
Snow-blindness, 102.
Soemmering's crystalline swelling, 698.
Soft cataract, 377; discission of, 688; simple linear extraction for, 692.
Solitary tuberculosis of chorioid, 327.
Solutions of continuity of conjunctiva, 100.
Sound eye, how protected in acute blennorrhœa, 52, 54; when requiring enucleation, 717.
Sounding, 514, 520.
Sounds, Bowman's, 514, 740.
Space, circumlental, 361; intervaginal, 250; perichorioidal, 250; subarachnoid, 424; subdural, 424; Tenon's, 250.
Space-sense, 20.
Spasm of accommodation, 663; macropsia in, 662; simulating and producing myopia, 633.
Spasm of lids, see BLEPHAROSPASM; of musculus palpebralis superior, 502; of orbicularis, 497.
Spastic ectropion, 491, 730; entropion, 488, 728; miosis, 308; mydriasis, 307.
Spatula, 744.
Spectroscope in testing color-blindness, 457.
Specula, 666, 737.
Spencer Watson's operation for trichiasis, 724, 725.
Spheres of Morgagni, 366.
Spherical lens, 600.
Sphincter, angles of, 668; iridis, 235; palpebrarum, 462.
Sphincterotomy, 726.
Spinal atrophy of optic nerve, 442; miosis, 308, 442.
Spongy exudate in anterior chamber, 276.
Spot, interpalpebral, 34; yellow, see MACULA LUTEA.
Spring speculum, 666, 737.
Squint, 562; alternating, 564, 569; apparent, 570; concomitant, 563, 707; convergent, 564, 565, 707; divergent, 564, 566, 708; dynamic, 543; intermittent, 570, 576; latent, 543; measurement of, 572; monolateral, 564; operations for, 705; paralytic, 547, 709; periodic, 564, 566; temporary, 568; vertical, 570.
Squint-hook, 739.
"Staar," origin and various applications of term, 388.
Staphylococci causing abscess and ulcer of cornea, 146, 158.
Staphyloma, annular, 316; ciliare, 214, 231; corneæ, 143; intercalare, 231; of cornea, 197; of cornea, enucleation for, 717; of cornea, iridectomy in, 683; of cornea, partial, 198; of cornea, total, 197; of sclera, 228; of sclera, enucleation for, 717; partiale conicum, 198; partiale sphæricum, 198; pellucidum, 210; posticum (Scarpæ), 228, 330, 231, 316, 635, 636, 639; totale conicum, 197; totale sphæricum, 197.
Stationary cataract, 368; myopia, 632; pterygium, 105.
Statometer, 581.
Steam in treatment of cicatrizing ulcer of cornea, 150; of parenchymatous keratitis, 177.
Stellate figure of lens, 362.
Stellwag's method of cataract-extraction,

694; operation for canthoplasty, 725; operation for symblepharon, 111; operation for trichiasis, 723; symptom in Basedow's disease, 589; theory of glaucoma, 350.
Stenopæic glasses, 194, 601; slit in testing for astigmatism, 656.
Stereoscopic vision, 539; absent in strabismus, 572; Hering's test for, 539.
Stevens's tenotomy-hook, 739; tenotomy-scissors, 739.
Stillicidium, 511.
Stilling's knife, 531, 740; pseudo-isochromatic diagrams, 457.
Stimulus, minimum (of light-sense), 27.
Stop-needle, 743.
Strabismic deviation, 563.
Strabismus, 562; alternans, 564, 569; apparent, 570; concomitans, 563, 707; convergens, 564, 565, 707; deorsumvergens, 570; divergens, 564, 566, 708; intermittent, 570, 576; latent, 543; measurement of, 572; monolateralis, 564; operations for, 705; paralyticus, 547, 709; periodic, 564, 566; sursumvergens, 570; temporary, in young children, 568; vertical, 570.
Strabismus-forceps, 739.
Strabismus-scissors, 739.
Straightening of tarsus, 722.
Stramonium producing retrobulbar neuritis, 441.
Streak, reflex, 15.
Streptothrix Fœrsteri occluding canaliculis, 519.
Strictures of lachrymal duct, 512; dilatation of, 514, 520; division of, 521.
Stroma of cornea, 123; of iris, 235; pigment, 247.
Strychnine in keratitis neuroparalytica, 165; in optic-nerve lesions, 441, 443; in retinitis pigmentosa, 412; in tobacco-amblyopia, 441.
Sty, 482.
Subarachnoid space, 424.
Subconjunctival ecchymosis, 113; emphysema, 115; œdema, 113.
Subdural space, 424.
Subjective method of determining hypermetropia, 643; of determining myopia, 628; orientation, 529.
Subluxation of lens, 389.
Substitution operation, 709.
Subtarsal groove. See SULCUS SUBTARSALIS.
Suction of cataract, 691, 744.
Suffusio, 388.
Sulcus subtarsalis, 33.
Sulphate of copper, sulphate of zinc. See COPPER SULPHATE, ZINC SULPHATE.
Superior lachrymal gland, 508; oblique, see OBLIQUE, SUPERIOR; rectus, see RECTI, SUPERIOR; tarsal arch, 32.
Supplemental crystalline lens, 617.
Suppuration of wound after eye-operations, 671.
Suppurative keratitis, 129.
Suprachorioid, 245.
Suture, Gaillard's, for entropion, 728; Snellen's, for ectropion, 730; Snellen's, for entropion, 730; tobacco-bag, 714.
Swelling cataract, 374, 377.
Symblepharon, 109, 493; anterius, 109; posterius, 65, 109; prevention of, in diphtheritic conjunctivitis, 83; totale, 109; treatment of, 110, 111.
Sympathetic inflammation, 289; iridocyclitis, 289, 292; irritation of eye, 289, 292; ophthalmia, 289, 292, 296, 298.
Sympathetic, paralysis of, 308.
Synchysis corporis vitrei, 396; scintillans, 398.
Syndesmitis catarrhalis, 40.
Synechia, annular posterior, 270, 280, 297, 298; anterior, 142, 297; anterior, occurring without perforation of cornea, 195; posterior, 269, 280, 297, 298; total, posterior, 271, 273, 281, 297.
Syphilis, hereditary, symptoms of, 176, 181; producing blennorrhœa of lachrymal sac, 513; producing optic neuritis, 436; producing parenchymatous keratitis, 175.
Syphilitic disease of skin causing conjunctivitis, 98; iritis, 285, 292, 295; keratitis, 175; neuritis, 436; paralysis of accommodation, 661; paralysis of ocular muscles, 554; retinitis, 404; tarsitis, 486; ulcers of conjunctiva, 104.
Syringe, Anel's, 514, 740.

Tabes causing paralysis of accommodation, 661; causing simple atrophy of optic nerve, 442.

Tapetum of the carnivora, 10.
Tar, preparations of, in blepharitis, 481.
Tarsal arches, inferior and superior, 32.
Tarsitis syphilitica, 486.
Tarsorrhaphia lateralis, 726; medialis, 726, 727.
Tarsorrhaphy, 726; in Basedow's disease, 590; in cicatricial ectropion, 731; lateral, 726; median, 727; provisional, 728, 732.
Tarsus, 463; diseases of, 486; straightening of, 722.
Tattooing of cornea, 194.
Tattooing-needles, 194, 741.
Teale's apparatus for suction of cataract, 744; operation for symblepharon, 111.
Tears, abolition of secretion of, 523; composition of, 510; conduction of, to nose, 510; excessive secretion of, 522; secretion of, 510; secretion of, in xerosis conjunctivæ, 113.
Teichopsia, 449.
Telangiectasis of lids, 505; of orbit, 592.
Temporal hemiopia, 429.
Temporary canthoplasty, 725; tarsorrhaphy, 728, 732.
Tendency to fusion of double images, 540.
Tenonitis, 585; diagnosis of, 475.
Tenon's capsule, 525, 578; space, 250, 578.
Tenotomy, 705; accidents after, 713; bilateral, when indicated, 711; effect of, how diminished, 712; effect of, how increased, 711; exophthalmus after, 713; final result of, 712; graduated, 712; how acting, 710; instruments for, 739; partial, 706, 712; sinking in of caruncle after, 713.
Tenotomy-hook, 739.
Tenotomy-scissors, 739.
Tension, intra-ocular, 253; diminution of, 360; how affected by miotics and mydriatics, 264; increase of, causing ectasiæ of sclera, 229; increase of, following discission, 689; increase of, how causing mydriasis, 307; increase of, how produced in glaucoma, 349; increase of, in primary and secondary glaucoma, 332; increase of, in staphyloma of cornea, 200, 205; increase of, reduced by iridectomy, 356; in cyclitis, 274; measurement of, 4, 254.
Tensor tarsi, 466; chorioideæ, 242.
Tesselated fundus, 16, 315.
Testing, functional, 20.
Test-types, Arlt's, 609; Jäger's, 608, 609; Snellen's, 608, 609; Snellen's, for detecting malingerers, 30.
Theobald's lachrymal probe, 740.
Theory of glasses, 598.
Thermo-cautery in conjunctivitis lymphatica, 90.
Third nerve, course of, 536; nucleus of, 537; paralysis of, 552.
Thread-operation, 710, 712.
Thrombosis of cavernous sinus, 475, 584; of central vein, 408.
Tinctura opii crocata, 46, 150; composition of, 150.
Tissue-paper test, 457.
Tobacco-amblyopia, 440.
Tobacco-bag suture, 714.
"Toilet" of the eye in cataract-extraction, 694.
Tone of ciliary muscle, 663.
Tonic spasms of ocular muscles, 576.
Tonometers, 255.
Torpid ulcer of cornea, 139.
Torpor retinæ, 164.
Total color-blindness, 456; ectasiæ of sclera, 229; excavation, 13, 335; hypermetropia, 643; posterior synechia, 271, 273, 281, 297; staphyloma of cornea, 197.
Trachoma, 59; acute, 63; anatomical characters of, 59, 74; Arlti, 74; brawny, 74; complications of, 61; complications of, treatment, 69; connection with acute blennorhœa, 77; connection with follicular conjunctivitis, 78; course, 61; diffusum, 74; dissemination of, 72; ectropion in, 65; endemic in Europe from the earliest times, 71; entropion in, 65; epidemic first when, 71; etiology of, 66, 79; folliculare, 74; geographical distribution of, 66; granular form of, 60, 73; history of, 71; hypertrophy in, varieties of, 59; intensity of, how varying, 62; microbe of, 79; mixtum, 74; opacities of cornea in, 66; pannus in, 60; papillary form of, 59, 72; prophylaxis of, 70; races, varying prevalence of, among, 66; radical treatment of, 79; sequelæ of, 64–66; sequelæ, treatment of, 70; statistics of,

71; symblepharon in, 65; symptoms of, 59; treatment of, 67–70; treatment of, radical, 79; trichiasis in, 65; ulcers of cornea in, 61, 151; varieties of, their interrelation, 77; verum, 74; xerosis in, 65.
Trachomatous conjunctivitis, 58; pannus, 60; ulcer of cornea, 61, 151.
Transparency of cornea, 128; of refracting media, how determined, 7.
Transplantation of cornea, 193; of zone of hair-follicles, 720.
Traumatic abscess of cornea, 156; cataract, 382, 386; dislocation of lens, 302, 392; iritis, 288, 296; paralyses of ocular muscles, 554; striped keratitis, 184; ulcers of cornea, 145, 151, 159.
Tremulous cataract, 377.
Trichiasis, 486; development of, in trachoma, 65; operations for, 719; relapses of, after operation, 723.
Trochlea, 524.
Trochlear nerve, 537; paralysis of, 552, 558.
True image, 532.
Tubercular iritis, 286; ulcers of conjunctiva, 102.
Tuberculosis of chorioid, 327; of conjunctiva, 102; of iris, 302, 304, 305; of lachrymal sac, 520.
Tumor cavernosus of lids, 505; lacrimalis, 511.
Tumors of brain producing choked disk, 437; of chorioid, 324; of ciliary body, 302; of conjunctiva, 115; of cornea, 210; of eyeball, enucleation for, 716; of iris, 302; of lids, 504; of optic nerve, 444, 716; of orbit, 591.
Tylosis, 477.
Typical hypermetropia, 644; myopia, 629.
Tyrrel's hook, 744.

Ulcer, asthenic, 139; atheromatous, 153; blennorrhœal, 151; catarrhal, 38, 151; central non-irritative, 151; cicatrization of, 139; cleansed, 126, 139; coated, 126, 138; foul, 126, 138; glaucomatous, 153; herpetic, 152; infiltrated, 126, 138; marginal, 152; of conjunctiva, 102; of cornea, see Cornea, Ulcer of; perforation of, 140; progressive, 126, 138; regeneration of, 134, 139, 142; regressive, 126, 139; rodent, 152, 506; syphilitic, 104; torpid, 139; trachomatous, 151; traumatic, 151, 159; tuberculous, 102; treatment of, 146, 150, 153, 154.
Ulcus corneæ, 138; corneæ rodens, 152; corneæ septicum, 159; corneæ serpens, 159; rodens (corneæ), 152; rodens (of lids), 506; septicum (corneæ), 159; serpens (corneæ), 159.
Unguentum emolliens in blepharitis, 479, 480.
Unguis, 136.
Unripe cataract, 374; artificial ripening of, 684; discission of, 689.
Uræmic amaurosis, 409.
Uvea, 234; anatomy and physiology of, 234; condition of, in glaucoma, 351; inflammation of, after operations, 672; participation of, in visual act, 256.
Uveal division of cornea, 125, 126; tract, 234.
Uveitis anterior, 172, 178.

Valences of colors, 455.
Valve, Hasner's, 511.
Valve-like closure of wounds in oblique incisions, 673.
Van Millingen's operation for trichiasis, 724.
Vaporization employed in cicatrizing ulcers of the cornea, 150; in parenchymatous keratitis, 177.
Variations of arrangement of vessels of optic nerve, 14.
Variola, abscess of cornea in, 157, 161.
Vascular fasciculus, 86, 151; funnel, 8.
Vascularization of cornea in keratitis, 132, 137.
Vein, central, 425; thrombosis of, 408.
Venæ vorticosæ, 248.
Venous pulse in vessels of optic nerve, 15.
Vernal catarrh, 94.
Vertical axis of eye, 525; diplopia, 531.
Vertigo in paralytic squint, 551.
Vesicle, ocular, primitive, 264; ocular, secondary, 365.
Vesicles upon cornea, 168.
Vesicular catarrh of conjunctiva, 41; keratitis, 168, 170.
Vessels of chorioid, etc. See Blood-vessels.
Vienna paste for obliteration of lachrymal sac, 516.

Violet-blindness, 452.
Virtual far-point in hypermetropia, 640; focus, 599; image, 599.
Visibility of opacities in the refractive media by ophthalmoscope, 8; of points, dependent on their brilliancy, 607.
Vision, after cataract-extraction, 698; binocular, 529, 539; central, 20; direct, 20; disturbances of, without apparent lesion, 445; double, 529, 539 (see also DIPLOPIA); in astigmatism, 651; in opacities of vitreous, variations of, 399; in strabismus, 564, 571; indirect, 20; peripheral, 20; qualitative, 609; quantitative, 609; spontaneous restoration of, in cataract, 380; solid, 539; stereoscopic, 539; tests for, in opacities of the refracting media, 681, 684; with excentric pupil, 685.
Visual acuity, 606; absolute, 610; diminution of, producing myopia, 633, 608; in cataract, 365; in opacities of vitreous, 399; in strabismus, 564, 571; relative, 610; tested with reference to central vision, 20; tests for, 607, 681, 684.
Visual angle, 607; field, see FIELD OF VISION; sensations, law governing, 428; sphere, 426.
Vitiated air producing conjunctivitis, 45.
Vitreous humor, 395; anatomy of, 395; artificial, 718; detachment of, 396; diseases of, 396; exudation into, in cyclitis, 274, 281; favoring the growth of germs, 223; foreign bodies in, 397; hæmorrhages into, 222, 398; liquefaction of, 396; luxation of lens into, 391, 697; nutrition of, how effected, 253; opacities of, 395, 397; prolapse of, in cataract-extraction, 697, 703; prolapse of, in iridectomy, 687; prolapse of, in iridotomy, 688.
Vitreous lamina of chorioid, 246.
Von Graefe's discovery of iridectomy in glaucoma, 335, 353; equilibrium test, 546; groping test, 549; linear knife, 702, 704; linear knife, uses of, 678–680, 686, 687, 693, 694; method of cataract-extraction, 693, 701–703; method of performing advancement, 710; method of performing tenotomy, 710; operation for ptosis, 734; symptom (in Basedow's disease), 589–591; theory of glaucoma, 349; thread-operation, 710, 712; tractor, 744.
Von Graefe, Alfred, his method of performing exenteration of eyeball, 718; rules for operation in paralytic strabismus, 709.
Von Walther's method of tarsorrhaphy, 726.
Vortices of the chorioid, 248.

Waldau's fixation-forceps, 667.
Waldeyer's mucous glands, 31, 465; glands assisting to keep the eyeball moist, 510.
Warmth, application of, in abscess of cornea, 157; in conjunctivitis lymphatica, 90; in diphtheritic conjunctivitis, 82; in iritis, 295; in keratitis neuroparalytica, 165; in keratitis profunda, 182; in keratomalacia, 164; in parenchymatous keratitis, in ulcers of the cornea, 147; method of, in eye-diseases, 147.
Warts on lids, 505.
Watered-silk reflex, 16.
Weber's canaliculus-knife, 514, 740; concave lance, 704, 744; double hook, 704, 744; loop, 697; method of cataract-extraction, 704; sound for gradual dilatation, 521, 740.
Weeping, 522.
Wenzel's method of cataract-extraction, 696.
Werneck's procedure in discission, 690.
Wernicke's hemiopic pupillary reaction, 433.
White-precipitate ointment in eczema, coryza, and blepharitis, 91, 479.
Winking, 462.
Wolfe's operation for symblepharon, 111.
Worsted test for color-blindness, 457.
Wound, operation-, external, 672; internal, 672; obliquity of, 672, 673; suppuration of, 671, 672.
Wounds of conjunctiva, 100; of cornea, 186; of eye, 216, 588; of eye, frequency of, 227; of iris, 299; of lids, 502; of optic nerve, 443; of orbit, 586; penetrating of eye, 216.

Xanthelasma, 504.
Xanthoma, 504.

Xerophthalmus, 65.
Xerosis, bacillus of, 113; conjunctivæ, 65, 111; epithelialis, 112; etiology of, 112; general, 112; glabra, 113; in trachoma, 65; local, 112; of cornea, 163, 168; parenchymatosa, 112; partialis, 113; pathology of, 113; squamosa, 113; symptoms of, 112; totalis, 113; varieties, 112, 113.

Yellow-spot, 400.
Yellow-oxide ointment, yellow-precipitate ointment, 90, 150, 177, 218.
Young-Helmholtz's theory of color-perception, 452.

Zeiss's glands, 463.
Zeissian sty, 482.
Zinc-oxide ointment in eczema of lids,
Zinc sulphate in conjunctivitis, 46.
Zinn, scleral circle of vessels of,
zonula of, 361, 363.
Zona ophthalmica, 169, 468.
Zone, interpalpebral, 467; nuclear lens, 363; of hair-follicles, ablatio 719; of hair-follicles, inversion of. of hair-follicles, transplantation of.
Zonula, 361.
Zonular cataract, 370; opacity of cor 190, 196.
Zonule of Zinn, 361, 363.

THE END.

TEXT-BOOK OF OPHTHALMOSCOPY

By EDWARD G. LORING, M. D.

Part I.

THE NORMAL EYE, DETERMINATION OF REFRACTION, DISEASES OF THE MEDIA, PHYSIOLOGICAL OPTICS, AND THEORY OF THE OPHTHALMOSCOPE.

Part II.

EDITED BY FRANCIS B. LORING, M. D.

DISEASES OF THE RETINA, OPTIC NERVE, AND CHORIOID, THEIR VARIETIES AND COMPLICATIONS.

AMERICAN LANCET.

"This is a beautiful book, the handsomest of its kind on this subject ever issued from an American press. The paper, press-work, and illustrations are gratifying to every person of correct tastes. The subject-matter is of such excellence as to be worthy of this beautiful dress. . . . His style is pleasant and easy. Avoiding the Scylla of too much technicality, he has not plunged into the Charybdis of too little. He will be doing a proper thing who adds this book to his working library."

CLEVELAND MEDICAL GAZETTE.

"We noticed in the Gazette the first part of this work, which appeared more than five years ago. In April, 1888, the talented author suddenly died, We feared the untimely death of Dr. Loring would prevent the completion of this work, which, on the whole, is the most creditable on ophthalmoscopy yet published by an American author; but, fortunately, he had already made notes and drawings enough to complete the second volume. The present editor, Dr. F. B. Loring, has published the work almost as he found it in the penciled notes of the author. The book before us is characterized by the original drawings and elaboration of clinical cases coming under the observation of the author, which characterized the former volume. The subjects treated in this part are diseases of the retina, of the nerve, and of the chorioid, their varieties and complications."

NEW YORK: D. APPLETON & CO., PUBLISHERS, 1, 3, & 5 BOND STREET.

A TREATISE ON THE DISEASES OF THE NERVOUS SYSTEM.

By WILLIAM A. HAMMOND, M. D.,
Surgeon-General U. S. Army (retired list).

With the Collaboration of GRAEME M. HAMMOND, M. D.,
Professor of Diseases of the Mind and Nervous System in the New York Post-Graduate Medical School and Hospital, etc.

With 118 Illustrations.

NINTH EDITION, WITH CORRECTIONS AND ADDITIONS.

8vo. 932 pages. Cloth, $5.00; sheep, $6.00.

"Dr. Hammond's treatise on the diseases of the nervous system is a work which has been long familiar to the profession, and has attained a great reputation among the standard books for reference. In the preparation of the present edition the author has been aided by his son. A vast amount of clinical material is made use of, and the results of experimental investigation recorded. The book is written in a clear and pleasing style, and obscure conditions are dealt with in a manner which will prove of great assistance in the study of this most interesting class of diseases."—*Canadian Practitioner.*

"Dr. Hammond published the first edition of his 'Treatise on Diseases of the Nervous System' in 1871. It has therefore been before the profession for twenty years, and during these years it has continued to grow in public favor, this being the ninth edition that has been issued. Appreciation of this work has not only been shown in this country, but abroad, as it has been translated into the French, the Italian, and the Spanish languages. The present edition has been thoroughly revised, and several new chapters added. This is a book of such great value, and is referred to so frequently by the medical press and other medical works, that no library is complete without it."—*Alabama Medical and Surgical Age.*

"There are few books, even upon those subjects which are constantly in the ordinary physician's mind, which succeed as has that of Dr. Hammond; and when we recollect that when the first edition of this work appeared, neurology in America was in its very infancy, the rapid exhaustion of its editions is the more remarkable. In the ninth edition the writer's son has done much toward keeping the work abreast of the times, and, with more confidence than ever, it can now be regarded as one of the best and most satisfactory works on nervous diseases, either for the practitioner or for the advanced student. The book is beautified and its usefulness increased by a larger number of illustrations than heretofore—among the best from a medical point of view being those representing syringo-myelia, which have been taken from the studies of Van Giesen."—*Medical News.*

New York: D. APPLETON & CO., 1, 3, & 5 Bond Street.

THE PRINCIPLES AND PRACTICE OF MEDICINE.

Designed for the Use of Practitioners and Students of Medicine.

By WILLIAM OSLER, M. D.,

Fellow of the Royal College of Physicians, London; Professor of Medicine in the Johns Hopkins University, and Physician-in-Chief of the Johns Hopkins Hospital, Baltimore.

SOLD ONLY BY SUBSCRIPTION.

8vo. Cloth, $5.50; sheep, $6.50; half morocco, $7.00.

"By reason of extensive clinical, pathologic, and teaching experience, of exceptional opportunity and broad training, and of rare scientific attainments, there are few men better qualified than Dr. Osler to write a work on the Practice of Medicine. Here in Philadelphia, where Dr. Osler spent but too few busy years, he will not soon be forgotten; the impress of his work and character will long remain, and the impetus given to careful pathologic study and observation will be transmitted through his colleagues, his assistants, and his pupils. To say that Dr. Osler has performed his task well, is but to echo the verdict concerning the work he has done in the past. If there were one fault of which we would complain, it is expressed in the wish that he had said more than he has. Everywhere throughout the work one feels the delightful personality of the man. Every page contains evidences of original observation, and is marked by an enlightened conservatism. It would be difficult to select any one section and say that it is much better than the others. All are conspicuous for their comprehensiveness. The descriptions are in places concise, but there are no important omissions. Dr. Osler's work needs no special laudation. It speaks for itself. We most heartily commend his 'Practice of Medicine' to those who desire to be in possession of the most recent and best knowledge on the subject with which it has to deal."—*Medical News.*

"This volume exhibits originality at the very beginning, inasmuch as there is no preface. The author does not take us into his confidence as to his motive for adding another book on the 'Principles and Practice of Medicine' to those which have preceded his. He does not tell us whether it is because there were too many good ones or too many bad ones; whether the publisher tempted him, or his university demanded it; or whether it was simply that he had noticed that 'they all do it.' He skips into the public presence without a word, but with a sort of air which suggests: 'Here I am! Take me, or leave me, but you had better do the former!' He had probably heard that good wine needs no bush; and as he has written a good book, with an excellent dedication and some sound aphorisms from the Greek on the first sheet, it mattered less about his motives. At any rate, after the table of contents and a list of charts and illustrations, we find ourselves plunging immediately into typhoid fever, which heads Section I (on 'Specific Infectious Diseases') of this royal octavo volume of 1,080 pages. No preliminaries are devoted to such abstract subjects as nosology, symptomatology, etiology, inflammation, fever, etc. In this respect Osler's book resembles Strümpell's. The style in which Dr. Osler's book is written is clear, concise, and at the same time animated. The type is very good. The finish of the paper is excellent, but the texture is not strong, and we doubt whether it stands well the strain of the eager student who will certainly want to use it often and much, or the inadvertence of the busy practitioner who will sometimes consult it hastily. The book has evidently been 'trained down' as much as possible to secure handiness without sacrificing even more important essentials. We should be glad to be able to think and speak as highly of every medical book presented for review as we can of this. In truth, had our enemy written it, we should be unable to find much consolation in his commitment."—*Boston Medical and Surgical Journal.*

New York: D. APPLETON & CO., 1, 3, & 5 Bond Street.

THE RULES OF ASEPTIC AND ANTISEPTIC SURGERY.

A PRACTICAL TREATISE FOR THE USE OF STUDENTS AND THE GENERAL PRACTITIONER.

By ARPAD G. GERSTER, M. D.,

PROFESSOR OF SURGERY AT THE NEW YORK POLYCLINIC; VISITING SURGEON TO THE GERMAN HOSPITAL AND TO MOUNT SINAI HOSPITAL, NEW YORK.

THIRD EDITION, REVISED.

8vo. Illustrated with Two Hundred and Forty-eight Fine Engravings. Cloth, $5.00; sheep, $6.00.

The attention of the Medical Profession is invited to the following points of excellence in this work:

It deals only with matters of practical interest to, and questions that are likely to arise daily in the work of the practicing physician. Its scope is a terse yet clear exposition of the principles governing modern operative surgery. It enters into the practical details of all the varying conditions of the application of the antiseptic method as brought about by emergencies. Every important principle is clearly illustrated by citations from actual cases occurring in the author's practice.

It is not intended to take the place of any text-book on surgery, but rather to supply a need which exists in every work on the subject in the English language, by furnishing information on the subject of Asepsis and Antisepsis, with which no book on surgery deals to an extent demanded by modern methods. It is, in short, a supplement to all surgical text-books.

The illustrations are typo-gravures, made from photographic negatives taken from life, and are marvels of beauty, artistic elegance, and fidelity; each illustration being a faithful representation, by the camera, of the details of the application of all important antiseptic dressings and apparatus, approaching nearer to an actual demonstration than has ever before been attempted to be done in any medical work. With the exception of a few bacteriological illustrations taken from Koch, Rosenbach, and Bumm, the illustrations are from negatives made *in the operating-room*, and are of a character now for the first time employed in a medical work.

The work has been adopted by the Medical Department of the United States Army.

New York: D. APPLETON & CO., Publishers, 1, 3, & 5 Bond Street.

February, 1893.

MEDICAL

AND

HYGIENIC WORKS

PUBLISHED BY

D. APPLETON & CO., 1, 3, & 5 Bond Street, New York.

AULDE (JOHN). The Pocket Pharmacy, with Therapeutic Index. A *résumé* of the Clinical Applications of Remedies adapted to the Pocket-case, for the Treatment of Emergencies and Acute Diseases. 12mo. Cloth, $2.00.

BARKER (FORDYCE). On Sea-Sickness. A Popular Treatise for Travelers and the General Reader. Small 12mo. Cloth, 75 cents.

BARKER (FORDYCE). On Puerperal Disease. Clinical Lectures delivered at Bellevue Hospital. A Course of Lectures valuable alike to the Student and the Practitioner. Third edition. 8vo. Cloth, $5.00; sheep, $6.00.

BARTHOLOW (ROBERTS). A Treatise on Materia Medica and Therapeutics. **Seventh edition.** Revised, enlarged, and adapted to "The New Pharmacopœia." 8vo. Cloth, $5.00; sheep, $6.00.

BARTHOLOW (ROBERTS). A Treatise on the Practice of Medicine, for the Use of Students and Practitioners. **Sixth edition,** revised and enlarged. 8vo. Cloth, $5.00; sheep, $6.00.

BARTHOLOW (ROBERTS). On the Antagonism between Medicines and between Remedies and Diseases. Being the Cartwright Lectures for the Year 1880. 8vo. Cloth, $1.25.

BILLINGS (F. S.). The Relation of Animal Diseases to the Public Health, and their Prevention. 8vo. Cloth, $4.00.

BILLROTH (THEODOR). General Surgical Pathology and Therapeutics. A Text-Book for Students and Physicians. Translated from the tenth German edition, by special permission of the author, by Charles E. Hackley, M. D. **Fifth American edition, revised and enlarged.** 8vo. Cloth, $5.00; sheep, $6.00.

BOYCE (RUBERT). A Text-Book of Morbid Histology. For Students and Practitioners. With 130 Colored Illustrations. Cloth, $7.50.

BRAMWELL (BYROM). Diseases of the Heart and Thoracic Aorta. Illustrated with 226 Wood-Engravings and 68 Lithograph Plates—showing 91 Figures—in all 317 Illustrations. 8vo. Cloth, $8.00; sheep, $9.00.

BRYANT (JOSEPH D.). A Manual of Operative Surgery. **New edition, revised and enlarged.** 793 Illustrations. 8vo. Cloth, $5.00; sheep, $6.00

BUCK (GURDON). Contributions to Reparative Surgery, showing its Application to the Treatment of Deformities produced by Destructive Disease or Injury; Congenital Defects from Arrest or Excess of Development; and Cicatricial Contractions following Burns. Illustrated by Thirty Cases and fine Engravings. 8vo. Cloth, $3.00.

CAMPBELL (F. R.). The Language of Medicine. A Manual giving the Origin, Etymology, Pronunciation, and Meaning of the Technical Terms found in Medical Literature. 8vo. Cloth, $3.00.

CASTRO (D'OLIVEIRA). Elements of Therapeutics and Practice according to the Dosimetric System. 8vo. Cloth, $4.00.

CHAUVEAU (A.) The Comparative Anatomy of the Domesticated Animals. By A. Chauveau, M. D., LL. D., Member of the Institute (Academy of Sciences); Inspector-General of Veterinary Schools in France; Professor at the Museum of Natural History, Paris. Revised and enlarged, with the co-operation of S. Arloing, Director of the Lyons Veterinary School; Professor of Experimental and Comparative Medicine at the Lyons Faculty of Medicine. Second English edition. Translated and edited by George Fleming, C. B., LL. D., F. R. C. V. S., late Principal Veterinary Surgeon of the British Army; Foreign Corresponding Member of the Société Royale de Médecine, and of the Société Royale de Médicine Publique, of Belgium, etc. 8vo, with 585 Illustrations. Cloth, $7.00.

CORNING (J. L.). Brain Exhaustion, with some Preliminary Considerations on Cerebral Dynamics. Crown 8vo. Cloth, $2.00.

CORNING (J. L.). Local Anæsthesia in General Medicine and Surgery. Being the Practical Application of the Author's Recent Discoveries. With Illustrations. Small 8vo. Cloth, $1.25.

DAVIDSON (ANDREW). Geographical Pathology: An Inquiry into the Geographical Distribution of Infective and Climatic Diseases. 2 vols. 8vo. Cloth, $7.00.

DEXTER (FRANKLIN). The Anatomy of the Peritonæum. 12mo. With 39 colored Illustrations. (*In press.*)

DOTY (ALVAH H.). A Manual of Instruction in the Principles of Prompt Aid to the Injured. Designed for Military and Civil Use. 96 Illustrations. 12mo. Cloth, $1.25.

ELLIOT (GEORGE T.). Obstetric Clinic: A Practical Contribution to the Study of Obstetrics and the Diseases of Women and Children. 8vo. Cloth, $4.50.

EVANS (GEORGE A.). Hand-Book of Historical and Geographical Phthisiology. With Special Reference to the Distribution of Consumption in the United States. 8vo. Cloth, $2.00.

EWALD (C. A.). Lectures on the Diseases of the Stomach. By Dr. C. A. Ewald, Professor of Pathology and Therapeutics in the University of Berlin, etc. Translated from the German by special permission of the author, by Morris Manges, A. M., M. D. Cloth, $5.00; sheep, $6.00.

FLINT (AUSTIN). Medical Ethics and Etiquette. Commentaries on the National Code of Ethics. 12mo. Cloth, 60 cents.

FLINT (AUSTIN). Medicine of the Future. An Address prepared for the Annual Meeting of the British Medical Association in 1886. With Portrait of Dr. Flint. 12mo. Cloth, $1.00.

FLINT (AUSTIN, JR.). Text-Book of Human Physiology; designed for the Use of Practitioners and Students of Medicine. Illustrated with three hundred and sixteen Woodcuts and Two Plates. **Fourth edition, revised.** Imperial 8vo. Cloth, $6.00; sheep, $7.00.

FLINT (AUSTIN, JR.). The Physiological Effects of Severe and Protracted Muscular Exercise; with Special Reference to its Influence upon the Excretion of Nitrogen. 12mo. Cloth, $1.00.

FLINT (AUSTIN, JR.). The Source of Muscular Power. Arguments and Conclusions drawn from Observation upon the Human Subject under Conditions of Rest and of Muscular Exercise. 12mo. Cloth, $1.00.

FLINT (AUSTIN, JR.). Physiology of Man. Designed to represent the Existing State of Physiological Science as applied to the Functions of the Human Body. Complete in 5 vols., 8vo. Per vol., cloth, $4.50; sheep, $5.50.

*** Vols. I and II can be had in cloth and sheep binding; Vol. III in sheep only. Vol. IV is at present out of print.

FLINT (AUSTIN, JR.). Manual of Chemical Examinations of the Urine in Disease; with Brief Directions for the Examination of the most Common Varieties of Urinary Calculi. Revised edition. 12mo. Cloth, $1.00.

FOSTER (FRANK P.). Illustrated Encyclopædic Medical Dictionary, being a Dictionary of the Technical Terms used by Writers on Medicine and the Collateral Sciences in the Latin, English, French, and German Languages. This work will be completed in four volumes. (*Sold only by subscription.*) The work will consist of Four Volumes, and will be sold in Parts; Three Parts to a Volume. Nine Parts are now ready for delivery.

FOURNIER (ALFRED). Syphilis and Marriage. Translated by P. Albert Morrow, M. D. 8vo. Cloth, $2.00; sheep, $3.00.

FREY (HEINRICH). The Histology and Histochemistry of Man. A Treatise on the Elements of Composition and Structure of the Human Body. Translated from the fourth German edition by Arthur E. J. Barker, M. D., and revised by the author. With 608 Engravings on Wood. 8vo. Cloth, $5.00; sheep, $6.00.

FRIEDLANDER (CARL). The Use of the Microscope in Clinical and Pathological Examinations. Second edition, enlarged and improved, with a Chromo-lithograph Plate. Translated, with the permission of the author, by Henry C. Coe, M. D. 8vo. Cloth, $1.00.

FUCHS (ERNEST). Text-Book of Ophthalmology. By Dr. Ernest Fuchs, Professor of Ophthalmology in the University of Vienna. With 178 Woodcuts. Authorized translation from the second enlarged and improved German edition, by A. Duane, M. D. Cloth, $5.00; sheep, $6.00.

GARMANY (JASPER J.). Operative Surgery on the Cadaver. With Two Colored Diagrams showing the Collateral Circulation after Ligatures of Arteries of Arm, Abdomen, and Lower Extremity. Small 8vo. Cloth, $2.00.

GERSTER (ARPAD G.). The Rules of Aseptic and Antiseptic Surgery. A Practical Treatise for the Use of Students and the General Practitioner. Illustrated with over two hundred fine Engravings. 8vo. Cloth, $5.00; sheep, $6.00.

GIBSON-RUSSELL. Physical Diagnosis: A Guide to Methods of Clinical Investigation. By G. A. Gibson, M. D., and William Russell, M. D. With 101 Illustrations. 12mo. (STUDENT'S SERIES.) Cloth, $2.50.

GOULEY (JOHN W. S.). Diseases of the Urinary Apparatus. Part I. Phlegmasic Affections. Being a Series of Twelve Lectures delivered during the autumn of 1891. With an Addendum on Retention of Urine from Prostatic Obstruction in Elderly Men. Cloth, $1.50.

GROSS (SAMUEL W.). A Practical Treatise on Tumors of the Mammary Gland. Illustrated. 8vo. Cloth, $2.50.

GRUBER (JOSEF). A Text-Book of the Diseases of the Ear. Translated from the second German edition by special permission of the author, and edited by Edward Law, M. D., and Coleman Jewell, M. D. With 150 Illustrations and 70 Colored Figures on Two Lithographic Plates. 8vo. Cloth, $5.00.

GUTMANN (EDWARD). The Watering-Places and Mineral Springs of Germany, Austria, and Switzerland. Illustrated. 12mo. Cloth, $2.50.

HAMMOND (W. A.). A Treatise on Diseases of the Nervous System. With the Collaboration of Graeme M. Hammond, M. D. With One Hundred and Eighteen Illustrations. **Ninth edition,** with corrections and additions. 8vo. Cloth, $5.00; sheep, $6.00.

HAMMOND (W. A.). A Treatise on Insanity, in its Medical Relations. 8vo. Cloth, $5.00; sheep, $6.00.

HAMMOND (W. A.). Clinical Lectures on Diseases of the Nervous System. Delivered at Bellevue Hospital Medical College. Edited by T. M. B. Cross, M. D. 8vo. Cloth, $3.50.

HARVEY (A.). First Lines of Therapeutics. 12mo. Cloth. $1.50.

HOFFMANN–ULTZMANN. Analysis of the Urine, with Special Reference to Diseases of the Urinary Apparatus. By M. B. Hoffmann, Professor in the University of Gratz; and R. Ultzmann, Tutor in the University of Vienna. **Third edition, revised and enlarged.** 8vo. Cloth, $2.00.

HIRT (LUDWIG). The Pathology and Therapeutics of Nervous Diseases. For Physicians and Students. By Dr. Ludwig Hirt, Professor at the University of Breslau. Translated by Aug. Hoch, M. D., Assistant Physician to the Johns Hopkins Hospital. With an Introduction by William Osler, M. D., Professor of Medicine in the Johns Hopkins University, and Physician-in-Chief to the Johns Hopkins Hospital, Baltimore. With Illustrations. *(In preparation.)*

HOWE (JOSEPH W.). Emergencies, and how to treat them. Fourth edition, revised. 8vo. Cloth, $2.50.

HOWE (JOSEPH W.). The Breath, and the Diseases which give it a Fetid Odor. With Directions for Treatment. **Second edition,** revised and corrected. 12mo. Cloth, $1.00.

HUEPPE (FERDINAND). The Methods of Bacteriological Investigation. Written at the request of Dr. Robert Koch. Translated by Hermann M. Biggs, M. D. Illustrated. 8vo. Cloth, $2.50.

JACCOUD (S.). The Curability and Treatment of Pulmonary Phthisis. Translated and edited by Montagu Lubbock, M. D. 8vo. Cloth, $4.00.

JOHNSTONE (ALEX.). Botany: A Concise Manual for Students of Medicine and Science. With 164 Illustrations and a Series of Floral Diagrams. 12mo. (STUDENT'S SERIES.) Cloth, $1.75.

JONES (H. MACNAUGHTON). Practical Manual of Diseases of Women and Uterine Therapeutics. For Students and Practitioners. 188 Illustrations. 12mo. Cloth, $3.00.

JOURNAL OF CUTANEOUS AND GENITO-URINARY DISEASES. Published Monthly. Edited by John A. Fordyce, M. D. Terms, $2.50 per annum.

KEYES (E. L.). A Practical Treatise on Genito-Urinary Diseases, including Syphilis. Being a new edition of a work with the same title, by Van Buren and Keyes. Almost entirely rewritten. 8vo. With Illustrations. Cloth, $5.00; sheep, $6.00.

KEYES (E. L.). The Tonic Treatment of Syphilis, including Local Treatment of Lesions. 8vo. Cloth, $1.00.

KINGSLEY (N. W.). A Treatise on Oral Deformities as a Branch of Mechanical Surgery. With over 350 Illustrations. 8vo. Cloth, $5.00; sheep, $6.00.

LEGG (J. WICKHAM). On the Bile, Jaundice, and Bilious Diseases. With Illustrations in Chromo-Lithography. 8vo. Cloth, $6.00; sheep, $7.00.

LITTLE (W. J.). Medical and Surgical Aspects of In-Knee (Genu-Valgum): its Relation to Rickets, its Prevention, and its Treatment, with and without Surgical Operation. Illustrated by upward of Fifty Figures and Diagrams. 8vo. Cloth, $2.00.

LORING (EDWARD G.). A Text-Book of Ophthalmoscopy.

Part I. The Normal Eye, Determination of Refraction, and Diseases of the Media. With 131 Illustrations, and 4 Chromo-Lithographs. 8vo. Buckram, $5.00.

Part II. Diseases of the Retina, Optic Nerve, and Choroid: their Varieties and Complications. The manuscript of this volume, which the author finished just prior to his death, has been thoroughly edited and revised by F. B. Loring, M. D., of Washington, D. C., and is now issued in the same style as the first volume. Profusely illustrated. Part II, buckram, $5.00. Two Parts, buckram, $10.00.

LUSK (WILLIAM T.). The Science and Art of Midwifery. With 246 Illustrations. **Fourth edition, revised and enlarged.** 8vo. Cloth, $5.00; sheep, $6.00

MARCY (HENRY O.). The Anatomy and Surgical Treatment of Hernia. 4to, with about Sixty full-page Heliotype and Lithographic Reproductions from the Old Masters, and numerous Illustrations in the Text. *(Sold only by subscription.)*

MARKOE (T. M.). A Treatise on Diseases of the Bones. With Illustrations. 8vo. Cloth, $4.50.

MATHEWS (JOSEPH M.). A Treatise on Diseases of the Rectum, Anus, and Sigmoid Flexure. 8vo. With Six Chromo-lithographs, and Illustrations in the text. *(Sold only by subscription.)*

MILLS (WESLEY). A Text-Book of Animal Physiology, with Introductory Chapters on General Biology and a full Treatment of Reproduction for Students of Human and Comparative Medicine. 8vo. With 505 Illustrations. Cloth, $5.00; sheep, $6.00.

MILLS (WESLEY). A Text-Book of Comparative Physiology. For Students and Practitioners of Veterinary Medicine. Small 8vo. Cloth, $3.00.

THE NEW YORK MEDICAL JOURNAL (weekly). Edited by Frank P Foster, M. D. Terms, $5.00 per annum.

Binding Cases, cloth, 50 cents each.

"Self-Binder" (this is used for temporary binding only), 90 cents.

GENERAL INDEX, from April, 1865, to June, 1876 (23 vols.) 8vo. Cloth, 75 cts.

NIEMEYER (FELIX VON). A Text-Book of Practical Medicine, with particular reference to Physiology and Pathological Anatomy. Containing all the author's Additions and Revisions in the eighth and last German edition. Translated by George H. Humphreys, M. D., and Charles E. Hackley, M. D. 2 vols., 8vo. Cloth, $9.00; sheep, $11.00.

NIGHTINGALE'S (FLORENCE) Notes on Nursing. 12mo. Cloth, 75 cents.

OSLER (WILLIAM). The Principles and Practice of Medicine. Designed for the Use of Practitioners and Students of Medicine. Sold only by subscription. Cloth, $5.50; sheep, $6.50; half morocco, $7.00.

PELLEW (C. E.). A Manual of Practical Medical Chemistry. 12mo. With Illustrations. (*In press.*)

PEREIRA'S (Dr.) Elements of Materia Medica and Therapeutics. Abridged and adapted for the Use of Medical and Pharmaceutical Practitioners and Students, and comprising all the Medicines of the British Pharmacopœia, with such others as are frequently ordered in Prescriptions, or required by the Physician. Edited by Robert Bentley and Theophilus Redwood. Royal 8vo. Cloth, $7.00; sheep, $8.00.

PEYER (ALEXANDER). An Atlas of Clinical Microscopy. Translated and edited by Alfred C. Girard, M. D. First American, from the manuscript of the second German edition, with Additions. Ninety Plates, with 100 Illustrations, Chromo-Lithographs. Square 8vo. Cloth, $6.00.

PIFFARD (HENRY G.). A Practical Treatise on Diseases of the Skin. By Henry G. Piffard, A. M. M. D., assisted by Robert M. Fuller, M. D. With Fifty full-page Original Plates and Thirty-three Illustrations in the Text. 4to. (*Sold only by subscription.*)

POMEROY (OREN D.). The Diagnosis and Treatment of Diseases of the Ear. With One Hundred Illustrations. **Second edition,** revised and enlarged. 8vo. Cloth, $3.00.

POORE (C. T.). Osteotomy and Osteoclasis, for the Correction of Deformities of the Lower Limbs. 50 Illustrations. 8vo. Cloth, $2.50.

QUAIN (RICHARD). A Dictionary of Medicine, including General Pathology, General Therapeutics, Hygiene, and the Diseases peculiar to Women and Children. By Various Writers. Edited by Richard Quain, M. D., In one large 8vo volume, with complete Index, and 138 Illustrations. (*Sold only by subscription.*)

RANNEY (AMBROSE L.). Applied Anatomy of the Nervous System, being a Study of this Portion of the Human Body from a Standpoint of its General Interest and Practical Utility, designed for Use as a Text-Book and as a Work of Reference. **Second edition, revised and enlarged.** Profusely illustrated. 8vo. Cloth, $5.00; sheep, $6.00.

ROBINSON (A. R.). A Manual of Dermatology. Revised and corrected. 8vo. Cloth, $5.00.

ROSCOE-SCHORLEMMER. Treatise on Chemistry.

Vol. 1. Non-Metallic Elements. 8vo. Cloth, $5.00.

Vol. 2. Part I. Metals. 8vo. Cloth, $3.00.

Vol. 2. Part II. Metals. 8vo. Cloth, $3.00.

Vol. 3. Part I. The Chemistry of the Hydrocarbons and their Derivatives. 8vo. Cloth, $5.00.

Vol. 3. Part II. The Chemistry of the Hydrocarbons and their Derivatives. 8vo. Cloth, $5.00.

Vol. 3. Part III. The Chemistry of the Hydrocarbons and their Derivatives. 8vo. Cloth, $3.00.

Vol. 3. Part IV. The Chemistry of the Hydrocarbons and their Derivatives. 8vo. Cloth, $3.00.

Vol. 3. Part V. The Chemistry of the Hydrocarbons and their Derivatives. 8vo. Cloth, $3.00.

ROSENTHAL (I.). General Physiology of Muscles and Nerves. With 75 Wood cuts. 12mo. Cloth, $1.50.

SAYRE (LEWIS A.). Practical Manual of the Treatment of Club-Foot. **Fourth edition, enlarged and corrected.** 12mo. Cloth, $1.25.

SAYRE (LEWIS A.). Lectures on Orthopedic Surgery and Diseases of the Joints, delivered at Bellevue Hospital Medical College. **New edition,** illustrated with 224 Engravings on Wood. 8vo. Cloth, $5.00; sheep, $6.00.

SCHULTZE (B. S.). The Pathology and Treatment of Displacements of the Uterus. Translated from the German by Jameson J. Macan, M. A., etc.; and edited by Arthur V. Macan, M. B., etc. With One Hundred and Twenty Illustrations. 8vo. Cloth, $3.50.

SHIELD (A. MARMADUKE). Surgical Anatomy for Students. 12mo. (STUDENT'S SERIES.) Cloth, $1.75.

SHOEMAKER (JOHN V.). A Text-Book of Diseases of the Skin. Six Chromo-Lithographs and numerous Engravings. Second edition, revised and enlarged. 8vo. Cloth, $5.00; sheep, $6.00.

SIMPSON (JAMES Y.). Selected Works: Anæsthesia, Diseases of Women. 3 vols., 8vo. Per volume. Cloth, $3.00; sheep, $4.00.

SIMS (J. MARION). The Story of my Life. Edited by his Son, H. Marion Sims, M. D. With Portrait. 12mo. Cloth, $1.50.

SKENE (ALEXANDER J. C.). A Text-Book on the Diseases of Women. Illustrated with two hundred and fifty-four Illustrations, of which one hundred and sixty-five are original, and nine chromo-lithographs. Second edition. 8vo. (*Sold only by subscription.*)

STEINER (JOHANNES). Compendium of Children's Diseases: a Hand-Book for Practitioners and Students. Translated from the second German edition, by Lawson Tait. 8vo. Cloth, $3.50; sheep, $4.50.

STEVENS (GEORGE T.) Functional Nervous Diseases: their Causes and their Treatment. Memoir for the Concourse of 1881–1883, Académie Royal de Médecine de Belgique. With a Supplement, on the Anomalies of Refraction and Accommodation of the Eye, and of the Ocular Muscles. Small 8vo. With six Photographic Plates and twelve Illustrations. Cloth, $2.50.

STONE (R. FRENCH). Elements of Modern Medicine, including Principles of Pathology and of Therapeutics, with many Useful Memoranda and Valuable Tables of Reference. Accompanied by Pocket Fever Charts. Designed for the Use of Students and Practitioners of Medicine. In wallet-book form, with pockets on each cover for Memoranda, Temperature Charts, etc. Roan, tuck, $2.50.

STRECKER (ADOLPH). Short Text-Book of Organic Chemistry. By Dr. Johannes Wislicenus. Translated and edited, with Extensive Additions, by W. H. Hodgkinson and A. J. Greenaway. 8vo. Cloth, $5.00.

STRÜMPELL (ADOLPH). A Text-Book of Medicine, for Students and Practitioners. With 111 Illustrations. 8vo. Cloth, $6.00; sheep, $7.00.

THOMAS (T. GAILLARD). Abortion and its Treatment, from the Standpoint of Practical Experience. A Special Course of Lectures delivered before the College of Physicians and Surgeons, New York, Session of 1889–'90. From Notes by P. Brynberg Porter, M. D. Revised by the Author. 12mo. Cloth, $1.00.

THOMSON (J. ARTHUR). Outlines of Zoölogy. With Thirty-two full-page Illustrations. 12mo. Cloth, $3.00.

TRACY (ROGER S.). The Essentials of Anatomy, Physiology, and Hygiene. 12mo. Cloth. $1.25.

TRANSACTIONS OF THE NEW YORK STATE MEDICAL ASSOCIATION, VOLS. I and II. Being the Proceedings of the First Annual Meeting of the New York State Medical Association, held in New York, November 18, 19, and 20, 1884. Small 8vo. Cloth, $5.00.

TYNDALL (JOHN). Essays on the Floating Matter of the Air, in Relation to Putrefaction and Infection. 12mo. Cloth. $1.50.

ULTZMANN (ROBERT). Pyuria, or Pus in the Urine, and its Treatment. Translated by permission, by Dr. Walter B. Platt. 12mo. Cloth, $1.00.

VAN BUREN (W. H.). Lectures upon Diseases of the Rectum, and the Surgery of the Lower Bowel, delivered at Bellevue Hospital Medical College. **Second edition, revised and enlarged.** 8vo. Cloth, $3.00; sheep, $4.00.

VAN BUREN (W. H.). Lectures on the Principles and Practice of Surgery. Delivered at Bellevue Hospital Medical College. Edited by Lewis A. Stimson, M. D. 8vo. Cloth, $4.00; sheep, $5.00.

VOGEL (A.). A Practical Treatise on the Diseases of Children. Translated and edited by H. Raphael, M. D. **Third American from the eighth German edition, revised and enlarged.** Illustrated by six Lithographic Plates. 8vo. Cloth, $4.50; sheep, $5.50.

VON ZEISSL (HERMANN). Outlines of the Pathology and Treatment of Syphilis and Allied Venereal Diseases. **Second edition,** revised by Maximilian von Zeissl. Authorized edition. Translated, with Notes, by H. Raphael, M. D. 8vo. Cloth, $4.00; sheep, $5.00.

WAGNER (RUDOLF). Hand-Book of Chemical Technology. Translated and edited from the eighth German edition, with extensive Additions, by William Crookes. With 336 Illustrations. 8vo. Cloth, $5.00.

WALTON (GEORGE E.). Mineral Springs of the United States and Canadas. Containing the latest Analyses, with full Description of Localities, Routes, etc. **Second edition, revised and enlarged.** 12mo. Cloth, $2.00.

WEBBER (S. G.). A Treatise on Nervous Diseases: Their Symptoms and Treatment. A Text-Book for Students and Practitioners. 8vo. Cloth, $3.00.

WEEKS-SHAW (CLARA S.). A Text-Book of Nursing. For the Use of Training-Schools, Families, and Private Students. Second edition, revised and enlarged. 12mo. With Illustrations, Questions for Review and Examination, and Vocabulary of Medical Terms. 12mo. Cloth, $1.75.

WELLS (T. SPENCER). Diseases of the Ovaries. 8vo. Cloth, $4.50.

WORCESTER (A.). Monthly Nursing. **Second edition, revised.** Cloth, $1.25.

WYETH (JOHN A.). A Text-Book on Surgery: General, Operative, and Mechanical. Profusely illustrated. 8vo. (*Sold only by subscription.*)

LANE MEDICAL LIBRARY
STANFORD UNIVERSITY
MEDICAL CENTER
STANFORD, CALIF. 94305

Q46 Fuchs, Ernst
F951d Textbook of ophthal-
1893 mology 17870

NAME	DATE DUE
O. A. Pfaff	DEC 19, 1915
C. S. Lindeen	DEC 23 1915
Miss Togasumi ret. Dec. 16 1915.	
B. Jamieson ret. Mar. 24 1916	
P. Burgin ret. Dec. 20, 1916	
Dr. Donovan	SEP 1917
F. Simpley	MAY 6 1922